

UNITED STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEY

SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir. Use Form 9-331-C for such proposals.)

1. oil ☐ well ☐ gas well ☐ other ☒
2. NAME OF OPERATOR ARCO Oil & Gas Co.
Division of Atlantic Richfield
3. ADDRESS OF OPERATOR
P.O. Box 1710, Hobbs, NM 88240
4. LOCATION OF WELL (REPORT LOCATION CLEARLY. See space 17 below.)
AT SURFACE: 1980' FSL & 1980' FWL
AT TOP PROD. INTERVAL: as above
AT TOTAL DEPTH: as above


16. CHECK APPROPRIATE BOX TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

REQUEST FOR APPROVAL TO: SUBSEQUENT REPORT OF:

TEST WATER SHUT-OFF	<input type="checkbox"/>	<input type="checkbox"/>
FRACTURE TREAT	<input type="checkbox"/>	<input type="checkbox"/>
SHOOT OR ACIDIZE	<input type="checkbox"/>	<input type="checkbox"/>
REPAIR WELL	<input type="checkbox"/>	<input type="checkbox"/>
PULL OR ALTER CASING	<input type="checkbox"/>	<input type="checkbox"/>
MULTIPLE COMPLETE	<input type="checkbox"/>	<input type="checkbox"/>
CHANGE ZONES	<input type="checkbox"/>	<input type="checkbox"/>
ABANDON*	<input type="checkbox"/>	<input type="checkbox"/>
(other) TA		

5. LEASE
LC-029426 (b)
6. IF INDIAN, ALLOTTEE OR TRIBE NAME
7. UNIT AGREEMENT NAME
8. FARM OR LEASE NAME
H.E. West "B"
9. WELL NO.
23
10. FIELD OR WILDCAT NAME
Grayburg Jackson SR-Q-G-SA
11. SEC., T., R., M., OR BLK. AND SURVEY OR AREA
3-17S-31E
12. COUNTY OR PARISH
Eddy
13. STATE
New Mexico
14. API NO.
15. ELEVATIONS (SHOW DF, KDB, AND WD)
3948' GL

(NOTE: Report results of multiple completion or zone change on Form 9-331-C)



17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

Rig up on 1-7-81. Install BOP. POH w/injection assy. RIH w/bit to 3454'. RIH w/CIBP, set BP @ 3451'. Run vertilog, indicated possible holes 1177-2512'. Spot 1 sk cmt on top of CIBP. RIH w/RBP, set BP @ 2978', pkr @ 2963'. Had 1" water flow out tbg, no flow out csg. Relsd pkr & RBP, POH. RIH w/RBP & pkr, set RBP @ 2978', set pkr @ 2945'. Test RBP to 1500#. OK. Had 1" stream flow back thru tbg. SI. Press 125# in 15 mins. POH w/pkr & RBP. RIH w/CIBP, set @ 2978'. Ran CBL/VDL/CCL/GR. Indicated TOC @ 2670'. Located defective csg 1177-2512'. Removed BOP, nipped up wellhead, TA eff 4-20-81. Final Report.

This approval of temporary
abandonment expires OCT 08 1981

Subsurface Safety Valve: Manu. and Type _____ Set @ _____ Ft.

18. I hereby certify that the foregoing is true and correct

SIGNED Jerry W. Schmidt TITLE Dist. Drlg. Supt. DATE 4-22-81

(This space for Federal or State office use)

APPROVED BY _____ TITLE _____ DATE _____
CONDITIONS OF APPROVAL, IF ANY:

*See Instructions on Reverse Side

