

Form 9-331
(May 1963)UNITED STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEYSUBMIT IN TRIP . . . TE*
(Other instructions on re-
verse side)Form approved.
Budget Bureau No. 42-R1424.

5. LEASE DESIGNATION AND SERIAL NO.

NM- 7752

6. IF INDIAN, ALLOTTEE OR TRIBE NAME

7. UNIT AGREEMENT NAME

8. FARM OR LEASE NAME

Randel

9. WELL NO.

1

10. FIELD AND POOL, OR WILDCAT

Grayberg-Jackson

11. SEC., T., R., M., OR BLK. AND
SURVEY OR AREA

7 - 17S - 30E

12. COUNTY OR PARISH

Eddy

13. STATE

New Mexico

SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir.
Use "APPLICATION FOR PERMIT—" for such proposals.)1. OIL WELL ☒ GAS WELL ☐ OTHER ☐

RECEIVED

2. NAME OF OPERATOR

General American Oil Company of Texas

MAY 4 1973

3. ADDRESS OF OPERATOR

P. O. Box 416 Loco Hills, New Mexico 88255

4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements.
See also space 17 below.)
At surface

E. G. C.

ARTESIA, OFFICE

330' FSL and 330' FEL

Sec. 7 T17S R30E

14. PERMIT NO.

15. ELEVATIONS (Show whether DF, RT, GR, etc.)

3661' GL

16. Check Appropriate Box To Indicate Nature of Notice, Report, or Other Data

NOTICE OF INTENTION TO:

TEST WATER SHUT-OFF

FRACTURE TREAT

SHOOT OR ACIDIZE

REPAIR WELL

(Other)

PULL OR ALTER CASING

MULTIPLE COMPLETE

ABANDON*

CHANGE PLANS

SUBSEQUENT REPORT OF:

WATER SHUT-OFF

FRACTURE TREATMENT

SHOOTING OR ACIDIZING

(Other)

REPAIRING WELL

ALTERING CASING

ABANDONMENT*

(NOTE: Report results of multiple completion on Well
Completion or Recompletion Report and Log form.)

17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

1. Spud at 1:00 P. M. March 21, 1973.

2. Ran 525' KB of 8 5/8" 20# casing as follows:

- Volume of cement equalled 132 cubic feet. (100 sacks)
 - Brand of cement was Southwestern Class C with 2% CaCl.
 - Approximate temperature of cement was 60°
 - Formation temperature was 65°
 - After standing cemented 9 hours compressive strength was 800#.
- Pressure tested to 400#. Tested OK.

3. Ran 3285' KB of 4 1/2" 9.5# casing and cemented with 350 sacks cement.

4. We perforated as follows: 2552'-2560' (16 holes); 2654'-2662' (16 holes);
2758'-2764' (8 holes); 2772'-2776' (8 holes); 2816'-2820' (4 holes);
3030'-3032' (4 holes); 3060'-3064' (8 holes); 3103'-3105' (4 holes).

5. Acidized from 3030- to 3105' with 3,000 gallons.

Acidized from 2816' to 2820' with 2,500 gallons.

Fraced from 2758' to 2776' with 30,000# sand and 30,000 gallons water.

Fraced from 2654' to 2662' with 30,000# sand and 30,000 gallons water.

Fraced from 2552' to 2560' with 30,000# sand and 30,000 gallons water.

18. I hereby certify that the foregoing is true and correct

SIGNED

W. E. Walter

TITLE

District Superintendent

DATE


April 24, 1973

(This space for Federal or State office use)

APPROVED BY
CONDITIONS OF APPROVAL, IF ANY:

TITLE

DATE



*See Instructions on Reverse Side

Instructions

General: This form is designed for submitting proposals to perform certain well operations, and reports of such operations when completed, as indicated, on Federal and Indian lands pursuant to applicable Federal law and regulations, and, if approved or accepted by any State, on all lands in such State, pursuant to applicable State law and regulations. Any necessary special instructions concerning the use of this form and the number of copies to be submitted, particularly with regard to local, area, or regional procedures and practices, either are shown below or will be issued by, or may be obtained from, the local Federal and/or State office.

Item 4: If there are no applicable State requirements, locations on Federal or Indian land should be described in accordance with Federal requirements. Consult local State or Federal office for specific instructions.

Item 17: Proposals to abandon a well and subsequent reports of abandonment should include such special information as is required by local Federal and/or State offices. In addition, such proposals and reports should include reasons for the abandonment; data on any former or present productive zones, or other zones with present significant fluid contents not sealed off by cement or otherwise; depths (top and bottom) and method of placement of cement plugs; mud or other material placed below, between and above plugs; amount, size, method of parting of any casing, liner or tubing pulled and the depth to top of any left in the hole; method of closing top of well; and date well site conditioned for final inspection looking to approval of the abandonment.