**Operator** LANG
**Well** State 'A' #2
**Unit** D **Section** 24 **Twnship** 19 **Range** 28
**API #** 30-015-10352

**TOPS**

| | |
|---|---|
| Salado | 373 |
| B Salt | 629' |
| Yates | 870' |
| 7 Rivers | 1262' |
| Queen | 1737' |
| Grayburg | 2156' |

← 60' Surface Plug.

8 5/8" @ 300'
w/100 sks cmt

← 350' TAG

← 729' TAG

Cal. Toc. 1820'

← 2065' TAG

Perfs 2165' - 2222'.

5 1/2" @ 2220'
w/150 sks cmt.

* Contact OCD 24 hrs. prior to any work done.
* Salt gel mud consisting of 10# brine with 25# of gel per barrel must be placed between each plug.
* Install dry hole marker as per Rule 202.B.2
* Plugs are to be set from point indicated up.
* Plugs must not be less than 100' or 25 Sacks of cement, whichever is greater, unless specifically indicated.
* Shoe and stub plugs will be 50' above and below shoe or stub and tagged.
* Surface plug will be from 0' - 60'
* Where plugs are required, cement must be placed inside and outside of **all** casing string(s) in the correct footage or sacks required, **if no cement exists.**
* Plugs to be tagged will be indicated.