

8. Maximum anticipated bottom hole pressure is 5200 at approximately 12,000', based upon offset well data. Mud weight required to balance this formation pressure at this depth is only 8.3 PPG. Maximum bottom hole temperature should approach 160° F. No sour or corrosive gas is expected.
9. Anticipated commencement date is August 1, 1978, with completion of drilling operations on September 25, 1978. Completion operations (perforation and stimulation) will immediately follow the drilling operations.

Michael P. Houston

Michael P. Houston
Division Engineer
May 17, 1978

/vlh