

E) DIRECTIONAL DRILLING

No directional services anticipated.

**POINT 7: ANTICIPATED RESERVOIR CONDITIONS**

Normal pressures are anticipated throughout Delaware section. A BHP of 1990 psi (max) or MWE of 8.7 ppg is expected. Lost circulation may exist in the Delaware section from 6000'-TD. No H<sub>2</sub>S is anticipated.

Estimated BHT is 116° F.

**POINT 8: OTHER PERTINENT INFORMATION**

A) Auxiliary Equipment

Upper and lower kelly cocks. Full opening stab in valve on the rig floor.

B) Anticipated Starting Date

Upon approval

12 days drilling operations

10 days completion operations

FDC/mac  
October 24, 2000