UNITED STATES

FORM APPROVED OMB No. 1004-0136 Expires November 30, 2000

DEPARTMENT OF .	HE INTERIOR		· _ · _ · _ · _ ·
BUREAU OF LAND	5. Lease Serial No. CONTRACT 457		
APPLICATION FOR PERMIT	6. If Indian, Allottee or Tribe Name JICARILLA APACHE		
1a. Type of Work: DRILL REENTER		7. If Unit or CA Agreement,	Name and No.
1b. Type of Well: ☐ Oil Well ☐ Gas Well ☐ Ott	ner Single Zone Multiple Zone	8. Lease Name and Well No. JIC 457-10 44	
2. Name of Operator Contact: MALEON OF COMPANY BLACK H) 115 Gas Res	ART CHILDERS E-Mail: achilder@bhep.com	9. API Well No. 300393	19321
3a. Address 350 INDIANA STREET, SUITE 400 GOLDEN, CO 80401	3b. Phone No. (include area code) Ph: 505.382.9100	10. Field and Pool, or Explo EAST BLANCO PICT	ratory FURED CLIFFS
4. Location of Well (Report location clearly and in accord	ance with any State *courrements.**	11. Sec., T., R., M., or Blk.	and Survey or Area
At surface SESE 990FSL 520FEL At proposed prod. zone	SEP 2005	Sec 10 T30N R3W N	
 Distance in miles and direction from nearest town or post MILES EAST OF BLOOMFIELD, NM 	office* COMS. DIV.	12. County or Parish RIO ARRIBA	13. State NM
15. Distance from proposed location to nearest property or lease line, ft. (Also to nearest drig. unit line, if any) 520' - LEASE	2560.00 Lease 10 Cl No. of Age in Lease 2000	17. Spacing Unit dedicated 1 160.00 SE/4	to this well
 Distance from proposed location to nearest well, drilling, completed, applied for, on this lease, ft. 2,320' - JIC 460-15 13 	19. Proposed Depth 4000 MD	20. BLM/BIA Bond No. on 1318288	file
21. Elevations (Show whether DF, KB, RT, GL, etc. 7313 GL	22. Approximate date work will start 08/27/2004	23. Estimated duration 45-60 DAYS	
	24. Attachments		
The following, completed in accordance with the requirements of	of Onshore Oil and Gas Order No. 1, shall be attached to	this form:	
 Well plat certified by a registered surveyor. A Drilling Plan. A Surface Use Plan (if the location is on National Forest Sys SUPO shall be filed with the appropriate Forest Service Of 	Item 20 above). 5. Operator certification	ons unless covered by an existin	,
25. Signature (Electronic Submission)	Name (Printed/Typed) KATHY L. SCHNEEBECK Ph: 303.820	.4480	Date 07/27/2004
AGENT			
Title Approved by Stephantes	Name (Printed/Typed) Office		Date 4-8-03
Application approval does not warrant or certify the applicant hoperations thereon. Conditions of approval, if any, are attached.			
Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, States any false, fictitious or fraudulent statements or representa		o make to any department or ag	ency of the United

Additional Operator Remarks (see next page)

Electronic Submission #33526 verified by the BLM Well Information System For MALLON OIL COMPANY, sent to the Rio Puerco Committed to AFMSS for processing by ANGIE MEDINA-JONES on 07/28/2004 ()

CONLLING OPERATIONS AUTHORIZED ARE SURJECT TO COMPLIANCE WITH ATTACHED "GENERAL REQUIREMENTS".

This action is subject to technical and procedural review pursuant to 43 CFR 3165.3 and appeal pursuant to 43 CFR 3165.4

AFMSS Adjud am Engr Geol Surf Appyl

** OPERATOR-SUBMITTED ** OPERATOR-SUBMITTED **

DISTRICT I 1625 N. French Dr., Hobbs, N.M. 88240

DISTRICT II 1301 W. Grand Ave., Artesia, N.M. 88210

DISTRICT III 1000 Rio Braxos Rd., Astec, N.M. 87410

State of New Mexico Energy, Minerals & Natural Resources Department

OIL CONSERVATION DIVISION 1220 South St. Francis Dr. Santa Fe, NM 87505

Form C-102 Revised June 10, 2003 Submit to Appropriate District Office

State Lease — 4 Copies Fee Lease — 3 Copies

DISTRICT IV 1220 South St. Francis Dr., Santa Fe, NM 67505

☐ AMENDED REPORT

WELL LOCATION AND ACREAGE DEDICATION PLAT

¹ API Number	*Pool Code 72400	*Pool Name East Blanco; Pictured Cliffs	
Property Code	• p	roperty Name	Well Number
24245 22860	JICARILLA 457-10		
OGRID No.	•0	* Elevation	
013925	MALLON OIL COMPANY		


¹⁰ Surface Location

					Dulluo	DOCUMENT			
UL or lot no.	Section	Township	Range	Lot Idm	Feet from the	North/South line	Feet from the	East/West line	County
Р	.10	30-N	3-W		990	SOUTH	520	EAST	RIO ARRIBA
			11 Bott	om Hole	Location I	f Different Fro	om Surface		
UL or lot no.	Section	Township	Range	Lot idn	Peet from the	North/South line	Feet from the	East/West line	County
¹⁸ Dedicated Acre	13		²⁸ Joint or	Infill	¹⁴ Consolidation (*Order No.		
l	60								

NO ALLOWABLE WILL BE ASSIGNED TO THIS COMPLETION UNTIL ALL INTERESTS HAVE BEEN CONSOLIDATED OR A NON-STANDARD UNIT HAS BEEN APPROVED BY THE DIVISION

16				17 OPERATOR CERTIFICATION I hereby certify that the information contained herein is true and complete to the best of my knowledge and belief
LOT 4	LOT 3	LOT 2	LOT 1	
	1	P ————	QTR. CORNER FD. 2 1/2" BC. 1917 U.S.G.L.O.	Kath & Schneebeck Signature Kathy L. Schneebeck Printed Name Agent for Mallon Oil Company Title July 27, 2004 Date
	LAT. 36°49'21"N LONG. 107"07'51"W	NAD 83) NAD 83)	N 00-02-54 W 2641.2' (M)	18 SURVEYOR CERTIFICATION I hereby certify that the well location shown on this plat was plotted from field notes of actual surveys made by me or under my supervision, and that the same is true and correct to the best of my beltef. Date of pury ME Signature and the of researchs survey.
	QTR. CORNER FD. 2 1/2" BC. 1917 U.S.G.L.O.	SEC. COF FD. 2 1/2' 1917 U.S.C S 89-59-03 W 	BC.	Signature and Market Signature

MALLON OIL COMPANY COMPANY:_ JICARILLA 457-10 No. 44 LEASE: _ 520' FEL . FOOTAGE: _ 990' FSL, SEC.: 10 3-W TWN: ____30-N __ RNG:. , NMPM **ELEVATION: _** 7313' REAR 5.4 F 1.7 125' 125' ELEV.= 7313' × 125' 25 100, [c 0.0 છે LAYDOWN SOTW 125 NOTE: د ^{6,0}ه c 6.2 DAGGETT ENTERPRISES, INC. IS NOT LIABLE FOR UNDERGROUND UTILITIES OR PIPELINES. NEW MEXICO ONE CALL TO BE NOTIFIED 48 HOURS PRIOR TO EXCAVATION OR CONSTRUCTION. 125 125 1753' NEW ACCESS ELEV. A-A' 7350 7340 7330 7320 7310 7300 7290



Mallon Oil Company
Jicarilla 457-10 44

990' FSL 520' FEL (SE/4 SE/4)
Sec. 10 T30N R3W

Rio Arriba County, New Mexico
Lease: Contract 457

-COLUMN TO THE

DRILLING PROGRAM (Per Rule 320)

This Application for Permit to Drill (APD) was initiated under the NOS process as stated in Onshore Order No. 1 and supporting Bureau of Land Management (BLM) documents. This NOS process includes an onsite meeting which was held on June 29, 2004 as determined by Bureau of Land Management (BLM), Bureau of Indian Affairs (BIA) and Jicarilla Oil & Gas Administration (JOGA), and at which time the specific concerns of Mallon Oil Company (Mallon), BLM, BIA and JOGA were discussed.

MALLON RESPECTFULLY REQUESTS THAT ALL INFORMATION REGARDING THIS WELL BE KEPT CONFIDENTIAL.

SURFACE FORMATION - San Jose

GROUND ELEVATION - 7,313'

TOTAL DEPTH

ESTIMATED FORMATION TOPS - (Water, oil, gas and/or other mineral-bearing formations)

San Jose		Surface	Sandstone, shales & siltstones
Nacimiento	1	1,977'	Sandstone, shales & siltstones
Ojo Alamo	· ·	3,185'	Sandstone, shales & siltstones
Fruitland		3,611'	Sandstone, shales & siltstones
Pictured Cliffs	6	3,700'	Sandstone, shales & siltstones
Lewis		3,808'	Sandstone, shales & siltstones
	er e		

Estimated depths of anticipated fresh water, oil, or gas:

4,000'

		\mathcal{A}^{\prime}
surface	Gas	thro
1,977'	Gas	1/20
3,185'	Gas	420
3,611'	Gas	01
3,700'	Gas	
	1,977' 3,185' 3,611'	1,977' Gas 3,185' Gas 3,611' Gas

CASING PROGRAM

Depth	Hole Diameter	Casing Diameter	Casing Weight and Grade	Cement
0'-250'	12-1/4"	8-5/8"	J-55 24# ST&C New	To surface (±175 sxs Class B)
0' - T.D.	7-7/8"	5-1/2"	J-55 15.5# LT&C New	TD to surface (±630 sxs lite or 65:35 poz and ±270 sxs 50:50 poz)*

^{*} Actual cement volume to be determined by caliper log.

Yields:

Class B yield = $1.18 \text{ ft}^3/\text{sx}$ 65:35 Poz yield = $1.62 \text{ ft}^3/\text{sx}$ 50:50 Poz yield = $1.26 \text{ ft}^3/\text{sx}$

All fresh water and prospectively valuable minerals encountered during drilling, will be recorded by depth and protected.

PRESSURE CONTROL

BOPs and choke manifold will be installed and pressure tested before drilling out under surface casing (subsequent pressure test will be performed whenever pressure seals are broken), and then will be checked daily as to mechanical operating condition. BOP's will be pressure tested at least once every 30 days. Ram type preventors and related pressure control equipment will be pressure tested to 1,000 psi. Annular type preventor will be pressure tested to 50% of the rated working pressure, not to exceed 1,000 psi. All casing strings will be pressure tested to 0.22 psi/ft. or 1,000 psi, whichever is greater, not to exceed 70% of internal yield.

BOP to be either double gate rams or an annular preventor as per Onshore Order No. 2.

Statement on Accumulator System and Location of Hydraulic Controls

The drilling rig has not yet been selected for this well. Selection will take place after approval of this application. Manual and/or hydraulic controls will be in compliance with Onshore Order No. 2 for 2M systems.

A remote accumulator will be used. Pressures, capacities, location of remote hydraulic and manual controls will be identified at the time of the BLM supervised BOP test.

MUD PROGRAM

0' - 250' Fresh water - M.W. 8.5 ppg, Vis 30-33
250' - TD Fresh water - Low solids non-dispersed
M.W. 8.5 - 9.2 ppg
Vis - 28 - 50 sec
W.L. 15cc or less

Sufficient mud materials to maintain mud properties, control lost circulation and to contain "kick" will be available at wellsite.

AUXILIARY EQUIPMENT

- A) A Kelly cock will be kept in the drill string at all times
- B) Inside BOP or stab-in valve (available on rig floor)
- C) Mud monitoring will be visually observed

LOGGING, CORING, TESTING PROGRAM

A) Logging: DIL-CNL-FDC-GR - TD - BSC (GR to surface)

Sonic (BSC to TD)

B) Coring: None

C) Testing: Possible DST – None anticipated. Drill stem tests may be run on shows of interest

ABNORMAL CONDITIONS

Pressures:

No abnormal conditions are anticipated

Bottom hole pressure gradient – 0.31 psi/ft

B) Temperatures:

No abnormal conditions are anticipated

C) H_2S : None is anticipated.

Estimated bottomhole pressure: 1,240 psi D)

ANTICIPATED START DATE


August 27, 2004

COMPLETION

The location pad will be of sufficient size to accommodate all completion activities and equipment. A string of 2-3/8" J-55 4.7#/ft tubing will be run for a flowing string. A Sundry Notice will be submitted with a revised completion program if warranted.

2-M SYSTEM MALLON OIL COMPANY

ANNULAR PREVENTOR MAY BE SUBSTITUTED FOR DOUBLE GATE PREVENTORS BOP PRESSURE TEST TO 1,000 PSI



Hydrogen Sulfide Drilling Operations Plan

I. Hydrogen Sulfide Training

All personnel, whether regularly assigned, contracted, or employed on an unscheduled basis, will receive training from a qualified instructor in the following areas prior to commencing drilling operations on this well:

- 1. The hazards and characteristics of hydrogen sulfide (H₂S).
- The proper use and maintenance of personal protective equipment and life support systems.
- The proper use of H₂S detectors, alarms, warning systems, briefing areas, evacuation procedures, and prevailing winds.
- 4. The proper techniques for first aid and rescue procedures.

In addition, supervisory personnel will be trained in the following areas:

- 1. The effects of H₂S on metal components. If high tensile tubulars are to be used, personnel will be trained in their special maintenance requirements.
- Corrective action and shut-in procedures when drilling or reworking a well and blowout prevention and well control procedures.
- The contents and requirements of the H₂S Drilling Operations Plan and the Public Protection Plan.

There will be an initial training session just prior to encountering a known or probable H_2S zone (within 3 days or 500 feet) and weekly H_2S and well control drills for all personnel in each crew. The initial training session shall include a review of the site specific H_2S Drilling Operations Plan and the Public Protection Plan. This plan shall be available at the well site. All personnel will be required to carry documentation that they have received the proper training.

II. H₂S Safety Equipment and Systems

Note: All H_2S safety equipment and systems will be installed, tested, and operational when drilling reaches a depth of 500 feet above or three days prior to penetrating the first zone containing or reasonably expected to contain H_2S .

- A. Well control equipment:
 - 1. Choke manifold with a minimum of one remote choke.
 - Blind rams and pipe rams to accommodate all pipe sizes with properly sized closing unit.
- B. Protective equipment for essential personnel.
 - 1. Mark II Surviveair 30-minute units located in the doghouse and at briefing areas, as indicated on well site diagram.

MALLON OIL COMPANY

C. H₂S detection and monitoring equipment:

 Two portable H₂S monitors positioned on location for best coverage and response. These units have warning lights and audible sirens when H₂S levels of 10 ppm are reached.

D. Visual warning systems:

- 1. Wind direction indicators as shown on well site diagram.
- Caution/Danger signs shall be posted on roads providing direct access to location. Signs will be painted a high visibility yellow with black lettering of sufficient size to be readable at a reasonable distance from the immediate location. Bilingual signs will be used when appropriate. See example attached.

E. Mud program:

 The mud program has been designed to minimize the volume of H₂S circulated to the surface. Proper mud weight, safe drilling practices, and the use of H₂S scavengers will minimize hazards when penetrating H₂S bearing zones.

F. Metallurgy:

- All drill strings, casings, tubing, wellhead, blowout preventers, drilling spool, kill lines, choke manifold and lines, and valves shall be suitable for H₂S service.
- 2. All elastomers used for packing and seals shall be H₂S trim.

G. Communication:

1. Cellular telephone communications in company vehicles.

H. Well testing:

 Drill stem testing will be performed with a minimum number of personnel in the immediate vicinity which are necessary to safely and adequately conduct the test. The drill stem testing will be conducted during daylight hours and formation fluids will not be flowed to the surface. All drill stem testing operations conducted in an H₂S environment will use the closed chamber method of testing.