

State of New Mexico  
Energy, Minerals and Natural Resources Department

Michelle Lujan Grisham  
Governor

Sarah Cottrell Propst  
Cabinet Secretary

Todd E. Leahy, JD, PhD  
Deputy Secretary

Gabriel Wade, Acting Director  
Oil Conservation Division



New Mexico Oil Conservation Division approval and conditions listed below are made in accordance with OCD Rule 19.15.7.11 and are in addition to the actions approved by BLM on the following 3160-3 APD form.

Operator Signature Date: 11/26/2018

Well information;

Operator Enduring, Well Name and Number W. Escobar Unit 307H

API# 30-043-21325, Section 19, Township 22N/S, Range 7 E/W

Conditions of Approval: (See the below checked and handwritten conditions)

- Notify Aztec OCD 24hrs prior to casing & cement.
- Hold C-104 for directional survey & "As Drilled" Plat
  - Hold C-104 for NSL, NSP, DHC
  - Spacing rule violation. Operator must follow up with change of status notification on other well to be shut in or abandoned
  - Regarding the use of a pit, closed loop system or below grade tank, the operator must comply with the following as applicable:
    - A pit requires a complete C-144 be submitted and approved prior to the construction or use of the pit, pursuant to 19.15.17.8.A
    - A closed loop system requires notification prior to use, pursuant to 19.15.17.9.A
    - A below grade tank requires a registration be filed prior to the construction or use of the below grade tank, pursuant to 19.15.17.8.C
  - Once the well is spud, to prevent ground water contamination through whole or partial conduits from the surface, the operator shall drill without interruption through the fresh water zone or zones and shall immediately set in cement the water protection string
  - Submit Gas Capture Plan form prior to spudding or initiating recompletion operations
  - Regarding Hydraulic Fracturing, review EPA Underground Injection Control Guidance 84
  - Oil base muds are not to be used until fresh water zones are cased and cemented providing isolation from the oil or diesel. This includes synthetic oils. Oil based mud, drilling fluids and solids must be contained in a steel closed loop system.
  - Well-bore communication is regulated under 19.15.29 NMAC. This requires well-bore communication to be reported in accordance with 19.15.29.8.

Brend Bell  
NMOCD Approved by Signature

4/2/19  
Date

RECEIVED

FORM APPROVED  
OMB No. 1004-0136  
Expires January 31, 2004

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT

APPLICATION FOR PERMIT TO DRILL OR REENTER

|  |  |  |
|--|--|--|
| 1a. Type of Work: <input checked="" type="checkbox"/> DRILL <input type="checkbox"/> REENTER   |  | 5. Lease Serial No.<br>NOG-1311-1801   |
| 1b. Type of Well: <input checked="" type="checkbox"/> Oil Well <input type="checkbox"/> Gas Well <input type="checkbox"/> Other <input checked="" type="checkbox"/> Single Zone <input type="checkbox"/> Multiple Zone |  | 6. If Indian, Allottee or Tribe Name   |
| 2. Name of Operator<br>Enduring Resources IV LLC   |  | 7. If Unit or CA Agreement, Name and No.<br>ESCAVADA W; MANCOS NMNM135218X                           |
| 3a. Address<br>200 Energy Court Farmington NM 87401  |  | 8. Lease Name and Well No.<br>W ESCAVADA UNIT #307H  |
| 3b. Phone No. (include area code)<br>(505) 636-9743  |  | 9. API Well No.<br>30-043-21325  |
| 4. Location of Well (Report location clearly and in accordance with any State requirements. *)<br>At surface 497' FNL & 2171' FWL<br>At proposed prod. zone 2295' FSL & 1359' FWL                                      |  | 10. Field and Pool, or Exploratory<br>ESCAVADA W; MANCOS   |
| 14. Distance in miles and direction from nearest town or post office*<br>From Bloomfield NM Drive South approximately 48.9 miles to Mile Marker 103.1  |  | 11. Sec., T., R., M., or Blk. and Survey or Area<br>SHL: Sec 19, T22N, R7W<br>BHL: Sec 12, T22N, R8W |
| 15. Distance from proposed* location to nearest property or lease line, ft. (Also to nearest drig. unit line, if any) 497  | 16. No. of Acres in lease<br>160 acres   | 12. County or Parish<br>Sandoval County  |
| 17. Spacing Unit dedicated to this well<br>442.24 ACRES  | 18. Distance from proposed location* to nearest well, drilling, completed, applied for, on this lease, ft. 20' | 13. State<br>NM  |
| 19. Proposed Depth<br>15644' MD / 4720' TVD  | 20. BLM/BIA Bond No. on file<br>RLB0016899   |  |
| 21. Elevations (Show whether DF, KDB, RT, GL, etc.)<br>6824' GR  | 22. Approximate date work will start*<br>January 1, 2019   | 23. Estimated duration<br>1 month  |

NMOCD  
MAR 19 2019  
DISTRICT III

24. Attachments  
The following, completed in accordance with the requirements of Onshore Oil and Gas Order No. 1, shall be attached to this form:

- Well plat certified by a registered surveyor.
- A Drilling Plan.
- A Surface Use Plan (if the location is on National Forest System Lands, the SUPO shall be filed with the appropriate Forest Service Office).
- Bond to cover the operations unless covered by an existing bond on file (see Item 20 above).
- Operator certification.
- Such other site specific information and/or plans as may be required by the authorized officer.

|                             |  |                  |
|-----------------------------|--|------------------|
| 25. Signature<br>           | Name (Printed/Typed)<br>Lacey Granillo | Date<br>11/26/18 |
| Title<br>Permit Specialist  |  |                  |
| Approved by (Signature)<br> | Name (Printed/Typed)<br>D. Manriquez   | Date<br>3/18/19  |
| Title<br>AFM                | Office<br>FFO                          |                  |

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.  
Conditions of approval, if any, are attached.

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

\*(Instructions on reverse)

Enduring Resources IV, LLC, proposes to develop the ESCAVADA W; MANCOS formation at the above described location in accordance with the attached drilling and surface use plans.

The well pad surface is under jurisdiction of the BLM/FIMO and is off lease on BLM lands and will be twinned with the W Escavada Unit 308H. The pad will be permitted as a ROW with this APD.

This location has been archaeologically surveyed by La Plata Archeology. Copies of their report have been submitted directly to the BLM, FIMO, BIA & NNHPD.

A new 760.2' off lease access road will be built on BLM lands and permitted via ROW.

A new 1030.2 off lease pipeline on BLM lands will be built and permitted via ROW.

A new 2299.2' off lease access road on IA lands will be built and permitted via ROW.

A new 2264.4 off lease pipeline on IA lands will be built and permitted via ROW.

BLM'S APPROVAL OR ACCEPTANCE OF THIS ACTION DOES NOT CONSTITUTE THE LESSEE AND OPERATOR FROM OBTAINING ANY OTHER AUTHORIZATION REQUIRED FOR OPERATIONS ON FEDERAL AND INDIAN LANDS

DRILLING OPERATIONS ARE SUBJECT TO THE FOLLOWING REGULATIONS: 43 CFR 3165.2 AND 3165.3

~~OPERATOR~~  
NMOCD AV

District I  
1625 N. French Drive, Hobbs, NM 88240  
Phone: (575) 393-6161 Fax: (575) 393-0720

District II  
811 S. First Street, Artesia, NM 88210  
Phone: (575) 748-1283 Fax: (575) 748-9720

District III  
1000 Rio Brazos Road, Aztec, NM 87410  
Phone: (505) 334-6178 Fax: (505) 334-6170

District IV  
1220 S. St. Francis Drive, Santa Fe, NM 87505  
Phone: (505) 476-3460 Fax: (505) 476-3462

State of New Mexico  
Energy, Minerals & Natural Resources Department

Form C-102  
Revised August 1, 2011

Submit one copy to  
Appropriate District Office

OIL CONSERVATION DIVISION  
1220 South St. Francis Drive  
Santa Fe, NM 87505

AMENDED REPORT

WELL LOCATION AND ACREAGE DEDICATION PLAT

|                                   |  |                    |                                 |
|-----------------------------------|--|--------------------|---------------------------------|
| API Number<br><b>30-043-21325</b> |  | Pool Code<br>98225 | Pool Name<br>ESCAVADA W; MANCOS |
| Property Code<br>321258           | Property Name<br>W ESCAVADA UNIT         |                    | Well Number<br>307H             |
| OGRID No.<br>372286               | Operator Name<br>ENDURING RESOURCES, LLC |                    | Elevation<br>6824'              |

10 Surface Location


| UL or lot no. | Section | Township | Range | Lot Idn | Feet from the | North/South line | Feet from the | East/West line | County   |
|---------------|---------|----------|-------|---------|---------------|------------------|---------------|----------------|----------|
| C             | 19      | 22N      | 7W    |         | 497           | NORTH            | 2171          | WEST           | SANDOVAL |

11 Bottom Hole Location If Different From Surface

| UL or lot no. | Section | Township | Range | Lot Idn | Feet from the | North/South line | Feet from the | East/West line | County   |
|---------------|---------|----------|-------|---------|---------------|------------------|---------------|----------------|----------|
| K             | 12      | 22N      | 8W    |         | 2295          | SOUTH            | 1359          | WEST           | SAN JUAN |

|  |  |                 |                    |                      |
|--|--|-----------------|--------------------|----------------------|
| Dedicated Acres<br>442.24  |  | Joint or Infill | Consolidation Code | Order No.<br>R-14100 |
| E/2 SW/4, SW/4 SE/4 - Section 12<br>N/2 NE/4, SE/4 NE/4 - Section 13<br>SW/4 NW/4, N/2 SW/4<br>SE/4 SW/4, SW/4 SE/4 - Section 18 |  |                 |                    |                      |

NO ALLOWABLE WILL BE ASSIGNED TO THIS COMPLETION  
UNTIL ALL INTERESTS HAVE BEEN CONSOLIDATED OR A  
NON-STANDARD UNIT HAS BEEN APPROVED BY THE DIVISION



17 OPERATOR CERTIFICATION

I hereby certify that the information contained herein is true and complete to the best of my knowledge and belief, and that this organization either owns a working interest or unleased mineral interest in the land including the proposed bottom-hole location or has a right to drill this well at this location pursuant to a contract with an owner of such a mineral or working interest or to a voluntary pooling agreement or a compulsory pooling order heretofore entered by the division.

Signature: *[Signature]* Date: 11-20-18  
Printed Name: *[Name]*  
E-mail Address: *[Email]*

18 SURVEYOR CERTIFICATION

I hereby certify that the well location shown on this plat was plotted from field notes of actual surveys made by me or under my supervision, and that the same is true and correct to the best of my belief.

Date Revised: NOVEMBER 19, 2018  
Survey Date: OCTOBER 27, 2018

Signature and Seal of Professional Surveyor



JASON C. EDWARDS  
Certificate Number 15269




Enduring Resources LLC

Directional Drilling Plan  
Plan View & Section View


W Escavada Unit 307H

Sandoval County, New Mexico  
T22N-R07W-Sec.19-Lot C  
Surface Latitude: 36.131067°N  
Surface Longitude: 107.617389°W  
Ground Level: 6824.0  
Reference Elevation: KB @ 6849.0usft (Original Well Elev)



Design Target Details

| Name     | TVD    | +N/-S  | +E/-W   | Northing   | Easting    | Latitude    | Longitude    |
|----------|--------|--------|---------|------------|------------|-------------|--------------|
| 307H KOP | 4000.0 | 100.0  | 1250.0  | 1869914.86 | 1237875.52 | 36.131390°N | 107.613162°W |
| 307H POE | 4663.0 | 804.0  | 1139.6  | 1870618.82 | 1237765.14 | 36.133319°N | 107.613569°W |
| 307H BHL | 4720.0 | 8155.7 | -5945.5 | 1877970.54 | 1230680.01 | 36.153234°N | 107.637912°W |



Directional Drilling Plan Details

| MD      | Inc   | Azi    | TVD    | +N/-S  | +E/-W   | Dleg | VSect   |
|---------|-------|--------|--------|--------|---------|------|---------|
| 0.0     | 0.00  | 0.00   | 0.0    | 0.0    | 0.0     | 0.00 | 0.0     |
| 240.0   | 0.00  | 0.00   | 240.0  | 0.0    | 0.0     | 0.00 | 0.0     |
| 1000.0  | 0.00  | 0.00   | 1000.0 | 0.0    | 0.0     | 0.00 | 0.0     |
| 2452.4  | 29.05 | 85.43  | 2391.0 | 28.7   | 359.2   | 2.00 | -188.4  |
| 4292.9  | 29.05 | 85.43  | 4000.0 | 100.0  | 1250.0  | 0.00 | -655.5  |
| 5297.7  | 84.38 | 328.22 | 4655.9 | 696.9  | 1222.9  | 9.73 | -157.3  |
| 5433.9  | 89.68 | 316.06 | 4663.0 | 804.0  | 1139.6  | 9.73 | -21.7   |
| 15644.2 | 89.68 | 316.06 | 4720.0 | 8155.7 | -5945.5 | 0.00 | 10092.8 |



# **Enduring Resources LLC**

**San Juan Basin - West Escavada Unit**

**307H Pad**

**307H**

**Wellbore #1**

**Plan: Design #1**

## **Standard Planning Report**

**20 November, 2018**



Planning Report

|                  |                                     |                                     |                                      |
|------------------|-------------------------------------|-------------------------------------|--------------------------------------|
| <b>Database:</b> | EDM                                 | <b>Local Co-ordinate Reference:</b> | Well 307H                            |
| <b>Company:</b>  | Enduring Resources LLC              | <b>TVD Reference:</b>               | KB @ 6849.0usft (Original Well Elev) |
| <b>Project:</b>  | San Juan Basin - West Escavada Unit | <b>MD Reference:</b>                | KB @ 6849.0usft (Original Well Elev) |
| <b>Site:</b>     | 307H Pad                            | <b>North Reference:</b>             | Grid                                 |
| <b>Well:</b>     | 307H                                | <b>Survey Calculation Method:</b>   | Minimum Curvature                    |
| <b>Wellbore:</b> | Wellbore #1                         |                                     |                                      |
| <b>Design:</b>   | Design #1                           |                                     |                                      |

|                    |                                     |                      |                |
|--------------------|-------------------------------------|----------------------|----------------|
| <b>Project</b>     | San Juan Basin - West Escavada Unit |                      |                |
| <b>Map System:</b> | US State Plane 1983                 | <b>System Datum:</b> | Mean Sea Level |
| <b>Geo Datum:</b>  | North American Datum 1983           |                      |                |
| <b>Map Zone:</b>   | New Mexico Central Zone             |                      |                |

|                              |                                       |                     |                   |                          |              |
|------------------------------|---------------------------------------|---------------------|-------------------|--------------------------|--------------|
| <b>Site</b>                  | 307H Pad, Sandoval County, New Mexico |                     |                   |                          |              |
| <b>Site Position:</b>        |                                       | <b>Northing:</b>    | 1,869,814.86 usft | <b>Latitude:</b>         | 36.131067°N  |
| <b>From:</b>                 | Lat/Long                              | <b>Easting:</b>     | 1,236,625.51 usft | <b>Longitude:</b>        | 107.617389°W |
| <b>Position Uncertainty:</b> | 0.0 usft                              | <b>Slot Radius:</b> | 13-3/16 "         | <b>Grid Convergence:</b> | -0.81 °      |

|                             |              |          |                            |                   |                      |              |
|-----------------------------|--------------|----------|----------------------------|-------------------|----------------------|--------------|
| <b>Well</b>                 | 307H         |          |                            |                   |                      |              |
| <b>Well Position</b>        | <b>+N/-S</b> | 0.0 usft | <b>Northing:</b>           | 1,869,814.86 usft | <b>Latitude:</b>     | 36.131067°N  |
|                             | <b>+E/-W</b> | 0.0 usft | <b>Easting:</b>            | 1,236,625.51 usft | <b>Longitude:</b>    | 107.617389°W |
| <b>Position Uncertainty</b> |              | 0.0 usft | <b>Wellhead Elevation:</b> |                   | <b>Ground Level:</b> | 6,824.0 usft |

|                  |                   |                    |                        |                      |                            |
|------------------|-------------------|--------------------|------------------------|----------------------|----------------------------|
| <b>Wellbore</b>  | Wellbore #1       |                    |                        |                      |                            |
| <b>Magnetics</b> | <b>Model Name</b> | <b>Sample Date</b> | <b>Declination (°)</b> | <b>Dip Angle (°)</b> | <b>Field Strength (nT)</b> |
|                  | IGRF200510        | 12/31/2009         | 9.92                   | 63.01                | 50,575.05113442            |

|                          |                                |                     |                      |                      |
|--------------------------|--------------------------------|---------------------|----------------------|----------------------|
| <b>Design</b>            | Design #1                      |                     |                      |                      |
| <b>Audit Notes:</b>      |                                |                     |                      |                      |
| <b>Version:</b>          | <b>Phase:</b>                  | PROTOTYPE           | <b>Tie On Depth:</b> | 0.0                  |
| <b>Vertical Section:</b> | <b>Depth From (TVD) (usft)</b> | <b>+N/-S (usft)</b> | <b>+E/-W (usft)</b>  | <b>Direction (°)</b> |
|                          | 0.0                            | 0.0                 | 0.0                  | 323.91               |

|                                 |                        |                          |                         |                            |
|---------------------------------|------------------------|--------------------------|-------------------------|----------------------------|
| <b>Plan Survey Tool Program</b> | <b>Date</b>            | 11/20/2018               |                         |                            |
| <b>Depth From (usft)</b>        | <b>Depth To (usft)</b> | <b>Survey (Wellbore)</b> | <b>Tool Name</b>        | <b>Remarks</b>             |
| 1                               | 0.0                    | 15,644.2                 | Design #1 (Wellbore #1) | MWD<br>OWSG MWD - Standard |

|                              |                        |                    |                              |                     |                     |                                |                               |                              |                |               |
|------------------------------|------------------------|--------------------|------------------------------|---------------------|---------------------|--------------------------------|-------------------------------|------------------------------|----------------|---------------|
| <b>Plan Sections</b>         |                        |                    |                              |                     |                     |                                |                               |                              |                |               |
| <b>Measured Depth (usft)</b> | <b>Inclination (°)</b> | <b>Azimuth (°)</b> | <b>Vertical Depth (usft)</b> | <b>+N/-S (usft)</b> | <b>+E/-W (usft)</b> | <b>Dogleg Rate (°/100usft)</b> | <b>Build Rate (°/100usft)</b> | <b>Turn Rate (°/100usft)</b> | <b>TFO (°)</b> | <b>Target</b> |
| 0.0                          | 0.00                   | 0.00               | 0.0                          | 0.0                 | 0.0                 | 0.00                           | 0.00                          | 0.00                         | 0.00           |               |
| 240.0                        | 0.00                   | 0.00               | 240.0                        | 0.0                 | 0.0                 | 0.00                           | 0.00                          | 0.00                         | 0.00           |               |
| 1,000.0                      | 0.00                   | 0.00               | 1,000.0                      | 0.0                 | 0.0                 | 0.00                           | 0.00                          | 0.00                         | 0.00           |               |
| 2,452.4                      | 29.05                  | 85.43              | 2,391.0                      | 28.7                | 359.2               | 2.00                           | 2.00                          | 0.00                         | 85.43          |               |
| 4,292.9                      | 29.05                  | 85.43              | 4,000.0                      | 100.0               | 1,250.0             | 0.00                           | 0.00                          | 0.00                         | 0.00           | 307H KOP      |
| 5,297.7                      | 84.38                  | 328.22             | 4,655.9                      | 696.9               | 1,222.9             | 9.73                           | 5.51                          | -11.66                       | -116.71        |               |
| 5,433.9                      | 89.68                  | 316.06             | 4,663.0                      | 804.0               | 1,139.6             | 9.73                           | 3.90                          | -8.93                        | -66.81         | 307H POE      |
| 15,644.2                     | 89.68                  | 316.06             | 4,720.0                      | 8,155.7             | -5,945.5            | 0.00                           | 0.00                          | 0.00                         | 0.00           | 307H BHL      |



Planning Report

|                  |                                     |                                     |                                      |
|------------------|-------------------------------------|-------------------------------------|--------------------------------------|
| <b>Database:</b> | EDM                                 | <b>Local Co-ordinate Reference:</b> | Well 307H                            |
| <b>Company:</b>  | Enduring Resources LLC              | <b>TVD Reference:</b>               | KB @ 6849.0usft (Original Well Elev) |
| <b>Project:</b>  | San Juan Basin - West Escavada Unit | <b>MD Reference:</b>                | KB @ 6849.0usft (Original Well Elev) |
| <b>Site:</b>     | 307H Pad                            | <b>North Reference:</b>             | Grid                                 |
| <b>Well:</b>     | 307H                                | <b>Survey Calculation Method:</b>   | Minimum Curvature                    |
| <b>Wellbore:</b> | Wellbore #1                         |                                     |                                      |
| <b>Design:</b>   | Design #1                           |                                     |                                      |

| Planned Survey        |                 |             |                       |              |              |                         |                         |                        |                       |      |
|-----------------------|-----------------|-------------|-----------------------|--------------|--------------|-------------------------|-------------------------|------------------------|-----------------------|------|
| Measured Depth (usft) | Inclination (°) | Azimuth (°) | Vertical Depth (usft) | +N/-S (usft) | +E/-W (usft) | Vertical Section (usft) | Dogleg Rate (°/100usft) | Build Rate (°/100usft) | Turn Rate (°/100usft) |      |
| 0.0                   | 0.00            | 0.00        | 0.0                   | 0.0          | 0.0          | 0.0                     | 0.00                    | 0.00                   | 0.00                  | 0.00 |
| 100.0                 | 0.00            | 0.00        | 100.0                 | 0.0          | 0.0          | 0.0                     | 0.00                    | 0.00                   | 0.00                  | 0.00 |
| 200.0                 | 0.00            | 0.00        | 200.0                 | 0.0          | 0.0          | 0.0                     | 0.00                    | 0.00                   | 0.00                  | 0.00 |
| 240.0                 | 0.00            | 0.00        | 240.0                 | 0.0          | 0.0          | 0.0                     | 0.00                    | 0.00                   | 0.00                  | 0.00 |
| 300.0                 | 0.00            | 0.00        | 300.0                 | 0.0          | 0.0          | 0.0                     | 0.00                    | 0.00                   | 0.00                  | 0.00 |
| 400.0                 | 0.00            | 0.00        | 400.0                 | 0.0          | 0.0          | 0.0                     | 0.00                    | 0.00                   | 0.00                  | 0.00 |
| 500.0                 | 0.00            | 0.00        | 500.0                 | 0.0          | 0.0          | 0.0                     | 0.00                    | 0.00                   | 0.00                  | 0.00 |
| 600.0                 | 0.00            | 0.00        | 600.0                 | 0.0          | 0.0          | 0.0                     | 0.00                    | 0.00                   | 0.00                  | 0.00 |
| 700.0                 | 0.00            | 0.00        | 700.0                 | 0.0          | 0.0          | 0.0                     | 0.00                    | 0.00                   | 0.00                  | 0.00 |
| 800.0                 | 0.00            | 0.00        | 800.0                 | 0.0          | 0.0          | 0.0                     | 0.00                    | 0.00                   | 0.00                  | 0.00 |
| 900.0                 | 0.00            | 0.00        | 900.0                 | 0.0          | 0.0          | 0.0                     | 0.00                    | 0.00                   | 0.00                  | 0.00 |
| 1,000.0               | 0.00            | 0.00        | 1,000.0               | 0.0          | 0.0          | 0.0                     | 0.00                    | 0.00                   | 0.00                  | 0.00 |
| 1,100.0               | 2.00            | 85.43       | 1,100.0               | 0.1          | 1.7          | -0.9                    | 2.00                    | 2.00                   | 0.00                  | 0.00 |
| 1,200.0               | 4.00            | 85.43       | 1,199.8               | 0.6          | 7.0          | -3.6                    | 2.00                    | 2.00                   | 0.00                  | 0.00 |
| 1,300.0               | 6.00            | 85.43       | 1,299.5               | 1.3          | 15.6         | -8.2                    | 2.00                    | 2.00                   | 0.00                  | 0.00 |
| 1,400.0               | 8.00            | 85.43       | 1,398.7               | 2.2          | 27.8         | -14.6                   | 2.00                    | 2.00                   | 0.00                  | 0.00 |
| 1,500.0               | 10.00           | 85.43       | 1,497.5               | 3.5          | 43.4         | -22.8                   | 2.00                    | 2.00                   | 0.00                  | 0.00 |
| 1,600.0               | 12.00           | 85.43       | 1,595.6               | 5.0          | 62.4         | -32.7                   | 2.00                    | 2.00                   | 0.00                  | 0.00 |
| 1,700.0               | 14.00           | 85.43       | 1,693.1               | 6.8          | 84.8         | -44.5                   | 2.00                    | 2.00                   | 0.00                  | 0.00 |
| 1,800.0               | 16.00           | 85.43       | 1,789.6               | 8.8          | 110.6        | -58.0                   | 2.00                    | 2.00                   | 0.00                  | 0.00 |
| 1,900.0               | 18.00           | 85.43       | 1,885.3               | 11.2         | 139.8        | -73.3                   | 2.00                    | 2.00                   | 0.00                  | 0.00 |
| 2,000.0               | 20.00           | 85.43       | 1,979.8               | 13.8         | 172.2        | -90.3                   | 2.00                    | 2.00                   | 0.00                  | 0.00 |
| 2,100.0               | 22.00           | 85.43       | 2,073.2               | 16.6         | 207.9        | -109.1                  | 2.00                    | 2.00                   | 0.00                  | 0.00 |
| 2,200.0               | 24.00           | 85.43       | 2,165.2               | 19.8         | 246.9        | -129.5                  | 2.00                    | 2.00                   | 0.00                  | 0.00 |
| 2,300.0               | 26.00           | 85.43       | 2,255.8               | 23.1         | 289.0        | -151.6                  | 2.00                    | 2.00                   | 0.00                  | 0.00 |
| 2,400.0               | 28.00           | 85.43       | 2,344.9               | 26.7         | 334.3        | -175.3                  | 2.00                    | 2.00                   | 0.00                  | 0.00 |
| 2,452.4               | 29.05           | 85.43       | 2,391.0               | 28.7         | 359.2        | -188.4                  | 2.00                    | 2.00                   | 0.00                  | 0.00 |
| 2,500.0               | 29.05           | 85.43       | 2,432.6               | 30.6         | 382.2        | -200.5                  | 0.00                    | 0.00                   | 0.00                  | 0.00 |
| 2,600.0               | 29.05           | 85.43       | 2,520.0               | 34.5         | 430.6        | -225.8                  | 0.00                    | 0.00                   | 0.00                  | 0.00 |
| 2,700.0               | 29.05           | 85.43       | 2,607.4               | 38.3         | 479.0        | -251.2                  | 0.00                    | 0.00                   | 0.00                  | 0.00 |
| 2,800.0               | 29.05           | 85.43       | 2,694.9               | 42.2         | 527.4        | -276.6                  | 0.00                    | 0.00                   | 0.00                  | 0.00 |
| 2,900.0               | 29.05           | 85.43       | 2,782.3               | 46.1         | 575.8        | -302.0                  | 0.00                    | 0.00                   | 0.00                  | 0.00 |
| 3,000.0               | 29.05           | 85.43       | 2,869.7               | 49.9         | 624.2        | -327.4                  | 0.00                    | 0.00                   | 0.00                  | 0.00 |
| 3,100.0               | 29.05           | 85.43       | 2,957.1               | 53.8         | 672.6        | -352.8                  | 0.00                    | 0.00                   | 0.00                  | 0.00 |
| 3,200.0               | 29.05           | 85.43       | 3,044.5               | 57.7         | 721.0        | -378.1                  | 0.00                    | 0.00                   | 0.00                  | 0.00 |
| 3,300.0               | 29.05           | 85.43       | 3,132.0               | 61.6         | 769.4        | -403.5                  | 0.00                    | 0.00                   | 0.00                  | 0.00 |
| 3,400.0               | 29.05           | 85.43       | 3,219.4               | 65.4         | 817.8        | -428.9                  | 0.00                    | 0.00                   | 0.00                  | 0.00 |
| 3,500.0               | 29.05           | 85.43       | 3,306.8               | 69.3         | 866.2        | -454.3                  | 0.00                    | 0.00                   | 0.00                  | 0.00 |
| 3,600.0               | 29.05           | 85.43       | 3,394.2               | 73.2         | 914.6        | -479.7                  | 0.00                    | 0.00                   | 0.00                  | 0.00 |
| 3,700.0               | 29.05           | 85.43       | 3,481.6               | 77.0         | 963.0        | -505.1                  | 0.00                    | 0.00                   | 0.00                  | 0.00 |
| 3,800.0               | 29.05           | 85.43       | 3,569.1               | 80.9         | 1,011.4      | -530.4                  | 0.00                    | 0.00                   | 0.00                  | 0.00 |
| 3,900.0               | 29.05           | 85.43       | 3,656.5               | 84.8         | 1,059.8      | -555.8                  | 0.00                    | 0.00                   | 0.00                  | 0.00 |
| 4,000.0               | 29.05           | 85.43       | 3,743.9               | 88.7         | 1,108.2      | -581.2                  | 0.00                    | 0.00                   | 0.00                  | 0.00 |
| 4,100.0               | 29.05           | 85.43       | 3,831.3               | 92.5         | 1,156.6      | -606.6                  | 0.00                    | 0.00                   | 0.00                  | 0.00 |
| 4,200.0               | 29.05           | 85.43       | 3,918.8               | 96.4         | 1,205.0      | -632.0                  | 0.00                    | 0.00                   | 0.00                  | 0.00 |
| 4,292.9               | 29.05           | 85.43       | 4,000.0               | 100.0        | 1,250.0      | -655.5                  | 0.00                    | 0.00                   | 0.00                  | 0.00 |
| 4,300.0               | 28.74           | 84.15       | 4,006.2               | 100.3        | 1,253.4      | -657.3                  | 9.73                    | -4.29                  | -18.08                |      |
| 4,400.0               | 25.94           | 63.75       | 4,095.2               | 112.5        | 1,297.0      | -673.2                  | 9.73                    | -2.81                  | -20.40                |      |
| 4,500.0               | 26.38           | 41.59       | 4,185.2               | 138.8        | 1,331.5      | -672.2                  | 9.73                    | 0.44                   | -22.16                |      |
| 4,600.0               | 29.92           | 22.27       | 4,273.5               | 178.6        | 1,355.7      | -654.3                  | 9.73                    | 3.54                   | -19.32                |      |
| 4,700.0               | 35.65           | 7.66        | 4,357.7               | 230.7        | 1,369.1      | -620.1                  | 9.73                    | 5.73                   | -14.61                |      |
| 4,800.0               | 42.68           | 356.97      | 4,435.3               | 293.6        | 1,371.2      | -570.5                  | 9.73                    | 7.03                   | -10.69                |      |
| 4,900.0               | 50.47           | 348.91      | 4,504.0               | 365.4        | 1,362.0      | -507.0                  | 9.73                    | 7.79                   | -8.06                 |      |
| 5,000.0               | 58.70           | 342.52      | 4,562.0               | 444.2        | 1,341.7      | -431.4                  | 9.73                    | 8.23                   | -6.39                 |      |



Planning Report

|                  |                                     |                                     |                                      |
|------------------|-------------------------------------|-------------------------------------|--------------------------------------|
| <b>Database:</b> | EDM                                 | <b>Local Co-ordinate Reference:</b> | Well 307H                            |
| <b>Company:</b>  | Enduring Resources LLC              | <b>TVD Reference:</b>               | KB @ 6849.0usft (Original Well Elev) |
| <b>Project:</b>  | San Juan Basin - West Escavada Unit | <b>MD Reference:</b>                | KB @ 6849.0usft (Original Well Elev) |
| <b>Site:</b>     | 307H Pad                            | <b>North Reference:</b>             | Grid                                 |
| <b>Well:</b>     | 307H                                | <b>Survey Calculation Method:</b>   | Minimum Curvature                    |
| <b>Wellbore:</b> | Wellbore #1                         |                                     |                                      |
| <b>Design:</b>   | Design #1                           |                                     |                                      |

| Planned Survey        |                 |             |                       |              |              |                         |                         |                        |                       |  |
|-----------------------|-----------------|-------------|-----------------------|--------------|--------------|-------------------------|-------------------------|------------------------|-----------------------|--|
| Measured Depth (usft) | Inclination (°) | Azimuth (°) | Vertical Depth (usft) | +N/-S (usft) | +E/-W (usft) | Vertical Section (usft) | Dogleg Rate (°/100usft) | Build Rate (°/100usft) | Turn Rate (°/100usft) |  |
| 5,100.0               | 67.19           | 337.18      | 4,607.4               | 527.6        | 1,310.9      | -345.9                  | 9.73                    | 8.49                   | -5.34                 |  |
| 5,200.0               | 75.84           | 332.48      | 4,639.1               | 613.3        | 1,270.5      | -252.9                  | 9.73                    | 8.65                   | -4.70                 |  |
| 5,297.7               | 84.38           | 328.22      | 4,655.9               | 696.9        | 1,222.9      | -157.3                  | 9.73                    | 8.73                   | -4.36                 |  |
| 5,300.0               | 84.46           | 328.02      | 4,656.1               | 698.8        | 1,221.7      | -155.0                  | 9.73                    | 3.83                   | -8.99                 |  |
| 5,400.0               | 88.35           | 319.08      | 4,662.4               | 779.0        | 1,162.5      | -55.4                   | 9.73                    | 3.89                   | -8.94                 |  |
| 5,433.9               | 89.68           | 316.06      | 4,663.0               | 804.0        | 1,139.6      | -21.7                   | 9.73                    | 3.93                   | -8.90                 |  |
| 5,500.0               | 89.68           | 316.06      | 4,663.4               | 851.6        | 1,093.8      | 43.8                    | 0.00                    | 0.00                   | 0.00                  |  |
| 5,600.0               | 89.68           | 316.06      | 4,663.9               | 923.6        | 1,024.4      | 142.9                   | 0.00                    | 0.00                   | 0.00                  |  |
| 5,700.0               | 89.68           | 316.06      | 4,664.5               | 995.6        | 955.0        | 241.9                   | 0.00                    | 0.00                   | 0.00                  |  |
| 5,800.0               | 89.68           | 316.06      | 4,665.0               | 1,067.6      | 885.6        | 341.0                   | 0.00                    | 0.00                   | 0.00                  |  |
| 5,900.0               | 89.68           | 316.06      | 4,665.6               | 1,139.6      | 816.2        | 440.1                   | 0.00                    | 0.00                   | 0.00                  |  |
| 6,000.0               | 89.68           | 316.06      | 4,666.2               | 1,211.6      | 746.8        | 539.1                   | 0.00                    | 0.00                   | 0.00                  |  |
| 6,100.0               | 89.68           | 316.06      | 4,666.7               | 1,283.6      | 677.4        | 638.2                   | 0.00                    | 0.00                   | 0.00                  |  |
| 6,200.0               | 89.68           | 316.06      | 4,667.3               | 1,355.6      | 608.0        | 737.2                   | 0.00                    | 0.00                   | 0.00                  |  |
| 6,300.0               | 89.68           | 316.06      | 4,667.8               | 1,427.6      | 538.6        | 836.3                   | 0.00                    | 0.00                   | 0.00                  |  |
| 6,400.0               | 89.68           | 316.06      | 4,668.4               | 1,499.6      | 469.2        | 935.4                   | 0.00                    | 0.00                   | 0.00                  |  |
| 6,500.0               | 89.68           | 316.06      | 4,669.0               | 1,571.6      | 399.8        | 1,034.4                 | 0.00                    | 0.00                   | 0.00                  |  |
| 6,600.0               | 89.68           | 316.06      | 4,669.5               | 1,643.6      | 330.4        | 1,133.5                 | 0.00                    | 0.00                   | 0.00                  |  |
| 6,700.0               | 89.68           | 316.06      | 4,670.1               | 1,715.6      | 261.0        | 1,232.5                 | 0.00                    | 0.00                   | 0.00                  |  |
| 6,800.0               | 89.68           | 316.06      | 4,670.6               | 1,787.6      | 191.7        | 1,331.6                 | 0.00                    | 0.00                   | 0.00                  |  |
| 6,900.0               | 89.68           | 316.06      | 4,671.2               | 1,859.6      | 122.3        | 1,430.7                 | 0.00                    | 0.00                   | 0.00                  |  |
| 7,000.0               | 89.68           | 316.06      | 4,671.7               | 1,931.6      | 52.9         | 1,529.7                 | 0.00                    | 0.00                   | 0.00                  |  |
| 7,100.0               | 89.68           | 316.06      | 4,672.3               | 2,003.6      | -16.5        | 1,628.8                 | 0.00                    | 0.00                   | 0.00                  |  |
| 7,200.0               | 89.68           | 316.06      | 4,672.9               | 2,075.6      | -85.9        | 1,727.9                 | 0.00                    | 0.00                   | 0.00                  |  |
| 7,300.0               | 89.68           | 316.06      | 4,673.4               | 2,147.6      | -155.3       | 1,826.9                 | 0.00                    | 0.00                   | 0.00                  |  |
| 7,400.0               | 89.68           | 316.06      | 4,674.0               | 2,219.6      | -224.7       | 1,926.0                 | 0.00                    | 0.00                   | 0.00                  |  |
| 7,500.0               | 89.68           | 316.06      | 4,674.5               | 2,291.6      | -294.1       | 2,025.0                 | 0.00                    | 0.00                   | 0.00                  |  |
| 7,600.0               | 89.68           | 316.06      | 4,675.1               | 2,363.6      | -363.5       | 2,124.1                 | 0.00                    | 0.00                   | 0.00                  |  |
| 7,700.0               | 89.68           | 316.06      | 4,675.7               | 2,435.6      | -432.9       | 2,223.2                 | 0.00                    | 0.00                   | 0.00                  |  |
| 7,800.0               | 89.68           | 316.06      | 4,676.2               | 2,507.6      | -502.3       | 2,322.2                 | 0.00                    | 0.00                   | 0.00                  |  |
| 7,900.0               | 89.68           | 316.06      | 4,676.8               | 2,579.6      | -571.7       | 2,421.3                 | 0.00                    | 0.00                   | 0.00                  |  |
| 8,000.0               | 89.68           | 316.06      | 4,677.3               | 2,651.6      | -641.0       | 2,520.3                 | 0.00                    | 0.00                   | 0.00                  |  |
| 8,100.0               | 89.68           | 316.06      | 4,677.9               | 2,723.6      | -710.4       | 2,619.4                 | 0.00                    | 0.00                   | 0.00                  |  |
| 8,200.0               | 89.68           | 316.06      | 4,678.4               | 2,795.6      | -779.8       | 2,718.5                 | 0.00                    | 0.00                   | 0.00                  |  |
| 8,300.0               | 89.68           | 316.06      | 4,679.0               | 2,867.6      | -849.2       | 2,817.5                 | 0.00                    | 0.00                   | 0.00                  |  |
| 8,400.0               | 89.68           | 316.06      | 4,679.6               | 2,939.6      | -918.6       | 2,916.6                 | 0.00                    | 0.00                   | 0.00                  |  |
| 8,500.0               | 89.68           | 316.06      | 4,680.1               | 3,011.7      | -988.0       | 3,015.6                 | 0.00                    | 0.00                   | 0.00                  |  |
| 8,600.0               | 89.68           | 316.06      | 4,680.7               | 3,083.7      | -1,057.4     | 3,114.7                 | 0.00                    | 0.00                   | 0.00                  |  |
| 8,700.0               | 89.68           | 316.06      | 4,681.2               | 3,155.7      | -1,126.8     | 3,213.8                 | 0.00                    | 0.00                   | 0.00                  |  |
| 8,800.0               | 89.68           | 316.06      | 4,681.8               | 3,227.7      | -1,196.2     | 3,312.8                 | 0.00                    | 0.00                   | 0.00                  |  |
| 8,900.0               | 89.68           | 316.06      | 4,682.3               | 3,299.7      | -1,265.6     | 3,411.9                 | 0.00                    | 0.00                   | 0.00                  |  |
| 9,000.0               | 89.68           | 316.06      | 4,682.9               | 3,371.7      | -1,335.0     | 3,511.0                 | 0.00                    | 0.00                   | 0.00                  |  |
| 9,100.0               | 89.68           | 316.06      | 4,683.5               | 3,443.7      | -1,404.4     | 3,610.0                 | 0.00                    | 0.00                   | 0.00                  |  |
| 9,200.0               | 89.68           | 316.06      | 4,684.0               | 3,515.7      | -1,473.8     | 3,709.1                 | 0.00                    | 0.00                   | 0.00                  |  |
| 9,300.0               | 89.68           | 316.06      | 4,684.6               | 3,587.7      | -1,543.1     | 3,808.1                 | 0.00                    | 0.00                   | 0.00                  |  |
| 9,400.0               | 89.68           | 316.06      | 4,685.1               | 3,659.7      | -1,612.5     | 3,907.2                 | 0.00                    | 0.00                   | 0.00                  |  |
| 9,500.0               | 89.68           | 316.06      | 4,685.7               | 3,731.7      | -1,681.9     | 4,006.3                 | 0.00                    | 0.00                   | 0.00                  |  |
| 9,600.0               | 89.68           | 316.06      | 4,686.3               | 3,803.7      | -1,751.3     | 4,105.3                 | 0.00                    | 0.00                   | 0.00                  |  |
| 9,700.0               | 89.68           | 316.06      | 4,686.8               | 3,875.7      | -1,820.7     | 4,204.4                 | 0.00                    | 0.00                   | 0.00                  |  |
| 9,800.0               | 89.68           | 316.06      | 4,687.4               | 3,947.7      | -1,890.1     | 4,303.4                 | 0.00                    | 0.00                   | 0.00                  |  |
| 9,900.0               | 89.68           | 316.06      | 4,687.9               | 4,019.7      | -1,959.5     | 4,402.5                 | 0.00                    | 0.00                   | 0.00                  |  |
| 10,000.0              | 89.68           | 316.06      | 4,688.5               | 4,091.7      | -2,028.9     | 4,501.6                 | 0.00                    | 0.00                   | 0.00                  |  |
| 10,100.0              | 89.68           | 316.06      | 4,689.0               | 4,163.7      | -2,098.3     | 4,600.6                 | 0.00                    | 0.00                   | 0.00                  |  |
| 10,200.0              | 89.68           | 316.06      | 4,689.6               | 4,235.7      | -2,167.7     | 4,699.7                 | 0.00                    | 0.00                   | 0.00                  |  |



Planning Report

|                  |                                     |                                     |                                      |
|------------------|-------------------------------------|-------------------------------------|--------------------------------------|
| <b>Database:</b> | EDM                                 | <b>Local Co-ordinate Reference:</b> | Well 307H                            |
| <b>Company:</b>  | Enduring Resources LLC              | <b>TVD Reference:</b>               | KB @ 6849.0usft (Original Well Elev) |
| <b>Project:</b>  | San Juan Basin - West Escavada Unit | <b>MD Reference:</b>                | KB @ 6849.0usft (Original Well Elev) |
| <b>Site:</b>     | 307H Pad                            | <b>North Reference:</b>             | Grid                                 |
| <b>Well:</b>     | 307H                                | <b>Survey Calculation Method:</b>   | Minimum Curvature                    |
| <b>Wellbore:</b> | Wellbore #1                         |                                     |                                      |
| <b>Design:</b>   | Design #1                           |                                     |                                      |

| Planned Survey        |                 |             |                       |              |              |                         |                         |                        |                       |
|-----------------------|-----------------|-------------|-----------------------|--------------|--------------|-------------------------|-------------------------|------------------------|-----------------------|
| Measured Depth (usft) | Inclination (°) | Azimuth (°) | Vertical Depth (usft) | +N/-S (usft) | +E/-W (usft) | Vertical Section (usft) | Dogleg Rate (°/100usft) | Build Rate (°/100usft) | Turn Rate (°/100usft) |
| 10,300.0              | 89.68           | 316.06      | 4,690.2               | 4,307.7      | -2,237.1     | 4,798.8                 | 0.00                    | 0.00                   | 0.00                  |
| 10,400.0              | 89.68           | 316.06      | 4,690.7               | 4,379.7      | -2,306.5     | 4,897.8                 | 0.00                    | 0.00                   | 0.00                  |
| 10,500.0              | 89.68           | 316.06      | 4,691.3               | 4,451.7      | -2,375.8     | 4,996.9                 | 0.00                    | 0.00                   | 0.00                  |
| 10,600.0              | 89.68           | 316.06      | 4,691.8               | 4,523.7      | -2,445.2     | 5,095.9                 | 0.00                    | 0.00                   | 0.00                  |
| 10,700.0              | 89.68           | 316.06      | 4,692.4               | 4,595.7      | -2,514.6     | 5,195.0                 | 0.00                    | 0.00                   | 0.00                  |
| 10,800.0              | 89.68           | 316.06      | 4,693.0               | 4,667.7      | -2,584.0     | 5,294.1                 | 0.00                    | 0.00                   | 0.00                  |
| 10,900.0              | 89.68           | 316.06      | 4,693.5               | 4,739.7      | -2,653.4     | 5,393.1                 | 0.00                    | 0.00                   | 0.00                  |
| 11,000.0              | 89.68           | 316.06      | 4,694.1               | 4,811.7      | -2,722.8     | 5,492.2                 | 0.00                    | 0.00                   | 0.00                  |
| 11,100.0              | 89.68           | 316.06      | 4,694.6               | 4,883.7      | -2,792.2     | 5,591.2                 | 0.00                    | 0.00                   | 0.00                  |
| 11,200.0              | 89.68           | 316.06      | 4,695.2               | 4,955.7      | -2,861.6     | 5,690.3                 | 0.00                    | 0.00                   | 0.00                  |
| 11,300.0              | 89.68           | 316.06      | 4,695.7               | 5,027.7      | -2,931.0     | 5,789.4                 | 0.00                    | 0.00                   | 0.00                  |
| 11,400.0              | 89.68           | 316.06      | 4,696.3               | 5,099.7      | -3,000.4     | 5,888.4                 | 0.00                    | 0.00                   | 0.00                  |
| 11,500.0              | 89.68           | 316.06      | 4,696.9               | 5,171.7      | -3,069.8     | 5,987.5                 | 0.00                    | 0.00                   | 0.00                  |
| 11,600.0              | 89.68           | 316.06      | 4,697.4               | 5,243.7      | -3,139.2     | 6,086.6                 | 0.00                    | 0.00                   | 0.00                  |
| 11,700.0              | 89.68           | 316.06      | 4,698.0               | 5,315.7      | -3,208.6     | 6,185.6                 | 0.00                    | 0.00                   | 0.00                  |
| 11,800.0              | 89.68           | 316.06      | 4,698.5               | 5,387.8      | -3,277.9     | 6,284.7                 | 0.00                    | 0.00                   | 0.00                  |
| 11,900.0              | 89.68           | 316.06      | 4,699.1               | 5,459.8      | -3,347.3     | 6,383.7                 | 0.00                    | 0.00                   | 0.00                  |
| 12,000.0              | 89.68           | 316.06      | 4,699.7               | 5,531.8      | -3,416.7     | 6,482.8                 | 0.00                    | 0.00                   | 0.00                  |
| 12,100.0              | 89.68           | 316.06      | 4,700.2               | 5,603.8      | -3,486.1     | 6,581.9                 | 0.00                    | 0.00                   | 0.00                  |
| 12,200.0              | 89.68           | 316.06      | 4,700.8               | 5,675.8      | -3,555.5     | 6,680.9                 | 0.00                    | 0.00                   | 0.00                  |
| 12,300.0              | 89.68           | 316.06      | 4,701.3               | 5,747.8      | -3,624.9     | 6,780.0                 | 0.00                    | 0.00                   | 0.00                  |
| 12,400.0              | 89.68           | 316.06      | 4,701.9               | 5,819.8      | -3,694.3     | 6,879.0                 | 0.00                    | 0.00                   | 0.00                  |
| 12,500.0              | 89.68           | 316.06      | 4,702.4               | 5,891.8      | -3,763.7     | 6,978.1                 | 0.00                    | 0.00                   | 0.00                  |
| 12,600.0              | 89.68           | 316.06      | 4,703.0               | 5,963.8      | -3,833.1     | 7,077.2                 | 0.00                    | 0.00                   | 0.00                  |
| 12,700.0              | 89.68           | 316.06      | 4,703.6               | 6,035.8      | -3,902.5     | 7,176.2                 | 0.00                    | 0.00                   | 0.00                  |
| 12,800.0              | 89.68           | 316.06      | 4,704.1               | 6,107.8      | -3,971.9     | 7,275.3                 | 0.00                    | 0.00                   | 0.00                  |
| 12,900.0              | 89.68           | 316.06      | 4,704.7               | 6,179.8      | -4,041.3     | 7,374.3                 | 0.00                    | 0.00                   | 0.00                  |
| 13,000.0              | 89.68           | 316.06      | 4,705.2               | 6,251.8      | -4,110.6     | 7,473.4                 | 0.00                    | 0.00                   | 0.00                  |
| 13,100.0              | 89.68           | 316.06      | 4,705.8               | 6,323.8      | -4,180.0     | 7,572.5                 | 0.00                    | 0.00                   | 0.00                  |
| 13,200.0              | 89.68           | 316.06      | 4,706.4               | 6,395.8      | -4,249.4     | 7,671.5                 | 0.00                    | 0.00                   | 0.00                  |
| 13,300.0              | 89.68           | 316.06      | 4,706.9               | 6,467.8      | -4,318.8     | 7,770.6                 | 0.00                    | 0.00                   | 0.00                  |
| 13,400.0              | 89.68           | 316.06      | 4,707.5               | 6,539.8      | -4,388.2     | 7,869.7                 | 0.00                    | 0.00                   | 0.00                  |
| 13,500.0              | 89.68           | 316.06      | 4,708.0               | 6,611.8      | -4,457.6     | 7,968.7                 | 0.00                    | 0.00                   | 0.00                  |
| 13,600.0              | 89.68           | 316.06      | 4,708.6               | 6,683.8      | -4,527.0     | 8,067.8                 | 0.00                    | 0.00                   | 0.00                  |
| 13,700.0              | 89.68           | 316.06      | 4,709.1               | 6,755.8      | -4,596.4     | 8,166.8                 | 0.00                    | 0.00                   | 0.00                  |
| 13,800.0              | 89.68           | 316.06      | 4,709.7               | 6,827.8      | -4,665.8     | 8,265.9                 | 0.00                    | 0.00                   | 0.00                  |
| 13,900.0              | 89.68           | 316.06      | 4,710.3               | 6,899.8      | -4,735.2     | 8,365.0                 | 0.00                    | 0.00                   | 0.00                  |
| 14,000.0              | 89.68           | 316.06      | 4,710.8               | 6,971.8      | -4,804.6     | 8,464.0                 | 0.00                    | 0.00                   | 0.00                  |
| 14,100.0              | 89.68           | 316.06      | 4,711.4               | 7,043.8      | -4,874.0     | 8,563.1                 | 0.00                    | 0.00                   | 0.00                  |
| 14,200.0              | 89.68           | 316.06      | 4,711.9               | 7,115.8      | -4,943.4     | 8,662.1                 | 0.00                    | 0.00                   | 0.00                  |
| 14,300.0              | 89.68           | 316.06      | 4,712.5               | 7,187.8      | -5,012.7     | 8,761.2                 | 0.00                    | 0.00                   | 0.00                  |
| 14,400.0              | 89.68           | 316.06      | 4,713.1               | 7,259.8      | -5,082.1     | 8,860.3                 | 0.00                    | 0.00                   | 0.00                  |
| 14,500.0              | 89.68           | 316.06      | 4,713.6               | 7,331.8      | -5,151.5     | 8,959.3                 | 0.00                    | 0.00                   | 0.00                  |
| 14,600.0              | 89.68           | 316.06      | 4,714.2               | 7,403.8      | -5,220.9     | 9,058.4                 | 0.00                    | 0.00                   | 0.00                  |
| 14,700.0              | 89.68           | 316.06      | 4,714.7               | 7,475.8      | -5,290.3     | 9,157.5                 | 0.00                    | 0.00                   | 0.00                  |
| 14,800.0              | 89.68           | 316.06      | 4,715.3               | 7,547.8      | -5,359.7     | 9,256.5                 | 0.00                    | 0.00                   | 0.00                  |
| 14,900.0              | 89.68           | 316.06      | 4,715.8               | 7,619.8      | -5,429.1     | 9,355.6                 | 0.00                    | 0.00                   | 0.00                  |
| 15,000.0              | 89.68           | 316.06      | 4,716.4               | 7,691.8      | -5,498.5     | 9,454.6                 | 0.00                    | 0.00                   | 0.00                  |
| 15,100.0              | 89.68           | 316.06      | 4,717.0               | 7,763.9      | -5,567.9     | 9,553.7                 | 0.00                    | 0.00                   | 0.00                  |
| 15,200.0              | 89.68           | 316.06      | 4,717.5               | 7,835.9      | -5,637.3     | 9,652.8                 | 0.00                    | 0.00                   | 0.00                  |
| 15,300.0              | 89.68           | 316.06      | 4,718.1               | 7,907.9      | -5,706.7     | 9,751.8                 | 0.00                    | 0.00                   | 0.00                  |
| 15,400.0              | 89.68           | 316.06      | 4,718.6               | 7,979.9      | -5,776.1     | 9,850.9                 | 0.00                    | 0.00                   | 0.00                  |
| 15,500.0              | 89.68           | 316.06      | 4,719.2               | 8,051.9      | -5,845.4     | 9,949.9                 | 0.00                    | 0.00                   | 0.00                  |
| 15,600.0              | 89.68           | 316.06      | 4,719.8               | 8,123.9      | -5,914.8     | 10,049.0                | 0.00                    | 0.00                   | 0.00                  |



Planning Report

|                  |                                     |                                     |                                      |
|------------------|-------------------------------------|-------------------------------------|--------------------------------------|
| <b>Database:</b> | EDM                                 | <b>Local Co-ordinate Reference:</b> | Well 307H                            |
| <b>Company:</b>  | Enduring Resources LLC              | <b>TVD Reference:</b>               | KB @ 6849.0usft (Original Well Elev) |
| <b>Project:</b>  | San Juan Basin - West Escavada Unit | <b>MD Reference:</b>                | KB @ 6849.0usft (Original Well Elev) |
| <b>Site:</b>     | 307H Pad                            | <b>North Reference:</b>             | Grid                                 |
| <b>Well:</b>     | 307H                                | <b>Survey Calculation Method:</b>   | Minimum Curvature                    |
| <b>Wellbore:</b> | Wellbore #1                         |                                     |                                      |
| <b>Design:</b>   | Design #1                           |                                     |                                      |

| Measured Depth (usft) | Inclination (°) | Azimuth (°) | Vertical Depth (usft) | +N/-S (usft) | +E/-W (usft) | Vertical Section (usft) | Dogleg Rate (°/100usft) | Build Rate (°/100usft) | Turn Rate (°/100usft) |
|-----------------------|-----------------|-------------|-----------------------|--------------|--------------|-------------------------|-------------------------|------------------------|-----------------------|
| 15,644.2              | 89.68           | 316.06      | 4,720.0               | 8,155.7      | -5,945.5     | 10,092.8                | 0.00                    | 0.00                   | 0.00                  |

| Target Name<br>- hit/miss target<br>- Shape      | Dip Angle (°) | Dip Dir. (°) | TVD (usft) | +N/-S (usft) | +E/-W (usft) | Northing (usft) | Easting (usft) | Latitude    | Longitude    |
|--|---------------|--------------|------------|--------------|--------------|-----------------|----------------|-------------|--------------|
| 307H KOP<br>- plan hits target center<br>- Point | 0.00          | 0.00         | 4,000.0    | 100.0        | 1,250.0      | 1,869,914.86    | 1,237,875.51   | 36.131390°N | 107.613162°W |
| 307H POE<br>- plan hits target center<br>- Point | 0.00          | 0.00         | 4,663.0    | 804.0        | 1,139.6      | 1,870,618.82    | 1,237,765.13   | 36.133319°N | 107.613569°W |
| 307H BHL<br>- plan hits target center<br>- Point | 0.00          | 0.00         | 4,720.0    | 8,155.7      | -5,945.5     | 1,877,970.54    | 1,230,680.01   | 36.153234°N | 107.637912°W |

| Measured Depth (usft) | Vertical Depth (usft) | Name    | Casing Diameter (") | Hole Diameter (") |
|-----------------------|-----------------------|---------|---------------------|-------------------|
| 240.0                 | 240.0                 | 13 3/8" | 13-3/8              | 17-1/2            |
| 2,764.7               | 2,664.0               | 9 5/8"  | 9-5/8               | 12-1/4            |



## Planning Report

**Database:** EDM  
**Company:** Enduring Resources LLC  
**Project:** San Juan Basin - West Escavada Unit  
**Site:** 307H Pad  
**Well:** 307H  
**Wellbore:** Wellbore #1  
**Design:** Design #1

**Local Co-ordinate Reference:** Well 307H  
**TVD Reference:** KB @ 6849.0usft (Original Well Elev)  
**MD Reference:** KB @ 6849.0usft (Original Well Elev)  
**North Reference:** Grid  
**Survey Calculation Method:** Minimum Curvature

| Formations            |                       |                  |           |         |                   |  |
|-----------------------|-----------------------|------------------|-----------|---------|-------------------|--|
| Measured Depth (usft) | Vertical Depth (usft) | Name             | Lithology | Dip (°) | Dip Direction (°) |  |
| 504.0                 | 504.0                 | Ojo Alamo        |           | 0.00    |                   |  |
| 579.0                 | 579.0                 | Kirtland         |           | 0.00    |                   |  |
| 821.0                 | 821.0                 | Fruitland        |           | 0.00    |                   |  |
| 1,119.0               | 1,119.0               | Pictured Cliffs  |           | 0.00    |                   |  |
| 1,321.7               | 1,321.0               | Lewis            |           | 0.00    |                   |  |
| 1,469.1               | 1,467.0               | Chacra           |           | 0.00    |                   |  |
| 2,598.8               | 2,519.0               | Cliff House      |           | 0.00    |                   |  |
| 2,650.3               | 2,564.0               | Menefee          |           | 0.00    |                   |  |
| 3,708.4               | 3,489.0               | Point Lookout    |           | 0.00    |                   |  |
| 3,905.2               | 3,661.0               | Mancos           |           | 0.00    |                   |  |
| 4,220.9               | 3,937.0               | Gallup (Mncs. A) |           | 0.00    |                   |  |
| 4,342.8               | 4,044.0               | MNCS B           |           | 0.00    |                   |  |
| 4,448.6               | 4,139.0               | MNCS C           |           | 0.00    |                   |  |
| 4,484.2               | 4,171.0               | MNCS Cms         |           | 0.00    |                   |  |
| 4,626.1               | 4,296.0               | MNCS D           |           | 0.00    |                   |  |
| 4,823.1               | 4,452.0               | MNCS E           |           | 0.00    |                   |  |
| 4,900.0               | 4,504.0               | MNCS F           |           | 0.00    |                   |  |
| 5,021.8               | 4,573.0               | MNCS G           |           | 0.00    |                   |  |
| 5,149.8               | 4,625.0               | MNCS H           |           | 0.00    |                   |  |
| 5,433.9               | 4,663.0               | MNCS H (TARGET)  |           | 0.00    |                   |  |



**ENDURING RESOURCES IV, LLC**  
**1050 SEVENTEENTH STREET, SUITE 2500**  
**DENVER, COLORADO 80265**

**DRILLING PLAN:** *Drill, complete, and equip single lateral in the Mancos-H formation*

**WELL INFORMATION:**

**Name:** W Escavada Unit 307H

**API Number:** 30-043-

**State:** New Mexico

**County:** San Juan

|                           |                        |                          |              |
|---------------------------|------------------------|--------------------------|--------------|
| <b>Surface Elevation:</b> | 6,824 ft ASL (GL)      | 6,849 ft ASL (KB)        |              |
| <b>Surface Location:</b>  | 19-22N-07W Sec-Twn-Rng | 497 ft FNL               | 2,171 ft FWL |
|                           | 36.131067 ° N latitude | 107.617389 ° W longitude | (NAD 83)     |
| <b>BH Location:</b>       | 12-22N-08W Sec-Twn-Rng | 2,295 ft FSL             | 1,359 ft FWL |
|                           | 36.153234 ° N latitude | 107.637912 ° W longitude | (NAD 83)     |

**Driving Directions:** From Bloomfield, NM: South on US Hwy 550 for 48.9 miles to MM 103.1, turn right (south) on Atkins Road for 5.9 miles to 4-way intersection, right (west) exiting Atkins Road onto existing roadway for 1.9 miles to fork, left (southwest) following existing access for 317H and 300H pads for 0.5 miles to fork, left (south) following existing acces to 302H pad for 0.8 miles, right (west) for 0.9 miles to 305H pad, continue for an additional 0.7 miles to the 307H pad.

**GEOLOGIC AND RESERVOIR INFORMATION:**

| <i>Prognosis:</i> | Formation Tops           | TVD (ft ASL) | TVD (ft KB)  | MD (ft KB)    | O / G / W  | Pressure           |
|-------------------|--------------------------|--------------|--------------|---------------|------------|--------------------|
|                   | Ojo Alamo                | 6,345        | 504          | 504           | W          | normal             |
|                   | Kirtland                 | 6,270        | 579          | 579           | W          | normal             |
|                   | Fruitland                | 6,028        | 821          | 821           | G, W       | sub                |
|                   | Pictured Cliffs          | 5,730        | 1,119        | 1,119         | G, W       | sub                |
|                   | Lewis                    | 5,528        | 1,321        | 1,322         | G, W       | normal             |
|                   | Chacra                   | 5,382        | 1,467        | 1,469         | G, W       | normal             |
|                   | Cliff House              | 4,330        | 2,519        | 2,599         | G, W       | sub                |
|                   | Menefee                  | 4,285        | 2,564        | 2,650         | G, W       | normal             |
|                   | Point Lookout            | 3,360        | 3,489        | 3,708         | G, W       | normal             |
|                   | Mancos                   | 3,188        | 3,661        | 3,905         | O,G        | sub (~0.38)        |
|                   | Gallup (MNCS_A)          | 2,912        | 3,937        | 4,221         | O,G        | sub (~0.38)        |
|                   | <b>MNCS_H (TARGET)</b>   | <b>2,186</b> | <b>4,663</b> | <b>5,434</b>  | <b>O,G</b> | <b>sub (~0.38)</b> |
|                   | <b>PROJECTED WELL TD</b> | <b>2,129</b> | <b>4,720</b> | <b>15,644</b> | <b>O,G</b> | <b>sub (~0.38)</b> |

**Surface:** Nacimiento

**Oil & Gas Zones:** Several gas bearing zones will be encountered; target formation is the Gallup

**Pressure:** Normal (0.43 psi/ft) or sub-normal pressure gradients anticipated in all formations

|   |      |        |                          |              |            |
|---|------|--------|--------------------------|--------------|------------|
| Max. pressure gradient:   | 0.43 | psi/ft | Evacuated hole gradient: | 0.22         | psi/ft     |
| <b>Maximum anticipated BH pressure, assuming maximum pressure gradient:</b>     |      |        |                          | <b>2,030</b> | <b>psi</b> |
| <b>Maximum anticipated surface pressure, assuming partially evacuated hole:</b> |      |        |                          | <b>1,010</b> | <b>psi</b> |

**Temperature:** Maximum anticipated BHT is 135° F or less

**H<sub>2</sub>S INFORMATION:**

**H<sub>2</sub>S Zones:** Encountering hydrogen-sulfide bearing zones is **NOT** anticipated.

**Safety:** Sensors and alarms will be placed in the substructure, on the rig floor, above the pits, and at the shakers.

#### LOGGING, CORING, AND TESTING:

**Mud Logs:** None planned; remote geo-steering from drill out of 9-5/8" casing to TD; gas chromatograph from drillout of 13-3/8" casing to TD.

**MWD / LWD:** Gamma Ray from drillout of 13-3/8" casing to TD

**Open Hole Logs:** None planned

**Testing:** None planned

**Coring:** None planned

**Cased Hole Logs:** CBL on 5-1/2" casing from deepest free-fall depth to surface

#### DRILLING RIG INFORMATION:

**Contractor:** Aztec

**Rig No.:** 1000

**Draw Works:** E80 AC 1,500 hp

**Mast:** Hyduke Triple (136 ft, 600,000 lbs, 10 lines)

**Top Drive:** NOV IDS-350PE (350 ton)

**Prime Movers:** 4 - GE Jenbacher Natural Gas Generator

**Pumps:** 2 - RS F-1600 (7,500 psi)

**BOPE 1:** Cameron double gate ram (13-5/8", 3,000 psi)

**BOPE 2:** Cameron annular (13-5/8", 2,500 psi)

**Choke:** Cameron (4", 10,000 psi)

**KB-GL (ft):** 25

#### BOPE REQUIREMENTS:

*See attached diagram for details regarding BOPE specifications and configuration.*

- 1) Rig will be equipped with upper and lower kelly cocks with handles available.
- 2) Inside BOP and TIW valves will be available to use on all sizes and threads of drill pipe used while drilling the well.
- 2) BOP accumulator will have enough capacity to open the HCR valve, close all rams and annular preventer, and retain minimum of 200 psi above precharge on the closing manifold without the use of closing pumps. The fluid reservoir capacity shall be at least double the usable fluid volume of the accumulator system capacity, and the fluid level shall be maintained at manufacturer's recommendation. There will be two additional sources of power for the closing pumps (electric and air). Sufficient nitrogen bottles will be available and will be recharged when pressure falls below manufacturer's recommended minimum.
- 3) BOP testing shall be conducted (a) when initially installed, (b) whenever any seal is broken or repaired, (c) if the time since the previous test exceeds 30 days. Tests will be conducted using a test plug. BOP ram preventers will be tested to 3,000 psig for 10 minutes, and the annular preventer will be tested to 1,500 psi for 10 minutes. Ram and annular preventers will be tested to 250 psi for 5 minutes. Additionally, BOP and casing strings will be tested to .22 psi/ft or 1,500 psi, whichever is greater but not exceeding 70% of yield strength of the casing, for 30 minutes, prior to drilling out 13-3/8" and 9-5/8" casing. Rams and hydraulically operated remote choke line valve will be function tested daily at a minimum.
- 4) Remote valve for BOP rams, HCR, and choke shall be placed in a location that is readily available to the driller. The remote BOP valve shall be capable of closing and opening the rams.
- 5) Manual locking devices (hand wheels) shall be intalled on rams. A valve will be installed on the annular preventer's closing line as close as possible to the preventer to act as a locking device. The valve will be maintained in the open position and shall only be closed when there is no power to the accumulator.

#### FLUIDS AND SOLIDS CONTROL PROGRAM:

**Fluid Measurement:** Pumps shall be equipped with stroke counters with displays in the dog-house. Slow pump speed shall be recorded daily and after mudding up, at a minimum, on the drilling report. A Pit Volume Totalizer will be installed and the readout will be displayed in the dog-house. Gas-detecting equipment will be installed at the shakers, and readouts will be available in the dog-house and the in the geologist's work-station (if geologist or mud-logger is on-site).

✓ **Closed-Loop System:** A fully, closed-loop system will be utilized. The system will consist of above-ground piping and above-ground storage tanks and bins. The system will not entail any earthen pits, below-grade storage, or drying pads. All equipment will be disassembled and removed from the site when drilling operations cease. The system will be capable of storing all fluids and generated cuttings and of preventing uncontrolled releases of the same. The system will be operated in an efficient manner to allow the recycling and reuse of as much fluid as possible and to minimize the amount of fluids and solids that require disposal.

**Fluid Disposal:** Fluids that cannot be reused, recycled, or returned to the supplier will be hauled to and disposed of at an approved disposal site (Industrial Ecosystem, Inc. or Envirotech, Inc.).

**Solids Disposal:** Drilling solids will be stored (until haul-off) on-site in separate containers with no other waste, debris, or garbage products. Waste solids will be hauled to and disposed of at an approved disposal site (Industrial Ecosystem, Inc. or Envirotech, Inc.).

**Fluid Program:** See "Detailed Drilling Plan" section for specifics.

**DETAILED DRILLING PLAN:**

**SURFACE:** *Drill vertically to casing setting depth (plus necessary rathole), run casing, cement casing to surface.*

|            |    |              |                      |        |
|------------|----|--------------|----------------------|--------|
| 0 ft (MD)  | to | 240 ft (MD)  | Hole Section Length: | 240 ft |
| 0 ft (TVD) | to | 240 ft (TVD) | Casing Required:     | 240 ft |

*Note: Surface hole may be drilled, cased, and cemented with a smaller rig in advance of the drilling rig.*

| Fluid: | Type        | MW (ppg) | FL (mL/30 min) | PV (cp) | YP (lb/100 sqft) | pH  | Comments |
|--------|-------------|----------|----------------|---------|------------------|-----|----------|
|        | Fresh Water | 8.4      | N/C            | 2 - 8   | 2 - 12           | 9.0 | Spud mud |

**Hole Size:** 17-1/2"

**Bit / Motor:** Mill Tooth or PDC, no motor

**MWD / Survey:** No MWD, run deviation survey after drilling

**Logging:** None

| Casing Specs: | Wt (lb/ft) | Grade | Conn. | Collapse (psi) | Burst (psi) | Tens. Body (lbs) | Tens. Conn (lbs) |
|---------------|------------|-------|-------|----------------|-------------|------------------|------------------|
| Specs         | 13.375     | 54.5  | J-55  | BTC            | 1,130       | 2,730            | 853,000          |
| Loading       |            |       |       |                | 105         | 573              | 111,406          |
| Min. S.F.     |            |       |       |                | 10.78       | 4.76             | 7.66             |

*Assumptions: Collapse: fully evacuated casing with 8.4 ppg equivalent external pressure gradient*

*Burst: maximum anticipated surface pressure with 9.5 ppg fluid inside casing while drilling intermediate hole and 8.4 ppg equivalent external pressure gradient*

*Tension: buoyed weight in 8.4 ppg fluid with 100,000 lbs over-pull*

**MU Torque (ft lbs):** Minimum: N/A Optimum: N/A Maximum: N/A

*Make-up as per API Buttress Connection running procedure.*

**Casing Details:** Float shoe, 1 jt casing, float collar, casing to surface

**Centralizers:** 2 centralizers per jt stop-banded 10' from each collar on bottom 3 jts, 1 centralizer per 2 jts to surface

| Cement: | Type    | Weight (ppg) | Yield (cuft/sk) | Water (gal/sk) | Hole Cap. (cuft/ft) | % Excess | Planned TOC (ft MD) | Total Cmt (sx) |
|---------|---------|--------------|-----------------|----------------|---------------------|----------|---------------------|----------------|
|         | Class G | 15.8         | 1.174           | 5.15           | 0.6946              | 100%     | 0                   | 284            |

*Calculated cement volumes assume gauge hole and the excess noted in table*

*Halliburton HALCEM surface cementing blend*

**Notify NMOCD & BLM if cement is not circulated to surface. Cement must achieve 500 psi compressive strength before drilling out.**

**INTERMEDIATE:** Drill as per directional plan to casing setting depth, run casing, cement casing to surface, install wellhead.

|              |    |                |                      |          |
|--------------|----|----------------|----------------------|----------|
| 240 ft (MD)  | to | 2,765 ft (MD)  | Hole Section Length: | 2,525 ft |
| 240 ft (TVD) | to | 2,664 ft (TVD) | Casing Required:     | 2,765 ft |

| Fluid: | Type | MW (ppg)  | FL (mL/30 min) | PV (cp) | YP (lb/100 sqft) | pH        | Comments           |
|--------|------|-----------|----------------|---------|------------------|-----------|--------------------|
|        | LSND | 8.8 - 9.5 | 20             | 8 - 14  | 8 - 14           | 9.0 - 9.5 | OBM as contingency |

**Hole Size:** 12-1/4"

**Bit / Motor:** PDC w/mud motor

**MWD / Survey:** MWD with GR, inclination, and azimuth survey (every 100' at a minimum)

**Logging:** None

**Pressure Test:** NU BOPE and test (as noted above); pressure test 13-3/8" casing to 1,500 psi for 30 minutes.

| Casing Specs: | Wt (lb/ft) | Grade | Conn. | Collapse (psi) | Burst (psi) | Tens. Body (lbs) | Tens. Conn (lbs) |
|---------------|------------|-------|-------|----------------|-------------|------------------|------------------|
| Specs         | 9.625      | 36.0  | J-55  | LTC            | 2,020       | 3,520            | 564,000          |
| Loading       |            |       |       |                | 1,164       | 1,162            | 186,804          |
| Min. S.F.     |            |       |       |                | 1.74        | 3.03             | 3.02             |

**Assumptions:** Collapse: fully evacuated casing with 8.4 ppg equivalent external pressure gradient

Burst: maximum anticipated surface pressure with 9.5 ppg fluid inside casing while drilling production hole and 8.4 ppg equivalent external pressure gradient

Tension: buoyed weight in 8.4 ppg fluid with 100,000 lbs over-pull

**MU Torque (ft lbs):** Minimum: 3,400 Optimum: 4,530 Maximum: 5,660

**Casing Details:** Float shoe, 1 jt casing, float collar, casing to surface

**Centralizers:** 2 centralizers per jt stop-banded 10' from each collar on bottom 3 jts, 1 centralizer per 2 jts to surface

| Cement: | Type        | Weight (ppg) | Yield (cuft/sk) | Water (gal/sk) | Hole Cap. (cuft/ft) | % Excess | Planned TOC (ft MD) | Total Cmt (sx) |
|---------|-------------|--------------|-----------------|----------------|---------------------|----------|---------------------|----------------|
| Lead    | G:POZ Blend | 12.3         | 1.987           | 10.16          | 0.3132              | 40%      | 0                   | 500            |
| Tail    | Class G     | 15.8         | 1.148           | 4.98           | 0.3132              | 10%      | 2,265               | 150            |

Calculated cement volumes assume gauge hole and the excess noted in table

Halliburton ECONOCEM & HALCEM cementing blend

Notify NMOCD & BLM if cement is not circulated to surface. Cement must achieve 500 psi compressive strength before drilling out.

**PRODUCTION:** Drill to TD following directional plan, run casing, cement casing to surface.

|                |    |                |                      |           |
|----------------|----|----------------|----------------------|-----------|
| 2,765 ft (MD)  | to | 15,644 ft (MD) | Hole Section Length: | 12,879 ft |
| 2,664 ft (TVD) | to | 4,720 ft (TVD) | Casing Required:     | 15,644 ft |

|  |                |                |
|--|----------------|----------------|
| <b>Estimated KOP:</b>                    | 4,293 ft (MD)  | 4,000 ft (TVD) |
| <b>Estimated Landing Point (P.O.E.):</b> | 5,434 ft (MD)  | 4,663 ft (TVD) |
| <b>Estimated Lateral Length:</b>         | 10,210 ft (MD) |                |

| Fluid: | Type | MW (ppg)  | FL (mL/30') | PV (cp) | YP (lb/100 sqft) | pH        | Comments           |
|--------|------|-----------|-------------|---------|------------------|-----------|--------------------|
|        | LSND | 8.8 - 9.5 | 20          | 8 - 14  | 8 - 14           | 9.0 - 9.5 | OBM as contingency |

**Hole Size:** 8-1/2"

**Bit / Motor:** PDC w/mud motor

**MWD / Survey:** MWD with GR, inclination, and azimuth (survey every joint from KOP to Landing Point and survey every 100' minimum before KOP and after Landing Point)

**Logging:** GR MWD for entire section, no mud-log or cuttings sampling, no OH WL logs

**Pressure Test:** NU BOPE and test (as noted above); pressure test 9-5/8" casing to 1,500 psi for 30 minutes.

|                      |           |            |       |       |                |             |                  |                  |
|----------------------|-----------|------------|-------|-------|----------------|-------------|------------------|------------------|
| <b>Casing Specs:</b> | Size (in) | Wt (lb/ft) | Grade | Conn. | Collapse (psi) | Burst (psi) | Tens. Body (lbs) | Tens. Conn (lbs) |
| Specs                | 5.500     | 17.0       | P-110 | LTC   | 7,460          | 10,640      | 546,000          | 445,000          |
| Loading              |           |            |       |       | 2,332          | 8,942       | 329,489          | 329,489          |
| Min. S.F.            |           |            |       |       | <b>3.20</b>    | <b>1.19</b> | <b>1.66</b>      | <b>1.35</b>      |

Assumptions: Collapse: fully evacuated casing with 9.5 ppg fluid in the annulus (floating casing during running)  
 Burst: 8,500 psi maximum surface treating pressure with 10.2 ppg equivalent mud weight sand laden fluid with 8.4 ppg equivalent external pressure gradient  
 Tension: buoyed weight in 9.0 ppg fluid with 100,000 lbs over-pull

**MU Torque (ft lbs):** Minimum: 3,470 Optimum: 4,620 Maximum: 5,780

**Casing Details:** Float shoe, float collar, 2 jts casing, float collar, 1 jt casing, toe-initiation sleeve, 20' marker joint, toe-initiation sleeve, casing to KOP with 20' marker joints spaced evenly in lateral every 2,000'. Place Floation Sub at KOP (+/-). Continue running casing to surface. **The toe-initiation sleeves must be positioned INSIDE the 330' unit setback.**

**Centralizers:** Centralizer count and placement may be adjusted based on well conditions and as-drilled surveys.

Lateral: estimated 1 centralizer per joints

Curve: estimated 1 centralizer per joint from landing point to KOP

Vertical: estimated 1 centralizer per 2 joints from KOP to 9-5/8" shoe, 1 per 3 joints from 9-5/8" shoe to surface

| Cement: | Type        | Weight (ppg) | Yield (cuft/sk) | Water (gal/sk) | Hole Cap. (cuft/ft) | % Excess | Planned TOC (ft MD) | Total Cmt (sx) |
|---------|-------------|--------------|-----------------|----------------|---------------------|----------|---------------------|----------------|
| Lead    | G:POZ blend | 12.3         | 1.987           | 10.16          | 0.2691              | 40%      | 0                   | 724            |
| Tail    | G:POZ blend | 13.3         | 1.354           | 5.94           | 0.2291              | 10%      | 4,000               | 2,167          |

Calculated cement volumes assume gauge hole and the excess noted in table

Halliburton ECONOCEM & EXTENDACEM cementing blend

**Notify NMOCD & BLM if cement is not circulated to surface.**

**Note:** The lateral may be drilled past applicable setback to maximize the length of the completed interval and to maximize resource recovery. If the well is drilled past the setback, the toe Initiation sleeve and all perforations will be placed inside the setback. An unorthodox location application is not required because the completed interval will be entirely within the setback as defined and allowed by NMAC 19.15.16.7B(1), NMAC 19.15.16.14B(2), NMAC 19.15.16.15B(2) . W Escavada Unit Order Number is R-14100.

**FINISH WELL: ND BOP, NU WH, RDMO.**

#### COMPLETION AND PRODUCTION PLAN:

**Frac:** Lateral will be fracture-stimulated in approximately 55 plug-and-perf stages with approximately 225,000 bbls slickwater fluid and 19,000,000 lbs of proppant.

**Flowback:** Well will be flowed back through production tubing. An ESP may be used to assist in load water recovery.

**Production:** Well will produce up production tubing via gas-lift into permanent production and storage facilities.

#### ESTIMATED START DATES:

**Drilling:** 2/15/2019


**Completion:** 4/1/2019

**Production:** 5/1/2019


**Prepared by:** Alec Bridge 11/20/2018

# BOPE & CHOKE MANIFOLD DIAGRAMS

## BOPE



## CHOKE MANIFOLD



**Directions from the Intersection of US Hwy 550 & US Hwy 64**  
**in Bloomfield, NM to Enduring Resources, LLC W Escavada Unit #307H**  
**497' FNL & 2171' FWL, Section 19, T22N, R7W, N.M.P.M., Sandoval County, NM**

**Latitude: 36.131067°N Longitude: 107.617389°W Datum: NAD1983**

From the intersection of US Hwy 550 & US Hwy 64 in Bloomfield, NM, travel Southerly on US Hwy 550 for 48.9 miles to Mile Marker 103.1;

Go Right (Southerly) on Atkins Road for 5.9 miles to 4-way intersection;

Go Right (Westerly) exiting Atkins Road onto existing roadway for 1.9 miles to fork in roadway;

Go Left (South-westerly) which is straight following along Enduring N Escavada Unit #317H & Enduring W Escavada Unit #300H existing access's for 0.5 miles to fork in roadway;

Go Left (Southerly) which is straight following along Enduring W Escavada Unit #302H existing access for 0.8 miles to existing #302H location;

Go Right (Westerly) following along Enduring W Escavada Unit #305H proposed access for 4416.6' to begin proposed access on left-hand side, from which continuing for an additional 3708.2' to staked Enduring W Escavada Unit #307H.