

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

APPLICATION FOR PERMIT TO DRILL OR REENTER

FORM APPROVED
OMB No. 1004-0136
Expires January 31, 2004

1a. Type of Work: <input checked="" type="checkbox"/> DRILL <input type="checkbox"/> REENTER		5. Lease Serial No. MDA 701-04-0014	
1b. Type of Well: <input type="checkbox"/> Oil Well <input checked="" type="checkbox"/> Gas Well <input type="checkbox"/> Other		6. If Indian, Allottee or Tribe Name JICARILLA APACHE NATION	
2. Name of Operator JICARILLA APACHE ENERGY CORP		7. If Unit or CA Agreement, Name and No.	
3a. Address P.O. BOX 710 DULCE, NEW MEXICO 87528		8. Lease Name and Well No. JAECO 28-3 No. 3	
3b. Phone No. (include area code) 505-759-3224		9. API Well No. 30-039-30010	
4. Location of Well (Report location clearly and in accordance with any State requirements. *) At surface 1660' FSL & 660' FWL At proposed prod. zone AS ABOVE		10. Field and Pool, or Exploratory BLANCO MESAVERDE	
14. Distance in miles and direction from nearest town or post office* 29.5 MILES SSW OF DULCE, NM		11. Sec., T., R., M., or Blk. and Survey or Area 25, T28N, R3W, NMPM	
15. Distance from proposed* location to nearest property or lease line, ft. (Also to nearest drig. unit line, if any) 660'		12. County or Parish RIO ARRIBA	
16. No. of Acres in lease 8863.50		13. State NM	
17. Spacing Unit dedicated to this well SOUTH HALF - 320 ACRES			
18. Distance from proposed location* to nearest well, drilling, completed, applied for, on this lease, ft. 3236'		20. BLM/BIA Bond No. on file ON FILE	
19. Proposed Depth 6217'			
21. Elevations (Show whether DF, KDB, RT, GL, etc.) 7120' UGL		22. Approximate date work will start* OCTOBER 1, 2006	
		23. Estimated duration 15 DAYS	

24. Attachments

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No.1, shall be attached to this form:

- | | |
|---|--|
| 1. Well plat certified by a registered surveyor. | 4. Bond to cover the operations unless covered by an existing bond on file (see Item 20 above). |
| 2. A Drilling Plan. | 5. Operator certification. |
| 3. A Surface Use Plan (if the location is on National Forest System Lands, the SUPO shall be filed with the appropriate Forest Service Office). | 6. Such other site specific information and/or plans as may be required by the authorized officer. |

25. Signature <i>Charles Neeley</i>	Name (Printed/Typed) CHARLES NEELEY	Date 7/26/06
Title CONTRACT DRILLING ENGINEER		
Approved by (Signature) <i>[Signature]</i>	Name (Printed/Typed)	Date 3/27/07
Title <i>AFM</i>	Office <i>PFO</i>	

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Conditions of approval, if any, are attached.

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

*(Instructions on reverse)

NOTIFY AZTEC OCD 24 HRS.
PRIOR TO CASING & CEMENT

NMOCD



3/30/07

DISTRICT II
1301 W. Grand Ave., Artesia, N.M. 88210

OIL CONSERVATION DIVISION

Revised October 12, 2005

Submit to Appropriate District Office

State Lease - 4 Copies

Fee Lease - 3 Copies

DISTRICT III
1000 Rio Brazos Rd., Aztec, N.M. 87410

1220 South St. Francis Dr.
Santa Fe, NM 87505

DISTRICT IV
1220 South St. Francis Dr., Santa Fe, NM 87505

☐ AMENDED REPORT

WELL LOCATION AND ACREAGE DEDICATION PLAT

¹ API Number 30-039-30010	² Pool Code 72319	³ Pool Name BLANCO - MESA VERDE
⁴ Property Code 36388	⁵ Property Name JAECO 28-3	⁶ Well Number 3
⁷ OGRID No. 11859	⁸ Operator Name JICARILLA APACHE ENERGY CORP.	⁹ Elevation 7120

¹⁰ Surface Location

UL or lot no.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County
L	25	28-N	3-W		1660	SOUTH	660	WEST	RIO ARRIBA

11 Bottom Hole Location If Different From Surface

UL or lot no.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County
12 Dedicated Acres S/320 Acres		13 Joint or Infill N		14 Consolidation Code			15 Order No.		

NO ALLOWABLE WILL BE ASSIGNED TO THIS COMPLETION UNTIL ALL INTERESTS HAVE BEEN CONSOLIDATED
OR A NON-STANDARD UNIT HAS BEEN APPROVED BY THE DIVISION

16

SECTION COR.
FD 2 1/2" BC
1917 G.L.O.

5282.22' (M)

E

N 0-02-09

660'

1660'

25

LAT: 36.60804° N. (NAD 83)
LONG: 107.10885° W. (NAD 83)

RECEIVED
MAR 2007
OIL CONS. DIV. DIST. 3

SECTION COR.
FD 2 1/2" BC
1917 G.L.O.

N 89-44-34 E 5274.42' (M)

SECTION COR.
FD 2 1/2" BC
1917 G.L.O.

17 OPERATOR CERTIFICATION

I hereby certify that the information contained herein is true and complete to the best of my knowledge and belief, and that this organization either owns a working interest or unleased mineral interest in the land including the proposed bottom hole location or has a right to drill this well at this location pursuant to a contract with an owner of such a mineral or working interest, or to a voluntary pooling agreement or a compulsory pooling order heretofore entered by the division.

Signature Charles Nealey 7/24/50 Date 7/24/50
Printed Name Charles Nealey

18 SURVEYOR CERTIFICATION

I hereby certify that the well location shown on this plat was plotted from field notes of actual surveys made by me or under my supervision, and that the same is true and correct to the best of my belief.

APRIL 25, 2006

Date of Survey _____

Signature and Seal of Professional Surveyor

Certificate Number

Submit 3 Copies To Appropriate District Office
District I
1625 N. French Dr., Hobbs, NM 88240
District II
1301 W. Grand Ave., Artesia, NM 88210
District III
1000 Rio Brazos Rd., Aztec, NM 87410
District IV
1220 S. St. Francis Dr., Santa Fe, NM 87505

State of New Mexico
Energy, Minerals and Natural Resources

Form C-103
May 27, 2004

OIL CONSERVATION DIVISION
1220 South St. Francis Dr.
Santa Fe, NM 87505

WELL API NO. 30-039-30010
5. Indicate Type of Lease STATE <input type="checkbox"/> FEE <input type="checkbox"/>
6. State Oil & Gas Lease No.
7. Lease Name or Unit Agreement Name Jicarilla Apache MDA 701-04-0014
8. Well Number JAECO 28-3 No. 3
9. OGRID Number 11859
10. Pool name or Wildcat Blanco Mesaverde

SUNDRY NOTICES AND REPORTS ON WELLS (DO NOT USE THIS FORM FOR PROPOSALS TO DRILL OR TO DEEPEN OR PLUG BACK TO A DIFFERENT RESERVOIR. USE "APPLICATION FOR PERMIT" (FORM C-101) FOR SUCH PROPOSALS.)	
1. Type of Well: Oil Well <input type="checkbox"/> Gas Well <input checked="" type="checkbox"/> Other	
2. Name of Operator Jicarilla Apache Energy Corp	
3. Address of Operator P.O. Box 710, Dulce NM, 87528	
4. Well Location Unit Letter L : 1660 feet from the South line and 660 feet from the West line Section 25 Township 28 North Range 3 West NMPM Rio Arriba County New Mexico	
11. Elevation (Show whether DR, RKB, RT, GR, etc.) 7120' UGL	
Pit or Below-grade Tank Application <input checked="" type="checkbox"/> or Closure <input type="checkbox"/>	
Pit type Drilling Reserve Pit Depth to Groundwater <50 ft Distance from nearest fresh water well >1000 ft Distance from nearest surface water <200 ft	
Pit Liner Thickness: 15 mfl Below-Grade Tank: Volume bbls; Construction Material Location Dirt	

12. Check Appropriate Box to Indicate Nature of Notice, Report or Other Data

NOTICE OF INTENTION TO: PERFORM REMEDIAL WORK <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> TEMPORARILY ABANDON <input type="checkbox"/> CHANGE PLANS <input type="checkbox"/> PULL OR ALTER CASING <input type="checkbox"/> MULTIPLE COMPL <input type="checkbox"/> OTHER: Application for New Drilling Reserve Pit <input checked="" type="checkbox"/>	SUBSEQUENT REPORT OF: REMEDIAL WORK <input type="checkbox"/> ALTERING CASING <input type="checkbox"/> COMMENCE DRILLING OPNS. <input type="checkbox"/> P AND A <input type="checkbox"/> CASING/CEMENT JOB <input type="checkbox"/> OTHER: <input type="checkbox"/>
--	---

13. Describe proposed or completed operations. (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work). SEE RULE 1103. For Multiple Completions: Attach wellbore diagram of proposed completion or recompletion.

Drilling reserve pit to be located approximately 40 feet from well head. Pit to be lined, constructed, operated and closed in accordance with NMOCD guidelines and BLM, BIA, Jicarilla Apache Oil & Gas Administration and JAECO procedures.

I hereby certify that the information above is true and complete to the best of my knowledge and belief. I further certify that any pit or below-grade tank has been/will be constructed or closed according to NMOCD guidelines ☒, a general permit ☐ or an (attached) alternative OCD-approved plan ☐.

SIGNATURE Charles Neeley TITLE Contract Drilling Engineer DATE 7/21/06

Type or print name Charles Neeley E-mail address: neelece@msn.com Telephone No. 505-486-0211


For State Use Only

APPROVED BY: [Signature] TITLE DEPUTY OIL & GAS INSPECTOR, DIST. 4 DATE MAR 30 2007
Conditions of Approval (if any):

COMPANY: JICARILLA APACHE ENERGY CORP.
 LEASE: JAECO 28-3 No. 3
 FOOTAGE: 1660 FSL 660 FWL
 SEC.: 25 TWN: 28-N RNG: 3-W NMPM
 ELEVATION: 7120'

NOTE:

DAGGETT ENTERPRISES, INC. IS NOT LIABLE FOR UNDERGROUND UTILITIES OR PIPELINES. NEW MEXICO ONE CALL TO BE NOTIFIED 48 HOURS PRIOR TO EXCAVATION OR CONSTRUCTION.



ELEV. A-A'

				C/L
7140				
7130				
7120				
7110				
7100				

ELEV. B-B'

				C/L
7140				
7130				
7120				
7110				
7100				

ELEV. C-C'

				C/L
7140				
7130				
7120				
7110				
7100				

REVISION:	DATE:	REVISED BY:

Daggett Enterprises, Inc.
 Surveying and Oil Field Services
 P. O. Box 15068 • Farmington, NM 87401
 Phone (505) 326-1772 • Fax (505) 326-8019
 NEW MEXICO L.S. No. 14831
 DRAWN BY: B.L.
 ROW#: JAED08

Daggett Enterprises, Inc.
 DATE: 05/08/08

Jicarilla Apache Energy Corp

JAECO 28-3 No. 3

1660' FSL & 660' FWL

Section 25, T28N, R3W, NMPM

Rio Arriba County, New Mexico

TEN POINT DRILLING PLAN

1. **Surface Formation:** San Jose

2. **Surface Elevation:** 7120' UGL

Est KB, ft: 7132

3. **Estimated Formation Tops:**

Formation	Top	Top	Rock Type	Comments
	MD (KB), ft	Subsea, ft		
San Jose	Surface	Surface	Sandstone & Shale	Sticking
Nacimiento	2266	4866	Shale & Sandstone	Bit balling, sticking & LC
Ojo Alamo	3371	3761	Sandstone	Gauge Hole
Kirtland	3516	3616	Shale w/Sandstone	
Fruitland	3611	3521	Coal, Shale, Sandstone	Gas, Water
Pictured Cliffs	3672	3460	Sandstone, Shale, Coal	Gas - Mud Loss
Lower PC	3838	3294	Sandstone & Shale	Gas - Mud Loss
Lewis	4056	3076	Shale	
Huerfanito	4432	2700	Shale	Bentonite
Cliff House	5716	1416	Sandstone	Gas
Menefee	5744	1388	Coal, Shale, Sandstone	Gas & Oil
Pt. Lookout	5972	1160	Sandstone & Shale	Gas
Mancos	6142	990	Shale	
Total Depth:	6217	915		

4. **Casing and Cementing Program:**

Drill a 12 1/4" Hole to 320'. A new string of 9 5/8" 36# J-55 or K-55 ST&C casing will be set and cemented to the surface in a single stage with 180 sacks (212.5 cf) of Class "B" cement (yield = 1.18 cf/sk) containing 2% CaCl₂ and 1/4 lb/sack cellophane flake. Slurry volume assumes 100% excess over calculated hole volume. Clearance between couplings and hole is 1.625". If cement does not circulate to surface, cement will be topped off using 1" pipe down the 12 1/4" by 9 5/8" annulus.

Safety factors utilized in the design of this casing string were: burst = 1.1; collapse = 1.125; and tension = 1.8 or 100,000 lb overpull whichever is greater.

Hole Dia	Casing Data				Collapse (psi)	Burst (psi)	Jt. Strength (Lbs.)
	OD	Wt/FT	Grade	Thread			
12 1/4"	9 5/8"	36	J-55	STC	2,020	3,520	394,000
		36	K-55	STC	2,020	3,950	452,000

WOC 12 HOURS. Nipple up 11" 2000# BOPE. Install proper size test plug, calibrated test guage and recorder. Pressure test BOPE at 250 psi for 5 minutes and 2000 psi for 10 minutes. Pull test plug, drill wiper plug, float collar and cement to within 10' of casing shoe. Close pipe rams and pressure test surface casing to 1500 psi for 30 minutes.

Drilling Plan
Jicarilla Apache Energy Corporation
JAECO 28-3 No. 3

4. Casing and Cementing Program: Continued

Drill an 8 3/4" hole to 4126' feet, approximately 70' feet into the Lewis Shale.

Run Induction and Compensated density/neutron logs from 4126' to the surface casing shoe.

A string of new 7" 20#, J-55, STC Intermediate casing will be set at 4126' with a mechanical DV tool set at 2321', 55' below Nacimiento top. Stage 1 (4126' - 2321', 1805') will be cemented with 167 sacks (314.3 cf) of 35/65 Poz/B + 6% Gel + 5#/sk Gilsonite and 1/4 #/sk cellophane flake mixed at 12.1 ppg, yield 1.88 cf/sk. Followed by 136 sacks (170.7 cf) Class B with 5#/sk Gilsonite, 1/4#/sk cellophane flake and mixed at 15.2 ppg, yield 1.26 cf/sk.

Circulate and WOC between stages for four (4) hours. Stage 2 (2321' - surface) will be cemented with 284 sacks (538.8 cf) of 35/65 Poz/B + 6% Gel + 10#/sk Gilsonite and 1/4 #/sk cellophane flake mixed at 12.5 ppg, yield 1.90 cf/sk. Followed by 50 sks (63cf) Class B with 5#/sk Gilsonite and 1/4 #/sk cellophane flake, mixed at 15.2 ppg, yield 1.26 cf/sk. Slurry volumes assume a 75% excess over gauge hole volume for stage 1 and 83% over gauge volume for stage 2 (consistent with our experience in the area). Cement volume is subject to change after review of open hole caliper logs.

Clearance between couplings and hole is 1.094 ". Safety factors utilized in the design of this casing string were: burst = 1.1; collapse = 1.125; and tension = 1.8 or 100,000 lb over pull, whichever is greater.

Hole Dia	Casing Data				Collapse (psi)	Burst (psi)	Jt. Strength (Lbs.)
	OD	Wt/FT	Grade	Thread			
8.75"	7.0"	20	J-55	STC	2,270	3,740	234,000

WOC 12 Hours: Nipple up BOP, tag cement & drill out DV, pressure test casing to 500 psi, drill out float collar and cement to within 10' of casing shoe, close pipe rams and pressure test casing/BOPE to 2000 psi for 30 minutes.

Air drill a 6 1/4" hole from 4126' to 6217' TD, approximately 75' feet into the Upper Mancos.

Run Dual Induction and Compensated density/neutron logs from TD to the intermediate casing.

A new 4 1/2" 10.5#, J-55, STC production liner will be run from 6217' TD to a minimum overlap of 120 feet inside the 7" intermediate casing (6217' - 4006', 2211'). This string will be cemented in a single stage with 10 bbls POZ spacer w/4% gel, .2% Halad 9, .15# Fe & 3% KCl mixed at 11.0 ppg followed by 257 sacks (339.8 cf) 50/50 Poz/H containing 2% Gel, 5#/sk Gilsonite, 1/4 #/sk Flocele, 4% H-9 and 0.2% HR-5, mixed at 13.5 ppg, yield 1.32 cf/sk.

Slurry volume assumes a 50% excess over gauge hole volume. Cement volume is subject to change after review of the open hole caliper log. Clearance between couplings and hole is 1.25". Safety factors utilized in the design of this casing string were burst = 1.1; collapse = 1.125; and tension = 1.8 or 100,000 lb overpull, whichever is greater.

Hole Dia	Casing Data				Collapse (psi)	Burst (psi)	Jt Strength (Lbs.)
	OD	Wt/FT	Grade	Thread			
6.25"	4.5"	10.5	J-55	STC	4,010	4,790	132,000

Drilling Plan
Jicarilla Apache Energy Corporation
JAECO 28-3 No. 3

4. Casing and Cementing Program: Continued

Bits: 12 1/4" surface hole - MT class 115 or 116 to ~320 feet.
8 3/4" intermediate hole - TCI class 447 to ~4126'.
6 1/4" production hole - Air hammer and bit - to TD

Centralizers:

Surface string: 3 - 9 5/8" X 12 1/4": One centralizer run in middle of shoe joint with lock ring and one centralizer each on the next two joints of casing.

Intermediate string: 4 - 7" X 8 3/4" turbolizers will be spaced such that one is just below the Basal Fruitland Coal, three (3) across the Fruitland/Kirtland and one (1) into the Ojo Alamo. One centralizer will be run on the 1st jt of casing, the PC will be centralized, a centralizer will be run above and one centralizer will be run below the DV tool.

Production string: 7 - 4 1/2" X 6 1/4" bow spring centralizers will be run across all prospective pays; provided well control conditions permit.

Float Equipment:

Surface string: Texas pattern guide shoe w/insert float (1 jt above shoe).

Intermediate string: Cement nose guide shoe, float collar and DV tool with 2 cement baskets below DV tool.

Production string: Cement nose float shoe and a float collar (1 jt above shoe).

5. Pressure Control Equipment:

A 2,000 psi BOP well control system will be utilized. BOP's and choke manifold will be installed and pressure tested to a minimum of 2000 psig before drilling out of surface casing. Pipe rams will be operated daily. Pipe and blind rams will be operated on each trip. BOP's, intermediate casing and choke manifold will be pressure tested to 2000 psi prior to drill out of the 7" intermediate casing shoe.

7" & 4 1/2" casing rams will be installed prior to running intermediate and production casing, respectfully.

A full opening internal blowout preventor or drill pipe safety valve (capable of fitting all connections) will be on the rig floor at all times.

An upper kelly cock will be utilized. The handle will be available on rig floor at all times.

A BOPE pit level drill shall be conducted weekly for each drilling crew.

6. Mud Program:

The well will be spudded and drilled to surface casing depth with a high viscosity slurry of bentonite, lime and fresh water. A fresh water, low solids, non-dispersed mud system will be utilized to drill the well from surface casing to intermediate casing depth. Air will be used to drill from intermediate casing depth to total TD; Mud circulating equipment, water, and mud materials (not mixed) sufficient to maintain the capacity of the hole and circulating pits will be in place and operational during air drilling operations.

Sufficient mud materials will be on location at all times to maintain mud properties and to control any lost circulation problem or unforeseen abnormal pressures.

Mud volume markers will be in place and visually monitored and recorded on a routine basis.

Drilling Plan
Jicarilla Apache Energy Corporation
JAECO 28-3 No. 3

6. **Mud Program:** Continued

Mud Property Guidelines:

Interval (ft)	Weight (ppg)	Vis (sec/qt)	pH	Fluid Loss (cc/30 min)
0 - 320'	8.6 - 9.2	40 - 35	9 - 9.5	No Control
320' - 4126'	8.6 - 9.2	30 - 35	8.0 - 8.5	< 10
4126' - TD	Air	Air	Air	Air

Note: Raise mud viscosity to 45 - 60 for logging. Thin mud viscosity to 40 - 45 to run casing. Lost Circulation: may occur anywhere from the Nacimiento formation to intermediate depth. Have a minimum of 10% LCM in mud prior to running and cementing intermediate casing. Mud pH will be maintained with lime at the recommended levels to assure drill pipe corrosion protection.

7. **Auxiliary Equipment:**

All applicable equipment defined in Onshore Order No. 2 will be in place and operational during **Air Drilling Operations**.

8. **Logging Program:**

Dual Induction with GR and Neutron / Density logs will be run from TD to surface casing shoe.

Coring and Drill Stem Testing Program:

No cores or drill stem tests are planned

9. **Abnormal Pressure and/or Temperature:**

Although not expected, abnormal pressures are possible in the Fruitland formation. Abnormal temperatures are not expected.


Estimated Bottom Hole, Pressure: 1840 psig **BHT:** 140 deg F

10. **Anticipated Starting Date:** October 1, 2006

Duration of Operations: It is estimated a total of 15 days will be required for drilling operations.

JAECO 28-3 No. 3

2000 psi BOP Stack
Minimum Requirements




Components

- 1 - Wellhead 9-5/8" (2M)
 - 2 - Drilling spool 11" (2M)
 - 3 - A double or two single rams with blinds on bottom 11" (2M)
 - 4 - Bell nipple*
 - 5 - 2" Manual valves (2M)
- *Note: A Rotating Head will replace the Bell nipple during air drilling operations.
All line and valve sizes listed are minimum requirements.

JAECO 28-3 No. 3

2000 psi Choke Manifold

Minimum Requirements



Jicarilla Apache Energy Corp proposes to drill a vertical well to develop the Mesa Verde formation at the described location in accordance to the attached Drilling and Surface Use Plans.

This location has been archaeologically surveyed and an EA prepared by Velarde Energy Services. Copies of their report have been submitted directly to your office.

The location including respective right-of-ways was On-Sited on July 6, 2006. The stipulations made at the onsite were: 1) to construct a drainage dam, with access across the top, for access across the wash 40' east of location; A 24" CMP culvert is to be used to control pond overflow and 2) to cleanout and repair the existing pond located approximately 300' NE of location. These changes have been made and are incorporated into the applicable documents contained in this APD.

This APD also is serving as an application to obtain expedited road and pipeline right-of-ways. These right-of-ways are explained in detail in the Surface Use Plan.

Jicarilla Apache Energy Corp appreciates your efforts in assisting us with this project and respectfully solicits your approval.