


5 USGS

1 El Paso Prod.

Form 9-581a 1 File
(Feb. 1961)

(SUBMIT IN TRIPLICATE)

UNITED STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEY

Budget Bureau No. 42-R358.4
Approval expires 12-31-60.Land Office **Santa Fe**Lease No. **SF 078924**Unit **RECEIVED**

JUN 16 1960

SUNDRY NOTICES AND REPORTS ON WELLS

U. S. GEOLOGICAL SURVEY
CLINTON, NEW MEXICO

NOTICE OF INTENTION TO DRILL.....	SUBSEQUENT REPORT OF WATER SHUT-OFF.....	X
NOTICE OF INTENTION TO CHANGE PLANS.....	SUBSEQUENT REPORT OF SHOOTING OR ACIDIZING.....	
NOTICE OF INTENTION TO TEST WATER SHUT-OFF.....	SUBSEQUENT REPORT OF ALTERING CASING.....	
NOTICE OF INTENTION TO RE-DRILL OR REPAIR WELL.....	SUBSEQUENT REPORT OF RE-DRILLING OR REPAIR.....	
NOTICE OF INTENTION TO SHOOT OR ACIDIZE.....	SUBSEQUENT REPORT OF ABANDONMENT.....	
NOTICE OF INTENTION TO PULL OR ALTER CASING.....	SUPPLEMENTARY WELL HISTORY.....	
NOTICE OF INTENTION TO ABANDON WELL.....		

(INDICATE ABOVE BY CHECK MARK NATURE OF REPORT, NOTICE, OR OTHER DATA)

June 15, 1960

Connie
Well No. **#3-29** is located **1850** ft. from **[N]** line and **1850** ft. from **[E]** line of sec. **29**
[S] **[W]**

NE/4 SW/4 Sec. 29

(1/4 Sec. and Sec. No.)

24N

(Twp.)

7W

(Range)

NMPM

(Meridian)

Escrito-Gallup

(Field)

Rio Arriba

(County or Subdivision)

New Mexico


(State or Territory)

Ground LevelThe elevation of the ~~surface~~ above sea level is **7330** ft.

DETAILS OF WORK

(State names of and expected depths to objective sands; show sizes, weights, and lengths of proposed casings; indicate mudding jobs, cementing points, and all other important proposed work)

Spudded 5:30 P. M. 5-17-60. Drilled 15" hole to 205'. Ran 6 joints 10-3/4" 32.75# H-40 casing. T. E. 189' set at 204' R. K. B. Cemented w/200 sx plus 2% CaCl. P. O. B. 4:45 A. M. 5-18-60. WOC. Drilled 8-3/4" hole to 7164'. Ran 77 joints 7" 26# J-55 8 Rd. S. T. & C. casing and 142 joints 23# J-55 8 Rd. S. T. & C. casing. T. E. 7147.56' set at 7161.76' R. K. B. Cemented w/250 sx 4% gel and 100 sx regular. P. O. B. 3:16 P. M. 6-13-60.



I understand that this plan of work must receive approval in writing by the Geological Survey before operations may be commenced.

Company **Val R. Reese & Associates, Inc.**Address **Lobby of Simms Bldg.****Albuquerque, New Mexico**By **Val R. Reese**Title **President**