District I
1625 N. French Dr, Hobbs, NM 88240
District II
1301 W. Grand Avenue, Artesia, NM 88210
District III
1000 Rio Brazos Road, Aztec, NM 87410
District IV
1220 S. St. Francis Dr., Santa Fe, NM 87505

# State of New Mexico Energy Minerals and Natural Resources Department Oil Conservation Division 1220 South St. Francis Dr. Santa Fe, NM 87505

For temporary pits, closed-loop systems, and below-grade tanks, submit to the appropriate NMOCD District Office.
For permanent pits and exceptions submit to the Santa Fe Environmental Bureau office and provide a copy to the appropriate NMOCD District Office.

| 30  | 170 |
|-----|-----|
| ~)" | 40  |

# Pit, Closed-Loop System, Below-Grade Tank, or Proposed Alternative Method Permit or Closure Plan Application

| Proposed Alternative Method Permit or Closure Plan Application   |  |  |
|--|--|--|
| Type of action:  Permit of a pit, closed-loop system, below-grade tank, or proposed alternative method  Closure of a pit, closed-loop system, below-grade tank, or proposed alternative method  Modification to an existing permit  Closure plan only submitted for an existing permitted or non-permitted pit, closed-loop system, below-grade tank, or proposed alternative method |  |  |
| Instructions: Please submit one application (Form C-144) per individual pit, closed-loop system, below-grade tank or alternative request   |  |  |
| Please be advised that approval of this request does not relieve the operator of liability should operations result in pollution of surface water, ground water or the environment. Nor does approval relieve the operator of its responsibility to comply with any other applicable governmental authority's rules, regulations or ordinances.                                      |  |  |
| Operator: ELM RIDGE EXPLORATION COMPANY, LLC OGRID #: 149052   |  |  |
| Address: P. O. BOX 156, BLOOMFIELD, NM 87413   |  |  |
| Facility or well name: JICARILLA APACHE J 5  |  |  |
| API Number: <u>30-039-30258</u> OCD Permit Number:   |  |  |
| U/L or Qtr/Qtr J Section 4 Township 23 N Range 4 W County: RIO ARRIBA  |  |  |
| Center of Proposed Design: Latitude <u>36.25114° N</u> Longitude <u>107.25980° W</u> NAD: □1927 ⊠ 1983   |  |  |
| Surface Owner:  Foderal State Private Tribal Trust or Indian Allotment   |  |  |
| 2.   |  |  |
| ☑ Pit: Subsection F or G of 19.15.17.11 NMAC   Temporary: ☑ Drilling ☐ Workover   ☐ Permanent ☐ Emergency ☐ Cavitation ☐ P&A   ☑ Lined ☐ Unlined Liner type: Thickness 20 mil ☑ LLDPE ☐ HDPE ☐ PVC ☐ Other ☐   ☑ String-Reinforced   Liner Seams: ☑ Welded ☑ Factory ☐ Other ☐ Volume:   2.939 bbl Dimensions: L 160' x W 40' x D 10'  |  |  |
| Closed-loop System: Subsection H of 19.15.17.11 NMAC   Type of Operation: P&A Drilling a new well Workover or Drilling (Applies to activities which require prior approval of a permit or notice of intent)   Drying Pad Above Ground Steel Tanks Haul-off Bins Other Lined Unlined Liner type: Thicknessmil LLDPE   HDPE PVC Other Liner Seams: Welded Factory Other                |  |  |
| Below-grade tank: Subsection I of 19.15.17.11 NMAC   Volume:   |  |  |
| 5.  Alternative Method:  |  |  |

Submittal of an exception request is required. Exceptions must be submitted to the Santa Fe Environmental Bureau office for consideration of approval.

| ·  |                                  |
|--|----------------------------------|
| 6.  Fencing: Subsection D of 19.15.17.11 NMAC (Applies to permanent pits, temporary pits, and below-grade tanks)   |                                  |
| Chain link, six feet in height, two strands of barbed wire at top (Required if located within 1000 feet of a permanent residence, school,  | hospital,                        |
| institution or church)  Four foot height, four strands of barbed wire evenly spaced between one and four feet  |                                  |
| Alternate. Please specify minimum 36" hog wire topped with at least 1 strand of barbed wire = at least 48" high fence  |                                  |
| 7.   |                                  |
| Netting: Subsection E of 19.15.17.11 NMAC (Applies to permanent pits and permanent open top tanks)   |                                  |
| Screen Notting Other  Marthly impacting (If patting an according is not physically faceible)   |                                  |
| Monthly inspections (If netting or screening is not physically feasible)   |                                  |
| Signs: Subsection C of 19.15.17.11 NMAC  |                                  |
| 12"x 24", 2" lettering, providing Operator's name, site location, and emergency telephone numbers  |                                  |
| ☑ Signed in compliance with 19.15.3.103 NMAC   |                                  |
| 9. Administrative Approvals and Exceptions:  |                                  |
| Justifications and/or demonstrations of equivalency are required. Please refer to 19.15.17 NMAC for guidance.  |                                  |
| Please check a box if one or more of the following is requested, if not leave blank:  Administrative approval(s): Requests must be submitted to the appropriate division district or the Santa Fe Environmental Bureau   | office for                       |
| consideration of approval. See requests for alternate fence, slopes, & marker on Pages 2 & 3 of attachment   |                                  |
| Exception(s): Requests must be submitted to the Santa Fe Environmental Bureau office for consideration of approval.  |                                  |
| 10. Siting Criteria (regarding permitting): 19.15.17.10 NMAC   |                                  |
| Instructions: The applicant must demonstrate compliance for each siting criteria below in the application. Recommendations of accept material are provided below. Requests regarding changes to certain siting criteria may require administrative approval from the appro-  | otable source<br>priate district |
| office or may be considered an exception which must be submitted to the Santa Fe Environmental Bureau office for consideration of a Applicant must attach justification for request. Please refer to 19.15.17.10 NMAC for guidance. Siting criteria does not apply to dryi   | pproval.                         |
| above-grade tanks associated with a closed-loop system.  | ng pads or                       |
| Ground water is less than 50 feet below the bottom of the temporary pit, permanent pit, or below-grade tank.  - NM Office of the State Engineer - iWATERS database search; USGS; Data obtained from nearby wells   | ☐ Yes ⊠ No                       |
| Within 300 feet of a continuously flowing watercourse, or 200 feet of any other significant watercourse or lakebed, sinkhole, or playa lake (measured from the ordinary high-water mark).  | ☐ Yes ⊠ No                       |
| - Topographic map; Visual inspection (certification) of the proposed site  | ☐ Yes ☒ No                       |
| Within 300 feet from a permanent residence, school, hospital, institution, or church in existence at the time of initial application.  (Applies to temporary, emergency, or cavitation pits and below-grade tanks)  - Visual inspection (certification) of the proposed site; Aerial photo; Satellite image  | □ NA                             |
| Within 1000 feet from a permanent residence, school, hospital, institution, or church in existence at the time of initial application.   | ☐ Yes ☒ No<br>☐ NA               |
| (Applies to permanent pits) - Visual inspection (certification) of the proposed site; Aerial photo; Satellite image  |                                  |
| Within 500 horizontal feet of a private, domestic fresh water well or spring that less than five households use for domestic or stock watering purposes, or within 1000 horizontal feet of any other fresh water well or spring, in existence at the time of initial application.  - NM Office of the State Engineer - iWATERS database search; Visual inspection (certification) of the proposed site | ☐ Yes ⊠ No                       |
| Within incorporated municipal boundaries or within a defined municipal fresh water well field covered under a municipal ordinance  | ☐ Yes ⊠ No                       |
| adopted pursuant to NMSA 1978, Section 3-27-3, as amended.  - Written confirmation or verification from the municipality; Written approval obtained from the municipality  |                                  |
| Within 500 feet of a wetland US Fish and Wildlife Wetland Identification map; Topographic map; Visual inspection (certification) of the proposed site  | ☐ Yes ⊠ No                       |
| Within the area overlying a subsurface mine Written confirmation or verification or map from the NM EMNRD-Mining and Mineral Division  | ☐ Yes ☒ No                       |
| Within an unstable area.  - Engineering measures incorporated into the design; NM Bureau of Geology & Mineral Resources; USGS, NM Geological Society; Topographic map  | ☐ Yes ⊠ No                       |
| Within a 100-year floodplain.  | ☐ Yes ⊠ No                       |

| Temporary Pits, Emergency Pits, and Below-grade Tanks Permit Application Attachment Checklist: Subsection B of 19.15.17.9 NMAC  Instructions: Each of the following items must be attached to the application. Please indicate, by a check mark in the box, that the documents are attached.  Hydrogeologic Report (Below-grade Tanks) - based upon the requirements of Paragraph (4) of Subsection B of 19.15.17.9 NMAC  Hydrogeologic Data (Temporary and Emergency Pits) - based upon the requirements of Paragraph (2) of Subsection B of 19.15.17.9 NMAC  Siting Criteria Compliance Demonstrations - based upon the appropriate requirements of 19.15.17.10 NMAC  Design Plan - based upon the appropriate requirements of 19.15.17.12 NMAC  Closure Plan (Please complete Boxes 14 through 18, if applicable) - based upon the appropriate requirements of Subsection C of 19.15.17.9 NMAC and 19.15.17.13 NMAC  Previously Approved Design (attach copy of design) API Number:  or Permit Number:  |  |  |  |
|--|--|--|--|
| 12.  |  |  |  |
| Closed-loop Systems Permit Application Attachment Checklist: Subsection B of 19.15.17.9 NMAC  Instructions: Each of the following items must be attached to the application. Please indicate, by a check mark in the box, that the documents are attached.  Geologic and Hydrogeologic Data (only for on-site closure) - based upon the requirements of Paragraph (3) of Subsection B of 19.15.17.9  Siting Criteria Compliance Demonstrations (only for on-site closure) - based upon the appropriate requirements of 19.15.17.10 NMAC  Design Plan - based upon the appropriate requirements of 19.15.17.11 NMAC  Operating and Maintenance Plan - based upon the appropriate requirements of 19.15.17.12 NMAC  Closure Plan (Please complete Boxes 14 through 18, if applicable) - based upon the appropriate requirements of Subsection C of 19.15.17.9 NMAC and 19.15.17.13 NMAC  |  |  |  |
| Previously Approved Design (attach copy of design)  API Number:  |  |  |  |
| ☐ Previously Approved Operating and Maintenance Plan API Number: (Applies only to closed-loop system that use  |  |  |  |
| above ground steel tanks or haul-off bins and propose to implement waste removal for closure)  |  |  |  |
| Permanent Pits Permit Application Checklist: Subsection B of 19.15.17.9 NMAC  Instructions: Each of the following items must be attached to the application. Please indicate, by a check mark in the box, that the documents are attached.  Hydrogeologic Report - based upon the requirements of Paragraph (1) of Subsection B of 19.15.17.9 NMAC  Siting Criteria Compliance Demonstrations - based upon the appropriate requirements of 19.15.17.10 NMAC  Climatological Factors Assessment  Certified Engineering Design Plans - based upon the appropriate requirements of 19.15.17.11 NMAC  Dike Protection and Structural Integrity Design - based upon the appropriate requirements of 19.15.17.11 NMAC  Leak Detection Design - based upon the appropriate requirements of 19.15.17.11 NMAC  Liner Specifications and Compatibility Assessment - based upon the appropriate requirements of 19.15.17.11 NMAC  Quality Control/Quality Assurance Construction and Installation Plan  Operating and Maintenance Plan - based upon the appropriate requirements of 19.15.17.12 NMAC  Freeboard and Overtopping Prevention Plan - based upon the appropriate requirements of 19.15.17.11 NMAC  Nuisance or Hazardous Odors, including H <sub>2</sub> S, Prevention Plan  Emergency Response Plan  Oil Field Waste Stream Characterization  Monitoring and Inspection Plan  Erosion Control Plan  Closure Plan - based upon the appropriate requirements of Subsection C of 19.15.17.9 NMAC and 19.15.17.13 NMAC |  |  |  |
| <u>Proposed Closure</u> : 19.15.17.13 NMAC  Instructions: Please complete the applicable boxes, Boxes 14 through 18, in regards to the proposed closure plan.  |  |  |  |
| Type: Drilling Workover Emergency Cavitation P&A Permanent Pit Below-grade Tank Closed-loop System Alternative   |  |  |  |
| Proposed Closure Method: Waste Excavation and Removal  |  |  |  |
| <ul> <li>☐ Waste Removal (Closed-loop systems only)</li> <li>☐ On-site Closure Method (Only for temporary pits and closed-loop systems)</li> </ul>   |  |  |  |
| ☐ In-place Burial ☐ On-site Trench Burial  |  |  |  |
| Alternative Closure Method (Exceptions must be submitted to the Santa Fe Environmental Bureau for consideration)  15.  |  |  |  |
| Waste Excavation and Removal Closure Plan Checklist: (19.15.17.13 NMAC) Instructions: Each of the following items must be attached to the closure plan. Please indicate, by a check mark in the box, that the documents are attached.  Protocols and Procedures - based upon the appropriate requirements of 19.15.17.13 NMAC  Confirmation Sampling Plan (if applicable) - based upon the appropriate requirements of Subsection F of 19.15.17.13 NMAC  Disposal Facility Name and Permit Number (for liquids, drilling fluids and drill cuttings)  Soil Backfill and Cover Design Specifications - based upon the appropriate requirements of Subsection H of 19.15.17.13 NMAC  Re-vegetation Plan - based upon the appropriate requirements of Subsection G of 19.15.17.13 NMAC   |  |  |  |

| Waste Removal Closure For Closed-loop Systems That Utilize Above Groun Instructions: Please indentify the facility or facilities for the disposal of liquid   | d Steel Tanks or Haul-off Bins Only: (19.15.17.13.I<br>s, drilling fluids and drill cuttings. Use attachment if t | O NMAC)<br>more than two |
|---|---|--------------------------|
| facilities are required.  Disposal Facility Name:   | Disposal Facility Permit Number:  |                          |
| Disposal Facility Name:   | •   |                          |
| Will any of the proposed closed-loop system operations and associated activities occur on or in areas that will not be used for future service and operations?  Yes (If yes, please provide the information below) \( \sumsymbol{\substack} \) No   |   |                          |
| Required for impacted areas which will not be used for future service and operations:    Soil Backfill and Cover Design Specifications based upon the appropriate requirements of Subsection H of 19.15.17.13 NMAC   Re-vegetation Plan - based upon the appropriate requirements of Subsection I of 19.15.17.13 NMAC   Site Reclamation Plan - based upon the appropriate requirements of Subsection G of 19.15.17.13 NMAC   |   |                          |
| Siting Criteria (regarding on-site closure methods only): 19.15.17.10 NMAC Instructions: Each siting criteria requires a demonstration of compliance in the closure plan. Recommendations of acceptable source material are provided below. Requests regarding changes to certain siting criteria may require administrative approval from the appropriate district office or may be considered an exception which must be submitted to the Santa Fe Environmental Bureau office for consideration of approval. Justifications and/or demonstrations of equivalency are required. Please refer to 19.15.17.10 NMAC for guidance.  |   |                          |
| Ground water is less than 50 feet below the bottom of the buried waste.  - NM Office of the State Engineer - iWATERS database search; USGS; D   | ata obtained from nearby wells  | ☐ Yes ☑ No<br>☐ NA       |
| Ground water is between 50 and 100 feet below the bottom of the buried waste - NM Office of the State Engineer - iWATERS database search; USGS; D   | ata obtained from nearby wells  | ☐ Yes ☑ No<br>☐ NA       |
| Ground water is more than 100 feet below the bottom of the buried waste.  - NM Office of the State Engineer - iWATERS database search; USGS; D  | ata obtained from nearby wells  | Yes No                   |
| Within 300 feet of a continuously flowing watercourse, or 200 feet of any other s lake (measured from the ordinary high-water mark).  - Topographic map; Visual inspection (certification) of the proposed site   | significant watercourse or lakebed, sinkhole, or playa  | ☐ Yes ⊠ No               |
| Within 300 feet from a permanent residence, school, hospital, institution, or chur  - Visual inspection (certification) of the proposed site; Aerial photo; Satell  |   | ☐ Yes ⊠ No               |
| Within 500 horizontal feet of a private, domestic fresh water well or spring that l watering purposes, or within 1000 horizontal feet of any other fresh water well o  NM Office of the State Engineer - iWATERS database; Visual inspection  | r spring, in existence at the time of initial application.  | ☐ Yes ☒ No               |
| Within incorporated municipal boundaries or within a defined municipal fresh ward adopted pursuant to NMSA 1978, Section 3-27-3, as amended.  - Written confirmation or verification from the municipality; Written appropri  |   | ☐ Yes ⊠ No               |
| Within 500 feet of a wetland.  - US Fish and Wildlife Wetland Identification map; Topographic map; Vis  | sual inspection (certification) of the proposed site  | ☐ Yes ☑ No               |
| Within the area overlying a subsurface mine.  - Written confirmation or verification or map from the NM EMNRD-Mini  | ng and Mineral Division   | ☐ Yes ☒ No               |
| Within an unstable area.  - Engineering measures incorporated into the design; NM Bureau of Geold Society; Topographic map  | ogy & Mineral Resources; USGS; NM Geological  | ☐ Yes ☒ No               |
| Within a 100-year floodplain FEMA map   |   | ☐ Yes ⊠ No               |
| On-Site Closure Plan Checklist: (19.15.17.13 NMAC) Instructions: Each of the following items must be attached to the closure plan. Please indicate, by a check mark in the box, that the documents are attached.  Siting Criteria Compliance Demonstrations - based upon the appropriate requirements of 19.15.17.10 NMAC  Proof of Surface Owner Notice - based upon the appropriate requirements of Subsection F of 19.15.17.13 NMAC See 10. on APD Page 9 (Exhibit K)  Construction/Design Plan of Burial Trench (if applicable) based upon the appropriate requirements of 19.15.17.11 NMAC  Construction/Design Plan of Temporary Pit (for in-place burial of a drying pad) - based upon the appropriate requirements of 19.15.17.13 NMAC  Protocols and Procedures - based upon the appropriate requirements of 19.15.17.13 NMAC  Confirmation Sampling Plan (if applicable) - based upon the appropriate requirements of Subsection F of 19.15.17.13 NMAC  Waste Material Sampling Plan - based upon the appropriate requirements of Subsection F of 19.15.17.13 NMAC  Disposal Facility Name and Permit Number (for liquids, drilling fluids and drill cuttings or in case on-site closure standards cannot be achieved)  Soil Cover Design - based upon the appropriate requirements of Subsection H of 19.15.17.13 NMAC  Re-vegetation Plan - based upon the appropriate requirements of Subsection G of 19.15.17.13 NMAC |   |                          |

| Operator Application Certification:  I hereby certify that the information submitted with this application is true, accurate and complete to the best of my knowledge and belief.   |  |  |  |
|---|--|--|--|
| Name (Print): BRIAN WOOD Title: CONSULTANT  |  |  |  |
| Signature: Date: <u>8-15-09</u>   |  |  |  |
| e-mail address: brian@permitswest.com Telephone: (505) 466-8120   |  |  |  |
| 20.  OCD Approval: Permit Application (including closure plan) Closure Plan (only) CCD Conditions (see attachment)  |  |  |  |
| OCD Representative Signature: Bol Sell Approval Date: 9/1/09  |  |  |  |
| Title: OCD Permit Number:   |  |  |  |
| Closure Report (required within 60 days of closure completion): Subsection K of 19.15.17.13 NMAC  Instructions: Operators are required to obtain an approved closure plan prior to implementing any closure activities and submitting the closure report.  The closure report is required to be submitted to the division within 60 days of the completion of the closure activities. Please do not complete this section of the form until an approved closure plan has been obtained and the closure activities have been completed.  Closure Completion Date:  |  |  |  |
|   |  |  |  |
| Closure Method:  Waste Excavation and Removal On-Site Closure Method Alternative Closure Method Waste Removal (Closed-loop systems only)  If different from approved plan, please explain.  |  |  |  |
| 23.  Closure Report Regarding Waste Removal Closure For Closed-loop Systems That Utilize Above Ground Steel Tanks or Haul-off Bins Only:  Instructions: Please indentify the facility or facilities for where the liquids, drilling fluids and drill cuttings were disposed. Use attachment if more than two facilities were utilized.  |  |  |  |
| Disposal Facility Name: Disposal Facility Permit Number:  |  |  |  |
| Disposal Facility Name: Disposal Facility Permit Number:  |  |  |  |
| Were the closed-loop system operations and associated activities performed on or in areas that will not be used for future service and operations?  Yes (If yes, please demonstrate compliance to the items below) \( \subseteq \text{No} \)  |  |  |  |
| Required for impacted areas which will not be used for future service and operations.  Site Reclamation (Photo Documentation)  Soil Backfilling and Cover Installation  Re-vegetation Application Rates and Seeding Technique   |  |  |  |
| Closure Report Attachment Checklist: Instructions: Each of the following items must be attached to the closure report. Please indicate, by a check mark in the box, that the documents are attached.  Proof of Closure Notice (surface owner and division)  Proof of Deed Notice (required for on-site closure)  Plot Plan (for on-site closures and temporary pits)  Confirmation Sampling Analytical Results (if applicable)  Waste Material Sampling Analytical Results (required for on-site closure)  Disposal Facility Name and Permit Number  Soil Backfilling and Cover Installation  Re-vegetation Application Rates and Seeding Technique  Site Reclamation (Photo Documentation)  On-site Closure Location: Latitude |  |  |  |
| 25.   |  |  |  |
| Operator Closure Certification:  I hereby certify that the information and attachments submitted with this closure report is true, accurate and complete to the best of my knowledge and belief. I also certify that the closure complies with all applicable closure requirements and conditions specified in the approved closure plan.   |  |  |  |
| Name (Print): Title:  |  |  |  |
| Signature Date:   |  |  |  |

Telephone: \_

e-mail address:

### Siting Criteria

1. Ground water is  $\geq 100$ ' below the bottom of the pit. This estimate is based on the closest water well (Exhibit A), which is a windmill >10,000' southwest. Depth to water is unknown (State Engineer has no records of any water well in a >2 mile radius (Exhibit B)). However, the windmill ground elevation is 241' lower than the pit bottom elevation.

7,187' graded ground

- 10' deep pit

7,177' bottom of pit

- 6,906' windmill ground elevation

271' minimum distance from bottom of pit to ground water

- 2. Pit is not within 300' of a continuously flowing watercourse. Pit is not within 200' of any other significant watercourse as defined by OCD. Closest first order tributary of Cañon Largo is miles to the southwest (Exhibit C).
- 3. Pit is not within 300' of any building. Closest buildings are a line camp cabin and outhouse  $\approx 900$ ' south (Exhibits A & D).
- 4. Pit is not within 1,000' of any fresh water well or spring (Exhibits A & B).
- 5. Pit is not within municipal boundaries or within a municipal fresh water well field (Exhibits A & B).
- 6. Pit is not within 500' of a wetland (Exhibit E).
- 7. Pit does not overly a mine (Exhibit F).
- 8. Pit is not in an unstable area. No evidence of earth movement was found during a September 28, 2008 inspection. Maximum grade is  $\approx$ 9% (Exhibit G).
- 9. FEMA has not mapped flood plains in the project area (Exhibit H). Pit does not appear to be in a 100 year flood plain for 3 reasons:



- it is on a ridge
- no evidence of inundation was found during a site inspection
- piñon juniper trees are not indicative of saturated soils
- 10. C-102 is attached as Exhibit I.
- 11. Closure notice to the surface owner (Jicarilla Apache Nation) is attached as Exhibit J.

## **Hydrogeology**

Surface formation is the San Jose, a mix of sandstones and mudstones. San Jose mudstone is exposed as badlands a mile northwest in Johnson Canyon. According to Stone et al in <u>Hydrogeology and water resources of San Juan Basin, New Mexico</u>, San Jose aquifers are "largely untested", but there are "numerous wells and springs". Transmissivities of 40 and 120 feet<sup>2</sup> per day have been measured. Specific conductance has ranged from 320 to 5,000  $\mu$ mhos. The Ojo Alamo sandstone is  $\approx 2,437$ ' below the surface.

# Alternative for 19.15.17.11 D. (3)

Elm Ridge is proposing an alternate fence. Sheep graze in the project area and hog wire has been found to be more effective than just barbed wire. The operator will fence the pit with a minimum 48" high fence. Fence will consist of minimum 36" woven wire (hog wire) topped with at least 1 strand of barbed wire.

# Alternative for 19.15.17.11 F. (2)

Elm Ridge is proposing alternate (vertical) slopes for the 160' long sides of the pit. Alternate is requested to minimize well site footprint. This allows a smaller rig to be used. Rig must be close to the deep part of the pit since the pump is on the rig itself. Elm Ridge will install extra liner to allow for some slack and avoid stress and strain. Elm Ridge will also install two rope ladders - one on each of the 160' long sides.



## Alternative for 19.15.17.13 F. (1) (d)

If the well goes into production, then an alternate interim marking system will be used to allow for safer and more efficient operations. A minimum 4"  $\circ$ 0. D. steel pipe will be set at least 36" deep at the center of the pit. A threaded collar will be on the top of the pipe. A minimum 12" x 12" steel plate will welded atop the threaded collar. Top of the plate will be flush with ground level. The standard location information listed will be welded onto the plate, plus a notation that it marks an on site buried temporary pit. Upon plugging the well, the plate will be removed and the pit marked as described in 19.15.17.13 F. (1) (d).

Executed this <u>15th</u> day of <u>August</u>, <u>2009</u>.

Brian Wood, Consultant

Permits West, Inc.

37 Verano Loop, Santa Fe, NM 87508

(505) 466-8120

FAX: (505) 466-9682

Cellular: (505) 699-2276

The operator's field representative is:

Terry Lindeman Elm Ridge Exploration Company, LLC P. O. Box 156 Bloomfield, NM 87413 (505) 632-3476

## NMOCD Rules

#### 19.15.17.11 DESIGN AND CONSTRUCTION SPECIFICATIONS:

- A. General specifications. An operator shall design and construct a pit, <del>closed-loop system, below-grade tank-or sump</del> to contain liquids and solids and prevent contamination of fresh water and protect public health and the environment.
  - B. Stockpiling of topsoil. Prior to constructing a pit or closed-looped system, except a pit



constructed in an emergency, the operator shall strip and stockpile the topsoil for use as the final cover or fill at the time of closure.

C. Signs. The operator shall post an upright sign not less than 12 inches by 24 inches with lettering not less than two inches in height in a conspicuous place on the fence surrounding the pit, closed-loop system or below-grade tank, unless the pit, closed-loop system or below-grade tank is located on a site where there is an existing well, signed in compliance with 19.15.3.103 NMAC, that is operated by the same operator. The operator shall post the sign in a manner and location such that a person can easily read the legend. The sign shall provide the following information: the operator's name; the location of the site by quarter-quarter or unit letter, section, township and range; and emergency telephone numbers.

#### D. Fencing.

- (1) The operator shall fence or enclose a pit or below-grade tank in a manner that prevents unauthorized access and shall maintain the fences in good repair. Fences are not required if there is an adequate surrounding perimeter fence that prevents unauthorized access to the well site or facility, including the pit or below-grade tank. During drilling or work over operations, the operator is not required to fence the edge of the pit adjacent to the drilling or work over rig.
- (2)—The operator shall fence or enclose a pit or below grade tank located within 1000 feet of a permanent residence, school, hospital, institution or church with a chain link security fence, at least six feet in height with at least two strands of barbed wire at the top. The operator shall ensure that all gates associated with the fence are closed and locked when responsible personnel are not on-site. During drilling or work over operations, the operator is not required to fence the edge of the temporary pit adjacent to the drilling or work over rig.
- (3) The operator shall fence any other pit or below-grade tank to exclude livestock with a four foot fence that has at least four strands of barbed wire evenly spaced in the interval between one foot and four feet above ground level. The appropriate division district office may approve an alternative to this requirement if the operator demonstrates that an alternative provides equivalent or better protection. The appropriate division district office may impose additional fencing requirements for protection of wildlife in particular areas.

The operator will fence the pit with a minimum 48" high fence. Fence will consist of minimum 36" woven wire (hog wire) topped with at least 1 strand of barbed wire.

E. Netting. The operator shall ensure that a permanent pit or a permanent open top tank is screened, netted or otherwise rendered non-hazardous to wildlife, including migratory birds. Where netting or screening is not feasible, the operator shall on a monthly basis inspect for, and within 30 days of discovery, report discovery of dead migratory birds or other wildlife to the appropriate wildlife agency and to the appropriate division district office in order to facilitate assessment and implementation of measures to



#### prevent-incidents-from reoccurring.

- **F.** Temporary pits. The operator shall design and construct a temporary pit in accordance with the following requirements.
- (1) The operator shall design and construct a temporary pit to ensure the confinement of liquids to prevent unauthorized releases.
- (2) A temporary pit shall have a properly constructed foundation and interior slopes consisting of a firm, unyielding base, smooth and free of rocks, debris, sharp edges or irregularities to prevent the liner's rupture or tear. The operator shall construct a temporary pit so that the slopes are no steeper than two horizontal feet to one vertical foot (2H:1V). The short (40' wide) side slopes will be no steeper than two horizontal feet to one vertical foot (2H:1V). The long (160' wide) side slopes will be vertical. The appropriate division district office may approve an alternative to the slope requirement if the operator demonstrates that it can construct and operate the temporary pit in a safe manner to prevent contamination of fresh water and protect public health and the environment.
- (3) The operator shall design and construct a temporary pit with a geomembrane liner. The geomembrane liner shall consist of 20-mil string reinforced LLDPE or equivalent liner material that the appropriate division district office approves. The geomembrane liner shall be composed of an impervious, synthetic material that is resistant to petroleum hydrocarbons, salts and acidic and alkaline solutions. The liner material shall be resistant to ultraviolet light. Liner compatibility shall comply with EPA SW-846 method 9090A.
- (4) The operator shall minimize liner seams and orient them up and down, not across a slope. The operator shall use factory welded seams where possible. Prior to field seaming, the operator shall overlap liners four to six inches and orient seams parallel to the line of maximum slope, *i.e.*, oriented along, not across, the slope. The operator shall minimize the number of field seams in corners and irregularly shaped areas. Qualified personnel shall perform field seaming. The operator shall weld field liner seams.
  - (5) Construction shall avoid excessive stress-strain on the liner.
- (6) Geotextile is required under the liner where needed to reduce localized stress-strain or protuberances that may otherwise compromise the liner's integrity.
- (7) The operator shall anchor the edges of all liners in the bottom of a compacted earth-filled trench. The anchor trench shall be at least 18 inches deep.
- (8) The operator shall ensure that the liner is protected from any fluid force or mechanical damage at any point of discharge into or suction from the lined temporary pit by using an



≈8" O. D. PVC pipe at a ≈45° angle.

- (9) The operator shall design and construct a temporary pit to prevent run-on of surface water. A berm, ditch, proper sloping or other diversion shall surround a temporary pit to prevent run-on of surface water. During drilling operations, the edge of the temporary pit adjacent to the drilling or work over rig is not required to have run-on protection if the operator is using the temporary pit to collect liquids escaping from the drilling or work over rig and run-on will not result in a breach of the temporary pit.
- (10) The volume of a temporary pit shall not exceed 10 acre-feet, including freeboard.
- (11) The part of a temporary pit used to vent or flare gas during a drilling or work over operation that is designed to allow liquids to drain to a separate temporary pit does not require a liner, unless the appropriate division district office requires an alternative design in order to protect surface water, ground water and the environment. The operator shall not allow freestanding liquids to remain on the unlined portion of a temporary pit used to vent or flare gas.

#### 19.15.17.12 OPERATIONAL REQUIREMENTS:

- A. General specifications. An operator shall maintain and operate a pit, <del>closed-loop-system, below-grade tank or sump</del> in accordance with the following requirements.
- (1) The operator shall operate and maintain a pit, closed-loop system, below-grade-tank or sump to contain liquids and solids and maintain the integrity of the liner, liner system or secondary containment system, prevent contamination of fresh water and protect public health and the environment.
- (2) The operator shall recycle, reuse or reclaim or dispose of all drilling fluids in a manner, approved by division rules, that prevents the contamination of fresh water and protects public health and the environment. *Operator will haul such fluids to the Basin Disposal (NM-01-005)* evaporation pond (F 3-29n-11w).
- (3) The operator shall not discharge into or store any hazardous waste in a pit, closed-loop system, below-grade tank or sump.
- (4) If any pit liner's integrity is compromised, or if any penetration of the liner occurs above the liquid's surface, then the operator shall notify the appropriate division district office within 48 hours of the discovery and repair the damage or replace the liner.



- (5) If a pit, below-grade tank, closed-loop system or sump develops a leak, or if any penetration of the pit liner, below-grade tank, closed-loop system or sump occurs below the liquid's surface, then the operator shall remove all liquid above the damage or leak line within 48 hours, notify the appropriate division district office within 48 hours of the discovery and repair the damage or replace the pit liner, below-grade tank, closed-loop system or sump.
- (6) The injection or withdrawal of liquids from a pit shall be accomplished through a header, diverter or other hardware that prevents damage to the liner by erosion, fluid jets or impact from installation and removal of hoses or pipes.
- (7) The operator shall operate and install a pit, below-grade tank or sump to prevent the collection of surface water run-on.
- (8) The operator shall install, or maintain on site, an oil absorbent boom or other device to contain and remove oil from a pit's surface.
- **B.** Temporary pits. An operator shall maintain and operate a temporary pit in accordance with the following additional requirements.
- (1) Only fluids used or generated during the drilling or work over process may be discharged into a temporary pit. The operator shall maintain a temporary pit free of miscellaneous solid waste or debris. The operator shall use a tank made of steel or other material, which the appropriate division district office approves, to contain hydrocarbon-based drilling fluids. Immediately after cessation of a drilling or work over operation, the operator shall remove any visible or measurable layer of oil from the surface of a drilling or work over pit.
  - (2) The operator shall maintain at least 2 feet of freeboard for a temporary pit.
- (3) The operator shall inspect a temporary pit containing drilling fluids at least daily while the drilling or work over rig is on-site. Thereafter, the operator shall inspect the temporary pit weekly so long as liquids remain in the temporary pit. The operator shall maintain a log of such inspections and make the log available for the appropriate division district office's review upon request. The operator shall file a copy of the log with the appropriate division district office when the operator closes the temporary pit.
- (4) The operator shall remove all free liquids from a temporary pit within 30 days from the date that the operator releases the drilling or work over rig. The operator shall note the date of the drilling or work over rig's release on form C-105 or C-103 upon well or work over completion. The appropriate division district office may grant an extension of up to three months.



(5) The operator shall remove any liquids from the temporary pit used for cavitation within 48 hours after completing cavitation. The operator may request and receive additional time to remove the liquids from the temporary pit used for cavitation if the operator demonstrates to the appropriate division district office's satisfaction that it is not feasible to access the location with 48 hours.

#### 19.15.17.13 CLOSURE REQUIREMENTS:

- A. Time requirements for closure. An operator shall close a pit, closed-loop system orbelow-grade tank within the time periods provided in 19.15.17.13 NMAC, or by an earlier date that the division requires because of imminent danger to fresh water, public health or the environment.
- (1) An-operator shall cease discharging into an existing unlined permanent pit that is permitted by or registered with the division within two years after June 16, 2008. An operator shall close an existing unlined permanent pit that is permitted by or registered with the division within three years after June 16, 2008.
- (2) An operator-shall cease discharging into an existing, lined or unlined, permanent pit that is not permitted by or registered with the division on or by June 16, 2008. An operator shall close an existing, lined or unlined, permanent pit that is not permitted by or registered with the division within six months after June 16, 2008.
- (3) -- An operator shall close an existing unlined temporary pit within three months after-June 16, 2008.
- (4) An operator shall close an existing below grade tank that does not meet the requirements of Paragraphs (1) through (4) of Subsection I of 19.15.17.11 NMAC or is not included in Paragraph (5) of Subsection I of 19.15.17.11 NMAC within five years after June 16, 2008, if not retrofitted to comply with Paragraphs (1) through (4) of Subsection I of 19.15.17.11 NMAC.
- (5) An operator shall close an existing below-grade-tank that does not meet the requirements-of-Paragraphs—(1) through (4) of Subsection I of 19.15.17.11 NMAC, if not retrofitted to comply with-Paragraphs—(1) through (4) of Subsection I of 19.15.17.11 NMAC, prior to any sale or change of operator-pursuant to 19.15.9.9 NMAC.
- (6) An operator shall close any other permitted permanent pit within 60-days of cessation of operation of the permanent pit in accordance with a closure plan that the environmental bureau in the division's Santa Fe office approves.
- (7) An operator shall close any other permitted temporary pit within six months from the date that the operator releases the drilling or work over rig. The appropriate division district office may grant an extension not to exceed three months.
- B. Closure methods for temporary pits. The operator of a temporary pit shall remove all liquids from the temporary pit prior to closure and dispose of the liquids in a division-approved facility or recycle, reuse or reclaim the liquids in a manner that the appropriate division district office approves. The operator shall close the temporary pit by one of the following



methods.

#### (1) Waste excavation and removal.

- (2) On-site burial. The operator shall demonstrate and comply with the siting requirements in Subsection C of 19.15.17.10 NMAC and the closure requirements and standards of Subsection F of 19.15.17.13 NMAC if the proposed closure method of a temporary pit involves on-site burial.
- F. On-site closure methods. The following closure requirements and standards apply if the operator proposes a closure method for a drying pad associated with a closed-loop system or a temporary pit pursuant to Paragraph (2) of Subsection D of 19.15.17.13 NMAC or Paragraph (2) of Subsection B of 19.15.17.13 NMAC that involves on-site burial, or an alternative closure method pursuant to Paragraph (3) of Subsection D of 19.15.17.13 NMAC or Paragraph (3) of Subsection B of 19.15.17.13 NMAC and Subsection B of 19.15.17.15 NMAC.
  - (1) General requirements.
- (a) Any proposed on-site closure method shall comply with the siting criteria specified in Subsection C of 19.15.17.10 NMAC.
- (b) The operator shall provide the surface owner notice of the operator's proposal of an on-site closure method. The operator shall attach the proof of notice to the permit application.
- (c) The operator shall comply with the closure requirements and standards of Paragraphs (2) and (3), as applicable, of Subsection F of 19.15.17.13 NMAC if the proposed closure method for a drying pad associated with a closed-loop system or for a temporary pit involves on-site burial pursuant to Paragraph (2) of Subsection D of 19.15.17.13 NMAC or Paragraph (2) of Subsection B of 19.15.17.13 NMAC, or involves an alternative closure method pursuant to Paragraph (3) of Subsection D of 19.15.17.13 NMAC or Paragraph (3) of Subsection B of 19.15.17.13 NMAC and Subsection B of 19.15.17.15 NMAC.
- (d) The operator shall place a steel marker at the center of an on-site burial. The steel marker shall be not less than four inches in diameter and shall be cemented in a three-foot deep hole at a minimum. The steel marker shall extend at least four feet above mean ground level and at least three feet below ground level. The operator name, lease name and well number and location, including unit letter, section, township and range, and that the marker designates an on-site burial location shall be welded, stamped or otherwise permanently engraved into the metal of the steel marker. A person shall not build permanent structures over an on-site burial without the appropriate



division district office's written approval. A person shall not remove an on-site burial marker without the division's written permission.

If the well goes into production, then an alternate interim marking system will be used to allow for safer and more efficient operations. A minimum 4" O. D. steel pipe will be set at least 36" deep at the center of the pit. A threaded collar will be on the top of the pipe. A minimum 12" x 12" steel plate will welded atop the threaded collar. Top of the plate will be flush with ground level. The same information listed in the preceding paragraph will be welded onto the plate, plus a notation that it marks an on site buried temporary pit. Upon plugging the well, the plate will be removed and the pit marked as described in the preceding paragraph.

- (e) The operator shall report the exact location of the on-site burial on form C-105 filed with the division.
- (f) The operator shall file a deed notice identifying the exact location of the on-site burial with the county clerk in the county where the on-site burial occurs.
  - (2) In-place burial.
- (a) Where the operator meets the siting criteria specified in Paragraphs (2) or (3) of Subsection C of 19.15.17.10 NMAC and the applicable waste criteria specified in Subparagraphs (c) or (d) of Paragraph (2) of Subsection F of 19.15.17.13 NMAC, an operator may use in-place burial (burial in the existing temporary pit) for closure of a temporary pit or bury the contents of a drying pad associated with a closed-loop system in a temporary pit that the operator constructs in accordance with Paragraphs (1) through (6) and (10) of Subsection F of 19.15.17.11 NMAC for closure of a drying pad associated with a closed loop system.
- (b) Prior to closing an existing temporary pit or to placing the contents from a drying pad associated with a closed-loop system into a temporary pit that the operator constructs for disposal, the operator shall stabilize or solidify the contents to a bearing capacity sufficient to support the temporary pit's final cover. The operator shall not mix the contents with soil or other material at a mixing ratio of greater than 3:1, soil or other material to contents.
- (c) Where ground water will be between 50 and 100 feet below the bottom of the buried waste, the operator shall collect at a minimum, a five point, composite sample of the contents of the drying pad associated with a closed loop system or the contents of a temporary pit after treatment or stabilization, if treatment or stabilization is required, to demonstrate that benzene, as determined by EPA SW-846 method 8021 B or 8260B, does not exceed 0.2 mg/kg; total BTEX, as determined by EPA SW-846 method 8021 B or 8260B, does not exceed 50 mg/kg; TPH, as determined by EPA SW-846 method 418.1 or other EPA method approved that the division approves, does not exceed 2500 mg/kg; the GRO and DRO combined fraction, as determined by EPA SW-846 method 8015M, does not exceed 500 mg/kg; and chlorides, as determined by



EPA method 300.1, do not exceed 500 mg/kg or the background concentration, whichever is greater. The operator may collect the composite sample prior to treatment or stabilization to demonstrate that the contents do not exceed these concentrations. However, if the contents collected prior to treatment or stabilization exceed the specified concentrations the operator shall collect a second five point, composite sample of the contents after treatment or stabilization to demonstrate that the contents do not exceed these concentrations.

- (d) Where the ground water will be more than 100 feet below the bottom of the buried waste, the operator shall collect at a minimum, a five point, composite sample of the contents of the drying pad associated with a closed-loop system or the contents of a temporary pit after treatment or stabilization, if treatment or stabilization is required, to demonstrate that benzene, as determined by EPA SW-846 method 8021B or 8260B, does not exceed 0.2 mg/kg; total BTEX, as determined by EPA SW-846 method 8021B or 8260B, does not exceed 50 mg/kg; the GRO and DRO combined fraction, as determined by EPA SW-846 method 8015M, does not exceed 500 mg/kg; TPH, as determined by EPA method 418.1 or other EPA method that the division approves, does not exceed 2500 mg/kg; and chlorides, as determined by EPA method 300.1, do not exceed 1000 mg/kg or the background concentration, whichever is greater. The operator may collect the composite sample prior to treatment or stabilization to demonstrate that the contents do not exceed these concentrations. However, if the contents collected prior to treatment or stabilization exceed the specified concentrations the operator shall collect a second five point, composite sample of the contents after treatment or stabilization to demonstrate that the contents do not exceed these concentrations.
- (e) Upon closure of a temporary pit, or closure of a temporary pit that the operator constructs for burial of the contents of a drying pad associated with a closed-loop system, the operator shall cover the geomembrane lined, filled, temporary pit with compacted, non-waste containing, earthen material; construct a division-prescribed soil cover; recontour and revegetate the site. The division-prescribed soil cover, recontouring and revegetation shall comply with Subsections G, H and I of 19.15.17.13 NMAC.
  - G. Reclamation of pit locations, on-site burial locations and drying pad locations.
- (1) Once the operator has closed a pit or trench or is no longer using a drying pad, below-grade tank or an area associated with a closed-loop system, pit, trench or below-grade tank, the operator shall reclaim the pit location, drying pad location, below-grade tank location or trench location and all areas associated with the closed-loop system, pit, trench or below-grade tank including associated access roads to a safe and stable condition that blends with the surrounding undisturbed area. The operator shall substantially restore the impacted surface area to the condition that existed prior to oil and gas operations by placement of the soil cover as provided in Subsection H of 19.15.17.13



NMAC, recontour the location and associated areas to a contour that approximates the original contour and blends with the surrounding topography and revegetate according to Subsection I of 19.15.17.13 NMAC.

(2) The operator may propose an alternative to the revegetation requirement if the operator demonstrates that the proposed alternative effectively prevents erosion, and protects fresh water, human health and the environment. The proposed alternative shall be agreed upon by the surface owner. The operator shall submit the proposed alternative, with written documentation that the surface owner agrees to the alternative, to the division for approval.

#### H. Soil cover designs.

- (1) The soil cover for closures where the operator has removed the pit contents or remediated the contaminated soil to the division's satisfaction shall consist of the background thickness of topsoil or one foot of suitable material to establish vegetation at the site, whichever is greater.
- (2) The soil cover for burial-in-place or trench burial shall consist of a minimum of four feet of compacted, non-waste containing, earthen material. The soil cover shall include either the background thickness of topsoil or one foot of suitable material to establish vegetation at the site, whichever is greater.
- (3) The operator shall construct the soil cover to the site's existing grade and prevent ponding of water and erosion of the cover material.

#### I. Re-vegetation.

- (1) The first growing season after the operator closes a pit or trench or is no longer using a drying pad, below-grade tank or an area associated with a closed-loop system, pit or below-grade tank including access roads, the operator shall seed or plant the disturbed areas.
- (2) The operator shall accomplish seeding by drilling on the contour whenever practical or by other division-approved methods. The operator shall obtain vegetative cover that equals 70% of the native perennial vegetative cover (un-impacted by overgrazing, fire or other intrusion damaging to native vegetation) consisting of at least three native plant species, including at least one grass, but not including noxious weeds, and maintain that cover through two successive growing seasons. During the two growing seasons that prove viability, there shall be no artificial irrigation of the vegetation.
- (3) The operator shall repeat seeding or planting until it successfully achieves the required vegetative cover.




- (4) When conditions are not favorable for the establishment of vegetation, such as periods of drought, the division may allow the operator to delay seeding or planting until soil moisture conditions become favorable or may require the operator to use additional cultural techniques such as mulching, fertilizing, irrigating, fencing or other practices.
- (5) The operator shall notify the division when it has seeded or planted and when it successfully achieves re-vegetation.

#### J. Closure notice.

- (1) The operator shall notify the surface owner by certified mail, return receipt requested, that the operator plans to close a temporary pit, a permanent pit, a below-grade tank or where the operator has approval for on-site closure. Evidence of mailing of the notice to the address of the surface owner shown in the county tax records is sufficient to demonstrate compliance with this requirement.
- (2) The operator of a temporary pit or below-grade tank or an operator who is approved for on-site closure shall notify the appropriate division district office verbally or by other means at least 72 hours, but not more than one week, prior to any closure operation. The notice shall include the operator's name and the location to be closed by unit letter, section, township and range. If the closure is associated with a particular well, then the notice shall also include the well's name, number and API number.
- K. Closure report. Within 60 days of closure completion, the operator shall submit a closure report on form C-144, with necessary attachments to document all closure activities including sampling results; information required by 19.15.17 NMAC; a plot plan; and details on back-filling, capping and covering, where applicable. In the closure report, the operator shall certify that all information in the report and attachments is correct and that the operator has complied with all applicable closure requirements and conditions specified in the approved closure plan. If the operator used a temporary pit, the operator shall provide a plat of the pit location on form C-105 within 60 days of closing the temporary pit.

The operator shall file a deed notice identifying the exact location of the on-site burial with the county clerk in the county where the on-site burial occurs.







## New Mexico Office of the State Engineer

# Point of Diversion by Location (with Drilling Information)

No PODs found.

PLSS Search:

Township: 24N

Range: 04W

The data is furnished by the NMOSE/ISC and is accepted by the recipient with the expressed understanding that the OSE/ISC make no warranties, expressed or implied, concerning the accuracy, completeness, reliability, usability, or suitability for any particular purpose of the data

7/4/09 10:33 AM

Page 1 of 1



# New Mexico Office of the State Engineer

Point of Diversion by Location (with Drilling Information)


No PODs found

PLSS Search:

Township: 23N

Range: 04W

EXHIBITB




Jicarilla Apache J 5

Image courtesy of the U.S. Geological Survey


© 2004 Microsoft Corporation. **Terr** 

Terms of Use Privacy Statement






# MMQonline Public Version



EXHIBITE





| A-A'       |  | ·                                     | ·····        |
|------------|--|---------------------------------------|--------------|
| 7210       |  |                                       | •            |
| 7200 ··    | · · · · · ·   · · · · ·  |                                       | •            |
| 7190 -     |  |                                       | <u>.</u>     |
| 7180       | 1 · · · · · · · A  | 3:                                    | •            |
| 7170       |  |                                       | •            |
| 3B'        |  | ଜୂ                                    |              |
| 7210       |  |                                       | -            |
| 7200       |  |                                       | · .          |
| 7190       |  | · · · · · · · · · · · · · · · · · · · | -            |
| 7180       | تعنيف أن المالية   |                                       | • ]          |
| 7170       |  |                                       | · ]          |
| G-C'       |  | ę.                                    | · ·          |
| 7210       |  |                                       | <u>.  </u>   |
| 7200       |  |                                       | <u>•</u>   . |
| 7190       |  | .,                                    | <u>·</u>     |
| 7180       | · · · · · · · · / \. · · / \. · · / \. · · / \. · · · / \.         | 44. 1                                 | <u>.</u> .   |
| 7170 ·     | · · · · · · · <del>/   6 · · · · · · · · · · · · · · · · · ·</del> |                                       | ٠            |
|            |  |                                       | KHIBI        |
| LLA APACHE | = ,1 #5  |                                       | ת מס זכ      |

LEASE: JICARILLA APACHE J #5

FOOTAGE: 1950' FSL, 1950' FEL

SEC<u>, 4 TWN, 23 N RNG, 4 W N.M.</u>P.M.

LATITUDE: 36°15'03.6" LONGITUDE: 107°15'34.4"

ELEVATION: 7187

# ELM RIDGE EXPLORATION DALLAS, TEXAS

| -   |           |         |                     |                    |
|-----|-----------|---------|---------------------|--------------------|
| į   | SURVEYED: | 6/28/05 | REV. DATE: 8/15/05  | APP. BY R.P.       |
| •   | DRAWN BY: | A.D.    | DATE DRAWN: 6/30/05 | FILE NAME: 5931CO1 |
| - 1 |           | -757E-  |                     |                    |



P.O. BOX 3651 FARMINGTON, NM 87499 OFFICE: (505) 334-0408



# Map Service Center

Product Catalog | Map Search | Quick Order | Digital Post Office | Help

Log on

Home > Map Search Results

#### Map Search Results

Non-printed Panel(s)

| item ID Community ID Community Name |        |                 |
|-------------------------------------|--------|-----------------|
| 3500490010B                         | 350049 | RIO ARRIBA CO * |

FEMA.gov | Accessibility | Privacy Policy | FAQ | Site Help | Site Index | Contact Us

FEMA Map Service Center, P.O. Box 1038 Jessup, Maryland 20794-1038 Phone: (800) 358-9616 Adobe Acrobat Reader required to view certain documents. Click here to download.

EXHIBITH

DISTRICT I P.O. Box 1980, Hobbs, N.M. 86241-1980 DISTRICT II 811 South First, Artesia, N.M. 88210

1000 Rio Brazos Rd., Aztec, N.M. 87410

DISTRICT III

DISTRICT IV

<sup>18</sup> Dedicated Acres

160

13 Joint or Infill

16 Consolidation Code

State of New Mexico Energy, Minerals & Natural Resources Department

OIL CONSERVATION DIVISION
P.O. Box 2088
Santa Fe, NM 87504-2088


Revised Febuary 21, 1994
Instructions on back
Submit to Appropriate District Office
State Lease - 4 Copies
Fee Lease - 3 Copies
The Lea

2040 South Pacheco, Santa Fe, NM 87504—2088

15 Order No.

WELL LOCATION AND ACREAGE DEDICATION PLAT BLM PICTURED CLIFFS API Number BALLARD 30-039-71439 Well Number Property Code Property Name 19031 JICARILLA APACHE J 5 OGRID No. Operator Name Elevation 149052 7187 ELM RIDGE EXPLORATION <sup>10</sup> Surface Location North/South line UL or lot no. Feet from the County Section Township Range Lot Idn Feet from the East/West line 23 N 4 W 1950 1950 **EAST** RIO ARRIBA 4 SOUTH <sup>11</sup> Bottom Hole Location If Different From Surface UL or lot no. Section Lot Idn Feet from the North/South line Feet from the Township Range East/West line County

NO ALLOWABLE WILL BE ASSIGNED TO THIS COMPLETION UNTIL ALL INTERESTS HAVE BEEN CONSOLIDATED OR A NON-STANDARD UNIT HAS BEEN APPROVED BY THE DIVISION





From: brian wood <bri>drian@permitswest.com>

Subject: Elm Ridge Jicarilla Apache J 5
Date: August 15, 2009 3:30:32 PM MDT

To: ANNETTE TORIVIO <annettetorivio@jicarillaoga.com>



As required by NMOCD pit rule Subsection F of 19.15.17.13 NMAC, I am notifying the Jicarilla Apache Nation that Elm Ridge plans to close its temporary (reserve) pit after it is built and used using on site closure (burial) in the same pit.

The well is staked at 1950 FSL & 1950 FEL 4-23n-4w

The well is on lease BIA Contract 361

API # 30-039-30258

Please call me if you have any questions.

Brian Wood Permits West, Inc. 37 Verano Loop, Santa Fe, NM 87508

Phone: 505 466-8120 FAX: 505 466-9682

EXHIBIT J