


Submit 3 Copies To Appropriate District  
Office  
District I  
1625 N. French Dr., Hobbs, NM 88240  
District II  
1301 W. Grand Ave., Artesia, NM 88210  
District III  
1000 Rio Brazos Rd., Aztec, NM 87410  
District IV  
1220 S. St. Francis Dr., Santa Fe, NM  
87505

State of New Mexico  
Energy, Minerals and Natural Resources

OIL CONSERVATION DIVISION  
1220 South St. Francis Dr.  
Santa Fe, NM 87505

Form C-103  
Revised June 10, 2003

<b>SUNDRY NOTICES AND REPORTS ON WELLS</b> (DO NOT USE THIS FORM FOR PROPOSALS TO DRILL OR TO DEEPEN OR PLUG BACK TO A DIFFERENT RESERVOIR. USE "APPLICATION FOR PERMIT" (FORM C-101) FOR SUCH PROPOSALS.)		WELL API NO. 30-045-08227
1. Type of Well: Oil Well <input type="checkbox"/> Gas Well <input checked="" type="checkbox"/> Other		5. Indicate Type of Lease STATE <input type="checkbox"/> FEE <input checked="" type="checkbox"/>
2. Name of Operator Richardson Operating Company		6. State Oil & Gas Lease No. N/A
3. Address of Operator 3100 La Plata Highway, Farmington, NM 87401		7. Lease Name or Unit Agreement Name Fawkes
4. Well Location Unit Letter _____ P _____ 740 feet from the South line and _____ 790 feet from the _____ East line Section 18 Township 29 North Range 13 West NMPM San Juan County		8. Well Number 19219
11. Elevation (Show whether DR, RKB, RT, GR, etc.) 5230' GR		9. OGRID Number 19219
		10. Pool name or Wildcat West Kutz PC



12. Check Appropriate Box to Indicate Nature of Notice, Report or Other Data

**NOTICE OF INTENTION TO:**  
PERFORM REMEDIAL WORK ☐ PLUG AND ABANDON ☒  
TEMPORARILY ABANDON ☐ CHANGE PLANS ☐  
PULL OR ALTER CASING ☐ MULTIPLE COMPLETION ☐  
OTHER: ☐

**SUBSEQUENT REPORT OF:**  
REMEDIAL WORK ☐ ALTERING CASING ☐  
COMMENCE DRILLING OPNS. ☐ PLUG AND ABANDONMENT ☐  
CASING TEST AND CEMENT JOB ☐  
OTHER: ☐

13. Describe proposed or completed operations. (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work). SEE RULE 1103. For Multiple Completions: Attach wellbore diagram of proposed completion or recompletion.

Richardson Operating Company proposed the following P & A Procedure for the subject well:

fc 340

Pull tubing from wellbore. 8 5/8" casing from surface to 108'. 5 1/2" casing set to 940'. Top of PC @ 936'. Top of FC @ 382'. Set Balanced Plug from 965' to 700'. Perforate @ 432'. Attempt to circulate. If successful pump cement (285sx) to surface. If not pump a balanced plug from 432' to 282'. Then perforate @ 220'. Attempt to circulate cement (165sx) to surface. If successful pump cement to surface. If not pump plug @ 250' to 150'. Circulate cement (85sx) to surface. Remove wellhead and install P & A marker. Work will commence upon approval.  
Location will be used for proposed ROPCO 18 #4 well which was proposed via E-permitting on 1/30/04.

I hereby certify that the information above is true and complete to the best of my knowledge and belief.

SIGNATURE \_\_\_\_\_ TITLE Landman DATE 2/4/04

Type or print name Paul Lehrman E-mail address: plehrman@digii.net Telephone No. 564-8115

(This space for State use)

APPROVED BY \_\_\_\_\_ TITLE D. O. G. inc. DATE 2-5-04  
Conditions of approval, if any: