Jones, Brad A., EMNRD

From: Sent: Kim_Champlin@xtoenergy.com Thursday, March 11, 2010 2:12 PM

To:

Jones, Brad A., EMNRD

Subject:

Fw: BGT P&A's

Brad,

The closure requests for the three locations listed below did go out in this afternoon's mail per our discussion 3/10/10. Should you have any questions once you receive them feel free to contact me. Thanks for your time on this.

OH Randel #8 API 30-045-24788 09F-26N-11W submitted September 2008 Quine GC #2 API 30-045-29704 31K-30N-12W submitted September 2008 Evensen #2 API 30-045-06318 19P-27N-10W submitted September 2008

Kim Champlin XTO Energy Inc. EH&S Administrative Coordinator San Juan Division (505) 333-3100 office (505) 330-8357 cell (505) 333-3280 fax kim_champlin@xtoenergy.com

This inbound email has been scanned for malicious software and transmitted safely to you using Webroot Email Security.

District I 1625 N. French Dr., Hobbs, NM 88240 District II 1301 W. Grand Avenue, Artesia, NM 88210 District III 1000 Rio Brazos Road, Aztec, NM 87410 District IV

State of New Mexico Energy Minerals and Natural Resources For temporary pits, closed-loop systems, and Department--below-grade tanks, submit to the appropriate Oil Conservation Division - NMOCD District Office.
- For permanent pits and exceptions submit to the Santa Fe Environmental Bureau office and 1220 South St. Francis Dr. provide a copy to the appropriate NMOCD

1 Digital Office. Santa Fe NM 875052

1220 S. St. Francis Dr., Santa Fe, NM 87505 Pit, Closed-Loop System, Below-Grade Tank, or Proposed Alternative Method Permit or Closure Plan Application Permit of a pit, closed-loop system, below-grade tank, or proposed alternative method Type of action: Closure of a pit, closed-loop system, below-grade tank, or proposed alternative method Modification to an existing permit X Closure plan only submitted for an existing permitted or non-permitted pit, closed-loop system, below-grade tank, or proposed alternative method Instructions: Please submit one application (Form C-144) per individual pit, closed-loop system, below-grade tank or alternative request Please be advised that approval of this request does not relieve the operator of liability should operations result in pollution of surface water, ground water or the environment. Nor does approval relieve the operator of its responsibility to comply with any other applicable governmental authority's rules, regulations or ordinances. Operator: XTO ENERGY, INC. Address: #382 County Road 3100, Aztec, NM 87410 Facility or well name: Quine Gas Com #2 API Number: 30-045-29704 OCD Permit Number: U/L or Qtr/Qtr K Section 31 Township 30N Range 12W County: San Juan ____Longitude ______108.14106 NAD: □1927 □ 1983 Center of Proposed Design: Latitude 36.76661 Surface Owner: Federal State Private Tribal Trust or Indian Allotment Pit: Subsection F or G of 19.15.17.11 NMAC Temporary: Drilling Workover ☐ Permanent ☐ Emergency ☐ Cavitation ☐ P&A ☐ Lined ☐ Unlined Liner type: Thickness mil ☐ LLDPE ☐ HDPE ☐ PVC ☐ Other ☐ String-Reinforced Liner Seams: Welded Factory Other Closed-loop System: Subsection H of 19.15.17.11 NMAC Type of Operation: P&A Drilling a new well Workover or Drilling (Applies to activities which require prior approval of a permit or notice of intent) ☐ Drying Pad ☐ Above Ground Steel Tanks ☐ Haul-off Bins ☐ Other ☐ Lined ☐ Unlined Liner type: Thickness mil ☐ LLDPE ☐ HDPE ☐ PVC ☐ Other Liner Seams: Welded Factory Other **☒** Below-grade tank: Subsection I of 19.15.17.11 NMAC Produced Water bbl Type of fluid: Volume: Tank Construction material: Steel ☐ Secondary containment with leak detection ☐ Visible sidewalls, liner, 6-inch lift and automatic overflow shut-off ☐ Visible sidewalls and liner ☐ Visible sidewalls only ☒ Other Visible sidewalls, vault, automatic overflow shut off mil HDPE PVC Other Liner type: Thickness Alternative Method: Submittal of an exception request is required. Exceptions must be submitted to the Santa Fe Environmental Bureau office for consideration of approval.

Fencing: Subsection D of 19.15.17.11 NMAC (Applies to permanent pits, temporary pits, and below-grade tanks) Chain link, six feet in height, two strands of barbed wire at top (Required if located within 1000 feet of a permanent residence, school, institution or church) Four foot height, four strands of barbed wire evenly spaced between one and four feet Alternate. Please specify	hospital,
7. Netting: Subsection E of 19.15.17.11 NMAC (Applies to permanent pits and permanent open top tanks) Screen Netting Other Monthly inspections (If netting or screening is not physically feasible)	
8. Signs: Subsection C of 19.15.17.11 NMAC 12"x 24", 2" lettering, providing Operator's name, site location, and emergency telephone numbers Signed in compliance with 19.15.3.103 NMAC	
9. Administrative Approvals and Exceptions: Justifications and/or demonstrations of equivalency are required. Please refer to 19.15.17 NMAC for guidance. Please check a box if one or more of the following is requested, if not leave blank: Administrative approval(s): Requests must be submitted to the appropriate division district or the Santa Fe Environmental Bureau consideration of approval. Exception(s): Requests must be submitted to the Santa Fe Environmental Bureau office for consideration of approval.	office for
Siting Criteria (regarding permitting): 19.15.17.10 NMAC Instructions: The applicant must demonstrate compliance for each siting criteria below in the application. Recommendations of accept material are provided below. Requests regarding changes to certain siting criteria may require administrative approval from the appropriate of the Santa Fe Environmental Bureau office for consideration of a Applicant must attach justification for request. Please refer to 19.15.17.10 NMAC for guidance. Siting criteria does not apply to dry above-grade tanks associated with a closed-loop system.	ppriate district pproval.
Ground water is less than 50 feet below the bottom of the temporary pit, permanent pit, or below-grade tank. - NM Office of the State Engineer - iWATERS database search; USGS; Data obtained from nearby wells	☐ Yes ☐ No
Within 300 feet of a continuously flowing watercourse, or 200 feet of any other significant watercourse or lakebed, sinkhole, or playa lake (measured from the ordinary high-water mark). - Topographic map; Visual inspection (certification) of the proposed site	Yes No
Within 300 feet from a permanent residence, school, hospital, institution, or church in existence at the time of initial application. (Applies to temporary, emergency, or cavitation pits and below-grade tanks) - Visual inspection (certification) of the proposed site; Aerial photo; Satellite image	Yes No
Within 1000 feet from a permanent residence, school, hospital, institution, or church in existence at the time of initial application. (Applies to permanent pits) - Visual inspection (certification) of the proposed site; Aerial photo; Satellite image	☐ Yes ☐ No ☐ NA
Within 500 horizontal feet of a private, domestic fresh water well or spring that less than five households use for domestic or stock watering purposes, or within 1000 horizontal feet of any other fresh water well or spring, in existence at the time of initial application. - NM Office of the State Engineer - iWATERS database search; Visual inspection (certification) of the proposed site	☐ Yes ☐ No
Within incorporated municipal boundaries or within a defined municipal fresh water well field covered under a municipal ordinance adopted pursuant to NMSA 1978, Section 3-27-3, as amended. - Written confirmation or verification from the municipality; Written approval obtained from the municipality	☐ Yes ☐ No
Within 500 feet of a wetland. - US Fish and Wildlife Wetland Identification map; Topographic map; Visual inspection (certification) of the proposed site	Yes No
Within the area overlying a subsurface mine. - Written confirmation or verification or map from the NM EMNRD-Mining and Mineral Division	☐ Yes ☐ No
Within an unstable area. - Engineering measures incorporated into the design; NM Bureau of Geology & Mineral Resources; USGS; NM Geological Society; Topographic map	☐ Yes ☐ No
Within a 100-year floodplain FEMA map	☐ Yes ☐ No

Temporary Pits, Emergency Pits, and Below-grade Tanks Permit Application Attachment Checklist: Subsection B of 19.15.17.9 NMAC Instructions: Each of the following items must be attached to the application. Please indicate, by a check mark in the box, that the documents are attached. Hydrogeologic Report (Below-grade Tanks) - based upon the requirements of Paragraph (4) of Subsection B of 19.15.17.9 NMAC Hydrogeologic Data (Temporary and Emergency Pits) - based upon the requirements of Paragraph (2) of Subsection B of 19.15.17.9 NMAC Siting Criteria Compliance Demonstrations - based upon the appropriate requirements of 19.15.17.10 NMAC Design Plan - based upon the appropriate requirements of 19.15.17.11 NMAC Operating and Maintenance Plan - based upon the appropriate requirements of 19.15.17.12 NMAC Closure Plan (Please complete Boxes 14 through 18, if applicable) - based upon the appropriate requirements of Subsection C of 19.15.17.9 NMAC and 19.15.17.13 NMAC Previously Approved Design (attach copy of design) API Number: or Permit Number:
Closed-loop Systems Permit Application Attachment Checklist: Subsection B of 19.15.17.9 NMAC Instructions: Each of the following items must be attached to the application. Please indicate, by a check mark in the box, that the documents are attached. Geologic and Hydrogeologic Data (only for on-site closure) - based upon the requirements of Paragraph (3) of Subsection B of 19.15.17.9 Siting Criteria Compliance Demonstrations (only for on-site closure) - based upon the appropriate requirements of 19.15.17.10 NMAC Design Plan - based upon the appropriate requirements of 19.15.17.11 NMAC Operating and Maintenance Plan - based upon the appropriate requirements of 19.15.17.12 NMAC Closure Plan (Please complete Boxes 14 through 18, if applicable) - based upon the appropriate requirements of Subsection C of 19.15.17.9 NMAC and 19.15.17.13 NMAC
Previously Approved Design (attach copy of design) API Number:
Previously Approved Operating and Maintenance Plan API Number:(Applies only to closed-loop system that use
above ground steel tanks or haul-off bins and propose to implement waste removal for closure)
Permanent Pits Permit Application Checklist: Subsection B of 19.15.17.9 NMAC Instructions: Each of the following items must be attached to the application. Please indicate, by a check mark in the box, that the documents are attached. Hydrogeologic Report - based upon the requirements of Paragraph (1) of Subsection B of 19.15.17.9 NMAC Siting Criteria Compliance Demonstrations - based upon the appropriate requirements of 19.15.17.10 NMAC Climatological Factors Assessment Certified Engineering Design Plans - based upon the appropriate requirements of 19.15.17.11 NMAC Dike Protection and Structural Integrity Design - based upon the appropriate requirements of 19.15.17.11 NMAC Leak Detection Design - based upon the appropriate requirements of 19.15.17.11 NMAC Liner Specifications and Compatibility Assessment - based upon the appropriate requirements of 19.15.17.11 NMAC Quality Control/Quality Assurance Construction and Installation Plan Operating and Maintenance Plan - based upon the appropriate requirements of 19.15.17.12 NMAC Freeboard and Overtopping Prevention Plan - based upon the appropriate requirements of 19.15.17.11 NMAC Nuisance or Hazardous Odors, including H ₂ S, Prevention Plan Emergency Response Plan Oil Field Waste Stream Characterization Monitoring and Inspection Plan Erosion Control Plan Erosion Control Plan Erosion Control Plan Erosion Control Plan - based upon the appropriate requirements of Subsection C of 19.15.17.9 NMAC and 19.15.17.13 NMAC
Proposed Closure: 19.15.17.13 NMAC
Instructions: Please complete the applicable boxes, Boxes 14 through 18, in regards to the proposed closure plan. Type: Drilling Workover Emergency Cavitation P&A Permanent Pit Below-grade Tank Closed-loop System Alternative Proposed Closure Method: Waste Excavation and Removal Waste Removal (Closed-loop systems only) On-site Closure Method (Only for temporary pits and closed-loop systems) In-place Burial On-site Trench Burial
Alternative Closure Method (Exceptions must be submitted to the Santa Fe Environmental Bureau for consideration)
Waste Excavation and Removal Closure Plan Checklist: (19.15.17.13 NMAC) Instructions: Each of the following items must be attached to the closure plan. Please indicate, by a check mark in the box, that the documents are attached. ☐ Protocols and Procedures - based upon the appropriate requirements of 19.15.17.13 NMAC ☐ Confirmation Sampling Plan (if applicable) - based upon the appropriate requirements of Subsection F of 19.15.17.13 NMAC ☐ Disposal Facility Name and Permit Number (for liquids, drilling fluids and drill cuttings) ☐ Soil Backfill and Cover Design Specifications - based upon the appropriate requirements of Subsection H of 19.15.17.13 NMAC ☐ Re-vegetation Plan - based upon the appropriate requirements of Subsection G of 19.15.17.13 NMAC ☐ Site Reclamation Plan - based upon the appropriate requirements of Subsection G of 19.15.17.13 NMAC

Waste Removal Closure For Closed-loop Systems That Utilize Above Ground Steel Tanks or Haul-off Bins Only: (19.15.17.13. Instructions: Please indentify the facility or facilities for the disposal of liquids, drilling fluids and drill cuttings. Use attachment if n	NMAC) nore than two
facilities are required.	
Disposal Facility Name: Disposal Facility Permit Number:	
Disposal Facility Name: Disposal Facility Permit Number:	
Will any of the proposed closed-loop system operations and associated activities occur on or in areas that will not be used for future server of the proposed closed-loop system operations and associated activities occur on or in areas that will not be used for future server of the proposed closed-loop system operations and associated activities occur on or in areas that will not be used for future server of the proposed closed-loop system operations and associated activities occur on or in areas that will not be used for future server of the proposed closed-loop system operations and associated activities occur on or in areas that will not be used for future server of the proposed closed-loop system operations and associated activities occur on or in areas that will not be used for future server of the proposed closed-loop system operations are also server of the proposed closed-loop system operations are also server of the proposed closed-loop system operations are also server of the proposed closed-loop system operations are also server of the proposed closed-loop system operations are also server of the proposed closed-loop system operations are also server of the proposed closed-loop system operations are also server of the proposed closed-loop system operations are also server of the proposed closed-loop system operations are also server of the proposed closed-loop system operations are also server of the proposed closed-loop system operations are also server of the proposed closed-loop system operations are also server of the proposed closed-loop system operations are also server of the proposed closed-loop system operations are also server of the proposed closed-loop system operations are also server of the proposed closed-loop system operations are also server of the proposed closed-loop system operations are also server of the proposed closed-loop system operations are also server of the proposed closed-loop system operations are also server of the proposed closed-loop system operations are also server	vice and operations?
Required for impacted areas which will not be used for future service and operations: Soil Backfill and Cover Design Specifications based upon the appropriate requirements of Subsection H of 19.15.17.13 NMAC Re-vegetation Plan - based upon the appropriate requirements of Subsection I of 19.15.17.13 NMAC Site Reclamation Plan - based upon the appropriate requirements of Subsection G of 19.15.17.13 NMAC	0
Siting Criteria (regarding on-site closure methods only): 19.15.17.10 NMAC Instructions: Each siting criteria requires a demonstration of compliance in the closure plan. Recommendations of acceptable sour provided below. Requests regarding changes to certain siting criteria may require administrative approval from the appropriate districtions of exception which must be submitted to the Santa Fe Environmental Bureau office for consideration of approval. Justif demonstrations of equivalency are required. Please refer to 19.15.17.10 NMAC for guidance.	rict office or may be
Ground water is less than 50 feet below the bottom of the buried waste. - NM Office of the State Engineer - iWATERS database search; USGS; Data obtained from nearby wells	☐ Yes ☐ No ☐ NA
Ground water is between 50 and 100 feet below the bottom of the buried waste - NM Office of the State Engineer - iWATERS database search; USGS; Data obtained from nearby wells	☐ Yes ☐ No ☐ NA
Ground water is more than 100 feet below the bottom of the buried waste. - NM Office of the State Engineer - iWATERS database search; USGS; Data obtained from nearby wells	Yes No
Within 300 feet of a continuously flowing watercourse, or 200 feet of any other significant watercourse or lakebed, sinkhole, or playa lake (measured from the ordinary high-water mark). - Topographic map; Visual inspection (certification) of the proposed site	☐ Yes ☐ No
Within 300 feet from a permanent residence, school, hospital, institution, or church in existence at the time of initial application. - Visual inspection (certification) of the proposed site; Aerial photo; Satellite image	☐ Yes ☐ No
Within 500 horizontal feet of a private, domestic fresh water well or spring that less than five households use for domestic or stock watering purposes, or within 1000 horizontal feet of any other fresh water well or spring, in existence at the time of initial application. - NM Office of the State Engineer - iWATERS database; Visual inspection (certification) of the proposed site	☐ Yes ☐ No
Within incorporated municipal boundaries or within a defined municipal fresh water well field covered under a municipal ordinance adopted pursuant to NMSA 1978, Section 3-27-3, as amended. - Written confirmation or verification from the municipality; Written approval obtained from the municipality	Yes No
Within 500 feet of a wetland. - US Fish and Wildlife Wetland Identification map; Topographic map; Visual inspection (certification) of the proposed site	☐ Yes ☐ No
Within the area overlying a subsurface mine. - Written confirmation or verification or map from the NM EMNRD-Mining and Mineral Division	☐ Yes ☐ No
Within an unstable area. - Engineering measures incorporated into the design; NM Bureau of Geology & Mineral Resources; USGS; NM Geological Society; Topographic map	☐ Yes ☐ No
Within a 100-year floodplain FEMA map	☐ Yes ☐ No
On-Site Closure Plan Checklist: (19.15.17.13 NMAC) Instructions: Each of the following items must be attached to the closure plan by a check mark in the box, that the documents are attached. Siting Criteria Compliance Demonstrations - based upon the appropriate requirements of 19.15.17.10 NMAC Proof of Surface Owner Notice - based upon the appropriate requirements of Subsection F of 19.15.17.13 NMAC Construction/Design Plan of Burial Trench (if applicable) based upon the appropriate requirements of 19.15.17.11 NMAC Construction/Design Plan of Temporary Pit (for in-place burial of a drying pad) - based upon the appropriate requirements of 19. Protocols and Procedures - based upon the appropriate requirements of 19.15.17.13 NMAC Confirmation Sampling Plan (if applicable) - based upon the appropriate requirements of Subsection F of 19.15.17.13 NMAC Waste Material Sampling Plan - based upon the appropriate requirements of Subsection I of 19.15.17.13 NMAC Soil Cover Design - based upon the appropriate requirements of Subsection I of 19.15.17.13 NMAC Re-vegetation Plan - based upon the appropriate requirements of Subsection I of 19.15.17.13 NMAC	15.17.11 NMAC

Operator Application Certification: I hereby certify that the information submitted with this application is true, accurate and complete to the best of my knowledge and belief.
Name (Print): Kim Champlin Title: EH&S Adminstrative Coordinator
Signature: Date: March 11, 2010
e-mail address: kim_champlin@xtoenergy.com Telephone: (505) 333-3100
20. OCD Approval: ☐ Permit Application (including closure plan) ☐ Closure Plan (only) ☐ OCD Conditions (see attachment)
OCD Representative Signature: Approval Date: 3/14/10
Title: OCD Permit Number:
Closure Report (required within 60 days of closure completion): Subsection K of 19.15.17.13 NMAC Instructions: Operators are required to obtain an approved closure plan prior to implementing any closure activities and submitting the closure report. The closure report is required to be submitted to the division within 60 days of the completion of the closure activities. Please do not complete this section of the form until an approved closure plan has been obtained and the closure activities have been completed.
Closure Completion Date:
Closure Method: Waste Excavation and Removal On-Site Closure Method Alternative Closure Method Waste Removal (Closed-loop systems only) If different from approved plan, please explain.
23. <u>Closure Report Regarding Waste Removal Closure For Closed-loop Systems That Utilize Above Ground Steel Tanks or Haul-off Bins Only:</u> Instructions: Please indentify the facility or facilities for where the liquids, drilling fluids and drill cuttings were disposed. Use attachment if more than two facilities were utilized.
Disposal Facility Name: Disposal Facility Permit Number:
Disposal Facility Name: Disposal Facility Permit Number:
Were the closed-loop system operations and associated activities performed on or in areas that <i>will not</i> be used for future service and operations? \[\sum \text{ Yes (If yes, please demonstrate compliance to the items below) } \sum \text{ No} \]
Required for impacted areas which will not be used for future service and operations: Site Reclamation (Photo Documentation) Soil Backfilling and Cover Installation Re-vegetation Application Rates and Seeding Technique
24. Closure Report Attachment Checklist: Instructions: Each of the following items must be attached to the closure report. Please indicate, by a check
mark in the box, that the documents are attached. Proof of Closure Notice (surface owner and division) Proof of Deed Notice (required for on-site closure) Plot Plan (for on-site closures and temporary pits) Confirmation Sampling Analytical Results (if applicable) Waste Material Sampling Analytical Results (required for on-site closure) Disposal Facility Name and Permit Number Soil Backfilling and Cover Installation Re-vegetation Application Rates and Seeding Technique Site Reclamation (Photo Documentation)
On-site Closure Location: Latitude Longitude NAD: \[\Boxed{1927} \Boxed{1983}
Operator Closure Certification: I hereby certify that the information and attachments submitted with this closure report is true, accurate and complete to the best of my knowledge and belief. I also certify that the closure complies with all applicable closure requirements and conditions specified in the approved closure plan.
Name (Print): Title:
Signature: Date:
e-mail address: Telephone:

Client: **XTO Energy** Lodestar Services, Inc. Pit Permits Project: Pit Permit Revised: 14-Oct-08 PO Box 4465, Durango, CO 81302 **Siting Criteria** Prepared by: Brooke Herb API#: 3004529704 **USPLSS:** T30N,R12W,S31K Lat/Long: 36.76661, -108.14106 Name: QUINE GAS COM #2 Geologic Depth to groundwater: < 50' Nacimiento Formation formation: Distance to closest 2870' NW of the Animas River continuously flowing watercourse: Distance to closest significant watercourse, 260' E of Hood Arroyo lakebed, playa lake, or sinkhole: Soil Type: **Entisols** Permanent residence, school, hospital, No institution or church within 300 **Annual** 8.21 inches (Farmington) Precipitation: Precipitation Domestic fresh water no significant precip events No Notes: well or spring within 500' Any other fresh water Yes - iWaters wells SJ01236 and well or spring within SJ03122 1000' Within incorporated **Attached** YES - Farmington Groundwater report and Data; FEMA Flood Zone Map municipal boundaries **Documents:** Within defined municipal No Aerial Photo, Topo Map, Mines Mills and Quarries Map fresh water well field Wetland within 500' No Mining Activity: 1.74 miles NW of a Materials Pit Within unstable area No Within 100 year flood

Additional Notes:

No FEMA data in city limits

QUINE GAS COM #2 Below Ground Tank Siting Criteria and Closure Plan

Well Site Location

Legals: T30N, R12W, Section 31, Quarter Section K Latitude/Longitude: approximately 36.76661, -108.14106

County: San Juan County, NM

General Description: near Animas River

General Geology and Hydrology

The San Juan Basin is a typical Rocky Mountain basin with a gently dipping southern flank and a steeply dipping northern flank. Asymmetrically layered Tertiary sandstones and shales, along with Quaternary alluvial deposits dominate surficial geology (Dane and Bachman, 1965). The proposed below ground tank location will be located on the flanks of the Farmington Glade between Aztec and La Plata, New Mexico. Within the Farmington Glade, the Tertiary Nacimiento Formation is exposed, along with Quaternary alluvial and aeoloian sands surrounding the center of the wash.

Cretaceous and Tertiary sandstones, as well as Quaternary alluvial deposits serve as the primary aquifers in the San Juan basin (Stone et al., 1983). In most of the proposed area, the Nacimiento Formation lies at the surface. Thickness of the Nacimiento ranges from 418 to 2232 feet (Stone et al., 1983). Aquifers within the coarser and continuous sandstone bodies of the Nacimiento Formation are between 0 and 1000' deep in this section of the basin (Stone et al., 1983). Groundwater within these aquifers flows toward the nearby San Juan River and its tributaries.

The prominent soil type at the proposed site is entisols, which are defined as soils that do not show any profile development. Soils are basically unaltered from their parent rock. Miles of arroyos, washes and intermittent streams exist as part of the drainage network towards the La Plata River (www.emnrd.state.nm.us). These features often cut into soil and other unconsolidated materials, contributing to sedimentation downstream. The sudden influx of water from storm events easily erodes soils that cover the area.

The climate of the region is arid, averaging just over 8 inches of rainfall annually. As is typical of the southwestern United States monsoonal weather patterns, most precipitation falls from August through October. The heaviest rainfall occurs in the summer in isolated, intense cloudbursts. November through June is relatively dry. Snow generally falls from December to mid-February and averages less than one-half inch in depth. However, most recharge occurs during the winter months during snowmelt periods from the upper elevations (Western Regional Climate Center www.wrcc.dri.edu).


The predominant vegetation is sagebrush and grasses with a more restricted pinon-juniper association (Dick-Peddie, 1993).


Site Specific Hydrogeology

Depth to groundwater is estimated to be less than 50 feet. This estimation is based on data from Stone and others, 1983 and depth to groundwater data published on the New Mexico State Engineer's iWaters Database website. Local topography and proximity to surface hydrologic features are also taken into consideration.

Local aquifers include sandstones within the Nacimiento Formation, which ranges from 0 to 1000 feet deep in this area, as well as shallow aquifers within Quaternary alluvial deposits (Stone et al., 1983). The 1000-foot depth range for Nacimiento aquifers covers an area over 20 miles wide, and depth decreases towards the margin of the San Juan Basin. The site in question is more centrally located, and depth to the aquifer is expected to be closer to 1000 feet. It is well known that groundwater close to the Animas River can be shallow, as the Quaternary deposits near the river itself form shallow aquifers. The proposed site is situated 2870 feet to the northwest of the Animas River, and is approximately 60 feet higher in elevation (Google Earth).

Groundwater data available from the NM State Engineer's iWaters Database for wells near the proposed site are attached. A map showing the location of wells in reference to the proposed pit location is also included. Pinpoints show locations of wells and the labels for each pinpoint indicate depth to groundwater in feet. Wells are clustered near the proposed site to the east, north, and south along the animas river. Depth to groundwater within the nearby wells ranges from 5 to 47 feet below ground surface. The closest well is situated 560 feet to the north-northwest of the proposed site, and is 10 feet higher in topographic elevation (Google Earth). Depth to groundwater within the well is 38 feet below ground surface. A well to the southeast has a depth to groundwater of 15 feet below ground surface, and is approximately 20 feet lower in elevation from the proposed site.





Aerial Photograph

Lodestar Services, Inc PO Box 4465 Durango, CO 81302

San Juan County, NM QUINE GAS COM #2 T30N, R12W, S31K



Inc QUINE GAS COM #2 T30N, R12W, S31K San Juan County, NM

iWaters Groundwater Data Map

Lodestar Services, Inc PO Box 4465 Durango, CO 81302

New Mexico Office of the State Engineer POD Reports and Downloads

		1 :	All
			હ
I		Suffix:	Domestic
1	lius:	1	C
Township: Sange: 12M Sections: 28,29,30,31,32,33	Search Radius:	Number:	Non-Domestic C Domestic G All
ection	.e.		
	Zone:		
<u></u>			(Last)
Rang			ı
80		Basin:	:
nship:	×		
Towa	NAD27 X. [,	First)
	NAI	:	ne: (
		nty:	r Nan
		County:	Owner Name: (First)

WATER COLUMN REPORT 10/14/2008

POD / Surface Data Report Avg Depth to Water Report Water Column Report

	quarters	are	1=N biq	3 6	2=NE	are 1=NW 2=NE 3=SW 4=SE)			Deoth	Depth	Water	(in feet)
POD Number	Tws	Rng	Sec	ָ ט	מ	Zone	×	*	Well	Water	Column	
SJ 00282	30N		28						84	52	32	
SJ 00122 CLW28372	۱	12W	28	 H	m				126	61	65	
SJ 01309	30N	12W	(7) (2)		m				52	32	23	
SJ 00122	1	12W	(V)	 1	W (2)				80	40	40	
SJ 02142		12W	8	,I	511				55	32	20	
SJ 01275	1	12W	28		(Y)				30	Ŋ	25	
SJ 02016	30N	12W	8	C4	_				120	10 10	64	
SJ 01129	30N	12W	88	C)	1 2				40	10	30	
SJ 03702	30N	12W	28	OI.	(N)				30	Ŋ	25	
SJ 03702 POD1	30N	12W	(A)	CSI	m				30	ιŊ	25	
SJ 00346	30N	12W	28	C)	٦				.T.	15	26	
SJ 03796 POD1	30N	12W	28	m	1 2	264258		2104657	C)	Ŋ	17	
SJ 02571	30N	12W	28	4.	۳ ا				2.1	Ø	15	
SJ 03096	30N	12W	8	4	۲۳' ۲۳'				125			

0 5	30N	2W	œ (Ω	4		70
J 028	30N	2W	88	4		20
3 033	30N	2W	ω (3)	-		50
J 036	30N	2W	ထ	-	ίų	50
J 036	30N	2.W	ф (V)			50
J 020	30N	2 W	9	ო		\mathcal{Q}^{j}
SJ 03187	30N		Ω Ω	3		160
ы	30N	2W	9	ω ⊘	1	CAL
5	30N	2W	9			\circ
ה	30N	2 W	9			0
Ы	30N	28	ω σ			CAL
Ы	30N	2 W	Ω Ω			(A)
Ы	30N	2W	Q.	4.		50
SJ 02309	30N	2W	9	7	N	20
Ы	30N	2W	Ω O	4	-1	44
ы	30N	2W	9	•		ტ
Ы	30N	2 W	30			დ ტ
ы	30N	ZW	30		1	47,
Ы	30N	2W	30			CA1
כיו	30N	2W	30		<1°	175
Ы	30N	2 W	30			ᄭ
ה	30N	2 W	31			S
ח	30N	2 W	31			20
Ы	30N	2W	31		עי	58
Ы	30N	2W	31			4 ,
ы	30N	2W	31			63
Ы	30N	2 W	31			45
ы	30N	2W	31			63
b	30N	2W	31		(4)	60
Ы	30N	2W	31			67
ח	30N	2W	31			62
ה	30N	2W	31			42
Ы	30N	2W	31			70
ы	30N	2 W	31			53
ь	30N	2W	31			20
ח	30N	2W	31			30
ה	30N	2W	31			56
מ	30N	2 W	31	4	C)	40
Ы	30N	2W	31			6 7
SJ 02882	30N	2₩	3.1			33

() () () () () () () () () () () () () (наамм н		**************************************
	33 24 24 24 24 24 24 24 24 24 24 24 24 24	n n n n n n n n n n n : a a a a a a a a a	- 0000000000000000
028 032 030 030 030 030	031 031 022 022 016 016 016 016	0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	

SJ 01832	30N	12W	23	ص ب				4.1	10	
Ы	30N	3	32	رد) اا				40	18	
SJ 02262	30N		22	1.3						
SJ 02177	30N		22	.T				33		
Ь	30N		27	æ .∓				3.4	11	
Ь	30N		<u>~</u>	.⊣ .⊣				36		
	30N		2	13				70		
	30N		22	.⊣	 1			35	5 7	
SJ 03009	30N		22	.7	61			37		
SJ 03190	30N		22	⁴	m			25		
SJ 03748 POD1	30N		22	₩ 33	m					
	30N		22	∵†	4,			3.1	11	
	30N		2	<u>:</u> 7				34	15	
SJ 02239	30N	12W	22	2	C)			65	17	
	30N		22	Ω ω	CI			60	30	
SJ 03206	30N		≅	(Z)	C 1			60		
	SON		2	Ω ω	m			12 13		
SJ 00116 S	30N		22	ω ω	ო			25		
SJ 03606	30N		22	3.4	m			67	94	
SJ 02908	30N		22	4 2	V)			50		
	30N		22	4 2	42,	263644	2098600	26	ထ	
SJ 02804	30N	12W	22	43	4.			20		
	30N		2	4 4	ო			24	12	
SJ 03349	30N		Ω	1 2				55		
	30N		83	12				97	60	
	30N		33	1 2				320	1.U 4.	
	30N		33	1.3				36	10	
01390	30N		33	.⊓				40	22	
	30N		ლ	<u>1</u>				40	10	
SJ 03133	30N	12W	33	1.4	4			თ ო	20	
SJ 00605	SON		33	KI KI	N			72	35	
sJ 00606	30N		33	2				104	35	
SJ 02981	30N		33	•				100	99	
SJ 01072	30N		33					110	50	
SJ 01036	30N			•				105	70	
	30N		33	ΘΘ				73	45	
ı 1	30N	12W 3	33		•			42	20	
SJ 00474	30N				m			104	60	
	30N		33	о С	• •			42	33	
SJ 01256	30N							250	160	

Record Count: 146

New Mexico Office of the State Engineer POD Reports and Downloads


Township: 30NRange: 13V Sections: 26,27,35

POD / Surface Data Report Avg Depth to Water Report Water Column Report

WATER COLUMN REPORT 10/02/2008

	(quarter:	s are	1=N	Σ	ENE	quarters are 1=NW 2=NE 3=SW 4=SE)							
	(quarters are biggest to	sare	big	ges	t to	smallest)			Depth	Depth	Water	(in feet)	at)
POD Number	Tws	Rng S	Sec	ים ים	יט		×	×	Well	Water	Column		
SJ 01736	30N			 ⊲7'					332	300	32		
SJ 01119	30N		26	1.4	খ				370	300	70		
SJ 01454	30N			.T %	 1				400	350	50		
SJ 01117	30N			3	47'				360	300	60		
SJ 02225	30N		(Q)	ω 2	C)				339	300	99		
SJ 01895	30N		(S)	9	খ				370	250	120		
SJ 01181	30N	13W 2		ო ო	(2)				257	230	27		
SJ 01503	30N		9	42	Ŋ				310	260	50		
SJ 02674	30N		27	3.4	٠.1.				270	250	20		
sJ 02391	30N	13W	35	<u>.</u>	₩				260	200	60		

Record Count: 10



Mines, Mills, and Quarries Map

Lodestar Services, Inc PO Box 4465 Durango, CO 81302

San Juan County, NM QUINE GAS COM #2 T30N, R12W, S31K

XTO Energy Inc. San Juan Basin (Northwest New Mexico) General Closure Plan For Below-Grade Tanks

In accordance with Rule 19.15.17.13 NMAC the following information describes the closure requirements of below-grade tanks on XTO Energy Inc. (XTO) locations. This is XTO's standard procedure for all below-grade tanks. A separate plan will be submitted for any below-grade tank which does not conform to this plan.

General Plan

- 1. XTO will close below-grade tanks within the time periods provided in 19.15.17.13 NMAC, or by an earlier date that the division requires because of imminent danger to fresh water, public health or the environment.
- 2. XTO will close a below-grade tank that does not meet the requirements of Paragraphs (1) through (4) of Subsection I of 19.15.17.11 NMAC or is not included in Paragraph (5) of Subsection I of 19.15.17.11 NMAC within five years after June 16, 2008, if not retrofitted to comply with Paragraphs (1) through (4) of Subsection I of 19.15.17.11 NMAC.
- 3. XTO will close a permitted below-grade tank within 60 days of cessation of the below-grade tank's operation or as required by the transitional provisions of Subsection B of 19.15.17.17 NMAC in accordance with a closure plan that the appropriate division district office approves. The closure report will be filed on form C-144.
- 4. XTO will remove liquids and sludge from below-grade tanks prior to implementing a closure method and will dispose of the liquids and sludge in a division-approved facility. Approved facilities and waste streams include:

Envirotech Permit No. NM01-0011 and IEI Permit No. NM 01-0010B Soil contaminated by exempt petroleum hydrocarbons Produced sand, pit sludge and contaminated bottoms from storage of exempt wastes

Basin Disposal Permit No. NM01-005 Produced water

- 5. XTO will remove the below-grade tank and dispose of it in a division approved facility or recycle, reuse, or reclaim it in a manner that the appropriate division district office has approved prior to removal. Any associated liners will be removed, properly cleaned and disposed of per 19.15.9.712 NMAC at San Juan County Landfill. Documentation of the final disposition will be included in the closure report.
- 6. XTO will remove any on-site equipment associated with a below-grade tank unless the equipment is required for some other purpose.
- 7. XTO will test the soils beneath the below-grade tank to determine whether a release has occurred. At a minimum 5 point composite sample will be collected along with individual grab samples from any area that is wet, discolored or showing other evidence of a release. Samples will be

XTO Energy Inc. San Juan Basin (Northwest New Mexico) General Closure Plan For Below-Grade Tanks Page 2

analyzed for BTEX, TPH and chlorides to demonstrate that the benzene concentration, as determined by EPA SW-846 methods 8021B or 8260B or EPA method that the division approves, does not exceed 0.2 mg/kg; total BTEX concentration, as determined by EPA SW-846 methods 8021B or 8260B or other EPA method that the division approves, does not exceed 50 mg/kg; the TPH concentration, as determined by EPA method 418.1 or other EPA method that the division approves, does not exceed 100mg/kg; and the chloride concentration, as determined by EPA method 300.1 or other EPA method that the division approves, does not exceed 250 mg/kg, or the background concentration, whichever is greater. XTO will notify the division of its results on form C-141.

- 8. If XTO or the division determines that a release has occurred, XTO will comply with 19.15.3.116 NMAC and 19.15.1.19NMAC as appropriate.
- 9. If the sampling program demonstrates that a release has not occurred or that any release does not exceed the concentrations specified in Paragraph (4) of Subsection E of 19.15.17.13 NMAC, XTO will backfill the excavation with compacted, non-waste containing, earthen material; construct a division prescribed soil cover; recontour and re-vegetate the site.
- 10. Notice of Closure operations will be given to the Aztec Division District III office between 72 hours and one week prior to the start of closure activities via email or verbally. The notification will include the following:
 - i. Operator's name
 - ii. Well Name and API Number
 - iii. Location by Unit Letter, Section, Township, and Range

The surface owner shall also be notified prior to the implementation of any closure operations of below-grade tanks as per the approved closure plan using certified mail, return receipt requested.

- 11. Re-contouring of location will match fit, shape, line, form and texture of the surrounding area. Re-shaping will include drainage control, prevent ponding, and prevent erosion. Natural drainages will be unimpeded and water bars and/or silt traps will be placed in areas where needed to prevent erosion on a large scale. Final re-contour shall have a uniform appearance with smooth surface, fitting the natural landscape.
- 12. A minimum of 4 feet of cover shall be achieved and the cover shall include 1 foot of suitable material to establish vegetation at the site, or the background thickness of topsoil, whichever is greater. Soil cover will be constructed to the site's existing grade and ponding of water and erosion of the cover material will be prevented with drainage control, natural drainages and silt traps where needed.
- 13. XTO will seed the disturbed areas the first growing season after the operator closes the pit. Seeding will be accomplished via drilling on the contour whenever practical or by other division-approved methods. BLM or Forest Service stipulated seed mixes will be used on federal lands. Vegetative cover will equal 70% of the native perennial vegetative cover (un-impacted) consisting of at least three native plant species, including at least one grass, but not including noxious weeds, and maintain that cover through two successive growing seasons. Repeat seeding or planting will be continued until successful vegetative growth occurs.

XTO Energy Inc. San Juan Basin (Northwest New Mexico) General Closure Plan For Below-Grade Tanks Page 3

- 14. All closure activities will include proper documentation and be available for review upon request and will be submitted in closure report form to OCD within 60 days of closure of the below-grade tank. Closure report will be filed on form C-144 and incorporate the following:
 - i. Proof of closure notice to division and surface owner;
 - ii. Details on capping and covering, where applicable;
 - iii. Inspection reports;
 - iv. Confirmation sampling analytical results;
 - v. Disposal facility name(s) and permit number(s);
 - vi. Soil backfilling and cover installation;
 - vii. Re-vegetation application rates and seeding techniques, (or approved alternative to re-vegetation requirements if applicable);
 - viii. Photo documentation of the site reclamation.