District I

1625 N. French Dr., Hobbs, NM 88240

District II

1301 W. Grand Ave., Artesia, NM 88210

District III

1000 Rio Brazos Rd., Aztec, NM 87410

State of New Mexico Energy Minerals and Natural Resources

> Department Oil Conservation Division 1220 South St. Francis Dr. Santa Ea NM 87505

Form C-144 July 21, 2008

For temporary pits, closed-loop sytems, and below-grade tanks, submit to the appropriate NMOCD District Office.

For parmanent nite and exceptions submit to the Santa Fa

| District IV | Santa Fe, NW 67303 | Environmental Bureau office and provide a copy to the | re |
|--|---|--|----------|
| 1220 S. St. Francis Dr., Santa Fe, NM 87505 | 11 C / D1 | appropriate NMOCD District Office. | |
| | sed-Loop System, Below-C | | |
| Proposed And | ernative Method Permit or | Closure Plan Application | |
| <u></u> | · · · · · · · · · · · · · · · · · · · | grade tank, or proposed alternative method | |
| XClosur | e of a pit, closed-loop system, below- | grade tank, or proposed alternative method | |
| | cation to an existing permit | | |
| | e plan only submitted for an existing grade tank, or proposed alternative m | permitted or non-permitted pit, closed-loop system, nethod | |
| Instructions: Please submit one application (| Form C-144) per individual pit, close | ed-loop system, below-grade tank or alternative requ | est |
| | · · · · · · · · · · · · · · · · · · · | ations result in pollution of surface water, ground water or the | |
| environment. Nor does approval relieve the operator | of its responsibility to comply with any other appl | licable governmental authority's rules, regulations or ordinances. | |
| Operator: Burlington Resources Oil & Gas Co | mpany, LP | OGRID#: 14538 | _ |
| Address: P.O. Box 4289, Farmington, NM 87 | 7499 | | |
| Facility or well name: SAN JUAN 28-6 UNIT | 166N | | <u> </u> |
| API Number: 30-039-3063 | OCD Permit | Number: | |
| U/L or Qtr/Qtr: F(SE/NW) Section: 1 | Township: 27N Range: | 6W County: Rio Arriba | [|
| · | 6.606108 °N Longitude: | | 983 |
| Surface Owner: X Federal Stat | e Private Tribal Trust or | Indian Allotment | |
| X Pit: Subsection F or G of 19.15.17.11 NMAC Temporary: X Drilling Workover Permanent Emergency Cavitation X Lined Unlined Liner type: X String-Reinforced | P&A Thickness 20 mil X LLDPI | E HDPE PVC Other | |
| Liner Seams: X Welded X Factory | Other Volume: | 7700 bbl Dimensions L 120' x W 55' x D 12 | 2' |
| 3 Closed-loop System: Subsection H of 19.1 Type of Operation: P&A Drilling a re | | plies to activities which require prior approval of a permit or | |
| | | E HDPE PVD Other 20212223 | 2423 |
| 4 | 44.55.61.6 | 12 LEOFIAF | |
| Below-grade tank: Subsection I of 19.15.17. | | JUN 2010 | 0 |
| | e of fluid: | OIL CONS. DIV. DIS | ST. 3 |
| Tank Construction material: | Tylida damai rocki ka | Constant S | |
| Secondary containment with leak detection Visible sidewalls and liner Visible | Visible sidewalls, liner, 6-inch lift and e sidewalls only | and automatic overflow shut-off | 2) |

Alternative Method:

Liner Type:

Submittal of an exception request is required. Exceptions must be submitted to the Santa Fe Environmental Bureau office for consideration of approval.

PVC

HDPE

mil

Thickness

Other

| Fencing: Subsection D of 19.15.17.11 NMAC (Applies to permanent pit, temporary pits, and below-grade tanks) Chain link, six feet in height, two strands of barbed wire at top (Required if located within 1000 feet of a permanent residence, school, hospital, institution four foot height, four strands of barbed wire evenly spaced between one and four feet Alternate. Please specify Netting: Subsection E of 19.15.17.11 NMAC (Applies to permanent pits and permanent open top tanks) Screen Netting Other Monthly inspections (If netting or screening is not physically feasible) Signs: Subsection C of 19.15.17.11 NMAC 12" X 24", 2" lettering, providing Operator's name, site location, and emergency telephone numbers | tion or church, | |
|--|-------------------|-------|
| Administrative Approvals and Exceptions: Justifications and/or demonstrations of equivalency are required. Please refer to 19.15.17 NMAC for guidance. Please check a box if one or more of the following is requested, if not leave blank: Administrative approval(s): Requests must be submitted to the appropriate division district of the Santa Fe Environmental Bureau office for consideration of approval. Exception(s): Requests must be submitted to the Santa Fe Environmental Bureau office for consideration of approval. | leration of appr | oval. |
| | | |
| Siting Criteria (regarding permitting) 19.15.17.10 NMAC Instructions: The applicant must demonstrate compliance for each siting criteria below in the application. Recommendations of acceptable source material are provided below. Requests regarding changes to certain siting criteria may require administrative approval from the appropriate district office or may be considered an exception which must be submitted to the Santa Fe Environmental Bureau Office for consideration of approval. Applicant must attach justification for request. Please refer to 19.15.17.10 NMAC for guidance. Siting criteria does not apply to drying pads or above grade-tanks associated with a closed-loop system. | | |
| Ground water is less than 50 feet below the bottom of the temporary pit, permanent pit, or below-grade tank. NM Office of the State Engineer - iWATERS database search; USGS; Data obtained from nearby wells | Yes | □No |
| Within 300 feet of a continuously flowing watercourse, or 200 feet of any other watercourse, lakebed, sinkhole, or playa lake (measured from the ordinary high-water mark). - Topographic map; Visual inspection (certification) of the proposed site | Yes | □No |
| Within 300 feet from a permanent residence, school, hospital, institution, or church in existence at the time of initial application. | Yes | □No |
| (Applies to temporary, emergency, or cavitation pits and below-grade tanks) | NA | |
| - Visual inspection (certification) of the proposed site; Aerial photo; Satellite image | نـــبا | |
| Within 1000 feet from a permanent residence, school, hospital, institution, or church in existence at the time of initial application. (Applied to permanent pits) Visual inspection (certification) of the proceed site. A cried photos Setellite inspect | ☐Yes ☐NA | No |
| Visual inspection (certification) of the proposed site; Aerial photo; Satellite image Within 500 horizonal feet of a private, domestic fresh water well or spring that less than five households use for domestic or stock watering purposes, or within 1000 horizontal feet of any other fresh water well or spring, in existence at the time of initial application. | Yes | □No |
| - NM Office of the State Engineer - iWATERS database search; Visual inspection (certification) of the proposed site. | | 1 |
| Within incorporated municipal boundaries or within a defined municipal fresh water well field covered under a municipal ordinance adopted pursuant to NMSA 1978, Section 3-27-3, as amended - Written confirmation or verification from the municipality; Written approval obtained from the municipality | Yes | □No |
| Within 500 feet of a wetland. - US Fish and Wildlife Wetland Identification map; Topographic map; Visual inspection (certification) of the proposed site | Yes | □No |
| Within the area overlying a subsurface mine Written confirmation or verification or map from the NM EMNRD - Mining and Mineral Division | Yes | □No |
| Within an unstable area. - Engineering measures incorporated into the design; NM Bureau of Geology & Mineral Resources; USGS; NM Geological Society; Topographic map | Yes | No |
| Within a 100-year floodplain - FEMA map | Yes | □No |

| Temporary Pits, Emergency Pits and Below-grade Tanks Permit Application Attachment Checklist Subsection B of 19.15.17.9 NMAC |
|--|
| Instructions: Each of the following items must be attached to the application. Please indicate, by a check mark in the box, that the documents are attached. |
| Hydrogeologic Report (Below-grade Tanks) - based upon the requirements of Paragraph (4) of Subsection B of 19.15.17.9 NMAC |
| Hydrogeologic Data (Temporary and Emergency Pits) - based upon the requirements of Paragraph (2) of Subsection B of 19.15.17.9 |
| Siting Criteria Compliance Demonstrations - based upon the appropriate requirements of 19.15.17.10 NMAC |
| Design Plan - based upon the appropriate requirements of 19.15.17.11 NMAC |
| Operating and Maintenance Plan - based upon the appropriate requirements of 19.15.17.12 NMAC |
| Closure Plan (Please complete Boxes 14 through 18, if applicable) - based upon the appropriate requirements of Subsection C of 19.15.17.9 NMAC and 19.15.17.13 NMAC |
| Previously Approved Design (attach copy of design) API or Permit |
| 12 |
| Closed-loop Systems Permit Application Attachment Checklist: Subsection B of 19.15.17.9 NMAC Instructions: Each of the following items must be attached to the application. Please indicate, by a check mark in the box, that the documents are attached. Geologic and Hydrogeologic Data (only for on-site closure) - based upon the requirements of Paragraph (3) of Subsection B of 19.15.17.9 |
| Siting Criteria Compliance Demonstrations (only for on-site closure) - based upon the appropriate requirements of 19.15.17.10 NMAC |
| Design Plan - based upon the appropriate requirements of 19.15.17.11 NMAC |
| Operating and Maintenance Plan - based upon the appropriate requirements of 19.15.17.12 NMAC |
| Closure Plan (Please complete Boxes 14 through 18, if applicable) - based upon the appropriate requirements of Subsection C of 19.15.17.9 NMAC and 19.15.17.13 NMAC |
| Previously Approved Design (attach copy of design) API |
| Previously Approved Operating and Maintenance Plan API |
| 13 |
| Permanent Pits Permit Application Checklist: Subsection B of 19.15.17.9 NMAC |
| Instructions: Each of the following items must be attached to the application. Please indicate, by a check mark in the box, that the documents are attached. |
| Hydrogeologic Report - based upon the requirements of Paragraph (I) of Subsection B of 19.15.17.9 NMAC |
| Siting Criteria Compliance Demonstrations - based upon the appropriate requirements of 19.15.17.10 NMAC |
| Climatological Factors Assessment |
| Certified Engineering Design Plans - based upon the appropriate requirements of 19.15.17.11 NMAC |
| Dike Protection and Structural Integrity Design: based upon the appropriate requirements of 19.15.17.11 NMAC Leak Detection Design - based upon the appropriate requirements of 19.15.17.11 NMAC |
| Liner Specifications and Compatibility Assessment - based upon the appropriate requirements of 19.15.17.11 NMAC |
| Quality Control/Quality Assurance Construction and Installation Plan |
| Operating and Maintenance Plan - based upon the appropriate requirements of 19.15.17.12 NMAC |
| Freeboard and Overtopping Prevention Plan - based upon the appropriate requirements of 19.15.17.11 NMAC |
| Nuisance or Hazardous Odors, including H2S, Prevention Plan |
| Emergency Response Plan |
| Oil Field Waste Stream Characterization |
| Monitoring and Inspection Plan |
| Erosion Control Plan |
| Closure Plan - based upon the appropriate requirements of Subsection C of 19.15.17.9 NMAC and 19.15.17.13 NMAC |
| Proposed Closure: 19.15.17.13 NMAC |
| Instructions: Please complete the applicable boxes, Boxes 14 through 18, in regards to the proposed closure plan. |
| Type: Drilling Workover Emergency Cavitation P&A Permanent Pit Below-grade Tank Closed-loop System |
| Alternative |
| Proposed Closure Method: Waste Excavation and Removal |
| Waste Removal (Closed-loop systems only) |
| On-site Closure Method (only for temporary pits and closed-loop systems) |
| In-place Burial On-site Trench |
| Alternative Closure Method (Exceptions must be submitted to the Santa Fe Environmental Bureau for consideration) |
| 15 |
| Waste Excavation and Removal Closure Plan Checklist (19.15.17.13 NMAC) Instructions: Each of the following items must be attached to the closure plan. Please indicate, by a check mark in the box, that the documents are attached. |
| Protocols and Procedures - based upon the appropriate requirements of 19.15.17.13 NMAC |
| Confirmation Sampling Plan (if applicable) - based upon the appropriate requirements of Subsection F of 19.15.17.13 NMAC |
| Disposal Facility Name and Permit Number (for liquids, drilling fluids and drill cuttings) |
| Soil Backfill and Cover Design Specifications - based upon the appropriate requirements of Subsection H of 19.15.17.13 NMAC |
| Re-vegetation Plan - based upon the appropriate requirements of Subsection I of 19.15.17.13 NMAC |
| Site Reclamation Plan - based upon the appropriate requirements of Subsection G of 19.15.17.13 NMAC |

Form C-144 Oil Conservation Division Page 3 of 5

| 16 Waste Removal Closure For Closed-loop Systems That Utilize Above Ground Ste | eel Tanks or Haul-off Bins Only:(19.15.17.13.D NMAC) | |
|--|---|-----------------------------|
| Instructions: Please identify the facility or facilities for the disposal of liquids, drilling facilities are required. | g fluids and drill cuttings. Use attachment if more than two | |
| 1 * | Disposal Facility Permit #: | |
| • | Disposal Facility Permit #: | |
| Will any of the proposed closed-loop system operations and associated activ Yes (If yes, please provide the information No | | |
| Required for impacted areas which will not be used for future service and operations. Soil Backfill and Cover Design Specification - based upon the appropriate requirements of Subse Site Reclamation Plan - based upon the appropriate requirements of Subsection Plan - based upo | oriate requirements of Subsection H of 19.15.17.13 N oction I of 19.15.17.13 NMAC | MAC |
| 17 Siting Criteria (Regarding on-site closure methods only: 19.15.17.10 NMA: Instructions: Each siting criteria requires a demonstration of compliance in the closure plan. Recertain siting criteria may require administrative approval from the appropriate district office or office for consideration of approval. Justifications and/or demonstrations of equivalency are required. | ecommendations of acceptable source material are provided below r may be considered an exception which must be submitted to the Se | |
| Ground water is less than 50 feet below the bottom of the buried waste. - NM Office of the State Engineer - iWATERS database search; USGS: Data ob | tained from nearby wells | Yes No |
| Ground water is between 50 and 100 feet below the bottom of the buried wa | cte | ☐Yes ☐No |
| - NM Office of the State Engineer - iWATERS database search; USGS; Data obt | | N/A |
| Ground water is more than 100 feet below the bottom of the buried waste. | | Yes No |
| - NM Office of the State Engineer - iWATERS database search; USGS; Data obt | ained from nearby wells | □N/A |
| Within 300 feet of a continuously flowing watercourse, or 200 feet of any other signif (measured from the ordinary high-water mark). | icant watercourse or lakebed, sinkhole, or playa lake | Yes No |
| - Topographic map; Visual inspection (certification) of the proposed site | | |
| Within 300 feet from a permanent residence, school, hospital, institution, or church in - Visual inspection (certification) of the proposed site; Aerial photo; satellite image | | Yes No |
| Within 500 horizontal feet of a private, domestic fresh water well or spring that less the purposes, or within 1000 horizontal fee of any other fresh water well or spring, in exist - NM Office of the State Engineer - iWATERS database; Visual inspection (certification) | stence at the time of the initial application. | YesNo |
| Within incorporated municipal boundaries or within a defined municipal fresh water we pursuant to NMSA 1978, Section 3-27-3, as amended. | | Yes No |
| Written confirmation or verification from the municipality; Written approval ob Within 500 feet of a wetland | tained from the municipanty | □Yes □No |
| - US Fish and Wildlife Wetland Identification map; Topographic map; Visual ins | pection (certification) of the proposed site | |
| Within the area overlying a subsurface mine. - Written confirantion or verification or map from the NM EMNRD-Mining and | Mineral Division | Yes No |
| Within an unstable area. | 2.77.5.0 | Yes No |
| Engineering measures incorporated into the design; NM Bureau of Geology & N Topographic map | fineral Resources; USGS; NM Geological Society; | |
| Within a 100-year floodplain. - FEMA map | | Yes No |
| On-Site Closure Plan Checklist: (19.15.17.13 NMAC) Instructions: Each by a check mark in the box, that the documents are attached. | h of the following items must bee attached to the clo | sure plan. Please indicate, |
| Siting Criteria Compliance Demonstrations - based upon the appropri | ate requirements of 19.15.17.10 NMAC | |
| Proof of Surface Owner Notice - based upon the appropriate requiren | • | |
| Construction/Design Plan of Burial Trench (if applicable) based upon | the appropriate requirements of 19.15.17.11 NMAC | |
| Construction/Design Plan of Temporary Pit (for in place burial of a d | | of 19.15.17.11 NMAC |
| Protocols and Procedures - based upon the appropriate requirements of | | |
| Confirmation Sampling Plan (if applicable) - based upon the appropri | • | AC |
| Waste Material Sampling Plan - based upon the appropriate requirem Disposal Facility Name and Permit Number (for liquids, drilling fluid | | s cannot be achieved) |
| Soil Cover Design - based upon the appropriate requirements of Subs | • | s camiot oc achieveu) |
| Re-vegetation Plan - based upon the appropriate requirements of Sub- | | |
| Site Reclamation Plan - based upon the appropriate requirements of S | ubsection G of 19.15.17.13 NMAC | |

| 19 . Operator Application Certification: |
|--|
| I hereby certify that the information submitted with this application is true, accurate and complete to the best of my knowledge and belief. |
| Name (Print): Title: |
| Signature: Date: |
| e-mail address: Telephone: |
| OCD Approval: Permit Application (including closure plan) Closure Plan (only) OCD Conditions (see attachment) OCD Representative Signature: Approval Date: 2/7/1/ Title: OCD Permit Number: |
| Closure Report (required within 60 days of closure completion): Subsection K of 19.15.17.13 NMAC Instructions: Operators are required to obtain an approved closure plan prior to implementing any closure activities and submitting the closure report. The closure report is required to be submitted to the division within 60 days of the completion of the closure activities. Please do not complete this section of the form until an approved closure plan has been obtained and the closure activities have been completed. X Closure Completion Date: |
| 22 |
| Closure Method: Waste Excavation and Removal X On-site Closure Method Alternative Closure Method Waste Removal (Closed-loop systems only) If different from approved plan, please explain. |
| 23 |
| Instructions: Please identify the facility or facilities for where the liquids, drilling fluids and drill cuttings were disposed. Use attachment if more than two facilities were utilized. Disposal Facility Name: Disposal Facility Permit Number: Disposal Facility Name: Disposal Facility Permit Number: Were the closed-loop system operations and associated activities performed on or in areas that will not be used for future service and operations? Yes (If yes, please demonstrate compliance to the items below) Required for impacted areas which will not be used for future service and operations: Site Reclamation (Photo Documentation) Soil Backfilling and Cover Installation Re-vegetation Application Rates and Seeding Technique |
| Closure Report Attachment Checklist: Instructions: Each of the following items must be attached to the closure report. Please indicate, by a check mark in the box, that the documents are attached. X Proof of Closure Notice (surface owner and division) X Proof of Deed Notice (required for on-site closure) X Plot Plan (for on-site closures and temporary pits) X Confirmation Sampling Analytical Results (if applicable) Waste Material Sampling Analytical Results (if applicable) X Disposal Facility Name and Permit Number X Soil Backfilling and Cover Installation X Re-vegetation Application Rates and Seeding Technique X Site Reclamation (Photo Documentation) On-site Closure Location: Latitude: 36.606297 °N Longitude: 107.418823 °W NAD 1927 X 1983 |
| Operator Closure Certification: I hereby certify that the information and attachments submitted with this closure report is ture, accurate and complete to the best of my knowledge and belief. I also certify that the closure complies with all applicable closure requirements and conditions specified in the approved closure plan. Name (Print): Signature: Date: e-mail address: Marie E. jaramillo@conocophillips.com Telephone: 505-326-9865 |

Form C-144

Oil Conservation Division

Page 5 of 5

Burlington Resources Oil Gas Company, LP San Juan Basin Closure Report

Lease Name: SAN JUAN 28-6 UNIT 166N

API No.: 30-039-30637

In accordance with Rule 19.15.17.13 NMAC the following information describes the closure of the temporary pit referenced above. All proper documentation regarding closure activities is being included with the C-144. The temporary pit for this location was constructed and location drilled before June 16, 2008 (effective date for Rule 19.15.17). While closure of the temporary pit did fall within the rule some dates for submittals are after the rig release date.

- Details on Capping and Covering, where applicable. (See report)
- Plot Plan (Pit Diagram) (Included as an attachment)
- Inspection Reports (Included as an attachment)
- Sampling Results (Included as an attachment)
- C-105 (Included as an attachment)
- Copy of Deed Notice will be filed with County Clerk (Not required on Federal, State, or Tribal land as stated by FAQ dated October 30, 2008)

General Plan:

1. All free standing liquids will be removed at the start of the pit closure process from the pit and disposed of in a division—approved facility or recycle, reuse or reclaim the liquids in a manner that the appropriate division district office approves.

All recovered liquids were disposed of at Basin Disposal (Permit #NM-01-005) and any sludge or soil required to be removed to facilitate closure was hauled to Envirotech Land Farm (Permit #NM-01-011) and JFJ Landfarm % IEI (Permit #NM-01-0010B).

2. The preferred method of closure for all temporary pits will be on-site burial, assuming that all the criteria listed in sub-section (B) of 19.15.17.13 are met.

The pit was closed using onsite burial.

3. The surface owner shall be notified of BR's closing of the temporary pit as per the approved closure plan using certified mail, return receipt requested.

The closure process notification to the landowner was sent via email. (See Attached)(Well located on Federal Land, certified mail is not required for Federal Land per BLM/OCD MOU.)

Within 6 months of the Rig Off status occurring BR will ensure that temporary pits are closed, re-contoured, and reseeded.

Provision 4 of the closure plan requirements were not met due to rig move off date as noted on C-105 which was prior to pit rule change. Burlington will ensure compliance with this rule in the future.

- 5. Notice of Closure will be given to the Aztec Division office between 72 hours and one week of closure via email, or verbally. The notification of closure will include the following:
 - i. Operator's name
 - ii. Location by Unit Letter, Section, Township, and Range. Well name and API number.

Notification is attached.

6. Liner of temporary pit shall be removed above "mud level" after stabilization. Removal of liner will consist of manually or mechanically cutting liner at mud level and removing all remaining liner. Care will be taken to remove "All" of the liner i.e., edges of liner entrenched or buried. All excessive liner will be disposed of at a licensed disposal facility.

Liner of temporary pit was removed above "mud level" after stabilization. Removal of the liner consisted of manually cutting liner at mud level and removing all remaining liner. Care was taken to remove "ALL" of the liner i.e., edges of liner entrenched or buried. All excessive liner was disposed of at a licensed disposal facility, (San Juan County Landfill).

7. Pit contents shall be mixed with non-waste containing, earthen material in order to achieve the solidification process. The solidification process will be accomplished using a combination of natural drying and mechanically mixing. Pit contents will be mixed with non-waste, earthen material to a consistency that is deemed a safe and stable. The mixing ratio shall not exceed 3 parts clean soil to 1 part pit contents.

Burlington mixed the Pit contents with non-waste containing, earthen material in order to achieve the solidification process. The solidification process was accomplished by using a combination of natural drying and mechanically mixing. Pit contents were mixed with non-waste, earthen material to a consistency that is deemed as safe and stable. The mixing ratio consisted of approximately 3 parts clean soil to 1 part pit contents.

8. A five point composite sample will be taken of the pit using sampling tools and all samples tested per Subsection B of 19.15.17.13(B)(1)(b). In the event that the criteria are not met, all contents will be handled per Subparagraph (a) of Paragraph (1) of Subsection B of 19.15.17.13 i.e., Dig and haul.

A five point composite sample was taken of the pit using sampling tools and all samples tested per Subsection B of 19.15.17.1 3(B)(1)(b). (Sample results attached).

| Components | Tests Method | Limit (mg/Kg) | Results |
|------------|---------------------------|---------------|------------|
| Benzene | EPA SW-846 8021B or 8260B | 0.2 | 1.7 ug/kg |
| BTEX | EPA SW-846 8021B or 8260B | 50 | 50.8 ug/kG |
| TPH | EPA SW-846 418.1 | 2500 | 382mg/kg |
| GRO/DRO | EPA SW-846 8015M | 500 | 150 mg/Kg |
| Chlorides | EPA 300.1 | 1000/500 | 403 mg/L |

9. Upon completion of solidification and testing standards being passed, the pit area will be backfilled with compacted, non-waste containing, earthen material. A minimum of four feet of cover shall be achieved and the cover shall include one foot of suitable material to establish vegetation at the site, or the background thickness of topsoil, whichever is greater. If standard testing fails BR will dig and haul all contents pursuant to 19.15.17.13.i.a. After doing such, confirmation sampling will be conducted to ensure a release has not occurred.

The pit material passed solidification and testing standards. The pit area was then backfilled with compacted, non-waste containing, earthen material. More than four feet of cover was achieved and the cover included one foot of suitable material to establish vegetation at the site.

10. During the stabilization process if the liner is ripped by equipment the Aztec OCD office will be notified within 48 hours and the liner will be repaired if possible. If the liner can not be repaired then all contents will be excavated and removed.

The integrity of the liner was not damaged in the pit closure process.

11. Dig and Haul Material will be transported to the Envirotech Land Farm located 16 miles south of Bloomfield on Angel Peak Road, CR 7175. Permit # NM010011

Dig and Haul was not required.

12. Re-contouring of location will match fit, shape, line, form and texture of the surrounding. Re-shaping will include drainage control, prevent ponding, and prevent erosion. Natural drainages will be unimpeded and water bars and/or silt traps will be place in areas where needed to prevent erosion on a large scale. Final recontour shall have a uniform appearance with smooth surface, fitting the natural landscape.

The pit area was re-contoured to match fit, shape, line, form and texture of the surrounding area. Re-shaping included drainage control, to prevent ponding and erosion. Natural drainages were unimpeded and water bars and/or silt traps were placed in areas where needed to prevent erosion on a large scale. Final recontour has a uniform appearance with smooth surface, fitting the natural landscape.

13. Notification will be sent to OCD when the reclaimed area is seeded.

Provision 13 was accomplished through complying with BLM seeding requirements as allowed by the BLM/OCD MOU.

14. BR shall seed the disturbed areas the first growing season after the operator closes the pit. Seeding will be accomplished via drilling on the contour whenever practical or by other division-approved methods. BLM or Forest Service stipulated seed mixes will used on federal lands. Vegetative cover will equal 70% of the native perennial vegetative cover (un-impacted) consisting of at least three native plant species, including at least one grass, but not including noxious weeds, and maintain that cover through two successive growing seasons. Repeat seeding or planting will be continued until successful vegetative growth occurs.

Provision 14 was accomplished through complying with BLM seeding requirements as allowed by the BLM/OCD MOU.

15. The temporary pit will be located with a steel marker, no less than four inches in diameter, cemented in a hole three feet deep in the center of the onsite burial upon the abandonment of all the wells on the pad. The marker will be flush with the ground to allow access of the active well pad and for safety concerns. The marker will include a threaded collar to be used for future abandonment. The top of the marker will contain a welded steel 12" square plate that indicates the onsite burial of the temporary pit. The plate will be easily removable and a four foot tall riser will be threaded into the top of the collar marker and welded around the base with the operator's information at the time of all wells on the pad are abandoned. The operator's information will include the following: Operator Name, Lease Name, Well Name and number, Unit Number, Section, Township, Range and an indicator that the marker is an onsite burial location.

Provision 15 was accomplished by installing a steel marker in the temporary pit, no less than four inches in diameter, cemented in a hole three feet deep in the center of the onsite burial. The marker is flush with the ground to allow access of the active well pad and for safety concerns. The top of the marker contains a welded steel 12" square plate that indicates the onsite burial of the temporary pit. The plate contains the following: Operator Name, Lease Name, Well Name and number, Unit Number, Section, Township, Range and an indicator that the marker is an onsite burial location.

The plate will be easily removable and a four foot tall riser will be threaded into the top of the collar marker and welded around the base with the following operator's information at the time of all wells on the pad are abandoned. The riser will be labeled: BR, BLM, SAN JUAN 28-6 UNIT 166N, UL-F, Sec. 1, T 27N, R 6W, API # 30-039-30637

Tally, Ethel

From:

Tally, Ethel

Sent:

Monday, January 19, 2009 3:46 PM 'mark_kelly@nm.blm.gov' SURFACE OWNER NOTIFICATION

To:

Subject:

The following location will have temporary pits that will be closed on-site.

San Juan 28-6 Unit 166N

Picase let Tamara Sessions (326-9834) or I know if you have any questions or concerns.

Ethel Tally ConccaPhillips-SJBU 3401 E. 30th Farmington Nat 57402 (\$05)599-5077 HAGAG Ethnu Telve Cone collidius com DISTRICT I 1825 N. French Dr., Hobbs, N.M. 88240

DISTRICT II 1301 West Grand Avenue, Artesia, N.M. 88210

DISTRICT III 1000 Rio Brazos Rd., Aztec, N.M. 87410

State of New Mexico
Energy, Minerals & Natural Resources Department

OIL CONSERVATION DIVISION 1220 South St. Francis Dr. Santa Fe, NM 87505

Form C Revised October 12, 2005

Submit to Appropriate District Office To

State Lease - 4 Copies Fee Lease - 3 Copies

☐ AMENDED REPORT


1220 S. St. Francis Dr., Santa Fe, NM 87505 WELL LOCATION AND ACREAGE DEDICATION PLAT

| ¹ API Number | 14 15.47 | ³ Pool Code | 1925 F 5 1 1 2 2 5 5 | 7. 7. 37.4 | ⁸ Pool Name | <u>an Tariffe (1941)</u> 1811 In North Agenta | The street and a street and the stre |
|-------------------------|----------|------------------------|------------------------------------|------------|------------------------|--|--|
| | | | | BASIN | DAKOTA/BLAN | | ERDE |
| *Property Code | | SAN J | ⁶ Property JUAN 28 — | | | | Well Number |
| TOGRID No. | | BURLINGTON RESC | *Operator OURCES OIL | | W LP | | Elevation 6523' |


Surface Location UL or lot no. Section Range Feet from the Lot Idn North/South line Feet from the East/West line County F, -1 27-N 6-W 1605 NORTH 2495 WEST RIO ARRIBA ¹¹ Bottom Hole Location If Different From Surface UL or lot no. Section Township Range Lot Idn Feet from the North/South line Feet from the East/West line County

⁸ Dedicated Acres Joint or Infill Consolidation Code 15 Order No DK 320.32 ACRES W/2 MV 320.32 ACRES W/2

NO ALLOWABLE WILL BE ASSIGNED TO THIS COMPLETION UNTIL ALL INTERESTS HAVE BEEN CONSOLIDATED OR A NON-STANDARD UNIT HAS BEEN APPROVED BY THE DIVISION



SECTION 1, T-27-N, R-6-W, NMPM, RIO ARRIBA COUNTY, NM BURLINGTON RESOURCES OIL & GAS COMPANY LP SAN JUAN 28-6 UNIT #166N, 1605' FNL & 2495' FWL



,09 ,0

30

0

THE STATE OF THE S Scale: 1'' = 60'

RESERVE PIT DIKE; TO BE 8' ABOVE DEEP SIDE (OVERFLOW -- 3' WIDE AND 1' ABOVE SHALLOW SIDE)



EPA METHOD 8015 Modified Nonhalogenated Volatile Organics Total Petroleum Hydrocarbons

| Client: | ConocoPhillips | Project #: | 96052-0026 |
|----------------------|----------------|---------------------|------------|
| Sample ID: | Reserve Pit | Date Reported: | 04-22-10 |
| Laboratory Number: | 53764 | Date Sampled: | 04-19-10 |
| Chain of Custody No: | 8951 | Date Received: | 04-19-10 |
| Sample Matrix: | Soil | Date Extracted: | 04-20-10 |
| Preservative: | Cool | Date Analyzed: | 04-21-10 |
| Condition: | Intact | Analysis Requested: | 8015 TPH |

| Parameter | Concentration (mg/Kg) | Det. Limit (mg/Kg) | |
|------------------------------|--------------------------|--------------------------|--|
| Gasoline Range (C5 - C10) | 40.9 | 0.2 | |
| Diesel Range (C10 - C28) | 109 | 0.1 | |
| Total Petroleum Hydrocarbons | 150 | 0.2 | |

ND - Parameter not detected at the stated detection limit.

References:

Method 8015B, Nonhalogenated Volatile Organics, Test Methods for Evaluating Solid Waste,

SW-846, USEPA, December 1996.

Comments:

San Juan 28-6 Unit 166N

Analyst

Beview

Ph (505) 632-0615 Fr (800) 362-1879 Fx (505) 632-1865 lab@envirotech-inc.com envirotech-inc.com



EPA METHOD 8015 Modified Nonhalogenated Volatile Organics Total Petroleum Hydrocarbons

| Client: | ConocoPhillips | Project #: | 96052-0026 |
|----------------------|----------------|---------------------|-------------------|
| Sample ID: | Background | Date Reported: | 04-22-10 |
| Laboratory Number: | 53765 | Date Sampled: | 04-19-10 |
| Chain of Custody No: | 8951 | Date Received: | 04-19 - 10 |
| Sample Matrix: | Soil | Date Extracted: | 04-20-10 |
| Preservative: | Cool | Date Analyzed: | 04-21-10 |
| Condition: | Intact | Analysis Requested: | 8015 TPH |

| Parameter | Concentration (mg/Kg) | Det. Limit (mg/Kg) |
|------------------------------|--------------------------|--------------------------|
| Gasoline Range (C5 - C10) | ND | 0.2 |
| Diesel Range (C10 - C28) | ND | 0.1 |
| Total Petroleum Hydrocarbons | ND | 0.2 |

ND - Parameter not detected at the stated detection limit.

References:

Method 8015B, Nonhalogenated Volatile Organics, Test Methods for Evaluating Solid Waste,

SW-846, USEPA, December 1996.

Comments:

San Juan 28-6 Unit 166N

Analyst

Review

Ph (505) 632-0615 Fr (800) 362-1879 Fx (505) 632-1865 lab@envirotech-inc.com envirotech-inc.com



EPA Method 8015 Modified Nonhalogenated Volatile Organics Total Petroleum Hydrocarbons

Quality Assurance Report

| Client: | QA/QC | | Project #: | | N/A |
|------------------------------|-----------------|------------------|-----------------|--------------|-------------------|
| Sample ID: | 04-21-10 QA/0 | QC . | Date Reported: | | 04-22-10 |
| Laboratory Number: | 53736 | | Date Sampled: | | N/A |
| Sample Matrix: | Methylene Chlor | ide | Date Received: | | N/A |
| Preservative: | N/A | | Date Analyzed: | | 04-21-10 |
| Condition: | N/A | | Analysis Reques | ted: | TPH |
| | LCal Date | i cathe | C-ColeRS | % Difference | Accept Range |
| Gasoline Range C5 - C10 | 05-07-07 | 1.0949E+003 | 1.0953E+003 | 0.04% | 0 - 15% |
| Diesel Range C10 - C28 | 05-07-07 | 1.1777E+003 | 1.1781E+003 | 0.04% | 0 - 15% |
| - | | | | | |
| Blank Conc. (mg/Lemg/kg) | 医黑线性肠炎 | - Concernation | | Detection Em | |
| Gasoline Range C5 - C10 | | ND | | 0.2 | |
| Diesel Range C10 - C28 | | ND | | 0.1 | |
| Total Petroleum Hydrocarbons | | ND | | 0.2 | |
| Duplicate Conc. (mg/Kg) | Samble | <u>Diplicate</u> | %ionterance | Accept Range | |
| Gasoline Range C5 - C10 | 213 | 212 | 0.6% | 0 - 30% | tial |
| Diesel Range C10 - C28 | 446 | 444 | 0.6% | 0 - 30% | |
| Spike Conc. (mg/Kg) | s sa Seinigers | | Solke Result | % Receivery | Accept Range |
| Gasoline Range C5 - C10 | 213 | 250 | 525 | 113% | 75 - 125% |
| Diesel Range C10 - C28 | 446 | 250 | 670 | 96.2% | 75 - 12 5% |
| | | | | | |

ND - Parameter not detected at the stated detection limit.

References:

Method 8015B, Nonhalogenated Volatile Organics, Test Methods for Evaluating Solid Waste,

SW-846, USEPA, December 1996.

Comments:

QA/QC for Samples 53736, 53738, 53740, 53742, 73744, 73746, 73748, 73753, 73764, 73765



EPA METHOD 8021 AROMATIC VOLATILE ORGANICS

| Client: | ConocoPhillips | Project #: | 96052-0026 |
|--------------------|----------------|---------------------|------------|
| Sample ID: | Reserve Pit | Date Reported: | 04-22-10 |
| Laboratory Number: | 53764 | Date Sampled: | 04-19-10 |
| Chain of Custody: | 8951 | Date Received: | 04-19-10 |
| Sample Matrix: | Soil | Date Analyzed: | 04-21-10 |
| Preservative: | Cool | Date Extracted: | 04-20-10 |
| Condition: | Intact | Analysis Requested: | BTEX |

| Parameter | Concentration (ug/Kg) | Det. Limit (ug/Kg) | |
|--------------|--------------------------|--------------------------|--|
| | | | |
| Benzene | 1.7 | 0.9 | |
| Toluene | 12.8 | 1.0 | |
| Ethylbenzene | 2.5 | 1.0 | |
| p,m-Xylene | 31.9 | 1.2 | |
| o-Xylene | 1.9 | 0.9 | |
| Total BTEX | 50.8 | | |

ND - Parameter not detected at the stated detection limit.

| Surrogate Recoveries: | Parameter | Percent Recovery |
|-----------------------|---------------------|------------------|
| | Fluorobenzene | 91.0 % |
| | 1,4-difluorobenzene | 99.0 % |
| | Bromochlorobenzene | 94.0 % |

References:

Method 5030B, Purge-and-Trap, Test Methods for Evaluating Solid Waste, SW-846, USEPA,

December 1996.

Method 8021B, Aromatic Volatile Organics, Test Methods for Evaluating Solid Waste, SW-846,

USEPA, December 1996.

Comments:

San Juan 28-6 Unit 166N

Analyst

Mustin M Wolles



EPA METHOD 8021 AROMATIC VOLATILE ORGANICS

| Client: | ConocoPhillips | Project #: | 96052-0026 |
|--------------------|----------------|---------------------|------------|
| Sample ID: | Background | Date Reported: | 04-22-10 |
| Laboratory Number: | 53765 | Date Sampled: | 04-19-10 |
| Chain of Custody: | 8951 | Date Received: | 04-19-10 |
| Sample Matrix: | Soil | Date Analyzed: | 04-21-10 |
| Preservative: | Cool | Date Extracted: | 04-20-10 |
| Condition: | Intact | Analysis Requested: | BTEX |

| Parameter | Concentration (ug/Kg) | Det. Limit (ug/Kg) | |
|--------------|--------------------------|--------------------------|--|
| _ | | | |
| Benzene | ND | 0.9 | |
| Toluene | ND | 1.0 | |
| Ethylbenzene | ND | 1.0 | |
| p,m-Xylene | ND | 1.2 | |
| o-Xylene | ND | 0.9 | |
| Total BTEX | ND | | |

ND - Parameter not detected at the stated detection limit.

| Surrogate Recoveries: | Parameter | Percent Recovery | | |
|-----------------------|---------------------|------------------|--|--|
| | Fluorobenzene | 93.0 % | | |
| | 1,4-difluorobenzene | 99.5 % | | |
| | Bromochlorobenzene | 97.0 % | | |

References:

Method 5030B, Purge-and-Trap, Test Methods for Evaluating Solid Waste, SW-846, USEPA,

December 1996.

Method 8021B, Aromatic Volatile Organics, Test Methods for Evaluating Solid Waste, SW-846,

USEPA, December 1996.

Comments:

San Juan 28-6 Unit 166N

Analyst

Review



EPA METHOD 8021 AROMATIC VOLATILE ORGANICS

| Project #: | N/A |
|----------------|--|
| Date Reported: | 04-22-10 |
| Date Sampled: | N/A |
| Date Received: | N/A |
| Date Analyzed: | 04-21-10 |
| Analysis: | BTEX |
| | Date Reported: Date Sampled: Date Received: Date Analyzed: |

| Calibration and Detection Limits (ug/L) | / LICARE | G Oalige Accept Fan | 19/40)ft # 1 18 0 - 15% | Blank Cond | Detect Plimit |
|---|-------------|------------------------|----------------------------|---------------|------------------|
| Benzene | 1.6392E+006 | 1.6425E+006 | 0.2% | ND | 0.1 |
| Toluene | 1.1398E+006 | 1.1420E+006 | 0.2% | ND | 0.1 |
| Ethylbenzene | 9.5819E+005 | 9.6011E+005 | 0.2% | ND | 0.1 |
| p,m-Xylene | 1.8888E+006 | 1.8926E+006 | 0.2% | ND | 0.1 |
| o-Xylene | 6.1648E+005 | 6.1772E+005 | 0.2% | ND | 0.1 |

| Duplicate/Conc.(ug/Kg) | Semiles Page in | (Pilesite | - 2/60/AV | //coepulkanae | Detect Limit |
|------------------------|-----------------|-----------|-----------|---------------|--------------|
| Benzene | 4.8 | 4.8 | 0.0% | 0 - 30% | 0.9 |
| Toluene | 188 | 187 | 0.2% | 0 - 30% | 1.0 |
| Ethylbenzene | 3.6 | 3.6 | 0.0% | 0 - 30% | 1.0 |
| p,m-Xylene | 72.0 | 71.8 | 0.3% | 0 - 30% | 1.2 |
| o-Xylene | 4.2 | 4.2 | 0.0% | 0 - 30% | 0.9 |

| Spike Conc (ug/kg) | Sample) VAnic | ina Galkeá a Salk | (deSample) | % Recovery | Accept Range |
|--------------------|---------------|-------------------|------------|------------|--------------|
| Benzene | 4.8 | 50.0 | 51.4 | 93.8% | 39 - 150 |
| Toluene | 188 | 50.0 | 234 | 98.4% | 46 - 148 |
| Ethylbenzene | 3.6 | 50.0 | 51.2 | 95.5% | 32 - 160 |
| p,m-Xylene | 72.0 | 100 | 167 | 97.0% | 46 - 148 |
| o-Xylene | 4.2 | 50.0 | 52.1 | 96.1% | 46 - 148 |

ND - Parameter not detected at the stated detection limit.

References:

Method 5030B, Purge-and-Trap, Test Methods for Evaluating Solid Waste, SW-846, USEPA,

December 1996.

Method 8021B, Aromatic and Halogenated Volatiles by Gas Chromatography Using

Photoionization and/or Electrolytic Conductivity Detectors, SW-846, USEPA December 1996.

Comments:

QA/QC for Samples 53736, 53738, 53740, 53742, 73744, 73746, 73748, 73753, 73764, 73765

Analyst

EPA METHOD 418.1 TOTAL PETROLEUM HYDROCARBONS

| Client: | ConocoPhillips | Project #: | 96052-0026 |
|----------------------|----------------|------------------|------------|
| Sample ID: | Reserve Pit | Date Reported: | 04-22-10 |
| Laboratory Number: | 53764 | Date Sampled: | 04-19-10 |
| Chain of Custody No: | 8951 | Date Received: | 04-19-10 |
| Sample Matrix: | Soil | Date Extracted: | 04-21-10 |
| Preservative: | Cool | Date Analyzed: | 04-21-10 |
| Condition: | Intact | Analysis Needed: | TPH-418.1 |

| | | Det. |
|-----------|---------------|---------|
| | Concentration | Limit |
| Parameter | (mg/kg) | (mg/kg) |

Total Petroleum Hydrocarbons

382

22.2

ND = Parameter not detected at the stated detection limit.

References:

Method 418.1, Petroleum Hydrocarbons, Total Recoverable, Chemical Analysis of Water

and Waste, USEPA Storet No. 4551, 1978.

Comments:

San Juan 28-6 Unit 166N

Analyst

Review

EPA METHOD 418.1 TOTAL PETROLEUM HYDROCARBONS

| Client: | ConocoPhillips | Project #: | 96052-0026 |
|----------------------|----------------|------------------|------------|
| Sample ID: | Background | Date Reported: | 04-22-10 |
| Laboratory Number: | 53765 | Date Sampled: | 04-19-10 |
| Chain of Custody No: | 8951 | Date Received: | 04-19-10 |
| Sample Matrix: | Soil | Date Extracted: | 04-21-10 |
| Preservative: | Cool | Date Analyzed: | 04-21-10 |
| Condition: | Intact | Analysis Needed: | TPH-418.1 |

| | | Det. |
|-----------|---------------|---------|
| | Concentration | Limit |
| Parameter | (mg/kg) | (mg/kg) |

Total Petroleum Hydrocarbons

24.7

22.2

ND = Parameter not detected at the stated detection limit.

References:

Method 418.1, Petroleum Hydrocarbons, Total Recoverable, Chemical Analysis of Water

and Waste, USEPA Storet No. 4551, 1978.

Comments:

San Juan 28-6 Unit 166N

Anaivst

Review



EPA METHOD 418.1 TOTAL PETROLEUM HYROCARBONS QUALITY ASSURANCE REPORT

Client:

QA/QC

Project #:

N/A

Sample ID:

QA/QC

Date Reported:

04-22-10

Laboratory Number:

04-21-TPH.QA/QC 53764

N/A

Sample Matrix:

Freon-113

Date Sampled: Date Analyzed:

Preservative:

Date Extracted:

04-21-10 04-21-10

Condition:

N/A N/A

Analysis Needed:

TPH

Calibration

I-Cal Date 04-05-10

C-Cal Date I-Cal RF: 04-21-10

1,540

1,470

4.5% +/- 10%

TPH

Concentration ND

Detection Limit 22.2

Duplicate Conc. (mg/Kg)

Sample: Duplicate % Difference Accept. Range

TPH

24.7

29.6

19.8%

+/- 30%

Spike Conc. (mg/Kg) Sample **TPH**

24.7

Spike Added Spike Result % Recovery 2,000

1,850

91.4%

Accept Range 80 - 120%

ND = Parameter not detected at the stated detection limit.

References:

Method 418.1, Petroleum Hydrocarbons, Total Recoverable, Chemical Analysis of Water

and Waste, USEPA Storet No. 4551, 1978.

Comments:

QA/QC for Samples 53764 - 53765.

Mustum Westers



Chloride

| Client: | ConocoPhillips | Project #: | 96052-0026 |
|----------------|----------------|-------------------|------------|
| Sample ID: | Reserve Pit | Date Reported: | 04-22-10 |
| Lab ID#: | 53764 | Date Sampled: | 04-19-10 |
| Sample Matrix: | Soil | Date Received: | 04-19-10 |
| Preservative: | Cool | Date Analyzed: | 04-21-10 |
| Condition: | Intact | Chain of Custody: | 8951 |

Parameter

Concentration (mg/Kg)

Total Chloride

403

Reference:

U.S.E.P.A., 4500B, "Methods for Chemical Analysis of Water and Wastes", 1983.

Standard Methods For The Examination of Water And Waste Water", 18th ed., 1992.

Comments:

San Juan 28-6 Unit 166N

Analyst



Chloride

Client: ConocoPhillips Project #: 96052-0026 04-22-10 Sample ID: Background Date Reported: Lab ID#: 53765 Date Sampled: 04-19-10 Soil Sample Matrix: Date Received: 04-19-10 Preservative: Cool Date Analyzed: 04-21-10 Condition: Chain of Custody: Intact 8951

Parameter

Concentration (mg/Kg)

Total Chloride

10

Reference:

U.S.E.P.A., 4500B, "Methods for Chemical Analysis of Water and Wastes", 1983. Standard Methods For The Examination of Water And Waste Water", 18th ed., 1992.

Comments:

San Juan 28-6 Unit 166N

Analyst

<u>Printine</u> M Walters
Review

| Submit To Appropri | nate Distric | et Office | | State of New Mexico | | | | | | | Form C-105 | | | | | | |
|---|---|-----------------------|----------------------------|--|-----------------|------------------------------------|--|--------------|-----------------------|----------------|--|----------|--------------|-----------------------|-----------|---|--|
| District I 1625 N. French Dr. | , Hobbs, N | M 88240 | | Energy, Minerals and Natural Resources | | | | | | | July 17, 2008 1. WELL API NO. | | | | | | |
| District II 1301 W. Grand Ave | | , | | Oil Conservation Division | | | | | | | 30-039-30637 | | | | | | |
| District III | | | | | | | | | | | 2. Type of Lea | | | | | | |
| 1000 Rio Brazos Ro District IV | d., Aztec, N | NM 87410 | | 1220 South St. Francis Dr. Santa Fe, NM 87505 | | | | | | | ☐ STATE ☐ FEE ☒ FED/INDIAN 3. State Oil & Gas Lease No. | | | | | | |
| 1220 S. St. Francis | Dr., Santa | Fe, NM 87505 | | | | Santa Fe, I | NM | 87505 | | | 3. State Oil & SF-073963 | Gas | Lease No | • | | | |
| WELL (| | LETION | OR R | ECO | MPL | ETION RE | POF | RT ANI | LOG | | 5. Lease Name | I | mit A ano | According 196,966 | 110 | | |
| | _ | | | | | | | | | | SAN JUAN | | | | iiic | | |
| ☐ COMPLETI | COMPLETION REPORT (Fill in boxes #1 through #31 for State and Fee wells only) | | | | | | | | | 6. Well Number | | | | | | | |
| C-144 CLOS #33; attach this at | nd the pla | | | | | | | | | l/or | 166N | | | | | | |
| Type of Comp NEW V | |] workov | ′ER □ | DEEPE | NING | □PLUGBACI | к 🗆 | DIFFERE | NT RESERV | /OIR | R OTHER | | | | | | |
| 8. Name of Opera | tor | | | | | | | | | | 9. OGRID | | | | | *************************************** | |
| Burlington R 10. Address of O | | es Oil Ga | s Com | pany, | LP | | | | | | 14538 | 337 | 11 | | | | |
| PO Box 4298, Fa | | , NM 87499 | | | | | | | | | 11. Foot name | OI W | ilucai | | | | |
| 12.Location Surface: | Unit Ltr | Section | ı | Towns | hip | Range | Lot | | Feet from | the | N/S Line | Feet | from the | E/W I | ine | County | |
| BH: | | | | | | | ├ | | | | | | | | | | |
| 13. Date Spudded | 1 14. D | ate T.D. Rea | ched | 15. E | | Released | <u> </u> | 16 | Date Comp | leted | (Ready to Produ | ice) | | 7. Elevat T, GR, e | | and RKB, | |
| 18. Total Measur | ed Depth | of Well | | | | ck Measured Dep | pth | 20 | Was Direct | tiona | al Survey Made? | | | · · | | her Logs Run | |
| 22. Producing Int | erval(s), o | of this compl | etion - T | op, Bot | tom, N | ame | | | | | T | | | , i. . | | | |
| 22 | · | | | | CAS | INC DEC | ΩD | D (Pan | owt all at | | as set in xxx | 111 | | | | | |
| CASING SI | ZE. | WEIGH | IT LB./F | | CAS | DEPTH SET | UK | | OLE SIZE | rmį | gs set in we | | CORD | AN | MOUNT | PULLED | |
| 02151110 51 | | WEIGH | | <u></u> | | DEI III SEI | | | JEE SIEE | | CENTERVIEW | , KL | CORD | 711 | 100111 | TOLLED | |
| | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | ļ | | | | | | |
| 24. | | | | | LIN | ER RECORD | <u>.</u> | | | 25. | T | IRIN | NG REC | ORD | | | |
| SIZE | TOP | | BOT | ТОМ | Dire | SACKS CEM | ENT | SCREE | V | SIZ | | | EPTH SET | | PACKI | ER SET | |
| | | · | | | | | | | | L_ | | | | | | | |
| 26 Porforation | rooped (is | -ta-val aina | | b) | | | | 27. 46 | ID GHOT | <u></u> | A COTURE OF | (5) | TT. COLU | CEZE 1 | CTC. | | |
| 26. Perforation | recora (11 | ntervai, size, | and num | ber) | | | | | ID, SHOT, INTERVAL | | ACTURE, CENTANT AND AMOUNT AND | | | | | | |
| | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | |
| | | | | | | | | 1 | | | | | | | | | |
| 28. | | | D 1 4 | N (1 | 1 (5) | | | <u>ODUC</u> | | | I ny n o | <u> </u> | | | | | |
| Date First Produc | шоп | | Productio | on Metr | ioa (<i>Fu</i> | owing, gas lift, p | umpin | ig - Size an | a type pump, | , | Well Status | (Prod | i. or Snui- | -in) | | | |
| Date of Test | Hours | Tested | Chol | e Size | | Prod'n For Test Period | _ | Oil - Bb | ı | Gas | as - MCF | | Water - Bbl. | | Gas - C | il Ratio | |
| Flow Tubing | Casin | g Pressure | Calc | ulated 2 | 4- | Oil - Bbl. | | Gae | - MCF | | Water - Bbl. | <u> </u> | Oil Gra | vity - Al | PI - (Cor | r.) | |
| Press. | | 5 1 1 cooda. c | | Rate | • | | | | MOI | | Water Box. | | 0 | 11. | 1 (007) | ., | |
| 29. Disposition of | Gas (Soi | d, used for fi | iel, vente | d, etc.) | | | ~ | L | | | | 30. 1 | est Witne | ssed By | | | |
| 31. List Attachme | ents | | | | | | | | | | L | | | | | | |
| 32. If a temporary | pit was u | used at the w | ell, attac | h a plat | with th | e location of the | tempe | orary pit. | | | | | | | | | |
| 33. If an on-site b | urial was | - 1 | · 7 | | | | | | 71027 1 | 002 | | | | | | | |
| I hereby cerțij | fy that ti | tatitud he informa | e 36.600 tion sh | gwn o | n boti | ngitude 107.418 h sides of this | forn | n is true | and compl | ete lete | to the best of | my | knowled | lge and | d belief | | |
| Signature | 1/1/1/ | M nu | WI | | Pri | | - | | _ | | Legulatory Te | - | | : 6/18/ | _ | | |
| E-mail Addre | ss mari | e.e.jaramil | lo@co | nocop | | | | | | | | | | | | | |
| | | $\sqrt{}$ | | | | | | | | | | | | | | | |

ConocoPhillips

| Pit Closure Form: | | , |
|-------------------------|--|-----------------|
| Date: 5-7-10 | | |
| Well Name: ST 28 | 5-6 166N | _ |
| Footages: 1605 F | NL, 2495 FWL | Unit Letter: _F |
| Section:, T | N, R- <u>06</u> -W, County: <u>&</u> | Annua State: MM |
| Contractor Closing Pit: | AZTEC EXCAVATION | |
| | | 5-7-10 |
| Construction Inspector: | JARED CHAVEZ | Date: |
| Inspector Signature: | 1 | |
| | | |

Jaramillo, Marie E

From: Sent:

Payne, Wendy F

Friday, April 30, 2010 3:00 PM

To:

'brook@crossfire-llc.com'; GRP:SJBU Regulatory; 'Isaiah Lee'; 'tevans48@msn.com'; (bko@digii.net); Mark Kelly; Robert Switzer; Sherrie Landon; Bassing, Kendal R.; Chavez, Virgil E; Elmer Perry; Faver Norman; Fred Martinez; Jared Chavez; Lowe, Terry; Payne, Wendy F; Silverman, Jason M; Spearman, Bobby E; 'Steve McGlasson'; Tally, Ethel; Becker, Joey W; Bowker, Terry D; Gordon Chenault; GRP:SJBU Production Leads; Hockett, Christy R; Johnson, Kirk L; Bassing, Kendal R.; Kennedy, Jim R; Lopez, Richard A; O'Nan, Mike J. Peace, James T; Pierce, Richard M; Poulson, Mark E; Smith, Randall O; Spearman, Bobby E; Stamets, Steve A; Thacker, LARRY; Work, Jim A; Blair, Maxwell O; Blakley, Mac; Clark, Joni E; Farrell, Juanita R; Gillette, Steven L (Gray Surface Specialties and Consulting, Ltd.); Greer,

David A; Hines, Derek J (Finney Land Co.); Maxwell, Mary Alice; McWilliams, Peggy L;

Seabolt, Elmo F; Stallsmith, Mark R

Cc:

'Aztec Excavation'

Subject:

Reclamation Notice: San Juan 28-6 Unit 166N

Attachments:

San Juan 28-6 Unit 166N.pdf

Aztec Excavation will move a tractor to the **San Juan 28-6 Unit 166N** to start the reclamation process on Thursday, May 6th, 2010. Please contact Jared Chavez (793-7912) if you have questions or need further assistance. Driving Directions are attached.



San Juan 28-6 Unit 166N.pdf (2...

Burlington Resources Well- Network #: 10234740 - D250 = reclamation/seeding & D260 = pit closure

Rio Arriba County, NM

SAN JUAN 28-6 UNIT 166N BLM surface / BLM minerals

Twin: n/a

1605' FNL, 2495' FWL

SEC.1, T27N, R06W

Unit Letter 'F'

Lease #: USA SF-079363

Latitude: 36° 36 min 21.98880sec N (NAD 83)

Longitude: 107° 25 min 07.41720 sec W (NAD83)

Total Acres Disturbed: 3.03 acres

Access Road: 197.07'

API #: 30-039-30637


Wendy Payne
ConocoPhillips-SJBU
505-326-9533
Wendy.F.Payne@conocophillips.com

ConocoPhillips


| Reclamation Form: | |
|----------------------------|---|
| Date: <u>6/8/10</u> | _ |
| Well Name: <u>くっ ス8・</u> G | 166N |
| Footages: 1605 FNU | J 2495 FWL Unit Letter: F |
| Section:/, T- <u>27</u> -N | I, R- <u>oc</u> -W, County: <u>Ro Arriba</u> State: <u>NM</u> |
| Reclamation Contractor: _ | AZTEC EXCAVATION |
| Reclamation Date: | 5/18/10 |
| Road Completion Date: | 5/20/10 |
| Seeding Date: | 5/24/10 |
| | |
| **PIT MAKER STATUS (WI | nen Required): |
| MARKER PLACED : | 5/20/10 (DATE) |
| LATATUDE: N36 | . 606297 |
| LONGITUDE: W/C | 7.418823 |
| | |
| Construction Inspector: _ | JARED CHAVEZ Date: 6/8/10 |
| Inspector Signature: | 12 |
| | |
| R1 N | 1/2 |

BLM/BLM









WELL PAD SAFETY AND ENVIRONMENTAL CHECK LIST

WELL NAME: SAN JUAN 28-6 UNIT 166N

API#: 30-039-30637

| COMMENTS | LOCATION LOOKS GOOD. JEG | | LOCATION ROAD HAS BEEN BLADED STILL HAS SNOW | LOCATION ROAD HAS BEEN BLADED STILL HAS SNOW | LOCATION STILL HAS SNOW | ROAD AND LOCATION RUTTED, SIGN ON LOCATION | ROAD AND LOCATION RUTTED; SIGN ON LOCATION | SIGN ON LOCATION, LOCATION NEEDS BLADED | | SIGN ON LOCATION; CULVERT PLUGGED | SIGN ON LOCATION; CULVERT PLUGGED |
|-------------------|--------------------------|-----------------|--|--|-------------------------|--|--|---|----------------|-----------------------------------|-----------------------------------|
| PICTURES TAKEN | × | × | × | × | × | × | × | × | | | |
| LOCATION | × | × | × | × | × | × | × | × | × | × | × |
| SAFETY | × | | | | | × | × | × | × | × | × |
| INSPECTOR | JARED CHAVEZ | NORMAN FAVER | NORMAN FAVER | NORMAN FAVER | NORMAN FAVER | ELMER PERRY | ELMER PERRY | ELMER PERRY | ELMER PERRY | ELMER PERRY | ELMER PERRY |
| DATE | 11/24/09 | 01/08/09 | 02/15/09 | 02/24/09 | 02/26/09 | 03/23/10 | 03/30/10 | 04/08/10 | 04/19/10 | 04/23/10 | 05/03/10 |