1625 N. French Dr., Hobbs, NM 88240

District II

1301 W. Grand Ave., Artesia, NM 88210

District III

1000 Rio Brazos Rd., Aztec, NM 87410

District IV

1220 S. St. Francis Dr., Santa Fe, NM 87505

State of New Mexico **Energy Minerals and Natural Resources**

Department Oil Conservation Division 1220 South St. Francis Dr. Santa Fe, NM 87505

July 21, 2008 For temporary pits, closed-loop sytems, and below-grade

Form C-144

tanks, submit to the appropriate NMOCD District Office.

For permanent pits and exceptions submit to the Santa Fe Environmental Bureau office and provide a copy to the appropriate NMOCD District Office.

5	١	81	-1
	•	•	1

Pit, Closed-Loop System, Below-Grade Tank, or Proposed Alternative Method Permit or Closure Plan Application

Type of action:	Permit of a pit, closed-loop system, below-grade tank, or proposed alternative method
	X Closure of a pit, closed-loop system, below-grade tank, or proposed alternative method
	Modification to an existing permit
	Closure plan only submitted for an existing permitted or non-permitted pit, closed-loop system, below-grade tank, or proposed alternative method

Instructions: Please submit one application (Form C-144) per individual pit, closed-loop system, below-grade tank or alternative request

environ	•••	perator of its responsibility to comply	= =	=	-	
perator: Burl	lington Resources Oil & Ga	is Company, LP		OGRID#: <u>14</u> :	538	
ddress: P.O.	. Box 4289, Farmington, N	M 87499				
acility or well	name: NEW MEXICO B	COM 100				
API Number: _	30-045-	34627	OCD Permit Nun	nber:		
J/L or Qtr/Qtr:	D(NW/NW) Section:	16 Township: 29N	Range:	11W County	: San Juan	
Center of Propo	osed Design: Latitude:	36.73074 °N	Longitude:	108.00324	<u>°W</u> NAD: □] 1927 X] 1983
urface Owner:	Federal X		ribal Trust or Inc			
X Pit: Subset Temporary: Permanent X Lined	ection F or G of 19.15.17.11 NN X Drilling Workover Emergency Cavitation Unlined Liner type	on P&A	hor was don 2/2	SALM. Hed ON	. 1/28/11	
X String-Rein	forced					!
Liner Seams:	X Welded X Factory	Other	Volume: 44	00 bbl Dimensio	ns L <u>65'</u> x W <u>4</u>	5' x D 10'
Closed-I Type of Operat Drying P Lined [Liner Seams:	tion: P&A Drilli	notice of int	Ų (II	to activities which re	Other Other	6678910772 A RECEIVEL
Volume: Tank Construc Secondary	containment with leak detection idewalls and liner	Type of fluid:	ther	utomatic overflow sh	nt-off	L CONS. DIV. DIST.
	tive Method: n exception request is required.	Exceptions must be submitted to	the Santa Fe Envir	ronmental Bureau offi	ce for consideration o	f approval.

Fencing: Subsection D of 19.15.17.11 NMAC (Applies to permanent pit, temporary pits, and below-grade tanks) Chain link, six feet in height, two strands of barbed wire at top (Required if located within 1000 feet of a permanent residence, school, hospital, institution or church) Four foot height, four strands of barbed wire evenly spaced between one and four feet Alternate. Please specify				
Netting: Subsection E of 19.15.17.11 NMAC (Applies to permanent pits and permanent open top tanks) Screen Netting Other Monthly inspections (If netting or screening is not physically feasible)				
Signs: Subsection C of 19.15.17.11 NMAC 12" X 24", 2" lettering, providing Operator's name, site location, and emergency telephone numbers X Signed in compliance with 19.15.3.103 NMAC				
Administrative Approvals and Exceptions: Justifications and/or demonstrations of equivalency are required. Please refer to 19.15.17 NMAC for guidance. Please check a box if one or more of the following is requested, if not leave blank: Administrative approval(s): Requests must be submitted to the appropriate division district of the Santa Fe Environmental Bureau office for consiteration (Fencing/BGT Liner) Exception(s): Requests must be submitted to the Santa Fe Environmental Bureau office for consideration of approval.	deration of ap	proval.		
Siting Criteria (regarding permitting): 19.15.17.10 NMAC Instructions: The applicant must demonstrate compliance for each siting criteria below in the application. Recommendations of acceptable source material are provided below. Requests regarding changes to certain siting criteria may require administrative approval from the appropriate district office or may be considered an exception which must be submitted to the Santa Fe Environmental Bureau Office for consideration of approval. Applicant must attach justification for request. Please refer to 19.15.17.10 NMAC for guidance. Siting criteria does not apply to drying pads or above grade-tanks associated with a closed-loop system.				
Ground water is less than 50 feet below the bottom of the temporary pit, permanent pit, or below-grade tank. - NM Office of the State Engineer - iWATERS database search; USGS; Data obtained from nearby wells	Yes	No		
Within 300 feet of a continuously flowing watercourse, or 200 feet of any other watercourse, lakebed, sinkhole, or playa lake (measured from the ordinary high-water mark). - Topographic map; Visual inspection (certification) of the proposed site	Yes	No		
Within 300 feet from a permanent residence, school, hospital, institution, or church in existence at the time of initial application.	Yes	No		
(Applies to temporary, emergency, or cavitation pits and below-grade tanks) - Visual inspection (certification) of the proposed site; Aerial photo; Satellite image	NA			
Within 1000 feet from a permanent residence, school, hospital, institution, or church in existence at the time of initial application. (Applied to permanent pits)	Yes	No		
 Visual inspection (certification) of the proposed site; Aerial photo; Satellite image Within 500 horizonal feet of a private, domestic fresh water well or spring that less than five households use for domestic or stock watering purposes, or within 1000 horizontal feet of any other fresh water well or spring, in existence at the time of initial application. 	Yes	□No		
 NM Office of the State Engineer - iWATERS database search; Visual inspection (certification) of the proposed site. Within incorporated municipal boundaries or within a defined municipal fresh water well field covered under a municipal ordinance adopted pursuant to NMSA 1978, Section 3-27-3, as amended Written confirmation or verification from the municipality; Written approval obtained from the municipality 	Yes	No		
Within 500 feet of a wetland. - US Fish and Wildlife Wetland Identification map; Topographic map; Visual inspection (certification) of the proposed site	Yes	No		
Within the area overlying a subsurface mine. - Written confirmation or verification or map from the NM EMNRD - Mining and Mineral Division	Yes	□No		
 Within an unstable area. Engineering measures incorporated into the design; NM Bureau of Geology & Mineral Resources; USGS; NM Geological Society; Topographic map 	Yes	∐No		
Within a 100-year floodplain - FEMA map	Yes	No		

Temporary Pits, Emergency Pits and Below-grade Tanks Permit Application Attachment Checklist: Subsection B of 19.15.17.9 NMAC Instructions: Each of the following items must be attached to the application. Please indicate, by a check mark in the box, that the documents are attached. Hydrogeologic Report (Below-grade Tanks) - based upon the requirements of Paragraph (4) of Subsection B of 19.15.17.9 NMAC Hydrogeologic Data (Temporary and Emergency Pits) - based upon the requirements of Paragraph (2) of Subsection B of 19.15.17.9 Siting Criteria Compliance Demonstrations - based upon the appropriate requirements of 19.15.17.10 NMAC Design Plan - based upon the appropriate requirements of 19.15.17.12 NMAC Operating and Maintenance Plan - based upon the appropriate requirements of 19.15.17.12 NMAC Closure Plan (Please complete Boxes 14 through 18, if applicable) - based upon the appropriate requirements of Subsection C of 19.15.17.9 NMAC and 19.15.17.13 NMAC Previously Approved Design (attach copy of design) API or Permit
Closed-loop Systems Permit Application Attachment Checklist: Subsection B of 19.15.17.9 NMAC Instructions: Each of the following items must be attached to the application. Please indicate, by a check mark in the box, that the documents are attached. Geologic and Hydrogeologic Data (only for on-site closure) - based upon the requirements of Paragraph (3) of Subsection B of 19.15.17.9 Siting Criteria Compliance Demonstrations (only for on-site closure) - based upon the appropriate requirements of 19.15.17.10 NMAC Design Plan - based upon the appropriate requirements of 19.15.17.11 NMAC Operating and Maintenance Plan - based upon the appropriate requirements of 19.15.17.12 NMAC Closure Plan (Please complete Boxes 14 through 18, if applicable) - based upon the appropriate requirements of Subsection C of 19.15.17.9 NMAC and 19.15.17.13 NMAC Previously Approved Design (attach copy of design) API Previously Approved Operating and Maintenance Plan API API API Previously Approved Operating and Maintenance Plan API API
Permanent Pits Permit Application Checklist: Subsection B of 19.15.17.9 NMAC Instructions: Each of the following items must be attached to the application. Please indicate, by a check mark in the box, that the documents are attached. Hydrogeologic Report - based upon the requirements of Paragraph (I) of Subsection B of 19.15.17.9 NMAC Siting Criteria Compliance Demonstrations - based upon the appropriate requirements of 19.15.17.10 NMAC Climatological Factors Assessment Certified Engineering Design Plans - based upon the appropriate requirements of 19.15.17.11 NMAC Dike Protection and Structural Integrity Design: based upon the appropriate requirements of 19.15.17.11 NMAC Leak Detection Design - based upon the appropriate requirements of 19.15.17.11 NMAC Liner Specifications and Compatibility Assessment - based upon the appropriate requirements of 19.15.17.11 NMAC Quality Control/Quality Assurance Construction and Installation Plan Operating and Maintenance Plan - based upon the appropriate requirements of 19.15.17.12 NMAC Freeboard and Overtopping Prevention Plan - based upon the appropriate requirements of 19.15.17.11 NMAC Nuisance or Hazardous Odors, including H2S, Prevention Plan Coll Field Waste Stream Characterization Monitoring and Inspection Plan Erosion Control Plan Erosion Control Plan Erosion Control Plan Erosion Control Plan - based upon the appropriate requirements of Subsection C of 19.15.17.9 NMAC and 19.15.17.13 NMAC Plan - based upon the appropriate requirements of Subsection C of 19.15.17.9 NMAC and 19.15.17.13 NMAC Plan - based upon the appropriate requirements of Subsection C of 19.15.17.9 NMAC and 19.15.17.13 NMAC Plan - based upon the appropriate requirements of Subsection C of 19.15.17.9 NMAC and 19.15.17.13 NMAC Plan - Based upon the appropriate requirements of Subsection C of 19.15.17.9 NMAC and 19.15.17.13 NMAC Plan - Based upon the appropriate requirements of Subsection C of 19.15.17.19 NMAC and 19.15.17.13 NMAC Plan - Plan - Based upon
Proposed Closure: 19.15.17.13 NMAC Instructions: Please complete the applicable boxes, Boxes 14 through 18, in regards to the proposed closure plan. Type: Drilling Workover Emergency Cavitation P&A Permanent Pit Below-grade Tank Closed-loop System Alternative Proposed Closure Method: Waste Excavation and Removal Waste Removal (Closed-loop systems only) On-site Closure Method (only for temporary pits and closed-loop systems) In-place Burial On-site Trench Alternative Closure Method (Exceptions must be submitted to the Santa Fe Environmental Bureau for consideration)
Waste Excavation and Removal Closure Plan Checklist: (19.15.17.13 NMAC) Instructions: Each of the following items must be attached to the closure plan. Please indicate, by a check mark in the box, that the documents are attached. Protocols and Procedures - based upon the appropriate requirements of 19.15.17.13 NMAC Confirmation Sampling Plan (if applicable) - based upon the appropriate requirements of Subsection F of 19.15.17.13 NMAC Disposal Facility Name and Permit Number (for liquids, drilling fluids and drill cuttings) Soil Backfill and Cover Design Specifications - based upon the appropriate requirements of Subsection H of 19.15.17.13 NMAC Re-vegetation Plan - based upon the appropriate requirements of Subsection G of 19.15.17.13 NMAC

Form C-144 Oil Conservation Division Page 3 of 5

Wester Personal Change For Changel Land Co. A. The Allest Land Co. A. School Land	The day of the Lambing Order (10.15.17.12 DADAGE)			
Waste Removal Closure For Closed-loop Systems That Utilize Above Ground Steel Tanks or Haul-off Bins Only: (19.15.17.13.D NMAC) Instructions: Please identify the facility or facilities for the disposal of liquids, drilling fluids and drill cuttings. Use attachment if more than two facilities are required.				
Disposal Facility Name:	Disposal Facility Permit #:			
Disposal Facility Name: Disposal Facility Permit #: Disposal Facility Permit #:				
Will any of the proposed closed-loop system operations and associated activit Yes (If yes, please provide the information No				
Required for impacted areas which will not be used for future service and operations: Soil Backfill and Cover Design Specification - based upon the appropriate requirements of Subsection H of 19.15.17.13 NMAC Re-vegetation Plan - based upon the appropriate requirements of Subsection G of 19.15.17.13 NMAC Site Reclamation Plan - based upon the appropriate requirements of Subsection G of 19.15.17.13 NMAC				
17				
Siting Criteria (Regarding on-site closure methods only: 19,15,17,10 NMA Instructions: Each siting criteria requires a demonstration of compliance in the closure plan certain siting criteria may require administrative approval from the appropriate district office for consideration of approval. Justifications and/or demonstrations of equivalency and the consideration of approval.	n. Recommendations of acceptable source material are provided to ce or may be considered an exception which must be submitted to			
Ground water is less than 50 feet below the bottom of the buried waste. - NM Office of the State Engineer - iWATERS database search; USGS: Data ob	tained from nearby wells	Yes No		
Ground water is between 50 and 100 feet below the bottom of the buried wast - NM Office of the State Engineer - iWATERS database search; USGS; Data obt		Yes No		
	·			
Ground water is more than 100 feet below the bottom of the buried waste. - NM Office of the State Engineer - iWATERS database search; USGS; Data obt	ained from nearby wells	YesNo N/A		
Within 300 feet of a continuously flowing watercourse, or 200 feet of any other significance (measured from the ordinary high-water mark).	icant watercourse or lakebed, sinkhole, or playa lake	Yes No		
- Topographic map; Visual inspection (certification) of the proposed site		□Yes □No		
Within 300 feet from a permanent residence, school, hospital, institution, or church in - Visual inspection (certification) of the proposed site; Aerial photo; satellite imag				
Within 500 horizontal feet of a private, domestic fresh water well or spring that less than five households use for domestic or stock watering purposes, or within 1000 horizontal fee of any other fresh water well or spring, in existence at the time of the initial application. - NM Office of the State Engineer - iWATERS database; Visual inspection (certification) of the proposed site				
Within incorporated municipal boundaries or within a defined municipal fresh water well field covered under a municipal ordinance adopted pursuant to NMSA 1978, Section 3-27-3, as amended.				
 Written confirmation or verification from the municipality; Written approval obt Within 500 feet of a wetland 		Yes No		
- US Fish and Wildlife Wetland Identification map; Topographic map; Visual ins	pection (certification) of the proposed site			
Within the area overlying a subsurface mine. - Written confirantion or verification or map from the NM EMNRD-Mining and Mineral Division		Yes INO		
Within an unstable area.		Yes No		
 Engineering measures incorporated into the design; NM Bureau of Geology & N Topographic map 	fineral Resources; USGS; NM Geological Society;			
Within a 100-year floodplain FEMA map		Yes No		
18 On-Site Closure Plan Checklist: (19.15.17.13 NMAC) Instructions: Each by a check mark in the box, that the documents are attached.	h of the following items must bee attached to the closs	ure plan. Please indicate,		
Siting Criteria Compliance Demonstrations - based upon the appropria	ate requirements of 19.15.17.10 NMAC			
Proof of Surface Owner Notice - based upon the appropriate requirements of Subsection F of 19.15.17.13 NMAC				
Construction/Design Plan of Burial Trench (if applicable) based upon the appropriate requirements of 19.15.17.11 NMAC				
Construction/Design Plan of Temporary Pit (for in place burial of a drying pad) - based upon the appropriate requirements of 19.15.17.11 NMAC				
Protocols and Procedures - based upon the appropriate requirements of 19.15.17.13 NMAC				
Confirmation Sampling Plan (if applicable) - based upon the appropriate requirements of Subsection F of 19.15.17.13 NMAC Weste Metarial Sampling Plan, based upon the appropriate requirements of Subsection F of 19.15.17.13 NMAC				
Waste Material Sampling Plan - based upon the appropriate requirements of Subsection F of 19.15.17.13 NMAC Disposal Facility Name and Parmit Number (for liquide, drilling fluide and drill cuttings or in case on site closure standards cannot be achieved)				
Disposal Facility Name and Permit Number (for liquids, drilling fluids and drill cuttings or in case on-site closure standards cannot be achieved) Soil Cover Design - based upon the appropriate requirements of Subsection H of 19.15.17.13 NMAC				
Re-vegetation Plan - based upon the appropriate requirements of Subsection I of 19.15.17.13 NMAC				
Site Reclamation Plan - based upon the appropriate requirements of Subsection G of 19.15.17.13 NMAC				

19 Operator Application Cartification:
Operator Application Certification: I hereby certify that the information submitted with this application is true, accurate and complete to the best of my knowledge and belief.
Name (Print): Title:
Signature: Date:
e-mail address: Telephone:
20 OCD Approval: Permit Application (including closure plan) Closure Plan (anly) OCD Conditions (see attachment)
OCD Representative Signature: Approval Date: 2/25/11
Title: OCD Permit Number:
21 Clause Propert (a private lithin (0 days of alcours core latins) as a latin (0 days of alcours core latins).
Closure Report (required within 60 days of closure completion): Subsection K of 19.15.17.13 NMAC Instructions: Operators are required to obtain an approved closure plan prior to implementing any closure activities and submitting the closure report. The closure
report is required to be submitted to the division within 60 days of the completion of the closure activities. Please do not complete this section of the form until an
approved closure plan has been obtained and the closure activities have been completed. X Closure Completion Date: October 29, 2009
X Closure Completion Date: October 29, 2009
22
Closure Method: Waste Excavation and Removal Waste Removal (Closed-loop systems only)
If different from approved plan, please explain.
If directic from approved plan, please explain.
23 Closure Report Regarding Waste Removal Closure For Closed-loop Systems That Utilize Above Ground Steel Tanks or Haul-off Bins Only:
Instructions: Please identify the facility or facilities for where the liquids, drilling fluids and drill cuttings were disposed. Use attachment if more than two facilities
were utilized.
Disposal Facility Name: Disposal Facility Permit Number:
Disposal Facility Name: Disposal Facility Permit Number: Were the closed-loop system operations and associated activities performed on or in areas that will not be used for future service and operations?
Yes (If yes, please demonstrate compliane to the items below) No
Required for impacted areas which will not be used for future service and operations:
Site Reclamation (Photo Documentation)
Soil Backfilling and Cover Installation
Re-vegetation Application Rates and Seeding Technique
Classes Parant Attachment Charlifets Instructions Facts of the Collegies items must be attached to the electron parant. Places indicate by a check most in
Closure Report Attachment Checklist: Instructions: Each of the following items must be attached to the closure report. Please indicate, by a check mark in the box, that the documents are attached.
X Proof of Closure Notice (surface owner and division)
Proof of Deed Notice (required for on-site closure)
X Plot Plan (for on-site closures and temporary pits)
X Confirmation Sampling Analytical Results (if applicable)
Waste Material Sampling Analytical Results (if applicable)
X Disposal Facility Name and Permit Number X Soil Backfilling and Cover Installation
X Re-vegetation Application Rates and Seeding Technique
X Site Reclamation (Photo Documentation)
On-site Closure Location: Latitude: 36.730806 °N Longitude: 108.003472 °W NAD 1927 X 1983
25
Operator Closure Certification:
I hereby certify that the information and attachments submitted with this closure report is ture, accurate and complete to the best of my knowledge and belief. I also certify that the closure complies with all applicable closure requirements and conditions specified in the approved closure plan.
Name (Print): Crystal Tafoya Title: Regulatory Tech
Signature: Date: 2/8/20/0
e-mail address: crystal.tafoya@conocophillips.com Telephone: 505-326-9837

Burlington Resources Oil Gas Company, LP San Juan Basin Closure Report

Lease Name: NEW MEXICO B COM 100

API No.: 30-045-34627

In accordance with Rule 19.15.17.13 NMAC the following information describes the closure of the temporary pit referenced above. All proper documentation regarding closure activities is being included with the C-144. The temporary pit for this location was constructed and location drilled before June 16, 2008 (effective date for Rule 19.15.17). While closure of the temporary pit did fall within the rule some dates for submittals are after the rig release date.

- Details on Capping and Covering, where applicable. (See report)
- Plot Plan (Pit Diagram) (Included as an attachment)
- Inspection Reports (Included as an attachment)
- Sampling Results (Included as an attachment)
- C-105 (Included as an attachment)
- Copy of Deed Notice will be filed with County Clerk (Not required on Federal, State, or Tribal land as stated by FAQ dated October 30, 2008)

General Plan:

1. All free standing liquids will be removed at the start of the pit closure process from the pit and disposed of in a division—approved facility or recycle, reuse or reclaim the liquids in a manner that the appropriate division district office approves.

All recovered liquids were disposed of at Basin Disposal (Permit #NM-01-005) and any sludge or soil required to be removed to facilitate closure was hauled to Envirotech Land Farm (Permit #NM-01-011) and JFJ Landfarm % IEI (Permit #NM-01-0010B).

2. The preferred method of closure for all temporary pits will be on-site burial, assuming that all the criteria listed in sub-section (B) of 19.15.17.13 are met.

The pit was closed using onsite burial.

3. The surface owner shall be notified of BR's closing of the temporary pit as per the approved closure plan using certified mail, return receipt requested.

The closure process notification to the landowner was sent via permit submittal. (See Attached)(Well located on State Land, certified mail is not required for Federal Land per BLM/OCD MOU.)

4. Within 6 months of the Rig Off status occurring BR will ensure that temporary pits are closed, re-contoured, and reseeded.

Provision 4 of the closure plan requirements were not met due to rig move off date as noted on C-105 which was prior to pit rule change. Burlington will ensure compliance with this rule in the future.

- 5. Notice of Closure will be given to the Aztec Division office between 72 hours and one week of closure via email, or verbally. The notification of closure will include the following:
 - i. Operator's name
 - ii. Location by Unit Letter, Section, Township, and Range. Well name and API number.

Notification is attached.

6. Liner of temporary pit shall be removed above "mud level" after stabilization. Removal of liner will consist of manually or mechanically cutting liner at mud level and removing all remaining liner. Care will be taken to remove "All" of the liner i.e., edges of liner entrenched or buried. All excessive liner will be disposed of at a licensed disposal facility.

Liner of temporary pit was removed above "mud level" after stabilization. Removal of the liner consisted of manually cutting liner at mud level and removing all remaining liner. Care was taken to remove "ALL" of the liner i.e., edges of liner entrenched or buried. All excessive liner was disposed of at a licensed disposal facility, (San Juan County Landfill).

7. Pit contents shall be mixed with non-waste containing, earthen material in order to achieve the solidification process. The solidification process will be accomplished using a combination of natural drying and mechanically mixing. Pit contents will be mixed with non-waste, earthen material to a consistency that is deemed a safe and stable. The mixing ratio shall not exceed 3 parts clean soil to 1 part pit contents.

Burlington mixed the Pit contents with non-waste containing, earthen material in order to achieve the solidification process. The solidification process was accomplished by using a combination of natural drying and mechanically mixing. Pit contents were mixed with non-waste, earthen material to a consistency that is deemed as safe and stable. The mixing ratio consisted of approximately 3 parts clean soil to 1 part pit contents.

8. A five point composite sample will be taken of the pit using sampling tools and all samples tested per Subsection B of 19.15.17.13(B)(1)(b). In the event that the criteria are not met, all contents will be handled per Subparagraph (a) of Paragraph (1) of Subsection B of 19.15.17.13 i.e., Dig and haul.

A five point composite sample was taken of the pit using sampling tools and all samples tested per Subsection B of 19.15.17.1 3(B)(1)(b). (Sample results attached).

Components	Tests Method	Limit (mg/Kg)	Results
Benzene	EPA SW-846 8021B or 8260B	0.2	ND ug/kg
BTEX	EPA SW-846 8021B or 8260B	50	38.8 ug/kG
TPH	EPA SW-846 418.1	2500	55.2 mg/kg
GRO/DRO	EPA SW-846 8015M	500	11.0 mg/Kg
Chlorides	EPA 300.1	1000/ 500-	140 mg/L

9. Upon completion of solidification and testing standards being passed, the pit area will be backfilled with compacted, non-waste containing, earthen material. A minimum of four feet of cover shall be achieved and the cover shall include one foot of suitable material to establish vegetation at the site, or the background thickness of topsoil, whichever is greater. If standard testing fails BR will dig and haul all contents pursuant to 19.15.17.13.i.a. After doing such, confirmation sampling will be conducted to ensure a release has not occurred.

The pit material passed solidification and testing standards. The pit area was then backfilled with compacted, non-waste containing, earthen material. More than four feet of cover was achieved and the cover included one foot of suitable material to establish vegetation at the site.

10. During the stabilization process if the liner is ripped by equipment the Aztec OCD office will be notified within 48 hours and the liner will be repaired if possible. If the liner can not be repaired then all contents will be excavated and removed.

The integrity of the liner was not damaged in the pit closure process.

11. Dig and Haul Material will be transported to the Envirotech Land Farm located 16 miles south of Bloomfield on Angel Peak Road, CR 7175. Permit # NM010011

Dig and Haul was not required.

12. Re-contouring of location will match fit, shape, line, form and texture of the surrounding. Re-shaping will include drainage control, prevent ponding, and prevent erosion. Natural drainages will be unimpeded and water bars and/or silt traps will be place in areas where needed to prevent erosion on a large scale. Final recontour shall have a uniform appearance with smooth surface, fitting the natural landscape.

The pit area was re-contoured to match fit, shape, line, form and texture of the surrounding area. Reshaping included drainage control, to prevent ponding and erosion. Natural drainages were unimpeded and water bars and/or silt traps were placed in areas where needed to prevent erosion on a large scale. Final recontour has a uniform appearance with smooth surface, fitting the natural landscape.

13. Notification will be sent to OCD when the reclaimed area is seeded.

Provision 13 will be accomplished with the following seeding regiment and the OCD will be notified of the seeding date by the submission of a C103:

Туре	Variety or Cultivator	PLS/A
Western wheatgrass	Arriba	3.0
Indian ricegrass	Paloma or Rimrock	3.0
Slender wheatgrass	San Luis	2.0
Crested wheatgrass	Hy-crest	3.0
Bottlebrush Squirreltail	Unknown	2.0
Four-wing Saltbrush	Delar	.25

14. BR shall seed the disturbed areas the first growing season after the operator closes the pit. Seeding will be accomplished via drilling on the contour whenever practical or by other division-approved methods. BLM or Forest Service stipulated seed mixes will used on federal lands. Vegetative cover will equal 70% of the native perennial vegetative cover (un-impacted) consisting of at least three native plant species, including at least one grass, but not including noxious weeds, and maintain that cover through two successive growing seasons. Repeat seeding or planting will be continued until successful vegetative growth occurs.

Provision 14 will be accomplished with the above seeding regiment. Seeding will be accomplished via drilling on the contour whenever practical or by other division-approved methods. The OCD will be notified once two successive growing seasons have been accomplished by submitting a C-103.

15. The temporary pit will be located with a steel marker, no less than four inches in diameter, cemented in a hole—three feet deep in the center of the onsite burial upon the abandonment of all the wells on the pad. The marker will be flush with the ground to allow access of the active well pad and for safety concerns. The marker will include a threaded collar to be used for future abandonment. The top of the marker will contain a welded steel 12" square plate that indicates the onsite burial of the temporary pit. The plate will be easily removable and a four foot tall riser will be threaded into the top of the collar marker and welded around the base with the operator's information at the time of all wells on the pad are abandoned. The operator's information will include the following: Operator Name, Lease Name, Well Name and number, Unit Number, Section, Township, Range and an indicator that the marker is an onsite burial location.

Provision 15 was accomplished by installing a steel marker in the temporary pit, no less than four inches in diameter, cemented in a hole three feet deep in the center of the onsite burial. The marker is flush with the ground to allow access of the active well pad and for safety concerns. The top of the marker contains a welded steel 12" square plate that indicates the onsite burial of the temporary pit. The plate contains the following: Operator Name, Lease Name, Well Name and number, Unit Number, Section, Township, Range and an indicator that the marker is an onsite burial location.

The plate will be easily removable and a four foot tall riser will be threaded into the top of the collar marker and welded around the base with the following operator's information at the time of all wells on the pad are abandoned. The riser will be labeled: BR, State, NEW MEXICO B COM 100, UL-D, Sec. 16, T 29N, R 11W, API # 30-045-34627

DISTRICT I 1825 N. French Dr., Hobbs, N.M. 88240

State of New Mexico Energy, Minerals & Natural Resources Department

Form C-102 Revised October 12, 2005

DISTRICT II 1301 W. Grand Avenue, Artesia, N.M. 88210

DISTRICT III 1009 Rio Brazos Rd:, Aztec, N.M. 87410 OIL CONSERVATION DIVISION 1220 South St. Francis Dr. Santa Fe. NM 67505 Submit to Appropriate District Office State Lease — 4 Copies Fee Lease — 3 Copies


☐ AMENDED REPORT

DISTRICT IV 1220 S. St. Francis Dr., Santa Pe, NM 87605

	MELL LOCATION AND	ACREAGE DEDICATION PLAT	
¹ API Number	* Paol Code	Peol Name BASIN FRUITLAND COAL/BLANCO PICTURES	D ÇĻIFF
Property Code	*Pr	operty Name	.ª Well Number
	NEW M	EXICO B COM	100
OGRID No.	¹ 00	arator Name	6'Elevation
	BURLINGTON RESOURCE	S OIL AND GAS COMPANY LP	5657

¹⁰ Surface Location North/South line Feet from the East/West'line UL or lot no. Section Lot Idn Feet from the. Township Range County 783 839" D 16 29N 11W NORTH WEST SAN JUAN ii Bottom Hole Location If Different From Surface Feet from the North/South line Lot idn Feet from the East/West line UL or lot no. Section Township County Range Consolidation Code "Order No. Dedicated Acres Joint or Infill BASIN FRUIT 320.00 Acres - (W/2) BLÂNCO PC 160.0 Acres & (NW/4).

NO ALLOWABLE WILL BE ASSIGNED TO THIS COMPLETION UNTIL ALL INTERESTS HAVE BEEN CONSOLIDATED OR A NON-STANDARD UNIT HAS BEEN APPROVED BY THE DIVISION



Russell Surveying 1409 W. Aztec Bivd. #2 Aztec, New Mexico 87410 (505) 334-8637 .09 30, SCALE = 60 ACROSS NEW MEXICO STATE LANDS TO EXISTING ROAD 127 LF OF NEW ACCESS NOTE:
RESERVE PIT DIKE: TO BE 8' ABOVE DEEP SIDE (OVERELOW — 3' WDE) AND 1' ABOVE SHALLOW SIDE).
RESERVE PIT DIKE: TO BE 8' ABOVE DEEP SIDE (OVERELOW — 3' WDE) AND 1' ABOVE SHALLOW SIDE).
CONTRACTOR SHOULD CALL ONE—CALL FOR LOCATION OF ANY MARKED OR UNMARKED, BURIED PIPELINES OR CABLES ON WELL PAD, IN CONSTRUCTION ZONE AND/OR ACCESS ROAD AT LEAST TWO (2) WORKING DAYS PRIOR TO CONSTRUCTION. EDGE OF DISTURBANCE A' F+8.0 C-12.5 ±1.0 Θ ୍ଡ କ≪ OH Wellhead to front BURLINGTON RESOURCES O&G CO LP RIG. ANCHOR RIG ANCHOR LOCATED IN THE NW/4 NW/4 OF SECTION 16. FINISHED PAD ELEVATION: 5657.2", NAVD 88 LAYDOWN N 57'23"15" E 120" POWER BOX SAN JUAN COUNTY, NEW MEXICO GROUND ELEVATION: 5657; NAVD 88 **NEW MEXICO B COM #100** T29N, R11W, N.M.P.M. ANOHOR 783' FINE & 839' FWL ANCHOR O B'F+10.1 UINE DEIP 0.00 spie of besullaw ,09 110, C-5.5 12' Deep Slopes Reserve PIt VELL HEAD VELL HEAD NEV HEXICO B COM 3 IE 3 DIKE Wellhead to back BIG ANCHOR ENSTING PRELINE SEPERATOR 10, Deep RIG ANCHOR REAR F+3.7 OH က် (0.5.3 (0.00) C-0.7 • TANK 305' x 340' = 2.38 ACRES OF DISTURBANCE SCALE: 1" = 60' SLOPES TO BE CONSTRUCTED TO MATCH THE ORIGINAL CONTOURS AS CLOSE AS POSSIBLE. LONGITUDE: 108.00324°W LATITUDE: 36.73074°N DATUM: NAD 83 JOB No.: COPC118 DATE: 11/07/07



EPA METHOD 8015 Modified Nonhalogenated Volatile Organics Total Petroleum Hydrocarbons

Client:	Connecthilling	Duning the	00000 0000
Client.	ConocoPhillips	Project #:	96052-0026
Sample ID:	New Mexico B Com #100	Date Reported:	02-27-09
Laboratory Number:	49088	Date Sampled:	02-23-09
Chain of Custody No:	6367	Date Received:	02-23-09
Sample Matrix:	Soil	Date Extracted:	02-24-09
Preservative:	Cool	Date Analyzed:	02-25-09
Condition:	Intact	Analysis Requested:	8015 TPH

Parameter	Concentration (mg/Kg)	Det. Limit (mg/Kg)
Gasoline Range (C5 - C10)	ND	0.2
Diesel Range (C10 - C28)	11.0	0.1
Total Petroleum Hydrocarbons	11.0	0.2

ND - Parameter not detected at the stated detection limit.

References:

Method 8015B, Nonhalogenated Volatile Organics, Test Methods for Evaluating Solid Waste,

SW-846, USEPA, December 1996.

Comments:

Drilling Pit Sample.

Analyst

Review



EPA Method 8015 Modified Nonhalogenated Volatile Organics Total Petroleum Hydrocarbons

Quality Assurance Report

Client:	QA/QC	Project #:	N/A
Sample ID:	02-25-09 QA/QC	Date Reported:	02-27-09
Laboratory Number:	49084	Date Sampled:	N/A
Sample Matrix:	Methylene Chloride	Date Received:	N/A
Preservative:	N/A	Date Analyzed:	02-25-09
Condition:	N/A	Analysis Requested:	TPH

THE STATE OF THE S	t-Cal Date	I-Cal RF	C-Cel RF.	% Difference	Accept Range
Gasoline Range C5 - C10	05-07-07	1.0352E+003	1.0356E+003	0.04%	0 - 15%
Diesel Range C10 - C28	05-07-07	9.8898E+002	9.8938E+002	0.04%	0 - 15%

Blank Conc. (mg/L - mg/Kg)	Concentration	Detection Limit
Gasoline Range C5 - C10	ND	0.2
Diesel Range C10 - C28	ND	0.1
Total Petroleum Hydrocarbons	ND	0.2

Duplicate Conc. (mg/Kg)	Sample :	Duplicate	% Difference	Accept Range
Gasoline Range C5 - C10	3.2	3.1	3.1%	0 - 30%
Diesel Range C10 - C28	7.1	7.4	4.2%	0 - 30%

Spike Conc. (mg/Kg)	Sample	Spike Added	Spike Result	% Recovery	Accept Range
Gasoline Range C5 - C10	3.2	250	251	99.2%	75 - 125%
Diesel Range C10 - C28	7.1	250	253	98.4%	75 - 125%

ND - Parameter not detected at the stated detection limit.

References:

Method 8015B, Nonhalogenated Volatile Organics, Test Methods for Evaluating Solid Waste,

SW-846, USEPA, December 1996.

Comments:

QA/QC for Samples 49084, 49088, 49090, 49091, 49093, and 49094.

Analyst



EPA METHOD 8021 AROMATIC VOLATILE ORGANICS

Client:	ConocoPhillips	Project #:	96052-0026
Sample ID:	New Mexico B Com #100	Date Reported:	02-27-09
Laboratory Number:	49088	Date Sampled:	02-23-09
Chain of Custody:	6367	Date Received:	02-23-09
Sample Matrix:	Soil	Date Analyzed:	02-25-09
Preservative:	Cool	Date Extracted:	02-24-09
Condition:	Intact	Analysis Requested:	BTEX

Parameter	Concentration (ug/Kg)	Det. Limit (ug/Kg)	
Danasa	ND	20	
Benzene	ND	0.9	
Toluene	8.6	1.0	
Ethylbenzene	5.8	1.0	
p,m-Xylene	14.5	1.2	
o-Xylene	9.9	0.9	
Total BTEX	38.8		

ND - Parameter not detected at the stated detection limit.

Surrogate Recoveries:	Parameter	Percent Recovery
	Fluorobenzene	98.0 %
	1,4-difluorobenzene	98.0 %
	Bromochlorobenzene	98.0 %

References:

Method 5030B, Purge-and-Trap, Test Methods for Evaluating Solid Waste, SW-846, USEPA,

December 1996.

Method 8021B, Aromatic Volatile Organics, Test Methods for Evaluating Solid Waste, SW-846,

USEPA, December 1996.

Comments:

Drilling Pit Sample.



EPA METHOD 8021 AROMATIC VOLATILE ORGANICS

Client:	N/A	Project #: Date Reported: Date Sampled: Date Received:	N/A
Sample ID:	02-25-BT QA/QC		02-27-09
Laboratory Number:	49084		N/A
Sample Matrix:	Soil		N/A
Preservative: Condition:	Soil	Date Received:	N/A
	N/A	Date Analyzed:	02-25-09
	N/A	Analysis:	BTEX

Calibration and Detection Limits (ug/L	I-Cal _i RE; .)	C-Cal RF: Accept: Rand	%Diff. jë 0≃15%	Blank Conc	Detect. Limit
Benzene	1.4521E+005	1.4550E+005	0.2%	ND	0.1
Toluene	1.6033E+005	1.6066E+005	0.2%	ND	0.1
Ethylbenzene	1.5771E+005	1.5803E+005	0.2%	ND	0.1
p,m-Xylene	4.0785E+005	4.0867E+005	0.2%	ND	0.1
o-Xylene	1.7064E+005	1.7098E+005	0.2%	ND	0.1

Duplicate Conc. (ug/Kg)	Sample D	uplicate -	%Diff.	Accept Range	Detect: Limit
Benzene	5.5	5.8	5.5%	0 - 30%	0.9
Toluene	15.5	15.2	1.9%	0 - 30%	1.0
Ethylbenzene	12.8	12.0	6.3%	0 - 30%	1.0
p,m-Xylene	44.5	42.3	4.9%	0 - 30%	1.2
o-Xylene	21.6	20.2	6.5%	0 - 30%	0.9

Spike Conc. (ug/Kg)	Sample Amo	ount Spiked Spik	ked Sample	% Recovery	Accept Range
Benzene	5.5	50.0	54.2	97.7%	39 - 150
Toluene	15.5	50.0	62.1	94.8%	46 - 148
Ethylbenzene	12.8	50.0	60.7	96.7%	32 - 160
p,m-Xylene	44.5	100	140	97.1%	46 - 148
o-Xylene	21.6	50.0	65.6	91.6%	46 - 148

ND - Parameter not detected at the stated detection limit.

References:

Method 5030B, Purge-and-Trap, Test Methods for Evaluating Solid Waste, SW-846, USEPA,

December 1996.

Method 8021B, Aromatic and Halogenated Volatiles by Gas Chromatography Using

Photoionization and/or Electrolytic Conductivity Detectors, SW-846, USEPA December 1996.

Comments:

QA/QC for Samples 49084, 49088, 49090, 49091, and 49093 - 49098.

Analyst

THE PENELOTE AGIE EN PONONTIATATION EN PENEL GOT 100E Toh Manufestach inc com



EPA METHOD 418.1 TOTAL PETROLEUM HYDROCARBONS

Client:	ConocoPhillips	Project #:	96052-0026
Sample ID:	New Mexico B Com #100	Date Reported:	02-27-09
Laboratory Number:	49088	Date Sampled:	02-23-09
Chain of Custody No:	6367	Date Received:	02-23-09
Sample Matrix:	Soil	Date Extracted:	02-23-09
Preservative:	Cool	Date Analyzed:	02-23-09
Condition:	Intact	Analysis Needed:	TPH-418.1

		Det.
	Concentration	Limit
Parameter	(mg/kg)	(mg/kg)

Total Petroleum Hydrocarbons

55.2

5.0

ND = Parameter not detected at the stated detection limit.

References:

Method 418.1, Petroleum Hydrocarbons, Total Recoverable, Chemical Analysis of Water

and Waste, USEPA Storet No. 4551, 1978.

Comments:

Drilling Pit Sample.

Analysi Analysi T

Mistre Malters Review



EPA METHOD 418.1 TOTAL PETROLEUM HYROCARBONS QUALITY ASSURANCE REPORT

Client:

QA/QC

Project #:

N/A

Sample ID:

QA/QC

Date Reported:

02-24-09

Laboratory Number:

02-23-TPH.QA/QC 49020

Date Sampled:

Sample Matrix:

Freon-113

Date Analyzed:

N/A 02-23-09

TPH

Preservative:

Condition:

N/A N/A Date Extracted:

02-23-09

I-Cal Date

C-Cal Date

I-Cal RF:

Analysis Needed:

% Difference

Calibration

02-13-09

02-23-09

1,500

C-Cal RF: 1,610

7.3%

Accept. Range +/- 10%

Blank Conc. (mg/Kg)

Concentration

Detection Limit

TPH

ND

16.8

Duplicate Conc. (mg/Kg)

Sample

Duplicate

% Difference Accept. Range

TPH

TPH

192

180

6.3%

+/- 30%

Spike Conc. (mg/Kg)

Sample 192

Spike Added 2,000

Spike Result % Recovery 1,860

84.9%

Accept Range 80 - 120%

ND = Parameter not detected at the stated detection limit.

References:

Method 418.1, Petroleum Hydrocarbons, Total Recoverable, Chemical Analysis of Water

and Waste, USEPA Storet No. 4551, 1978.

Comments:

QA/QC for Samples 49020 - 49023, 49031, 49033, 49081, 49084 and 49088.



Chloride

Client: ConocoPhillips Project #: 96052-0026 Sample ID: New Mexico B Com #100 Date Reported: 02-27-09 Lab ID#: 49088 Date Sampled: 02-23-09 Sample Matrix: Soil Date Received: 02-23-09 Preservative: Cool Date Analyzed: 02-24-09 Condition: Intact Chain of Custody: 6367

Parameter

Concentration (mg/Kg)

Total Chloride

140

Reference:

U.S.E.P.A., 4500B, "Methods for Chemical Analysis of Water and Wastes", 1983.

Standard Methods For The Examination of Water And Waste Water", 18th ed., 1992.

Comments:

Drilling Pit Sample.

Date of Test Hours Tested Choke Size Production Date of Test Hours Tested Date of Test Hours Tested Date of Test Date of Test Hours Tested Date of Test Date of		rm C-105																
	, Hobbs, NM	88240	E	nergy, l	Minerals and	d Nat	ural	Re	sources		1. WELL	API	NO				July 17, 2008	
	enue, Artesia,	NM 88210		Oi	l Concervo	tion 1	Divi	cio	n		30-045-34	627	110.					
	i., Aztec, NM	1 87410												ree		ירוא/רוי	IANI	
	Dr., Santa Fe	, NM 87505							1.							ED/IND	IAN	
									1.00		E-9226-5							
		ETIONO	R REC	OMPL	ETION RE	ND	LUG											
☐ COMPLETI	ON REPO	RT (Fill in be	ves #1 thro	nigh #31	for State and Fed	e wells	only)				NEW ME	XIC						
		`					• /	,	1.//22 1	, ·		ber:						
#33; attach this ar	nd the plat to									/or						_		
		WORKOVER	. DEE	PENING	□PLUGBACI	K D E	DIFFE	REN	T RESERV	OIR	OTHER							
		Oil Cas C	omnanı	, rp														
10. Address of O	perator		ompany	γ, L.F								or V	Vildca	ıt				
PO Box 4298, Fa	rmington, N	IM 87499																
	Unit Ltr	Section	Tow	nship	Range	Lot			Feet from t	he	N/S Line	Fee	et fron	n the	E/W L	ine	County	
						l I						-				-		
	14. Date	T.D. Reache	d 15	Date Rig	Released			16.	Date Compl	leted	(Ready to Pro	duce)		17	. Elevati	ons (DF	and RKB.	
			08/	/16/2008										RT	Γ, GR, et	tc.)		
18. Total Measure	ed Depth of	19.	. Plug Bac	k Measured Dej	pth	20. Was Directiona			il Survey Made	21.	Тур	e Electric and Other Logs Run						
22. Producing Int	erval(s), of	this completion	n - Top, B	ottom, Na	ame													
23.				CAS	ING REC	ORI) (Re	epo	ort all str	ring	gs set in w	ell)						
CASING SIZ	ZE	WEIGHT I	.B./FT.							`				D	AN	OUNT	PULLED	
,																		
				ļ		\perp								_			****	
24.			<u></u>	LIN	ER RECORD					25.		ΓUB	ING I	L RECO	ORD			
SIZE	ТОР		BOTTOM		SACKS CEM	ENT	SCRI	EEN		SIZ	ZE	I	DEPTI	-I SET	`	PACKI	ER SET	
	-											+				_		
26. Perforation	record (inte	erval, size, and	number)				27. /	ACI	D, SHOT,	FR.								
							DEP	THI	NTERVAL		AMOUNT A	AND	KINE)·MA	ΓERIAL	USED		
			<u> </u>														•	
	tion	Pro	duction M	ethod (Fl						1	Well Statu	s (Pr	od or	Shut_	in)			
Date 1 list 1 loude	odoji	110	auction ivi	culou (1 1	owing, gus tijt, p	штртв	5 - 0120	· um	, суре ритр)	,	Wen State	3 (1 /	ou. or	Drui-	,			
Date of Test	Hours Tested Choke Size		ze	1		Oil - Bbl		}	Ga	G - MCF		Water - Bbl.			Gas - Oil Ratio			
Flow Tubing Press.	Casing	Pressure	Calculate Hour Rate		Oil - Bbl.			Gas -	MCF		Water - Bbl.		0	il Gra	rity - API - (Corr.)		r.)	
29. Disposition of Gas (Sold, used for fuel, vented, etc.)												30.	Test	Witne	ssed By			
31. List Attachme																		
32. If a temporary			-			=		it.										
33. If an on-site b	urial was u		•					υ	11027 5714	กดา	_							
I hereby certij	fy that the	Latitude 3		on boti		form	is tri	ue c	and compl	ete lete	to the best o	of m	y kno	owled	lge and	l beliej	<u>r</u>	
Signature _	nyste	al Ta	loya		nted ne Crystal T	afoya	a T	ìtle	: Regula	tory	y Tech I	Date	: 2	/8/	2010			
E-mail Addre	ss crysta	l.tafoya@c	nocoph	illips.co	m													

CorocoPhilips

Pit Closure Form:
Date: 10/29/2009
Well Name: New Mexico B com 100
Footages: 783 FNL 839 FWL Unit Letter: D
Section: 16, T-29-N, R-11-W, County: 53 State: NM
Contractor Closing Pit: ACC
Construction Inspector: Norman Faver Date: 10/29/2009
Inspector Signature: Jarman

Tafova, Crystal

From:

Silverman, Jason M

Sent:

Friday, October 23, 2009 9:44 AM

To:

Mark Kelly: Robert Switzer: Sherrie Landon

Cc:

'mike waybourn'; 'tevans48@msn.com'; 'bko@digii.net'; Elmer Perry; Faver Norman (faverconsulting@yahoo.com); Jared Chavez, Bassing, Kendal R.; Scott Smith; Silverman, Jason M; Smith Eric (sconsulting.eric@gmail.com); 'Steve McGlasson'; Terry Lowe; Becker, Joey W; Bonilla, Amanda; Bowker, Terry D; Gordon Chenault; GRP:SJBU Production Leads; Hockett, Christy R; Johnson, Kirk L; Kennedy, Jim R; Lopez, Richard A; O'Nan, Mike J.; Peace, James T; Pierce, Richard M; Poulson, Mark E; Smith, Randall O; Spearman, Bobby E; Stamets, Steve A; Thacker, LARRY; Work, Jim A; Blair, Maxwell O; Blakley, Mac; Clark, Joni E; Farrell, Juanita R; Gillette, Steven L (Gray Surface Specialties and Consulting, Ltd.); Greer,

David A; Hines, Derek J (Finney Land Co.); Maxwell, Mary Alice; McWilliams, Peggy L;

Seabolt, Elmo F; Stallsmith, Mark R

Subject:

Reclamation Notice: New Mexico B Com 100

Importance: High

Attachments: New Mexico B Com 100.pdf

Ace Services will move a tractor to the New Mexico B COM 100 on Wednesday, October **28th. 2009** to start the Reclamation Process.

Please contact Norm Faver (320-0670) if you have any questions or need further assistance.

Thanks, Jason Silverman

Burlington Resources Well - Network Number #: 10227131

San Juan County, NM:

New Mexico B Com 100 - State surface / State minerals

Twinned on New Mexico B Com 1E

783' FNL, 839' FWL Sec. 16, T29N, R11W

Unit Letter 'D'

Lease #: State of NM E-9226-5


Latitude: 36° 43' 50.66400" N (NAD 83)


Longitude: 108° 00' 11.66400" W

Elevation: 5657'

API #: 30-045-34627

Jason Silverman -----Construction Technician ConocoPhillips Company - SJBU Projects Team P.O. Box 4289 Farmington, NM 87499-4289





WELL PAD SAFETY AND ENVIRONMENTAL CHECK LIST

WELL NAME: New Mexico B Com 100

API#: 30-045-34627

WELL NA	WELL NAME: New Mexico B Com 100	B Com 100			API#: 30-045-34627
DATE	INSPECTOR	SAFETY	LOCATION	PICTURES	COMMENTS
8/8/08	Jared Chavez	OI FOR	NO III		AWS #580 IS ON LOCATION
8/28/08	Jared Chavez	×	×	×	PIT AND LOCATION IN GOOD CONDITION
9/11/08	Jared Chavez	×	×	×	PIT AND LOCATION IN GOOD CONDITION
9/18/08	Jared Chavez	×	×	×	PIT AND LOCATION IN GOOD CONDITION
10/15/08	Jared Chavez	×	×	×	PIT AND LOCATION IN GOOD CONDITION
11/26/08	Jared Chavez	×	×	×	FENCE NEEDS TIGHTENED - CONTACTED CROSFFIRE
12/3/08	Jared Chavez				DRAKE #29 IS ON LOCATION
12/19/08	Jared Chavez	×	×	×	PIT AND LOCATION IN GOOD CONDITION
1/20/09	Jared Chavez	×	×	×	FENCE NEEDS TIGHTENED - CONTACTED CROSSFIRE FOR REPAIRS
1/27/09	Jared Chavez	×	×	×	FENCE NEEDS TIGHTENED - CONTACTED CROSSFIRE FOR REPAIRS
2/3/09	Jared Chavez	×	×	×	PIT AND LOCATION IN GOOD CONDITION
2/9/09	Jared Chavez	×	×	×	PIT AND LOCATION IN GOOD CONDITION
2/9/09	Jared Chavez	×	×	×	PIT AND LOCATION IN GOOD CONDITION
2/13/09	Jared Chavez	×	×	×	WATER NEEDS PULLED - CONTACTED DAWN TRUCKING
2/13/09	Jared Chavez	×	×	×	WATER NEEDS PULLED - CONTACTED DAWN TRUCKING
2/20/09	Jared Chavez	×	×	×	FLUID IS UNDER THE LINER - CONTACTED DAWN TRUCKING TO PULL FLUID
2/20/09	Jared Chavez	×	×	×	FLUID IS UNDER THE LINER - CONTACTED DAWN TRUCKING TO PULL FLUID
2/27/09	Jared Chavez	×	×	×	PIT AND LOCATION IN GOOD CONDITION
2/27/09	Jared Chavez	×	×	×	PIT AND LOCATION IN GOOD CONDITION
3/6/09	Jared Chavez	×	×	×	PIT AND LOCATION IN GOOD CONDITION
		••			

	T	T	T	1	T	1				T	1	1			T	T		1	T		
PIT AND LOCATION IN GOOD CONDITION	LOCATION HAS BEEN RECLAIMED																				
×	×	×	×	×	×	×	×	×	×	×	×	×	×	×	×	×	×	×	×	×	
×	×	×	×	×	×	×	×	×	×	×	×	×	×	×	×	×	×	×	×	×	
			-													w					
×	×	×	×	×	×	×	×	×	×	×	×	×	×	×	×	×	×	×	×	×	
Jared Chavez	Jared Chavez																				
3/6/09	3/18/09	3/18/09	4/3/09	4/17/09	4/28/09	5/1/09	5/15/09	6/4/09	6/11/09	6/97/9	60/6/2	7/17/09	7/23/09	60/2/8	8/21/09	9/22/09	10/8/09	10/22/09	10/23/09	10/29/09	11/26/09