

UNITED STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEYSUBMIT IN TRIPLICATE*
(Other instructions on re-
verse side)Form approved
Budget Bureau No. 42-R1424.
5. LEASE DESIGNATION AND SERIAL NO.

147

6. IF INDIAN, ALLOTTEE OR TRIBE NAME

Jicarilla Apache

7. UNIT AGREEMENT NAME

8. FARM OR LEASE NAME

AXI Apache "J"

9. WELL NO.

17

10. FIELD AND POOL, OR WILDCAT

AXI Apache Area
Chacra & Mesa Verde11. SEC., T., R., M., OR BLK. AND
SURVEY OR AREA

Sec. 7, T25N, R5W

12. COUNTY OR PARISH 13. STATE

Rio Arriba New Mexico

1. OIL ☐ WELL GAS ☒ WELL OTHER ☐ Reentry - Multiple Zone
2. NAME OF OPERATOR Continental Oil Company
3. ADDRESS OF OPERATOR 152 North Durbin, Casper, Wyoming 82601
4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements.*
See also space 17 below.)
At surface NE NE 820' FNL, 1100' FEL (Unit Letter "A")

14. PERMIT NO.

15. ELEVATIONS (Show whether DF, RT, GR, etc.)

6704' Gr., 6718' KB

16. Check Appropriate Box To Indicate Nature of Notice, Report, or Other Data

NOTICE OF INTENTION TO:

TEST WATER SHUT-OFF

FRACTURE TREAT

SHOOT OR ACIDIZE

REPAIR WELL

(Other)

PULL OR ALTER CASING

MULTIPLE COMPLETE

ABANDON*

CHANGE PLANS

X

SUBSEQUENT REPORT OF:

WATER SHUT-OFF

FRACTURE TREATMENT

SHOOTING OR ACIDIZING

(Other)

REPAIRING WELL

ALTERING CASING

ABANDONMENT*

(NOTE: Report results of multiple completion on Well
Completion or Recompletion Report and Log form.)

17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*


Approval was received to reenter this well on August 20, 1971. Operations began 8-24-71 and reached a total depth of 5535'. 8 5/8" OD casing had been previously set at 428'. Lost 3075' of 2 7/8" drill pipe and 340' of 5 1/2" drill collars during drilling operations. Top of fish is at 3245' and we were unable to recover it after several days.

Verbal permission was received to plug and abandon this well on September 1, 1971 from Mr. Jerry Long (USGS) and Mr. Emery Arnold (NMOGCC). Formal approval is requested to plug and abandon the well as follows:

400 sks. - 3200-2000' - Picture Cliff & Farmington
100 sks. - 547-200' - In and out of 8 5/8" OD surface pipe
10 sks. - At surface w/regulation dry hole marker

RECEIVED

SLP 7 1971



USGS(6) File(2)

U. S. GEOLOGICAL SURVEY

18. I hereby certify that the foregoing is true and correct

SIGNED

Elmer L. Phillips

TITLE

Administrative Supervisor

DATE Sept. 2, 1971

(This space for Federal or State office use)

APPROVED BY

EL

TITLE

DATE

CONDITIONS OF APPROVAL, IF ANY: