

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
GEOLOGICAL SURVEY

## SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir. Use Form 9-331-C for such proposals.)

1. oil ☐ gas ☒ other ☐  
well well

2. NAME OF OPERATOR

J. Gregory Merrion &amp; Robert L. Bayless

3. ADDRESS OF OPERATOR

P.O. Box 507, Farmington, NM 87401

4. LOCATION OF WELL (REPORT LOCATION CLEARLY. See space 17 below.)

AT SURFACE: 790 FNL and 1450 FNL

AT TOP PROD. INTERVAL: 1450 FNL

AT TOTAL DEPTH: 1450 FNL

16. CHECK APPROPRIATE BOX TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA.

REQUEST FOR APPROVAL TO: ☐ INITIAL SUBSEQUENT REPORT OF:TEST WATER SHUT-OFF ☐FRACTURE TREATMENT ☐SHOOT OR ACIDIZE ☐REPAIR WELL ☐PULL OR ALTER CASING ☐MULTIPLE COMPLETE ☐CHANGE ZONES ☐ABANDON\* ☐(other) Drilling & Cementing ☐

5. LEASE

SF 078897A

6. IF INDIAN, ALLOTTEE OR TRIBE NAME

7. UNIT AGREEMENT NAME

8. FARM OR LEASE NAME

Western Federal

9. WELL NO.

8

10. FIELD OR WILDCAT NAME

South Gallegos Fruitland Unders. Pic. Cliffs

11. SEC., T., R., M. OR BLK. AND SURVEY OR AREA

Sec. 18, T26N, R11W

12. COUNTY OR PARISH

San Juan

13. STATE

New Mexico

14. API NO.

15. ELEVATIONS (SHOW DF. KDB. AND WD)

6101 Ground Level

(NOTE: Report results of multiple completion or zone change on Form 9-330.)

17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)\*

03-14-79 - Move in, Rig up L &amp; B Speed Drill. Spud 9-1/4" hole to 34 Feet Set 33.4 Feet of 7", 20 lb/ft surface casing with 10 sacks of WOC.

03-16-79 - Drill out from under surface w/ 5" bit. Drilling to 400 feet

03-17-79 - Reached total depth @ 1460 ft. G.R. Preparing to log

03-18-79 - Rig up Birdwell. Ran IES Induction tool, found tight spot at 123 ft.


G.R., unable to get down. Pulled logging tool out of hole. Ran in with drill pipe and bit. Found tight spot at 132 ft. and worked through to 1380 ft., unable to go deeper, bit plugged, unable to circulate. Trip out with drill pipe and found drill bit was left in hole. 3 stands of drill pipe filled with shale and coal.

03-19-79 - Ran drill pipe open ended to screw into bit. Failed. Tripped drill pipe. Ran mill and milled from 1390 to 1430. Conditioned mud. Ran deviation survey and found hole off 7° at 1360. Pulled 10 stands &amp; shut down. (over)

Subsurface Safety Valve: Manu. and Type \_\_\_\_\_ Set @ \_\_\_\_\_ Ft.

18. I hereby certify that the foregoing is true and correct

SIGNED



TITLE

Engineer

DATE

March 22, 1979

(This space for Federal or State office use)

APPROVED BY


TITLE

DATE

CONDITIONS OF APPROVAL, IF ANY:

\*See Instructions on Reverse Side

mymoc



DO NOT use this form for proposals to drill or to design or plug back to a different reservoir. Use Form J-331-C for such proposals.

|       |                                     |             |                          |             |
|-------|-------------------------------------|-------------|--------------------------|-------------|
| other | <input checked="" type="checkbox"/> | 269<br>Well | <input type="checkbox"/> | 110<br>Well |
|-------|-------------------------------------|-------------|--------------------------|-------------|

5. NAME OF OPERATOR

J. Gregory Merrion & Robert L. Bayless

-20-79 - Continued clean out from 1430 ft. to 1460 ft. Circulated hole clean and tripped out leaving drill bit on bottom. Rig up Birdwell and ran IES Induction and Compensated Density Logs. Lay down drill pipe and shut down over night.

16. CHECK APPROPRIATE BOX TO INDICATE NATURE OF NOTICE  
-21-79 - Ran 1451 ft. of 2-7/8" EUE, 6.4 lb/ft.,  
C-45 casing and landed at 1451 ft. G.R.  
National cemented casing w/ 150 sxx Class  
'G' cement. Good circulation throughout  
mixing. Lost returns while displacing  
plug. Bumped plug w/ 1000 PSIG. PBD  
1441 ft. G.R. WOCT

ABANDON\*  
CHANGE ZONES  
MULTIPLE COMPLETE  
PULL OR ALTER CASING

James C. Miller & Co. (cont)

17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent b including estimated date of starting any proposed work. If well is directional drilling measured and true vertical depths for all markers and zones pertinent to this work).\*

## Instructions

General: This form is designed for submitting proposals to perform certain well operations, and reports of such operations when completed, as indicated, on Federal and Indian lands pursuant to applicable Federal law and regulations, and, if approved or accepted by any State, on all lands in such State, pursuant to applicable State law and regulations. Any necessary special instructions concerning the use of this form and the number of copies to be submitted, particularly with regard to local, area, or regional procedures and practices, either are shown below or will be issued by, or may be obtained from, the local Federal and/or State office.

Item 4: If there are no applicable State requirements, locations on Federal or Indian land should be described in accordance with Federal requirements. Consult local State or Federal office for specific instructions.

**Item 17:** Proposals to abandon a well and subsequent reports of abandonment should include such special information as is required by local Federal and/or State offices. In addition, such proposals and reports should include reasons for the abandonment; data on any former or present productive zones, or other zones with present significant fluid contents not sealed by cement or otherwise; depths (top and bottom) and method of placement of cement plugs; mud or other material placed below, between and above plugs; amount, size, method of parting of any casing, liner or tubing pulled and the depth to top of any left in the hole; method of closing top of well; and data well site conditioned for final inspection looking to approval of the abandonment.

4-FOUO: 1978 O - 214-148

31 AG

APPROVED BY \_\_\_\_\_ TITLE \_\_\_\_\_  
 \_\_\_\_\_

(See page 10 for details of the survey.)

1991:25

18. I hereby certify that the foregoing is true and correct

2. Substances 2a) and 2b) are

03-14-79 - Move in, Rig up L & B Speed Drill. Spud 9-1/4" 03-14-79 -  
03-15-79 - Drill out from under surface w/ 3" bit. Drilling 03-15-79 -  
03-17-79 - Reached total depth of 1460 ft. G.R. Preparing to 03-17-79 -  
03-18-79 - Rig up Birdwell. Ran IES Induction tool, found 03-18-79 -  
G.R., unable to get down. Pulled logging tool of 03-18-79 -  
with drill pipe and bit. Found tight spot at 1380 ft. 03-18-79 -  
to 1380 ft., unable to go deeper, bit plugged, 03-18-79 -  
out with drill pipe and found drill bit was left 03-18-79 -  
drill pipe filled with shale and coal. 03-18-79 -  
- Ran drill pipe open ended to screw into bit. 03-18-79 -  
Ran mill and milled from 1390 to 1430. Conditions 03-18-79 -  
survey and found hole off 7° at 1360. Pulled 13 03-18-79 -

1. ELEVATION 6501

2. ELEVATION 6501

3. ARI NO. 28114

4. COUNTY SEC. 12

5. AREA SEC. 12

6. FIELD NO. 8

7. WELL NO. We

8. FARM NO. 8

9. UNIT AG. 7

10. TOWN 28

11. LEASE 28

Page 2 of 2