

Submit 3 copies
to Appropriate
District Office

State of New Mexico
Energy, Minerals and Natural Resources Department

Form C-103
Revised 1-1-89

OIL CONSERVATION DIVISION


District I
P.O. Box 1980, Hobbs, NM 88240

2040 Pacheco St.
Santa Fe, NM 87505

District II
P.O. Box Drawer DD, Artesia, NM 88210

District III
1000 Rio Brazos Rd., Aztec, NM 87410

Well API No.	30-045-27298
5. Indicate Type of Lease	STATE <input checked="" type="checkbox"/> FEE <input type="checkbox"/>
6. State Oil & Gas Lease No.	E-3150-1
7. Lease Name or Unit Agreement Name	Northeast Blanco Unit
8. Well No.	#473
9. Pool name or Wildcat	Basin Frtl Coal



SUNDRY NOTICES AND REPORTS ON WELLS
(DO NOT USE THIS FORM FOR PROPOSALS TO DRILL OR TO DEEPEN OR
PLUG BACK TO A DIFFERENT RESERVOIR, USE "APPLICATION FOR PERMIT"
(FORM C-101) FOR SUCH PROPOSALS.)

1. Type of Well:
Oil Well Gas Well Other

2. Name of Operator **Devon Energy Corporation**

3. Address of Operator **3300 North Butler Ave. Suite 211 Farmington, NM 87401**

4. Well Location
Unit Letter G: **1850 Feet From the NORTH Line and 1780 Feet From the EAST Line**
Section **36** Township **31N** Range **R8W** NMPM County: **San Juan**

10. Elevation (Show whether DF, RKB, RT, GR, etc.)
6457' GL

11. Check Appropriate Box to Indicate Nature of Notice, Report, or Other Data

NOTICE OF INTENTION TO: X	SUBSEQUENT REPORT OF:
PERFORM REMEDIAL WORK <input type="checkbox"/>	PLUG & ABANDON <input type="checkbox"/>
TEMPORARILY ABANDON <input type="checkbox"/>	REMEDIAL WORK <input type="checkbox"/>
PULL OR ALTER CASING <input type="checkbox"/>	ALTERING CASING <input type="checkbox"/>
OTHER: CBM Re-Cavitation <input checked="" type="checkbox"/>	CHANGE PLANS <input type="checkbox"/>
	COMMENCE DRILLING OPNS. <input type="checkbox"/>
	CASING TEST & CEMENT JOB <input type="checkbox"/>
	PLUG & ABANDON <input type="checkbox"/>
	OTHER <input type="checkbox"/>

12. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work) See Rule 1103.

Devon Energy proposes to move in a coal cavitation rig and remove the uncemented existing 5 1/2" liner. The Fruitland Coal open hole interval will undergo a re-cavitation and cleanout process, and under reaming across the open hole interval to a diameter of approximately 10.5" from bottom of 7" casing to total depth. The well will not be deepened. At the end of the re-cavitation process, a 5 1/2" pre-drilled liner will be installed across the open hole interval and set in the 7" casing with a liner hanger assembly.

I herby certify that the information above is true and complete to the best of my knowledge and belief.

SIGNATURE: Lori Cave TITLE: Company Representative DATE: 4-3-00

TYPE OR PRINT NAME: Lori Cave TELEPHONE NO. (505) 324-0033

APPROVED BY: ORIGINAL SIGNED BY CAROL J. PERRIN TITLE: DEPUTY OIL & GAS INSPECTOR, DIST. 43 DATE: APR -5 2000

CONDITIONS OF APPROVAL IF ANY: