

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
Budget Bureau No. 1004-0135
Expires: March 31, 1993

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to deepen or reentry to a different reservoir.

Use "APPLICATION FOR PERMIT -" for such proposals

SUBMIT IN TRIPLICATE

1. Type of Well

☐ Oil Well ☒ Gas Well ☐ Other

2. Name of Operator

ENERGEN RESOURCES CORPORATION

3. Address and Telephone No.

2198 Bloomfield Highway, Farmington, NM 87401

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

2330' FSL, 1048' FEL, Sec. 30, T32N, R5W, N.M.P.M.

5. Lease Designation and Serial No.

NM-02850-B

6. If Indian, Allottee or Tribe Name

7. If Unit or CA, Agreement Designation

San Juan 32-5 Unit

8. Well Name and No.

San Juan 32-5 Unit 9M

9. API Well No.

30-039-25879

10. Field and Pool, or exploratory Area

Blanco Mesaverde

11. County or Parish, State

Rio Arriba NM

12. CHECK APPROPRIATE BOX(es) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

- ☐ Notice of Intent
☒ Subsequent Report
☐ Final Abandonment Notice

TYPE OF ACTION

- ☐ Abandonment
☐ Recompletion
☒ Plugging Back
☐ Casing Repair
☐ Altering Casing
☐ Other _____
- ☐ Change of Plans
☐ New Construction
☐ Non-Routine Fracturing
☐ Water Shut-Off
☐ Conversion to Injection
☐ Dispose Water

(Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)

7/19/00 MIRU

7/20/00 TOH with tubing. NU frac valve

7/21/00 Set CIBP @ 8000'. Dump bail 10 sx cement on top of CIBP. Perforate Point Lookout from 5796-5951', 35 holes. Acidized with 1000 gals 15% HCL. Frac with 75,329 gals slickwater & 64,300# 20/40 sand @ 48 BPM. Set CIBP @ 5720'.

7/25/00 Perforate Cliffhouse/Menefee from 5278-5692', 30 holes. Acidized with 1000 gals 15% HCL. Frac with 51,618 gals slickwater & 36,053# 20/40 sand @ 48 BPM. Set 4 1/2 CIBP @ 5100'. Perforate Lewis from 4540-5020', 32 holes. Acidized with 1000 gals 15% HCL. Frac with 60Q Delta 140, 44,394 gals water & 136,896# 20/40 sand @ 50 BPM.

7/26-7/31 Clean out sand to 5100', mill CIBP @ 5100', clean out to 5720', mill CIBP @ 5720'.

8/1/00 RIH with pump out plug, 1 jt 2 3/8" tubing, seating nipple, 181 jts 2 3/8" tubing. Land @ 5891'.

Pump out plug, circ. well, RDMO.

14. I hereby certify that the foregoing is true and correct

Signed Monica Papp

Title Production Assistant


Date 8/8/2000

(This space for Federal or State office use)

Approved by _____

Title _____

Conditions of approval, if any: _____



ACCEPTED FOR RECORD

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

* See Instruction on Reverse Side

NMOCB

AUG 15 2000