

UNITED STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEY

SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir. Use Form 9-331-C for such proposals.)

1. oil ☐ well gas ☒ well other ☐
2. NAME OF OPERATOR
El Paso Natural Gas Company
3. ADDRESS OF OPERATOR
Box 289, Farmington, New Mexico 87401
4. LOCATION OF WELL (REPORT LOCATION CLEARLY. See space 17 below.)
1550'S, 1710'E
AT SURFACE:
AT TOP PROD. INTERVAL:
AT TOTAL DEPTH:

16. CHECK APPROPRIATE BOX TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA


REQUEST FOR APPROVAL TO:		SUBSEQUENT REPORT OF:
TEST WATER SHUT-OFF	<input type="checkbox"/>	<input type="checkbox"/>
FRACTURE TREAT	<input type="checkbox"/>	<input checked="" type="checkbox"/>
SHOOT OR ACIDIZE	<input type="checkbox"/>	<input type="checkbox"/>
REPAIR WELL	<input type="checkbox"/>	<input type="checkbox"/>
PULL OR ALTER CASING	<input type="checkbox"/>	<input type="checkbox"/>
MULTIPLE COMPLETE	<input type="checkbox"/>	<input type="checkbox"/>
CHANGE ZONES	<input type="checkbox"/>	<input type="checkbox"/>
ABANDON*	<input type="checkbox"/>	<input type="checkbox"/>
(other)	<input type="checkbox"/>	<input type="checkbox"/>

5. LEASE
SF078096
6. IF INDIAN, ALLOTTEE OR TRIBE NAME
7. UNIT AGREEMENT NAME
8. FARM OR LEASE NAME
Mudge
9. WELL NO.
1A (PM)
10. FIELD OR WILDCAT NAME
Aztec PC Ext. & Blanco M.V.
11. SEC., T., R., M., OR BLK. AND SURVEY OR AREA Sec. 21, T-31-N, R-11-W N.M.P.M.
12. COUNTY OR PARISH
San Juan
13. STATE
New Mexico
14. API NO.
15. ELEVATIONS (SHOW DF, KDB, AND WD)
5838' G.L.

(NOTE: Report results of multiple completion or zone change on Form 9-330.)

17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

9-29-79: PBTD 5134'. Tested casing 3500#, OK. Perfed 4692,4698,4704,4710,4716,4730, 4736,4742,4748,4754,4760,4766,4772,4778,4783,4801,4810,4825,4834,4860, 4935,4946,4968,4991,5018,5027,5041,5102' W/1 SPZ. Fraced w/ 102,000# 20/40 sand, 188,000 gal. wtr. Flushed w/ 6100 gal. wtr. Perfed 4534,4549,4558,4567, 4584,4596,4611' W/1 SPZ. Fraced w/27,500# 20/40 sand,55,000 gal. wtr. Flushed w/5,760 gal. wtr. Perfed 2438-2453,2472-2494,2518-2524,2535-2542,2546-2559, 2564-2574' W/16 SPZ. Fraced w/73,500# 10/20 sand, 58,800 gal. wtr. Dropped 5 sets of 16 balls each. Flushed w/4400 gal. wtr.



Subsurface Safety Valve: Manu. and Type

Set @ Ft.

18. I hereby certify that the foregoing is true and correct

SIGNED D. G. Buico TITLE Drilling Clerk DATE October 2, 1979

(This space for Federal or State office use)

APPROVED BY _____ TITLE _____ DATE _____
CONDITIONS OF APPROVAL, IF ANY:

*See Instructions on Reverse Side

NMOCC

