

UNITED STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEY

SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir. Use Form 9-331-C for such proposals.)

1. oil ☐ well ☐ gas ☒ well ☐ other
2. NAME OF OPERATOR
Southland Royalty Company
3. ADDRESS OF OPERATOR
P.O. Drawer 570, Farmington, New Mexico 87401
4. LOCATION OF WELL (REPORT LOCATION CLEARLY. See space 17 below.)
AT SURFACE: *1590' FNL & 1070' FEL*
AT TOP PROD. INTERVAL:
AT TOTAL DEPTH:
16. CHECK APPROPRIATE BOX TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA


5. LEASE
SF-077651
6. IF INDIAN, ALLOTTEE OR TRIBE NAME
7. UNIT AGREEMENT NAME
8. FARM OR LEASE NAME
Richardson
9. WELL NO.
8-E
10. FIELD OR WILDCAT NAME
Basin Dakota/Blanco Pictured Cliffs
11. SEC., T., R., M., OR BLK. AND SURVEY OR AREA
Section 10, T31N, R12W
12. COUNTY OR PARISH | 13. STATE
San Juan | New Mexico
14. API NO.
15. ELEVATIONS (SHOW DF, KDB, AND WD)
6183' GR

REQUEST FOR APPROVAL TO:

- TEST WATER SHUT-OFF ☐
FRACTURE TREAT ☐
SHOOT OR ACIDIZE ☐
REPAIR WELL ☐
PULL OR ALTER CASING ☐
MULTIPLE COMPLETE ☐
CHANGE ZONES ☐
ABANDON* ☐
(other) ☒ *Casing Report*

SUBSEQUENT REPORT OF:

- ☐
☐
☐
☐
☐
☐
☐
☐
☒



17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

- 6-14-80 Ran 110 joints (4913.15') of 7", 23#, K-55 casing set at 4929'. Stage Tool at 2946'. Cemented 1st Stage with 100 sacks of Class "B" 50/50 Poz with 6% gel followed by 50 sacks of Class "B" with 2% CaCl₂. Plug down at 11:45 P.M. 6-14-80. Cemented 2nd Stage with 170 sacks of Class "B" 50/50 Poz with 6% gel followed by 70 sacks of Class "B" with 2% CaCl₂. Plug down at 1:15 A.M. 6-15-80. Top of Cement at 1700'.
- 7-02-80 Ran 67 joints (2672.38') of 4-1/2", 11.6# & 10.5#, K-55 casing set from 4761'-7448'. Cemented with 315 sacks of Class "B" 50/50 Poz with 6% gel, 1/4# gel flake per sack and .6% Halad 9. Plug down at 10:00 P.M. 7-02-80.
WOCT...

Subsurface Safety Valve: Manu. and Type _____ Set @ _____ Ft.

18. I hereby certify that the foregoing is true and correct

SIGNED *[Signature]* TITLE *Dist. Prod. Mgr.* DATE *July 3, 1980*

(This space for Federal or State office use)

APPROVED BY _____ TITLE _____ DATE _____
CONDITIONS OF APPROVAL, IF ANY:

ACCEPTED FOR DEPOSIT
JUL 11 1980
BY *[Signature]*