

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

SUBMIT IN TRIPLICATE
(Other instructions on re-
verse side).

Form approved.
Budget Bureau No. 1004-0135

SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir.
Use "APPLICATION FOR PERMIT—" for such proposals.)

1. Oil <input type="checkbox"/> Well Gas <input checked="" type="checkbox"/> Well Other		5. LEASE DESIGNATION AND SERIAL NO. NMSF-078463	
2. NAME OF OPERATOR CHATEAU OIL and GAS, INC.		6. IF INDIAN, ALLOTTEE OR TRIBE NAME	
3. ADDRESS OF OPERATOR 5802 HIGHWAY 64, FARMINGTON, NM 87401		7. UNIT AGREEMENT NAME 30-45-24.348	
4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements.* See also space 17 below.) At surface 1100' FSL and 1100' FEL		8. FARM OR LEASE NAME Langendorf	
		9. WELL NO. 1E	
		10. FIELD AND POOL, OR WILDCAT Basin Dakota	
		11. SEC., T., R., M., OR BLK. AND SURVEY OR AREA Sec. 34, T31N, R13W	
14. PERMIT NO.	15. ELEVATIONS (Show whether DF, RT, GR, etc.)	12. COUNTY OR PARISH San Juan	13. STATE NM

16.

Check Appropriate Box To Indicate Nature of Notice, Report, or Other Data

NOTICE OF INTENTION TO:

TEST WATER SHUT-OFF ☐
FRACTURE TREAT ☐
SHOOT OR ACIDIZE ☐
REPAIR WELL ☐
(Other) _____

PULL OR ALTER CASING ☐
MULTIPLE COMPLETE ☐
ABANDON* ☐
CHANGE PLANS ☐

SUBSEQUENT REPORT OF:

WATER SHUT-OFF ☐
FRACTURE TREATMENT ☐
SHOOTING OR ACIDIZING ☐
(Other) _____

REPAIRING WELL ☐
ALTERING CASING ☐
ABANDONMENT* ☒

(NOTE: Report results of multiple completion on Well
Completion or Recompletion Report and Log form.)

17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

12-11-97 Plug and Abandoned well according to BLM approved procedure.
(See attached P&A Operation Cement Service Report)

RECEIVED
APR 13 1998
OIL CON. DIV.
DIST. 3

RECEIVED
BLM
98 APR -9 AM 10:48
070 FARMINGTON, NM

18. I hereby certify that the foregoing is true and correct

SIGNED Chester L. Deal TITLE Superintendent DATE 07-Apr-98

(This space for Federal or State office use)

APPROVED BY /s/ Joe Hewitt TITLE _____ DATE APR 10 1998


CONDITIONS OF APPROVAL, IF ANY:

***See Instructions on Reverse Side**

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and wilfully to make any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

RECEIVED
JAN 10 1964

ATLANTA, GA
JAN 10 1964



P.O. Drawer 3337, 700 S. Tucker, Farmington, New Mexico 87499
(505) 327-4961 • 24-Hour Dispatch (505) 325-6892 • (505) 327-0416

P&A OPERATION CEMENT SERVICE REPORT

WELL NAME: LANGENDORF #1-E

TOTAL PLUGS SET: 6

DATE STARTED: 12-09-97

TOTAL SACKS USED: 227 sx.

DATE COMPLETED: 12-11-97

BLM WITNESS: J. MORRIS
OPERATOR WITNESS: N/A

PLUG # 1 (6300'-6450')

RIH W/ 5 1/2" GAUGE RING TO 6470'. PU 5 1/2" RETAINER AND STRAPPED IN HOLE TO 6450'. TESTED TUBING TO 1000 PSI AND HELD OK. SET RETAINER @ 6450'. LOADED AND CIRCULATED HOLE W/ WATER. PRESSURE TESTED CASING TO 500 PSI FOR 10 MINUTES, HELD OK. PLACED 17 SX CLASS B CEMENT TO COVER PERFORATIONS AND THE DAKOTA.

PLUG # 2 (5551'-5701')

PUH TO 5701'. PLACED 17 SX CLASS B CEMENT TO COVER THE GALLUP.

PLUG # 3 (3464'-3614')

PUH TO 3614'. PLACED 17 SX CLASS B CEMENT TO COVER THE MESAVERDE.

PLUG # 4 (1871'-2021')


PUH TO 2021'. PLACED 17 SX CLASS B CEMENT TO COVER THE PICTURED CLIFFS.

PLUG # 5 (1500'-1650')

PUH TO 1650'. PLACED 17 SX CLASS B CEMENT TO COVER THE FRUITLAND.

PLUG # 6 (0'-381')

POOH. RIH AND PERFORATED 2 SQUEEZE HOLES @ 381'. ESTABLISHED CIRCULATION OUT BRADON HEAD WITH WATER. MIXED AND PUMPED 142 SX CLASS B CEMENT TO CIRCULATE GOOD CEMENT TO SURFACE.


NATHAN CRAWFORD
P&A SUPERVISOR