

OIL CONSERVATION DIVISION
P. O. BOX 2088
SANTA FE, NEW MEXICO 87501

Form C-103
Revised 10-1-78

NO. OF COPIES RECEIVED		
DISTRIBUTION		
SANTA FE		
FILE		
U.S.G.S.		
LAND OFFICE		
OPERATOR		

5a. Indicate Type of Lease
State ☐ Fee ☒
5. State Oil & Gas Lease No.

SUNDRY NOTICES AND REPORTS ON WELLS
(DO NOT USE THIS FORM FOR PROPOSALS TO DRILL OR TO DEEPEN OR PLUG BACK TO A DIFFERENT RESERVOIR.
USE "APPLICATION FOR PERMIT -" (FORM C-101) FOR SUCH PROPOSALS.)


1. OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER-	7. Unit Agreement Name
2. Name of Operator Southland Royalty Company	8. Farm or Lease Name Harper
3. Address of Operator P.O. Drawer 570, Farmington, New Mexico 87401	9. Well No. 3
4. Location of Well UNIT LETTER <u>P</u> <u>970</u> FEET FROM THE <u>South</u> LINE AND <u>1090</u> FEET FROM THE <u>East</u> LINE, SECTION <u>14</u> TOWNSHIP <u>31 North</u> RANGE <u>12 West</u> N.M.P.M.	10. Field and Pool, or Wildcat Aztec Pictured Cliffs/ Undesignated Fruitland
15. Elevation (Show whether DF, RT, GR, etc.) 6178' GR	12. County San Juan

16. Check Appropriate Box To Indicate Nature of Notice, Report or Other Data
NOTICE OF INTENTION TO: SUBSEQUENT REPORT OF:

PERFORM REMEDIAL WORK <input type="checkbox"/>	PLUG AND ABANDON <input type="checkbox"/>	REMEDIAL WORK <input type="checkbox"/>	ALTERING CASING <input type="checkbox"/>
TEMPORARILY ABANDON <input type="checkbox"/>	CHANGE PLANS <input type="checkbox"/>	COMMENCE DRILLING OPNS. <input type="checkbox"/>	PLUG AND ABANDONMENT <input type="checkbox"/>
PULL OR ALTER CASING <input type="checkbox"/>	OTHER <input type="checkbox"/>	CASING TEST AND CEMENT JOB <input type="checkbox"/>	OTHER <u>Perforation & Stimulation</u> <input checked="" type="checkbox"/>

17. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work) SEE RULE 1103.

10-07-81 Perforated Fruitland at 2483', 2493', 2498', 2503', 2531', 2540', 2545', 2550'.
Total of 8 holes.
Perforated Pictured Cliffs at 2712', 2720', 2728', 2736', 2755', 2764', 2810'.
Total of 7 holes.
Frac'd Pictured Cliffs with 51,822 gallons of slick water and 43,000# of 20/40 sand. AIR 13 BPM, ATP 1500 psi, ISIP 200 psi.
Frac'd Fruitland with 43,604 gallons slick water and 36,000# of 20/40 sand.
AIR 15 BPM, ATP 2400 psi, ISIP 900 psi.



18. I hereby certify that the information above is true and complete to the best of my knowledge and belief.

SIGNED Ethel Greengard TITLE Drilling Clerk DATE October 8, 1981

APPROVED BY Original Signed by FRANK T. CHAVEZ TITLE SUPERVISOR DISTRICT 3 DATE OCT 13 1981

CONDITIONS OF APPROVAL, IF ANY: