

(SUBMIT IN TRIPLICATE)

Indian Agency Jicarilla

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
GEOLOGICAL SURVEY

Contract No. 14  
Tract No. 22  
Allottee \_\_\_\_\_  
Lease No. \_\_\_\_\_

SUNDRY NOTICES AND REPORTS ON WELLS

NOTICE OF INTENTION TO DRILL	<input checked="" type="checkbox"/>	SUBSEQUENT REPORT OF WATER SHUT-OFF	
NOTICE OF INTENTION TO CHANGE PLANS		SUBSEQUENT REPORT OF SHOOTING OR ACIDIZING	
NOTICE OF INTENTION TO TEST WATER SHUT-OFF		SUBSEQUENT REPORT OF ALTERING CASING	
NOTICE OF INTENTION TO REDRILL OR REPAIR WELL		SUBSEQUENT REPORT OF REDRILLING	
NOTICE OF INTENTION TO SHOOT OR ACIDIZE		SUBSEQUENT REPORT OF ABANDONMENT	
NOTICE OF INTENTION TO PULL OR ALTER CASING		SUPPLEMENTARY WELL HISTORY	
NOTICE OF INTENTION TO ABANDON WELL			

(INDICATE ABOVE BY CHECK MARK NATURE OF REPORT, NOTICE, OR OTHER DATA)

June 28, 1955

Well No. B-1 is located 1030 ft. from N line and 600 ft. from W line of sec. 28

SW/4 SW/4, Sec. 28  
(1/4 Sec. and Sec. No.)

T 23 N  
(Twp.)

R-3-W  
(Range)

NMPM  
(Meridian)

Unnamed  
(Field)

Sandoval  
(County or Subdivision)

New Mexico  
(State or Territory)


The elevation of the derrick floor above sea level is 7479 ft. (Estimated)

Ground elevation is 7468' above sea level.

DETAILS OF WORK

(State names of and expected depths to objective sands; show sizes, weights, and lengths of proposed casings; indicate mudding jobs, cementing points, and all other important proposed work)

Reynolds proposes to drill this well to 7600' total depth. Approximately 350 feet of 10 3/4-inch, 32.75 pound, N-40 casing will be run with a sufficient amount of cement to completely encase the casing from bottom to top. All prospective oil and gas zones will be adequately tested by coring and/or drill stem testing. Mud will be used from the surface of the ground to total depth in order to insure good samples. The objective sand is expected at the approximate depth of 7250'. If oil and gas are found to be in commercial quantities, 5 1/2-inch casing will be run and cemented with sufficient cement to protect all commercial oil and gas zones.



I understand that this plan of work must receive approval in writing by the Geological Survey before operations may be commenced.

Company Reynolds Mining Corporation  
Oil and Gas Division  
Address 1030 1/2 Main Avenue  
Box 1328  
Durango, Colorado  
Phone 901

By C. C. McFarland  
C. C. McFarland  
Title Petroleum Engineer

Asiatic Paper Co.

being a  $3N$ -fold

Section No. 7466, ungraded ground. (Reynolds Mining Corp., datum)

RECEIVED

U. S. GEOLOGICAL SURVEY  
FARMINGTON, NEW MEXICO

26

DATE: June 27 1955

This is to certify that the above plot was prepared from field notes taken by me personally under my supervision and that the same are true and correct to the best of my knowledge and belief.

[illegible]