

OCD Hobbs

HOBBS OCD

ATS-15-59

FORM APPROVED  
OMB No. 1004-0137  
Expires October 31, 2014

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT

JUL 02 2015

APPLICATION FOR PERMIT TO DRILL OR REENTER

|                                                                                                                                                                                                             |  |                                                                                                                                                     |  |
|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--|-----------------------------------------------------------------------------------------------------------------------------------------------------|--|
| 1a. Type of work: <input checked="" type="checkbox"/> DRILL <input type="checkbox"/> REENTER                                                                                                                |  | 7. If Unit or CA Agreement, Name and No.                                                                                                            |  |
| 1b. Type of Well: <input checked="" type="checkbox"/> Oil Well <input type="checkbox"/> Gas Well <input type="checkbox"/> Other <input type="checkbox"/> Single Zone <input type="checkbox"/> Multiple Zone |  | 8. Lease Name and Well No. (313895)<br>SALADO DRAW 18 26 33 FED #1H                                                                                 |  |
| 2. Name of Operator CHEVRON USA INC (4323)                                                                                                                                                                  |  | 9. API Well No.<br>70-025-42659                                                                                                                     |  |
| 3a. Address 1616 W. BENDER BLVD<br>HOBBS, NM 88240                                                                                                                                                          |  | 10. Field and Pool, or Exploratory (97955)<br>WB-025 G-06 52633EP:AS                                                                                |  |
| 3b. Phone No. (include area code)<br>575-263-0431                                                                                                                                                           |  | 11. Sec., T. R. M. or Blk. and Survey or Area<br>SEC 19 T26S, R33E: UL D (SHL)<br>SEC 18 T26S, R33E: UL D (BHL)                                     |  |
| 4. Location of Well (Report location clearly and in accordance with any State requirements. *)<br>At surface 200' FNL & 873' FWL (D1)<br>At proposed prod. zone 280' FNL & 355' FWL (D1)                    |  | 12. County or Parish<br>LEA                                                                                                                         |  |
| 14. Distance in miles and direction from nearest town or post office*<br>50 MILES WEST OF JAL, NEW MEXICO                                                                                                   |  | 13. State<br>NM                                                                                                                                     |  |
| 15. Distance from proposed* location to nearest property or lease line, ft. (Also to nearest drig. unit line, if any)<br>200' FNL                                                                           |  | 16. No. of acres in lease<br>1517.74(NMNM27506)                                                                                                     |  |
| 17. Spacing Unit dedicated to this well<br>160.0 ACRES                                                                                                                                                      |  | 18. Distance from proposed location* to nearest well, drilling, completed, applied for, on this lease, ft.<br>1370 FT FROUM GULF LITTLEFIELD FED #1 |  |
| 19. Proposed Depth<br>TVD 9105'<br>MD 9402' 13793                                                                                                                                                           |  | 20. BLM/BIA Bond No. on file<br>CA 0329                                                                                                             |  |
| 21. Elevations (Show whether DF, KDB, RT, GL, etc.)<br>3176' GL                                                                                                                                             |  | 22. Approximate date work will start*                                                                                                               |  |
| 23. Estimated duration                                                                                                                                                                                      |  |                                                                                                                                                     |  |

24. Attachments

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No. I, must be attached to this form:

1. Well plat certified by a registered surveyor.
2. A Drilling Plan.
3. A Surface Use Plan (if the location is on National Forest System Lands, the SUPO must be filed with the appropriate Forest Service Office).
4. Bond to cover the operations unless covered by an existing bond on file (see Item 20 above).
5. Operator certification
6. Such other site specific information and/or plans as may be required by the BLM.

|                                        |                                               |                    |
|----------------------------------------|-----------------------------------------------|--------------------|
| 25. Signature<br>Cindy Herrera-Murillo | Name (Printed/Typed)<br>CINDY HERRERA-MURILLO | Date<br>09/16/2014 |
|----------------------------------------|-----------------------------------------------|--------------------|

Title

PERMITTING SPECIALIST

|                                         |                      |                      |
|-----------------------------------------|----------------------|----------------------|
| Approved by (Signature)<br>Steve Caffey | Name (Printed/Typed) | Date<br>JUL 1 - 2015 |
|-----------------------------------------|----------------------|----------------------|

Title

FIELD MANAGER

Office

CARLSBAD FIELD OFFICE

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Conditions of approval, if any, are attached.

APPROVAL FOR TWO YEARS

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Continued on page 2)

\*(Instructions on page 2)

Carlsbad Controlled Water Basin

KZ  
07/06/15

SEE ATTACHED FOR  
CONDITIONS OF APPROVAL

Approval Subject to General Requirements  
& Special Stipulations Attached

JUL 07 2015

HOBBS OCD

JUL 02 2015

RECEIVED

### 1. FORMATION TOPS

The estimated tops of important geologic markers are as follows:

| FORMATION                 | SUB-SEA TVD | KBTVD | MD    |
|---------------------------|-------------|-------|-------|
| Rustler                   | 2502        | 700   |       |
| Castile                   | 202         | 3000  |       |
| Lamar                     | -1598       | 4800  |       |
| Bell Canyon               | -1738       | 4940  |       |
| Cherry Canyon             | -2623       | 5825  |       |
| Brushy Canyon             | -4198       | 7400  |       |
| Bone Spring Limestone     | -5563       | 8765  |       |
| Upr. Avalon               | -5693       | 8895  |       |
|                           |             |       |       |
|                           |             |       |       |
|                           |             |       |       |
| Lateral TD (Upper Avalon) | -5908       | 9110  | 13793 |

### 2. ESTIMATED DEPTH OF WATER, OIL, GAS & OTHER MINERAL BEARING FORMATIONS

The estimated depths at which the top and bottom of the anticipated water, oil, gas, or other mineral bearing formations are expected to be encountered are as follows:

| Substance                            | Formation             | Depth |
|--------------------------------------|-----------------------|-------|
| Deepest Expected Base of Fresh Water |                       | 700   |
| Water                                | Rustler               | 700   |
| Water                                | Bell Canyon           | 4940  |
| Water                                | Cherry Canyon         | 5825  |
| Oil/Gas                              | Brushy Canyon         | 7400  |
| Oil/Gas                              | Bone Spring Limestone | 8765  |
| Oil/Gas                              | Upr. Avalon           | 8895  |
|                                      |                       |       |
|                                      |                       |       |

All shows of fresh water and minerals will be reported and protected.

### 3. BOP EQUIPMENT

Will have a minimum of a 5000 psi rig stack (see proposed schematic) for drill out below surface casing.

Stack will be tested as specified in the attached testing requirements.

Chevron requests a variance to use a GE/Vetco SH-2 Multibowl wellhead, which will be run through the rig floor on surface casing. BOPE will be nipped up and tested after cementing surface casing. Subsequent tests will be performed as needed, not to exceed 30 days. The field report from GE/Vetco and BOP test information will be provided in a subsequent report at the end of the well. Please see the attached wellhead schematic. An installation manual has been placed on file with the BLM office and remains unchanged from previous submittal.

#### 4. CASING PROGRAM

a. The proposed casing program will be as follows:

| Purpose      | From                                   | To      | Hole Size | Csg Size | Weight | Grade   | Thread | Condition |
|--------------|----------------------------------------|---------|-----------|----------|--------|---------|--------|-----------|
| Surface      | 0'                                     | 800'    | 17-1/2"   | 13-3/8"  | 48 #   | H-40    | STC    | New       |
| Intermediate | 0' <del>4,900'</del> <sup>4,260'</sup> | 13,793' | 12-1/4"   | 9-5/8"   | 40 #   | HCK-55  | LTC    | New       |
| Production   | 0'                                     | 13,793' | 8-3/4"    | 5-1/2"   | 17.0 # | HCP-110 | CDC    | New       |

b. Casing design subject to revision based on geologic conditions encountered.

c. \*\*\*A "Worst Case" casing design for wells in a particular area is used below to calculate the Casing Safety Factors. If for any reason the casing design for a particular well requires setting casing deeper than the following "worst case" design, then the Casing Safety Factors will be recalculated & sent to the BLM prior to drilling.

d. Chevron will fill casing at a minimum of every 20 jts (840') while running for intermediate and production casing in order to maintain collapse SF.

#### SF Calculations based on the following "Worst Case" casing design:

Surface Casing: 1000'  
Intermediate Casing: 5000'  
Production Casing: 17,426' MD/10,240' TVD (6900' VS @ 90 deg inc)

| Casing String | Min SF Burst | Min SF Collapse | Min SF Tension | Min SF Tri-Axial |
|---------------|--------------|-----------------|----------------|------------------|
| Surface       | 1.42         | 1.63            | 2.29           | 1.8              |
| Intermediate  | 1.24         | 1.44            | 2.09           | 1.32             |
| Production    | 1.26         | 1.71            | 2.2            | 1.46             |

Min SF is the smallest of a group of safety factors that include the following considerations:

|                                                                                                                        | Surf | Int | Prod |
|------------------------------------------------------------------------------------------------------------------------|------|-----|------|
| <b>Burst Design</b>                                                                                                    |      |     |      |
| Pressure Test- Surface, Int, Prod Csg<br>P external: Water<br>P internal: Test psi + next section heaviest mud in csg  | X    | X   | X    |
| Displace to Gas- Surf Csg<br>P external: Water<br>P internal: Dry Gas from Next Csg Point                              | X    |     |      |
| Frac at Shoe, Gas to Surf- Int Csg<br>P external: Water<br>P internal: Dry Gas, 15 ppg Frac Gradient                   |      | X   |      |
| Stimulation (Frac) Pressures- Prod Csg<br>P external: Water<br>P internal: Max inj pressure w/ heaviest injected fluid |      |     | X    |
| Tubing leak- Prod Csg (packer at KOP)<br>P external: Water<br>P internal: Leak just below surf, 8.7 ppg packer fluid   |      |     | X    |
| <b>Collapse Design</b>                                                                                                 |      |     |      |
| Full Evacuation<br>P external: Water gradient in cement, mud above TOC<br>P internal: none                             | X    | X   | X    |
| Cementing- Surf, Int, Prod Csg<br>P external: Wet cement<br>P internal: water                                          | X    | X   | X    |
| <b>Tension Design</b>                                                                                                  |      |     |      |
| 100k lb overpull                                                                                                       | X    | X   | X    |

## 5. CEMENTING PROGRAM

| Slurry       | Type                                                                                            | Top     | Bottom  | Weight | Yield      | %Excess   | Sacks | Water  |
|--------------|-------------------------------------------------------------------------------------------------|---------|---------|--------|------------|-----------|-------|--------|
| Surface      |                                                                                                 |         |         | (ppg)  | (sx/cu ft) | Open Hole |       | gal/sk |
| Tail         | Class C+2%CaCl                                                                                  | 0'      | 800'    | 14.8   | 1.35       | 125       | 953   | 6.57   |
| Intermediate |                                                                                                 |         |         |        |            |           |       |        |
| Lead         | EconoCem C + 3 lb/sk<br>Kol-Seal + 0.125 lb/sk<br>PolyFlake + 0.1% HR-601 + 0.25% D-Air 5000    | 0'      | 3,920'  | 11.9   | 2.46       | 150       | 1116  | 14.21  |
| Tail         | HalCem C                                                                                        | 3,920'  | 4,900'  | 14.8   | 1.33       | 85        | 456   | 6.37   |
| Production   |                                                                                                 |         |         |        |            |           |       |        |
| 1st Lead     | VariCem-PB1 + 0.1%<br>FWCA + 3 lb/sk Kol-Seal + 0.1% HR-601                                     | 4,050'  | 8,674'  | 11.3   | 2.54       | 50        | 650   | 15.51  |
| 2nd Lead     | VariCem-PB2 + 0.5%<br>Halad-344 + 0.3%<br>CFR-3 + 3 lb/sk<br>KolSeal + 0.05% FE-2 + 0.1% HR-601 | 8,674'  | 12,645' | 12.5   | 1.81       | 35        | 751   | 9.64   |
| Tail         | SoluCem H + 0.25<br>lb/sk D-Air 5000                                                            | 12,645' | 13,793' | 15     | 2.63       | 0         | 110   | 11.42  |

1. Final cement volumes will be determined by caliper.
2. Surface casing shall have at least one centralizer installed on each of the bottom three joints starting with the shoe joint.
3. Production casing will have one horizontal type centralizer on every joint for the first 1000' from TD, then every other joint to EOB, and then every third joint to KOP. Bowspring type centralizers will be run from KOP to intermediate casing.

## 6. MUD PROGRAM

| From   | To      | Type         | Weight     | F. Vis  | Filtrate |
|--------|---------|--------------|------------|---------|----------|
| 0'     | 800'    | Spud Mud     | 8.3 - 8.7  | 32 - 34 | NC - NC  |
| 800'   | 4,900'  | Brine        | 9.5 - 10.1 | 28 - 30 | NC - NC  |
| 4,900' | 8,674'  | FW/Cut Brine | 8.3 - 9.6  | 28 - 30 | NC - NC  |
| 8,674' | 9,402'  | Cut Brine    | 8.3 - 9.6  | 28 - 30 | 15 - 25  |
| 9,402' | 13,793' | FW/Cut Brine | 8.3 - 9.6  | 28 - 30 | 15 - 25  |

A closed system will be utilized consisting of above ground steel tanks. All wastes accumulated during drilling operations will be contained in a portable trash cage and removed from location and deposited in an approved sanitary landfill. Sanitary wastes will be contained in a chemical porta-toilet and then hauled to an approved sanitary landfill.

All fluids and cuttings will be disposed of in accordance with New Mexico Oil Conservation Division rules and regulations.

A mud test shall be performed every 24 hours after mudding up to determine, as applicable: density, viscosity, gel strength, filtration, and pH.

Visual mud monitoring equipment shall be in place to detect volume changes indicating loss or gain of circulating fluid volume. When abnormal pressures are anticipated -- a pit volume totalizer (PVT), stroke counter, and flow sensor will be used to detect volume changes indicating loss or gain of circulating fluid volume.

A weighting agent and lost circulating material (LCM) will be onsite to mitigate pressure or lost circulation as hole conditions dictate.

## 7. TESTING, LOGGING, AND CORING

The anticipated type and amount of testing, logging, and coring are as follows:

- Drill stem tests are not planned.
- The logging program will be as follows:

| TYPE    | Logs         | Interval            | Timing              | Vendor |
|---------|--------------|---------------------|---------------------|--------|
| Mudlogs | 2 man mudlog | Int Csg to TD       | Drillout of Int Csg | TBD    |
| LWD     | MWD Gamma    | Int. and Prod. Hole | While Drilling      | TBD    |

- Conventional whole core samples are not planned.
- A Directional Survey will be run.

## 8. ABNORMAL PRESSURES AND HYDROGEN SULFIDE

- No abnormal pressures or temperatures are expected. Estimated BHP is: 4450 psi
- Hydrogen sulfide gas is not anticipated. An H<sub>2</sub>S Contingency plan is attached with this APD in the event that H<sub>2</sub>S is encountered





Project: Lea County NM (NAD27 NME)  
Site: Salado Draw 18 26 33 Fed  
Well: 1H  
Wellbore: #1  
Design: Plan #1 07-25-14  
Rig: Planning



PHOENIX  
TECHNOLOGY SERVICES



Azimuths to Grid North  
True North: -0.38°  
Magnetic North: 6.83°  
Magnetic Field  
Strength: 48188.7 nT  
Dip Angle: 59.93°  
Date: 2014/07/25  
Model: IGRF2010\_14






| WELL DETAILS          |      |           |           |                  |                     |  |  |  |  |
|-----------------------|------|-----------|-----------|------------------|---------------------|--|--|--|--|
| Ground Level: 3176.00 |      |           |           |                  |                     |  |  |  |  |
| +N-S                  | +E-W | Northing  | Easting   | Latitude         | Longitude           |  |  |  |  |
| 0.00                  | 0.00 | 377410.00 | 722122.00 | 32° 2' 8.11866 N | 103° 36' 59.50691 W |  |  |  |  |

| SECTION DETAILS |          |       |        |         |         |         |       |        |         |                                 |                                          |
|-----------------|----------|-------|--------|---------|---------|---------|-------|--------|---------|---------------------------------|------------------------------------------|
| Sec             | MD       | Inc   | Azi    | TVD     | +N-S    | +E-W    | Dleg  | TFace  | VSec    | Target                          | Annotation                               |
| 1               | 0.00     | 0.00  | 0.00   | 0.00    | 0.00    | 0.00    | 0.00  | 0.00   | 0.00    | 0.00                            | KOP1, Start 1'100' Build                 |
| 2               | 1200.00  | 0.00  | 0.00   | 1200.00 | 0.00    | 0.00    | 0.00  | 0.00   | 0.00    | 0.00                            | EOB, Start hold at 4.68' Inc             |
| 3               | 1667.73  | 4.68  | 303.95 | 1667.21 | 10.66   | -15.83  | 1.00  | 303.95 | 12.27   |                                 | KOP2, Start 12'100' Build                |
| 4               | 8674.37  | 4.68  | 303.95 | 8650.52 | 329.76  | -489.76 | 0.00  | 0.00   | 379.55  |                                 | LP, 89.93° Inc, 359.64° Azm - Start hold |
| 5               | 9401.87  | 89.93 | 359.64 | 9105.00 | 805.98  | -523.43 | 12.00 | 55.78  | 856.66  |                                 |                                          |
| 6               | 13792.98 | 89.93 | 359.64 | 9110.00 | 5197.00 | -551.00 | 0.00  | 0.00   | 5228.13 | BHL Salado Draw 18 26 33 Fed 1H | TD at 13792.98' MD                       |

| DESIGN TARGET DETAILS           |         |         |         |           |           |                   |                    |       |  |  |  |
|---------------------------------|---------|---------|---------|-----------|-----------|-------------------|--------------------|-------|--|--|--|
| Name                            | TVD     | +N-S    | +E-W    | Northing  | Easting   | Latitude          | Longitude          | Shape |  |  |  |
| BHL Salado Draw 18 26 33 Fed 1H | 9110.00 | 5197.00 | -551.00 | 382607.00 | 721571.00 | 32° 2' 59.58378 N | 103° 37' 5.50789 W | Point |  |  |  |
| - plan hits target center       |         |         |         |           |           |                   |                    |       |  |  |  |

Map System: US State Plane 1927 (Exact solution)  
Datum: NAD 1927 (NADCON CONUS)  
Ellipsoid: Clarke 1866  
Zone Name: New Mexico East 3001  
Local Origin: Well 1H, Grid North  
Latitude: 32° 2' 8.11866 N  
Longitude: 103° 36' 59.50691 W  
Grid East: 722122.00  
Grid North: 377410.00  
Scale Factor: 1.000  
Geomagnetic Model: IGRF2010\_14  
Sample Date: 25-Jul-14  
Magnetic Declination: 7.21°  
Dip Angle from Horizontal: 59.93°  
Magnetic Field Strength: 48188  
To convert a Magnetic Direction to a Grid Direction, Add 6.83°  
To convert a Magnetic Direction to a True Direction, Add 7.21° East  
To convert a True Direction to a Grid Direction, Subtract 0.38°

LEGEND  
-- 2H, Wellbore #1, Plan #1 07-25-14 V0  
-- 1H, Wellbore #1, Plan #1 07-25-14 V0  
-- 2H, Wellbore #1, Plan #1 07-25-14 V0  
-- Plan #1 07-25-14





**PHOENIX**  
TECHNOLOGY SERVICES

## **Chevron**

**Lea County NM (NAD27 NME)**

**Salado Draw 18 26 33 Fed**


**1H**

**Wellbore #1**

**Plan: Plan #1 07-25-14**

## **Planning Report**

**25 July, 2014**





# Phoenix Technology Services

## Planning Report



|                  |                           |                                     |                                  |
|------------------|---------------------------|-------------------------------------|----------------------------------|
| <b>Company:</b>  | Chevron                   | <b>Local Co-ordinate Reference:</b> | Well 1H                          |
| <b>Project:</b>  | Lea County NM (NAD27 NME) | <b>TVD Reference:</b>               | KB: 27' @ 3203.00usft (Planning) |
| <b>Site:</b>     | Salado Draw 18 26 33 Fed  | <b>MD Reference:</b>                | KB: 27' @ 3203.00usft (Planning) |
| <b>Well:</b>     | 1H                        | <b>North Reference:</b>             | Grid                             |
| <b>Wellbore:</b> | Wellbore #1               | <b>Survey Calculation Method:</b>   | Minimum Curvature                |
| <b>Design:</b>   | Plan #1 07-25-14          | <b>Database:</b>                    | Compass 5000 GCR DB              |

|                    |                                      |                      |                |
|--------------------|--------------------------------------|----------------------|----------------|
| <b>Project</b>     | Lea County NM (NAD27 NME)            |                      |                |
| <b>Map System:</b> | US State Plane 1927 (Exact solution) | <b>System Datum:</b> | Mean Sea Level |
| <b>Geo Datum:</b>  | NAD 1927 (NADCON CONUS)              |                      |                |
| <b>Map Zone:</b>   | New Mexico East 3001                 |                      |                |

|                              |                          |                          |                     |
|------------------------------|--------------------------|--------------------------|---------------------|
| <b>Site</b>                  | Salado Draw 18 26 33 Fed |                          |                     |
| <b>Site Position:</b>        |                          | <b>Northing:</b>         | 377,418.00 usft     |
| <b>From:</b>                 | Map                      | <b>Easting:</b>          | 723,192.00 usft     |
| <b>Position Uncertainty:</b> | 0.00 usft                | <b>Slot Radius:</b>      | 13-3/16 "           |
|                              |                          | <b>Latitude:</b>         | 32° 2' 8.12739 N    |
|                              |                          | <b>Longitude:</b>        | 103° 36' 47.07645 W |
|                              |                          | <b>Grid Convergence:</b> | 0.38 °              |

|                      |       |           |                     |                 |               |                     |
|----------------------|-------|-----------|---------------------|-----------------|---------------|---------------------|
| Well                 | 1H    |           |                     |                 |               |                     |
| Well Position        | +N/-S | 0.00 usft | Northing:           | 377,410.00 usft | Latitude:     | 32° 2' 8.11866 N    |
|                      | +E/-W | 0.00 usft | Easting:            | 722,122.00 usft | Longitude:    | 103° 36' 59.50691 W |
| Position Uncertainty |       | 0.00 usft | Wellhead Elevation: | 0.00 usft       | Ground Level: | 3,176.00 usft       |

|                  |                   |                    |                        |                      |                            |
|------------------|-------------------|--------------------|------------------------|----------------------|----------------------------|
| <b>Wellbore</b>  | Wellbore #1       |                    |                        |                      |                            |
| <b>Magnetics</b> | <b>Model Name</b> | <b>Sample Date</b> | <b>Declination (°)</b> | <b>Dip Angle (°)</b> | <b>Field Strength (nT)</b> |
|                  | IGRF2010_14       | 2014/07/25         | 7.21                   | 59.93                | 48,189                     |

|                          |                                |                     |                      |                      |
|--------------------------|--------------------------------|---------------------|----------------------|----------------------|
| <b>Design</b>            | Plan #1 07-25-14               |                     |                      |                      |
| <b>Audit Notes:</b>      |                                |                     |                      |                      |
| <b>Version:</b>          | <b>Phase:</b>                  | PROTOTYPE           | <b>Tie On Depth:</b> | 0.00                 |
| <b>Vertical Section:</b> | <b>Depth From (TVD) (usft)</b> | <b>+N/-S (usft)</b> | <b>+E/-W (usft)</b>  | <b>Direction (°)</b> |
|                          | 0.00                           | 0.00                | 0.00                 | 353.95               |

|                            |                  |                                |                  |                                      |
|----------------------------|------------------|--------------------------------|------------------|--------------------------------------|
| <b>Survey Tool Program</b> | <b>Date</b>      | 2014/07/25                     |                  |                                      |
| <b>From (usft)</b>         | <b>To (usft)</b> | <b>Survey (Wellbore)</b>       | <b>Tool Name</b> | <b>Description</b>                   |
| 0.00                       | 13,792.98        | Plan #1 07-25-14 (Wellbore #1) | PHX+MWD+IGRF     | PHX+MWD+IGRF v3:standard declination |





# Phoenix Technology Services Planning Report



**Company:** Chevron  
**Project:** Lea County NM (NAD27 NME)  
**Site:** Salado Draw 18 26 33 Fed  
**Well:** 1H  
**Wellbore:** Wellbore #1  
**Design:** Plan #1 07-25-14

**Local Co-ordinate Reference:** Well 1H  
**TVD Reference:** KB: 27' @ 3203.00usft (Planning)  
**MD Reference:** KB: 27' @ 3203.00usft (Planning)  
**North Reference:** Grid  
**Survey Calculation Method:** Minimum Curvature  
**Database:** Compass 5000 GCR DB

## Planned Survey

| MD<br>(usft)                        | Inc<br>(°) | Azi (azimuth)<br>(°) | TVDSS<br>(usft) | TVD<br>(usft) | N/S<br>(usft) | E/W<br>(usft) | Northing<br>(usft) | Easting<br>(usft) | V. Sec<br>(usft) | DLeg<br>(°/100usft) |
|-------------------------------------|------------|----------------------|-----------------|---------------|---------------|---------------|--------------------|-------------------|------------------|---------------------|
| 0.00                                | 0.00       | 0.00                 | -3,203.00       | 0.00          | 0.00          | 0.00          | 377,410.00         | 722,122.00        | 0.00             | 0.00                |
| 100.00                              | 0.00       | 0.00                 | -3,103.00       | 100.00        | 0.00          | 0.00          | 377,410.00         | 722,122.00        | 0.00             | 0.00                |
| 200.00                              | 0.00       | 0.00                 | -3,003.00       | 200.00        | 0.00          | 0.00          | 377,410.00         | 722,122.00        | 0.00             | 0.00                |
| 300.00                              | 0.00       | 0.00                 | -2,903.00       | 300.00        | 0.00          | 0.00          | 377,410.00         | 722,122.00        | 0.00             | 0.00                |
| 400.00                              | 0.00       | 0.00                 | -2,803.00       | 400.00        | 0.00          | 0.00          | 377,410.00         | 722,122.00        | 0.00             | 0.00                |
| 500.00                              | 0.00       | 0.00                 | -2,703.00       | 500.00        | 0.00          | 0.00          | 377,410.00         | 722,122.00        | 0.00             | 0.00                |
| 600.00                              | 0.00       | 0.00                 | -2,603.00       | 600.00        | 0.00          | 0.00          | 377,410.00         | 722,122.00        | 0.00             | 0.00                |
| 700.00                              | 0.00       | 0.00                 | -2,503.00       | 700.00        | 0.00          | 0.00          | 377,410.00         | 722,122.00        | 0.00             | 0.00                |
| 800.00                              | 0.00       | 0.00                 | -2,403.00       | 800.00        | 0.00          | 0.00          | 377,410.00         | 722,122.00        | 0.00             | 0.00                |
| 900.00                              | 0.00       | 0.00                 | -2,303.00       | 900.00        | 0.00          | 0.00          | 377,410.00         | 722,122.00        | 0.00             | 0.00                |
| 1,000.00                            | 0.00       | 0.00                 | -2,203.00       | 1,000.00      | 0.00          | 0.00          | 377,410.00         | 722,122.00        | 0.00             | 0.00                |
| 1,100.00                            | 0.00       | 0.00                 | -2,103.00       | 1,100.00      | 0.00          | 0.00          | 377,410.00         | 722,122.00        | 0.00             | 0.00                |
| 1,200.00                            | 0.00       | 0.00                 | -2,003.00       | 1,200.00      | 0.00          | 0.00          | 377,410.00         | 722,122.00        | 0.00             | 0.00                |
| <b>KOP1, Start 1°/100' Build</b>    |            |                      |                 |               |               |               |                    |                   |                  |                     |
| 1,300.00                            | 1.00       | 303.95               | -1,903.01       | 1,299.99      | 0.49          | -0.72         | 377,410.49         | 722,121.28        | 0.56             | 1.00                |
| 1,400.00                            | 2.00       | 303.95               | -1,803.04       | 1,399.96      | 1.95          | -2.90         | 377,411.95         | 722,119.10        | 2.24             | 1.00                |
| 1,500.00                            | 3.00       | 303.95               | -1,703.14       | 1,499.86      | 4.39          | -6.51         | 377,414.39         | 722,115.49        | 5.05             | 1.00                |
| 1,600.00                            | 4.00       | 303.95               | -1,603.32       | 1,599.68      | 7.80          | -11.58        | 377,417.80         | 722,110.42        | 8.97             | 1.00                |
| 1,667.73                            | 4.68       | 303.95               | -1,535.79       | 1,667.21      | 10.66         | -15.83        | 377,420.66         | 722,106.17        | 12.27            | 1.00                |
| <b>EOB, Start hold at 4.68° Inc</b> |            |                      |                 |               |               |               |                    |                   |                  |                     |
| 1,700.00                            | 4.68       | 303.95               | -1,503.63       | 1,699.37      | 12.13         | -18.01        | 377,422.13         | 722,103.99        | 13.96            | 0.00                |
| 1,800.00                            | 4.68       | 303.95               | -1,403.96       | 1,799.04      | 16.68         | -24.77        | 377,426.68         | 722,097.23        | 19.20            | 0.00                |
| 1,900.00                            | 4.68       | 303.95               | -1,304.29       | 1,898.71      | 21.24         | -31.54        | 377,431.24         | 722,090.46        | 24.44            | 0.00                |
| 2,000.00                            | 4.68       | 303.95               | -1,204.63       | 1,998.37      | 25.79         | -38.30        | 377,435.79         | 722,083.70        | 29.68            | 0.00                |
| 2,100.00                            | 4.68       | 303.95               | -1,104.96       | 2,098.04      | 30.34         | -45.07        | 377,440.34         | 722,076.93        | 34.92            | 0.00                |
| 2,200.00                            | 4.68       | 303.95               | -1,005.29       | 2,197.71      | 34.90         | -51.83        | 377,444.90         | 722,070.17        | 40.17            | 0.00                |
| 2,300.00                            | 4.68       | 303.95               | -905.62         | 2,297.38      | 39.45         | -58.59        | 377,449.45         | 722,063.41        | 45.41            | 0.00                |



# Phoenix Technology Services Planning Report



**Company:** Chevron  
**Project:** Lea County NM (NAD27 NME)  
**Site:** Salado Draw 18 26 33 Fed  
**Well:** 1H  
**Wellbore:** Wellbore #1  
**Design:** Plan #1 07-25-14

**Local Co-ordinate Reference:** Well 1H  
**TVD Reference:** KB: 27' @ 3203.00usft (Planning)  
**MD Reference:** KB: 27' @ 3203.00usft (Planning)  
**North Reference:** Grid  
**Survey Calculation Method:** Minimum Curvature  
**Database:** Compass 5000 GCR DB

## Planned Survey

| MD<br>(usft) | Inc<br>(°) | Azi (azimuth)<br>(°) | TVDSS<br>(usft) | TVD<br>(usft) | N/S<br>(usft) | E/W<br>(usft) | Northing<br>(usft) | Easting<br>(usft) | V. Sec<br>(usft) | DLeg<br>(°/100usft) |
|--------------|------------|----------------------|-----------------|---------------|---------------|---------------|--------------------|-------------------|------------------|---------------------|
| 2,400.00     | 4.68       | 303.95               | -805.96         | 2,397.04      | 44.01         | -65.36        | 377,454.01         | 722,056.64        | 50.65            | 0.00                |
| 2,500.00     | 4.68       | 303.95               | -706.29         | 2,496.71      | 48.56         | -72.12        | 377,458.56         | 722,049.88        | 55.89            | 0.00                |
| 2,600.00     | 4.68       | 303.95               | -606.62         | 2,596.38      | 53.12         | -78.89        | 377,463.12         | 722,043.11        | 61.13            | 0.00                |
| 2,700.00     | 4.68       | 303.95               | -506.96         | 2,696.04      | 57.67         | -85.65        | 377,467.67         | 722,036.35        | 66.38            | 0.00                |
| 2,800.00     | 4.68       | 303.95               | -407.29         | 2,795.71      | 62.22         | -92.41        | 377,472.22         | 722,029.59        | 71.62            | 0.00                |
| 2,900.00     | 4.68       | 303.95               | -307.62         | 2,895.38      | 66.78         | -99.18        | 377,476.78         | 722,022.82        | 76.86            | 0.00                |
| 3,000.00     | 4.68       | 303.95               | -207.96         | 2,995.04      | 71.33         | -105.94       | 377,481.33         | 722,016.06        | 82.10            | 0.00                |
| 3,100.00     | 4.68       | 303.95               | -108.29         | 3,094.71      | 75.89         | -112.71       | 377,485.89         | 722,009.29        | 87.34            | 0.00                |
| 3,200.00     | 4.68       | 303.95               | -8.62           | 3,194.38      | 80.44         | -119.47       | 377,490.44         | 722,002.53        | 92.59            | 0.00                |
| 3,300.00     | 4.68       | 303.95               | 91.04           | 3,294.04      | 85.00         | -126.24       | 377,495.00         | 721,995.76        | 97.83            | 0.00                |
| 3,400.00     | 4.68       | 303.95               | 190.71          | 3,393.71      | 89.55         | -133.00       | 377,499.55         | 721,989.00        | 103.07           | 0.00                |
| 3,500.00     | 4.68       | 303.95               | 290.38          | 3,493.38      | 94.10         | -139.76       | 377,504.10         | 721,982.24        | 108.31           | 0.00                |
| 3,600.00     | 4.68       | 303.95               | 390.05          | 3,593.05      | 98.66         | -146.53       | 377,508.66         | 721,975.47        | 113.55           | 0.00                |
| 3,700.00     | 4.68       | 303.95               | 489.71          | 3,692.71      | 103.21        | -153.29       | 377,513.21         | 721,968.71        | 118.80           | 0.00                |
| 3,800.00     | 4.68       | 303.95               | 589.38          | 3,792.38      | 107.77        | -160.06       | 377,517.77         | 721,961.94        | 124.04           | 0.00                |
| 3,900.00     | 4.68       | 303.95               | 689.05          | 3,892.05      | 112.32        | -166.82       | 377,522.32         | 721,955.18        | 129.28           | 0.00                |
| 4,000.00     | 4.68       | 303.95               | 788.71          | 3,991.71      | 116.88        | -173.58       | 377,526.88         | 721,948.42        | 134.52           | 0.00                |
| 4,100.00     | 4.68       | 303.95               | 888.38          | 4,091.38      | 121.43        | -180.35       | 377,531.43         | 721,941.65        | 139.76           | 0.00                |
| 4,200.00     | 4.68       | 303.95               | 988.05          | 4,191.05      | 125.99        | -187.11       | 377,535.99         | 721,934.89        | 145.00           | 0.00                |
| 4,300.00     | 4.68       | 303.95               | 1,087.71        | 4,290.71      | 130.54        | -193.88       | 377,540.54         | 721,928.12        | 150.25           | 0.00                |
| 4,400.00     | 4.68       | 303.95               | 1,187.38        | 4,390.38      | 135.09        | -200.64       | 377,545.09         | 721,921.36        | 155.49           | 0.00                |
| 4,500.00     | 4.68       | 303.95               | 1,287.05        | 4,490.05      | 139.65        | -207.40       | 377,549.65         | 721,914.60        | 160.73           | 0.00                |
| 4,600.00     | 4.68       | 303.95               | 1,386.72        | 4,589.72      | 144.20        | -214.17       | 377,554.20         | 721,907.83        | 165.97           | 0.00                |
| 4,700.00     | 4.68       | 303.95               | 1,486.38        | 4,689.38      | 148.76        | -220.93       | 377,558.76         | 721,901.07        | 171.21           | 0.00                |
| 4,800.00     | 4.68       | 303.95               | 1,586.05        | 4,789.05      | 153.31        | -227.70       | 377,563.31         | 721,894.30        | 176.46           | 0.00                |
| 4,900.00     | 4.68       | 303.95               | 1,685.72        | 4,888.72      | 157.87        | -234.46       | 377,567.87         | 721,887.54        | 181.70           | 0.00                |
| 5,000.00     | 4.68       | 303.95               | 1,785.38        | 4,988.38      | 162.42        | -241.22       | 377,572.42         | 721,880.78        | 186.94           | 0.00                |



# Phoenix Technology Services Planning Report



**Company:** Chevron  
**Project:** Lea County NM (NAD27 NME)  
**Site:** Salado Draw 18 26 33 Fed  
**Well:** 1H  
**Wellbore:** Wellbore #1  
**Design:** Plan #1 07-25-14

**Local Co-ordinate Reference:** Well 1H  
**TVD Reference:** KB: 27' @ 3203.00usft (Planning)  
**MD Reference:** KB: 27' @ 3203.00usft (Planning)  
**North Reference:** Grid  
**Survey Calculation Method:** Minimum Curvature  
**Database:** Compass 5000 GCR DB

## Planned Survey

| MD<br>(usft) | Inc<br>(°) | Azi (azimuth)<br>(°) | TVDSS<br>(usft) | TVD<br>(usft) | N/S<br>(usft) | E/W<br>(usft) | Northing<br>(usft) | Easting<br>(usft) | V. Sec<br>(usft) | DLeg<br>(°/100usft) |
|--------------|------------|----------------------|-----------------|---------------|---------------|---------------|--------------------|-------------------|------------------|---------------------|
| 5,100.00     | 4.68       | 303.95               | 1,885.05        | 5,088.05      | 166.97        | -247.99       | 377,576.97         | 721,874.01        | 192.18           | 0.00                |
| 5,200.00     | 4.68       | 303.95               | 1,984.72        | 5,187.72      | 171.53        | -254.75       | 377,581.53         | 721,867.25        | 197.42           | 0.00                |
| 5,300.00     | 4.68       | 303.95               | 2,084.38        | 5,287.38      | 176.08        | -261.52       | 377,586.08         | 721,860.48        | 202.67           | 0.00                |
| 5,400.00     | 4.68       | 303.95               | 2,184.05        | 5,387.05      | 180.64        | -268.28       | 377,590.64         | 721,853.72        | 207.91           | 0.00                |
| 5,500.00     | 4.68       | 303.95               | 2,283.72        | 5,486.72      | 185.19        | -275.04       | 377,595.19         | 721,846.96        | 213.15           | 0.00                |
| 5,600.00     | 4.68       | 303.95               | 2,383.39        | 5,586.39      | 189.75        | -281.81       | 377,599.75         | 721,840.19        | 218.39           | 0.00                |
| 5,700.00     | 4.68       | 303.95               | 2,483.05        | 5,686.05      | 194.30        | -288.57       | 377,604.30         | 721,833.43        | 223.63           | 0.00                |
| 5,800.00     | 4.68       | 303.95               | 2,582.72        | 5,785.72      | 198.86        | -295.34       | 377,608.86         | 721,826.66        | 228.87           | 0.00                |
| 5,900.00     | 4.68       | 303.95               | 2,682.39        | 5,885.39      | 203.41        | -302.10       | 377,613.41         | 721,819.90        | 234.12           | 0.00                |
| 6,000.00     | 4.68       | 303.95               | 2,782.05        | 5,985.05      | 207.96        | -308.87       | 377,617.96         | 721,813.13        | 239.36           | 0.00                |
| 6,100.00     | 4.68       | 303.95               | 2,881.72        | 6,084.72      | 212.52        | -315.63       | 377,622.52         | 721,806.37        | 244.60           | 0.00                |
| 6,200.00     | 4.68       | 303.95               | 2,981.39        | 6,184.39      | 217.07        | -322.39       | 377,627.07         | 721,799.61        | 249.84           | 0.00                |
| 6,300.00     | 4.68       | 303.95               | 3,081.05        | 6,284.05      | 221.63        | -329.16       | 377,631.63         | 721,792.84        | 255.08           | 0.00                |
| 6,400.00     | 4.68       | 303.95               | 3,180.72        | 6,383.72      | 226.18        | -335.92       | 377,636.18         | 721,786.08        | 260.33           | 0.00                |
| 6,500.00     | 4.68       | 303.95               | 3,280.39        | 6,483.39      | 230.74        | -342.69       | 377,640.74         | 721,779.31        | 265.57           | 0.00                |
| 6,600.00     | 4.68       | 303.95               | 3,380.05        | 6,583.05      | 235.29        | -349.45       | 377,645.29         | 721,772.55        | 270.81           | 0.00                |
| 6,700.00     | 4.68       | 303.95               | 3,479.72        | 6,682.72      | 239.84        | -356.21       | 377,649.84         | 721,765.79        | 276.05           | 0.00                |
| 6,800.00     | 4.68       | 303.95               | 3,579.39        | 6,782.39      | 244.40        | -362.98       | 377,654.40         | 721,759.02        | 281.29           | 0.00                |
| 6,900.00     | 4.68       | 303.95               | 3,679.06        | 6,882.06      | 248.95        | -369.74       | 377,658.95         | 721,752.26        | 286.54           | 0.00                |
| 7,000.00     | 4.68       | 303.95               | 3,778.72        | 6,981.72      | 253.51        | -376.51       | 377,663.51         | 721,745.49        | 291.78           | 0.00                |
| 7,100.00     | 4.68       | 303.95               | 3,878.39        | 7,081.39      | 258.06        | -383.27       | 377,668.06         | 721,738.73        | 297.02           | 0.00                |
| 7,200.00     | 4.68       | 303.95               | 3,978.06        | 7,181.06      | 262.62        | -390.03       | 377,672.62         | 721,731.97        | 302.26           | 0.00                |
| 7,300.00     | 4.68       | 303.95               | 4,077.72        | 7,280.72      | 267.17        | -396.80       | 377,677.17         | 721,725.20        | 307.50           | 0.00                |
| 7,400.00     | 4.68       | 303.95               | 4,177.39        | 7,380.39      | 271.72        | -403.56       | 377,681.72         | 721,718.44        | 312.75           | 0.00                |
| 7,500.00     | 4.68       | 303.95               | 4,277.06        | 7,480.06      | 276.28        | -410.33       | 377,686.28         | 721,711.67        | 317.99           | 0.00                |
| 7,600.00     | 4.68       | 303.95               | 4,376.72        | 7,579.72      | 280.83        | -417.09       | 377,690.83         | 721,704.91        | 323.23           | 0.00                |
| 7,700.00     | 4.68       | 303.95               | 4,476.39        | 7,679.39      | 285.39        | -423.85       | 377,695.39         | 721,698.15        | 328.47           | 0.00                |



# Phoenix Technology Services Planning Report



**Company:** Chevron  
**Project:** Lea County NM (NAD27 NME)  
**Site:** Salado Draw 18 26 33 Fed  
**Well:** 1H  
**Wellbore:** Wellbore #1  
**Design:** Plan #1 07-25-14

**Local Co-ordinate Reference:** Well 1H  
**TVD Reference:** KB: 27' @ 3203.00usft (Planning)  
**MD Reference:** KB: 27' @ 3203.00usft (Planning)  
**North Reference:** Grid  
**Survey Calculation Method:** Minimum Curvature  
**Database:** Compass 5000 GCR DB

## Planned Survey

| MD<br>(usft)                      | Inc<br>(°) | Azi (azimuth)<br>(°) | TVDSS<br>(usft) | TVD<br>(usft) | N/S<br>(usft) | E/W<br>(usft) | Northing<br>(usft) | Easting<br>(usft) | V. Sec<br>(usft) | DLeg<br>(°/100usft) |
|-----------------------------------|------------|----------------------|-----------------|---------------|---------------|---------------|--------------------|-------------------|------------------|---------------------|
| 7,800.00                          | 4.68       | 303.95               | 4,576.06        | 7,779.06      | 289.94        | -430.62       | 377,699.94         | 721,691.38        | 333.71           | 0.00                |
| 7,900.00                          | 4.68       | 303.95               | 4,675.73        | 7,878.73      | 294.50        | -437.38       | 377,704.50         | 721,684.62        | 338.95           | 0.00                |
| 8,000.00                          | 4.68       | 303.95               | 4,775.39        | 7,978.39      | 299.05        | -444.15       | 377,709.05         | 721,677.85        | 344.20           | 0.00                |
| 8,100.00                          | 4.68       | 303.95               | 4,875.06        | 8,078.06      | 303.61        | -450.91       | 377,713.61         | 721,671.09        | 349.44           | 0.00                |
| 8,200.00                          | 4.68       | 303.95               | 4,974.73        | 8,177.73      | 308.16        | -457.67       | 377,718.16         | 721,664.33        | 354.68           | 0.00                |
| 8,300.00                          | 4.68       | 303.95               | 5,074.39        | 8,277.39      | 312.71        | -464.44       | 377,722.71         | 721,657.56        | 359.92           | 0.00                |
| 8,400.00                          | 4.68       | 303.95               | 5,174.06        | 8,377.06      | 317.27        | -471.20       | 377,727.27         | 721,650.80        | 365.16           | 0.00                |
| 8,500.00                          | 4.68       | 303.95               | 5,273.73        | 8,476.73      | 321.82        | -477.97       | 377,731.82         | 721,644.03        | 370.41           | 0.00                |
| 8,600.00                          | 4.68       | 303.95               | 5,373.39        | 8,576.39      | 326.38        | -484.73       | 377,736.38         | 721,637.27        | 375.65           | 0.00                |
| 8,674.37                          | 4.68       | 303.95               | 5,447.52        | 8,650.52      | 329.76        | -489.76       | 377,739.76         | 721,632.24        | 379.55           | 0.00                |
| <b>KOP2, Start 12°/100' Build</b> |            |                      |                 |               |               |               |                    |                   |                  |                     |
| 8,700.00                          | 6.89       | 325.65               | 5,473.02        | 8,676.02      | 331.62        | -491.50       | 377,741.62         | 721,630.50        | 381.57           | 12.00               |
| 8,725.00                          | 9.52       | 335.89               | 5,497.76        | 8,700.76      | 334.74        | -493.19       | 377,744.74         | 721,628.81        | 384.86           | 12.00               |
| 8,750.00                          | 12.32      | 341.62               | 5,522.31        | 8,725.31      | 339.16        | -494.87       | 377,749.16         | 721,627.13        | 389.43           | 12.00               |
| 8,775.00                          | 15.20      | 345.24               | 5,546.59        | 8,749.59      | 344.87        | -496.55       | 377,754.87         | 721,625.45        | 395.28           | 12.00               |
| 8,800.00                          | 18.11      | 347.72               | 5,570.53        | 8,773.53      | 351.83        | -498.21       | 377,761.83         | 721,623.79        | 402.39           | 12.00               |
| 8,825.00                          | 21.05      | 349.53               | 5,594.09        | 8,797.09      | 360.05        | -499.85       | 377,770.05         | 721,622.15        | 410.73           | 12.00               |
| 8,850.00                          | 24.01      | 350.92               | 5,617.18        | 8,820.18      | 369.49        | -501.47       | 377,779.49         | 721,620.53        | 420.28           | 12.00               |
| 8,875.00                          | 26.97      | 352.01               | 5,639.74        | 8,842.74      | 380.13        | -503.06       | 377,790.13         | 721,618.94        | 431.03           | 12.00               |
| 8,900.00                          | 29.94      | 352.91               | 5,661.72        | 8,864.72      | 391.93        | -504.62       | 377,801.93         | 721,617.38        | 442.94           | 12.00               |
| 8,925.00                          | 32.91      | 353.65               | 5,683.05        | 8,886.05      | 404.88        | -506.15       | 377,814.88         | 721,615.85        | 455.97           | 12.00               |
| 8,950.00                          | 35.89      | 354.29               | 5,703.67        | 8,906.67      | 418.92        | -507.63       | 377,828.92         | 721,614.37        | 470.09           | 12.00               |
| 8,975.00                          | 38.87      | 354.84               | 5,723.54        | 8,926.54      | 434.03        | -509.06       | 377,844.03         | 721,612.94        | 485.27           | 12.00               |
| 9,000.00                          | 41.86      | 355.32               | 5,742.58        | 8,945.58      | 450.16        | -510.45       | 377,860.16         | 721,611.55        | 501.45           | 12.00               |
| 9,025.00                          | 44.84      | 355.75               | 5,760.76        | 8,963.76      | 467.27        | -511.78       | 377,877.27         | 721,610.22        | 518.60           | 12.00               |
| 9,050.00                          | 47.83      | 356.13               | 5,778.02        | 8,981.02      | 485.30        | -513.06       | 377,895.30         | 721,608.94        | 536.68           | 12.00               |
| 9,075.00                          | 50.82      | 356.49               | 5,794.31        | 8,997.31      | 504.22        | -514.28       | 377,914.22         | 721,607.72        | 555.62           | 12.00               |



# Phoenix Technology Services Planning Report



**Company:** Chevron  
**Project:** Lea County NM (NAD27 NME)  
**Site:** Salado Draw 18 26 33 Fed  
**Well:** 1H  
**Wellbore:** Wellbore #1  
**Design:** Plan #1 07-25-14

**Local Co-ordinate Reference:** Well 1H  
**TVD Reference:** KB: 27' @ 3203.00usft (Planning)  
**MD Reference:** KB: 27' @ 3203.00usft (Planning)  
**North Reference:** Grid  
**Survey Calculation Method:** Minimum Curvature  
**Database:** Compass 5000 GCR DB

## Planned Survey

| MD<br>(usft)                                    | Inc<br>(°) | Azi (azimuth)<br>(°) | TVDSS<br>(usft) | TVD<br>(usft) | N/S<br>(usft) | E/W<br>(usft) | Northing<br>(usft) | Easting<br>(usft) | V. Sec<br>(usft) | DLeg<br>(°/100usft) |
|-------------------------------------------------|------------|----------------------|-----------------|---------------|---------------|---------------|--------------------|-------------------|------------------|---------------------|
| 9,100.00                                        | 53.81      | 356.81               | 5,809.60        | 9,012.60      | 523.97        | -515.44       | 377,933.97         | 721,606.56        | 575.38           | 12.00               |
| 9,125.00                                        | 56.80      | 357.11               | 5,823.83        | 9,026.83      | 544.49        | -516.53       | 377,954.49         | 721,605.47        | 595.90           | 12.00               |
| 9,150.00                                        | 59.79      | 357.39               | 5,836.97        | 9,039.97      | 565.73        | -517.55       | 377,975.73         | 721,604.45        | 617.13           | 12.00               |
| 9,175.00                                        | 62.78      | 357.65               | 5,848.98        | 9,051.98      | 587.63        | -518.49       | 377,997.63         | 721,603.51        | 639.01           | 12.00               |
| 9,200.00                                        | 65.77      | 357.90               | 5,859.83        | 9,062.83      | 610.14        | -519.37       | 378,020.14         | 721,602.63        | 661.48           | 12.00               |
| 9,225.00                                        | 68.76      | 358.14               | 5,869.49        | 9,072.49      | 633.18        | -520.16       | 378,043.18         | 721,601.84        | 684.47           | 12.00               |
| 9,250.00                                        | 71.75      | 358.37               | 5,877.93        | 9,080.93      | 656.70        | -520.88       | 378,066.70         | 721,601.12        | 707.94           | 12.00               |
| 9,275.00                                        | 74.75      | 358.59               | 5,885.14        | 9,088.14      | 680.62        | -521.51       | 378,090.62         | 721,600.49        | 731.80           | 12.00               |
| 9,300.00                                        | 77.74      | 358.80               | 5,891.08        | 9,094.08      | 704.90        | -522.07       | 378,114.90         | 721,599.93        | 755.99           | 12.00               |
| 9,325.00                                        | 80.73      | 359.01               | 5,895.75        | 9,098.75      | 729.45        | -522.53       | 378,139.45         | 721,599.47        | 780.46           | 12.00               |
| 9,350.00                                        | 83.72      | 359.22               | 5,899.13        | 9,102.13      | 754.21        | -522.92       | 378,164.21         | 721,599.08        | 805.13           | 12.00               |
| 9,375.00                                        | 86.72      | 359.42               | 5,901.22        | 9,104.22      | 779.12        | -523.21       | 378,189.12         | 721,598.79        | 829.93           | 12.00               |
| 9,401.87                                        | 89.93      | 359.64               | 5,902.00        | 9,105.00      | 805.98        | -523.43       | 378,215.98         | 721,598.57        | 856.66           | 12.00               |
| <b>LP, 89.93° Inc, 359.64° Azm - Start hold</b> |            |                      |                 |               |               |               |                    |                   |                  |                     |
| 9,500.00                                        | 89.93      | 359.64               | 5,902.11        | 9,105.11      | 904.10        | -524.05       | 378,314.10         | 721,597.95        | 954.30           | 0.00                |
| 9,600.00                                        | 89.93      | 359.64               | 5,902.23        | 9,105.23      | 1,004.10      | -524.67       | 378,414.10         | 721,597.33        | 1,053.81         | 0.00                |
| 9,700.00                                        | 89.93      | 359.64               | 5,902.34        | 9,105.34      | 1,104.10      | -525.30       | 378,514.10         | 721,596.70        | 1,153.32         | 0.00                |
| 9,800.00                                        | 89.93      | 359.64               | 5,902.45        | 9,105.45      | 1,204.10      | -525.93       | 378,614.10         | 721,596.07        | 1,252.82         | 0.00                |
| 9,900.00                                        | 89.93      | 359.64               | 5,902.57        | 9,105.57      | 1,304.10      | -526.56       | 378,714.10         | 721,595.44        | 1,352.33         | 0.00                |
| 10,000.00                                       | 89.93      | 359.64               | 5,902.68        | 9,105.68      | 1,404.09      | -527.19       | 378,814.09         | 721,594.81        | 1,451.84         | 0.00                |
| 10,100.00                                       | 89.93      | 359.64               | 5,902.79        | 9,105.79      | 1,504.09      | -527.81       | 378,914.09         | 721,594.19        | 1,551.34         | 0.00                |
| 10,200.00                                       | 89.93      | 359.64               | 5,902.91        | 9,105.91      | 1,604.09      | -528.44       | 379,014.09         | 721,593.56        | 1,650.85         | 0.00                |
| 10,300.00                                       | 89.93      | 359.64               | 5,903.02        | 9,106.02      | 1,704.09      | -529.07       | 379,114.09         | 721,592.93        | 1,750.36         | 0.00                |
| 10,400.00                                       | 89.93      | 359.64               | 5,903.14        | 9,106.14      | 1,804.09      | -529.70       | 379,214.09         | 721,592.30        | 1,849.87         | 0.00                |
| 10,500.00                                       | 89.93      | 359.64               | 5,903.25        | 9,106.25      | 1,904.08      | -530.32       | 379,314.08         | 721,591.68        | 1,949.37         | 0.00                |
| 10,600.00                                       | 89.93      | 359.64               | 5,903.36        | 9,106.36      | 2,004.08      | -530.95       | 379,414.08         | 721,591.05        | 2,048.88         | 0.00                |
| 10,700.00                                       | 89.93      | 359.64               | 5,903.48        | 9,106.48      | 2,104.08      | -531.58       | 379,514.08         | 721,590.42        | 2,148.39         | 0.00                |



# Phoenix Technology Services

## Planning Report



**Company:** Chevron  
**Project:** Lea County NM (NAD27 NME)  
**Site:** Salado Draw 18 26 33 Fed  
**Well:** 1H  
**Wellbore:** Wellbore #1  
**Design:** Plan #1 07-25-14

**Local Co-ordinate Reference:** Well 1H  
**TVD Reference:** KB: 27' @ 3203.00usft (Planning)  
**MD Reference:** KB: 27' @ 3203.00usft (Planning)  
**North Reference:** Grid  
**Survey Calculation Method:** Minimum Curvature  
**Database:** Compass 5000 GCR DB

### Planned Survey

| MD<br>(usft) | Inc<br>(°) | Azi (azimuth)<br>(°) | TVDSS<br>(usft) | TVD<br>(usft) | N/S<br>(usft) | E/W<br>(usft) | Northing<br>(usft) | Easting<br>(usft) | V. Sec<br>(usft) | DLeg<br>(°/100usft) |
|--------------|------------|----------------------|-----------------|---------------|---------------|---------------|--------------------|-------------------|------------------|---------------------|
| 10,800.00    | 89.93      | 359.64               | 5,903.59        | 9,106.59      | 2,204.08      | -532.21       | 379,614.08         | 721,589.79        | 2,247.90         | 0.00                |
| 10,900.00    | 89.93      | 359.64               | 5,903.71        | 9,106.71      | 2,304.08      | -532.84       | 379,714.08         | 721,589.16        | 2,347.40         | 0.00                |
| 11,000.00    | 89.93      | 359.64               | 5,903.82        | 9,106.82      | 2,404.07      | -533.46       | 379,814.07         | 721,588.54        | 2,446.91         | 0.00                |
| 11,100.00    | 89.93      | 359.64               | 5,903.93        | 9,106.93      | 2,504.07      | -534.09       | 379,914.07         | 721,587.91        | 2,546.42         | 0.00                |
| 11,200.00    | 89.93      | 359.64               | 5,904.05        | 9,107.05      | 2,604.07      | -534.72       | 380,014.07         | 721,587.28        | 2,645.92         | 0.00                |
| 11,300.00    | 89.93      | 359.64               | 5,904.16        | 9,107.16      | 2,704.07      | -535.35       | 380,114.07         | 721,586.65        | 2,745.43         | 0.00                |
| 11,400.00    | 89.93      | 359.64               | 5,904.28        | 9,107.28      | 2,804.07      | -535.98       | 380,214.07         | 721,586.02        | 2,844.94         | 0.00                |
| 11,500.00    | 89.93      | 359.64               | 5,904.39        | 9,107.39      | 2,904.06      | -536.60       | 380,314.06         | 721,585.40        | 2,944.45         | 0.00                |
| 11,600.00    | 89.93      | 359.64               | 5,904.50        | 9,107.50      | 3,004.06      | -537.23       | 380,414.06         | 721,584.77        | 3,043.95         | 0.00                |
| 11,700.00    | 89.93      | 359.64               | 5,904.62        | 9,107.62      | 3,104.06      | -537.86       | 380,514.06         | 721,584.14        | 3,143.46         | 0.00                |
| 11,800.00    | 89.93      | 359.64               | 5,904.73        | 9,107.73      | 3,204.06      | -538.49       | 380,614.06         | 721,583.51        | 3,242.97         | 0.00                |
| 11,900.00    | 89.93      | 359.64               | 5,904.84        | 9,107.84      | 3,304.06      | -539.11       | 380,714.06         | 721,582.89        | 3,342.47         | 0.00                |
| 12,000.00    | 89.93      | 359.64               | 5,904.96        | 9,107.96      | 3,404.05      | -539.74       | 380,814.05         | 721,582.26        | 3,441.98         | 0.00                |
| 12,100.00    | 89.93      | 359.64               | 5,905.07        | 9,108.07      | 3,504.05      | -540.37       | 380,914.05         | 721,581.63        | 3,541.49         | 0.00                |
| 12,200.00    | 89.93      | 359.64               | 5,905.19        | 9,108.19      | 3,604.05      | -541.00       | 381,014.05         | 721,581.00        | 3,641.00         | 0.00                |
| 12,300.00    | 89.93      | 359.64               | 5,905.30        | 9,108.30      | 3,704.05      | -541.63       | 381,114.05         | 721,580.37        | 3,740.50         | 0.00                |
| 12,400.00    | 89.93      | 359.64               | 5,905.41        | 9,108.41      | 3,804.05      | -542.25       | 381,214.05         | 721,579.75        | 3,840.01         | 0.00                |
| 12,500.00    | 89.93      | 359.64               | 5,905.53        | 9,108.53      | 3,904.04      | -542.88       | 381,314.04         | 721,579.12        | 3,939.52         | 0.00                |
| 12,600.00    | 89.93      | 359.64               | 5,905.64        | 9,108.64      | 4,004.04      | -543.51       | 381,414.04         | 721,578.49        | 4,039.02         | 0.00                |
| 12,700.00    | 89.93      | 359.64               | 5,905.76        | 9,108.76      | 4,104.04      | -544.14       | 381,514.04         | 721,577.86        | 4,138.53         | 0.00                |
| 12,800.00    | 89.93      | 359.64               | 5,905.87        | 9,108.87      | 4,204.04      | -544.77       | 381,614.04         | 721,577.23        | 4,238.04         | 0.00                |
| 12,900.00    | 89.93      | 359.64               | 5,905.98        | 9,108.98      | 4,304.04      | -545.39       | 381,714.04         | 721,576.61        | 4,337.55         | 0.00                |
| 13,000.00    | 89.93      | 359.64               | 5,906.10        | 9,109.10      | 4,404.03      | -546.02       | 381,814.03         | 721,575.98        | 4,437.05         | 0.00                |
| 13,100.00    | 89.93      | 359.64               | 5,906.21        | 9,109.21      | 4,504.03      | -546.65       | 381,914.03         | 721,575.35        | 4,536.56         | 0.00                |
| 13,200.00    | 89.93      | 359.64               | 5,906.32        | 9,109.32      | 4,604.03      | -547.28       | 382,014.03         | 721,574.72        | 4,636.07         | 0.00                |
| 13,300.00    | 89.93      | 359.64               | 5,906.44        | 9,109.44      | 4,704.03      | -547.90       | 382,114.03         | 721,574.10        | 4,735.57         | 0.00                |
| 13,400.00    | 89.93      | 359.64               | 5,906.55        | 9,109.55      | 4,804.03      | -548.53       | 382,214.03         | 721,573.47        | 4,835.08         | 0.00                |



# Phoenix Technology Services Planning Report



**Company:** Chevron  
**Project:** Lea County NM (NAD27 NME)  
**Site:** Salado Draw 18 26 33 Fed  
**Well:** 1H  
**Wellbore:** Wellbore #1  
**Design:** Plan #1 07-25-14

**Local Co-ordinate Reference:** Well 1H  
**TVD Reference:** KB: 27' @ 3203.00usft (Planning)  
**MD Reference:** KB: 27' @ 3203.00usft (Planning)  
**North Reference:** Grid  
**Survey Calculation Method:** Minimum Curvature  
**Database:** Compass 5000 GCR DB

## Planned Survey

| MD<br>(usft)       | Inc<br>(°) | Azi (azimuth)<br>(°) | TVDSS<br>(usft) | TVD<br>(usft) | N/S<br>(usft) | E/W<br>(usft) | Northing<br>(usft) | Easting<br>(usft) | V. Sec<br>(usft) | DLeg<br>(°/100usft) |
|--------------------|------------|----------------------|-----------------|---------------|---------------|---------------|--------------------|-------------------|------------------|---------------------|
| 13,500.00          | 89.93      | 359.64               | 5,906.67        | 9,109.67      | 4,904.02      | -549.16       | 382,314.02         | 721,572.84        | 4,934.59         | 0.00                |
| 13,600.00          | 89.93      | 359.64               | 5,906.78        | 9,109.78      | 5,004.02      | -549.79       | 382,414.02         | 721,572.21        | 5,034.10         | 0.00                |
| 13,700.00          | 89.93      | 359.64               | 5,906.89        | 9,109.89      | 5,104.02      | -550.42       | 382,514.02         | 721,571.58        | 5,133.60         | 0.00                |
| 13,792.98          | 89.93      | 359.64               | 5,907.00        | 9,110.00      | 5,197.00      | -551.00       | 382,607.00         | 721,571.00        | 5,226.13         | 0.00                |
| TD at 13792.98' MD |            |                      |                 |               |               |               |                    |                   |                  |                     |

## Plan Annotations

| Measured<br>Depth<br>(usft) | Vertical<br>Depth<br>(usft) | Local Coordinates |                 | Comment                                  |
|-----------------------------|-----------------------------|-------------------|-----------------|------------------------------------------|
|                             |                             | +N/-S<br>(usft)   | +E/-W<br>(usft) |                                          |
| 1,200.00                    | 1,200.00                    | 0.00              | 0.00            | KOP1, Start 1°/100' Build                |
| 1,667.73                    | 1,667.21                    | 10.66             | -15.83          | EOB, Start hold at 4.68° Inc             |
| 8,674.37                    | 8,650.52                    | 329.76            | -489.76         | KOP2, Start 12°/100' Build               |
| 9,401.87                    | 9,105.00                    | 805.98            | -523.43         | LP, 89.93° Inc, 359.64° Azm - Start hold |
| 13,792.98                   | 9,110.00                    | 5,197.00          | -551.00         | TD at 13792.98' MD                       |

Checked By: \_\_\_\_\_ Approved By: \_\_\_\_\_ Date: \_\_\_\_\_

# BLOWOUT PREVENTOR SCHEMATIC

## Minimum Requirements

**OPERATION** : Intermediate and Production Hole Sections

**Minimum System**

**Pressure Rating** : 5,000 psi


| SIZE  |         | PRESSURE                       | DESCRIPTION |
|-------|---------|--------------------------------|-------------|
| A     |         | N/A                            | Bell Nipple |
| B     | 13 5/8" | 5,000 psi                      | Annular     |
| C     | 13 5/8" | 5,000 psi                      | Pipe Ram    |
| D     | 13 5/8" | 5,000 psi                      | Blind Ram   |
| E     | 13 5/8" | 5,000 psi                      | Mud Cross   |
| F     |         |                                |             |
| DSA   |         | As required for each hole size |             |
| C-Sec |         |                                |             |
| B-Sec |         | 13-5/8" 5K x 11" 5K            |             |
| A-Sec |         | 13-3/8" SOW x 13-5/8" 5K       |             |

### Kill Line

| SIZE | PRESSURE  | DESCRIPTION |
|------|-----------|-------------|
| 2"   | 5,000 psi | Gate Valve  |
| 2"   | 5,000 psi | Gate Valve  |
| 2"   | 5,000 psi | Check Valve |
|      |           |             |
|      |           |             |

### Choke Line

| SIZE | PRESSURE  | DESCRIPTION |
|------|-----------|-------------|
| 3"   | 5,000 psi | Gate Valve  |
| 3"   | 5,000 psi | HCR Valve   |
|      |           |             |
|      |           |             |
|      |           |             |



### Installation Checklist

The following item must be verified and checked off prior to pressure testing of BOP equipment.

- ☐ The installed BOP equipment meets at least the minimum requirements (rating, type, size, configuration) as shown on this schematic. Components may be substituted for equivalent equipment rated to higher pressures. Additional components may be put into place as long as they meet or exceed the minimum pressure rating of the system.
- ☐ All valves on the kill line and choke line will be full opening and will allow straight through flow.
- ☐ The kill line and choke line will be straight unless turns use tee blocks or are targeted with running tool, and will be anchored to prevent whip and reduce vibration.
- ☐ Manual (hand wheels) or automatic locking devices will be installed on all ram preventers. Hand wheels will also be installed on all manual valves on the choke line and kill line.
- ☐ A valve will be installed in the closing line as close as possible to the annular preventer to act as a locking device. This valve will remain open unless accumulator is inoperative.
- ☐ Upper kelly cock valve with handle will be available on rig floor along with safety valve and subs to fit all drill string connections in use.

After Installation Checklist is complete, fill out the information below and email to Superintendent and Drilling Engineer

**Wellname:** \_\_\_\_\_

**Representative:** \_\_\_\_\_

**Date:** \_\_\_\_\_



# CHOKE MANIFOLD SCHEMATIC


## Minimum Requirements

**OPERATION** : Intermediate and Production Hole Sections

**Minimum System Pressure Rating** : 5,000 psi

### Choke Manifold

| SIZE | PRESSURE  | DESCRIPTION           |
|------|-----------|-----------------------|
| 3"   | 5,000 psi | Panic Line Valves     |
| 2"   | 5,000 psi | Valves on Choke Lines |
|      |           |                       |
|      |           |                       |
|      |           |                       |



### Installation Checklist

The following item must be verified and checked off prior to pressure testing of BOP equipment.

- ☐ The installed BOP equipment meets at least the minimum requirements (rating, type, size, configuration) as shown on this schematic. Components may be substituted for equivalent equipment rated to higher pressures. Additional components may be put into place as long as they meet or exceed the minimum pressure rating of the system.
- ☐ Adjustable Chokes may be Remotely Operated but will have backup hand pump for hydraulic actuation in case of loss of rig air pressure or power.
- ☐ Flare and Panic lines will terminate a minimum of 150' from the wellhead. These lines will terminate at a location as per approved APD.
- ☐ The choke line, kill line, and choke manifold lines will be straight unless turns use tee blocks or are targeted with running tress, and will be anchored to prevent whip and reduce vibration. This excludes the line between mud gas separator and shale shaker.
- ☐ All valves (except chokes) on choke line, kill line, and choke manifold will be full opening and will allow straight through flow. This excludes any valves between mud gas separator and shale shakers.
- ☐ All manual valves will have hand wheels installed.
- ☐ If used, flare system will have effective method for ignition
- ☐ All connections will be flanged, welded, or clamped (no threaded connections like hammer unions)
- ☐ If buffer tank is used, a valve will be used on all lines at any entry or exit point to or from the buffer tank.

After Installation Checklist is complete, fill out the information below and email to Superintendent and Drilling Engineer

**Wellname:** \_\_\_\_\_

**Representative:** \_\_\_\_\_

**Date:** \_\_\_\_\_

# BOPE Testing

## Minimum Requirements

### Closing Unit and Accumulator Checklist

The following item must be performed, verified, and checked off at least once per well prior to low/high pressure testing of BOP equipment. This must be repeated after 6 months on the same well.

- ☐ Precharge pressure for each accumulator bottle must fall within the range below. Bottles may be further charged with nitrogen gas only. Tested precharge pressures must be recorded for each individual bottle and kept on location through the end of the well. Test will be conducted prior to connecting unit to BOP stack.

| Check one that applies   | Accumulator working pressure rating | Minimum acceptable operating pressure | Desired precharge pressure | Maximum acceptable precharge pressure | Minimum acceptable precharge pressure |
|--------------------------|-------------------------------------|---------------------------------------|----------------------------|---------------------------------------|---------------------------------------|
| <input type="checkbox"/> | 1500 psi                            | 1500 psi                              | 750 psi                    | 800 psi                               | 700 psi                               |
| <input type="checkbox"/> | 2000 psi                            | 2000 psi                              | 1000 psi                   | 1100 psi                              | 900 psi                               |
| <input type="checkbox"/> | 3000 psi                            | 3000 psi                              | 1000 psi                   | 1100 psi                              | 900 psi                               |

- ☐ Accumulator will have sufficient capacity to open the hydraulically-controlled choke line valve (if used), close all rams, close the annular preventer, and retain a minimum of 200 psi above the maximum acceptable precharge pressure (see table above) on the closing manifold without the use of the closing pumps. This test will be performed with test pressure recorded and kept on location through the end of the well
- ☐ Accumulator fluid reservoir will be double the usable fluid volume of the accumulator system capacity. Fluid level will be maintained at manufacturer's recommendations. Usable fluid volume will be recorded. Reservoir capacity will be recorded. Reservoir fluid level will be recorded along with manufacturer's recommendation. All will be kept on location through the end of the well.
- ☐ Closing unit system will have two independent power sources (not counting accumulator bottles) to close the preventers.
- ☐ Power for the closing unit pumps will be available to the unit at all times so that the pumps will automatically start when the closing valve manifold pressure decreases to the pre-set level. It is recommended to check that air line to accumulator pump is "ON" during each tour change.
- ☐ With accumulator bottles isolated, closing unit will be capable of opening the hydraulically-operated choke line valve (if used) plus close the annular preventer on the smallest size drill pipe within 2 minutes and obtain a minimum of 200 psi above maximum acceptable precharge pressure (see table above) on the closing manifold. Test pressure and closing time will be recorded and kept on location through the end of the well.
- ☐ Master controls for the BOPE system will be located at the accumulator and will be capable of opening and closing all preventer and the choke line valve (if used)
- ☐ Remote controls for the BOPE system will be readily accessible (clear path) to the driller and located on the rig floor (not in the dog house). Remote controls will be capable of closing all preventers.
- ☐ Record accumulator tests in drilling reports and IADC sheet

### BOPE Test Checklist

The following item must be checked off prior to beginning test

- ☐ BLM will be given at least 4 hour notice prior to beginning BOPE testing
- ☐ Valve on casing head below test plug will be open
- ☐ Test will be performed using clear water.

The following item must be performed during the BOPE testing and then checked off

- ☐ BOPE will be pressure tested when initially installed, whenever any seal subject to test pressure is broken, following related repairs, and at a minimum of 30 days intervals. Test pressure and times will be recorded by a 3<sup>rd</sup> party on a test chart and kept on location through the end of the well.
- ☐ Test plug will be used
- ☐ Ram type preventer and all related well control equipment will be tested to 250 psi (low) and 5,000 psi (high).
- ☐ Annular type preventer will be tested to 250 psi (low) and 3,500 psi (high).
- ☐ Valves will be tested from the working pressure side with all down stream valves open. The check valve will be held open to test the kill line valve(s)
- ☐ Each pressure test will be held for 10 minutes with no allowable leak off.
- ☐ Master controls and remote controls to the closing unit (accumulator) must be function tested as part of the BOP testing
- ☐ Record BOP tests and pressures in drilling reports and IADC sheet

After Installation Checklist is complete, fill out the information below and email to Superintendent and Drilling Engineer along with any/all BOP and accumulator test charts and reports from 3<sup>rd</sup> parties.


Wellname: \_\_\_\_\_

Representative: \_\_\_\_\_

Date: \_\_\_\_\_

# Exhibit D

## Nabors Pace X Section 18-19 4<sup>th</sup> Pad



**NOTE:**

Please be advised, that while reasonable efforts are made to locate and verify pipelines and anomalies using our standard pipeline locating equipment, it is impossible to be 100% effective. As such, we advise using caution when performing work as there is a possibility that pipelines and other hazards, such as fiber optic cables, PVC pipelines, etc. may exist undetected on site.

**NOTE:**

Many states maintain information centers that establish links between those who dig (excavators) and those who own and operate underground facilities (operators). It is advisable and in most states, law, for the contractor to contact the center for assistance in locating and marking underground utilities. For guidance: New Mexico One Call - [www.nmonecall.org](http://www.nmonecall.org)


**DISCLAIMER:** At this time, C.H. Fenstermaker & Associates, LLC has not performed nor was asked to perform any type of engineering, hydrological modeling, flood plain, or "No Rise" certification analyses, including but not limited to determining whether the project will impact flood hazards in connection with federal/FEMA, state, and/or local laws, ordinances and regulations. Accordingly, Fenstermaker makes no warranty or representation of any kind as to the foregoing issues, and persons or entities using this information shall do so at their own risk.

| NW ARCH. AREA CORNER            | NE ARCH. AREA CORNER                             | SE ARCH. AREA CORNER                  | SW ARCH. AREA CORNER            | SALADO DRAW 19 26 33 FED 2H WELL   |
|---------------------------------|--------------------------------------------------|---------------------------------------|---------------------------------|------------------------------------|
| X= 721,819 NAD 27<br>Y= 377,707 | X= 722,494 NAD 27<br>Y= 377,713                  | X= 722,500 NAD 27<br>Y= 377,713       | X= 721,824 NAD 27<br>Y= 377,707 | X= 722,187 NAD 27<br>Y= 377,710    |
| ELEVATION +3187' NAVD 88        | ELEVATION +3187' NAVD 88                         | ELEVATION +3187' NAVD 88              | ELEVATION +3172' NAVD 88        | LAT. 32.035588<br>LONG. 103.616289 |
| NW TOP SOIL AREA CORNER         | NE TOP SOIL AREA CORNER                          | SE TOP SOIL AREA CORNER/NE PAD CORNER | SW TOP SOIL AREA CORNER         |                                    |
| X= 721,910 NAD 27<br>Y= 377,573 | X= 722,320 NAD 27<br>Y= 377,576                  | X= 722,321 NAD 27<br>Y= 377,536       | X= 721,913 NAD 27<br>Y= 377,203 | X= 763,384 NAD 83<br>Y= 377,468    |
| ELEVATION +3177' NAVD 88        | ELEVATION +3178' NAVD 88                         | ELEVATION +3178' NAVD 88              | ELEVATION +3172' NAVD 88        | LAT. 32.035713<br>LONG. 103.616757 |
| NW PAD CORNER                   | SE PAD CORNER/NE FACILITY PAD CORNER             | SW PAD CORNER                         | NW COMPRESSOR SITE CORNER       | NE COMPRESSOR SITE CORNER          |
| X= 721,951 NAD 27<br>Y= 377,534 | X= 722,323 NAD 27<br>Y= 377,206                  | X= 721,953 NAD 27<br>Y= 377,204       | X= 722,324 NAD 27<br>Y= 377,107 | X= 722,524 NAD 27<br>Y= 377,108    |
| ELEVATION +3176' NAVD 88        | ELEVATION +3178' NAVD 88                         | ELEVATION +3173' NAVD 88              | ELEVATION +3179' NAVD 88        | ELEVATION +3175' NAVD 88           |
| NW FACILITY PAD CORNER          | SE FACILITY PAD CORNER/SW COMPRESSOR SITE CORNER | SW FACILITY PAD CORNER                | SE COMPRESSOR SITE CORNER       |                                    |
| X= 722,023 NAD 27<br>Y= 377,204 | X= 722,025 NAD 27<br>Y= 376,904                  | X= 722,025 NAD 27<br>Y= 376,904       | X= 722,525 NAD 27<br>Y= 376,908 | ELEVATION +3188' NAVD 88           |
| ELEVATION +3173' NAVD 88        | ELEVATION +3173' NAVD 88                         | ELEVATION +3171' NAVD 88              | ELEVATION +3185' NAVD 88        |                                    |

Sec. 18

Bureau of Land Management

R 33 E

T  
26  
S


Sec. 19

Bureau of Land Management

FOR THE EXCLUSIVE USE OF

CHEVRON U.S.A. INC.

I, WM. J. Daniel III, Registered Professional Land Surveyor, do hereby state this plat is true and correct to the best of my knowledge.

WM. J. Daniel III  
Registration No. 15078

N=27 NEW MEXICO EAST ZONE

| LEGEND |                   |
|--------|-------------------|
| —      | Section Line      |
| —X—    | Fence Line        |
| - - -  | Ditch             |
| - - -  | Existing Pipeline |

CHEVRON U.S.A. INC.

PROPOSED PAD &amp; ACCESS ROAD

SALADO DRAW 19 26 33 FED 2H WELL

SECTION 19, T26S-R33E &amp; SECTIONS 23 &amp; 24, T26S-R32E

LEA COUNTY, NEW MEXICO

Page 1 of 2

135 Regency Sq. Lafayette, LA 70508  
Ph. 337-237-2200 Fax. 337-232-3299  
[www.fenstermaker.com](http://www.fenstermaker.com)Scale: 1"=100'  
100' 0 50' 100'

| DRAWN BY: VHV                                                     |       | REVISIONS          |                 |
|-------------------------------------------------------------------|-------|--------------------|-----------------|
| PROJ. MGR.: VHV                                                   | No. 1 | DATE: June 2, 2014 | REVISED BY: GDG |
| DATE: APRIL 24, 2014                                              | No.   | DATE:              | REVISED BY:     |
| FILENAME: T:\2014\2144673\DWG\Salado Draw 19 26 33 Fed 2H_SUP.dwg |       |                    |                 |