

BC Operating, Inc., Dogie Draw 23 Federal #2H

1. Geologic Formations

TVD of target	12250	Pilot hole depth	12750
MD at TD:	17282	Deepest expected fresh water:	450

HOBBS OCO

MAR 09 2017

RECEIVED

Basin

Formation	Depth (TVD) from KB)	Water/Mineral Bearing/ Target Zone?	Hazards*
Quaternary Alluvium	Surface	Water	
Rustler	875		
Salado	1350		
Castile	3700		
Lamar	5350		
Delaware Sands	5375	Oil/Gas	
Bone Spring Lime	9300	Oil/Gas	
First BS Sand	10400	Oil/Gas	
Second Carbonate	10600	Oil/Gas	
Second BS Sand	10900	Oil/Gas	
Third Carbonate	11400	Oil/Gas	
Third BS Sand	12000	Target Zone	
Wolfcamp	12500		
TD Pilot Hole	12750		

*H2S, water flows, loss of circulation, abnormal pressures, etc.

2. Casing Program

See COA

Hole Size	Casing Interval		Csg. Size	Weight (lbs)	Grade	Conn.	SF Collapse	SF Burst	SF Tension
	From	To							
16"	0	600' 1000'	13.375"	61	J55	STC	5.55	1.1	16.26
12.25"	0	5100	9.625"	40	N80	LTC	1.17	1.47	3.41
12.25"	5100	5400	9.625"	40	C95	LTC	1.18	1.03	70.58
8.75"	0	17282	5.5"	17	P110 HC	SEMI BUTT	1.13	1.61	2.73
						BLM Minimum Safety Factor	1.125	1	1.6 Dry 1.8 Wet

All casing strings will be tested in accordance with Onshore Oil and Gas Order #2 III.B.1.h

Must have table for contingency casing

BC Operating, Inc., Dogie Draw 23 Federal #2H

	Y or N
Is casing new? If used, attach certification as required in Onshore Order #1	Y
Does casing meet API specifications? If no, attach casing specification sheet.	Y
Is premium or uncommon casing planned? If yes attach casing specification sheet.	Y
Does the above casing design meet or exceed BLM's minimum standards? If not provide justification (loading assumptions, casing design criteria).	Y
Will the intermediate pipe be kept at a minimum 1/3 fluid filled to avoid approaching the collapse pressure rating of the casing?	Y
Is well located within Capitan Reef?	N
If yes, does production casing cement tie back a minimum of 50' above the Reef?	
Is well within the designated 4 string boundary.	N
Is well located in SOPA but not in R-111-P?	N
If yes, are the first 2 strings cemented to surface and 3 rd string cement tied back 500' into previous casing?	
Is well located in R-111-P and SOPA?	N
If yes, are the first three strings cemented to surface?	
Is 2 nd string set 100' to 600' below the base of salt?	
Is well located in high Cave/Karst?	N
If yes, are there two strings cemented to surface?	
(For 2 string wells) If yes, is there a contingency casing if lost circulation occurs?	
Is well located in critical Cave/Karst?	N
If yes, are there three strings cemented to surface?	

BC Operating, Inc., Dogie Draw 23 Federal #2H

3. Cementing Program

Casing	# Sks	Wt. lb/ gal	Yld ft3/ sack	H ₂ O gal/ sk	500# Comp. Strength (hours)	Slurry Description
Surf.	230	13.5	1.757	9.1	10	Lead: ExtendaCem + 2 lbm Kol-Seal + 0.125 lbm Poly-E-Flake
	200	14.8	1.345	6.2	8	Tail: HalCem + 2 lbm Kol-Seal + 0.125 lbm Poly-E-Flake + 1% Calcium Chloride - flake
Inter.	1530	12.6	1.934	10. 36	15	Lead: EconoCem + 0.25 lbm Poly-E-Flake + 0.60% Halad®-9 + 3 lbm Kol-Seal
	370	14.8	1.339	6.1 3	11	Tail: HalCem + 3 lbm Kol-Seal + 0.25 lbm Poly-E-Flake
Prod.	1380	11.9	2.303	13. 19	24	Lead: VersaCem + 10% Bentonite + 2 lbm Kol-Seal + 0.25 lbm D-Air 5000 + 0.50% HR-601
	1000	15	2.625	11. 4	10	Tail: SoluCem + 0.25 lbm D-Air 5000 + 0.80% HR-601 (Acid Soluble Cement)

DV tool depth(s), if used, will be adjusted based on hole conditions and cement volumes will be adjusted proportionally. DV tool will be set a minimum of 50 feet below previous casing and a minimum of 200 feet above current shoe. Lab reports with the 500 psi compressive strength time for the cement will be onsite for review.

Casing String	TOC	% Excess
Surface	0'	100%
Intermediate	0'	100%
Production	0'	30%

Include Pilot Hole Cementing specs: (Optional in subsequent wells in same section)

Pilot hole depth 12750

KOP 11677

Plug top	Plug Bottom	% Excess	No. Sacks	Wt. lb/gal	Yld ft3/sack	Water gal/sk	Slurry Description and Cement Type
11600	12050	13	180	15.6	1.18	5	Class H + 0.3% R-20
12450	12750	13	120	15.6	1.18	5	Class H + 0.3% R-20

4. Pressure Control Equipment

N	A variance is requested for the use of a diverter on the surface casing. See attached for schematic.
---	--

BOP installed and tested before drilling which hole?	Size?	Min. Required WP	Type	✓	Tested to:
16"	20"	2M	Annular	x	50% of working pressure
			Blind Ram		2M
			Pipe Ram		
			Double Ram		
			Other*		
12-1/4"	13-5/8"	2M	Annular	x	50% testing pressure
			Blind Ram		2M
			Pipe Ram		
			Double Ram		
			Other*		
8-3/4"	11"	5M 3M	Annular	X	50% testing pressure
			Blind Ram	X	5M 3M
			Pipe Ram	X	
			Double Ram		
			Other*		

*Specify if additional ram is utilized.

BOP/BOPE will be tested by an independent service company to 250 psi low and the high pressure indicated above per Onshore Order 2 requirements. The System may be upgraded to a higher pressure but still tested to the working pressure listed in the table above. If the system is upgraded all the components installed will be functional and tested.

Pipe rams will be operationally checked each 24 hour period. Blind rams will be operationally checked on each trip out of the hole. These checks will be noted on the daily tour sheets. Other accessories to the BOP equipment will include a Kelly cock and floor safety valve (inside BOP) and choke lines and choke manifold. See attached schematics.

X	Formation integrity test will be performed per Onshore Order #2. On Exploratory wells or on that portion of any well approved for a 5M BOPE system or greater, a pressure integrity test of each casing shoe shall be performed. Will be tested in
---	---

BC Operating, Inc., Dogie Draw 23 Federal #2H

	accordance with Onshore Oil and Gas Order #2 III.B.1.i.
X	A variance is requested for the use of a flexible choke line from the BOP to Choke Manifold. See attached for specs and hydrostatic test chart.
N	Are anchors required by manufacturer?
N	<p>A multibowl wellhead is being used. The BOP will be tested per Onshore Order #2 after installation on the surface casing which will cover testing requirements for a maximum of 30 days. If any seal subject to test pressure is broken the system must be tested.</p> <ul style="list-style-type: none"> • Provide description here <p>See attached schematic.</p>

5. Mud Program

Depth		Type	Weight (ppg)	Viscosity	Water Loss
From	To				
0	Surf. shoe	FW Gel	8.5-9.2	28-34	N/C
Surf csg	Int shoe	Brine	9.6-10	28-34	N/C
Int shoe	TD	Cut Brine/EVO	8.4-8.9	28-34	<15

Sufficient mud materials to maintain mud properties and meet minimum lost circulation and weight increase requirements will be kept on location at all times.

What will be used to monitor the loss or gain of fluid?	PVT/Pason/Visual Monitoring
---	-----------------------------

6. Logging and Testing Procedures

Logging, Coring and Testing.	
X	Will run GR/CNL from TD to surface (horizontal well – vertical portion of hole). Stated logs run will be in the Completion Report and submitted to the BLM.
	No Logs are planned based on well control or offset log information.
	Drill stem test? If yes, explain
	Coring? If yes, explain

Additional logs planned		Interval
X	Resistivity	Int. shoe to KOP
X	Density	Int. shoe to KOP
X	CBL	Production casing
X	Mud log	Intermediate shoe to TD
	PEX	

7. Drilling Conditions

Condition	Specify what type and where?
BH Pressure at deepest TVD	3900 psi
Abnormal Temperature	No

Mitigation measure for abnormal conditions. Describe. Lost circulation material/sweeps/mud scavengers.

Hydrogen Sulfide (H₂S) monitors will be installed prior to drilling out the surface shoe. If H₂S is detected in concentrations greater than 100 ppm, the operator will comply with the provisions of Onshore Oil and Gas Order #6. If Hydrogen Sulfide is encountered, measured values and formations will be provided to the BLM.

	H ₂ S is present
X	H ₂ S Plan attached

8. Other facets of operation

Is this a walking operation? N. If yes, describe.

Will be pre-setting casing? N. If yes, describe.

Attachments

☒ Directional Plan

☒ Other, describe

- Improved 5.5" casing thread design example
- 20" annular
- 13-5/8" annular
- 11" BOPE
- Flexible hose specs and test chart

GB Connection Performance Properties Sheet

Rev. 1 (02/05/2014)

ENGINEERING THE RIGHT CONNECTIONS™

Casing: 5.5 OD, 17 ppf
Grade: P-110

Connection: GB CD Butt 6.050
Grade: API P-110

PIPE BODY GEOMETRY

Nominal OD (in.)	5 1/2	Wall Thickness (in.)	0.304	Drift Diameter (in.)	4.767
Nominal Weight (ppf)	17.00	Nominal ID (in.)	4.892	API Alternate Drift Dia. (in.)	N/A
Plain End Weight (ppf)	16.89	Plain End Area (in. ²)	4.962		

PIPE BODY PERFORMANCE

Material Specification	P-110	Min. Yield Str. (psi)	110,000	Min. Ultimate Str. (psi)	125,000
Collapse		Tension		Pressure	
API (psi)	7,480	Pl. End Yield Str. (kips)	546	Min. Int. Yield Press. (psi)	10,640
High Collapse (psi)	8,580	Torque		Bending	
		Yield Torque (ft-lbs)	64,680	Build Rate to Yield (°/100 ft)	91.7

GB CD Butt 6.050 COUPLING GEOMETRY

Coupling OD (in.)	6.050	Makeup Loss (in.)	4.2500
Coupling Length (in.)	8.500	Critical Cross-Sect. (in. ²)	6.102

GB CD Butt 6.050 CONNECTION PERFORMANCE RATINGS/EFFICIENCIES

Material Specification	API P-110	Min. Yield Str. (psi)	110,000	Min. Ultimate Str. (psi)	125,000
Tension		Efficiency		Bending	
Thread Str. (kips)	568	Internal Pressure (%)	100%	Build Rate to Yield (°/100 ft)	83.3
Min. Tension Yield (kips)	638	External Pressure (%)	100%	Yield Torque	
Min. Tension Ult. (kips)	725	Tension (%)	100%	Yield Torque (ft-lbs)	17,030
Joint Str. (kips)	568	Compression (%)	100%		
		Ratio of Areas (Cplg/Pipe)	1.23		

MAKEUP TORQUE

Min. MU Tq. (ft-lbs)	6,470	Max. MU Tq. (ft-lbs)	12,940	Running Tq. (ft-lbs)	See GBT RP
				Max. Operating Tq. (ft-lbs)*	16,180

Units: US Customary (lbm, in., °F, lbf)

1 kip = 1,000 lbs


* See Running Procedure for description and limitations.

See attached: Notes for GB Connection Performance Properties.

GBT Running Procedure (GBT RP): www.gbtubulars.com/pdf/RP_GB_DWC_Connections.pdf


Blanking Dimensions: www.gbtubulars.com/pdf/GB_DWC_Blaning_Dimensions.pdf

20" 2K Annular




BC Operating, Inc.
Exhibit 1


2,000 psi BOP Schematic



11" x 5,000 psi BOP Stack



Choke Manifold Configuration with "Closed Loop System"



Choke Manifold - 3" minimum

Notes:

- Equipment configuration may vary
- Choke manifold may be located in any convenient position. Use steel fittings throughout. Make 90° turns with ball plugged tees only. No field welding will be permitted on any of the components of the choke manifold and related equipment upstream of the chokes. The choke spool and all lines and fittings must be at least equivalent to the test pressure of the preventers required. Independent closing control unit with clearly marked controls to be located on derrick floor near



Fluid Technology

Quality Document

QUALITY CONTROL	No.: QC-DB- 89 / 2011
	Page : 1 / 54
Hose No.: 60313, 60314, 60315, 60316	Revision : 0
	Date: 07. March 2011.
	Prepared by: <i>[Signature]</i>
	Appr. by: <i>[Signature]</i>

CHOKE AND KILL HOSES

id.: 3" 68,9 MPa x (25 ft) 7,62 m 1 pc
x (45 ft) 13,72 m 3 pcs

DATA BOOK

Purchaser:

Purchaser Order No.:

ContiTech Rubber Order No.: 493934

ContiTech Beattie Co. Order No.: 004795

ASSET 66-0638, 66-0639, 66-0640, 66-0641

ContiTech Rubber Industrial Kft.
Budapesti út 10., Szeged H-6728
P.O.Box 152 Szeged H-6701
Hungary

Phone: +36 62 566 737
Fax: +36 62 566 738
e-mail: info@fluid.contitech.hu
Internet: www.contitech-rubber.hu

The Court of Csongrád County as
Registry Court
Registry Court No: HU 06-09-002502
EU VAT No: HU11067209

Bank data
Commerzbank Zrt.
Budapest
14220106-28830003-00000000


ATTACHMENT OF QUALITY CONTROL INSPECTION AND TEST CERTIFICATE

No: 246, 249

Page: 1 / 1

Handwritten signature

Corstech Rubber
Industrial Kft.
Quality Control Dept.
(1)





Hose Data Sheet

CRI Order No.	493934
Customer	ContiTech Beattie Co.
Customer Order No	PO4795, PBC10685
Item No.	3
Hose Type	Flexible Hose
Standard	API SPEC 16 C
Inside dia in inches	3
Length	25 ft
Type of coupling one end	FLANGE 4.1/16" 10KPSI API SPEC 17D SV SWIVEL FLANGEC/W BX155 ST/ST INLAID RING GR
Type of coupling other end	FLANGE 4.1/16" 10KPSI API SPEC 17D SV SWIVEL FLANGE C/W BX155 ST/ST INLAID RING GR
H2S service NACE MR0175	Yes
Working Pressure	10 000 psi
Design Pressure	10 000 psi
Test Pressure	15 000 psi
Safety Factor	2,25
Marking	USUAL PHOENIX
Cover	NOT FIRE RESISTANT
Outside protection	St. steel outer wrap
Internal stripwound tube	No
Lining	OIL RESISTANT
Safety clamp	Yes
Lifting collar	Yes
Element C	Yes
Safety chain	No
Safety wire rope	Yes
Max.design temperature [°C]	100
Min.design temperature [°C]	-20
MBR operating [m]	1,60
MBR storage [m]	1,40
Type of packing	WOODEN CRATE ISPM-15

BC Operating, Inc. Closed Loop System

Design Plan

Equipment List

- 2 – 414 MI Swaco *Centrifuges*
- 2 – MI Swaco 4 screen *Moongoose Shale Shakers*
- 2 – double screen *Shakers* with rig inventory
- 2 – CRI *Haul off bins* with track system
- 2 – additional 500bbl *Frac tanks* for fresh and brine water
- 2 – 500bbl *water tanks* with rig inventory


**Equipment manufactures may vary due to availability but components will not.*

Operation and Maintenance

The system along with equipment will be inspected numerous times a day by each tour to make sure all equipment is operating correctly. Routine maintenance will be done to keep system running properly. Any leak in system will be repaired and/or contained immediately and the OCD notified within 48 hours of the remediation process start.


Closure Plan

While drilling, all cuttings and fluids associated with drilling will be hauled off and disposed of via Controlled Recovery Incorporated Facilities Permit NM01-0006.



TYPICAL
RIG LAYOUT SCHEMATIC
INCLUSIVE OF CLOSED-LOOP DESIGN PLAN

BC Operating, Inc.
Dogie Draw Federal #2H
SHL: 240' FNL & 1980' FEL, Unit Letter 'C'
Section 26, T-25S, R-34E
Lea County, New Mexico



BC Operating, Inc.
Statement of Certification

HOBBS OCD
MAR 09 2017
RECEIVED

Dogie Draw 23 Federal #2H

SHL: 240' FNL & 1980' FWL of Unit Letter 'C', Section 26, T-25S, R-34E

BHL: 240' FNL & 1980' FWL of Unit Letter 'C', Section 23, T-25S, R-34E

Lea County, New Mexico

This Statement of Certification is submitted with Form 3160-3, Application for Permit to Drill in accordance with BLM Onshore Oil and Gas Order Number 1 Section III.D.6., covering the above described well.

Certification:

I hereby certify that I, or someone under my direct supervision, have inspected the drill site and access route proposed herein; that I am familiar with the conditions which currently exist; that I have full knowledge of state and Federal laws applicable to this operation; that the statements made in this APD package are, to the best of my knowledge, true and correct; and that the work associated with the operations proposed herein will be performed in conformity with this APD package and the terms and conditions under which it is approved. I also certify that I, or the company I represent, am responsible for the operations conducted under this application. These statements are subject to the provisions of 18 U.S.C. 1001 for the filing of false statements.

Executed this 15th day of April, 2015.

Pam Stevens

Pam Stevens

Name: Pam Stevens
Position Title: Regulatory Analyst, BC Operating, Inc.
Address: P.O. Box 50820 – Midland, Texas 79710
Telephone: 432-684-9696

BC Operating, Inc.

Statement of Bond Coverage

Dogie Draw 23 Federal #2H

SHL: 240' FNL & 1980' FWL of Unit Letter 'C', Section 26, T-25S, R-34E

BHL: 240' FNL & 1980' FWL of Unit Letter 'C', Section 23, T-25S, R-34E

Lea County, New Mexico

This Statement of Bond Coverage is submitted with Form 3160-3, Application for Permit to Drill in accordance with BLM Onshore Oil and Gas Order Number 1 Section III.D.5., covering the above described well.


Bond Coverage: Statewide
BLM Bond File #: NM-2572

BC Operating, Inc.

Pam Stevens

Pam Stevens
Regulatory Analyst

BC Operating, Inc.
Dogie Draw 23 Federal #2H
240' FNL & 1980' FWL of Unit Letter 'C'
Section 26, T-25S, R-34E



Gray area to be reclaimed and seeded to BLM regulations