

2630

Submit 3 Copies To Appropriate District Office
District I
1625 N. French Dr., Hobbs, NM 87240
District II
811 South First, Artesia, NM 87210
District III
1000 Rio Brazos Rd., Aztec, NM 87410
District IV
2040 South Pacheco, Santa Fe, NM 87505

State of New Mexico
Energy, Minerals and Natural Resources

OIL CONSERVATION DIVISION
2040 South Pacheco
Santa Fe, NM 87505

Form C-103
Revised March 25, 1999


SUNDRY NOTICES AND REPORTS ON WELLS (DO NOT USE THIS FORM FOR PROPOSALS TO DRILL OR TO DEEPEN OR PLUG BACK TO A DIFFERENT RESERVOIR. USE "APPLICATION FOR PERMIT" (FORM C-101) FOR SUCH PROPOSALS.)		WELL API NO. 30-025-34134
1. Type of Well: Oil Well <input checked="" type="checkbox"/> Gas Well <input type="checkbox"/> Other <input type="checkbox"/>		5. Indicate Type of Lease STATE <input checked="" type="checkbox"/> FEE <input type="checkbox"/>
2. Name of Operator Xeric Oil & Gas Corporation		6. State Oil & Gas Lease No. E-1782
3. Address of Operator P. O. Box 352 Midland, TX 79702		7. Lease Name or Unit Agreement Name: Union State AB
4. Well Location Unit Letter <u>B</u> : <u>660</u> feet from the <u>North</u> line and <u>1980</u> feet from the <u>East</u> line Section <u>30</u> Township <u>20S</u> Range <u>36E</u> NMPM Lea County		8. Well No. 2
10. Elevation (Show whether DR, RKB, RT, GR, etc.) 3648' GR		9. Pool name or Wildcat Eumont Yates SR Queen

11. Check Appropriate Box to Indicate Nature of Notice, Report or Other Data	
NOTICE OF INTENTION TO: PERFORM REMEDIAL WORK <input type="checkbox"/> PLUG AND ABANDON <input checked="" type="checkbox"/> TEMPORARILY ABANDON <input type="checkbox"/> CHANGE PLANS <input type="checkbox"/> PULL OR ALTER CASING <input type="checkbox"/> MULTIPLE COMPLETION <input type="checkbox"/> OTHER: <input type="checkbox"/>	SUBSEQUENT REPORT OF: REMEDIAL WORK <input type="checkbox"/> ALTERING CASING <input type="checkbox"/> COMMENCE DRILLING OPNS. <input type="checkbox"/> PLUG AND ABANDONMENT <input type="checkbox"/> CASING TEST AND CEMENT JOB <input type="checkbox"/> OTHER: <input type="checkbox"/>

12. Describe proposed or completed operations. (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work). SEE RULE 1103. For Multiple Completions: Attach wellbore diagram of proposed completion or recompilation.

- 1) MIRU Pulling Unit.
- 2) Spot 25 sx @3960' & tag.
- 3) Circulate hole w/9.5# mud.
- 4) Spot 25 sx @ 2000' & tag.
- 5) Perf & squeeze 50 sx @ 385' & circulate to surface.
- 6) Spot 5 sx from 50' to surface.
- 7) Install dry hole marker & clean location.

THE COMMISSION MUST BE NOTIFIED 24 HOURS PRIOR TO THE BEGINNING OF PLUGGING OPERATIONS FOR THE C-103 TO BE APPROVED.



I hereby certify that the information above is true and complete to the best of my knowledge and belief.

SIGNATURE Angie Crawford TITLE Production Analyst DATE 3/2/04
Type or print name ACrawford@xericoil.com 432-683-2171
(This space for State use) Telephone No.

APPROVED BY Ray W. Wink TITLE FIELD REPRESENTATIVE II/STAFF MANAGER DATE 10 2004
Conditions of approval, if any:

XERIC OIL & GAS CORP.
WELLBORE DIAGRAM

WELL: Union State AB #2

COUNTY: Lea

STATE: NM

HOLE SIZE: 12 1/4"
CASING: 8 5/8" @ 382'
CEMENTED WITH: 250 SX
CEMENT TOP: Surf.

TUBING: _____
RODS: _____
PUMP: _____
PACKER: _____

PERFS:

3969' - 79'
C13P @ 4090'
4058' - 91'
C13P @ 4150'
4178' - 90'

PBTD: 4672'

TD: 4812'

HOLE SIZE: 7 7/8"
CASING: 5 1/2" @ 4778'
CEMENTED WITH: 580 SX
CEMENT TOP: 4600' Per ~~CB~~ CBL