- 5. Kill well, release packer, and POOH. RIH with bit and clean out to PBTD with foam. POOH. RIH with MA, perforated sub, SN, and 2 3/8" production tubing to  $\pm 3000$ '. ND BOP, NU wellhead. Deliver 3/4" grade KD rod string. RIH with 2" x 1.25" x 16' pump and rods. Space out and clamp off. Turn to production.
- 6. Production personnel will set pumpjack and lower tubing in 10 days.

Approved:		Date:
	T. J. Harrington	