

NM1 - 63

ENGINEERING CERTIFICATION REPORT

Cell 5-AB



May 10, 2023

Mr. Brad Jones
Environmental Scientist Specialist
Oil Conservation Division
New Mexico Energy, Minerals and Natural Resources
1220 South St. Francis Drive
Santa Fe, New Mexico 87505

Re: OWL NDBL SWMF Cell 5-AB Construction Plans
Document Received 4/24/2023

Dear Mr. Jones:

I have reviewed the construction plans and specifications for Cell 5-AB for its engineering content, completeness, and accuracy in accordance with NMAC 19.15.36 and/or applicable federal standards and guidelines, and generally acceptable engineering practice. The engineering firm of record is Parkhill, Inc. Contained herein are my observations and comments.

General:

Construction plans for Cell 5-AB and annotated specifications therein were provided by Parkhill, Inc. It is my professional opinion that the engineering detailed in the construction plans and specifications provided for Cell 5-AB components meets or exceeds the regulatory requirements established by the New Mexico Energy, Minerals and Natural Resources Department (NMEMNRD), Oil Conservation Division (OCD).

Construction Plans:

Construction drawing Sheets C-101 to 104 (Civil); C-301 (Subgrade cross-sections); and C-501 to 504 (Details) were reviewed. Cell 5-AB adjoins Cell 4-AB to the east and future Cell 6 to the west. The elements of design for Cell 5-AB were detailed. These details were annotated for efficient review of the proposed design. No design issues were noted as per the proposed cell layout and tie-in configuration with respect to Cell 4-AB and future Cell 6, base subgrade, cell cross-sections, floor and sidewall liner details, leachate management and temporary sump leak detection details, constructed cell fill, and interim stormwater management. Typical details for these design elements were provided and are the same as provided for approved Cells 3-AB and 4-AB. General engineering details for liner fusion and extrusion seaming and liner repair are typical per industry standard and are compliant with prescriptive regulatory requirements.

As stated the multi-layered liner system for cell bottom and sideslope is the same as approved for Cells 3-AB and 4-AB. An inside cell slope of 4H:1V is provided at the northern portion of the Cell 5-AB with an outside slope of 3H:1V. A general note indicates a specified compaction density for this fill construction at 90% standard proctor dry density

(ASTM D698). The anchor trench constructed at the top of the berm fill also specifies a 90% standard proctor dry density. No cut-fill estimates based on the cut-fill tic plan (Sheet C-104) were provided as was done for Cell 4-AB; however, based on the north-south cross-section existing topography and proposed in-ground cell layout, it is my professional opinion that a net soil volume balance would be available, more than sufficient to construct the northern berm. L-shaped liner anchorage is typical per industry standard and compliant with regulatory requirements. The specified bottom cross-slope on the subgrade grading plan for Cell 5-AB provides a 2.5% minimum liner slope. Compaction for the subgrade and is specified at 90 % standard proctor dry density.

The leachate collection trench at 2.5 % exceeds the minimum prescriptive slope requirement of 2 %. Leachate collection trench and piping as well as cleanout riser and trench are typical per industry standard and are compliant with prescriptive regulatory requirements. A 2 ft protective soil layer over the double composite liner system meets the prescriptive depth requirement. A saturated hydraulic conductivity of greater than or equal to 4.2×10^{-5} exceeds the prescriptive requirement.

Cell transition details for Cell 5-AB to the west and south at the lower portion of Cell 5-AB are typical per industry standard and are compliant with prescriptive regulatory requirements. A temporary sump for leachate extraction and leak detection was provided at the south end of Cell 5-AB for tie-in downgradient. These details are typical per industry standard and are compliant with prescriptive regulatory requirements. Easy access to leachate extraction and monitoring of leakage through the primary barrier layer is facilitated with the design provided.

Materials of Construction Compatibility:

No comment is needed as the geocomposites, HDPE geomembranes, geosynthetic clay liner, and HDPE collection pipe specified are industry standard materials of construction for landfills.

Conclusion:

Based on a review of the plans and specifications provided with one clarification as noted above, it is my professional opinion that the design for Cell 5-AB represents a state-of-the-art consensus practice for landfill engineering for this waste stream application.

If you require additional information or clarification on this review, please contact me directly at 505-835-5467 (w) or 505-838-6227 (c), or email me at clinton.richardson@nmt.edu.

Sincerely,

Clinton P. Richardson, Ph.D., P.E., BCEE

cc Matt Kingsley, PE.


OWL LANDFILL SERVICES, LLC

OWL NDBL SWMF

CELL 5AB

CONSTRUCTION PLANS


LEA COUNTY, NEW MEXICO



SHEET INDEX	
GENERAL	
G-001	COVER SHEET AND INDEX
CIVIL	
C-101	SITE PLAN EXISTING CONDITIONS
C-102	SITE DEVELOPMENT PLAN
C-103	LANDFILL SUBGRADE GRADING PLAN
C-104	LANDFILL SUBGRADE CUT-FILL TIC PLAN
CROSS SECTIONS	
C-301	LANDFILL SUBGRADE CROSS SECTIONS
DETAILS	
C-501	LANDFILL ENGINEERING DETAILS I
C-502	LANDFILL ENGINEERING DETAILS II
C-503	LANDFILL ENGINEERING DETAILS III
C-504	LANDFILL ENGINEERING DETAILS IV

LEGEND	
	PROPERTY BOUNDARY
	SECTION BOUNDARY
	SOLID WASTE DISPOSAL BOUNDARY
	PROCESSING AREA BOUNDARY
	CELL BOUNDARY
	PROJECT BOUNDARY
	BUILDING OUTLINE
	EXISTING EASEMENT
	EXISTING FENCE
	EXISTING PIPELINE
	EXISTING OVERHEAD ELECTRIC LINES
	EXISTING UNDERGROUND ELECTRIC LINE
	EXISTING BRINE LINE
	EXISTING CONTOUR - INDEX (10')
	EXISTING CONTOUR - INTERMEDIATE (2')
	PROPOSED GRADE CONTOUR - 10'
	PROPOSED GRADE CONTOUR - 2'
	PROPOSED TOP OF SLOPE
	PROPOSED TOE OF SLOPE
	EXISTING UNPAVED ROADWAY
	PROPOSED OCHOA INCLINED RAMP
	EXISTING PAVED ROADWAY
	EXISTING LEACHATE LINE
	PROPOSED LEACHATE LINE
	PROPOSED LINER TURNDOWN
	EXISTING DRAINAGE CHANNEL
	PROPOSED CULVERT
	BORING/WELL LOCATION
	GEOTECHNICAL BORING LOCATION
	POWER POLE
	POWER POLE
	CONTROL POINT
	LANDFILL FILL POINT (TO TOP OF SUBGRADE ELEVATION)
	LANDFILL CUT POINT (TO TOP OF SUBGRADE ELEVATION)
	TRANSITION ZONE
	PROJECT BOUNDARY

Parkhill



04/20/23

THIS DOCUMENT IS RELEASED UNDER THE AUTHORITY OF TYLER S. KRUEGER, P.E., NEW MEXICO LICENSE #24922 EXCLUSIVELY FOR THE PURPOSES CITED BELOW. IT IS NOT TO BE USED FOR ANY ADDITIONAL PURPOSES UNDER ANY CONDITION.
ALL REPORTS, DRAWINGS, SPECIFICATIONS, COMPUTER FILES, FIELD DATA, NOTES AND OTHER DOCUMENTS PREPARED BY THE ENGINEER AS INSTRUMENTS OF SERVICE SHALL REMAIN THE PROPERTY OF THE ENGINEER. THE ENGINEER SHALL RETAIN ALL COPYRIGHT, LAW, STATUTORY AND OTHER RESERVED RIGHTS, INCLUDING THE COPYRIGHT THEREON.

Parkhill.com

OWL NDBL SWMF
CELL 5AB
CONSTRUCTION PLANS



CLIENT

OWL LANDFILL
SERVICES, LLC.
2029 W. NM Hwy 128
JAL, NM 88252
LEA COUNTY

PROJECT NO.

7053.22


1 04/20/23 Issued for OCD review

- 02/07/22 Issued for client review


DATE DESCRIPTION

COVER SHEET
AND INDEX

G-001



FILE NAME: A:\2022\7053.22\03_DSGN\01_DWG\050_CIVIL\02_CONTENT\Cell 5AB\C-102-705322-7-22.dwg LAYOUT NAME: C-102 PRINTED: Thursday, April 20, 2023 - 9:24am USER: JCurley




GENERAL NOTE

- 1. PROPOSED GRADE = TOP OF SUBGRADE = EXCAVATION GRADE = BASE GRADE

SURVEY NOTES:

- 1. AERIAL TOPOGRAPHIC SURVEY BY PARKHILL 333 RIO RANCHO BLVD. NE, SUITE 400 RIO RANCHO, NM 87124 PHONE: (505-867-6990) DATE OF PHOTOGRAPHY: NOVEMBER 2022.
- 2. SURVEY CONTROL POINTS BY JOHN WEST SURVEYING CO., 412 N. DAL PASO ST., HOBBS, NM 88240 PHONE: (575-393-3117).
- 3. THE COORDINATES FOR THE PROJECT WERE ESTABLISHED BY RUNNING A STATIC OBSERVATION ON A SINGLE CONTROL POINT (CP DUKE) FOR 4.5 HOURS, RTK SURVEY METHODS ON 9 PANEL POINTS SET BY JOHN WEST SURVEYING CO. AND 5 EXISTING POINTS SET BY HARCROW SURVEYING, INC. (SURVEY DATE AUGUST 7, 2020).

Parkhill



THIS DOCUMENT IS RELEASED UNDER THE AUTHORITY OF TYLER S. KRUEGER, P.E., NEW MEXICO LICENSE #24922 EXCLUSIVELY FOR THE PURPOSES CITED BELOW. IT IS NOT TO BE USED FOR ANY ADDITIONAL PURPOSES UNDER ANY CONDITION.
ALL REPORTS, DRAWINGS, SPECIFICATIONS, COMPUTER FILES, FIELD DATA, NOTES AND OTHER DOCUMENTS PREPARED BY THE ENGINEER AS INSTRUMENTS OF SERVICE SHALL REMAIN THE PROPERTY OF THE ENGINEER. THE ENGINEER SHALL RETAIN ALL COPYRIGHT, LAW, STATUTORY AND OTHER RESERVED RIGHTS, INCLUDING THE COPYRIGHT THEREON.
Parkhill.com

OWL NDBL SWMF
CELL 5AB
CONSTRUCTION PLANS



CLIENT

OWL LANDFILL
SERVICES, LLC.
2029 W. NM Hwy 128
JAL, NM 88252
LEA COUNTY

PROJECT NO.
7053.22


1	04/20/23	Issued for OCD review
-	02/07/22	Issued for client review

DATE DESCRIPTION

SITE
DEVELOPMENT
PLAN

C-102

FILE NAME: A:\2022\7053.22\03_DSGN01_DWG\050_CIVIL\02_CONTENT\Cell 5AB\G-C-103-705322-7-22.dwg LAYOUT NAME: C-103 PRINTED: Thursday, April 20, 2023 - 9:27am USER: JCurley




GENERAL NOTE

1. PROPOSED GRADE = TOP OF SUBGRADE = EXCAVATION GRADE = BASE GRADE.
2. FILL SHALL BE COMPACTED TO A MINIMUM OF 90% STANDARD COMPACTION (ASTM D698) PER SPECIFICATION SECTION 31 23 23.10 - ENGINEERED STRUCTURAL FILL.

SURVEY NOTES:

1. AERIAL TOPOGRAPHIC SURVEY BY PARKHILL 333 RIO RANCHO BLVD. NE, SUITE 400 RIO RANCHO, NM 87124 PHONE: (505-867-6990) DATE OF PHOTOGRAPHY: NOVEMBER-2022.
2. SURVEY CONTROL POINTS BY JOHN WEST SURVEYING CO., 412 N. DAL PASO ST., HOBBS, NM 88240 PHONE: (575-393-3117).
3. THE COORDINATES FOR THE PROJECT WERE ESTABLISHED BY RUNNING A STATIC OBSERVATION ON A SINGLE CONTROL POINT (CP DUKE) FOR 4.5 HOURS, RTK SURVEY METHODS ON 9 PANEL POINTS SET BY JOHN WEST SURVEYING CO. AND 5 EXISTING POINTS SET BY HARCROW SURVEYING, INC. (SURVEY DATE AUGUST 7, 2020).

Parkhill



04/20/23

THIS DOCUMENT IS RELEASED UNDER THE AUTHORITY OF TYLER S. KRUEGER, P.E., NEW MEXICO LICENSE #24922 EXCLUSIVELY FOR THE PURPOSES CITED BELOW. IT IS NOT TO BE USED FOR ANY ADDITIONAL PURPOSES UNDER ANY CONDITION.

ALL REPORTS, DRAWINGS, SPECIFICATIONS, COMPUTER FILES, FIELD DATA, NOTES AND OTHER DOCUMENTS PREPARED BY THE ENGINEER AS INSTRUMENTS OF SERVICE SHALL REMAIN THE PROPERTY OF THE ENGINEER. THE ENGINEER SHALL RETAIN ALL COMMON LAW, STATUTORY AND OTHER RESERVED RIGHTS, INCLUDING THE COPYRIGHT THEREON.

Parkhill.com

OWL NDBL SWMF
CELL 5AB
CONSTRUCTION PLANS



CLIENT

OWL LANDFILL
SERVICES, LLC.
2029 W. NM Hwy 128
JAL, NM 88252
LEA COUNTY

PROJECT NO.

7053.22


1 04/20/23 Issued for OCD review

- 02/07/22 Issued for client review

DATE DESCRIPTION

LANDFILL
SUBGRADE
GRADING
PLAN

C-103




1. AERIAL TOPOGRAPHIC SURVEY BY PARKHILL 333 RIO RANCHO BLVD. NE, SUITE 400 RIO RANCHO, NM 87124 PHONE: (505-867-6990) DATE OF PHOTOGRAPHY: NOVEMBER-2022.
2. SURVEY CONTROL POINTS BY JOHN WEST SURVEYING CO., 412 N. DAL PASO ST., HOBBS, NM 88240 PHONE: (575-393-3117).
3. THE COORDINATES FOR THE PROJECT WERE ESTABLISHED BY RUNNING A STATIC OBSERVATION ON A SINGLE CONTROL POINT (CP DUKE) FOR 4.5 HOURS, RTK SURVEY METHODS ON 9 PANEL POINTS SET BY JOHN WEST SURVEYING CO. AND 5 EXISTING POINTS SET BY HARCROW SURVEYING, INC. (SURVEY DATE AUGUST 7, 2020).



1	04/20/23	Issued for OCD review
-	02/07/22	Issued for client review
#	DATE	DESCRIPTION

C-104




 EXISTING GRADE
 PROPOSED GRADE
 CELL 4AB EXCAVATION
 CELL 4AB FILL

TYLER S. KRUEGER
NEW MEXICO
24922
PROFESSIONAL ENGINEER
04/20/23

THIS DOCUMENT IS RELEASED UNDER THE AUTHORITY OF TYLER S. KRUEGER, P.E., NEW MEXICO LICENSE #24922 EXCLUSIVELY FOR THE PURPOSES CITED BELOW. IT IS NOT TO BE USED FOR ANY ADDITIONAL PURPOSES UNDER ANY CONDITION.

ALL REPORTS, DRAWINGS, SPECIFICATIONS, COMPUTER FILES, FIELD DATA, NOTES AND OTHER DOCUMENTS PREPARED BY THE ENGINEER AS INSTRUMENTS OF SERVICE SHALL REMAIN THE PROPERTY OF THE ENGINEER. THE ENGINEER SHALL RETAIN ALL COMMON LAW, STATUTORY AND OTHER RESERVED RIGHTS, INCLUDING THE COPYRIGHT THEREON.

Parkhill.com

**OWL NDBL SWMF
CELL 5AB
CONSTRUCTION PLANS**

**CLIENT**


**OWL LANDFILL
SERVICES, LLC.**
2029 W. NM Hwy 128
JAL, NM 88252
LEA COUNTY

PROJECT NO.

7053.22

1	04/20/23	Issued for OCD review
-	02/07/22	Issued for client review
#	DATE	DESCRIPTION

C-301




FILE NAME: A:\2022\7053.22\03_DSGN01_DWG\050_CIVIL\02_CONTENT\Cell 5AB\C-501-705322-7-22.dwg LAYOUT NAME: C-501 PRINTED: Thursday, April 20, 2023 - 9:24am USER: JCurley

D

C

B


A



- NOTES:
1. ALL EXTRUSION WELDS SHALL BE VACUUM TESTED

C1 TYPICAL EXTRUSION WELD


NOT TO SCALE SECTION VIEW



- NOTES:
1. ALL EXTRUSION WELDS SHALL BE VACUUM TESTED
 2. ALL DOUBLE TRACK FUSION WELDS SHALL BE AIR PRESSURE TESTED
 3. PANELS SHALL BE OVERLAPPED IN NUMERICAL ORDER - HIGHEST ON TOP

C2 TYPICAL HDPE LINER SEAM PATCH


NOT TO SCALE SECTION VIEW



- NOTES:
1. BOTH AREAS OF FUSED MATERIAL SHOULD BE VOID OF ANY SEAM LINES
 2. EDGE OF TRACKS NOT TO CUT THE LINER
 3. AIR CHANNEL SHOULD BE CLEAR
 4. BOTH WELDER TRACKS SHALL BE EQUAL WIDTHS
 5. SQUEEZE OUT SHOULD BE JUST BARELY VISIBLE IN ALL FOUR (4) LOCATIONS WHEN VIEWED IN THE TEST CROSS-SECTION
 6. ALL DOUBLE TRACK FUSION WELDS SHALL BE AIR PRESSURE TESTED

A1 TYPICAL DOUBLE TRACK FUSION WELD


NOT TO SCALE SECTION VIEW



- NOTES:
1. ALL EXTRUSION WELDS SHALL BE VACUUM TESTED
 2. ALL DOUBLE TRACK FUSION WELDS SHALL BE AIR PRESSURE TESTED
 3. PANELS SHALL BE OVERLAPPED IN NUMERICAL ORDER - HIGHEST ON TOP

A2 TYPICAL "T" AT BUTT SEAM

NOT TO SCALE SECTION VIEW




- NOTES:
1. ALL EXTRUSION WELDS SHALL BE VACUUM TESTED
 2. ALL DOUBLE TRACK FUSION WELDS SHALL BE AIR PRESSURE TESTED
 3. PANELS SHALL BE OVERLAPPED IN NUMERICAL ORDER - HIGHEST ON TOP

A3 TYPICAL PATCH AT PANEL END

NOT TO SCALE PLAN VIEW

Parkhill



04/20/23

THIS DOCUMENT IS RELEASED UNDER THE AUTHORITY OF TYLER S. KRUEGER, P.E., NEW MEXICO LICENSE #24922 EXCLUSIVELY FOR THE PURPOSES CITED BELOW. IT IS NOT TO BE USED FOR ANY ADDITIONAL PURPOSES UNDER ANY CONDITION.

ALL REPORTS, DRAWINGS, SPECIFICATIONS, COMPUTER FILES, FIELD DATA, NOTES AND OTHER DOCUMENTS PREPARED BY THE ENGINEER AS INSTRUMENTS OF SERVICE SHALL REMAIN THE PROPERTY OF THE ENGINEER. THE ENGINEER SHALL RETAIN ALL COMMON LAW, STATUTORY AND OTHER RESERVED RIGHTS, INCLUDING THE COPYRIGHT THEREO

Parkhill.com

OWL NDBL SWMF
CELL 5AB
CONSTRUCTION PLANS



CLIENT

OWL LANDFILL
SERVICES, LLC.
2029 W. NM Hwy 128
JAL, NM 88252
LEA COUNTY


PROJECT NO.
7053.22

1	04/20/23	Issued for OCD review
-	02/07/22	Issued for client review

#	DATE	DESCRIPTION
---	------	-------------


LANDFILL
ENGINEERING
DETAILS I

C-501




C2 LINER RUN-OUT ON LANDFILL FLOOR


NOT TO SCALE SECTION VIEW



B2 PERFORATED LEACHATE COLLECTION PIPE
NOT TO SCALE SECTION VIEW



A2 **SIDEWALL LINER SYSTEM WITH PSL SHOWN**
NOT TO SCALE SECTION VIEW



THIS DOCUMENT IS RELEASED UNDER THE AUTHORITY OF TYLER S. KRUEGER, P.E., NEW MEXICO LICENSE #24922 EXCLUSIVELY FOR THE PURPOSES CITED BELOW. IT IS NOT TO BE USED FOR ANY ADDITIONAL PURPOSES UNDER ANY CONDITION.

ALL REPORTS, DRAWINGS, SPECIFICATIONS, COMPUTER FILES, FIELD DATA, NOTES AND OTHER DOCUMENTS PREPARED BY THE ENGINEER AS INSTRUMENTS OF SERVICE SHALL REMAIN THE PROPERTY OF THE ENGINEER. THE ENGINEER SHALL RETAIN ALL COMMON LAW, STATUTORY AND OTHER RESERVED RIGHTS, INCLUDING THE COPYRIGHT THEREON.

Parkhill.com

**OWL NDBL SWMF
CELL 5AB
CONSTRUCTION PLANS**



CLIENT


**OWL LANDFILL
SERVICES, LLC.**
2029 W. NM Hwy 128
JAL, NM 88252
LEA COUNTY

PROJECT NO.
7053.22

1	04/20/23	Issued for OCD review
-	02/07/22	Issued for client review
#	DATE	DESCRIPTION


LANDFILL ENGINEERING DETAILS II

C-502




C2 HEADWALL ELEVATION

NOT TO SCALE ELEVATION VIEW



A2 PERMANENT ANCHOR TRENCH


NOT TO SCALE SECTION VIEW




PROJECT NO.
7053.22

LANDFILL ENGINEERING DETAILS III

C-503




C1 TYPICAL CELL TRANSITION AREA
NOT TO SCALE SECTION VIEW



A1 TEMPORARY SUMP DETAIL
NOT TO SCALE SECTION VIEW

Parkhill



THIS DOCUMENT IS RELEASED UNDER THE AUTHORITY OF TYLER S. KRUEGER, P.E., NEW MEXICO LICENSE #24922 EXCLUSIVELY FOR THE PURPOSES CITED BELOW. IT IS NOT TO BE USED FOR ANY ADDITIONAL PURPOSES UNDER ANY CONDITION.
ALL REPORTS, DRAWINGS, SPECIFICATIONS, COMPUTER FILES, FIELD DATA, NOTES AND OTHER DOCUMENTS PREPARED BY THE ENGINEER AS INSTRUMENTS OF SERVICE SHALL REMAIN THE PROPERTY OF THE ENGINEER. THE ENGINEER SHALL RETAIN ALL COMMON LAW, STATUTORY AND OTHER RESERVED RIGHTS, INCLUDING THE COPYRIGHT THEREOF.
Parkhill.com

OWL NDBL SWMF
CELL 5AB
CONSTRUCTION PLANS



CLIENT
OWL LANDFILL
SERVICES, LLC.
2029 W. NM Hwy 128
JAL, NM 88252
LEA COUNTY

PROJECT NO.
7053.22

1	04/20/23	Issued for OCD review
-	02/07/22	Issued for client review

LANDFILL
ENGINEERING
DETAILS IV

C-504

District I
1625 N. French Dr., Hobbs, NM 88240
Phone:(575) 393-6161 Fax:(575) 393-0720
District II
811 S. First St., Artesia, NM 88210
Phone:(575) 748-1283 Fax:(575) 748-9720
District III
1000 Rio Brazos Rd., Aztec, NM 87410
Phone:(505) 334-6178 Fax:(505) 334-6170
District IV
1220 S. St Francis Dr., Santa Fe, NM 87505
Phone:(505) 476-3470 Fax:(505) 476-3462

State of New Mexico
Energy, Minerals and Natural Resources
Oil Conservation Division
1220 S. St Francis Dr.
Santa Fe, NM 87505

CONDITIONS

Action 233930

CONDITIONS

Operator: OWL LANDFILL SERVICES, LLC 4143 Maple Avenue Dallas, TX 75219	OGRID: 371820
	Action Number: 233930
	Action Type: [C-137] Non-Fee SWMF Submittal (SWMF NON-FEE SUBMITTAL)

CONDITIONS

Created By	Condition	Condition Date
bjones	None	6/28/2023