

Form 3160-3
(June 2015)

FORM APPROVED
OMB No. 1004-0137
Expires: January 31, 2018

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT
APPLICATION FOR PERMIT TO DRILL OR REENTER

1a. Type of work: <input type="checkbox"/> DRILL <input type="checkbox"/> REENTER		5. Lease Serial No.
1b. Type of Well: <input type="checkbox"/> Oil Well <input type="checkbox"/> Gas Well <input type="checkbox"/> Other		6. If Indian, Allottee or Tribe Name
1c. Type of Completion: <input type="checkbox"/> Hydraulic Fracturing <input type="checkbox"/> Single Zone <input type="checkbox"/> Multiple Zone		7. If Unit or CA Agreement, Name and No.
2. Name of Operator [215099]		8. Lease Name and Well No. [330240]
3a. Address	3b. Phone No. (include area code)	9. API Well No. 30-025-50208
4. Location of Well (Report location clearly and in accordance with any State requirements. *) At surface At proposed prod. zone		10. Field and Pool, or Exploratory [98092] XXXXXX
14. Distance in miles and direction from nearest town or post office*		11. Sec., T. R. M. or Blk. and Survey or Area
15. Distance from proposed* location to nearest property or lease line, ft. (Also to nearest drig. unit line, if any)		12. County or Parish
16. No of acres in lease		13. State
17. Spacing Unit dedicated to this well		
18. Distance from proposed location* to nearest well, drilling, completed, applied for, on this lease, ft.		20. BLM/BIA Bond No. in file
19. Proposed Depth		
21. Elevations (Show whether DF, KDB, RT, GL, etc.)	22. Approximate date work will start*	23. Estimated duration
24. Attachments		

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No. 1, and the Hydraulic Fracturing rule per 43 CFR 3162.3-3 (as applicable)

- | | |
|--|---|
| 1. Well plat certified by a registered surveyor. | 4. Bond to cover the operations unless covered by an existing bond on file (see Item 20 above). |
| 2. A Drilling Plan. | 5. Operator certification. |
| 3. A Surface Use Plan (if the location is on National Forest System Lands, the SUPO must be filed with the appropriate Forest Service Office). | 6. Such other site specific information and/or plans as may be requested by the BLM. |

25. Signature	Name (Printed/Typed)	Date
Title		
Approved by (Signature)	Name (Printed/Typed)	Date
Title		
Office		

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.
Conditions of approval, if any, are attached.

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

NGMP Rec 05/20/2022



06/03/2022

SL

(Continued on page 2)

*(Instructions on page 2)

District I
1625 N. French Dr., Hobbs, NM 88240
Phone: (575) 393-6161 Fax: (575) 393-0720
District II
811 S. First St., Artesia, NM 88210
Phone: (575) 748-1283 Fax: (575) 748-9720
District III
1000 Rio Brazos Road, Aztec, NM 87410
Phone: (505) 334-6178 Fax: (505) 334-6170
District IV
1220 S. St. Francis Dr., Santa Fe, NM 87505
Phone: (505) 476-3460 Fax: (505) 476-3462

State of New Mexico
Energy, Minerals & Natural Resources Department
OIL CONSERVATION DIVISION
1220 South St. Francis Dr.
Santa Fe, NM 87505

Form C-102
Revised August 1, 2011
Submit one copy to appropriate
District Office

AMENDED REPORT

WELL LOCATION AND ACREAGE DEDICATION PLAT

¹ API Number 30-025-50208	² Pool Code 98092	³ Pool Name WC-025 G-09 S253236I;UPR WOLECAMP
⁴ Property Code 330240	⁵ Property Name RED HILLS 32-5 FED COM	
⁷ OGRID No. 215099	⁸ Operator Name CIMAREX ENERGY CO.	
	⁶ Well Number 158H	⁹ Elevation 3409.1'

¹⁰ Surface Location									
UL or lot no. C	Section 32	Township 25S	Range 33E	Lot Idn	Feet from the 330	North/South line NORTH	Feet from the 2305	East/West line WEST	County LEA

¹¹ Bottom Hole Location If Different From Surface									
UL or lot no. N	Section 5	Township 26S	Range 33E	Lot Idn	Feet from the 100	North/South line SOUTH	Feet from the 2305	East/West line WEST	County LEA
¹² Dedicated Acres 640		¹³ Joint or Infill		¹⁴ Consolidation Code		¹⁵ Order No.			

No allowable will be assigned to this completion until all interests have been consolidated or a non-standard unit has been approved by the division.

¹⁷ OPERATOR CERTIFICATION

I hereby certify that the information contained herein is true and complete to the best of my knowledge and belief, and that this organization either owns a working interest or unleased mineral interest in the land including the proposed bottom hole location or has a right to drill this well at this location pursuant to a contract with an owner of such a mineral or working interest, or to a voluntary pooling agreement or a compulsory pooling order heretofore entered by the division.

Amithy Crawford 5-13-21
Signature Date

Amithy Crawford
Printed Name

acrawford@cimarex.com
E-mail Address

¹⁸ SURVEYOR CERTIFICATION

I hereby certify that the well location shown on this plat was plotted from field notes of actual surveys made by me or under my supervision, and that the same is true and correct to the best of my belief.

May 01, 2018
Date of Survey

Signature and Seal of Professional Surveyor:

NOTE:

- Distances referenced on plat to section lines are perpendicular.
- Basis of Bearing is a Transverse Mercator Projection with a Central Meridian of W103°53'00"

● = SURFACE HOLE LOCATION /LANDING POINT/FIRST TAKE POINT
○ = BOTTOM HOLE LOCATION /LAST TAKE POINT
▲ = SECTION CORNER LOCATED

SCALE
DRAWN BY: J.A. 08-09-19
REV: 2 T.A. 01-08-20 (WELL BORE CHANGE)



Application for Permit to Drill

APD Package Report

Date Printed:

APD ID:	Well Status:
APD Received Date:	Well Name:
Operator:	Well Number:

APD Package Report Contents

- Form 3160-3
- Operator Certification Report
- Application Report
- Application Attachments
 - Well Plat: 2 file(s)
- Drilling Plan Report
- Drilling Plan Attachments
 - Blowout Prevention Choke Diagram Attachment: 2 file(s)
 - Blowout Prevention BOP Diagram Attachment: 2 file(s)
 - Casing Spec Documents: 1 file(s)
 - Casing Design Assumptions and Worksheet(s): 4 file(s)
 - Hydrogen sulfide drilling operations plan: 1 file(s)
 - Proposed horizontal/directional/multi-lateral plan submission: 2 file(s)
 - Other Facets: 3 file(s)
 - Other Variances: 2 file(s)
- SUPO Report
- SUPO Attachments
 - Existing Road Map: 1 file(s)
 - New Road Map: 1 file(s)
 - Attach Well map: 1 file(s)
 - Production Facilities map: 4 file(s)
 - Water source and transportation map: 1 file(s)
 - Well Site Layout Diagram: 1 file(s)
 - Recontouring attachment: 1 file(s)
 - Other SUPO Attachment: 3 file(s)
- PWD Report
- PWD Attachments
 - None

- Bond Report
- Bond Attachments
 - None

PECOS DISTRICT DRILLING CONDITIONS OF APPROVAL

OPERATOR'S NAME:	Cimarex Energy
LEASE NO.:	NMNM0106040A
LOCATION:	Section 32, T.25 S., R.33 E., NMPM
COUNTY:	Lea County, New Mexico

WELL NAME & NO.:	Red Hills 32-5 Fed Com 158H
SURFACE HOLE FOOTAGE:	330'/N & 2305'/W
BOTTOM HOLE FOOTAGE:	100'/S & 2305'/W

COA

H2S	<input checked="" type="radio"/> Yes	<input type="radio"/> No	
Potash	<input checked="" type="radio"/> None	<input type="radio"/> Secretary	<input type="radio"/> R-111-P
Cave/Karst Potential	<input checked="" type="radio"/> Low	<input type="radio"/> Medium	<input type="radio"/> High
Cave/Karst Potential	<input type="radio"/> Critical		
Variance	<input type="radio"/> None	<input checked="" type="radio"/> Flex Hose	<input type="radio"/> Other
Wellhead	<input type="radio"/> Conventional	<input checked="" type="radio"/> Multibowl	<input type="radio"/> Both
Other	<input type="checkbox"/> 4 String Area	<input type="checkbox"/> Capitan Reef	<input type="checkbox"/> WIPP
Other	<input checked="" type="checkbox"/> Fluid Filled	<input type="checkbox"/> Cement Squeeze	<input type="checkbox"/> Pilot Hole
Special Requirements	<input type="checkbox"/> Water Disposal	<input checked="" type="checkbox"/> COM	<input type="checkbox"/> Unit

A. HYDROGEN SULFIDE

A Hydrogen Sulfide (H2S) Drilling Plan shall be activated 500 feet prior to drilling into the **Wolfcamp** formation. As a result, the Hydrogen Sulfide area must meet Onshore Order 6 requirements, which includes equipment and personnel/public protection items. If Hydrogen Sulfide is encountered, please provide measured values and formations to the BLM.

B. CASING

1. The **10-3/4** inch surface casing shall be set at approximately **1000** feet (a minimum of **25 feet (Lea County)** into the Rustler Anhydrite and above the salt) and cemented to the surface.
 - a. If cement does not circulate to the surface, the appropriate BLM office shall be notified and a temperature survey utilizing an electronic type temperature survey with surface log readout will be used or a cement bond log shall be run to verify the top of the cement. Temperature survey will be run a minimum of six hours after pumping cement and ideally between 8-10 hours after completing the cement job.

- b. Wait on cement (WOC) time for a primary cement job will be a minimum of **8 hours** or 500 pounds compressive strength, whichever is greater. (This is to include the lead cement)
- c. Wait on cement (WOC) time for a remedial job will be a minimum of 4 hours after bringing cement to surface or 500 pounds compressive strength, whichever is greater.
- d. If cement falls back, remedial cementing will be done prior to drilling out that string.

Intermediate casing must be kept fluid filled to meet BLM minimum collapse requirement.

2. The minimum required fill of cement behind the **7-5/8** inch intermediate casing is: Operator has proposed a DV tool, the depth may be adjusted as long as the cement is changed proportionally. The DV tool may be cancelled if cement circulates to surface on the first stage.

- a. First stage to DV tool: Cement to circulate. If cement does not circulate off the DV tool, contact the appropriate BLM office before proceeding with second stage cement job.
- b. Second stage above DV tool:
 - Cement to surface. If cement does not circulate, contact the appropriate BLM office.
Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry due to cave/karst or potash.

Variance is approved for annular clearance between 7 5/8" and 5 1/2".

3. The minimum required fill of cement behind the **5-1/2 x 5** inch production casing is:
 - Cement should tie-back at least **200 feet** into previous casing string. Operator shall provide method of verification.

C. PRESSURE CONTROL

1. **Variance approved to use flex line from BOP to choke manifold. Manufacturer's specification to be readily available. No external damage to flex line. Flex line to be installed as straight as possible (no hard bends).**
2. Operator has proposed a multi-bowl wellhead assembly. This assembly will only be tested when installed on the surface casing. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the surface casing shoe shall be **10,000 (10M) psi. Variance is approved to use a Choose an item. Annular which shall be tested to 5000 (5M) psi.**

- a. Wellhead shall be installed by manufacturer's representatives, submit documentation with subsequent sundry.
- b. If the welding is performed by a third party, the manufacturer's representative shall monitor the temperature to verify that it does not exceed the maximum temperature of the seal.
- c. Manufacturer representative shall install the test plug for the initial BOP test.
- d. If the cement does not circulate and one inch operations would have been possible with a standard wellhead, the well head shall be cut off, cementing operations performed and another wellhead installed.
- e. Whenever any seal subject to test pressure is broken, all the tests in OOGO2.III.A.2.i must be followed.

D. SPECIAL REQUIREMENT (S)

Communitization Agreement

- The operator will submit a Communitization Agreement to the Santa Fe Office, 301 Dinosaur Trail Santa Fe, New Mexico 87508, at least 90 days before the anticipated date of first production from a well subject to a spacing order issued by the New Mexico Oil Conservation Division. The Communitization Agreement will include the signatures of all working interest owners in all Federal and Indian leases subject to the Communitization Agreement (i.e., operating rights owners and lessees of record), or certification that the operator has obtained the written signatures of all such owners and will make those signatures available to the BLM immediately upon request.
- If the operator does not comply with this condition of approval, the BLM may take enforcement actions that include, but are not limited to, those specified in 43 CFR 3163.1.
- In addition, the well sign shall include the surface and bottom hole lease numbers. When the Communitization Agreement number is known, it shall also be on the sign.

GENERAL REQUIREMENTS

The BLM is to be notified in advance for a representative to witness:

- a. Spudding well (minimum of 24 hours)
- b. Setting and/or Cementing of all casing strings (minimum of 4 hours)
- c. BOPE tests (minimum of 4 hours)

Eddy County
Call the Carlsbad Field Office, 620 East Greene St., Carlsbad, NM 88220,
(575) 361-2822

Lea County
Call the Hobbs Field Station, 414 West Taylor, Hobbs NM 88240, (575)
393-3612

1. Unless the production casing has been run and cemented or the well has been properly plugged, the drilling rig shall not be removed from over the hole without prior approval.
 - a. In the event the operator has proposed to drill multiple wells utilizing a skid/walking rig. Operator shall secure the wellbore on the current well, after installing and testing the wellhead, by installing a blind flange of like pressure rating to the wellhead and a pressure gauge that can be monitored while drilling is performed on the other well(s).
 - b. When the operator proposes to set surface casing with Spudder Rig
 - Notify the BLM when moving in and removing the Spudder Rig.
 - Notify the BLM when moving in the 2nd Rig. Rig to be moved in within 90 days of notification that Spudder Rig has left the location.
 - BOP/BOPE test to be conducted per Onshore Oil and Gas Order No. 2 as soon as 2nd Rig is rigged up on well.
2. Floor controls are required for 3M or Greater systems. These controls will be on the rig floor, unobstructed, readily accessible to the driller and will be operational at all times during drilling and/or completion activities. Rig floor is defined as the area immediately around the rotary table; the area immediately above the substructure on which the draw works are located, this does not include the dog house or stairway area.
3. The record of the drilling rate along with the GR/N well log run from TD to surface (horizontal well – vertical portion of hole) shall be submitted to the BLM office as well as all other logs run on the borehole 30 days from completion. If available, a digital copy of the logs is to be submitted in addition to the paper copies. The Rustler top and top and bottom of Salt are to be recorded on the Completion Report.

A. CASING

1. Changes to the approved APD casing program need prior approval if the items substituted are of lesser grade or different casing size or are Non-API. The Operator can exchange the components of the proposal with that of superior strength (i.e. changing from J-55 to N-80, or from 36# to 40#). Changes to the approved cement program need prior approval if the altered cement plan has less volume or strength or if the changes are substantial (i.e. Multistage tool, ECP, etc.). The initial wellhead installed on the well will remain on the well with spools used as needed.
2. Wait on cement (WOC) for Potash Areas: After cementing but before commencing any tests, the casing string shall stand cemented under pressure until both of the following conditions have been met: 1) cement reaches a minimum compressive strength of 500 psi for all cement blends, 2) until cement has been in place at least 24 hours. WOC time will be recorded in the driller's log. The casing integrity test can be done (prior to the cement setting up) immediately after bumping the plug.

3. Wait on cement (WOC) for Water Basin: After cementing but before commencing any tests, the casing string shall stand cemented under pressure until both of the following conditions have been met: 1) cement reaches a minimum compressive strength of 500 psi at the shoe, 2) until cement has been in place at least 8 hours. WOC time will be recorded in the driller's log. See individual casing strings for details regarding lead cement slurry requirements. The casing integrity test can be done (prior to the cement setting up) immediately after bumping the plug.
4. Provide compressive strengths including hours to reach required 500 pounds compressive strength prior to cementing each casing string. Have well specific cement details onsite prior to pumping the cement for each casing string.
5. No pea gravel permitted for remedial or fall back remedial without prior authorization from the BLM engineer.
6. On that portion of any well approved for a 5M BOPE system or greater, a pressure integrity test of each casing shoe shall be performed. Formation at the shoe shall be tested to a minimum of the mud weight equivalent anticipated to control the formation pressure to the next casing depth or at total depth of the well. This test shall be performed before drilling more than 20 feet of new hole.
7. If hardband drill pipe is rotated inside casing, returns will be monitored for metal. If metal is found in samples, drill pipe will be pulled and rubber protectors which have a larger diameter than the tool joints of the drill pipe will be installed prior to continuing drilling operations.
8. Whenever a casing string is cemented in the R-111-P potash area, the NMOCD requirements shall be followed.

B. PRESSURE CONTROL

1. All blowout preventer (BOP) and related equipment (BOPE) shall comply with well control requirements as described in Onshore Oil and Gas Order No. 2 and API RP 53 Sec. 17.
2. If a variance is approved for a flexible hose to be installed from the BOP to the choke manifold, the following requirements apply: The flex line must meet the requirements of API 16C. Check condition of flexible line from BOP to choke manifold, replace if exterior is damaged or if line fails test. Line to be as straight as possible with no hard bends and is to be anchored according to Manufacturer's requirements. The flexible hose can be exchanged with a hose of equal size and equal or greater pressure rating. Anchor requirements, specification sheet and hydrostatic pressure test certification matching the hose in service, to be onsite for review. These documents shall be posted in the company man's trailer and on the rig floor.

3. 5M or higher system requires an HCR valve, remote kill line and annular to match. The remote kill line is to be installed prior to testing the system and tested to stack pressure.
4. If the operator has proposed a multi-bowl wellhead assembly in the APD. The following requirements must be met:
 - a. Wellhead shall be installed by manufacturer's representatives, submit documentation with subsequent sundry.
 - b. If the welding is performed by a third party, the manufacturer's representative shall monitor the temperature to verify that it does not exceed the maximum temperature of the seal.
 - c. Manufacturer representative shall install the test plug for the initial BOP test.
 - d. Whenever any seal subject to test pressure is broken, all the tests in OOGO2.III.A.2.i must be followed.
 - e. If the cement does not circulate and one inch operations would have been possible with a standard wellhead, the well head shall be cut off, cementing operations performed and another wellhead installed.
5. The appropriate BLM office shall be notified a minimum of 4 hours in advance for a representative to witness the tests.
 - a. In a water basin, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. The casing cut-off and BOP installation can be initiated four hours after installing the slips, which will be approximately six hours after bumping the plug. For those casing strings not using slips, the minimum wait time before cut-off is eight hours after bumping the plug. BOP/BOPE testing can begin after cut-off or once cement reaches 500 psi compressive strength (including lead when specified), whichever is greater. However, if the float does not hold, cut-off cannot be initiated until cement reaches 500 psi compressive strength (including lead when specified).
 - b. In potash areas, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. For all casing strings, casing cut-off and BOP installation can be initiated at twelve hours after bumping the plug. However, **no tests** shall commence until the cement has had a minimum of 24 hours setup time, except the casing pressure test can be initiated immediately after bumping the plug (only applies to single stage cement jobs).
 - c. The tests shall be done by an independent service company utilizing a test plug not a cup or J-packer. The operator also has the option of utilizing an independent tester to test without a plug (i.e. against the casing) pursuant to Onshore Order 2 with the pressure not to exceed 70% of the burst rating for

the casing. Any test against the casing must meet the WOC time for water basin (8 hours) or potash (24 hours) or 500 pounds compressive strength, whichever is greater, prior to initiating the test (see casing segment as lead cement may be critical item).

- d. The test shall be run on a 5000 psi chart for a 2-3M BOP/BOP, on a 10000 psi chart for a 5M BOP/BOPE and on a 15000 psi chart for a 10M BOP/BOPE. If a linear chart is used, it shall be a one hour chart. A circular chart shall have a maximum 2 hour clock. If a twelve hour or twenty-four hour chart is used, tester shall make a notation that it is run with a two hour clock.
- e. The results of the test shall be reported to the appropriate BLM office.
- f. All tests are required to be recorded on a calibrated test chart. A copy of the BOP/BOPE test chart and a copy of independent service company test will be submitted to the appropriate BLM office.
- g. The BOP/BOPE test shall include a low pressure test from 250 to 300 psi. The test will be held for a minimum of 10 minutes if test is done with a test plug and 30 minutes without a test plug. This test shall be performed prior to the test at full stack pressure.
- h. BOP/BOPE must be tested by an independent service company within 500 feet of the top of the Wolfcamp formation if the time between the setting of the intermediate casing and reaching this depth exceeds 20 days. This test does not exclude the test prior to drilling out the casing shoe as per Onshore Order No. 2.

C. DRILLING MUD

Mud system monitoring equipment, with derrick floor indicators and visual and audio alarms, shall be operating before drilling into the Wolfcamp formation, and shall be used until production casing is run and cemented.

D. WASTE MATERIAL AND FLUIDS

All waste (i.e. drilling fluids, trash, salts, chemicals, sewage, gray water, etc.) created as a result of drilling operations and completion operations shall be safely contained and disposed of properly at a waste disposal facility. No waste material or fluid shall be disposed of on the well location or surrounding area.

Porto-johns and trash containers will be on-location during fracturing operations or any other crew-intensive operations.

ZS030121



U.S. Department of the Interior
BUREAU OF LAND MANAGEMENT

Application Data Report

05/02/2021

APD ID: 10400038355

Submission Date: 01/28/2019

Highlighted data
reflects the most
recent changes

Operator Name: CIMAREX ENERGY COMPANY

Well Name: RED HILLS 32-5 FEDERAL COM

Well Number: 158H

[Show Final Text](#)

Well Type: CONVENTIONAL GAS WELL

Well Work Type: Drill

Section 1 - General

APD ID: 10400038355

Tie to previous NOS? Y

Submission Date: 01/28/2019

BLM Office: CARLSBAD

User: Amithy Crawford

Title: Regulatory Analyst

Federal/Indian APD: FED

Is the first lease penetrated for production Federal or Indian? FED

Lease number: NMNM0106040A

Lease Acres:

Surface access agreement in place?

Allotted?

Reservation:

Agreement in place? NO

Federal or Indian agreement:

Agreement number:

Agreement name:

Keep application confidential? YES

Permitting Agent? NO

APD Operator: CIMAREX ENERGY COMPANY

Operator letter of designation:

Operator Info

Operator Organization Name: CIMAREX ENERGY COMPANY

Operator Address: 600 N MARIENFELD STREET ST SUITE 600

Zip: 79701

Operator PO Box:

Operator City: MIDLAND

State: TX

Operator Phone: (432)571-7800

Operator Internet Address: tstathem@cimarex.com

Section 2 - Well Information

Well in Master Development Plan? NO

Master Development Plan name:

Well in Master SUPO? NO

Master SUPO name:

Well in Master Drilling Plan? NO

Master Drilling Plan name:

Well Name: RED HILLS 32-5 FEDERAL COM

Well Number: 158H

Well API Number:

Field/Pool or Exploratory? Field and Pool

Field Name: Sanders Tank

Pool Name: UPPER
WOLFCAMP

Is the proposed well in an area containing other mineral resources? USEABLE WATER

Operator Name: CIMAREX ENERGY COMPANY

Well Name: RED HILLS 32-5 FEDERAL COM

Well Number: 158H

Is the proposed well in an area containing other mineral resources? USEABLE WATER

Is the proposed well in a Helium production area? N **Use Existing Well Pad?** NO **New surface disturbance?**

Type of Well Pad: MULTIPLE WELL

Multiple Well Pad Name: RED HILLS 32-5 FEDERAL COM

Number: E2E2 PAD

Well Class: HORIZONTAL

Number of Legs: 1

Well Work Type: Drill

Well Type: CONVENTIONAL GAS WELL

Describe Well Type:

Well sub-Type: INFILL

Describe sub-type:

Distance to town: 26 Miles

Distance to nearest well: 20 FT

Distance to lease line: 330 FT

Reservoir well spacing assigned acres Measurement: 1280 Acres

Well plat: Red_Hills_32_5_Fed_Com_158H_C102_BLM_Lease_20200115161529.pdf

Red_Hills_32_5_Fed_Com_158H_C102_20200115161536.pdf

Well work start Date: 12/01/2019

Duration: 30 DAYS

Section 3 - Well Location Table

Survey Type: RECTANGULAR

Describe Survey Type:

Datum: NAD83

Vertical Datum: NAVD88

Survey number: 23782

Reference Datum:

Wellbore	NS-Foot	NS Indicator	EW-Foot	EW Indicator	Twsp	Range	Section	Aliquot/Lot/Tract	Latitude	Longitude	County	State	Meridian	Lease Type	Lease Number	Elevation	MD	TVD	Will this well produce from this lease?
SHL Leg #1	330	FNL	2305	FWL	25S	33E	32	Aliquot NWNE	32.09341	-103.595413	LEA	NEW MEXICO	NEW MEXICO	S	STATE	3409	0	0	
KOP Leg #1	140	FNL	2339	FWL	25S	33E	32	Aliquot NENE	32.093931	-103.5953	LEA	NEW MEXICO	NEW MEXICO	S	STATE	-8385	11794	11794	

Operator Name: CIMAREX ENERGY COMPANY

Well Name: RED HILLS 32-5 FEDERAL COM

Well Number: 158H

Wellbore	NS-Foot	NS Indicator	EW-Foot	EW Indicator	Twsp	Range	Section	Aliquot/Lot/Tract	Latitude	Longitude	County	State	Meridian	Lease Type	Lease Number	Elevation	MD	TVD	Will this well produce from this lease?
PPP Leg #1-1	2633	FSL	2307	FWL	26S	33E	5	Aliquot NENE	32.072531	-103.595411	LEA	NEW MEXICO	NEW MEXICO	F	NMNM 0160973	-8891	19858	12300	
PPP Leg #1-2	3955	FSL	2308	FWL	26S	33E	5	Aliquot NENE	32.0798	-103.595411	LEA	NEW MEXICO	FIRST PRIN	F	NMNM 0106040A	-8891	18536	12300	
PPP Leg #1-3	5278	FSL	2309	FWL	26S	33E	5	Aliquot NENE	32.0798	-103.595411	LEA	NEW MEXICO	FIRST PRIN	F	FEE	-8891	17214	12300	
EXIT Leg #1	100	FSL	2305	FWL	26S	33E	5	Aliquot SWSE	32.065569	-103.595411	LEA	NEW MEXICO	NEW MEXICO	F	NMNM 0160973	-8891	22392	12300	
BHL Leg #1	100	FSL	2305	FWL	26S	33E	5	Aliquot SWSE	32.065569	-103.59511	LEA	NEW MEXICO	FIRST PRIN	F	NMNM 0160973	-8891	22392	12300	



U.S. Department of the Interior
BUREAU OF LAND MANAGEMENT

Drilling Plan Data Report

05/02/2021

APD ID: 10400038355

Submission Date: 01/28/2019

Highlighted data
reflects the most
recent changes

Operator Name: CIMAREX ENERGY COMPANY

Well Name: RED HILLS 32-5 FEDERAL COM

Well Number: 158H

[Show Final Text](#)

Well Type: CONVENTIONAL GAS WELL

Well Work Type: Drill

Section 1 - Geologic Formations

Formation ID	Formation Name	Elevation	True Vertical Depth	Measured Depth	Lithologies	Mineral Resources	Producing Formation
380580	RUSTLER	3464	934	934		USEABLE WATER	N
380581	TOP SALT	2115	1349	1349		NONE	N
380582	BASE OF SALT	-1187	4651	4651		NONE	N
380591	LAMAR	-1428	4892	4892		NONE	N
380592	BELL CANYON	-1465	4929	4929		NONE	N
629269	CHERRY CANYON	-2537	6001	6001		NATURAL GAS, OIL	N
629270	BRUSHY CANYON	-4073	7537	7537		NATURAL GAS, OIL	N
629271	BONE SPRING	-5575	9039	9039		NATURAL GAS, OIL	N
629272	UPPER AVALON SHALE	-5892	9356	9356		NATURAL GAS, OIL	N
629288	BONE SPRING 1ST	-6572	10036	10036		NATURAL GAS, OIL	N
629289	BONE SPRING 2ND	-6759	10223	10223		NATURAL GAS, OIL	N
629309	BONE SPRING 3RD	-7553	11017	11017		NATURAL GAS, OIL	N
629310	WOLFCAMP	-8661	12125	12125		NATURAL GAS, OIL	Y

Section 2 - Blowout Prevention

Operator Name: CIMAREX ENERGY COMPANY**Well Name:** RED HILLS 32-5 FEDERAL COM**Well Number:** 158H**Pressure Rating (PSI):** 10M**Rating Depth:** 22392

Equipment: A BOP consisting of three rams, including one blind ram and two pipe rams and one annular preventer. An accumulator that meets the requirements in Onshore Order #2 for the pressure rating of the BOP stack. A rotating head may be installed as needed. A Kelly clock will be installed and maintained in operable condition and a drill string safety valve in the open position will be available on the rig floor.

Requesting Variance? YES

Variance request: Co-flex line between the BOP and choke manifold. Certification for proposed co-flex hose is attached. The hose is not required by the manufacturer to be anchored. In the event the specific hose is not available, one of equal or higher rating will be used. Variance to include Hammer Union connections on lines downstream of the buffer tank only. Cimarex requests a 5M annular variance for the 10M BOP system. See attached procedure

Testing Procedure: A multi-bowl wellhead system will be utilized. After running the 10-3/4" surface casing, a 13 5/8" BOP/BOPE system with a minimum working pressure of 10000 psi will be installed on the wellhead system and will be pressure tested to 250 psi low followed by a 10000 psi test. Annular will be tested to 50% of working pressure. The pressure test will be repeated at least every 30 days, as per Onshore Order No. 2. The multi-bowl wellhead will be installed by vendor's representative. A copy of the installation instructions has been sent to the BLM field office. The wellhead will be installed by a third-party welder while being monitored by the wellhead vendor representative. All BOP equipment will be tested utilizing a conventional test plug. Not a cup or J-packer type. A solid steel body pack-off will be utilized after running and cementing the intermediate casing. After installation the pack-off and lower flange will be pressure tested to 10000 psi. The surface casing string will be tested as per Onshore Order No. 2 to at least 0.22 psi/ft or 1500 psi, whichever is greater. The casing string utilizing steel body pack-off will be tested to 70% of casing burst. If well conditions dictate conventional slips will be set and BOPE will be tested to appropriate pressures based on permitted pressure requirements.

Choke Diagram Attachment:

Red_Hills_32_5_Fed_Com_158H_Choke_10M_20200914100945.pdf

BOP Diagram Attachment:

Red_Hills_32_5_Fed_Com_158H_BOP_10M_20200914100959.pdf

Pressure Rating (PSI): 5M**Rating Depth:** 12426

Equipment: A BOP consisting of three rams, including one blind ram and two pipe rams and one annular preventer. An accumulator that meets the requirements in Onshore Order #2 for the pressure rating of the BOP stack. A rotating head may be installed as needed. A Kelly clock will be installed and maintained in operable condition and a drill string safety valve in the open position will be available on the rig floor.

Requesting Variance? YES

Variance request: Co-flex line between the BOP and choke manifold. Certification for proposed co-flex hose is attached. The hose is not required by the manufacturer to be anchored. In the event the specific hose is not available, one of equal or higher rating will be used. Variance to include Hammer Union connections on lines downstream of the buffer tank only.

Testing Procedure: A multi-bowl wellhead system will be utilized. After running the 10-3/4" surface casing, a 13 5/8" BOP/BOPE system with a minimum working pressure of 5000 psi will be installed on the wellhead system and will be pressure tested to 250 psi low followed by a 5000 psi test. Annular will be tested to 100% of working pressure. The pressure test will be repeated at least every 30 days, as per Onshore Order No. 2. The multi-bowl wellhead will be installed by vendor's representative. A copy of the installation instructions has been sent to the BLM field office. The wellhead will be installed by a third-party welder while being monitored by the wellhead vendor representative. All BOP equipment will be tested utilizing a conventional test plug. Not a cup or J-packer type. A solid steel body pack-off will be utilized after running and cementing the intermediate casing. After installation the pack-off and lower flange will be pressure tested to 5000 psi. The surface casing string will be tested as per Onshore Order No. 2 to at least 0.22 psi/ft or 1500 psi, whichever is greater. The casing string utilizing steel body pack-off will be tested to 70% of casing burst. If well conditions dictate conventional slips will be set and BOPE will be tested to appropriate pressures based on permitted pressure requirements.

Choke Diagram Attachment:

Operator Name: CIMAREX ENERGY COMPANY

Well Name: RED HILLS 32-5 FEDERAL COM

Well Number: 158H

Red_Hills_32_5_Fed_Com_158H_Choke_5M_20200122102608.pdf

BOP Diagram Attachment:

Red_Hills_32_5_Fed_Com_158H_BOP_5M_20200122102626.pdf

Section 3 - Casing

Casing ID	String Type	Hole Size	Csg Size	Condition	Standard	Tapered String	Top Set MD	Bottom Set MD	Top Set TVD	Bottom Set TVD	Top Set MSL	Bottom Set MSL	Calculated casing length MD	Grade	Weight	Joint Type	Collapse SF	Burst SF	Joint SF Type	Joint SF	Body SF Type	Body SF
1	SURFACE	14.75	10.75	NEW	API	N	0	984	0	984			984	J-55	40.5	BUTT	3.51	6.95	BUOY	15.78	BUOY	15.78
2	PRODUCTI ON	6.75	5.5	NEW	API	N	0	11700	0	11700			11700	L-80	20	LT&C	1.15	1.2	BUOY	1.88	BUOY	1.88
3	INTERMED IATE	9.875	7.625	NEW	NON API	N	0	12426	0	12251			12426	L-80	29.7	BUTT	2.5	1.2	BUOY	1.82	BUOY	1.82
4	PRODUCTI ON	6.75	5.0	NEW	API	N	11700	22392	11700	12300			10692	P- 110	18	BUTT	1.68	1.7	BUOY	53.7	BUOY	53.7

Casing Attachments

Casing ID: 1 **String Type:** SURFACE

Inspection Document:

Spec Document:

Tapered String Spec:

Casing Design Assumptions and Worksheet(s):

Red_Hills_32_5_Fed_Com_158H_Casing_Assumptions_20200402082310.pdf

Operator Name: CIMAREX ENERGY COMPANY

Well Name: RED HILLS 32-5 FEDERAL COM

Well Number: 158H

Casing Attachments

Casing ID: 2 **String Type:** PRODUCTION

Inspection Document:

Spec Document:

Tapered String Spec:

Casing Design Assumptions and Worksheet(s):

Red_Hills_32_5_Fed_Com_158H_Casing_Assumptions_20200402082822.pdf

Casing ID: 3 **String Type:** INTERMEDIATE

Inspection Document:

Spec Document:

Red_Hills_32_5_Fed_Com_158H_Spec_Sheet_for_L80_7.625_Inter_Csg_20200402082601.pdf

Tapered String Spec:

Casing Design Assumptions and Worksheet(s):

Red_Hills_32_5_Fed_Com_158H_Casing_Assumptions_20200402082646.pdf

Casing ID: 4 **String Type:** PRODUCTION

Inspection Document:

Spec Document:

Tapered String Spec:

Casing Design Assumptions and Worksheet(s):

Red_Hills_32_5_Fed_Com_158H_Casing_Assumptions_20200402083053.pdf

Section 4 - Cement

Operator Name: CIMAREX ENERGY COMPANY

Well Name: RED HILLS 32-5 FEDERAL COM

Well Number: 158H

String Type	Lead/Tail	Stage Tool Depth	Top MD	Bottom MD	Quantity(sx)	Yield	Density	Cu Ft	Excess%	Cement type	Additives
PRODUCTION	Lead		0	0	0	0	0	0	0		0

SURFACE	Lead		0	984	332	1.72	13.5	570	50	Class C	Bentonite
SURFACE	Tail		0	984	156	1.34	14.8	208	25	Class C	LCM
INTERMEDIATE	Lead		0	4892	579	3.64	10.3	2106	50	Tuned light	LCM
INTERMEDIATE	Tail		4892	1242 6	198	1.36	14.8	268	25	Class C	Retarder
INTERMEDIATE	Lead	4892	4892	1242 6	793	1.88	12.9	1490	50	35:65 PoZ c	Salt, Bentonite

PRODUCTION	Lead		1170 0	2239 2	852	1.3	14.2	1107	25	50:50 Poz:H	Salt, Bentonite, Fluid Loss, Dispersant, SMS
------------	------	--	-----------	-----------	-----	-----	------	------	----	-------------	--

Section 5 - Circulating Medium

Mud System Type: Closed

Will an air or gas system be Used? NO

Description of the equipment for the circulating system in accordance with Onshore Order #2:

Diagram of the equipment for the circulating system in accordance with Onshore Order #2:

Describe what will be on location to control well or mitigate other conditions: Sufficient mud materials will be kept on location at all times in order to combat lost circulation or unexpected kicks. In order to run DSTs, open hole logs, and casing, the viscosity and water loss may have to be adjusted in order to meet these needs.

Describe the mud monitoring system utilized: PVT/Pason/Visual Monitoring

Circulating Medium Table

Operator Name: CIMAREX ENERGY COMPANY**Well Name:** RED HILLS 32-5 FEDERAL COM**Well Number:** 158H

Top Depth	Bottom Depth	Mud Type	Min Weight (lbs/gal)	Max Weight (lbs/gal)	Density (lbs/cu ft)	Gel Strength (lbs/100 sqft)	PH	Viscosity (CP)	Salinity (ppm)	Filtration (cc)	Additional Characteristics
0	984	SPUD MUD	8.3	8.8							
984	1242 6	OTHER : Brine Diesel Emulsion	8.5	9							
1246 2	2239 2	OIL-BASED MUD	12	12.5							

Section 6 - Test, Logging, Coring

List of production tests including testing procedures, equipment and safety measures:

No DST Planned

List of open and cased hole logs run in the well:

CNL,DS,GR

Coring operation description for the well:

N/A

Section 7 - Pressure

Anticipated Bottom Hole Pressure: 7995

Anticipated Surface Pressure: 5289

Anticipated Bottom Hole Temperature(F): 190

Anticipated abnormal pressures, temperatures, or potential geologic hazards? YES

Describe:

Lost circulation may be encountered in the Delaware mountain group. Abnormal pressure as well as hole stability issues may be encountered in the Wolfcamp.

Contingency Plans geohazards description:

Lost circulation material will be available, as well as additional drilling fluid along with the fluid volume in the drilling rig pit system. Drilling fluid can be mixed on location or mixed in vendor mud plant and trucked to location if needed. Sufficient barite will be available to maintain appropriate mud weight for the Wolfcamp interval.

Contingency Plans geohazards attachment:

Hydrogen Sulfide drilling operations plan required? YES

Hydrogen sulfide drilling operations plan:

Red_Hills_32_5_Fed_Com_158H_H2S_Plan_20200122152720.pdf

Operator Name: CIMAREX ENERGY COMPANY

Well Name: RED HILLS 32-5 FEDERAL COM

Well Number: 158H

Section 8 - Other Information

Proposed horizontal/directional/multi-lateral plan submission:

Red_Hills_32_5_Fed_Com_158H_Directional_Plan_20200122153231.pdf

Red_Hills_32_5_Fed_Com_158H_AC_Report_20200122153232.pdf

Other proposed operations facets description:

Other proposed operations facets attachment:

Red_Hills_32_5_Fed_Com_158H_Gas_Capture_Plan_20200122153257.pdf

Red_Hills_32_5_Fed_Com_158H_Flex_Hose_20200122153308.pdf


Red_Hills_32_5_Fed_Com_158H_Drilling_Plan_20210204070809.pdf

Other Variance attachment:

Red_Hills_32_5_Fed_Com_158H_Multibowl_Wellhead_20200402091028.pdf

Red_Hills_32_5_Fed_Com_158H_Annular_Variance_Well_Control_Plan_20200914101110.pdf


CONFIDENTIAL



Choke Manifold Diagram
Red Hills 32-5 Fed Com 158H
 Cimarex Energy Co.
 32-25S-33E
 Lea Co., NM

Drilling Operations
Choke Manifold
5M Service

Mud Tanks
40'-50' from
wellbore



Choke Manifold Diagram
Red Hills 32-5 Fed Com 158H
 Cimarex Energy Co.
 32-25S-33E
 Lea Co., NM

**Drilling Operations
 Choke Manifold
 10M Service**

4" Choke Line:
 OPTIONAL: 4" Flex Hose may be
 used if approved in APD

Drilling 9-7/8" hole below
10-3/4" Casing

Fill Line

Flowline

5000# (5M)
BOP

Annular Preventer

SRR & A

Pipe Rams

Blind Rams

2" Minimum Kill Line

3" minimum choke line

Kill Line

Drilling
Spool

Choke Line

2 Valves Minimum

(HCR Required)

2 Valves and a check valve

Wellhead
Assembly

11" 5000 psi x 7-1/16" 10,000 psi
Wellhead Assembly

Wellhead
Assembly

13-5/8" 3000 psi x 11" 5000 psi
Wellhead Assembly

5000# BOP
Red Hills 32-5 Fed Com 158H
Cimarex Energy Co.
32-25S-33E
Lea Co., NM

13-5/8" 3000# psi x 13-3/8" SOW Casing Head

Drilling 6-3/4" Hole
below 7-5/8" Casing

5M Annular Preventer

10M Double
Ram BOP

Pipe Rams

Blind Rams

2" Kill Line Valves (2)
with Check Valve

3" Manual Choke Valve
and 3" HCR Valve

2" Kill Line

3" Choke Line

10M Single
Ram BOP

Pipe Rams

11" 10M x 13-5/8"
5M Casing Spool

13-5/8" 5M x
13-3/8" SOW
Wellhead

10,000# BOP
Red Hills 32-5 Fed Com 158H
Cimarex Energy Co.
32-25S-33E
Lea Co., NM

PERFORMANCE DATA

TMK UP ULTRA™ FJ
Technical Data Sheet

7.625 in

29.70 lbs/ft

L80 HC

Tubular Parameters

Size	7.625	in	Minimum Yield	80,000	psi
Nominal Weight	29.70	lbs/ft	Minimum Tensile	95,000	psi
Grade	L80 HC		Yield Load	683,000	lbs
PE Weight	29.04	lbs/ft	Tensile Load	811,000	lbs
Wall Thickness	0.375	in	Min. Internal Yield Pressure	6,890	psi
Nominal ID	6.875	in	Collapse Pressure	5,510	psi
Drift Diameter	6.750	in			
Nom. Pipe Body Area	8.541	in ²			

Connection Parameters

Connection OD	7.625	in
Connection ID	6.881	in
Make-Up Loss	4.022	in
Critical Section Area	5.316	in ²
Tension Efficiency	62.2	%
Compression Efficiency	62.2	%
Yield Load In Tension	425,000	lbs
Min. Internal Yield Pressure	6,890	psi
Collapse Pressure	5,510	psi
Uniaxial Bending	30	°/ 100 ft

Make-Up Torques

Min. Make-Up Torque	13,200	ft-lbs
Opt. Make-Up Torque	14,700	ft-lbs
Max. Make-Up Torque	16,200	ft-lbs
Operating Torque	13,200	ft-lbs
Yield Torque	23,500	ft-lbs



Printed on: August-27-2018

NOTE:

The content of this Technical Data Sheet is for general information only and does not guarantee performance or imply fitness for a particular purpose, which only a competent drilling professional can determine considering the specific installation and operation parameters. Information that is printed or downloaded is no longer controlled by TMK IPSCO and might not be the latest information. Anyone using the information herein does so at their own risk. To verify that you have the latest TMK IPSCO technical information, please contact TMK IPSCO Technical Sales toll-free at 1-888-258-2000.



Red Hills 32-5 Fed Com 158H Casing Assumptions

2. Casing Program

Hole Size	Casing Depth From	Casing Depth To	Setting Depth TVD	Casing Size	Weight (lb/ft)	Grade	Conn.	SF Collapse	SF Burst	SF Tension
14 3/4	0	984	984	10-3/4"	40.50	J-55	BT&C	3.51	6.95	15.78
9 7/8	0	12426	12251	7-5/8"	29.70	L-80	BT&C	2.50	1.20	1.82
6 3/4	0	11700	11700	5-1/2"	20.00	L-80	LT&C	1.16	1.21	1.88
6 3/4	11700	22392	12300	5"	18.00	P-110	BT&C	1.68	1.70	53.70
BLM Minimum Safety Factor								1.125	1	1.6 Dry 1.8 Wet

TVD was used on all calculations.

All casing strings will be tested in accordance with Onshore Oil and Gas Order #2 III.B.1.h

Request Variance for 5-1/2" x 7-5/8" annular clearance. The portion that does not meet clearance will not be cemented

Red Hills 32-5 Fed Com 158H Casing Assumptions

2. Casing Program

Hole Size	Casing Depth From	Casing Depth To	Setting Depth TVD	Casing Size	Weight (lb/ft)	Grade	Conn.	SF Collapse	SF Burst	SF Tension
14 3/4	0	984	984	10-3/4"	40.50	J-55	BT&C	3.51	6.95	15.78
9 7/8	0	12426	12251	7-5/8"	29.70	L-80	BT&C	2.50	1.20	1.82
6 3/4	0	11700	11700	5-1/2"	20.00	L-80	LT&C	1.16	1.21	1.88
6 3/4	11700	22392	12300	5"	18.00	P-110	BT&C	1.68	1.70	53.70
BLM Minimum Safety Factor								1.125	1	1.6 Dry 1.8 Wet

TVD was used on all calculations.

All casing strings will be tested in accordance with Onshore Oil and Gas Order #2 III.B.1.h

Request Variance for 5-1/2" x 7-5/8" annular clearance. The portion that does not meet clearance will not be cemented

Red Hills 32-5 Fed Com 158H Casing Assumptions

2. Casing Program

Hole Size	Casing Depth From	Casing Depth To	Setting Depth TVD	Casing Size	Weight (lb/ft)	Grade	Conn.	SF Collapse	SF Burst	SF Tension
14 3/4	0	984	984	10-3/4"	40.50	J-55	BT&C	3.51	6.95	15.78
9 7/8	0	12426	12251	7-5/8"	29.70	L-80	BT&C	2.50	1.20	1.82
6 3/4	0	11700	11700	5-1/2"	20.00	L-80	LT&C	1.16	1.21	1.88
6 3/4	11700	22392	12300	5"	18.00	P-110	BT&C	1.68	1.70	53.70
BLM Minimum Safety Factor								1.125	1	1.6 Dry 1.8 Wet

TVD was used on all calculations.

All casing strings will be tested in accordance with Onshore Oil and Gas Order #2 III.B.1.h

Request Variance for 5-1/2" x 7-5/8" annular clearance. The portion that does not meet clearance will not be cemented

Red Hills 32-5 Fed Com 158H Casing Assumptions

2. Casing Program

Hole Size	Casing Depth From	Casing Depth To	Setting Depth TVD	Casing Size	Weight (lb/ft)	Grade	Conn.	SF Collapse	SF Burst	SF Tension
14 3/4	0	984	984	10-3/4"	40.50	J-55	BT&C	3.51	6.95	15.78
9 7/8	0	12426	12251	7-5/8"	29.70	L-80	BT&C	2.50	1.20	1.82
6 3/4	0	11700	11700	5-1/2"	20.00	L-80	LT&C	1.16	1.21	1.88
6 3/4	11700	22392	12300	5"	18.00	P-110	BT&C	1.68	1.70	53.70
BLM Minimum Safety Factor								1.125	1	1.6 Dry 1.8 Wet

TVD was used on all calculations.

All casing strings will be tested in accordance with Onshore Oil and Gas Order #2 III.B.1.h

Request Variance for 5-1/2" x 7-5/8" annular clearance. The portion that does not meet clearance will not be cemented

- 1 All Company and Contract personnel admitted on location must be trained by a qualified H2S safety instructor to the following:
 - A. Characteristics of H₂S
 - B. Physical effects and hazards
 - C. Principal and operation of H₂S detectors, warning system and briefing areas.
 - D. Evacuation procedure, routes and first aid.
 - E. Proper use of safety equipment & life support systems
 - F. Essential personnel meeting Medical Evaluation criteria will receive additional training on the proper use of 30 minute pressure demand air packs.

H₂S Detection and Alarm Systems:

 - A. H₂S sensors/detectors to be located on the drilling rig floor, in the base of the sub structure/cellar area, on the mud pits in the shale shaker area. Additional H₂S detectors may play placed as deemed necessary.
 - B. An audio alarm system will be installed on the derrick floor and in the top doghouse.
- 3 Windsock and/or wind streamers:
 - A. Windsock at mudpit area should be high enough to be visible.
 - B. Windsock on the rig floor and / or top doghouse should be high enough to be visible.
- 4 Condition Flags and Signs
 - A. Warning sign on access road to location.
 - B. Flags to be displayed on sign at entrance to location. Green flag indicates normal safe condition. Yellow flag indicates potential pressure and danger. Red flag indicates danger (H₂S present in dangerous concentration). Only H₂S trained and certified personnel admitted to location.
- 5 Well control equipment:
 - A. See exhibit "E-1"
- 6 Communication:
 - A. While working under masks chalkboards will be used for communication.
 - B. Hand signals will be used where chalk board is inappropriate.
 - C. Two way radio will be used to communicate off location in case of emergency help is required. In most cases cellular telephones will be available at most drilling foreman's trailer or living quarters.
- 7 Drillstem Testing:

No DSTs r cores are planned at this time.
- 8 Drilling contractor supervisor will be required to be familiar with the effects H₂S has on tubular goods and other mechanical equipment.
- 9 If H₂S is encountered, mud system will be altered if necessary to maintain control of formation. A mud gas separator will be brought into service along with H₂S scavengers if necessary.

H₂S Contingency Plan
Red Hills 32-5 Federal Com 158H
Cimarex Energy Co. of Colorado
UL: C, Sec. 32, 25S, 33E
Lea Co., NM

Emergency Procedures

In the event of a release of gas containing H₂S, the first responder(s) must:

- « Isolate the area and prevent entry by other persons into the 100 ppm ROE.
- « Evacuate any public places encompassed by the 100 ppm ROE.
- « Be equipped with H₂S monitors and air packs in order to control the release.
- « Use the "buddy system" to ensure no injuries occur during the 432-620-1975
- « Take precautions to avoid personal injury during this operation.
- « Contact operator and/or local officials to aid in operation. See list of phone numbers attached.
- « Have received training in the:
 - Detection of H₂S, and
 - Measures for protection against the gas,
 - Equipment used for protection and emergency response.

Ignition of Gas Source

Should control of the well be considered lost and ignition considered, take care to protect against exposure to Sulfur Dioxide (SO₂). Intentional ignition must be coordinated with the NMOCD and local officials. Additionally, the NM State Police may become involved. NM State Police shall be the Incident Command on scene of any major release. Take care to protect downwind whenever there is an ignition of the gas.

Characteristics of H₂S and SO₂

Please see attached International Chemical Safety Cards.

Contacting Authorities

Cimarex Energy Co. of Colorado's personnel must liaise with local and state agencies to ensure a proper response to a major release. Additionally, the OCD must be notified of the release as soon as possible but no later than 4 hours. Agencies will ask for information such as type and volume of release, wind direction, location of release, etc. Be prepared with all information available including directions to site. The following call list of essential and potential responders has been prepared for use during a release. Cimarex Energy Co. of Colorado's response must be in coordination with the State of New Mexico's "Hazardous Materials Emergency Response Plan" (HMER).

H₂S Contingency Plan Emergency Contacts

Red Hills 32-5 Federal Com 158H

Cimarex Energy Co. of Colorado

UL: C, Sec. 32, 25S, 33E

Lea Co., NM

Company Office			
Cimarex Energy Co. of Colorado		800-969-4789	
Co. Office and After-Hours Menu			
Key Personnel			
Name	Title	Office	Mobile
Larry Seigrist	Drilling Manager	432-620-1934	580-243-8485
Charlie Pritchard	Drilling Superintendent	432-620-1975	432-238-7084
Roy Shirley	Construction Superintendent		432-634-2136
Artesia			
Ambulance		911	
State Police		575-746-2703	
City Police		575-746-2703	
Sheriff's Office		575-746-9888	
Fire Department		575-746-2701	
Local Emergency Planning Committee		575-746-2122	
New Mexico Oil Conservation Division		575-748-1283	
Carlsbad			
Ambulance		911	
State Police		575-885-3137	
City Police		575-885-2111	
Sheriff's Office		575-887-7551	
Fire Department		575-887-3798	
Local Emergency Planning Committee		575-887-6544	
US Bureau of Land Management		575-887-6544	
Santa Fe			
New Mexico Emergency Response Commission (Santa Fe)		505-476-9600	
New Mexico Emergency Response Commission (Santa Fe) 24 Hrs		505-827-9126	
New Mexico State Emergency Operations Center		505-476-9635	
National			
National Emergency Response Center (Washington, D.C.)		800-424-8802	
Medical			
Flight for Life - 4000 24th St.; Lubbock, TX		806-743-9911	
Aerocare - R3, Box 49F; Lubbock, TX		806-747-8923	
Med Flight Air Amb - 2301 Yale Blvd S.E., #D3; Albuquerque, NM		505-842-4433	
SB Air Med Service - 2505 Clark Carr Loop S.E.; Albuquerque, NM		505-842-4949	
Other			
Boots & Coots IWC		800-256-9688	or 281-931-8884
Cudd Pressure Control		432-699-0139	or 432-563-3356
Halliburton		575-746-2757	
B.J. Services		575-746-3569	



Cimarex Red Hills 32-5 Fed Com #158H Rev2 RM 14Jan20 Proposal Geodetic Report (Def Plan)



Report Date: January 14, 2020 - 01:41 PM
Client: Cimarex Energy
Field: NM Lea County (NAD 83)
Structure / Slot: Cimarex Red Hills 32-5 Fed Com #158H / New Slot
Well: Red Hills 32-5 Fed Com #158H
Borehole: Red Hills 32-5 Fed Com #158H
UWI / API#: Unknown / Unknown
Survey Name: Cimarex Red Hills 32-5 Fed Com #158H Rev2 RM 14Jan20
Survey Date: August 29, 2019
Tort / AHD / DDI / ERD Ratio: 101.846 ° / 10513.037 ft / 6.290 / 0.855
Coordinate Reference System: NAD83 New Mexico State Plane, Eastern Zone, US Feet
Location Lat / Long: N 32° 5' 36.27471", W 103° 35' 43.48760"
Location Grid N/E Y/X: N 398501.090 ftUS, E 769854.490 ftUS
CRS Grid Convergence Angle: 0.3921 °
Grid Scale Factor: 0.9999689
Version / Patch: 2.10.787.0

Survey / DLS Computation: Minimum Curvature / Lubinski
Vertical Section Azimuth: 179.604 ° (Grid North)
Vertical Section Origin: 0.000 ft, 0.000 ft
TVD Reference Datum: RKB
TVD Reference Elevation: 3435.100 ft above MSL
Seabed / Ground Elevation: 3409.100 ft above MSL
Magnetic Declination: 6.584 °
Total Gravity Field Strength: 998.4286mgn (9.80665 Based)
Gravity Model: GARM
Total Magnetic Field Strength: 47689.184 nT
Magnetic Dip Angle: 59.675 °
Declination Date: January 14, 2020
Magnetic Declination Model: HDGM 2019
North Reference: Grid North
Grid Convergence Used: 0.3921 °
Total Corr Mag North->Grid North: 6.1918 °
Local Coord Referenced To: Well Head

Comments	MD (ft)	Incl (°)	Azim Grid (°)	TVD (ft)	VSEC (ft)	NS (ft)	EW (ft)	DLS (°/100ft)	Northing (ftUS)	Easting (ftUS)	Latitude (N/S ° ' ")	Longitude (E/W ° ' ")
SHL [330' FNL, 2305' FWL]	0.00	0.00	0.00	0.00	0.00	0.00	0.00	N/A	398501.09	769854.49	N 32 5 36.27 W 103 35 43.49	
	100.00	0.00	10.00	100.00	0.00	0.00	0.00	0.00	398501.09	769854.49	N 32 5 36.27 W 103 35 43.49	
	200.00	0.00	10.00	200.00	0.00	0.00	0.00	0.00	398501.09	769854.49	N 32 5 36.27 W 103 35 43.49	
	300.00	0.00	10.00	300.00	0.00	0.00	0.00	0.00	398501.09	769854.49	N 32 5 36.27 W 103 35 43.49	
	400.00	0.00	10.00	400.00	0.00	0.00	0.00	0.00	398501.09	769854.49	N 32 5 36.27 W 103 35 43.49	
	500.00	0.00	10.00	500.00	0.00	0.00	0.00	0.00	398501.09	769854.49	N 32 5 36.27 W 103 35 43.49	
	600.00	0.00	10.00	600.00	0.00	0.00	0.00	0.00	398501.09	769854.49	N 32 5 36.27 W 103 35 43.49	
	700.00	0.00	10.00	700.00	0.00	0.00	0.00	0.00	398501.09	769854.49	N 32 5 36.27 W 103 35 43.49	
	800.00	0.00	10.00	800.00	0.00	0.00	0.00	0.00	398501.09	769854.49	N 32 5 36.27 W 103 35 43.49	
	900.00	0.00	10.00	900.00	0.00	0.00	0.00	0.00	398501.09	769854.49	N 32 5 36.27 W 103 35 43.49	
Rustler	934.00	0.00	10.00	934.00	0.00	0.00	0.00	0.00	398501.09	769854.49	N 32 5 36.27 W 103 35 43.49	
	1000.00	0.00	10.00	1000.00	0.00	0.00	0.00	0.00	398501.09	769854.49	N 32 5 36.27 W 103 35 43.49	
	1100.00	0.00	10.00	1100.00	0.00	0.00	0.00	0.00	398501.09	769854.49	N 32 5 36.27 W 103 35 43.49	
	1200.00	0.00	10.00	1200.00	0.00	0.00	0.00	0.00	398501.09	769854.49	N 32 5 36.27 W 103 35 43.49	
	1300.00	0.00	10.00	1300.00	0.00	0.00	0.00	0.00	398501.09	769854.49	N 32 5 36.27 W 103 35 43.49	
Top of Salt	1349.00	0.00	10.00	1349.00	0.00	0.00	0.00	0.00	398501.09	769854.49	N 32 5 36.27 W 103 35 43.49	
	1400.00	0.00	10.00	1400.00	0.00	0.00	0.00	0.00	398501.09	769854.49	N 32 5 36.27 W 103 35 43.49	
	1500.00	0.00	10.00	1500.00	0.00	0.00	0.00	0.00	398501.09	769854.49	N 32 5 36.27 W 103 35 43.49	
	1600.00	0.00	10.00	1600.00	0.00	0.00	0.00	0.00	398501.09	769854.49	N 32 5 36.27 W 103 35 43.49	
	1700.00	0.00	10.00	1700.00	0.00	0.00	0.00	0.00	398501.09	769854.49	N 32 5 36.27 W 103 35 43.49	
	1800.00	0.00	10.00	1800.00	0.00	0.00	0.00	0.00	398501.09	769854.49	N 32 5 36.27 W 103 35 43.49	
	1900.00	0.00	10.00	1900.00	0.00	0.00	0.00	0.00	398501.09	769854.49	N 32 5 36.27 W 103 35 43.49	
	2000.00	0.00	10.00	2000.00	0.00	0.00	0.00	0.00	398501.09	769854.49	N 32 5 36.27 W 103 35 43.49	
	2100.00	0.00	10.00	2100.00	0.00	0.00	0.00	0.00	398501.09	769854.49	N 32 5 36.27 W 103 35 43.49	
	2200.00	0.00	10.00	2200.00	0.00	0.00	0.00	0.00	398501.09	769854.49	N 32 5 36.27 W 103 35 43.49	
	2300.00	0.00	10.00	2300.00	0.00	0.00	0.00	0.00	398501.09	769854.49	N 32 5 36.27 W 103 35 43.49	
	2400.00	0.00	10.00	2400.00	0.00	0.00	0.00	0.00	398501.09	769854.49	N 32 5 36.27 W 103 35 43.49	

Comments	MD (ft)	Incl (°)	Azim Grid (°)	TVD (ft)	VSEC (ft)	NS (ft)	EW (ft)	DLS (°/100ft)	Northing (ftUS)	Easting (ftUS)	Latitude (N/S ° ' ")	Longitude (E/W ° ' ")
Nudge 2°/100' DLS	2500.00	0.00	10.00	2500.00	0.00	0.00	0.00	0.00	398501.09	769854.49	N 32 5 36.27 W	103 35 43.49
	2600.00	2.00	10.00	2599.98	-1.72	1.72	0.30	2.00	398502.81	769854.79	N 32 5 36.29 W	103 35 43.48
	2700.00	4.00	10.00	2699.84	-6.86	6.87	1.21	2.00	398507.96	769855.70	N 32 5 36.34 W	103 35 43.47
Hold Nudge	2775.00	5.50	10.00	2774.58	-12.97	12.99	2.29	2.00	398514.08	769856.78	N 32 5 36.40 W	103 35 43.46
	2800.00	5.50	10.00	2799.46	-15.33	15.35	2.71	0.00	398516.44	769857.20	N 32 5 36.43 W	103 35 43.45
	2900.00	5.50	10.00	2899.00	-24.76	24.79	4.37	0.00	398525.88	769858.86	N 32 5 36.52 W	103 35 43.43
	3000.00	5.50	10.00	2998.54	-34.18	34.23	6.04	0.00	398535.32	769860.52	N 32 5 36.61 W	103 35 43.41
	3100.00	5.50	10.00	3098.08	-43.61	43.67	7.70	0.00	398544.75	769862.19	N 32 5 36.71 W	103 35 43.39
	3200.00	5.50	10.00	3197.62	-53.04	53.10	9.36	0.00	398554.19	769863.85	N 32 5 36.80 W	103 35 43.37
	3300.00	5.50	10.00	3297.16	-62.47	62.54	11.03	0.00	398563.63	769865.52	N 32 5 36.89 W	103 35 43.35
	3400.00	5.50	10.00	3396.70	-71.89	71.98	12.69	0.00	398573.07	769867.18	N 32 5 36.99 W	103 35 43.33
	3500.00	5.50	10.00	3496.24	-81.32	81.42	14.36	0.00	398582.51	769868.85	N 32 5 37.08 W	103 35 43.31
	3600.00	5.50	10.00	3595.78	-90.75	90.86	16.02	0.00	398591.95	769870.51	N 32 5 37.17 W	103 35 43.29
	3700.00	5.50	10.00	3695.32	-100.17	100.30	17.69	0.00	398601.39	769872.17	N 32 5 37.27 W	103 35 43.27
	3800.00	5.50	10.00	3794.86	-109.60	109.74	19.35	0.00	398610.82	769873.84	N 32 5 37.36 W	103 35 43.25
	3900.00	5.50	10.00	3894.40	-119.03	119.18	21.01	0.00	398620.26	769875.50	N 32 5 37.45 W	103 35 43.23
	4000.00	5.50	10.00	3993.94	-128.46	128.62	22.68	0.00	398629.70	769877.17	N 32 5 37.55 W	103 35 43.21
	4100.00	5.50	10.00	4093.48	-137.88	138.05	24.34	0.00	398639.14	769878.83	N 32 5 37.64 W	103 35 43.19
	4200.00	5.50	10.00	4193.02	-147.31	147.49	26.01	0.00	398648.58	769880.50	N 32 5 37.73 W	103 35 43.17
	4300.00	5.50	10.00	4292.56	-156.74	156.93	27.67	0.00	398658.02	769882.16	N 32 5 37.83 W	103 35 43.15
	4400.00	5.50	10.00	4392.10	-166.16	166.37	29.34	0.00	398667.46	769883.82	N 32 5 37.92 W	103 35 43.13
	4500.00	5.50	10.00	4491.64	-175.59	175.81	31.00	0.00	398676.89	769885.49	N 32 5 38.01 W	103 35 43.11
Drop to Vertical 2°/100' DLS	4508.40	5.50	10.00	4500.00	-176.38	176.60	31.14	0.00	398677.69	769885.63	N 32 5 38.02 W	103 35 43.11
	4600.00	3.67	10.00	4591.30	-183.58	183.81	32.41	2.00	398684.90	769886.90	N 32 5 38.09 W	103 35 43.10
Base of Salt	4659.79	2.47	10.00	4651.00	-186.73	186.97	32.97	2.00	398688.05	769887.46	N 32 5 38.12 W	103 35 43.09
	4700.00	1.67	10.00	4691.19	-188.16	188.40	33.22	2.00	398689.48	769887.71	N 32 5 38.14 W	103 35 43.09
Hold Vertical	4783.40	0.00	10.00	4774.58	-189.36	189.59	33.43	2.00	398690.68	769887.92	N 32 5 38.15 W	103 35 43.08
	4800.00	0.00	10.00	4791.18	-189.36	189.59	33.43	0.00	398690.68	769887.92	N 32 5 38.15 W	103 35 43.08
	4900.00	0.00	10.00	4891.18	-189.36	189.59	33.43	0.00	398690.68	769887.92	N 32 5 38.15 W	103 35 43.08
Lamar	4900.82	0.00	10.00	4892.00	-189.36	189.59	33.43	0.00	398690.68	769887.92	N 32 5 38.15 W	103 35 43.08
Bell Canyon	4937.82	0.00	10.00	4929.00	-189.36	189.59	33.43	0.00	398690.68	769887.92	N 32 5 38.15 W	103 35 43.08
	5000.00	0.00	10.00	4991.18	-189.36	189.59	33.43	0.00	398690.68	769887.92	N 32 5 38.15 W	103 35 43.08
	5100.00	0.00	10.00	5091.18	-189.36	189.59	33.43	0.00	398690.68	769887.92	N 32 5 38.15 W	103 35 43.08
	5200.00	0.00	10.00	5191.18	-189.36	189.59	33.43	0.00	398690.68	769887.92	N 32 5 38.15 W	103 35 43.08
	5300.00	0.00	10.00	5291.18	-189.36	189.59	33.43	0.00	398690.68	769887.92	N 32 5 38.15 W	103 35 43.08
	5400.00	0.00	10.00	5391.18	-189.36	189.59	33.43	0.00	398690.68	769887.92	N 32 5 38.15 W	103 35 43.08
	5500.00	0.00	10.00	5491.18	-189.36	189.59	33.43	0.00	398690.68	769887.92	N 32 5 38.15 W	103 35 43.08
	5600.00	0.00	10.00	5591.18	-189.36	189.59	33.43	0.00	398690.68	769887.92	N 32 5 38.15 W	103 35 43.08
	5700.00	0.00	10.00	5691.18	-189.36	189.59	33.43	0.00	398690.68	769887.92	N 32 5 38.15 W	103 35 43.08
	5800.00	0.00	10.00	5791.18	-189.36	189.59	33.43	0.00	398690.68	769887.92	N 32 5 38.15 W	103 35 43.08
	5900.00	0.00	10.00	5891.18	-189.36	189.59	33.43	0.00	398690.68	769887.92	N 32 5 38.15 W	103 35 43.08
	6000.00	0.00	10.00	5991.18	-189.36	189.59	33.43	0.00	398690.68	769887.92	N 32 5 38.15 W	103 35 43.08
Cherry Canyon	6009.82	0.00	10.00	6001.00	-189.36	189.59	33.43	0.00	398690.68	769887.92	N 32 5 38.15 W	103 35 43.08
	6100.00	0.00	10.00	6091.18	-189.36	189.59	33.43	0.00	398690.68	769887.92	N 32 5 38.15 W	103 35 43.08
	6200.00	0.00	10.00	6191.18	-189.36	189.59	33.43	0.00	398690.68	769887.92	N 32 5 38.15 W	103 35 43.08
	6300.00	0.00	10.00	6291.18	-189.36	189.59	33.43	0.00	398690.68	769887.92	N 32 5 38.15 W	103 35 43.08
	6400.00	0.00	10.00	6391.18	-189.36	189.59	33.43	0.00	398690.68	769887.92	N 32 5 38.15 W	103 35 43.08
	6500.00	0.00	10.00	6491.18	-189.36	189.59	33.43	0.00	398690.68	769887.92	N 32 5 38.15 W	103 35 43.08
	6600.00	0.00	10.00	6591.18	-189.36	189.59	33.43	0.00	398690.68	769887.92	N 32 5 38.15 W	103 35 43.08
	6700.00	0.00	10.00	6691.18	-189.36	189.59	33.43	0.00	398690.68	769887.92	N 32 5 38.15 W	103 35 43.08
	6800.00	0.00	10.00	6791.18	-189.36	189.59	33.43	0.00	398690.68	769887.92	N 32 5 38.15 W	103 35 43.08
	6900.00	0.00	10.00	6891.18	-189.36	189.59	33.43	0.00	398690.68	769887.92	N 32 5 38.15 W	103 35 43.08
	7000.00	0.00	10.00	6991.18	-189.36	189.59	33.43	0.00	398690.68	769887.92	N 32 5 38.15 W	103 35 43.08
	7100.00	0.00	10.00	7091.18	-189.36	189.59	33.43	0.00	398690.68	769887.92	N 32 5 38.15 W	103 35 43.08
	7200.00	0.00	10.00	7191.18	-189.36	189.59	33.43	0.00	398690.68	769887.92	N 32 5 38.15 W	103 35 43.08
	7300.00	0.00	10.00	7291.18	-189.36	189.59	33.43	0.00	398690.68	769887.92	N 32 5 38.15 W	103 35 43.08
	7400.00	0.00	10.00	7391.18	-189.36	189.59	33.43	0.00	398690.68	769887.92	N 32 5 38.15 W	103 35 43.08

Comments	MD (ft)	Incl (°)	Azim Grid (°)	TVD (ft)	VSEC (ft)	NS (ft)	EW (ft)	DLS (°/100ft)	Northing (ftUS)	Easting (ftUS)	Latitude (N/S ° ' ")	Longitude (E/W ° ' ")
Brusy Canyon	7500.00	0.00	10.00	7491.18	-189.36	189.59	33.43	0.00	398690.68	769887.92	N 32 5 38.15 W	103 35 43.08
	7545.82	0.00	10.00	7537.00	-189.36	189.59	33.43	0.00	398690.68	769887.92	N 32 5 38.15 W	103 35 43.08
	7600.00	0.00	10.00	7591.18	-189.36	189.59	33.43	0.00	398690.68	769887.92	N 32 5 38.15 W	103 35 43.08
	7700.00	0.00	10.00	7691.18	-189.36	189.59	33.43	0.00	398690.68	769887.92	N 32 5 38.15 W	103 35 43.08
	7800.00	0.00	10.00	7791.18	-189.36	189.59	33.43	0.00	398690.68	769887.92	N 32 5 38.15 W	103 35 43.08
	7900.00	0.00	10.00	7891.18	-189.36	189.59	33.43	0.00	398690.68	769887.92	N 32 5 38.15 W	103 35 43.08
	8000.00	0.00	10.00	7991.18	-189.36	189.59	33.43	0.00	398690.68	769887.92	N 32 5 38.15 W	103 35 43.08
	8100.00	0.00	10.00	8091.18	-189.36	189.59	33.43	0.00	398690.68	769887.92	N 32 5 38.15 W	103 35 43.08
	8200.00	0.00	10.00	8191.18	-189.36	189.59	33.43	0.00	398690.68	769887.92	N 32 5 38.15 W	103 35 43.08
	8300.00	0.00	10.00	8291.18	-189.36	189.59	33.43	0.00	398690.68	769887.92	N 32 5 38.15 W	103 35 43.08
	8400.00	0.00	10.00	8391.18	-189.36	189.59	33.43	0.00	398690.68	769887.92	N 32 5 38.15 W	103 35 43.08
	8500.00	0.00	10.00	8491.18	-189.36	189.59	33.43	0.00	398690.68	769887.92	N 32 5 38.15 W	103 35 43.08
	8600.00	0.00	10.00	8591.18	-189.36	189.59	33.43	0.00	398690.68	769887.92	N 32 5 38.15 W	103 35 43.08
	8700.00	0.00	10.00	8691.18	-189.36	189.59	33.43	0.00	398690.68	769887.92	N 32 5 38.15 W	103 35 43.08
	8800.00	0.00	10.00	8791.18	-189.36	189.59	33.43	0.00	398690.68	769887.92	N 32 5 38.15 W	103 35 43.08
8900.00	0.00	10.00	8891.18	-189.36	189.59	33.43	0.00	398690.68	769887.92	N 32 5 38.15 W	103 35 43.08	
9000.00	0.00	10.00	8991.18	-189.36	189.59	33.43	0.00	398690.68	769887.92	N 32 5 38.15 W	103 35 43.08	
Bone Spring	9047.82	0.00	10.00	9039.00	-189.36	189.59	33.43	0.00	398690.68	769887.92	N 32 5 38.15 W	103 35 43.08
Leonard Shale	9100.00	0.00	10.00	9091.18	-189.36	189.59	33.43	0.00	398690.68	769887.92	N 32 5 38.15 W	103 35 43.08
	9102.82	0.00	10.00	9094.00	-189.36	189.59	33.43	0.00	398690.68	769887.92	N 32 5 38.15 W	103 35 43.08
Avalon Shale	9200.00	0.00	10.00	9191.18	-189.36	189.59	33.43	0.00	398690.68	769887.92	N 32 5 38.15 W	103 35 43.08
	9300.00	0.00	10.00	9291.18	-189.36	189.59	33.43	0.00	398690.68	769887.92	N 32 5 38.15 W	103 35 43.08
	9364.82	0.00	10.00	9356.00	-189.36	189.59	33.43	0.00	398690.68	769887.92	N 32 5 38.15 W	103 35 43.08
	9400.00	0.00	10.00	9391.18	-189.36	189.59	33.43	0.00	398690.68	769887.92	N 32 5 38.15 W	103 35 43.08
	9500.00	0.00	10.00	9491.18	-189.36	189.59	33.43	0.00	398690.68	769887.92	N 32 5 38.15 W	103 35 43.08
Lower Avalon Shale	9600.00	0.00	10.00	9591.18	-189.36	189.59	33.43	0.00	398690.68	769887.92	N 32 5 38.15 W	103 35 43.08
	9700.00	0.00	10.00	9691.18	-189.36	189.59	33.43	0.00	398690.68	769887.92	N 32 5 38.15 W	103 35 43.08
	9739.82	0.00	10.00	9731.00	-189.36	189.59	33.43	0.00	398690.68	769887.92	N 32 5 38.15 W	103 35 43.08
	9800.00	0.00	10.00	9791.18	-189.36	189.59	33.43	0.00	398690.68	769887.92	N 32 5 38.15 W	103 35 43.08
1st Bone Spring Sand	9900.00	0.00	10.00	9891.18	-189.36	189.59	33.43	0.00	398690.68	769887.92	N 32 5 38.15 W	103 35 43.08
	10000.00	0.00	10.00	9991.18	-189.36	189.59	33.43	0.00	398690.68	769887.92	N 32 5 38.15 W	103 35 43.08
	10044.82	0.00	10.00	10036.00	-189.36	189.59	33.43	0.00	398690.68	769887.92	N 32 5 38.15 W	103 35 43.08
2nd Bone Spring Carb	10100.00	0.00	10.00	10091.18	-189.36	189.59	33.43	0.00	398690.68	769887.92	N 32 5 38.15 W	103 35 43.08
	10200.00	0.00	10.00	10191.18	-189.36	189.59	33.43	0.00	398690.68	769887.92	N 32 5 38.15 W	103 35 43.08
	10231.82	0.00	10.00	10223.00	-189.36	189.59	33.43	0.00	398690.68	769887.92	N 32 5 38.15 W	103 35 43.08
	10300.00	0.00	10.00	10291.18	-189.36	189.59	33.43	0.00	398690.68	769887.92	N 32 5 38.15 W	103 35 43.08
	10400.00	0.00	10.00	10391.18	-189.36	189.59	33.43	0.00	398690.68	769887.92	N 32 5 38.15 W	103 35 43.08
2nd Bone Spring Sand	10500.00	0.00	10.00	10491.18	-189.36	189.59	33.43	0.00	398690.68	769887.92	N 32 5 38.15 W	103 35 43.08
	10572.82	0.00	10.00	10564.00	-189.36	189.59	33.43	0.00	398690.68	769887.92	N 32 5 38.15 W	103 35 43.08
	10600.00	0.00	10.00	10591.18	-189.36	189.59	33.43	0.00	398690.68	769887.92	N 32 5 38.15 W	103 35 43.08
	10700.00	0.00	10.00	10691.18	-189.36	189.59	33.43	0.00	398690.68	769887.92	N 32 5 38.15 W	103 35 43.08
	10800.00	0.00	10.00	10791.18	-189.36	189.59	33.43	0.00	398690.68	769887.92	N 32 5 38.15 W	103 35 43.08
	10900.00	0.00	10.00	10891.18	-189.36	189.59	33.43	0.00	398690.68	769887.92	N 32 5 38.15 W	103 35 43.08
	11000.00	0.00	10.00	10991.18	-189.36	189.59	33.43	0.00	398690.68	769887.92	N 32 5 38.15 W	103 35 43.08
3rd Bone Spring Carb	11025.82	0.00	10.00	11017.00	-189.36	189.59	33.43	0.00	398690.68	769887.92	N 32 5 38.15 W	103 35 43.08
3rd Bone Spring Sand	11100.00	0.00	10.00	11091.18	-189.36	189.59	33.43	0.00	398690.68	769887.92	N 32 5 38.15 W	103 35 43.08
	11200.00	0.00	10.00	11191.18	-189.36	189.59	33.43	0.00	398690.68	769887.92	N 32 5 38.15 W	103 35 43.08
	11300.00	0.00	10.00	11291.18	-189.36	189.59	33.43	0.00	398690.68	769887.92	N 32 5 38.15 W	103 35 43.08
	11400.00	0.00	10.00	11391.18	-189.36	189.59	33.43	0.00	398690.68	769887.92	N 32 5 38.15 W	103 35 43.08
	11500.00	0.00	10.00	11491.18	-189.36	189.59	33.43	0.00	398690.68	769887.92	N 32 5 38.15 W	103 35 43.08
	11600.00	0.00	10.00	11591.18	-189.36	189.59	33.43	0.00	398690.68	769887.92	N 32 5 38.15 W	103 35 43.08
3rd Bone Spring Sand	11690.82	0.00	10.00	11682.00	-189.36	189.59	33.43	0.00	398690.68	769887.92	N 32 5 38.15 W	103 35 43.08
	11700.00	0.00	10.00	11691.18	-189.36	189.59	33.43	0.00	398690.68	769887.92	N 32 5 38.15 W	103 35 43.08

Comments	MD (ft)	Incl (°)	Azim Grid (°)	TVD (ft)	VSEC (ft)	NS (ft)	EW (ft)	DLS (°/100ft)	Northing (ftUS)	Easting (ftUS)	Latitude (N/S ° ' ")	Longitude (E/W ° ' ")
KOP - Build	11794.51	0.00	10.00	11785.68	-189.36	189.59	33.43	0.00	398690.68	769887.92	N 32 5 38.15 W	103 35 43.08
12°/100' DLS	11800.00	0.66	190.27	11791.18	-189.33	189.56	33.42	12.00	398690.64	769887.91	N 32 5 38.15 W	103 35 43.08
	11900.00	12.66	190.27	11890.32	-177.95	178.17	31.36	12.00	398679.26	769885.85	N 32 5 38.04 W	103 35 43.11
	12000.00	24.66	190.27	11984.89	-146.57	146.75	25.67	12.00	398647.83	769880.16	N 32 5 37.73 W	103 35 43.18
Build & Turn	12086.17	35.00	190.27	12059.55	-104.50	104.63	18.04	12.00	398605.71	769872.52	N 32 5 37.31 W	103 35 43.27
12°/100' DLS	12100.00	36.60	189.51	12070.76	-96.54	96.66	16.65	12.00	398597.75	769871.14	N 32 5 37.23 W	103 35 43.29
Wolfcamp	12171.68	44.95	186.32	12125.00	-50.26	50.33	10.32	12.00	398551.42	769864.81	N 32 5 36.77 W	103 35 43.36
	12200.00	48.26	185.31	12144.46	-29.81	29.86	8.24	12.00	398530.95	769862.73	N 32 5 36.57 W	103 35 43.39
	12300.00	60.04	182.42	12202.93	50.88	-50.86	2.94	12.00	398450.23	769857.43	N 32 5 35.77 W	103 35 43.46
	12400.00	71.86	180.15	12243.62	141.99	-141.99	0.99	12.00	398359.11	769855.48	N 32 5 34.87 W	103 35 43.49
Build 4°/100' DLS	12426.56	75.00	179.60	12251.19	167.44	-167.44	1.04	12.00	398333.66	769855.53	N 32 5 34.62 W	103 35 43.49
Wolfcamp Y Sand	12441.56	75.60	179.60	12255.00	181.95	-181.95	1.14	4.00	398319.15	769855.63	N 32 5 34.47 W	103 35 43.49
	12500.00	77.94	179.60	12268.37	238.84	-238.83	1.54	4.00	398262.27	769856.03	N 32 5 33.91 W	103 35 43.49
Wolfcamp Y SS Target	12594.08	81.70	179.60	12285.00	331.42	-331.41	2.18	4.00	398169.69	769856.67	N 32 5 33.00 W	103 35 43.49
	12600.00	81.94	179.60	12285.84	337.28	-337.27	2.22	4.00	398163.83	769856.71	N 32 5 32.94 W	103 35 43.49
	12700.00	85.94	179.60	12296.40	436.70	-436.69	2.90	4.00	398064.42	769857.39	N 32 5 31.95 W	103 35 43.49
	12800.00	89.94	179.60	12300.00	536.61	-536.60	3.59	4.00	397964.51	769858.08	N 32 5 30.96 W	103 35 43.49
Landing Point	12801.56	90.00	179.60	12300.00	538.17	-538.16	3.60	4.00	397962.95	769858.09	N 32 5 30.95 W	103 35 43.49
	12900.00	90.00	179.60	12300.00	636.61	-636.60	4.28	0.00	397864.51	769858.77	N 32 5 29.98 W	103 35 43.49
	13000.00	90.00	179.60	12300.00	736.61	-736.60	4.98	0.00	397764.52	769859.47	N 32 5 28.99 W	103 35 43.49
	13100.00	90.00	179.60	12300.00	836.61	-836.59	5.67	0.00	397664.52	769860.16	N 32 5 28.00 W	103 35 43.49
	13200.00	90.00	179.60	12300.00	936.61	-936.59	6.36	0.00	397564.53	769860.85	N 32 5 27.01 W	103 35 43.49
	13300.00	90.00	179.60	12300.00	1036.61	-1036.59	7.05	0.00	397464.53	769861.54	N 32 5 26.02 W	103 35 43.49
	13400.00	90.00	179.60	12300.00	1136.61	-1136.59	7.74	0.00	397364.54	769862.23	N 32 5 25.03 W	103 35 43.49
	13500.00	90.00	179.60	12300.00	1236.61	-1236.58	8.43	0.00	397264.55	769862.92	N 32 5 24.04 W	103 35 43.49
	13600.00	90.00	179.60	12300.00	1336.61	-1336.58	9.12	0.00	397164.55	769863.61	N 32 5 23.05 W	103 35 43.49
	13700.00	90.00	179.60	12300.00	1436.61	-1436.58	9.81	0.00	397064.56	769864.30	N 32 5 22.06 W	103 35 43.49
	13800.00	90.00	179.60	12300.00	1536.61	-1536.58	10.51	0.00	396964.56	769864.99	N 32 5 21.07 W	103 35 43.49
	13900.00	90.00	179.60	12300.00	1636.61	-1636.58	11.20	0.00	396864.57	769865.69	N 32 5 20.08 W	103 35 43.49
	14000.00	90.00	179.60	12300.00	1736.61	-1736.57	11.89	0.00	396764.57	769866.38	N 32 5 19.09 W	103 35 43.49
	14100.00	90.00	179.60	12300.00	1836.61	-1836.57	12.58	0.00	396664.58	769867.07	N 32 5 18.10 W	103 35 43.49
	14200.00	90.00	179.60	12300.00	1936.61	-1936.57	13.27	0.00	396564.59	769867.76	N 32 5 17.11 W	103 35 43.49
	14300.00	90.00	179.60	12300.00	2036.61	-2036.57	13.96	0.00	396464.59	769868.45	N 32 5 16.12 W	103 35 43.49
	14400.00	90.00	179.60	12300.00	2136.61	-2136.56	14.65	0.00	396364.60	769869.14	N 32 5 15.13 W	103 35 43.49
	14500.00	90.00	179.60	12300.00	2236.61	-2236.56	15.34	0.00	396264.60	769869.83	N 32 5 14.14 W	103 35 43.49
	14600.00	90.00	179.60	12300.00	2336.61	-2336.56	16.03	0.00	396164.61	769870.52	N 32 5 13.15 W	103 35 43.49
	14700.00	90.00	179.60	12300.00	2436.61	-2436.56	16.73	0.00	396064.61	769871.22	N 32 5 12.16 W	103 35 43.49
	14800.00	90.00	179.60	12300.00	2536.61	-2536.55	17.42	0.00	395964.62	769871.91	N 32 5 11.17 W	103 35 43.49
	14900.00	90.00	179.60	12300.00	2636.61	-2636.55	18.11	0.00	395864.63	769872.60	N 32 5 10.18 W	103 35 43.49
	15000.00	90.00	179.60	12300.00	2736.61	-2736.55	18.80	0.00	395764.63	769873.29	N 32 5 9.19 W	103 35 43.49
	15100.00	90.00	179.60	12300.00	2836.61	-2836.55	19.49	0.00	395664.64	769873.98	N 32 5 8.21 W	103 35 43.49
	15200.00	90.00	179.60	12300.00	2936.61	-2936.54	20.18	0.00	395564.64	769874.67	N 32 5 7.22 W	103 35 43.49
	15300.00	90.00	179.60	12300.00	3036.61	-3036.54	20.87	0.00	395464.65	769875.36	N 32 5 6.23 W	103 35 43.49
	15400.00	90.00	179.60	12300.00	3136.61	-3136.54	21.56	0.00	395364.65	769876.05	N 32 5 5.24 W	103 35 43.49
	15500.00	90.00	179.60	12300.00	3236.61	-3236.54	22.26	0.00	395264.66	769876.74	N 32 5 4.25 W	103 35 43.49
	15600.00	90.00	179.60	12300.00	3336.61	-3336.53	22.95	0.00	395164.67	769877.44	N 32 5 3.26 W	103 35 43.49
	15700.00	90.00	179.60	12300.00	3436.61	-3436.53	23.64	0.00	395064.67	769878.13	N 32 5 2.27 W	103 35 43.49
	15800.00	90.00	179.60	12300.00	3536.61	-3536.53	24.33	0.00	394964.68	769878.82	N 32 5 1.28 W	103 35 43.49
	15900.00	90.00	179.60	12300.00	3636.61	-3636.53	25.02	0.00	394864.68	769879.51	N 32 5 0.29 W	103 35 43.49
	16000.00	90.00	179.60	12300.00	3736.61	-3736.53	25.71	0.00	394764.69	769880.20	N 32 4 59.30 W	103 35 43.49
	16100.00	90.00	179.60	12300.00	3836.61	-3836.52	26.40	0.00	394664.69	769880.89	N 32 4 58.31 W	103 35 43.49
	16200.00	90.00	179.60	12300.00	3936.61	-3936.52	27.09	0.00	394564.70	769881.58	N 32 4 57.32 W	103 35 43.49
	16300.00	90.00	179.60	12300.00	4036.61	-4036.52	27.78	0.00	394464.71	769882.27	N 32 4 56.33 W	103 35 43.49
	16400.00	90.00	179.60	12300.00	4136.61	-4136.52	28.48	0.00	394364.71	769882.97	N 32 4 55.34 W	103 35 43.49

Comments	MD (ft)	Incl (°)	Azim Grid (°)	TVD (ft)	VSEC (ft)	NS (ft)	EW (ft)	DLS (°/100ft)	Northing (ftUS)	Easting (ftUS)	Latitude (N/S ° ' ")	Longitude (E/W ° ' ")
	16500.00	90.00	179.60	12300.00	4236.61	-4236.51	29.17	0.00	394264.72	769883.66	N 32 4 54.35 W	103 35 43.49
	16600.00	90.00	179.60	12300.00	4336.61	-4336.51	29.86	0.00	394164.72	769884.35	N 32 4 53.36 W	103 35 43.49
	16700.00	90.00	179.60	12300.00	4436.61	-4436.51	30.55	0.00	394064.73	769885.04	N 32 4 52.37 W	103 35 43.49
	16800.00	90.00	179.60	12300.00	4536.61	-4536.51	31.24	0.00	393964.73	769885.73	N 32 4 51.38 W	103 35 43.49
	16900.00	90.00	179.60	12300.00	4636.61	-4636.50	31.93	0.00	393864.74	769886.42	N 32 4 50.39 W	103 35 43.49
	17000.00	90.00	179.60	12300.00	4736.61	-4736.50	32.62	0.00	393764.75	769887.11	N 32 4 49.40 W	103 35 43.49
	17100.00	90.00	179.60	12300.00	4836.61	-4836.50	33.31	0.00	393664.75	769887.80	N 32 4 48.41 W	103 35 43.49
	17200.00	90.00	179.60	12300.00	4936.61	-4936.50	34.01	0.00	393564.76	769888.49	N 32 4 47.43 W	103 35 43.48
Private Leaseline Crossing	17214.20	90.00	179.60	12300.00	4950.81	-4950.70	34.10	0.00	393550.56	769888.59	N 32 4 47.28 W	103 35 43.48
	17300.00	90.00	179.60	12300.00	5036.61	-5036.49	34.70	0.00	393464.76	769889.19	N 32 4 46.44 W	103 35 43.48
	17400.00	90.00	179.60	12300.00	5136.61	-5136.49	35.39	0.00	393364.77	769889.88	N 32 4 45.45 W	103 35 43.48
	17500.00	90.00	179.60	12300.00	5236.61	-5236.49	36.08	0.00	393264.77	769890.57	N 32 4 44.46 W	103 35 43.48
	17600.00	90.00	179.60	12300.00	5336.61	-5336.49	36.77	0.00	393164.78	769891.26	N 32 4 43.47 W	103 35 43.48
	17700.00	90.00	179.60	12300.00	5436.61	-5436.48	37.46	0.00	393064.79	769891.95	N 32 4 42.48 W	103 35 43.48
	17800.00	90.00	179.60	12300.00	5536.61	-5536.48	38.15	0.00	392964.79	769892.64	N 32 4 41.49 W	103 35 43.48
	17900.00	90.00	179.60	12300.00	5636.61	-5636.48	38.84	0.00	392864.80	769893.33	N 32 4 40.50 W	103 35 43.48
	18000.00	90.00	179.60	12300.00	5736.61	-5736.48	39.54	0.00	392764.80	769894.02	N 32 4 39.51 W	103 35 43.48
	18100.00	90.00	179.60	12300.00	5836.61	-5836.47	40.23	0.00	392664.81	769894.71	N 32 4 38.52 W	103 35 43.48
	18200.00	90.00	179.60	12300.00	5936.61	-5936.47	40.92	0.00	392564.81	769895.41	N 32 4 37.53 W	103 35 43.48
	18300.00	90.00	179.60	12300.00	6036.61	-6036.47	41.61	0.00	392464.82	769896.10	N 32 4 36.54 W	103 35 43.48
	18400.00	90.00	179.60	12300.00	6136.61	-6136.47	42.30	0.00	392364.83	769896.79	N 32 4 35.55 W	103 35 43.48
	18500.00	90.00	179.60	12300.00	6236.61	-6236.47	42.99	0.00	392264.83	769897.48	N 32 4 34.56 W	103 35 43.48
Private - NMNMO106040 4 Crossing	18536.60	90.00	179.60	12300.00	6273.21	-6273.06	43.24	0.00	392228.23	769897.73	N 32 4 34.20 W	103 35 43.48
	18600.00	90.00	179.60	12300.00	6336.61	-6336.46	43.68	0.00	392164.84	769898.17	N 32 4 33.57 W	103 35 43.48
	18700.00	90.00	179.60	12300.00	6436.61	-6436.46	44.37	0.00	392064.84	769898.86	N 32 4 32.58 W	103 35 43.48
	18800.00	90.00	179.60	12300.00	6536.61	-6536.46	45.06	0.00	391964.85	769899.55	N 32 4 31.59 W	103 35 43.48
	18900.00	90.00	179.60	12300.00	6636.61	-6636.46	45.76	0.00	391864.85	769900.24	N 32 4 30.60 W	103 35 43.48
	19000.00	90.00	179.60	12300.00	6736.61	-6736.45	46.45	0.00	391764.86	769900.94	N 32 4 29.61 W	103 35 43.48
	19100.00	90.00	179.60	12300.00	6836.61	-6836.45	47.14	0.00	391664.87	769901.63	N 32 4 28.62 W	103 35 43.48
	19200.00	90.00	179.60	12300.00	6936.61	-6936.45	47.83	0.00	391564.87	769902.32	N 32 4 27.63 W	103 35 43.48
	19300.00	90.00	179.60	12300.00	7036.61	-7036.45	48.52	0.00	391464.88	769903.01	N 32 4 26.64 W	103 35 43.48
	19400.00	90.00	179.60	12300.00	7136.61	-7136.44	49.21	0.00	391364.88	769903.70	N 32 4 25.66 W	103 35 43.48
	19500.00	90.00	179.60	12300.00	7236.61	-7236.44	49.90	0.00	391264.89	769904.39	N 32 4 24.67 W	103 35 43.48
	19600.00	90.00	179.60	12300.00	7336.61	-7336.44	50.59	0.00	391164.89	769905.08	N 32 4 23.68 W	103 35 43.48
	19700.00	90.00	179.60	12300.00	7436.61	-7436.44	51.29	0.00	391064.90	769905.77	N 32 4 22.69 W	103 35 43.48
	19800.00	90.00	179.60	12300.00	7536.61	-7536.43	51.98	0.00	390964.91	769906.46	N 32 4 21.70 W	103 35 43.48
NMNMO106040 4 - NMNMO160973 Crossing	19858.90	90.00	179.60	12300.00	7595.51	-7595.33	52.38	0.00	390906.01	769906.87	N 32 4 21.11 W	103 35 43.48
	19900.00	90.00	179.60	12300.00	7636.61	-7636.43	52.67	0.00	390864.91	769907.16	N 32 4 20.71 W	103 35 43.48
	20000.00	90.00	179.60	12300.00	7736.61	-7736.43	53.36	0.00	390764.92	769907.85	N 32 4 19.72 W	103 35 43.48
	20100.00	90.00	179.60	12300.00	7836.61	-7836.43	54.05	0.00	390664.92	769908.54	N 32 4 18.73 W	103 35 43.48
	20200.00	90.00	179.60	12300.00	7936.61	-7936.42	54.74	0.00	390564.93	769909.23	N 32 4 17.74 W	103 35 43.48
	20300.00	90.00	179.60	12300.00	8036.61	-8036.42	55.43	0.00	390464.93	769909.92	N 32 4 16.75 W	103 35 43.48
	20400.00	90.00	179.60	12300.00	8136.61	-8136.42	56.12	0.00	390364.94	769910.61	N 32 4 15.76 W	103 35 43.48
	20500.00	90.00	179.60	12300.00	8236.61	-8236.42	56.81	0.00	390264.95	769911.30	N 32 4 14.77 W	103 35 43.48
	20600.00	90.00	179.60	12300.00	8336.61	-8336.42	57.51	0.00	390164.95	769911.99	N 32 4 13.78 W	103 35 43.48
	20700.00	90.00	179.60	12300.00	8436.61	-8436.41	58.20	0.00	390064.96	769912.69	N 32 4 12.79 W	103 35 43.48
	20800.00	90.00	179.60	12300.00	8536.61	-8536.41	58.89	0.00	389964.96	769913.38	N 32 4 11.80 W	103 35 43.48
	20900.00	90.00	179.60	12300.00	8636.61	-8636.41	59.58	0.00	389864.97	769914.07	N 32 4 10.81 W	103 35 43.48
	21000.00	90.00	179.60	12300.00	8736.61	-8736.41	60.27	0.00	389764.97	769914.76	N 32 4 9.82 W	103 35 43.48
	21100.00	90.00	179.60	12300.00	8836.61	-8836.40	60.96	0.00	389664.98	769915.45	N 32 4 8.83 W	103 35 43.48
	21200.00	90.00	179.60	12300.00	8936.61	-8936.40	61.65	0.00	389564.98	769916.14	N 32 4 7.84 W	103 35 43.48
	21300.00	90.00	179.60	12300.00	9036.61	-9036.40	62.34	0.00	389464.99	769916.83	N 32 4 6.85 W	103 35 43.48

Comments	MD (ft)	Incl (°)	Azim Grid (°)	TVD (ft)	VSEC (ft)	NS (ft)	EW (ft)	DLS (°/100ft)	Northing (ftUS)	Easting (ftUS)	Latitude (N/S ° ' ")	Longitude (E/W ° ' ")
	21400.00	90.00	179.60	12300.00	9136.61	-9136.40	63.04	0.00	389365.00	769917.52	N 32 4 5.86 W	103 35 43.48
	21500.00	90.00	179.60	12300.00	9236.61	-9236.39	63.73	0.00	389265.00	769918.21	N 32 4 4.88 W	103 35 43.48
	21600.00	90.00	179.60	12300.00	9336.61	-9336.39	64.42	0.00	389165.01	769918.91	N 32 4 3.89 W	103 35 43.48
	21700.00	90.00	179.60	12300.00	9436.61	-9436.39	65.11	0.00	389065.01	769919.60	N 32 4 2.90 W	103 35 43.48
	21800.00	90.00	179.60	12300.00	9536.61	-9536.39	65.80	0.00	388965.02	769920.29	N 32 4 1.91 W	103 35 43.48
	21900.00	90.00	179.60	12300.00	9636.61	-9636.38	66.49	0.00	388865.02	769920.98	N 32 4 0.92 W	103 35 43.48
	22000.00	90.00	179.60	12300.00	9736.61	-9736.38	67.18	0.00	388765.03	769921.67	N 32 3 59.93 W	103 35 43.48
	22100.00	90.00	179.60	12300.00	9836.61	-9836.38	67.87	0.00	388665.04	769922.36	N 32 3 58.94 W	103 35 43.48
	22200.00	90.00	179.60	12300.00	9936.61	-9936.38	68.56	0.00	388565.04	769923.05	N 32 3 57.95 W	103 35 43.48
	22300.00	90.00	179.60	12300.00	10036.61	-10036.37	69.26	0.00	388465.05	769923.74	N 32 3 56.96 W	103 35 43.48

Cimarex Red Hills 32-5 Fed Com #158H - PBHL [100' FSL, 2305' FWL]

22392.06	90.00	179.60	12300.00	10128.68	-10128.44	69.89	0.00	388372.99	769924.38	N 32 3 56.05 W	103 35 43.48
----------	-------	--------	----------	----------	-----------	-------	------	-----------	-----------	----------------	--------------

Survey Type: Def Plan


Survey Error Model: ISCWSA Rev 0 *** 3-D 95.000% Confidence 2.7955 sigma
 Survey Program:

Description	Part	MD From (ft)	MD To (ft)	EOU Freq (ft)	Hole Size (in)	Casing Diameter (in)	Expected Max Inclination (deg)	Survey Tool Type	Borehole / Survey
	1	0.000	26.000	1/100.000	17.500	13.375		NAL_MWD_IFR1+MS-Depth Only	Red Hills 32-5 Fed Com #158H / Cimarex Red Hills 32-5 Fed Com #158H Rev2 RM 14Jan20
	1	26.000	22392.063	1/100.000	17.500	13.375		NAL_MWD_IFR1+MS	Red Hills 32-5 Fed Com #158H / Cimarex Red Hills 32-5 Fed Com

Borehole: Red Hills 32-5 Fed Com #158H	Well: Red Hills 32-5 Fed Com #158H	Field: NM Lea County (NAD 83)	Structure: Cimarex Red Hills 32-5 Fed Com #158H
--	--	---	---

Gravity & Magnetic Parameters Model: HDGM 2019 MagDec: 6.584°	Dip: 59.67° FS: 47688.184mT	Date: 14-Jan-2020 Gravity FS: 998.429mgm (8.80665 Based)	Surface Location Lat: N 32 5 36.27 Lon: W 103 35 43.49	NAD83 New Mexico State Plane, Eastern Zone, US Feet Northing: 398501.09HUS Easting: 769554.49HUS	Grid Conv: Scale Fact: 0.3921° 0.9999689	Miscellaneous Slot: New Slot Plan: Cimarex Red Hills 32-5 Fed Com #158H Rev2 RM 14Jan20	TVD Ref: RKB(3435.1ft above MSL)
--	--------------------------------	---	---	---	---	--	--

Critical Point	MD	INCL	AZIM	Critical Points	TVD	VSEC	N(+)/S(-)	E(+)/W(-)	DLS
SHL (330° FNL, 2305' FWL)	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Rustler	934.00	0.00	10.00	934.00	0.00	0.00	0.00	0.00	0.00
Top of Salt	1349.00	0.00	10.00	1349.00	0.00	0.00	0.00	0.00	0.00
Nudge 2'100' DLS	2550.00	0.00	10.00	2550.00	0.00	0.00	0.00	0.00	0.00
Hold Nudge	2775.00	5.50	10.00	2774.58	12.99	-12.97	176.80	311.14	2.00
Drop to Vertical 2'100' DLS	4536.40	5.50	10.00	4530.00	-176.38	-176.38	176.80	311.14	0.00
Base of Salt	4659.79	2.47	10.00	4651.00	-186.73	-186.73	186.97	32.97	2.00
Hold Vertical	4783.40	0.00	10.00	4774.58	-189.36	-189.36	189.59	33.43	2.00
Lamar	4900.92	0.00	10.00	4892.00	-189.36	-189.36	189.59	33.43	0.00
Ball Canyon	4937.82	0.00	10.00	4929.00	-189.36	-189.36	189.59	33.43	0.00
Cherry Canyon	6009.92	0.00	10.00	6001.00	-189.36	-189.36	189.59	33.43	0.00
Brusy Canyon	7545.82	0.00	10.00	7537.00	-189.36	-189.36	189.59	33.43	0.00
Bone Spring	9047.82	0.00	10.00	9039.00	-189.36	-189.36	189.59	33.43	0.00
Leonard Shale	9102.92	0.00	10.00	9094.00	-189.36	-189.36	189.59	33.43	0.00
Avalon Shale	9384.82	0.00	10.00	9356.00	-189.36	-189.36	189.59	33.43	0.00
Lower Avalon Shale	9739.92	0.00	10.00	9731.00	-189.36	-189.36	189.59	33.43	0.00
1st Bone Spring Sand	10044.82	0.00	10.00	10036.00	-189.36	-189.36	189.59	33.43	0.00
2nd Bone Spring Carb	10231.82	0.00	10.00	10223.00	-189.36	-189.36	189.59	33.43	0.00
2nd Bone Spring Sand	10271.82	0.00	10.00	10264.00	-189.36	-189.36	189.59	33.43	0.00
3rd Bone Spring Carb	11025.82	0.00	10.00	11017.00	-189.36	-189.36	189.59	33.43	0.00
3rd Bone Spring Sand	11090.92	0.00	10.00	11082.00	-189.36	-189.36	189.59	33.43	0.00
KOP - Build 12'100' DLS	11794.51	0.00	10.00	11785.68	-189.36	-189.36	189.59	33.43	0.00
Build & Turn 12'100' DLS	12086.17	35.00	190.27	12059.55	-104.50	-104.50	104.63	18.04	12.00
Wolfcamp	12171.68	44.95	186.32	12126.00	-50.26	-50.26	50.33	10.32	0.00
Build 4'100' DLS	12426.56	75.00	179.80	12251.19	167.44	167.44	-167.44	1.04	12.00
Wolfcamp Y Sand	12441.56	75.60	179.60	12255.00	181.95	-181.95	-181.95	1.14	4.00
Wolfcamp Y SS Target	12594.08	81.70	179.60	12285.00	331.42	-331.41	-331.41	2.18	4.00
Landing Point	12961.56	90.00	179.60	12300.00	538.17	-538.16	-538.16	3.60	4.00
Private Lease/line Crossing	17214.20	90.00	179.60	12300.00	4950.81	-4950.70	-4950.70	34.10	0.00
Private - NMNM1060404 Crossing	18536.60	90.00	179.60	12300.00	6273.21	-6273.06	-6273.06	43.24	0.00
NMNM1060404 - NMNM106073 Crossing	19859.90	90.00	179.60	12300.00	7695.51	-7695.33	-7695.33	52.38	0.00
Wolcamp A1	22392.06	90.00	179.60	12300.00	10128.68	-10128.44	-10128.44	69.89	0.00
Wolcamp A1	NaN	NaN	NaN	12301.00					0.00



CONTROLLED



Drawn by: Cimarex Red Hills 32-5 Fed Com #158H Rev2 RM 14Jan20

Copy number: 1 of 1

Date: 14-Jan-2020

1	Client	
2	Client	
3	Office	
4	Office	

Copy number for:



Vertical Section (ft) Azim = 179.60° Scale = 1:798.12(ft) Origin = ON-S, 0E/W



Cimarex Red Hills 32-5 Fed Com #158H Rev2 RM 14Jan20 Anti-Collision Summary Report

Analysis Date-24hr Time: January 14, 2020 - 13:42
Client: Cimarex Energy
Field: NM Lea County (NAD 83)
Structure: Cimarex Red Hills 32-5 Fed Com #158H
Slot: New Slot
Well: Red Hills 32-5 Fed Com #158H
Borehole: Red Hills 32-5 Fed Com #158H
Scan MD Range: 0.00ft ~ 22392.06ft

Analysis Method: 3D Least Distance
Reference Trajectory: Cimarex Red Hills 32-5 Fed Com #158H Rev2 RM 14Jan20 (Def Plan)
Depth Interval: Every 10.00 Measured Depth (ft)
Rule Set: NAL Procedure: D&M AntiCollision Standard S002
Min Pts: All local minima indicated.
Version / Patch: 2.10.787.0
Database \ Project: us1153APP452.DIR.SLB.COMDRILLING-NM Lea County 2.10

Trajectory Error Model: ISCWSA0 3-D 95.000% Confidence 2.7955 sigma, for subject well. For offset wells, error model version is specified with each well respectively.

Offset Trajectories Summary

Offset Selection Criteria

Wellhead distance scan: Not performed!
 Selection filters: Definitive Surveys - Definitive Plans - Definitive surveys exclude definitive plans
 - All Non-Def Surveys when no Def-Survey is set in a borehole - All Non-Def Plans when no Def-Plan is set in a borehole

Offset Trajectory	Separation			Allow Dev. (ft)	Sep. Fact.	Controlling Rule	Reference Trajectory		Risk Level			Alert	Status
	Ct-Ct (ft)	MAS (ft)	EOU (ft)				MD (ft)	TVD (ft)	Alert	Minor	Major		

Results highlighted: Sep-Factor separation <= 1.50 ft

Cimarex Red Hills 32-5 Fed Com #159H Rev3 RM 14Jan19 (Def Plan) Fail Minor

20.00	16.26	18.71	3.74	N/A	MAS = 4.96 (m)	0.00	0.00	CtCt<=15m<15.00	Enter Alert
20.00	16.26	18.71	3.74	N/A	MAS = 4.96 (m)	26.00	26.00		WRP
20.00	20.02	6.23	-0.02	1.50	OSF1.50	2050.00	2050.00	OSF<1.50	Enter Minor
20.00	22.37	4.66	-2.37	1.33	OSF1.50	2300.00	2300.00		MinPt-CtCt
20.22	23.59	4.06	-3.37	1.27	OSF1.50	2430.00	2430.00		MINPT-O-EOU
20.30	23.69	4.08	-3.39	1.27	OSF1.50	2440.00	2440.00		MinPt-O-SF
20.39	23.78	4.11	-3.39	1.27	OSF1.50	2450.00	2450.00		MinPt-O-ADP
25.69	25.72	8.11	-0.03	1.50	OSF1.50	2660.00	2659.92	OSF>1.50	Exit Minor
27.49	27.21	8.92	0.28	1.52	OSF1.50	2820.00	2819.37		MINPT-O-EOU
28.79	28.79	9.17	0.00	1.50	OSF1.50	2990.00	2988.59	OSF<1.50	Enter Minor
28.88	28.88	9.20	0.00	1.50	OSF1.50	3000.00	2998.54		MinPts
28.97	28.98	9.23	0.00	1.50	OSF1.50	3010.00	3008.50	OSF>1.50	Exit Minor
78.09	78.14	25.56	-0.06	1.50	OSF1.50	8680.00	8671.18	OSF<1.50	Enter Minor
78.09	94.60	14.59	-16.52	1.23	OSF1.50	10430.00	10421.18		MinPts
91.54	93.02	29.09	-1.49	1.48	OSF1.50	10570.00	10561.18	OSF>1.50	Exit Minor
238.62	74.05	188.82	164.56	4.89	OSF1.50	10900.00	10891.18	OSF>5.00	Exit Alert
1400.04	316.49	1188.62	1083.55	6.66	OSF1.50	22392.06	12300.00		MinPts

Cimarex Red Hills Unit #3H (Offset) Gas Gyro & Inc Off-17597ft (Def Survey) Fail Minor

8235.67	32.81	8234.38	8202.86	N/A	MAS = 10.00 (m)	0.00	0.00		Surface
8235.54	32.81	8234.24	8202.73	572327.58	MAS = 10.00 (m)	26.00	26.00		WRP
8179.82	32.81	8163.14	8147.01	532.26	MAS = 10.00 (m)	2580.00	2579.99		MinPts
8179.85	32.81	8163.14	8147.04	531.03	MAS = 10.00 (m)	2590.00	2589.99		MINPT-O-EOU
8334.84	38.40	8308.81	8296.44	336.79	OSF1.50	4600.00	4591.30		MinPt-O-SF
8338.40	40.96	8310.67	8297.45	315.25	OSF1.50	5370.00	5361.18		MinPt-CtCt

Offset Trajectory	Separation			Allow Dev. (ft)	Sep. Fact.	Controlling Rule	Reference Trajectory		Risk Level			Alert	Status
	Ct-Ct (ft)	MAS (ft)	EOU (ft)				MD (ft)	TVD (ft)	Alert	Minor	Major		
8339.20	44.08		8309.39	8295.12	292.26	OSF1.50	6050.00	6041.18				MINPT-O-EOU	
8339.94	45.18		8309.39	8294.76	284.97	OSF1.50	6280.00	6271.18				MINPT-O-EOU	
8341.08	47.42		8309.04	8293.66	271.17	OSF1.50	6710.00	6701.18				MINPT-O-EOU	
8342.30	49.29		8309.01	8293.01	260.63	OSF1.50	7010.00	7001.18				MINPT-O-EOU	
8343.17	50.35		8309.18	8292.83	255.06	OSF1.50	7170.00	7161.18				MinPt-O-ADP	
8445.33	77.56		8393.19	8367.76	166.05	OSF1.50	11794.51	11785.68				MinPt-O-SF	
8372.74	76.00		8321.65	8296.74	168.08	OSF1.50	12080.00	12054.47				MinPt-O-SF	
8361.75	75.90		8310.72	8285.85	168.08	OSF1.50	12100.00	12070.76				MinPt-O-SF	
343.96	113.33		263.88	230.62	4.97	OSF1.50	20220.00	12300.00	OSF<5.00			Enter Alert	
168.01	168.13		52.89	-0.12	1.50	OSF1.50	20440.00	12300.00		OSF<1.50		Enter Minor	
138.82	189.08		12.16	-50.26	1.10	OSF1.50	20530.00	12300.00				MinPts	
162.82	166.72		51.24	-3.90	1.46	OSF1.50	20620.00	12300.00		OSF>1.50		Exit Minor	
335.25	105.42		264.54	229.83	4.81	OSF1.50	20840.00	12300.00	OSF>5.00			Exit Alert	
1862.25	76.88		1810.57	1785.37	36.93	OSF1.50	22392.06	12300.00				TD	

Cimarex Red Hills 32-5 Fed
Com #160H Rev3 RM
14Jan20 (Def Plan)

Warning Alert

39.99	32.25		38.71	7.74	N/A	MAS = 9.83 (m)	0.00	0.00	CtCt<=15m<15.00			Enter Alert	
39.99	32.25		38.71	7.74	N/A	MAS = 9.83 (m)	26.00	26.00				WRP	
39.99	32.25		23.39	7.74	2.53	MAS = 9.83 (m)	2500.00	2500.00				MinPts	
40.27	32.25		23.11	8.02	2.46	MAS = 9.83 (m)	2590.00	2589.99				MINPT-O-EOU	
41.03	32.25		23.43	8.78	2.44	MAS = 9.83 (m)	2660.00	2659.92				MinPt-O-SF	
115.02	35.43		90.97	79.58	5.00	OSF1.50	3690.00	3685.37	OSF>5.00			Exit Alert	
203.55	61.98		161.80	141.56	5.00	OSF1.50	6740.00	6731.18	OSF<5.00			Enter Alert	
203.55	91.04		142.42	112.51	3.38	OSF1.50	9830.00	9821.18				MinPts	
203.60	91.08		142.45	112.52	3.38	OSF1.50	9840.00	9831.18				MinPt-O-SF	
271.94	83.88		215.60	188.06	4.92	OSF1.50	10150.00	10141.18	OSF>5.00			Exit Alert	
2000.20	314.11		1790.37	1686.09	9.58	OSF1.50	22392.06	12300.00				MinPts	

Cimarex Red Hills 32-5 Fed
Com #156H Rev4 RM
19Dec19 (Def Plan)

Warning Alert

84.84	32.81		83.56	52.03	N/A	MAS = 10.00 (m)	0.00	0.00				Surface	
84.84	32.81		83.56	52.03	62678.49	MAS = 10.00 (m)	26.00	26.00				WRP	
69.10	32.81		54.20	36.30	4.98	MAS = 10.00 (m)	2340.00	2340.00	OSF<5.00			Enter Alert	
53.59	32.81		37.44	20.78	3.52	MAS = 10.00 (m)	2610.00	2609.97				MinPts	
53.78	32.81		37.53	20.97	3.51	MAS = 10.00 (m)	2630.00	2629.96				MinPt-O-SF	
82.89	32.81		65.17	50.08	4.96	MAS = 10.00 (m)	2940.00	2938.82	OSF>5.00			Exit Alert	
466.35	84.95		409.29	381.40	8.34	OSF1.50	10440.00	10431.18				MinPts	
466.77	85.08		409.62	381.69	8.33	OSF1.50	10470.00	10461.18				MinPt-O-SF	
1456.04	318.08		1243.55	1137.96	6.89	OSF1.50	22390.00	12300.00				MinPt-CtCt	
1456.04	318.14		1243.51	1137.89	6.89	OSF1.50	22392.06	12300.00				MinPts	

Cimarex Red Hills 32-5 Fed
Com #157H Rev4 RM
19Dec19 (Def Plan)

Warning Alert

72.10	32.81		70.81	39.29	N/A	MAS = 10.00 (m)	0.00	0.00				Surface	
72.10	32.81		70.81	39.29	63741.71	MAS = 10.00 (m)	26.00	26.00				WRP	
62.73	32.81		49.15	29.92	5.00	MAS = 10.00 (m)	2150.00	2150.00	OSF<5.00			Enter Alert	
59.99	32.81		45.79	27.18	4.55	MAS = 10.00 (m)	2300.00	2300.00				MinPts	
60.01	32.81		45.77	27.20	4.53	MAS = 10.00 (m)	2310.00	2310.00				MINPT-O-EOU	
60.66	32.81		46.16	27.85	4.49	MAS = 10.00 (m)	2370.00	2370.00				MinPt-O-SF	
71.45	32.81		55.99	38.64	4.95	MAS = 10.00 (m)	2590.00	2589.99	OSF>5.00			Exit Alert	
441.21	39.62		414.36	401.59	17.21	OSF1.50	4960.00	4951.18				MinPt-O-SF	
499.37	77.87		447.03	421.50	9.76	OSF1.50	9810.00	9801.18				MinPts	

Offset Trajectory	Separation			Allow		Sep. Fact.	Controlling Rule	Reference Trajectory		Risk Level			Alert	Status
	Ct-Ct (ft)	MAS (ft)	EOU (ft)	Dev. (ft)	MD (ft)			TVD (ft)	Alert	Minor	Major			
	499.87	78.00	447.44	421.87	9.75		OSF1.50	9840.00	9831.18				MinPt-O-SF	
	2088.76	316.13	1877.58	1772.63	9.95		OSF1.50	22392.06	12300.00				MinPts	
Cimarex Red Hills 32-5 Fed Com #155H Rev4 RM 19Dec19 (Def Plan) Warning Alert														
	99.98	32.81	98.69	67.17	N/A		MAS = 10.00 (m)	0.00	0.00				Surface	
	99.98	32.81	98.69	67.17	63456.49		MAS = 10.00 (m)	26.00	26.00				WRP	
	99.98	32.81	83.38	67.17	6.44		MAS = 10.00 (m)	2500.00	2500.00				MinPts	
	100.10	32.81	83.25	67.30	6.35		MAS = 10.00 (m)	2540.00	2540.00				MINPT-O-EOU	
	104.02	32.81	86.05	71.21	6.16		MAS = 10.00 (m)	2720.00	2719.78				MinPt-O-SF	
	273.43	40.83	245.78	232.60	10.32		OSF1.50	5060.00	5051.18				MinPt-O-SF	
	404.99	96.17	340.45	308.82	6.38		OSF1.50	11790.00	11781.18				MinPts	
	405.02	96.18	340.47	308.85	6.38		OSF1.50	11794.51	11785.68				MinPt-O-SF	
	344.28	87.82	285.31	256.46	5.95		OSF1.50	12530.00	12274.34				MinPt-CtCt	
	344.37	88.03	285.25	256.34	5.93		OSF1.50	12550.00	12277.97				MINPT-O-EOU	
	344.46	88.12	285.28	256.34	5.93		OSF1.50	12560.00	12279.68				MinPt-O-ADP	
	345.26	88.48	285.84	256.78	5.92		OSF1.50	12610.00	12287.21				MinPt-O-SF	
	348.88	105.66	278.00	243.21	5.00		OSF1.50	14880.00	12300.00	OSF<5.00			Enter Alert	
	351.24	315.46	140.51	35.79	1.67		OSF1.50	22392.06	12300.00				MinPts	
Cimarex Red Hills 32-5 Fed Com #171H Rev0 RM 04Sept19 (Non-Def Plan) Warning Alert														
	701.86	32.81	699.88	669.05	N/A		MAS = 10.00 (m)	0.00	0.00				Surface	
	701.86	32.81	699.88	669.05	630001.74		MAS = 10.00 (m)	26.00	26.00				WRP	
	698.70	32.81	676.25	665.89	34.04		MAS = 10.00 (m)	3330.00	3327.02				MinPts	
	700.21	37.19	674.76	663.02	29.75		OSF1.50	3810.00	3804.81				MINPT-O-EOU	
	702.09	39.44	675.13	662.65	28.03		OSF1.50	4050.00	4043.71				MinPt-O-ADP	
	708.96	44.21	678.82	664.74	25.11		OSF1.50	4600.00	4591.30				MinPt-O-SF	
	709.94	109.25	636.45	600.69	9.90		OSF1.50	11710.00	11701.18				MinPt-O-SF	
	531.47	102.84	462.11	428.63	7.90		OSF1.50	12790.00	12299.95				MinPt-O-SF	
	531.16	102.78	461.85	428.38	7.90		OSF1.50	12810.00	12300.00				MinPt-O-SF	
	529.99	102.30	460.99	427.69	7.92		OSF1.50	12960.00	12300.00				MinPt-O-ADP	
	529.91	102.21	460.97	427.70	7.93		OSF1.50	12990.00	12300.00				MINPT-O-EOU	
	529.82	101.97	461.05	427.85	7.95		OSF1.50	13080.00	12300.00				MinPt-CtCt	
	530.57	160.96	422.47	369.61	5.00		OSF1.50	17110.00	12300.00	OSF<5.00			Enter Alert	
	531.75	313.59	321.90	218.17	2.55		OSF1.50	22392.06	12300.00				MinPts	
Cimarex Red Hills Unit #1 (Offset) Gas Inc Only Off-21321ft (Def Survey) Warning Alert														
	4660.42	32.81	4658.44	4627.61	N/A		MAS = 10.00 (m)	0.00	0.00				Surface	
	4660.39	32.81	4658.40	4627.58	N/A		MAS = 10.00 (m)	10.00	10.00				MinPt-O-SF	
	4660.38	32.81	4658.40	4627.57	N/A		MAS = 10.00 (m)	20.00	20.00				MinPts	
	4660.38	32.81	4658.40	4627.57	N/A		MAS = 10.00 (m)	26.00	26.00				WRP	
	4660.19	32.81	4645.33	4627.38	361.74		MAS = 10.00 (m)	440.00	440.00				MinPts	
	4660.49	32.81	4644.42	4627.68	330.78		MAS = 10.00 (m)	520.00	520.00				MINPT-O-EOU	
	4659.31	34.15	4635.88	4625.16	217.14		OSF1.50	690.00	690.00				MinPt-CtCt	
	4659.38	41.07	4631.34	4618.31	178.71		OSF1.50	820.00	820.00				MinPt-CtCt	
	4660.66	44.30	4630.46	4616.36	165.11		OSF1.50	960.00	960.00				MINPT-O-EOU	
	4660.21	56.03	4622.20	4604.18	129.28		OSF1.50	1110.00	1110.00				MinPt-CtCt	
	4661.18	58.76	4621.35	4602.42	123.08		OSF1.50	1230.00	1230.00				MINPT-O-EOU	
	4660.54	70.32	4613.00	4590.22	102.25		OSF1.50	1380.00	1380.00				MinPt-CtCt	
	4660.35	91.69	4598.57	4568.67	77.89		OSF1.50	1790.00	1790.00				MinPt-CtCt	
	4660.06	117.28	4581.21	4542.78	60.60		OSF1.50	2280.00	2280.00				MinPt-CtCt	

Offset Trajectory	Separation			Allow Dev. (ft)	Sep. Fact.	Controlling Rule	Reference Trajectory		Risk Level			Alert	Status
	Ct-Ct (ft)	MAS (ft)	EOU (ft)				MD (ft)	TVD (ft)	Alert	Minor	Major		
4662.91	138.33		4570.04	4524.58	51.28	OSF1.50	2620.00	2619.96				MINPT-O-EOU	
4663.86	139.43		4570.25	4524.43	50.87	OSF1.50	2650.00	2649.93				MinPt-O-ADP	
4700.60	162.76		4591.43	4537.84	43.84	OSF1.50	3080.00	3078.17				MinPts	
4723.67	174.91		4606.40	4548.76	40.96	OSF1.50	3340.00	3336.98				MinPts	
4754.92	193.55		4625.22	4561.37	37.22	OSF1.50	3660.00	3655.50				MinPts	
4776.10	206.96		4637.47	4569.14	34.94	OSF1.50	3900.00	3894.40				MinPts	
4801.94	221.11		4653.88	4580.83	32.86	OSF1.50	4190.00	4183.06				MinPts	
4828.28	234.37		4671.37	4593.91	31.15	OSF1.50	4480.00	4471.73				MINPT-O-EOU	
4832.46	241.01		4671.13	4591.45	30.31	OSF1.50	4540.00	4531.47				MinPts	
4838.93	277.16	4653.50	4561.77	26.37	OSF1.50	5360.00	5351.18				MinPt-CtCt		
4839.21	335.02	4615.20	4504.19	21.79	OSF1.50	6470.00	6461.18				MinPt-CtCt		
4837.83	381.00	4583.17	4456.83	19.14	OSF1.50	7350.00	7341.18				MinPt-CtCt		
4838.39	457.80	4532.53	4380.59	15.92	OSF1.50	8820.00	8811.18				MinPt-CtCt		
4839.89	520.45	4492.26	4319.44	14.00	OSF1.50	10020.00	10011.18				MinPt-CtCt		
4841.16	588.71	4448.03	4252.46	12.37	OSF1.50	11330.00	11321.18				MinPt-CtCt		
2131.12	646.55	1697.92	1484.58	4.98	OSF1.50	14860.00	12300.00		OSF<5.00		Enter Alert		
702.86	644.22	272.72	58.64	1.64	OSF1.50	16870.00	12300.00				MinPts		
2117.15	639.28	1690.30	1477.87	4.98	OSF1.50	18870.00	12300.00		OSF>5.00		Exit Alert		
5563.49	637.43	5137.88	4926.06	13.13	OSF1.50	22392.06	12300.00				TD		

Cimarex Red Hills 32-5 Fed Com #170H Rev0 RM 04Sept19 (Non-Def Plan) Warning Alert

721.79	32.81	720.50	688.98	N/A	MAS = 10.00 (m)	0.00	0.00				Surface		
721.79	32.81	720.50	688.98	463261.36	MAS = 10.00 (m)	26.00	26.00				WRP		
720.36	32.81	701.76	687.55	41.54	MAS = 10.00 (m)	2830.00	2829.32				MinPts		
720.38	32.81	701.75	687.58	41.44	MAS = 10.00 (m)	2840.00	2839.28				MINPT-O-EOU		
863.77	37.71	838.20	826.06	35.52	OSF1.50	4508.40	4500.00				MinPt-O-SF		
953.09	98.24	887.17	854.85	14.73	OSF1.50	11790.00	11781.18				MINPT-O-EOU		
953.10	98.26	887.17	854.84	14.72	OSF1.50	11794.51	11785.68				MinPts		
954.87	90.63	894.02	864.24	16.01	OSF1.50	12880.00	12300.00				MinPt-O-ADP		
954.75	90.49	894.00	864.26	16.03	OSF1.50	12930.00	12300.00				MINPT-O-EOU		
954.67	90.26	894.07	864.41	16.07	OSF1.50	13040.00	12300.00				MinPt-CtCt		
956.02	287.82	763.71	668.20	5.00	OSF1.50	21550.00	12300.00		OSF<5.00		Enter Alert		
956.18	313.91	746.47	642.26	4.58	OSF1.50	22392.06	12300.00				MinPts		

Cimarex Red Hills 32-5 Fed Com #127H Rev3 RM 19Dec19 (Def Plan) Warning Alert

1795.82	32.81	1794.53	1763.01	N/A	MAS = 10.00 (m)	0.00	0.00				Surface		
1795.76	32.81	1794.47	1762.96	348219.63	MAS = 10.00 (m)	10.00	10.00				MinPt-O-SF		
1795.76	32.81	1794.47	1762.95	N/A	MAS = 10.00 (m)	26.00	26.00				WRP		
1795.76	32.81	1779.20	1762.95	117.50	MAS = 10.00 (m)	2500.00	2500.00				MinPts		
1795.99	32.81	1778.94	1763.19	113.80	MAS = 10.00 (m)	2580.00	2579.99				MINPT-O-EOU		
956.60	95.14	892.32	861.46	15.46	OSF1.50	11800.00	11791.18				MinPt-O-SF		
892.10	92.39	829.58	799.71	14.88	OSF1.50	12310.00	12207.83				MinPt-O-SF		
889.15	91.86	826.99	797.29	14.92	OSF1.50	12390.00	12240.41				MinPts		
889.13	91.79	827.03	797.35	14.93	OSF1.50	12400.00	12243.62				MinPt-CtCt		
910.79	275.35	726.36	635.44	4.99	OSF1.50	20840.00	12300.00		OSF<5.00		Enter Alert		
910.08	323.30	693.68	586.78	4.24	OSF1.50	22392.06	12300.00				MinPts		

Cimarex Red Hills Unit #2H (Offset) Gas Inc Only 0ft-15005ft (Def Survey) Warning Alert

6084.30	32.81	6082.32	6051.49	N/A	MAS = 10.00 (m)	0.00	0.00				Surface		
6084.11	32.81	6082.10	6051.30	252671.68	MAS = 10.00 (m)	26.00	26.00				MinPt-O-SF		

Offset Trajectory	Separation			Allow	Sep. Fact.	Controlling Rule	Reference Trajectory		Risk Level			Alert	Status
	Ct-Ct (ft)	MAS (ft)	EOU (ft)	Dev. (ft)			MD (ft)	TVD (ft)	Alert	Minor	Major		
6084.02	32.81	6081.96	6051.21	74763.91	MAS = 10.00 (m)	60.00	60.00					MinPts	
6084.19	32.81	6065.83	6051.38	371.35	MAS = 10.00 (m)	600.00	600.00					MinPts	
6083.66	36.84	6058.44	6046.82	261.70	OSF1.50	800.00	800.00					MinPt-CiCt	
6079.75	66.30	6034.89	6013.46	141.75	OSF1.50	1340.00	1340.00					MinPt-CiCt	
6077.67	110.72	6003.20	5966.95	83.81	OSF1.50	2190.00	2190.00					MinPt-CiCt	
6080.12	117.43	6001.17	5962.69	78.97	OSF1.50	2430.00	2430.00					MINPT-O-EOU	
6081.92	119.73	6001.44	5962.19	77.45	OSF1.50	2510.00	2510.00					MinPt-O-ADP	
6085.72	140.59	5991.33	5945.13	65.84	OSF1.50	2640.00	2639.94					MINPT-O-EOU	
6086.23	141.21	5991.43	5945.02	65.55	OSF1.50	2660.00	2659.92					MinPt-O-ADP	
6131.96	168.55	6018.93	5963.41	55.20	OSF1.50	3210.00	3207.58					MinPts	
6155.03	180.74	6033.88	5974.29	51.63	OSF1.50	3470.00	3466.38					MinPts	
6193.86	205.41	6056.26	5988.45	45.66	OSF1.50	3870.00	3864.54					MinPts	
6224.81	222.22	6076.01	6002.59	42.38	OSF1.50	4220.00	4212.93					MinPts	
6261.22	245.60	6096.83	6015.62	38.54	OSF1.50	4690.00	4681.19					MinPts	
6261.81	246.64	6096.73	6015.17	38.38	OSF1.50	4800.00	4791.18					MinPt-CiCt	
6261.97	247.17	6096.54	6014.81	38.30	OSF1.50	4850.00	4841.18					MINPT-O-EOU	
6261.16	255.77	6089.99	6005.39	36.99	OSF1.50	4980.00	4971.18					MinPt-CiCt	
6261.20	255.87	6089.96	6005.33	36.98	OSF1.50	5000.00	4991.18					MINPT-O-EOU	
6258.97	267.01	6080.30	5991.95	35.41	OSF1.50	5190.00	5181.18					MinPt-CiCt	
6259.10	267.46	6080.14	5991.64	35.35	OSF1.50	5240.00	5231.18					MINPT-O-EOU	
6259.35	267.74	6080.19	5991.61	35.32	OSF1.50	5270.00	5261.18					MinPt-O-ADP	
6257.02	284.12	6066.94	5972.89	33.25	OSF1.50	5520.00	5511.18					MinPt-CiCt	
6257.54	360.86	6016.30	5896.67	26.15	OSF1.50	7000.00	6991.18					MinPt-CiCt	
6265.39	384.65	6008.30	5880.74	24.55	OSF1.50	7600.00	7591.18					MINPT-O-EOU	
6257.28	433.81	5967.42	5823.47	21.73	OSF1.50	8390.00	8381.18					MinPt-CiCt	
6260.40	444.03	5963.72	5816.37	21.24	OSF1.50	8700.00	8691.18					MINPT-O-EOU	
6263.97	448.32	5964.43	5815.65	21.04	OSF1.50	8840.00	8831.18					MinPt-O-ADP	
6261.52	473.68	5945.07	5787.83	19.91	OSF1.50	9150.00	9141.18					MinPt-CiCt	
6262.21	475.55	5944.52	5786.66	19.83	OSF1.50	9260.00	9251.18					MINPT-O-EOU	
6263.14	476.65	5944.72	5786.49	19.79	OSF1.50	9320.00	9311.18					MinPt-O-ADP	
6266.41	515.34	5922.19	5751.07	18.30	OSF1.50	9970.00	9961.18					MinPt-CiCt	
2115.11	642.01	1684.49	1473.10	4.98	OSF1.50	16580.00	12300.00	OSF<5.00				Enter Alert	
1355.77	645.85	924.54	709.92	3.15	OSF1.50	18200.00	12300.00					MinPt-CiCt	
1355.78	645.89	924.53	709.89	3.15	OSF1.50	18210.00	12300.00					MinPts	
1355.87	645.94	924.58	709.93	3.15	OSF1.50	18220.00	12300.00					MinPt-O-SF	
2140.23	644.69	1709.78	1495.54	4.99	OSF1.50	19860.00	12300.00	OSF>5.00				Exit Alert	
4401.78	642.82	3972.57	3758.96	10.30	OSF1.50	22392.06	12300.00					TD	

Neil H Wills Continental State #1 (Offset) Plugged Blind Off-5020ft (Def Survey)													Warning Alert
3781.43	32.81	3779.45	3748.62	N/A	MAS = 10.00 (m)	0.00	0.00					Surface	
3781.20	32.81	3779.20	3748.39	156604.50	MAS = 10.00 (m)	26.00	26.00					MinPt-O-SF	
3781.15	757.94	3275.19	3023.21	7.50	OSF1.50	2500.00	2500.00					MinPt-CiCt	
3854.10	1158.74	3080.95	2695.36	5.00	OSF1.50	3780.00	3774.95	OSF<5.00				Enter Alert	
3910.54	1567.71	2864.74	2342.82	3.74	OSF1.50	5090.00	5081.18					MinPts	
4519.17	1357.17	3613.73	3162.00	5.00	OSF1.50	7350.00	7341.18	OSF>5.00				Exit Alert	
7596.88	491.74	7268.40	7105.14	23.26	OSF1.50	15220.00	12300.00					MinPt-CiCt	
7596.92	491.86	7268.36	7105.06	23.26	OSF1.50	15250.00	12300.00					MINPT-O-EOU	
7597.16	492.13	7268.41	7105.03	23.24	OSF1.50	15290.00	12300.00					MinPt-O-ADP	
10192.54	1120.84	9444.65	9071.69	13.66	OSF1.50	22020.00	12300.00					MinPt-O-SF	
10444.27	1147.16	9678.84	9297.11	13.68	OSF1.50	22392.06	12300.00					TD	

Offset Trajectory	Separation			Allow Dev. (ft)	Sep. Fact.	Controlling Rule	Reference Trajectory		Risk Level			Alert	Status
	Ct-Ct (ft)	MAS (ft)	EOU (ft)				MD (ft)	TVD (ft)	Alert	Minor	Major		
Cimarex Red Hills 32-5 Fed Com #169H Rev0 RM 04Sept19 (Non-Def Plan)													
												Pass	
	741.71	32.81	740.43	708.90	N/A	MAS = 10.00 (m)	0.00	0.00				Surface	
	741.71	32.81	740.42	708.90	416562.67	MAS = 10.00 (m)	26.00	26.00				WRP	
	741.71	32.81	725.80	708.90	50.62	MAS = 10.00 (m)	2390.00	2390.00				MinPts	
	741.77	32.81	725.71	708.96	50.12	MAS = 10.00 (m)	2420.00	2420.00				MINPT-O-EOU	
	974.13	37.33	948.82	936.81	40.49	OSF1.50	4508.40	4500.00				MinPt-O-SF	
	1359.29	62.12	1317.44	1297.17	33.48	OSF1.50	7610.00	7601.18				MinPt-O-SF	
	1367.76	93.48	1305.01	1274.28	22.23	OSF1.50	11794.51	11785.68				MinPts	
	1379.72	86.99	1321.29	1292.73	24.13	OSF1.50	12870.00	12300.00				MinPt-O-ADP	
	1379.58	86.83	1321.27	1292.75	24.17	OSF1.50	12970.00	12300.00				MINPT-O-EOU	
	1379.57	86.79	1321.27	1292.77	24.18	OSF1.50	13010.00	12300.00				MINPT-O-EOU	
	1379.56	86.79	1321.27	1292.77	24.18	OSF1.50	13040.00	12300.00				MinPt-CtCt	
	1380.91	316.80	1169.29	1064.12	6.56	OSF1.50	22392.06	12300.00				MinPts	
Cimarex Red Hills Unit #4 (Offset) Gas Gyro + Blind Off- 17675ft (Def Survey)													
												Pass	
	4547.34	32.81	4545.36	4514.53	N/A	MAS = 10.00 (m)	0.00	0.00				Surface	
	4547.14	32.81	4545.14	4514.33	205998.17	MAS = 10.00 (m)	26.00	26.00				MinPt-O-SF	
	4546.78	32.81	4543.28	4513.98	2973.46	MAS = 10.00 (m)	390.00	390.00				MinPts	
	4548.06	32.81	4535.15	4515.25	416.06	MAS = 10.00 (m)	2510.00	2510.00				MinPts	
	4548.09	32.81	4535.14	4515.28	414.53	MAS = 10.00 (m)	2520.00	2520.00				MINPT-O-EOU	
	4717.40	33.12	4694.66	4684.28	227.17	OSF1.50	4508.40	4500.00				MinPt-O-SF	
	4778.32	68.59	4731.93	4709.73	107.56	OSF1.50	10430.00	10421.18				MinPt-CtCt	
	4779.39	71.29	4731.21	4708.10	103.40	OSF1.50	10820.00	10811.18				MINPT-O-EOU	
	4780.89	73.02	4731.55	4707.87	100.90	OSF1.50	11050.00	11041.18				MinPt-O-ADP	
	4782.84	77.69	4730.38	4705.14	94.72	OSF1.50	11720.00	11711.18				MinPt-CtCt	
	4782.95	78.02	4730.28	4704.93	94.32	OSF1.50	11770.00	11761.18				MINPT-O-EOU	
	4783.02	78.18	4730.24	4704.84	94.12	OSF1.50	11800.00	11791.18				MinPt-O-SF	
	843.40	114.77	766.23	728.63	11.19	OSF1.50	16780.00	12300.00				MinPts	
	843.50	114.90	766.24	728.60	11.18	OSF1.50	16790.00	12300.00				MinPt-O-ADP	
	845.08	115.33	767.54	729.76	11.16	OSF1.50	16830.00	12300.00				MinPt-O-SF	
	5677.84	80.96	5623.21	5596.88	107.80	OSF1.50	22392.06	12300.00				TD	
Cimarex Red Hills 32-5 Fed Com #130H Rev3 RM 19Dec19 (Def Plan)													
												Pass	
	1815.80	32.81	1814.52	1782.99	N/A	MAS = 10.00 (m)	0.00	0.00				Surface	
	1815.74	32.81	1814.45	1782.94	336942.32	MAS = 10.00 (m)	10.00	10.00				MinPt-O-SF	
	1815.74	32.81	1814.45	1782.93	N/A	MAS = 10.00 (m)	26.00	26.00				WRP	
	1815.74	32.81	1799.18	1782.93	118.82	MAS = 10.00 (m)	2500.00	2500.00				MinPts	
	1815.97	32.81	1798.92	1783.16	115.07	MAS = 10.00 (m)	2580.00	2579.99				MINPT-O-EOU	
	1701.22	38.62	1675.02	1662.60	68.48	OSF1.50	4600.00	4591.30				MinPt-O-SF	
	1487.51	95.38	1423.35	1392.13	23.80	OSF1.50	11800.00	11791.18				MinPt-O-SF	
	1432.27	89.36	1372.07	1342.91	24.52	OSF1.50	12660.00	12293.01				MinPt-O-ADP	
	1432.15	89.22	1372.06	1342.94	24.56	OSF1.50	12690.00	12295.66				MINPT-O-EOU	
	1432.00	88.75	1372.22	1343.25	24.69	OSF1.50	12800.00	12300.00				MinPt-CtCt	
	1432.49	315.17	1221.76	1117.32	6.85	OSF1.50	22392.06	12300.00				MinPts	
Cimarex Red Hills 32-5 Fed Com #199H Rev0 RM 04Sept19 (Non-Def Plan)													
												Pass	
	2577.77	32.81	2575.79	2544.96	N/A	MAS = 10.00 (m)	0.00	0.00				Surface	
	2577.71	32.81	2575.73	2544.90	396101.22	MAS = 10.00 (m)	10.00	10.00				MinPt-O-SF	

Offset Trajectory	Separation			Allow Dev. (ft)	Sep. Fact.	Controlling Rule	Reference Trajectory		Risk Level			Alert	Status
	Ct-Ct (ft)	MAS (ft)	EOU (ft)				MD (ft)	TVD (ft)	Alert	Minor	Major		
2577.69	32.81	2575.72	2544.89	N/A	MAS = 10.00 (m)	26.00	26.00					WRP	
1799.82	95.24	1735.30	1704.58	29.24	OSF1.50	11794.51	11785.68					MinPt-CtCt	
1799.83	95.26	1735.29	1704.57	29.24	OSF1.50	11800.00	11791.18					MinPts	
1804.53	88.69	1744.39	1715.84	31.55	OSF1.50	12850.00	12300.00					MinPt-O-ADP	
1804.48	88.63	1744.38	1715.85	31.57	OSF1.50	12880.00	12300.00					MINPT-O-EOU	
1804.44	88.56	1744.38	1715.88	31.59	OSF1.50	12920.00	12300.00					MINPT-O-EOU	
1804.41	88.48	1744.41	1715.93	31.62	OSF1.50	12990.00	12300.00					MinPt-CtCt	
1804.42	88.47	1744.43	1715.95	31.63	OSF1.50	13070.00	12300.00					MinPt-O-SF	
1805.46	317.44	1592.82	1488.02	8.60	OSF1.50	22392.06	12300.00					MinPts	

Cimarex Red Hills 32-5 Fed Com #131H Rev2 RM 19Dec19 (Def Plan)

1835.79	32.81	1834.51	1802.99	N/A	MAS = 10.00 (m)	0.00	0.00					Surface	
1835.74	32.81	1834.44	1802.93	338362.86	MAS = 10.00 (m)	10.00	10.00					MinPt-O-SF	
1835.73	32.81	1834.44	1802.92	N/A	MAS = 10.00 (m)	26.00	26.00					WRP	
1835.73	32.81	1819.17	1802.92	120.13	MAS = 10.00 (m)	2500.00	2500.00					MinPts	
1835.78	32.81	1819.07	1802.97	118.92	MAS = 10.00 (m)	2530.00	2530.00					MINPT-O-EOU	
2016.50	37.41	1991.13	1979.09	83.69	OSF1.50	4600.00	4591.30					MinPt-O-SF	
2024.80	99.86	1957.79	1924.93	30.79	OSF1.50	11800.00	11791.18					MinPt-O-SF	
2008.24	99.57	1941.43	1908.67	30.63	OSF1.50	12030.00	12011.74					MinPt-O-SF	
1974.98	96.57	1910.17	1878.41	31.07	OSF1.50	12390.00	12240.41					MinPt-O-ADP	
1974.92	96.49	1910.16	1878.43	31.10	OSF1.50	12400.00	12243.62					MINPT-O-EOU	
1974.91	96.41	1910.21	1878.51	31.12	OSF1.50	12410.00	12246.63					MinPt-CtCt	
1984.41	312.90	1775.37	1671.50	9.55	OSF1.50	22390.00	12300.00					MinPt-CtCt	
1984.41	312.94	1775.35	1671.47	9.54	OSF1.50	22392.06	12300.00					MinPts	

Cimarex Red Hills 32-5 Fed Com #128H Rev3 RM 19Nov19 (Def Plan)

1874.78	32.81	1873.50	1841.97	N/A	MAS = 10.00 (m)	0.00	0.00					Surface	
1874.74	32.81	1873.45	1841.93	693629.99	MAS = 10.00 (m)	10.00	10.00					MinPts	
1874.74	32.81	1873.45	1841.93	N/A	MAS = 10.00 (m)	26.00	26.00					WRP	
1874.74	32.81	1858.18	1841.93	122.65	MAS = 10.00 (m)	2500.00	2500.00					MinPts	
1875.26	32.81	1857.69	1842.46	115.04	MAS = 10.00 (m)	2660.00	2659.92					MINPT-O-EOU	
1899.10	41.30	1871.14	1857.80	71.15	OSF1.50	4600.00	4591.30					MinPt-O-SF	
1900.30	94.06	1837.17	1806.24	30.70	OSF1.50	10420.00	10411.18					MinPts	
1900.68	94.10	1837.52	1806.58	30.70	OSF1.50	10530.00	10521.18					MinPt-O-SF	
2324.12	307.36	2118.79	2016.76	11.38	OSF1.50	22160.00	12300.00					MinPt-CtCt	
2324.31	307.99	2118.56	2016.32	11.36	OSF1.50	22190.00	12300.00					MINPT-O-EOU	
2324.65	308.37	2118.64	2016.27	11.35	OSF1.50	22210.00	12300.00					MinPt-O-ADP	
2332.66	310.64	2125.14	2022.02	11.30	OSF1.50	22360.00	12300.00					MinPt-O-SF	
2335.62	310.97	2127.88	2024.65	11.31	OSF1.50	22392.06	12300.00					TD	

Cimarex Red Hills 32-5 Fed Com #129H Rev2 RM 15Nov19 (Def Plan)

1894.78	32.81	1893.50	1861.97	N/A	MAS = 10.00 (m)	0.00	0.00					Surface	
1894.74	32.81	1893.45	1861.93	684897.32	MAS = 10.00 (m)	10.00	10.00					MinPts	
1894.74	32.81	1893.45	1861.93	N/A	MAS = 10.00 (m)	26.00	26.00					WRP	
1894.74	32.81	1878.18	1861.93	123.97	MAS = 10.00 (m)	2500.00	2500.00					MinPts	
1895.05	32.81	1877.87	1862.24	119.11	MAS = 10.00 (m)	2600.00	2599.98					MINPT-O-EOU	
1937.01	43.45	1907.61	1893.55	68.86	OSF1.50	4600.00	4591.30					MinPt-O-SF	
1938.60	90.69	1877.71	1847.91	32.50	OSF1.50	9820.00	9811.18					MinPt-O-SF	
1935.07	90.56	1874.26	1844.51	32.49	OSF1.50	10100.00	10091.18					MinPts	
1937.01	90.79	1876.05	1846.22	32.44	OSF1.50	10200.00	10191.18					MinPt-O-SF	

Offset Trajectory	Separation			Allow Dev. (ft)	Sep. Fact.	Controlling Rule	Reference Trajectory		Risk Level			Alert	Status
	Ct-Ct (ft)	MAS (ft)	EOU (ft)				MD (ft)	TVD (ft)	Alert	Minor	Major		
2725.01	306.01	2520.58	2419.00	13.41	OSF1.50	22160.00	12300.00				MinPt-CtCt		
2725.29	306.83	2520.31	2418.46	13.37	OSF1.50	22200.00	12300.00				MINPT-O-EOU		
2725.46	307.02	2520.34	2418.43	13.37	OSF1.50	22210.00	12300.00				MinPt-O-ADP		
2734.82	309.94	2527.77	2424.88	13.28	OSF1.50	22392.06	12300.00				MinPt-O-SF		

Cimarex Red Hills 32-5 Fed Com #198H Rev0 RM 04Sept19 (Non-Def Plan)

Pass												
2597.74	32.81	2595.76	2564.93	N/A	MAS = 10.00 (m)	0.00	0.00				Surface	
2597.68	32.81	2595.70	2564.88	410824.08	MAS = 10.00 (m)	10.00	10.00				MinPt-O-SF	
2597.67	32.81	2595.69	2564.86	N/A	MAS = 10.00 (m)	26.00	26.00				WRP	
2383.52	39.59	2356.40	2343.93	95.45	OSF1.50	4600.00	4591.30				MinPt-O-SF	
2219.00	97.11	2153.46	2121.90	35.12	OSF1.50	11794.51	11785.68				MinPt-CtCt	
2219.00	97.13	2153.44	2121.88	35.11	OSF1.50	11800.00	11791.18				MinPts	
2229.80	90.19	2168.88	2139.61	38.04	OSF1.50	12740.00	12298.68				MinPt-O-ADP	
2229.51	89.83	2168.83	2139.67	38.19	OSF1.50	12820.00	12300.00				MINPT-O-EOU	
2229.34	89.32	2169.01	2140.03	38.42	OSF1.50	12990.00	12300.00				MinPt-CtCt	
2230.38	313.92	2020.32	1916.46	10.73	OSF1.50	22392.06	12300.00				MinPts	

Cimarex Red Hills SWD #1 (Offset) Inc Only 0ft-19000ft (Def Survey)


Pass												
6940.62	32.81	6938.64	6907.81	N/A	MAS = 10.00 (m)	0.00	0.00				Surface	
6940.38	32.81	6938.37	6907.58	217812.52	MAS = 10.00 (m)	26.00	26.00				MinPt-O-SF	
6940.21	32.81	6938.09	6907.41	47688.11	MAS = 10.00 (m)	80.00	80.00				MinPts	
6943.47	87.23	6884.66	6856.25	122.14	OSF1.50	1750.00	1750.00				MinPt-CtCt	
6956.51	140.40	6862.25	6816.11	75.36	OSF1.50	2690.00	2689.86				MINPT-O-EOU	
6970.76	156.51	6865.76	6814.25	67.64	OSF1.50	2920.00	2918.91				MinPt-O-ADP	
7089.83	251.15	6921.74	6838.69	42.67	OSF1.50	4420.00	4412.00				MINPT-O-EOU	
7083.48	267.94	6904.19	6815.54	39.94	OSF1.50	5170.00	5161.18				MinPt-CtCt	
7084.54	271.16	6903.11	6813.39	39.47	OSF1.50	5330.00	5321.18				MINPT-O-EOU	
7085.71	272.55	6903.36	6813.17	39.27	OSF1.50	5400.00	5391.18				MinPt-O-ADP	
7091.91	283.05	6902.55	6808.86	37.84	OSF1.50	5660.00	5651.18				MINPT-O-EOU	
7092.43	348.92	6859.15	6743.51	30.66	OSF1.50	6770.00	6761.18				MinPt-CtCt	
7096.08	433.93	6806.14	6662.15	24.64	OSF1.50	8410.00	8401.18				MinPt-CtCt	
7094.60	516.29	6749.75	6578.31	20.69	OSF1.50	9990.00	9981.18				MinPt-CtCt	
7085.21	600.56	6684.18	6484.65	17.75	OSF1.50	11590.00	11581.18				MinPt-CtCt	
7086.55	604.68	6682.78	6481.88	17.63	OSF1.50	11770.00	11761.18				MINPT-O-EOU	
2559.83	650.82	2125.28	1909.00	5.91	OSF1.50	18710.00	12300.00				MinPt-CtCt	
2559.83	650.87	2125.26	1908.96	5.91	OSF1.50	18720.00	12300.00				MINPT-O-EOU	
2559.88	650.92	2125.27	1908.96	5.91	OSF1.50	18730.00	12300.00				MinPt-O-ADP	
2560.25	651.07	2125.55	1909.18	5.91	OSF1.50	18760.00	12300.00				MinPt-O-SF	
4481.70	651.45	4046.74	3830.25	10.35	OSF1.50	22392.06	12300.00				TD	

Cimarex Red Hills 32-5 Fed Com #197H Rev0 RM 04Sept19 (Non-Def Plan)

Pass												
2617.69	32.81	2615.71	2584.88	N/A	MAS = 10.00 (m)	0.00	0.00				Surface	
2617.64	32.81	2615.66	2584.83	490167.36	MAS = 10.00 (m)	10.00	10.00				MinPt-O-SF	
2617.63	32.81	2615.65	2584.82	N/A	MAS = 10.00 (m)	26.00	26.00				WRP	
2600.11	110.02	2526.10	2490.09	36.07	OSF1.50	11794.51	11785.68				MinPt-CtCt	
2600.11	110.03	2526.10	2490.09	36.07	OSF1.50	11800.00	11791.18				MinPts	
2654.63	103.09	2585.25	2551.54	39.35	OSF1.50	12760.00	12299.40				MINPT-O-EOU	
2654.29	101.97	2585.65	2552.32	39.79	OSF1.50	13000.00	12300.00				MinPt-CtCt	
2655.32	312.31	2446.46	2343.01	12.83	OSF1.50	22392.06	12300.00				MinPts	

Offset Trajectory	Separation			Allow Dev. (ft)	Sep. Fact.	Controlling Rule	Reference Trajectory		Risk Level			Alert	Status
	Ct-Ct (ft)	MAS (ft)	EOU (ft)				MD (ft)	TVD (ft)	Alert	Minor	Major		
Rector Oil Maechtel Permit #1 (Offset) Plugged Oil Blind Off- 5006ft (Def Survey)												Pass	
10071.48	32.81	10070.19	10038.67	N/A		MAS = 10.00 (m)	0.00	0.00				Surface	
10071.15	32.81	10069.81	10038.34	194086.58		MAS = 10.00 (m)	26.00	26.00				MinPt-O-SF	
10070.49	727.39	9585.13	9343.09	20.80		OSF1.50	2500.00	2500.00				MinPt-CtCt	
10262.99	1559.49	9222.90	8703.50	9.88		OSF1.50	5160.00	5151.18				MinPts	
10089.18	1101.75	9354.25	8987.43	13.75		OSF1.50	15300.00	12300.00				MinPt-O-SF	
7412.83	464.66	7102.63	6948.17	23.99		OSF1.50	22140.00	12300.00				MinPt-CtCt	
7413.45	466.19	7102.22	6947.26	23.91		OSF1.50	22240.00	12300.00				MINPT-O-EOU	
7416.58	469.80	7102.95	6946.78	23.74		OSF1.50	22380.00	12300.00				MinPt-O-ADP	
7416.98	470.19	7103.09	6946.78	23.72		OSF1.50	22392.06	12300.00				MinPt-O-SF	

Co-Flex Hose
Red Hills 32-5 Fed Com 158H
Cimarex Energy Co.
32-25S-33E
Lea Co., NM



Co-Flex Hose Hydrostatic Test
 Red Hills 32-5 Fed Com 158H

Cimarex Energy Co.
 32-25S-33E
 Lea Co., NM



Midwest Hose & Specialty, Inc.

INTERNAL HYDROSTATIC TEST REPORT			
Customer:		P.O. Number:	
Oderco Inc		odyd-271	
HOSE SPECIFICATIONS			
Type:	Stainless Steel Armor Choke & Kill Hose		Hose Length: 45'ft.
I.D.	4 INCHES	O.D.	9 INCHES
WORKING PRESSURE	TEST PRESSURE	BURST PRESSURE	
10,000 PSI	15,000 PSI	0 PSI	
COUPLINGS			
Stem Part No.		Ferrule No.	
OKC OKC		OKC OKC	
Type of Coupling:			
Swage-It			
PROCEDURE			
<i>Hose assembly pressure tested with water at ambient temperature.</i>			
TIME HELD AT TEST PRESSURE		ACTUAL BURST PRESSURE:	
15 MIN.		0 PSI	
Hose Assembly Serial Number:		Hose Serial Number:	
79793		OKC	
Comments:			
Date:	Tested:	Approved:	
3/8/2011	<i>A. Joins</i>	<i>[Signature]</i>	

March 3, 2011

Co-Flex Hose Hydrostatic Test
Red Hills 32-5 Fed Com 158H
Cimarex Energy Co.
32-25S-33E
Lea Co., NM


Internal Hydrostatic Test Graph

Customer: Houston Pick Ticket #: 94260



Midwest Hose
& Specialty, Inc.

Hose Specifications		Verification	
Hose Type C & K	Length 45'	Type of Fittings 4 1/16 10K	Coupling Method Swage
I.D. 4"	O.D. 6.09"	Die Size 6.38"	Final O.D. 6.25"
Working Pressure 10000 PSI	Burst Pressure Standard Safety Multiplier Applies	Hose Serial # 5544	Hose Assembly Serial # 79793




Test Pressure 15000 PSI Time Held at Test Pressure 11 Minutes Actual Burst Pressure Peak Pressure 15483 PSI

Comments: Hose assembly pressure tested with water at ambient temperature.

Tested By: Zac McConnell

Approved By: Kim Thomas

Co-Flex Hose
Red Hills 32-5 Fed Com 158H
Cimarex Energy Co.
32-25S-33E
Lea Co., NM



Midwest Hose & Specialty, Inc.

Certificate of Conformity

Customer:	DEM	PO	ODYD-271
------------------	-----	-----------	----------

SPECIFICATIONS

Sales Order	79793	Dated:	3/8/2011
--------------------	-------	---------------	----------

We hereby certify that the material supplied for the referenced purchase order to be true according to the requirements of the purchase order and current industry standards

Supplier:
Midwest Hose & Specialty, Inc.
10640 Tanner Road
Houston, Texas 77041

Comments:	
Approved:	Date:
<i>Jamal Garcia</i>	3/8/2011



Co-Flex Hose
Red Hills 32-5 Fed Com 158H
 Cimarex Energy Co.
 32-25S-33E
 Lea Co., NM

Specification Sheet Choke & Kill Hose

The Midwest Hose & Specialty Choke & Kill hose is manufactured with only premium components. The reinforcement cables, inner liner and cover are made of the highest quality material to handle the tough drilling applications of today's industry. The end connections are available with API flanges, API male threads, hubs, hammer unions or other special fittings upon request. Hose assembly is manufactured to API 7K. This assembly is wrapped with fire resistant vermiculite coated fiberglass insulation, rated at 2000 degrees with stainless steel armor cover.

Working Pressure:	5,000 or 10,000 psi working pressure
Test Pressure:	10,000 or 15,000 psi test pressure
Reinforcement:	Multiple steel cables
Cover:	Stainless Steel Armor
Inner Tube:	Petroleum resistant, Abrasion resistant
End Fitting:	API flanges, API male threads, threaded or butt weld hammer unions, unbolt and other special connections
Maximum Length:	110 Feet
ID:	2-1/2", 3", 3-1/2", 4"
Operating Temperature:	-22 deg F to +180 deg F (-30 deg C to +82 deg C)

P.O. Box 96558 – 1421 S.E. 29th St. Oklahoma City, OK 73143 * (405) 670-6718 * Fax: (405) 670-6816

1. Geological Formations

TVD of target 12,300
MD at TD 22,392

Pilot Hole TD N/A
Deepest expected fresh water

Formation	Depth (TVD) from KB	Water/Mineral Bearing/Target Zone	Hazards
Rustler	934	Useable Water	
Top Salt	1349	N/A	
Base Salt	4651	N/A	
Lamar	4892	N/A	
Bell Canyon	4929	N/A	
Cherry Canyon	6001	Hydrocarbons	
Brushy Canyon	7537	Hydrocarbons	
Bone Spring	9039	Hydrocarbons	
Upper Avalon shale	9356	Hydrocarbons	
1st Bone Spring	10036	Hydrocarbons	
2nd Bone Spring	10223	Hydrocarbons	
3rd Bone Spring	11017	Hydrocarbons	
Wolfcamp	12125	Hydrocarbons	

2. Casing Program

Hole Size	Casing Depth From	Casing Depth To	Setting Depth TVD	Casing Size	Weight (lb/ft)	Grade	Conn.	SF Collapse	SF Burst	SF Tension
14 3/4	0	984	984	10-3/4"	40.50	J-55	BT&C	3.51	6.95	15.78
9 7/8	0	12426	12251	7-5/8"	29.70	L-80	BT&C	2.50	1.20	1.82
6 3/4	0	11700	11700	5-1/2"	20.00	L-80	LT&C	1.16	1.21	1.88
6 3/4	11700	22392	12300	5"	18.00	P-110	BT&C	1.68	1.70	53.70
BLM Minimum Safety Factor								1.125	1	1.6 Dry 1.8 Wet

TVD was used on all calculations.

All casing strings will be tested in accordance with Onshore Oil and Gas Order #2 III.B.1.h

Request Variance for 5-1/2" x 7-5/8" annular clearance. The portion that does not meet clearance will not be cemented

Cimarex Energy Co., Red Hills 32-5 Federal Com 158H

	Y or N
Is casing new? If used, attach certification as required in Onshore Order #1	Y
Does casing meet API specifications? If no, attach casing specification sheet.	Y
Is premium or uncommon casing planned? If yes attach casing specification sheet.	Y
Does the above casing design meet or exceed BLM's minimum standards? If not provide justification (loading assumptions, casing design criteria).	Y
Will the intermediate pipe be kept at a minimum 1/3 fluid filled to avoid approaching the collapse pressure rating of the casing?	Y
Is well located within Capitan Reef?	N
If yes, does production casing cement tie back a minimum of 50' above the Reef?	N
Is well within the designated 4 string boundary.	N
Is well located in SOPA but not in R-111-P?	N
If yes, are the first 2 strings cemented to surface and 3rd string cement tied back 500' into previous casing?	N
Is well located in R-111-P and SOPA?	N
If yes, are the first three strings cemented to surface?	N
Is 2nd string set 100' to 600' below the base of salt?	N
Is well located in high Cave/Karst?	N
If yes, are there two strings cemented to surface?	N
(For 2 string wells) If yes, is there a contingency casing if lost circulation occurs?	N
Is well located in critical Cave/Karst?	N
If yes, are there three strings cemented to surface?	N
Is AC Report included?	N

3. Cementing Program

Casing	# Sk	Wt. lb/gal	Yld ft ³ /sack	H ₂ O gal/sk	500# Comp. Strength (hours)	Slurry Description
Surface	332	13.50	1.72	9.15	15.5	Lead: Class C + Bentonite
	156	14.80	1.34	6.32	9.5	Tail: Class C + LCM
Intermediate Stage 1	579	10.30	3.64	22.18		Lead: Tuned Light + LCM
	198	14.80	1.36	6.57	9.5	Tail: Class C + Retarder
Intermediate Stage 2	793	12.90	1.88	9.65	12	Lead: 35:65 (Poz:C) + Salt + Bentonite
Production	852	14.20	1.30	5.86	14:30	Tail: 50:50 (Poz:H) + Salt + Bentonite + Fluid Loss + Dispersant + SMS

DV tool with possible annular casing packer as needed is proposed at a depth of +/- 4,892'.

Casing String	TOC	% Excess
Surface	0	42
Intermediate Stage 1	4892	47
Intermediate Stage 2	0	40
Production	12200	25

Cimarex request the ability to perform casing integrity tests after plug bump of cement job.

4. Pressure Control Equipment

	A variance is requested for the use of a diverter on the surface casing. See attached for schematic.
--	--

BOP installed and tested before drilling which hole?	Size	Min Required WP	Type		Tested To
9 7/8	13 5/8	5M	Annular	X	5M
			Blind Ram		
			Pipe Ram	X	
			Double Ram	X	
			Other		
6 3/4	13 5/8	10M	Annular	X	50% of working pressure
			Blind Ram		10M
			Pipe Ram	X	
			Double Ram	X	
			Other		

BOP/BOPE will be tested by an independent service company to 250 psi low and the high pressure indicated above per Onshore Order 2 requirements. The System may be upgraded to a higher pressure but still tested to the working pressure listed in the table above. If the system is upgraded all the components installed will be functional and tested.

Pipe rams will be operationally checked each 24 hour period. Blind rams will be operationally checked on each trip out of the hole. These checks will be noted on the daily tour sheets. Other accessories to the BOP equipment will include a Kelly cock and floor safety valve (inside BOP) and choke lines and choke manifold. See attached schematics.

X	Formation integrity test will be performed per Onshore Order #2. On Exploratory wells or on that portion of any well approved for a 5M BOPE system or greater, a pressure integrity test of each casing shoe shall be performed. Will be tested in accordance with Onshore Oil and Gas Order #2 III.B.1.i.
X	A variance is requested for the use of a flexible choke line from the BOP to Choke Manifold. See attached for specs and hydrostatic test chart.
N	Are anchors required by manufacturer?

5. Mud Program

Depth	Type	Weight (ppg)	Viscosity	Water Loss
0' to 984'	FW Spud Mud	8.30 - 8.80	30-32	N/C
984' to 12426'	Brine Diesel Emulsion	8.50 - 9.00	30-35	N/C
12426' to 22392'	OBM	12.00 - 12.50	50-70	N/C

Sufficient mud materials to maintain mud properties and meet minimum lost circulation and weight increase requirements will be kept on location at all times. The Brine Emulsion is completely saturated brine fluid that ties diesel into itself to lower the weight of the fluid. The drilling fluid is completely salt saturated.

What will be used to monitor the loss or gain of fluid?	PVT/Pason/Visual Monitoring
---	-----------------------------

6. Logging and Testing Procedures

Logging, Coring and Testing	
X	Will run GR/CNL from TD to surface (horizontal well – vertical portion of hole). Stated logs run will be in the Completion Report and submitted to the BLM.
	No logs are planned based on well control or offset log information.
	Drill stem test?
	Coring?

Additional Logs Planned	Interval

7. Drilling Conditions

Condition	
BH Pressure at deepest TVD	7995 psi
Abnormal Temperature	No

Hydrogen Sulfide (H2S) monitors will be installed prior to drilling out the surface shoe. If H2S is detected in concentrations greater than 100 ppm, the operator will comply with the provisions of Onshore Oil and Gas Order #6. If Hydrogen Sulfide is encountered, measured values and formations will be provided to the BLM.

X	H2S is present
X	H2S plan is attached

8. Other Facets of Operation

9. Wellhead

A multi-bowl wellhead system will be utilized.

After running the 10-3/4" surface casing, a 13 5/8" BOP/BOPE system with a minimum working pressure of 10000 psi will be installed on the wellhead system and will be pressure tested to 250 psi low followed by a 10000 psi test. Annular will be tested to 50% of working pressure. The pressure test will be repeated at least every 30 days, as per Onshore Order No. 2.

The multi-bowl wellhead will be installed by vendor's representative. A copy of the installation instructions has been sent to the BLM field office.

The wellhead will be installed by a third-party welder while being monitored by the wellhead vendor representative.

All BOP equipment will be tested utilizing a conventional test plug. Not a cup or J-packer type.

A solid steel body pack-off will be utilized after running and cementing the intermediate casing. After installation the pack-off and lower flange will be pressure tested to 10000 psi.

All casing strings will be tested as per Onshore Order No.2 to atleast 0.22 psi/ft or 1,500 whichever is greater and not to exceed 70% of casing burst.

If well conditions dictate conventional slips will be set and BOPE will be tested to appropriate pressures based on permitted pressure requirements.




Red Hills 32-5 Fed Com 158H

CACTUS FOR SERVICE
WEARBUSHING
IN CASING HEAD &
CASING SPOOL

LEA CO., NM

Multi-bowl Wellhead Diagram



2. Casing Program

Hole Size	Casing Depth From	Casing Depth To	Setting Depth TVD	Casing Size	Weight (lb/ft)	Grade	Conn.	SF Collapse	SF Burst	SF Tension
14 3/4	0	984	984	10-3/4"	40.50	J-55	BT&C	3.51	6.95	15.78
9 7/8	0	12426	12251	7-5/8"	29.70	L-80	BT&C	2.50	1.20	1.82
6 3/4	0	11700	11700	5-1/2"	20.00	L-80	LT&C	1.16	1.21	1.88
6 3/4	11700	22392	12300	5"	18.00	P-110	BT&C	1.68	1.70	53.70
PLM Minimum Safety Factor								1.125	1	1.6 Dry 1.8 Wet



Cimarex 10M Well Control Plan

Version 1.0

BOPE Preventer Utilization

The table below displays all BHA components, drill pipe, casing, or open hole that could be present during a required shut in and the associated preventer component that would provide a barrier to flow. It is specific to the hole section that requires a 10M system. The mud system being utilized in the hole will always assumed to be the first barrier to flow. The below table, combined with the mud program, documents that two barriers to flow can be maintained at all times, independent of the rating of the annular preventer.

Drill String Element	OD	Preventer	RWP
4" Drillpipe	4"	Lower Ram 3 1/2" - 5 1/2" VBR* Upper Ram 3 1/2" - 5 1/2" VBR*	10M
4.5" Drillpipe	4.5"	Lower Ram 3 1/2" - 5 1/2" VBR* Upper Ram 3 1/2" - 5 1/2" VBR*	10M
4" HWDP Drillpipe	4"	Lower Ram 3 1/2" - 5 1/2" VBR* Upper Ram 3 1/2" - 5 1/2" VBR*	10M
4.5" HWDP Drillpipe	4.5"	Lower Ram 3 1/2" - 5 1/2" VBR* Upper Ram 3 1/2" - 5 1/2" VBR*	10M
Drill Collars (including non-magnetic)	4.75- 5.25"	Lower Ram 3 1/2" - 5 1/2" VBR* Upper Ram 3 1/2" - 5 1/2" VBR*	10M
Production Casing	5.5"	Lower Ram 3 1/2" - 5 1/2" VBR* Upper Ram 3 1/2" - 5 1/2" VBR*	10M
Production Casing	5"	Lower Ram 3 1/2" - 5 1/2" VBR* Upper Ram 3 1/2" - 5 1/2" VBR*	10M
Production Casing	4.5"	Lower Ram 3 1/2" - 5 1/2" VBR* Upper Ram 3 1/2" - 5 1/2" VBR*	10M
ALL	0-13 5/8"	Annular	5M
Open Hole		Blind Rams	10M

*VBR – Variable Bore Ram

Well Control Procedures

Proper well control response is highly specific to current well conditions and must be adapted based on environment as needed. The procedures below are given in "common" operating conditions to cover the basic and most necessary operations required during the wellbore construction. These include drilling ahead, tripping pipe, tripping BHA, running casing, and pipe out of the hole/open hole. In some of the procedures below, there will be a switch of control from the lesser RWP annular to the appropriate 10M RWP ram. The pressure at which this is done is variable based on overall well conditions that must be evaluated situationally. The pressure that control is switched may be equal to or less than the RWP but at no time will the pressure on the annular preventer exceed the RWP of the annular. The annular will be tested to 5,000 psi. This will be the RWP of the annular preventer.

Shutting In While Drilling

1. Sound alarm to alert crew
2. Space out drill string
3. Shut down pumps
4. Shut in uppermost BOPE preventer (typically the annular preventer) and open HCR.
5. Verify well is shut-in and flow has stopped
6. Notify supervisory personnel
7. Record data (SIDP, SICP, Pit Gain, and Time)
8. Hold pre-job safety meeting and discuss kill procedure

9. If pressure is anticipated to climb to the RWP of the annular preventer during kill procedure, swap control of the well to the upper pipe ram

Shutting In While Tripping

1. Sound alarm and alert crew
2. Install open, full open safety valve and close valve
3. Shut in uppermost BOPE preventer (typically the annular preventer) and open HCR.
4. Verify well is shut-in and flow has stopped
5. Notify supervisory personnel
6. Record data (SIDP, SICP, Pit Gain, and Time)
7. Hold pre-job safety meeting and discuss kill procedure
8. If pressure is anticipated to climb to the RWP of the annular preventer during kill procedure, swap control of the well to the upper pipe ram

Shutting In While Running Casing

1. Sound alarm and alert crew
2. Install circulating swedge. Close high pressure, low torque valves.
3. Shut in uppermost BOPE preventer (typically the annular preventer) and open HCR.
4. Verify well is shut-in and flow has stopped
5. Notify supervisory personnel
6. Record data (SIDP, SICP, Pit Gain, and Time)
7. Hold Pre-job safety meeting and discuss kill procedure
8. If pressure is anticipated to climb to the RWP of the annular preventer during kill procedure, swap control of the well to the upper pipe ram

Shutting in while out of hole

1. Sound alarm
2. Shut-in well: close blind rams
3. Verify well is shut-in and monitor pressures
4. Notify supervisory personnel
5. Record data (SIDP, SICP, Pit Gain, and Time)
6. Hold Pre-job safety meeting and discuss kill procedure

Shutting in prior to pulling BHA through stack

1. Prior to pulling last joint of drill pipe thru the stack space out and check flow. If flowing see steps below.
2. Sound alarm and alert crew
3. Install open, full open safety valve and close valve
4. Shut in upper pipe ram and open HCR.

5. Verify well is shut-in and flow has stopped
6. Notify supervisory personnel
7. Record data (SIDP, SICP, Pit Gain, and Time)
8. Hold pre-job safety meeting and discuss kill procedure

Shutting in while BHA is in the stack and ram preventer and combo immediately available

1. Sound alarm and alert crew
2. Stab Crossover and install open, full open safety valve and close valve
3. Space out drill string with upset just beneath the compatible pipe ram.
4. Shut in upper compatible pipe ram and open HCR.
5. Verify well is shut-in and flow has stopped
6. Notify supervisory personnel
7. Record data (SIDP, SICP, Pit Gain, and Time)
8. Hold pre-job safety meeting and discuss kill procedure

Shutting in while BHA is in the stack and no ram preventer or combo immediately available

1. Sound alarm and alert crew
2. If possible pick up high enough, to pull string clear and follow "Open Hole" scenario
3. If not possible to pick up high enough:
 1. Stab Crossover, make up one joint/stand of drill pipe, and install open, full open safety valve and close valve
4. Space out drill string with upset just beneath the compatible pipe ram.
5. Shut in upper compatible pipe ram and open HCR.
6. Verify well is shut-in and flow has stopped
7. Notify supervisory personnel
8. Record data (SIDP, SICP, Pit Gain, and Time)
9. Hold pre-job safety meeting and discuss kill procedure



SUPO Data Report

05/02/2021

U.S. Department of the Interior
BUREAU OF LAND MANAGEMENT

APD ID: 10400038355

Submission Date: 01/28/2019

Highlighted data reflects the most recent changes

Operator Name: CIMAREX ENERGY COMPANY

Well Name: RED HILLS 32-5 FEDERAL COM

Well Number: 158H

[Show Final Text](#)

Well Type: CONVENTIONAL GAS WELL

Well Work Type: Drill

Section 1 - Existing Roads

Will existing roads be used? YES

Existing Road Map:

Red_Hills_32_5_Fed_Com_E2W2_Pad_3_Existing_Access_20200914100018.pdf

Existing Road Purpose: ACCESS

Row(s) Exist? NO

ROW ID(s)

ID:

Do the existing roads need to be improved? NO

Existing Road Improvement Description:

Existing Road Improvement Attachment:

Section 2 - New or Reconstructed Access Roads

Will new roads be needed? NO

Section 3 - Location of Existing Wells

Existing Wells Map? YES

Attach Well map:

Red_Hills_32_5_Fed_Com_158H_One_Mile_Radius_existing_wells_20200122155622.pdf

Operator Name: CIMAREX ENERGY COMPANY

Well Name: RED HILLS 32-5 FEDERAL COM

Well Number: 158H

Section 4 - Location of Existing and/or Proposed Production Facilities

Submit or defer a Proposed Production Facilities plan? SUBMIT

Production Facilities description: 500' x 560' pad was staked with the BLM for construction and will use 4 Central Tank Batteries: Red Hills Unit 32 West BS CTB 1 , Red Hills Unit West WC CTB 2, Red Hills Unit East BS CTB 3, Red Hills Unit WC CTB 4 will be utilized for this project.

Production Facilities map:

Red_Hills_Unit_32_West_WC_2_CTB_Battery_Layout_20200109112322.pdf

Red_Hills_Unit_32_East_BS_3_CTB_Battery_Layout_20200109112308.pdf

Red_Hills_Unit_32_East_WC_4_CTB_Battery_Layout_20200109112313.pdf

Red_Hills_Unit_32_West_BS_1_CTB_Battery_Layout_20200109112318.pdf

Section 5 - Location and Types of Water Supply

Water Source Table

Water source type: MUNICIPAL

Water source use type: SURFACE CASING
INTERMEDIATE/PRODUCTION CASING

Source latitude: **Source longitude:**

Source datum:

Water source permit type: WATER RIGHT

Permit Number:

Water source transport method: TRUCKING

Source land ownership: STATE

Source transportation land ownership: STATE

Water source volume (barrels): 5000 **Source volume (acre-feet):** 0.6444655

Source volume (gal): 210000

Water source and transportation map:

Red_Hills_32_5_Fed_Com_E2W2_Pad_3_Drilling_Water_Routes_20200914100125.pdf

Water source comments:

New water well? NO

Operator Name: CIMAREX ENERGY COMPANY

Well Name: RED HILLS 32-5 FEDERAL COM

Well Number: 158H

New Water Well Info

Well latitude:

Well Longitude:

Well datum:

Well target aquifer:

Est. depth to top of aquifer(ft):

Est thickness of aquifer:

Aquifer comments:

Aquifer documentation:

Well depth (ft):

Well casing type:

Well casing outside diameter (in.):

Well casing inside diameter (in.):

New water well casing?

Used casing source:

Drilling method:

Drill material:

Grout material:

Grout depth:

Casing length (ft.):

Casing top depth (ft.):

Well Production type:

Completion Method:

Water well additional information:

State appropriation permit:

Additional information attachment:

Section 6 - Construction Materials

Using any construction materials: YES

Construction Materials description: Caliche will be obtained from the actual well site if available. If not available onsite caliche will be obtained for a pit located in Sec. 20-25S-33E Lea, NM.

Construction Materials source location attachment:

Section 7 - Methods for Handling Waste

Waste type: SEWAGE

Waste content description: Human Waste

Amount of waste: 300 gallons

Waste disposal frequency : Weekly

Safe containment description: Waste will be properly contined and disposed of properly at a state approved disopal facility.

Safe containmant attachment:

Waste disposal type: HAUL TO COMMERCIAL FACILITY Disposal location ownership: PRIVATE

Disposal type description:

Disposal location description: A licensed 3rd party contractor will be used to haul and dispose human waste to City of Toyah TX waste water facility.

Operator Name: CIMAREX ENERGY COMPANY

Well Name: RED HILLS 32-5 FEDERAL COM

Well Number: 158H

Waste type: GARBAGE

Waste content description: garbage & trash produced during drilling & completion operations

Amount of waste: 32500 pounds

Waste disposal frequency : Weekly

Safe containment description: N/A

Safe containmant attachment:

Waste disposal type: HAUL TO COMMERCIAL FACILITY **Disposal location ownership:** COMMERCIAL FACILITY

Disposal type description:

Disposal location description: Windmill Spraying Service hauls trash to Lea County Landfill

Waste type: DRILLING

Waste content description: Drilling Fluids, drill cuttings, water and other waste produced from the well during drilling operations.

Amount of waste: 15000 barrels

Waste disposal frequency : Weekly

Safe containment description: N/A

Safe containmant attachment:

Waste disposal type: HAUL TO COMMERCIAL FACILITY **Disposal location ownership:** COMMERCIAL FACILITY

Disposal type description:

Disposal location description: Haul to R360 commercial disposal

Reserve Pit

Reserve Pit being used? NO

Temporary disposal of produced water into reserve pit?

Reserve pit length (ft.) **Reserve pit width (ft.)**

Reserve pit depth (ft.) **Reserve pit volume (cu. yd.)**

Is at least 50% of the reserve pit in cut?

Reserve pit liner

Reserve pit liner specifications and installation description

Cuttings Area

Cuttings Area being used? NO

Are you storing cuttings on location? NO

Operator Name: CIMAREX ENERGY COMPANY

Well Name: RED HILLS 32-5 FEDERAL COM

Well Number: 158H

Description of cuttings location

Cuttings area length (ft.)

Cuttings area width (ft.)

Cuttings area depth (ft.)

Cuttings area volume (cu. yd.)

Is at least 50% of the cuttings area in cut?

WCuttings area liner

Cuttings area liner specifications and installation description

Section 8 - Ancillary Facilities

Are you requesting any Ancillary Facilities?: NO

Ancillary Facilities attachment:

Comments:

Section 9 - Well Site Layout

Well Site Layout Diagram:

Red_Hills_32_5_Fed_Com_158H_Wellsite_Layout_20200122160908.pdf

Comments:

Section 10 - Plans for Surface Reclamation

Type of disturbance: New Surface Disturbance

Multiple Well Pad Name: RED HILLS 32-5 FEDERAL COM

Multiple Well Pad Number: E2E2 PAD

Recontouring attachment:

Red_Hills_32_5_Fed_Com_E2W2_Pad_3_Interim_Reclaim_20200122160930.pdf

Drainage/Erosion control construction: To control and prevent potentially contaminated precipitation from leaving the pad site, a perimeter berm and settlement pond will be installed. Contaminated water will be removed from pond, stored in waste tanks, and disposed of at a state approved facility. Standing water or puddles will not be allowed. Drainage ditches would be established and maintained on the pad and along access roads to divert water away from operations. Natural drainage areas disturbed during construction would be re-contoured to near original condition prior to construction. Erosion Control Best Management Practices would be used where necessary and consist of seeding, fiber rolls, water bars, silt fences, and temporary diversion dikes. Areas disturbed during construction that are no longer needed for operations would be obliterated, re-contoured to near original condition prior to construction. Erosion Control Best Management Practices would be used where necessary and consist of seeding, fiber rolls, water bars, silt fences, and temporary diversion dikes. Areas disturbed during construction that are no longer needed for operations would be obliterated, re-contoured, and reclaimed to near original condition to re-establish natural drainage.

Drainage/Erosion control reclamation: All disturbed and re-contoured areas would be reseeded according to specifications. Approved seed mixtures would be certified weed free and consist of grasses, forbs, or shrubs similar to the surrounding area. Compacted soil areas may need to be obliterated and reclaimed to near natural conditions by re-contouring all slopes to facilitate and re-establish natural drainage.

Operator Name: CIMAREX ENERGY COMPANY

Well Name: RED HILLS 32-5 FEDERAL COM

Well Number: 158H

Well pad proposed disturbance (acres): 7.03	Well pad interim reclamation (acres): 3.45	Well pad long term disturbance (acres): 3.55
Road proposed disturbance (acres): 6.22	Road interim reclamation (acres): 0	Road long term disturbance (acres): 6.22
Powerline proposed disturbance (acres): 0	Powerline interim reclamation (acres): 0	Powerline long term disturbance (acres): 0
Pipeline proposed disturbance (acres): 8.13	Pipeline interim reclamation (acres): 8.13	Pipeline long term disturbance (acres): 0
Other proposed disturbance (acres): 25.13	Other interim reclamation (acres): 0	Other long term disturbance (acres): 25.13
Total proposed disturbance: 46.51	Total interim reclamation: 11.58	Total long term disturbance: 34.9

Disturbance Comments: Bulk line: 6009'. Access Road: 9041' Temp fresh water line: 17007'. We have been working on engineering solutions to reduce our footprint in the section to lower cost, disturbance, and our economic hurdle for other marginal benches within the section to increase our total mineral recovery. It turns out that simply changing our flowline / well approach and moving our separation to our drilling pads significantly reduces our foot print and cost. By placing our separation on our drill pads we can use 6-12 Group lines to gather the separated oil gas and water from the entire section instead of using up to 90 flowlines to move production to the tank batteries for separation. The Group line ability to gather the entire section helps us eliminate 2 batteries per section by simply utilizing the group line approach

Reconstruction method: After well plugging, all disturbed areas would be returned to the original contour or a contour that blends with the surrounding landform including roads unless the surface owner requests that they be left intact. In consultation with the surface owners it will be determined if any gravel or similar materials used to reinforce an area are to be removed, buried, or left in place during final reclamation. Salvaged topsoil, if any, would be re-spread evenly over the surfaces to be re-vegetated. As necessary, the soil surface would be prepared to provide a seedbed for re-establishment of desirable vegetation. Site preparation may include gouging, scarifying, dozer track-walking, mulching, or fertilizing. Reclamation, Re-vegetation, and Drainage: All disturbed and re-contoured areas would be reseeded using techniques outlined under Phase I and II of this plan or as specified by the land owner. Approved seed mixtures would be certified weed free and consist of grasses, forbs, or shrubs similar to the surrounding area. Compacted soil areas may need to be obliterated and reclaimed to near natural conditions by re-contouring all slopes to facilitate and re-establish natural drainage. **Topsoil redistribution:** Salvaged topsoil, if any, would be re-spread evenly over the surfaces to be re-vegetated.

Soil treatment: As necessary, the soil surface would be prepared to provide a seedbed for re-establishment of desirable vegetation. Site preparation may include gouging, scarifying, dozer track-walking, mulching or fertilizing.

Existing Vegetation at the well pad:

Existing Vegetation at the well pad attachment:

Existing Vegetation Community at the road:

Existing Vegetation Community at the road attachment:

Existing Vegetation Community at the pipeline:

Existing Vegetation Community at the pipeline attachment:

Existing Vegetation Community at other disturbances:

Existing Vegetation Community at other disturbances attachment:

Non native seed used? NO

Non native seed description:

Seedling transplant description:

Operator Name: CIMAREX ENERGY COMPANY

Well Name: RED HILLS 32-5 FEDERAL COM

Well Number: 158H

Will seedlings be transplanted for this project? NO

Seedling transplant description attachment:

Will seed be harvested for use in site reclamation? NO

Seed harvest description:

Seed harvest description attachment:

Seed Management

Seed Table

Seed Summary	
Seed Type	Pounds/Acre

Total pounds/Acre:

Seed reclamation attachment:

Operator Contact/Responsible Official Contact Info

First Name: Amithy

Last Name: Crawford

Phone: (432)620-1909

Email: acrawford@cimarex.com

Seedbed prep:

Seed BMP:

Seed method:

Existing invasive species? NO

Existing invasive species treatment description:

Existing invasive species treatment attachment:

Weed treatment plan description: na

Weed treatment plan attachment:

Monitoring plan description: na

Monitoring plan attachment:

Success standards: na

Pit closure description: na

Pit closure attachment:

Operator Name: CIMAREX ENERGY COMPANY

Well Name: RED HILLS 32-5 FEDERAL COM

Well Number: 158H

Section 11 - Surface Ownership

Disturbance type: WELL PAD

Describe:

Surface Owner: BUREAU OF LAND MANAGEMENT

Other surface owner description:

BIA Local Office:

BOR Local Office:

COE Local Office:

DOD Local Office:

NPS Local Office:

State Local Office:

Military Local Office:

USFWS Local Office:

Other Local Office:

USFS Region:

USFS Forest/Grassland:

USFS Ranger District:

Disturbance type: NEW ACCESS ROAD

Describe:

Surface Owner: BUREAU OF LAND MANAGEMENT

Other surface owner description:

BIA Local Office:

BOR Local Office:

COE Local Office:

DOD Local Office:

NPS Local Office:

State Local Office:

Military Local Office:

USFWS Local Office:

Other Local Office:

USFS Region:

Operator Name: CIMAREX ENERGY COMPANY

Well Name: RED HILLS 32-5 FEDERAL COM

Well Number: 158H

USFS Forest/Grassland:

USFS Ranger District:

Disturbance type: PIPELINE

Describe:

Surface Owner: BUREAU OF LAND MANAGEMENT

Other surface owner description:

BIA Local Office:

BOR Local Office:

COE Local Office:

DOD Local Office:

NPS Local Office:

State Local Office:

Military Local Office:

USFWS Local Office:

Other Local Office:

USFS Region:

USFS Forest/Grassland:

USFS Ranger District:

Section 12 - Other Information

Right of Way needed? YES

Use APD as ROW? YES

ROW Type(s): 281001 ROW - ROADS,287001 ROW – Water Facility,288100 ROW – O&G Pipeline,288101 ROW – O&G Facility Sites,289001 ROW- O&G Well Pad,Other

ROW Applications

SUPO Additional Information:

Operator Name: CIMAREX ENERGY COMPANY

Well Name: RED HILLS 32-5 FEDERAL COM

Well Number: 158H

Use a previously conducted onsite? YES

Previous Onsite information: Onsite with BLM(Jeff Robertson) and Cimarex Barry Hunt on April 17, 2018

Other SUPO Attachment

Red_Hills_32_5_Fed_Com_158H_Road_Description_20200122161558.pdf

Red_Hills_32_5_Fed_E2W2_Pad_3_Well_list_20200402173048.docx

Red_Hills_32_5_Fed_Com_158H_SUPO_20200403083104.pdf

CONFIDENTIAL



U.S. Department of the Interior
BUREAU OF LAND MANAGEMENT

PWD Data Report

05/02/2021

APD ID: 10400038355

Submission Date: 01/28/2019

Operator Name: CIMAREX ENERGY COMPANY

Well Name: RED HILLS 32-5 FEDERAL COM

Well Number: 158H

Well Type: CONVENTIONAL GAS WELL

Well Work Type: Drill

Section 1 - General

Would you like to address long-term produced water disposal? NO

Section 2 - Lined Pits

Would you like to utilize Lined Pit PWD options? NO

Produced Water Disposal (PWD) Location:

PWD surface owner:

PWD disturbance (acres):

Lined pit PWD on or off channel:

Lined pit PWD discharge volume (bbl/day):

Lined pit specifications:

Pit liner description:

Pit liner manufacturers information:

Precipitated solids disposal:

Describe precipitated solids disposal:

Precipitated solids disposal permit:

Lined pit precipitated solids disposal schedule:

Lined pit precipitated solids disposal schedule attachment:

Lined pit reclamation description:

Lined pit reclamation attachment:

Leak detection system description:

Leak detection system attachment:

Operator Name: CIMAREX ENERGY COMPANY

Well Name: RED HILLS 32-5 FEDERAL COM

Well Number: 158H

Lined pit Monitor description:

Lined pit Monitor attachment:

Lined pit: do you have a reclamation bond for the pit?

Is the reclamation bond a rider under the BLM bond?

Lined pit bond number:

Lined pit bond amount:

Additional bond information attachment:

Section 3 - Unlined Pits

Would you like to utilize Unlined Pit PWD options? NO

Produced Water Disposal (PWD) Location:

PWD disturbance (acres):

PWD surface owner:

Unlined pit PWD on or off channel:

Unlined pit PWD discharge volume (bbl/day):

Unlined pit specifications:

Precipitated solids disposal:

Describe precipitated solids disposal:

Precipitated solids disposal permit:

Unlined pit precipitated solids disposal schedule:

Unlined pit precipitated solids disposal schedule attachment:

Unlined pit reclamation description:

Unlined pit reclamation attachment:

Unlined pit Monitor description:

Unlined pit Monitor attachment:

Do you propose to put the produced water to beneficial use?

Beneficial use user confirmation:

Estimated depth of the shallowest aquifer (feet):

Does the produced water have an annual average Total Dissolved Solids (TDS) concentration equal to or less than that of the existing water to be protected?

TDS lab results:

Geologic and hydrologic evidence:

State authorization:

Unlined Produced Water Pit Estimated percolation:

Unlined pit: do you have a reclamation bond for the pit?

Operator Name: CIMAREX ENERGY COMPANY

Well Name: RED HILLS 32-5 FEDERAL COM

Well Number: 158H

Is the reclamation bond a rider under the BLM bond?

Unlined pit bond number:

Unlined pit bond amount:

Additional bond information attachment:

Section 4 - Injection

Would you like to utilize Injection PWD options? NO

Produced Water Disposal (PWD) Location:

PWD surface owner:

PWD disturbance (acres):

Injection PWD discharge volume (bbl/day):

Injection well mineral owner:

Injection well type:

Injection well number:

Injection well name:

Assigned injection well API number?

Injection well API number:

Injection well new surface disturbance (acres):

Minerals protection information:

Mineral protection attachment:

Underground Injection Control (UIC) Permit?

UIC Permit attachment:

Section 5 - Surface Discharge

Would you like to utilize Surface Discharge PWD options? NO

Produced Water Disposal (PWD) Location:

PWD surface owner:

PWD disturbance (acres):

Surface discharge PWD discharge volume (bbl/day):

Surface Discharge NPDES Permit?

Surface Discharge NPDES Permit attachment:

Surface Discharge site facilities information:

Surface discharge site facilities map:

Section 6 - Other

Would you like to utilize Other PWD options? NO

Produced Water Disposal (PWD) Location:

PWD surface owner:

PWD disturbance (acres):

Other PWD discharge volume (bbl/day):

Operator Name: CIMAREX ENERGY COMPANY

Well Name: RED HILLS 32-5 FEDERAL COM

Well Number: 158H

Other PWD type description:

Other PWD type attachment:

Have other regulatory requirements been met?

Other regulatory requirements attachment:



U.S. Department of the Interior
BUREAU OF LAND MANAGEMENT

Bond Info Data Report

05/02/2021

APD ID: 10400038355

Submission Date: 01/28/2019

Highlighted data reflects the most recent changes

Operator Name: CIMAREX ENERGY COMPANY

Well Name: RED HILLS 32-5 FEDERAL COM

Well Number: 158H

[Show Final Text](#)

Well Type: CONVENTIONAL GAS WELL

Well Work Type: Drill

Bond Information

Federal/Indian APD: FED

BLM Bond number: NMB001187

BIA Bond number:

Do you have a reclamation bond? NO

Is the reclamation bond a rider under the BLM bond?

Is the reclamation bond BLM or Forest Service?

BLM reclamation bond number:

Forest Service reclamation bond number:

Forest Service reclamation bond attachment:

Reclamation bond number:

Reclamation bond amount:

Reclamation bond rider amount:

Additional reclamation bond information attachment:

State of New Mexico
 Energy, Minerals and Natural Resources Department

Submit Electronically
 Via E-permitting

Oil Conservation Division
 1220 South St. Francis Dr.
 Santa Fe, NM 87505

NATURAL GAS MANAGEMENT PLAN

This Natural Gas Management Plan must be submitted with each Application for Permit to Drill (APD) for a new or recompleted well.

Section 1 – Plan Description Effective May 25, 2021

I. Operator: Cimarex Energy Company **OGRID:** 215099 **Date:** 5 / 2 / 2022

II. Type: Original Amendment due to 19.15.27.9.D(6)(a) NMAC 19.15.27.9.D(6)(b) NMAC Other.

If Other, please describe: _____

III. Well(s): Provide the following information for each new or recompleted well or set of wells proposed to be drilled or proposed to be recompleted from a single well pad or connected to a central delivery point.

Well Name	API	ULSTR	Footages	Anticipated Oil BBL/D	Anticipated Gas MCF/D	Anticipated Produced Water BBL/D
Red Hills 32-5 Fed Com 158H		C, Sec 32, T25S, R33E	330 FNL/2305 FWL	1900	2850	3500
	30-025-50208					

IV. Central Delivery Point Name: Red Hills 32-5 17H CTB CDP Sales [See 19.15.27.9(D)(1) NMAC]

V. Anticipated Schedule: Provide the following information for each new or recompleted well or set of wells proposed to be drilled or proposed to be recompleted from a single well pad or connected to a central delivery point.

Well Name	API	Spud Date	TD Reached Date	Completion Commencement Date	Initial Flow Back Date	First Production Date
Red Hills 32-5 Fed Com 158H		1/1/2023	3/1/2023	6/1/2023	8/1/2023	8/1/2023
	30-025-50208					

VI. Separation Equipment: Attach a complete description of how Operator will size separation equipment to optimize gas capture.

VII. Operational Practices: Attach a complete description of the actions Operator will take to comply with the requirements of Subsection A through F of 19.15.27.8 NMAC.

VIII. Best Management Practices: Attach a complete description of Operator's best management practices to minimize venting during active and planned maintenance.

Section 2 – Enhanced Plan

EFFECTIVE APRIL 1, 2022

Beginning April 1, 2022, an operator that is not in compliance with its statewide natural gas capture requirement for the applicable reporting area must complete this section.

Operator certifies that it is not required to complete this section because Operator is in compliance with its statewide natural gas capture requirement for the applicable reporting area.

IX. Anticipated Natural Gas Production:

Well	API	Anticipated Average Natural Gas Rate MCF/D	Anticipated Volume of Natural Gas for the First Year MCF

X. Natural Gas Gathering System (NGGS):

Operator	System	ULSTR of Tie-in	Anticipated Gathering Start Date	Available Maximum Daily Capacity of System Segment Tie-in

XI. Map. Attach an accurate and legible map depicting the location of the well(s), the anticipated pipeline route(s) connecting the production operations to the existing or planned interconnect of the natural gas gathering system(s), and the maximum daily capacity of the segment or portion of the natural gas gathering system(s) to which the well(s) will be connected.

XII. Line Capacity. The natural gas gathering system will will not have capacity to gather 100% of the anticipated natural gas production volume from the well prior to the date of first production.

XIII. Line Pressure. Operator does does not anticipate that its existing well(s) connected to the same segment, or portion, of the natural gas gathering system(s) described above will continue to meet anticipated increases in line pressure caused by the new well(s).

Attach Operator’s plan to manage production in response to the increased line pressure.

XIV. Confidentiality: Operator asserts confidentiality pursuant to Section 71-2-8 NMSA 1978 for the information provided in Section 2 as provided in Paragraph (2) of Subsection D of 19.15.27.9 NMAC, and attaches a full description of the specific information for which confidentiality is asserted and the basis for such assertion.

Section 3 - Certifications

Effective May 25, 2021

Operator certifies that, after reasonable inquiry and based on the available information at the time of submittal:

Operator will be able to connect the well(s) to a natural gas gathering system in the general area with sufficient capacity to transport one hundred percent of the anticipated volume of natural gas produced from the well(s) commencing on the date of first production, taking into account the current and anticipated volumes of produced natural gas from other wells connected to the pipeline gathering system; or

Operator will not be able to connect to a natural gas gathering system in the general area with sufficient capacity to transport one hundred percent of the anticipated volume of natural gas produced from the well(s) commencing on the date of first production, taking into account the current and anticipated volumes of produced natural gas from other wells connected to the pipeline gathering system.

If Operator checks this box, Operator will select one of the following:

Well Shut-In. Operator will shut-in and not produce the well until it submits the certification required by Paragraph (4) of Subsection D of 19.15.27.9 NMAC; or

Venting and Flaring Plan. Operator has attached a venting and flaring plan that evaluates and selects one or more of the potential alternative beneficial uses for the natural gas until a natural gas gathering system is available, including:

- (a) power generation on lease;
- (b) power generation for grid;
- (c) compression on lease;
- (d) liquids removal on lease;
- (e) reinjection for underground storage;
- (f) reinjection for temporary storage;
- (g) reinjection for enhanced oil recovery;
- (h) fuel cell production; and
- (i) other alternative beneficial uses approved by the division.

Section 4 - Notices

1. If, at any time after Operator submits this Natural Gas Management Plan and before the well is spud:

(a) Operator becomes aware that the natural gas gathering system it planned to connect the well(s) to has become unavailable or will not have capacity to transport one hundred percent of the production from the well(s), no later than 20 days after becoming aware of such information, Operator shall submit for OCD's approval a new or revised venting and flaring plan containing the information specified in Paragraph (5) of Subsection D of 19.15.27.9 NMAC; or

(b) Operator becomes aware that it has, cumulatively for the year, become out of compliance with its baseline natural gas capture rate or natural gas capture requirement, no later than 20 days after becoming aware of such information, Operator shall submit for OCD's approval a new or revised Natural Gas Management Plan for each well it plans to spud during the next 90 days containing the information specified in Paragraph (2) of Subsection D of 19.15.27.9 NMAC, and shall file an update for each Natural Gas Management Plan until Operator is back in compliance with its baseline natural gas capture rate or natural gas capture requirement.

2. OCD may deny or conditionally approve an APD if Operator does not make a certification, fails to submit an adequate venting and flaring plan which includes alternative beneficial uses for the anticipated volume of natural gas produced, or if OCD determines that Operator will not have adequate natural gas takeaway capacity at the time a well will be spud.

I certify that, after reasonable inquiry, the statements in and attached to this Natural Gas Management Plan are true and correct to the best of my knowledge and acknowledge that a false statement may be subject to civil and criminal penalties under the Oil and Gas Act.

Signature: <i>Sarah Jordan</i>
Printed Name: Sarah Jordan
Title: Regulatory Analyst
E-mail Address: sarah.jordan@coterra.com
Date: 5/2/2022
Phone: 432/620-1909

OIL CONSERVATION DIVISION
(Only applicable when submitted as a standalone form)

Approved By:
Title:
Approval Date:
Conditions of Approval:

From State of New Mexico, Natural Gas Management Plan

VI. Separation Equipment: Attach a complete description of how Operator will size separation equipment to optimize gas capture.

XEC Standard Response

Standard facility gas process flow begins at the inlet separator. These vessels are designed based off of forecasted rates and residence times in accordance with, and often greater than, API 12J. The separated gas is then routed to an additional separation vessel (ie sales scrubber) in order to extract liquids that may have carried over or developed due to the decrease in pressure. The sales scrubber is sized based on API 521. From the sales scrubber, the gas leaves the facility and enters the gas midstream gathering network.

Cimarex

VII. Operational Practices

Cimarex values the sustainable development of New Mexico's natural resources. Venting and flaring of natural gas is a source of waste in the industry, and Cimarex will ensure that its values are aligned with those of NMOCD. As such, Cimarex plans to take pointed steps to ensure compliance with Subsection A through F of 19.15.27.8 NMAC.

Specifically, below are the steps Cimarex will plan to follow under routine well commissioning and operations.

1. Capture or combust natural gas during drilling operations where technically feasible, using the best industry practices and control technologies.
 - a. All flares during these operations will be a minimum of 100ft away from the nearest surface-hole location.
2. All gas present during post-completion drill-out and flow back will be routed through separation equipment, and, if technically feasible, flare unsellable vapors rather than vent. Lastly, formal sales separator commissioning to process well-stream fluids and send gas to a gas flow line/collection system or use the gas for on-site fuel or beneficial usage, gas as soon as is safe and technically feasible.
3. Cimarex will ensure the flare or combustion equipment is properly sized to handle expected flow rates, ensure this equipment is equipped with an automatic or continuous ignition source, and ensure this equipment is designed for proper combustion efficiency.
4. If Cimarex must flare because gas is not meeting pipeline specifications, Cimarex will limit flaring to <60 days, analyze gas composition at least twice per week, and route gas into a gathering pipeline as soon as pipeline specifications are met.
5. Under routine production operations, Cimarex will not flare/vent unless:
 - a. Venting or flaring occurs due to an emergency or equipment malfunction.
 - b. Venting or flaring occurs as a result of unloading practices, and an operator is onsite (or within 30 minutes of drive time and posts contact information at the wellsite) until the end of unloading practice.
 - c. The venting or flaring occurs during automated plungerlift operations, in which case the Cimarex operator will work to optimize the plungerlift system to minimize venting/flaring.
 - d. The venting or flaring occurs during downhole well maintenance, in which case Cimarex will work to minimize venting or flaring operations to the extent that it does not pose a risk to safe operations.
 - e. The well is an exploratory well, the division has approved the well as an exploratory well, venting or flaring is limited to 12 months, as approved by the division, and venting/flaring does not cause Cimarex to breach its State-wide 98% gas capture requirement.
 - f. Venting or flaring occurs because the stock tanks or other low-pressure vessels are being gauged, sampled, or liquids are being loaded out.
 - g. The venting or flaring occurs because pressurized vessels are being maintained and are being blown-down or depressurized.
 - h. Venting or flaring occurs as a result of normal dehydration unit operations.

- i. Venting or flaring occurs as a result of bradenhead testing.
 - j. Venting or flaring occurs as a result of normal compressor operations, including general compressor operations, compressor engines and turbines.
 - k. Venting or flaring occurs as a result of a packer leakage test.
 - l. Venting or flaring occurs as a result of a production test lasting less than 24 hours unless otherwise approved by the division.
 - m. Venting or flaring occurs as a result of new equipment commissioning and is necessary to purge impurities from the pipeline or production equipment.
6. Cimarex will maintain its equipment in accordance with its Operations and Maintenance Program, to ensure venting or flaring events are minimized and that equipment is properly functioning.
7. Cimarex will install automatic tank gauging equipment on all production facilities constructed after May 25, 2021, to ensure minimal emissions from tank gauging practices.
8. By November 25, 2022, all Cimarex facilities equipped with flares or combustors will be equipped with continuous pilots or automatic igniters, and technology to ensure proper function, i.e. thermocouple, fire-eye, etc...
9. Cimarex will perform AVO (audio, visual, olfactory) facility inspections in accordance with NMOCD requirements. Specifically, Cimarex will:
 - a. Perform weekly inspections during the first year of production, and so long as production is greater than 60 MCFD.
 - b. If production is less than 60 MCFD, Cimarex will perform weekly AVO inspections when an operator is present on location, and inspections at least once per calendar month with at least 20 calendar days between inspections.
10. Cimarex will measure or estimate the volume of vented, flared or beneficially used natural gas, regardless of the reason or authorization for such venting or flaring.
11. On all facilities constructed after May 25, 2021, Cimarex will install metering where feasible and in accordance with available technology and best engineering practices, in an effort to measure how much gas could have been vented or flared.
 - a. In areas where metering is not technically feasible, such as low-pressure/low volume venting or flaring applications, engineering estimates will be used such that the methodology could be independently verified.
12. Cimarex will fulfill the division's requirements for reporting and filing of venting or flaring that exceeds 50 MCF in volume or last eight hours or more cumulatively within any 24-hour period.

VIII. Best Management Practices to minimize venting during active and planned maintenance

Cimarex strives to ensure minimal venting occurs during active and planned maintenance activities. Below is a description of common maintenance practices, and the steps Cimarex takes to limit venting exposure.

- **Workovers:**
 - Always strive to kill well when performing downhole maintenance.
 - If vapors or trapped pressure is present and must be relieved then:
 - Initial blowdown to production facility:
 - Route vapors to LP flare if possible/applicable
 - Blowdown to portable gas buster tank:
 - Vent to existing or portable flare if applicable.
- **Stock tank servicing:**
 - Minimize time spent with thief hatches open.
 - When cleaning or servicing via manway, suck tank bottoms to ensure minimal volatiles exposed to atmosphere.
 - Connect vacuum truck to low pressure flare while cleaning bottoms to limit venting.
 - Isolate the vent lines and overflows on the tank being serviced from other tanks.
- **Pressure vessel/compressor servicing and associated blowdowns:**
 - Route to flare where possible.
 - Blow vessel down to minimum available pressure via pipeline, prior to venting vessel.
 - Preemptively changing anodes to reduce failures and extended corrosion related servicing.
 - When cleaning or servicing via manway, suck vessel bottoms to ensure minimal volatiles exposed to atmosphere.
- **Flare/combustor maintenance:**
 - Minimize downtime by coordinating with vendor and Cimarex staff travel logistics.
 - Utilizing preventative and predictive maintenance programs to replace high wear components before failure.
 - Because the flare/combustor is the primary equipment used to limit venting practices, ensure flare/combustor is properly maintained and fully operational at all times via routine maintenance, temperature telemetry, onsite visual inspections.

The Cimarex expectation is to limit all venting exposure. Equipment that may not be listed on this document is still expected to be maintained and associated venting during such maintenance minimized.

District I
 1625 N. French Dr., Hobbs, NM 88240
 Phone:(575) 393-6161 Fax:(575) 393-0720

District II
 811 S. First St., Artesia, NM 88210
 Phone:(575) 748-1283 Fax:(575) 748-9720

District III
 1000 Rio Brazos Rd., Aztec, NM 87410
 Phone:(505) 334-6178 Fax:(505) 334-6170

District IV
 1220 S. St Francis Dr., Santa Fe, NM 87505
 Phone:(505) 476-3470 Fax:(505) 476-3462

State of New Mexico
Energy, Minerals and Natural Resources
Oil Conservation Division
1220 S. St Francis Dr.
Santa Fe, NM 87505

CONDITIONS

Action 108524

CONDITIONS

Operator: CIMAREX ENERGY CO. 600 N. Marienfeld Street Midland, TX 79701	OGRID: 215099
	Action Number: 108524
	Action Type: [C-101] BLM - Federal/Indian Land Lease (Form 3160-3)

CONDITIONS

Created By	Condition	Condition Date
pkautz	Will require a File As Drilled C-102 and a Directional Survey with the C-104	6/3/2022
pkautz	Once the well is spud, to prevent ground water contamination through whole or partial conduits from the surface, the operator shall drill without interruption through the fresh water zone or zones and shall immediately set in cement the water protection string	6/3/2022
pkautz	Oil base muds are not to be used until fresh water zones are cased and cemented providing isolation from the oil or diesel. This includes synthetic oils. Oil based mud, drilling fluids and solids must be contained in a steel closed loop system	6/3/2022
pkautz	Cement is required to circulate on both surface and production strings of casing	6/3/2022