

Well Name: NORTH BLONDIE 3-15 FED COM	Well Location: T25S / R34E / SEC 34 / SWSE /	County or Parish/State:
Well Number: 4H	Type of Well: OIL WELL	Allottee or Tribe Name:
Lease Number: NMNM114990	Unit or CA Name:	Unit or CA Number:
US Well Number: 3002551799	Well Status: Approved Application for Permit to Drill	Operator: DEVON ENERGY PRODUCTION COMPANY LP

Notice of Intent

Sundry ID: 2753859

Type of Submission: Notice of Intent

Type of Action: APD Change

Date Sundry Submitted: 09/27/2023

Time Sundry Submitted: 04:06

Date proposed operation will begin: 09/27/2023

Procedure Description: Devon Energy Production Company L.P. respectfully requests the following changes to the approved APD: BHL change from 2050 FNL & 1320 FEL to 2050 FNL & 1500 FEL, both 15-26S-34E. Defining well designation revision. Please see attached revised C-102, and drilling & directional plans.

NOI Attachments

Procedure Description

- NORTH_BLONDIE_3_15_FED_COM_4H_C_102_BHL_20230927160501.pdf
- North_Blondie_3_15_Fed_Com_4H_Directional_Plan_09_27_23_20230927160459.pdf
- North_Blondie_3_15_Fed_Com_4H_20230927160459.pdf

Well Name: NORTH BLONDIE 3-15 FED COM	Well Location: T25S / R34E / SEC 34 / SWSE /	County or Parish/State:
Well Number: 4H	Type of Well: OIL WELL	Allottee or Tribe Name:
Lease Number: NMNM114990	Unit or CA Name:	Unit or CA Number:
US Well Number: 3002551799	Well Status: Approved Application for Permit to Drill	Operator: DEVON ENERGY PRODUCTION COMPANY LP

Operator

I certify that the foregoing is true and correct. Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction. Electronic submission of Sundry Notices through this system satisfies regulations requiring a

Operator Electronic Signature: REBECCA DEAL	Signed on: SEP 27, 2023 04:05 PM
Name: DEVON ENERGY PRODUCTION COMPANY LP	
Title: Regulatory Analyst	
Street Address: 333 W SHERIDAN AVE	
City: OKLAHOMA CITY	State: OK
Phone: (303) 299-1406	
Email address: REBECCA.DEAL@DVN.COM	

Field

Representative Name:		
Street Address:		
City:	State:	Zip:
Phone:		
Email address:		

BLM Point of Contact

BLM POC Name: LONG VO	BLM POC Title: Petroleum Engineer
BLM POC Phone: 5759885402	BLM POC Email Address: LVO@BLM.GOV
Disposition: Approved	Disposition Date: 10/11/2023
Signature: Long Vo	

Form 3160-5
(June 2019)

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB No. 1004-0137
Expires: October 31, 2021

SUNDRY NOTICES AND REPORTS ON WELLS
Do not use this form for proposals to drill or to re-enter an abandoned well. Use Form 3160-3 (APD) for such proposals.

5. Lease Serial No.	
6. If Indian, Allottee or Tribe Name	
7. If Unit of CA/Agreement, Name and/or No.	
8. Well Name and No.	
9. API Well No.	
10. Field and Pool or Exploratory Area	
11. Country or Parish, State	

SUBMIT IN TRIPLICATE - Other instructions on page 2

1. Type of Well		
☐ Oil Well	☐ Gas Well	☐ Other
2. Name of Operator		
3a. Address	3b. Phone No. (include area code)	
4. Location of Well (Footage, Sec., T.,R.,M., or Survey Description)		

12. CHECK THE APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION				
☐ Notice of Intent	☐ Acidize	☐ Deepen	☐ Production (Start/Resume)	☐ Water Shut-Off	
☐ Subsequent Report	☐ Alter Casing	☐ Hydraulic Fracturing	☐ Reclamation	☐ Well Integrity	
☐ Final Abandonment Notice	☐ Casing Repair	☐ New Construction	☐ Recomplete	☐ Other	
	☐ Change Plans	☐ Plug and Abandon	☐ Temporarily Abandon		
	☐ Convert to Injection	☐ Plug Back	☐ Water Disposal		

13. Describe Proposed or Completed Operation: Clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recompleat horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be perfonned or provide the Bond No. on file with BLM/BIA. Required subsequent reports must be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompleation in a new interval, a Form 3160-4 must be filed once testing has been completed. Final Abandonment Notices must be filed only after all requirements, including reclamation, have been completed and the operator has detennined that the site is ready for final inspection.)

14. I hereby certify that the foregoing is true and correct. Name (Printed/Typed)	Title
Signature	Date

THE SPACE FOR FEDERAL OR STATE OFFICE USE

Approved by	Title	Date
Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.	Office	

Title 18 U.S.C Section 1001 and Title 43 U.S.C Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Instructions on page 2)

GENERAL INSTRUCTIONS

This form is designed for submitting proposals to perform certain well operations and reports of such operations when completed as indicated on Federal and Indian lands pursuant to applicable Federal law and regulations. Any necessary special instructions concerning the use of this form and the number of copies to be submitted, particularly with regard to local area or regional procedures and practices, are either shown below, will be issued by or may be obtained from the local Federal office.

SPECIFIC INSTRUCTIONS

Item 4 - Locations on Federal or Indian land should be described in accordance with Federal requirements. Consult the local Federal office for specific instructions.

Item 13: Proposals to abandon a well and subsequent reports of abandonment should include such special information as is required by the local Federal office. In addition, such proposals and reports should include reasons for the abandonment; data on any former or present productive zones or other zones with present significant fluid contents not sealed off by cement or otherwise; depths (top and bottom) and method of placement of cement plugs; mud or other material placed below, between and above plugs; amount, size, method of parting of any casing, liner or tubing pulled and the depth to the top of any tubing left in the hole; method of closing top of well and date well site conditioned for final inspection looking for approval of the abandonment. If the proposal will involve **hydraulic fracturing operations**, you must comply with 43 CFR 3162.3-3, including providing information about the protection of usable water. Operators should provide the best available information about all formations containing water and their depths. This information could include data and interpretation of resistivity logs run on nearby wells. Information may also be obtained from state or tribal regulatory agencies and from local BLM offices.

NOTICES

The privacy Act of 1974 and the regulation in 43 CFR 2.48(d) provide that you be furnished the following information in connection with information required by this application.

AUTHORITY: 30 U.S.C. 181 et seq., 351 et seq., 25 U.S.C. 396; 43 CFR 3160.

PRINCIPAL PURPOSE: The information is used to: (1) Evaluate, when appropriate, approve applications, and report completion of subsequent well operations, on a Federal or Indian lease; and (2) document for administrative use, information for the management, disposal and use of National Resource lands and resources, such as: (a) evaluating the equipment and procedures to be used during a proposed subsequent well operation and reviewing the completed well operations for compliance with the approved plan; (b) requesting and granting approval to perform those actions covered by 43 CFR 3162.3-2, 3162.3-3, and 3162.3-4; (c) reporting the beginning or resumption of production, as required by 43 CFR 3162.4-1(c) and (d) analyzing future applications to drill or modify operations in light of data obtained and methods used.

ROUTINE USES: Information from the record and/or the record will be transferred to appropriate Federal, State, local or foreign agencies, when relevant to civil, criminal or regulatory investigations or prosecutions in connection with congressional inquiries or to consumer reporting agencies to facilitate collection of debts owed the Government.

EFFECT OF NOT PROVIDING THE INFORMATION: Filing of this notice and report and disclosure of the information is mandatory for those subsequent well operations specified in 43 CFR 3162.3-2, 3162.3-3, 3162.3-4.

The Paperwork Reduction Act of 1995 requires us to inform you that:

The BLM collects this information to evaluate proposed and/or completed subsequent well operations on Federal or Indian oil and gas leases.

Response to this request is mandatory.

The BLM would like you to know that you do not have to respond to this or any other Federal agency-sponsored information collection unless it displays a currently valid OMB control number.

BURDEN HOURS STATEMENT: Public reporting burden for this form is estimated to average 8 hours per response, including the time for reviewing instructions, gathering and maintaining data, and completing and reviewing the form. Direct comments regarding the burden estimate or any other aspect of this form to U.S. Department of the Interior, Bureau of Land Management (1004-0137), Bureau Information Collection Clearance Officer (WO-630), 1849 C St., N.W., Mail Stop 401 LS, Washington, D.C. 20240

Additional Information

Location of Well

0. SHL: SWSE / 230 FSL / 2490 FEL / TWSP: 25S / RANGE: 34E / SECTION: 34 / LAT: 32.08037 / LONG: -103.457307 (TVD: 0 feet, MD: 0 feet)

PPP: NENE / 100 FNL / 1320 FEL / TWSP: 26S / RANGE: 34E / SECTION: 3 / LAT: 32.0794536 / LONG: -103.4535285 (TVD: 9470 feet, MD: 9642 feet)

PPP: SENE / 1536 FNL / 1320 FEL / TWSP: 26S / RANGE: 34E / SECTION: 3 / LAT: 32.075503 / LONG: -103.4535274 (TVD: 9755 feet, MD: 11200 feet)

PPP: NENE / 151 FNL / 1319 FEL / TWSP: 26S / RANGE: 34E / SECTION: 10 / LAT: 32.064798 / LONG: -103.4535223 (TVD: 9962 feet, MD: 15100 feet)

BHL: SENE / 2050 FNL / 1320 FEL / TWSP: 26S / RANGE: 34E / SECTION: 15 / LAT: 32.045068 / LONG: -103.453513 (TVD: 10344 feet, MD: 22288 feet)

CONFIDENTIAL

DISTRICT I
1625 N. FRENCH DR., HOBBS, NM 88240
Phone: (505) 393-6161 Fax: (505) 393-0720

DISTRICT II
811 S. FIRST ST., ARTESIA, NM 88210
Phone: (505) 748-1283 Fax: (505) 748-9720

DISTRICT III
1000 RIO BRAZOS RD., AZTEC, NM 87410
Phone: (505) 334-6178 Fax: (505) 334-6170

DISTRICT IV
1220 S. ST. FRANCIS DR., SANTA FE, NM 87505
Phone: (505) 476-3460 Fax: (505) 476-3462

State of New Mexico
Energy, Minerals & Natural Resources Department
OIL CONSERVATION DIVISION
1220 SOUTH ST. FRANCIS DR.
Santa Fe, New Mexico 87505

Form C-102
Revised August 1, 2011
Submit one copy to appropriate
District Office

☒ AMENDED REPORT

WELL LOCATION AND ACREAGE DEDICATION PLAT

API Number 30-025-51799	Pool Code 96661	Pool Name HARDIN TANK;BONE SPRING
Property Code 344567	Property Name NORTH BLONDIE 3-15 FED COM	Well Number 4H
OGRID No. 6137	Operator Name DEVON ENERGY PRODUCTION COMPANY, L.P.	Elevation 3311.1'

Surface Location

UL or lot No.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County
0	34	25-S	34-E		230	SOUTH	2490	EAST	LEA

Bottom Hole Location If Different From Surface

UL or lot No.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County
G	15	26-S	34-E		2050	NORTH	1500	EAST	LEA

Dedicated Acres	Joint or Infill	Consolidation Code	Order No.
800			

NO ALLOWABLE WILL BE ASSIGNED TO THIS COMPLETION UNTIL ALL INTERESTS HAVE BEEN CONSOLIDATED
OR A NON-STANDARD UNIT HAS BEEN APPROVED BY THE DIVISION

NORTH BLONDIE 3-15 FED COM 4H

EL:3311.1'
GEODETIC COORDINATES
NAD 83 NMSP EAST
SURFACE LOCATION
N:394077.51
E:812662.60
LAT:32.080370
LON:103.457307

KICK OFF POINT

CALLS:
N:
E:
LAT:
LON:

FIRST TAKE POINT (PPP 1)

100' FNL 1500' FEL SEC. 3
N:393752.69
E:813655.73
LAT:32.079455
LON:103.454110

LAST TAKE POINT

1970' FNL 1500' FEL SEC. 15
N:381323.48
E:813761.82
LAT:32.045289
LON:103.454094

BOTTOM OF HOLE

N:381243.48
E:813762.51
LAT:32.045069
LON:103.454094

(PPP 2)

0' FSL 1499' FEL SEC. 3
N:388572.01
E:813699.95
LAT:32.065214
LON:103.454103


(PPP 3)

2640' FNL 1500' FEL SEC. 10
N:385931.75
E:813722.49
LAT:32.057957
LON:103.454100

(PPP 4)

1319' FSL 1500' FEL SEC. 10
N:384612.59
E:813733.74
LAT:32.054330
LON:103.454098

A=N:396462.79 E:809946.22
B=N:396502.82 E:815132.77
C=N:393826.32 E:809868.53
D=N:393846.74 E:812510.98
E=N:393860.48 E:815154.85
F=N:391185.34 E:809892.17
G=N:391221.50 E:815177.82
H=N:388547.78 E:809915.60
I=N:388581.61 E:815199.26
J=N:385909.71 E:808938.27
K=N:385940.49 E:815221.99
L=N:383264.34 E:809962.78
M=N:383287.54 E:812605.90
N=N:383301.17 E:815244.85
O=N:380624.94 E:809985.91
P=N:380655.87 E:815267.62



OPERATOR CERTIFICATION

I hereby certify that the information herein is true and complete to the best of my knowledge and belief, and that this organization either owns a working interest or unleased mineral interest in the land including the proposed bottom hole location or has a right to drill this well at this location pursuant to a contract with an owner of such mineral or working interest, or to a voluntary pooling agreement or a compulsory pooling order heretofore entered by the division.

Rebecca Deal 9/22/2023
Signature Date

Rebecca Deal, Regulatory Analyst
Printed Name

rebecca.deal@dvn.com
E-mail Address


SURVEYOR CERTIFICATION

I hereby certify that the well location shown on this plat was plotted from field notes of actual surveys made by me or under my supervision, and that the same is true and correct to the best of my belief.

04/05/2022

Date of Survey

Signature & Seal of Professional Surveyor



REV: 09/15/2023

Certificate No. 22404 B.L. LAMAN
DRAWN BY: CM

Intent ☒ As Drilled ☐

API #		
Operator Name: DEVON ENERGY PRODUCTION COMPANY, LP.	Property Name: NORTH BLONDIE 3-15 FED COM	Well Number 4H

Kick Off Point (KOP)

UL	Section	Township	Range	Lot	Feet	From N/S	Feet	From E/W	County
Latitude					Longitude				NAD

First Take Point (FTP)

UL	Section	Township	Range	Lot	Feet	From N/S	Feet	From E/W	County
B	3	26-S	34-E		100	NORTH	1500	EAST	LEA
Latitude					Longitude				NAD
32.079455					103.454110				83

Last Take Point (LTP)

UL	Section	Township	Range	Lot	Feet	From N/S	Feet	From E/W	County
G	15	26-S	34-E		1970	NORTH	1500	EAST	LEA
Latitude					Longitude				NAD
32.045289					103.454094				83

Is this well the defining well for the Horizontal Spacing Unit?

☐ N

Is this well an infill well?

☐ Y

If infill is yes please provide API if available, Operator Name and well number for Defining well for Horizontal Spacing Unit.

API #		
Operator Name: DEVON ENERGY PRODUCTION COMPANY, LP.	Property Name: NORTH BLONDIE 3-15 FED COM	Well Number 11H


KZ 06/29/2018



Well: North Blondie 3-15 Fed Com 4H
County: Lea
Wellbore: Permit Plan
Design: Permit Plan #1

Geodetic System: US State Plane 1983
Datum: North American Datum 1927
Ellipsoid: Clarke 1866
Zone: 3001 - NM East (NAD83)

MD	INC	AZI	TVD	NS	EW	VS	DLS	Comment
(ft)	(°)	(°)	(ft)	(ft)	(ft)	(ft)	(°/100ft)	
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	SHL
2000.00	0.00	105.00	2000.00	0.00	0.00	0.00	0.00	Start Tangent
2750.00	15.00	105.00	2741.46	-25.26	94.29	33.22	2.00	Hold Tangent
5965.36	15.00	105.00	5847.27	-240.65	898.13	316.46	0.00	Drop to Vertical
6715.36	0.00	105.00	6588.73	-265.92	992.42	349.68	2.00	Hold Vertical
9254.50	0.00	179.51	9127.86	-265.92	992.42	349.68	0.00	KOP
10123.85	86.93	179.51	9700.00	-808.22	997.06	890.40	10.00	Landing Point
22167.33	86.93	179.51	10344.00	-12834.03	1099.91	12881.08	0.00	BHL



Key Depths	MD (ft)	TVD (ft)
Rustler	860.00	860.00
Salt	1300.00	1300.00
Base of Salt	5139.97	5050.00
Delaware	5419.50	5320.00
Cherry Canyon	6446.24	6320.00
Brushy Canyon	8076.64	7950.00
1st Bone Spring Lime	9561.05	9420.00
Leonard / Point of Penetration	9621.15	9470.00
exit	22087.33	10339.74

SHL
KOP
Point of Penetration
Exit
BHL

MD	TVD	Lat	Long	Section Footages
(ft)	(ft)	(°)	(°)	
0.00	0.00	32.0803	-103.4574	230' FSL, 2490' FEL of Sec 34 in T25S, R34E
9254.50	9127.86	32.0795	-103.4542	39' FNL, 1500' FEL of Sec 3 in T26S, R34E
9621.15	9470.00	32.0795	-103.4541	100' FNL, 1500' FEL of Sec 3 in T26S, R34E
22087.33	10339.74	32.0453	-103.4541	1970' FNL, 1500' FEL of Sec 15 in T26S, R34E
22167.33	10344.00	32.0450	-103.4542	2050' FNL, 1500' FEL of Sec 15 in T26S, R34E

Y	X	MD
KOP	393812	813655
		9254.50

North Blondie 3-15 Fed Com 4H



Well: North Blondie 3-15 Fed Com 4H
County: Lea
Wellbore: Permit Plan
Design: Permit Plan #1

Geodetic System: US State Plane 1983
Datum: North American Datum 1927
Ellipsoid: Clarke 1866
Zone: 3001 - NM East (NAD83)

MD (ft)	INC (°)	AZI (°)	TVD (ft)	NS (ft)	EW (ft)	VS (ft)	DLS (°/100ft)	Comment
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	SHL
100.00	0.00	105.00	100.00	0.00	0.00	0.00	0.00	
200.00	0.00	105.00	200.00	0.00	0.00	0.00	0.00	
300.00	0.00	105.00	300.00	0.00	0.00	0.00	0.00	
400.00	0.00	105.00	400.00	0.00	0.00	0.00	0.00	
500.00	0.00	105.00	500.00	0.00	0.00	0.00	0.00	
600.00	0.00	105.00	600.00	0.00	0.00	0.00	0.00	
700.00	0.00	105.00	700.00	0.00	0.00	0.00	0.00	
800.00	0.00	105.00	800.00	0.00	0.00	0.00	0.00	
860.00	0.00	105.00	860.00	0.00	0.00	0.00	0.00	Rustler
900.00	0.00	105.00	900.00	0.00	0.00	0.00	0.00	
1000.00	0.00	105.00	1000.00	0.00	0.00	0.00	0.00	
1100.00	0.00	105.00	1100.00	0.00	0.00	0.00	0.00	
1200.00	0.00	105.00	1200.00	0.00	0.00	0.00	0.00	
1300.00	0.00	105.00	1300.00	0.00	0.00	0.00	0.00	Salt,
1400.00	0.00	105.00	1400.00	0.00	0.00	0.00	0.00	
1500.00	0.00	105.00	1500.00	0.00	0.00	0.00	0.00	
1600.00	0.00	105.00	1600.00	0.00	0.00	0.00	0.00	
1700.00	0.00	105.00	1700.00	0.00	0.00	0.00	0.00	
1800.00	0.00	105.00	1800.00	0.00	0.00	0.00	0.00	
1900.00	0.00	105.00	1900.00	0.00	0.00	0.00	0.00	
2000.00	0.00	105.00	2000.00	0.00	0.00	0.00	0.00	Start Tangent
2100.00	2.00	105.00	2099.98	-0.45	1.69	0.59	2.00	
2200.00	4.00	105.00	2199.84	-1.81	6.74	2.38	2.00	
2300.00	6.00	105.00	2299.45	-4.06	15.16	5.34	2.00	
2400.00	8.00	105.00	2398.70	-7.22	26.93	9.49	2.00	
2500.00	10.00	105.00	2497.47	-11.26	42.04	14.81	2.00	
2600.00	12.00	105.00	2595.62	-16.20	60.47	21.31	2.00	
2700.00	14.00	105.00	2693.06	-22.02	82.20	28.96	2.00	
2750.00	15.00	105.00	2741.46	-25.26	94.29	33.22	2.00	Hold Tangent
2800.00	15.00	105.00	2789.76	-28.61	106.79	37.63	0.00	
2900.00	15.00	105.00	2886.35	-35.31	131.79	46.44	0.00	
3000.00	15.00	105.00	2982.94	-42.01	156.79	55.25	0.00	
3100.00	15.00	105.00	3079.54	-48.71	181.79	64.06	0.00	
3200.00	15.00	105.00	3176.13	-55.41	206.79	72.86	0.00	
3300.00	15.00	105.00	3272.72	-62.11	231.79	81.67	0.00	
3400.00	15.00	105.00	3369.31	-68.81	256.79	90.48	0.00	
3500.00	15.00	105.00	3465.91	-75.50	281.79	99.29	0.00	
3600.00	15.00	105.00	3562.50	-82.20	306.79	108.10	0.00	
3700.00	15.00	105.00	3659.09	-88.90	331.79	116.91	0.00	
3800.00	15.00	105.00	3755.68	-95.60	356.79	125.72	0.00	
3900.00	15.00	105.00	3852.28	-102.30	381.79	134.53	0.00	
4000.00	15.00	105.00	3948.87	-109.00	406.79	143.34	0.00	
4100.00	15.00	105.00	4045.46	-115.70	431.79	152.15	0.00	
4200.00	15.00	105.00	4142.05	-122.40	456.79	160.95	0.00	
4300.00	15.00	105.00	4238.65	-129.09	481.79	169.76	0.00	
4400.00	15.00	105.00	4335.24	-135.79	506.79	178.57	0.00	
4500.00	15.00	105.00	4431.83	-142.49	531.79	187.38	0.00	
4600.00	15.00	105.00	4528.42	-149.19	556.79	196.19	0.00	
4700.00	15.00	105.00	4625.02	-155.89	581.79	205.00	0.00	
4800.00	15.00	105.00	4721.61	-162.59	606.79	213.81	0.00	
4900.00	15.00	105.00	4818.20	-169.29	631.79	222.62	0.00	
5000.00	15.00	105.00	4914.80	-175.99	656.79	231.43	0.00	
5100.00	15.00	105.00	5011.39	-182.68	681.79	240.23	0.00	
5139.97	15.00	105.00	5050.00	-185.36	691.78	243.76	0.00	Base of Salt
5200.00	15.00	105.00	5107.98	-189.38	706.79	249.04	0.00	
5300.00	15.00	105.00	5204.57	-196.08	731.79	257.85	0.00	
5400.00	15.00	105.00	5301.17	-202.78	756.79	266.66	0.00	
5419.50	15.00	105.00	5320.00	-204.09	761.66	268.38	0.00	Delaware
5500.00	15.00	105.00	5397.76	-209.48	781.79	275.47	0.00	
5600.00	15.00	105.00	5494.35	-216.18	806.79	284.28	0.00	
5700.00	15.00	105.00	5590.94	-222.88	831.79	293.09	0.00	
5800.00	15.00	105.00	5687.54	-229.57	856.79	301.90	0.00	
5900.00	15.00	105.00	5784.13	-236.27	881.79	310.71	0.00	
5965.36	15.00	105.00	5847.27	-240.65	898.13	316.46	0.00	Drop to Vertical
6000.00	14.31	105.00	5880.77	-242.92	906.59	319.45	2.00	
6100.00	12.31	105.00	5978.08	-248.88	928.83	327.28	2.00	
6200.00	10.31	105.00	6076.14	-253.95	947.76	333.95	2.00	
6300.00	8.31	105.00	6174.82	-258.14	963.38	339.46	2.00	
6400.00	6.31	105.00	6274.00	-261.43	975.67	343.79	2.00	

North Blondie 3-15 Fed Com 4H



Well: North Blondie 3-15 Fed Com 4H
County: Lea
Wellbore: Permit Plan
Design: Permit Plan #1

Geodetic System: US State Plane 1983
Datum: North American Datum 1927
Ellipsoid: Clarke 1866
Zone: 3001 - NM East (NAD83)

MD (ft)	INC (")	AZI (°)	TVD (ft)	NS (ft)	EW (ft)	VS (ft)	DLS (°/100ft)	Comment
6446.24	5.38	105.00	6320.00	-262.65	980.22	345.39	2.00	Cherry Canyon
6500.00	4.31	105.00	6373.57	-263.82	984.60	346.94	2.00	
6600.00	2.31	105.00	6473.39	-265.32	990.18	348.90	2.00	
6700.00	0.31	105.00	6573.36	-265.91	992.38	349.68	2.00	
6715.36	0.00	105.00	6588.73	-265.92	992.42	349.68	2.00	Hold Vertical
6800.00	0.00	179.51	6673.36	-265.92	992.42	349.69	0.00	
6900.00	0.00	179.51	6773.36	-265.92	992.42	349.69	0.00	
7000.00	0.00	179.51	6873.36	-265.92	992.42	349.69	0.00	
7100.00	0.00	179.51	6973.36	-265.92	992.42	349.69	0.00	
7200.00	0.00	179.51	7073.36	-265.92	992.42	349.69	0.00	
7300.00	0.00	179.51	7173.36	-265.92	992.42	349.69	0.00	
7400.00	0.00	179.51	7273.36	-265.92	992.42	349.69	0.00	
7500.00	0.00	179.51	7373.36	-265.92	992.42	349.69	0.00	
7600.00	0.00	179.51	7473.36	-265.92	992.42	349.69	0.00	
7700.00	0.00	179.51	7573.36	-265.92	992.42	349.69	0.00	
7800.00	0.00	179.51	7673.36	-265.92	992.42	349.69	0.00	
7900.00	0.00	179.51	7773.36	-265.92	992.42	349.69	0.00	
8000.00	0.00	179.51	7873.36	-265.92	992.42	349.69	0.00	
8076.64	0.00	179.51	7950.00	-265.92	992.42	349.69	0.00	Brushy Canyon
8100.00	0.00	179.51	7973.36	-265.92	992.42	349.69	0.00	
8200.00	0.00	179.51	8073.36	-265.92	992.42	349.69	0.00	
8300.00	0.00	179.51	8173.36	-265.92	992.42	349.69	0.00	
8400.00	0.00	179.51	8273.36	-265.92	992.42	349.69	0.00	
8500.00	0.00	179.51	8373.36	-265.92	992.42	349.69	0.00	
8600.00	0.00	179.51	8473.36	-265.92	992.42	349.69	0.00	
8700.00	0.00	179.51	8573.36	-265.92	992.42	349.69	0.00	
8800.00	0.00	179.51	8673.36	-265.92	992.42	349.69	0.00	
8900.00	0.00	179.51	8773.36	-265.92	992.42	349.69	0.00	
9000.00	0.00	179.51	8873.36	-265.92	992.42	349.69	0.00	
9100.00	0.00	179.51	8973.36	-265.92	992.42	349.69	0.00	
9200.00	0.00	179.51	9073.36	-265.92	992.42	349.69	0.00	
9254.50	0.00	179.51	9127.86	-265.92	992.42	349.68	0.00	KOP
9300.00	4.55	179.51	9173.32	-267.72	992.43	351.49	10.00	
9400.00	14.55	179.51	9271.80	-284.29	992.58	368.01	10.00	
9500.00	24.55	179.51	9365.92	-317.71	992.86	401.33	10.00	
9561.05	30.66	179.51	9420.00	-345.99	993.10	429.53	10.00	1st Bone Spring Lime
9600.00	34.55	179.51	9452.80	-366.97	993.28	450.44	10.00	
9621.15	36.67	179.51	9470.00	-379.28	993.39	462.72	10.00	Leonard / Point of Penetration
9700.00	44.55	179.51	9529.81	-430.56	993.83	513.85	10.00	
9800.00	54.55	179.51	9594.61	-506.56	994.48	589.63	10.00	
9900.00	64.55	179.51	9645.22	-592.65	995.21	675.47	10.00	
10000.00	74.55	179.51	9680.12	-686.23	996.02	768.77	10.00	
10100.00	84.55	179.51	9698.23	-784.44	996.86	866.70	10.00	
10123.85	86.93	179.51	9700.00	-808.22	997.06	890.40	10.00	Landing Point
10200.00	86.93	179.51	9704.07	-884.26	997.71	966.23	0.00	
10300.00	86.93	179.51	9709.42	-984.11	998.56	1065.79	0.00	
10400.00	86.93	179.51	9714.77	-1083.97	999.42	1165.35	0.00	
10500.00	86.93	179.51	9720.11	-1183.82	1000.27	1264.91	0.00	
10600.00	86.93	179.51	9725.46	-1283.67	1001.12	1364.47	0.00	
10700.00	86.93	179.51	9730.81	-1383.53	1001.98	1464.03	0.00	
10800.00	86.93	179.51	9736.16	-1483.38	1002.83	1563.59	0.00	
10900.00	86.93	179.51	9741.50	-1583.23	1003.69	1663.16	0.00	
11000.00	86.93	179.51	9746.85	-1683.09	1004.54	1762.72	0.00	
11100.00	86.93	179.51	9752.20	-1782.94	1005.40	1862.28	0.00	
11200.00	86.93	179.51	9757.55	-1882.79	1006.25	1961.84	0.00	
11300.00	86.93	179.51	9762.89	-1982.65	1007.10	2061.40	0.00	
11400.00	86.93	179.51	9768.24	-2082.50	1007.96	2160.96	0.00	
11500.00	86.93	179.51	9773.59	-2182.35	1008.81	2260.53	0.00	
11600.00	86.93	179.51	9778.94	-2282.21	1009.67	2360.09	0.00	
11700.00	86.93	179.51	9784.28	-2382.06	1010.52	2459.65	0.00	
11800.00	86.93	179.51	9789.63	-2481.91	1011.38	2559.21	0.00	
11900.00	86.93	179.51	9794.98	-2581.77	1012.23	2658.77	0.00	
12000.00	86.93	179.51	9800.33	-2681.62	1013.08	2758.33	0.00	
12100.00	86.93	179.51	9805.67	-2781.47	1013.94	2857.89	0.00	
12200.00	86.93	179.51	9811.02	-2881.33	1014.79	2957.46	0.00	
12300.00	86.93	179.51	9816.37	-2981.18	1015.65	3057.02	0.00	
12400.00	86.93	179.51	9821.72	-3081.03	1016.50	3156.58	0.00	
12500.00	86.93	179.51	9827.06	-3180.89	1017.36	3256.14	0.00	
12600.00	86.93	179.51	9832.41	-3280.74	1018.21	3355.70	0.00	
12700.00	86.93	179.51	9837.76	-3380.59	1019.06	3455.26	0.00	

North Blondie 3-15 Fed Com 4H



Well: North Blondie 3-15 Fed Com 4H
County: Lea
Wellbore: Permit Plan
Design: Permit Plan #1

Geodetic System: US State Plane 1983
Datum: North American Datum 1927
Ellipsoid: Clarke 1866
Zone: 3001 - NM East (NAD83)

MD (ft)	INC (°)	AZI (°)	TVD (ft)	NS (ft)	EW (ft)	VS (ft)	DLS (°/100ft)	Comment
12800.00	86.93	179.51	9843.11	-3480.45	1019.92	3554.82	0.00	
12900.00	86.93	179.51	9848.45	-3580.30	1020.77	3654.39	0.00	
13000.00	86.93	179.51	9853.80	-3680.15	1021.63	3753.95	0.00	
13100.00	86.93	179.51	9859.15	-3780.01	1022.48	3853.51	0.00	
13200.00	86.93	179.51	9864.49	-3879.86	1023.34	3953.07	0.00	
13300.00	86.93	179.51	9869.84	-3979.71	1024.19	4052.63	0.00	
13400.00	86.93	179.51	9875.19	-4079.57	1025.04	4152.19	0.00	
13500.00	86.93	179.51	9880.54	-4179.42	1025.90	4251.76	0.00	
13600.00	86.93	179.51	9885.88	-4279.27	1026.75	4351.32	0.00	
13700.00	86.93	179.51	9891.23	-4379.12	1027.61	4450.88	0.00	
13800.00	86.93	179.51	9896.58	-4478.98	1028.46	4550.44	0.00	
13900.00	86.93	179.51	9901.93	-4578.83	1029.31	4650.00	0.00	
14000.00	86.93	179.51	9907.27	-4678.68	1030.17	4749.56	0.00	
14100.00	86.93	179.51	9912.62	-4778.54	1031.02	4849.12	0.00	
14200.00	86.93	179.51	9917.97	-4878.39	1031.88	4948.69	0.00	
14300.00	86.93	179.51	9923.32	-4978.24	1032.73	5048.25	0.00	
14400.00	86.93	179.51	9928.66	-5078.10	1033.59	5147.81	0.00	
14500.00	86.93	179.51	9934.01	-5177.95	1034.44	5247.37	0.00	
14600.00	86.93	179.51	9939.36	-5277.80	1035.29	5346.93	0.00	
14700.00	86.93	179.51	9944.71	-5377.66	1036.15	5446.49	0.00	
14800.00	86.93	179.51	9950.05	-5477.51	1037.00	5546.05	0.00	
14900.00	86.93	179.51	9955.40	-5577.36	1037.86	5645.62	0.00	
15000.00	86.93	179.51	9960.75	-5677.22	1038.71	5745.18	0.00	
15100.00	86.93	179.51	9966.10	-5777.07	1039.57	5844.74	0.00	
15200.00	86.93	179.51	9971.44	-5876.92	1040.42	5944.30	0.00	
15300.00	86.93	179.51	9976.79	-5976.78	1041.27	6043.86	0.00	
15400.00	86.93	179.51	9982.14	-6076.63	1042.13	6143.42	0.00	
15500.00	86.93	179.51	9987.49	-6176.48	1042.98	6242.99	0.00	
15600.00	86.93	179.51	9992.83	-6276.34	1043.84	6342.55	0.00	
15700.00	86.93	179.51	9998.18	-6376.19	1044.69	6442.11	0.00	
15800.00	86.93	179.51	10003.53	-6476.04	1045.55	6541.67	0.00	
15900.00	86.93	179.51	10008.88	-6575.90	1046.40	6641.23	0.00	
16000.00	86.93	179.51	10014.22	-6675.75	1047.25	6740.79	0.00	
16100.00	86.93	179.51	10019.57	-6775.60	1048.11	6840.35	0.00	
16200.00	86.93	179.51	10024.92	-6875.46	1048.96	6939.92	0.00	
16300.00	86.93	179.51	10030.26	-6975.31	1049.82	7039.48	0.00	
16400.00	86.93	179.51	10035.61	-7075.16	1050.67	7139.04	0.00	
16500.00	86.93	179.51	10040.96	-7175.02	1051.53	7238.60	0.00	
16600.00	86.93	179.51	10046.31	-7274.87	1052.38	7338.16	0.00	
16700.00	86.93	179.51	10051.65	-7374.72	1053.23	7437.72	0.00	
16800.00	86.93	179.51	10057.00	-7474.58	1054.09	7537.28	0.00	
16900.00	86.93	179.51	10062.35	-7574.43	1054.94	7636.85	0.00	
17000.00	86.93	179.51	10067.70	-7674.28	1055.80	7736.41	0.00	
17100.00	86.93	179.51	10073.04	-7774.14	1056.65	7835.97	0.00	
17200.00	86.93	179.51	10078.39	-7873.99	1057.50	7935.53	0.00	
17300.00	86.93	179.51	10083.74	-7973.84	1058.36	8035.09	0.00	
17400.00	86.93	179.51	10089.09	-8073.70	1059.21	8134.65	0.00	
17500.00	86.93	179.51	10094.43	-8173.55	1060.07	8234.22	0.00	
17600.00	86.93	179.51	10099.78	-8273.40	1060.92	8333.78	0.00	
17700.00	86.93	179.51	10105.13	-8373.26	1061.78	8433.34	0.00	
17800.00	86.93	179.51	10110.48	-8473.11	1062.63	8532.90	0.00	
17900.00	86.93	179.51	10115.82	-8572.96	1063.48	8632.46	0.00	
18000.00	86.93	179.51	10121.17	-8672.82	1064.34	8732.02	0.00	
18100.00	86.93	179.51	10126.52	-8772.67	1065.19	8831.58	0.00	
18200.00	86.93	179.51	10131.87	-8872.52	1066.05	8931.15	0.00	
18300.00	86.93	179.51	10137.21	-8972.38	1066.90	9030.71	0.00	
18400.00	86.93	179.51	10142.56	-9072.23	1067.76	9130.27	0.00	
18500.00	86.93	179.51	10147.91	-9172.08	1068.61	9229.83	0.00	
18600.00	86.93	179.51	10153.26	-9271.94	1069.46	9329.39	0.00	
18700.00	86.93	179.51	10158.60	-9371.79	1070.32	9428.95	0.00	
18800.00	86.93	179.51	10163.95	-9471.64	1071.17	9528.51	0.00	
18900.00	86.93	179.51	10169.30	-9571.49	1072.03	9628.08	0.00	
19000.00	86.93	179.51	10174.65	-9671.35	1072.88	9727.64	0.00	
19100.00	86.93	179.51	10179.99	-9771.20	1073.74	9827.20	0.00	
19200.00	86.93	179.51	10185.34	-9871.05	1074.59	9926.76	0.00	
19300.00	86.93	179.51	10190.69	-9970.91	1075.44	10026.32	0.00	
19400.00	86.93	179.51	10196.03	-10070.76	1076.30	10125.88	0.00	
19500.00	86.93	179.51	10201.38	-10170.61	1077.15	10225.45	0.00	
19600.00	86.93	179.51	10206.73	-10270.47	1078.01	10325.01	0.00	
19700.00	86.93	179.51	10212.08	-10370.32	1078.86	10424.57	0.00	

North Blondie 3-15 Fed Com 4H



Well: North Blondie 3-15 Fed Com 4H
County: Lea
Wellbore: Permit Plan
Design: Permit Plan #1

Geodetic System: US State Plane 1983
Datum: North American Datum 1927
Ellipsoid: Clarke 1866
Zone: 3001 - NM East (NAD83)

MD	INC	AZI	TVD	NS	EW	VS	DLS	Comment
(ft)	(°)	(°)	(ft)	(ft)	(ft)	(ft)	(°/100ft)	
19800.00	86.93	179.51	10217.42	-10470.17	1079.72	10524.13	0.00	
19900.00	86.93	179.51	10222.77	-10570.03	1080.57	10623.69	0.00	
20000.00	86.93	179.51	10228.12	-10669.88	1081.42	10723.25	0.00	
20100.00	86.93	179.51	10233.47	-10769.73	1082.28	10822.81	0.00	
20200.00	86.93	179.51	10238.81	-10869.59	1083.13	10922.38	0.00	
20300.00	86.93	179.51	10244.16	-10969.44	1083.99	11021.94	0.00	
20400.00	86.93	179.51	10249.51	-11069.29	1084.84	11121.50	0.00	
20500.00	86.93	179.51	10254.86	-11169.15	1085.69	11221.06	0.00	
20600.00	86.93	179.51	10260.20	-11269.00	1086.55	11320.62	0.00	
20700.00	86.93	179.51	10265.55	-11368.85	1087.40	11420.18	0.00	
20800.00	86.93	179.51	10270.90	-11468.71	1088.26	11519.75	0.00	
20900.00	86.93	179.51	10276.25	-11568.56	1089.11	11619.31	0.00	
21000.00	86.93	179.51	10281.59	-11668.41	1089.97	11718.87	0.00	
21100.00	86.93	179.51	10286.94	-11768.27	1090.82	11818.43	0.00	
21200.00	86.93	179.51	10292.29	-11868.12	1091.67	11917.99	0.00	
21300.00	86.93	179.51	10297.64	-11967.97	1092.53	12017.55	0.00	
21400.00	86.93	179.51	10302.98	-12067.83	1093.38	12117.11	0.00	
21500.00	86.93	179.51	10308.33	-12167.68	1094.24	12216.68	0.00	
21600.00	86.93	179.51	10313.68	-12267.53	1095.09	12316.24	0.00	
21700.00	86.93	179.51	10319.03	-12367.39	1095.95	12415.80	0.00	
21800.00	86.93	179.51	10324.37	-12467.24	1096.80	12515.36	0.00	
21900.00	86.93	179.51	10329.72	-12567.09	1097.65	12614.92	0.00	
22000.00	86.93	179.51	10335.07	-12666.95	1098.51	12714.48	0.00	
22087.33	86.93	179.51	10339.74	-12754.15	1099.25	12801.43	0.00	exit
22100.00	86.93	179.51	10340.42	-12766.80	1099.36	12814.04	0.00	
22167.33	86.93	179.51	10344.00	-12834.03	1099.91	12881.08	0.00	BHL

North Blondie 3-15 Fed Com 4H

1. Geologic Formations

TVD of target	10340	Pilot hole depth	N/A
MD at TD:	22167	Deepest expected fresh water	

Basin

Formation	Depth (TVD) from KB	Water/Mineral Bearing/Target Zone?	Hazards*
Rustler	860		
Salt	1300		
Base of Salt	5050		
Delaware	5320		
Cherry Canyon	6320		
Brushy Canyon	7950		
1st Bone Spring Lime	9420		
Leonard	9470		

*H2S, water flows, loss of circulation, abnormal pressures, etc.

North Blondie 3-15 Fed Com 4H

2. Casing Program

Hole Size	Csg. Size	Wt (PPF)	Grade	Conn	Casing Interval		Casing Interval	
					From (MD)	To (MD)	From (TVD)	To (TVD)
17 1/2	13 3/8	48	H40	BTC	0	885	0	885
12 1/4	9 5/8	40	J-55	BTC	0	5150	0	5150
8 3/4	5 1/2	17	P110	BTC	0	22167	0	10340

- All casing strings will be tested in accordance with Onshore Oil and Gas Order #2 IILB.1.h Must have table for contingency casing.

North Blondie 3-15 Fed Com 4H

3. Cementing Program (3-String Primary Design)

Casing	# Sks	TOC	Wt. (lb/gal)	Yld (ft ³ /sack)	Slurry Description
Surface	679	Surf	13.2	1.4	Lead: Class C Cement + additives
Int 1	571	Surf	9.0	3.3	Lead: Class C Cement + additives
	154	4650	13.2	1.4	Tail: Class H / C + additives
Int 1 Intermediate Squeeze	742	Surf	9.0	3.3	Squeeze Lead: Class C Cement + additives
	571	Surf	9.0	3.3	Lead: Class C Cement + additives
	154	4650	13.2	1.4	Tail: Class H / C + additives
Production	393	4650	9.0	3.3	Lead: Class H / C + additives
	2492	9254	13.2	1.4	Tail: Class H / C + additives

If a DV tool is ran the depth(s) will be adjusted based on hole conditions and cement volumes will be adjusted proportionally. Slurry weights will be adjusted based on estimated fracture gradient of the formation. DV tool will be set a minimum of 50 feet below previous casing and a minimum of 200 feet above current shoe. If cement is not returned to surface during the primary cement job on the surface casing string, a planned top job will be conducted immediately after completion of the primary job.

Casing String	% Excess
Surface	50%
Intermediate	30%
Production	10%

North Blondie 3-15 Fed Com 4H

4. Pressure Control Equipment (Three String Design)

BOP installed and tested before drilling which hole?	Size?	Min. Required WP	Type	✓	Tested to:
Int 1	13-5/8"	5M	Annular	X	50% of rated working pressure
			Blind Ram	X	5M
			Pipe Ram		
			Double Ram	X	
			Other*		
Production	13-5/8"	5M	Annular	X	50% of rated working pressure
			Blind Ram	X	5M
			Pipe Ram		
			Double Ram	X	
			Other*		
			Annular (5M)		
			Blind Ram		
			Pipe Ram		
			Double Ram		
			Other*		

North Blondie 3-15 Fed Com 4H

5. Mud Program (Three String Design)

Section	Type	Weight (ppg)
Surface	FW Gel	8.5-9
Intermediate	Brine	10-10.5
Production	WBM	8.5-9

Sufficient mud materials to maintain mud properties and meet minimum lost circulation and weight increase requirements will be kept on location at all times.

What will be used to monitor the loss or gain of fluid?	PVT/Pason/Visual Monitoring
---	-----------------------------

6. Logging and Testing Procedures

Logging, Coring and Testing	
X	Will run GR/CNL from TD to surface (horizontal well - vertical portion of hole). Stated logs run will be in the Completion Report and submitted to the BLM.
	No logs are planned based on well control or offset log information.
	Drill stem test? If yes, explain.
	Coring? If yes, explain.

Additional logs planned		Interval
	Resistivity	
	Density	
X	CBL	Production casing
X	Mud log	KOP to TD
	PEX	

7. Drilling Conditions

Condition	Specify what type and where?
BH pressure at deepest TVD	4839
Abnormal temperature	No

Mitigation measure for abnormal conditions. Describe. Lost circulation material/sweeps/mud scavengers.

Hydrogen Sulfide (H₂S) monitors will be installed prior to drilling out the surface shoe. If H₂S is detected in concentrations greater than 100 ppm, the operator will comply with the provisions of Onshore Oil and Gas Order #6. If Hydrogen Sulfide is encountered measured values and formations will be provided to the BLM.

N	H ₂ S is present
Y	H ₂ S plan attached.

North Blondie 3-15 Fed Com 4H

8. Other facets of operation

Is this a walking operation? Potentially

- 1 If operator elects, drilling rig will batch drill the surface holes and run/cement surface casing; walking the rig to next wells on the pad.
- 2 The drilling rig will then batch drill the intermediate sections and run/cement intermediate casing; the wellbore will be isolated with a blind flange and pressure gauge installed for monitoring the well before walking to the next well.
- 3 The drilling rig will then batch drill the production hole sections on the wells with OBM, run/cement production casing, and install TA caps or tubing heads for completions.

NOTE: During batch operations the drilling rig will be moved from well to well however, it will not be removed from the pad until all wells have production casing run/cemented.

Will be pre-setting casing? Potentially

- 1 Spudder rig will move in and batch drill surface hole.
 - a. Rig will utilize fresh water based mud to drill surface hole to TD. Solids control will be handled entirely on a closed loop basis.
- 2 After drilling the surface hole section, the spudder rig will run casing and cement following all of the applicable rules and regulations (OnShore Order 2, all COAs and NMOCD regulations).
- 3 The wellhead will be installed and tested once the surface casing is cut off and the WOC time has been reached.
- 4 A blind flange with the same pressure rating as the wellhead will be installed to seal the wellbore. Pressure will be monitored with a pressure gauge installed on the wellhead.
- 5 Spudder rig operations is expected to take 4-5 days per well on a multi-well pad.
- 6 The NMOCD will be contacted and notified 24 hours prior to commencing spudder rig operations.
- 7 Drilling operations will be performed with drilling rig. At that time an approved BOP stack will be nipped up and tested on the wellhead before drilling operations commences on each well.
 - a. The NMOCD will be contacted / notified 24 hours before the drilling rig moves back on to the pad with the pre-set surface casing.

Attachments

X Directional Plan
 Other, describe

District I
1625 N. French Dr., Hobbs, NM 88240
Phone:(575) 393-6161 Fax:(575) 393-0720
District II
811 S. First St., Artesia, NM 88210
Phone:(575) 748-1283 Fax:(575) 748-9720
District III
1000 Rio Brazos Rd., Aztec, NM 87410
Phone:(505) 334-6178 Fax:(505) 334-6170
District IV
1220 S. St Francis Dr., Santa Fe, NM 87505
Phone:(505) 476-3470 Fax:(505) 476-3462

State of New Mexico
Energy, Minerals and Natural Resources
Oil Conservation Division
1220 S. St Francis Dr.
Santa Fe, NM 87505

CONDITIONS

Action 277450

CONDITIONS

Operator: DEVON ENERGY PRODUCTION COMPANY, LP 333 West Sheridan Ave. Oklahoma City, OK 73102	OGRID: 6137
	Action Number: 277450
	Action Type: [C-103] NOI Change of Plans (C-103A)

CONDITIONS

Created By	Condition	Condition Date
pkautz	None	10/26/2023