

U.S. Department of the Interior BUREAU OF LAND MANAGEMENT

Sundry Print Reports
11/30/2023

Well Name: RED HILLS UNIT Well Location: T25S / R33E / SEC 33 / County or Parish/State: LEA /

NWNE / 32.0929692 / -103.5795927 NM

Well Number: 49H Type of Well: CONVENTIONAL GAS Allottee or Tribe Name:

WELL

Lease Number: NMNM0024368A, Unit or CA Name: Unit or CA Number:

NMNM024368A

US Well Number: 3002548456 Well Status: Approved Application for Operator: CIMAREX ENERGY

Permit to Drill COMPANY OF COLORADO

Notice of Intent

Sundry ID: 2739382

Type of Submission: Notice of Intent

Type of Action: APD Change

Date Sundry Submitted: 07/05/2023 Time Sundry Submitted: 01:34

Date proposed operation will begin: 01/01/2024

Procedure Description: Please see the attached sundry language and supporting documents regarding requested APD changes on the Red Hills 49H approved APD. The Drilling Plan has been updated to reflect the correct Production cement string procedure.

NOI Attachments

Procedure Description

RED_HILLS_49H_SUNDRY_LANGUAGE_AND_ATTACHMENTS___REV3_11_29_23_20231129110551.pdf

Conditions of Approval

Specialist Review

Red_Hills_Unit_49H_COA_20231129122956.pdf

eived by OCD: 12/6/2023 8:48:47 AM Well Name: RED HILLS UNIT

Well Location: T25S / R33E / SEC 33 /

NWNE / 32.0929692 / -103.5795927

County or Parish/State: LEA/ 2 of

NM

Well Number: 49H

Type of Well: CONVENTIONAL GAS

Allottee or Tribe Name:

Lease Number: NMNM0024368A,

NMNM024368A

Unit or CA Name:

Unit or CA Number:

US Well Number: 3002548456

Well Status: Approved Application for

Permit to Drill

Operator: CIMAREX ENERGY COMPANY OF COLORADO

Operator

I certify that the foregoing is true and correct. Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction. Electronic submission of Sundry Notices through this system satisfies regulations requiring a

Operator Electronic Signature: AMY DOEBELE Signed on: NOV 29, 2023 11:05 AM

Name: CIMAREX ENERGY COMPANY OF COLORADO

Title: Authorized Agent

Street Address: 85 S 200 E

City: VERNAL State: UT

Phone: (435) 789-1017

Email address: ADOEBELE@UINTAHGROUP.COM

Field

Representative Name: Shelly Bowen

Street Address: 6001 Deauville Blvd, 300N

City: Midland State: TN **Zip:** 79706

Phone: (432)620-1644

Email address: shelly.bowen@coterra.com

BLM Point of Contact

BLM POC Name: CHRISTOPHER WALLS BLM POC Title: Petroleum Engineer

BLM POC Phone: 5752342234 BLM POC Email Address: cwalls@blm.gov

Disposition: Approved Disposition Date: 11/29/2023

Signature: Chris Walls

Page 2 of 2

Form 3160-5 (June 2019)

UNITED STATES DEPARTMENT OF THE INTERIOR BUREAU OF LAND MANAGEMENT

FORM APPROVE	Ð
OMB No. 1004-01	37
Expires: October 31,	2021

5.	Lease	Serial	No

DOK	EAU OF LAND MANAGEMENT					
Do not use this t	OTICES AND REPORTS ON Worm for proposals to drill or to Use Form 3160-3 (APD) for suc	o re-enter an	6. If Indian, Allottee or Tribe Name			
	TRIPLICATE - Other instructions on page		7. If Unit of CA/Agree	ment, Name and/or No.		
1. Type of Well	HIPLICATE - Other Instructions on pag	le 2		,		
Oil Well Gas W	Vell Other		8. Well Name and No.			
2. Name of Operator			9. API Well No.			
	21- DL N -	(include area code)	10. Field and Pool or E	Avaloratory Aran		
3a. Address	30. Phone No.	(inciuae area coae)	10. Field and Foot of E	xpioratory Area		
4. Location of Well (Footage, Sec., T., K	.,M., or Survey Description)		11. Country or Parish,	State		
12. CHE	CK THE APPROPRIATE BOX(ES) TO IN	DICATE NATURE OF NO	TICE, REPORT OR OTH	ER DATA		
TYPE OF SUBMISSION		TYPE OF A	CTION			
Notice of Intent	Acidize Deep	pen Pro	oduction (Start/Resume)	Water Shut-Off		
Notice of intent	Alter Casing Hydr	raulic Fracturing Re	clamation	Well Integrity		
Subsequent Report			complete	Other		
Final Abandonment Notice		=	mporarily Abandon			
	Convert to Injection Plug peration: Clearly state all pertinent details, i		nter Disposal			
14. I hereby certify that the foregoing is	true and correct. Name (Printed/Typed)					
		Title				
Signature		Date				
	THE SPACE FOR FED	ERAL OR STATE O	FICE USE			
Approved by						
		Title		Pate		
	ned. Approval of this notice does not warrar equitable title to those rights in the subject leduct operations thereon.	t or				
	3 U.S.C Section 1212, make it a crime for an ents or representations as to any matter with		illfully to make to any dep	partment or agency of the United States		

(Instructions on page 2)

GENERAL INSTRUCTIONS

This form is designed for submitting proposals to perform certain well operations and reports of such operations when completed as indicated on Federal and Indian lands pursuant to applicable Federal law and regulations. Any necessary special instructions concerning the use of this form and the number of copies to be submitted, particularly with regard to local area or regional procedures and practices, are either shown below, will be issued by or may be obtained from the local Federal office.

SPECIFIC INSTRUCTIONS

Item 4 - Locations on Federal or Indian land should be described in accordance with Federal requirements. Consult the local Federal office for specific instructions.

Item 13: Proposals to abandon a well and subsequent reports of abandonment should include such special information as is required by the local Federal office. In addition, such proposals and reports should include reasons for the abandonment; data on any former or present productive zones or other zones with present significant fluid contents not sealed off by cement or otherwise; depths (top and bottom) and method of placement of cement plugs; mud or other material placed below, between and above plugs; amount, size, method of parting of any casing, liner or tubing pulled and the depth to the top of any tubing left in the hole; method of closing top of well and date well site conditioned for final inspection looking for approval of the abandonment. If the proposal will involve **hydraulic fracturing operations**, you must comply with 43 CFR 3162.3-3, including providing information about the protection of usable water. Operators should provide the best available information about all formations containing water and their depths. This information could include data and interpretation of resistivity logs run on nearby wells. Information may also be obtained from state or tribal regulatory agencies and from local BLM offices.

NOTICES

The privacy Act of 1974 and the regulation in 43 CFR 2.48(d) provide that you be furnished the following information in connection with information required by this application.

AUTHORITY: 30 U.S.C. 181 et seq., 351 et seq., 25 U.S.C. 396; 43 CFR 3160.

PRINCIPAL PURPOSE: The information is used to: (1) Evaluate, when appropriate, approve applications, and report completion of subsequent well operations, on a Federal or Indian lease; and (2) document for administrative use, information for the management, disposal and use of National Resource lands and resources, such as: (a) evaluating the equipment and procedures to be used during a proposed subsequent well operation and reviewing the completed well operations for compliance with the approved plan; (b) requesting and granting approval to perform those actions covered by 43 CFR 3162.3-2, 3162.3-3, and 3162.3-4; (c) reporting the beginning or resumption of production, as required by 43 CFR 3162.4-1(c)and (d) analyzing future applications to drill or modify operations in light of data obtained and methods used.

ROUTINE USES: Information from the record and/or the record will be transferred to appropriate Federal, State, local or foreign agencies, when relevant to civil, criminal or regulatory investigations or prosecutions in connection with congressional inquiries or to consumer reporting agencies to facilitate collection of debts owed the Government.

EFFECT OF NOT PROVIDING THE INFORMATION: Filing of this notice and report and disclosure of the information is mandatory for those subsequent well operations specified in 43 CFR 3162.3-2, 3162.3-3, 3162.3-4.

The Paperwork Reduction Act of 1995 requires us to inform you that:

The BLM collects this information to evaluate proposed and/or completed subsequent well operations on Federal or Indian oil and gas leases.

Response to this request is mandatory.

The BLM would like you to know that you do not have to respond to this or any other Federal agency-sponsored information collection unless it displays a currently valid OMB control number.

BURDEN HOURS STATEMENT: Public reporting burden for this form is estimated to average 8 hours per response, including the time for reviewing instructions, gathering and maintaining data, and completing and reviewing the form. Direct comments regarding the burden estimate or any other aspect of this form to U.S. Department of the Interior, Bureau of Land Management (1004-0137), Bureau Information Collection Clearance Officer (WO-630), 1849 C St., N.W., Mail Stop 401 LS, Washington, D.C. 20240

(Form 3160-5, page 2)

Additional Information

Location of Well

 $0. \, SHL: \, NWNE \, / \, 527 \, FNL \, / \, 2022 \, FWL \, / \, TWSP: \, 25S \, / \, RANGE: \, 33E \, / \, SECTION: \, 33 \, / \, LAT: \, 32.0929692 \, / \, LONG: \, -103.5795927 \, (TVD: \, 0 \, feet, \, MD: \, 0 \, feet \,)$ $PPP: \, NWNE \, / \, 2640 \, FSL \, / \, 2430 \, FWL \, / \, TWSP: \, 25S \, / \, RANGE: \, 33E \, / \, SECTION: \, 33 \, / \, LAT: \, 32.08709 \, / \, LONG: \, -103.581067 \, (TVD: \, 9940 \, feet, \, MD: \, 11900 \, feet \,)$ $BHL: \, SESW \, / \, 100 \, FSL \, / \, 1590 \, FWL \, / \, TWSP: \, 26S \, / \, RANGE: \, 33E \, / \, SECTION: \, 4 \, / \, LAT: \, 32.0656775 \, / \, LONG: \, -103.581113 \, (TVD: \, 9940 \, feet, \, MD: \, 19690 \, feet \,)$



Cimarex Energy Company of Colorado respectfully requests the following drilling and directional changes be made to the existing, approved APD for the following well:

RED HILLS UNIT 49H

The AFMSS Location Table does not match the points in the C-102 & Directional Plan attached to the approved APD 527' FNL 1,590' FWL, NENW (C-102) 10,236 MD & 9,940' TVD (DIR PLAN)

Exit point #1 was called out at 0' FNL of Section 4, which would not account for the bottom lateral portion of the producing wellbore.

APPROVED APD

Wellbore	NS-Foot	NS Indicator		EW Indicator	Twsp	Range	Sec	Aliquot/Lot/Tr ack	Latitude	Longitude	County	State	Meridian	Lease Type	Lease Number	Elevation	TVD	MD
SHL #1 Leg	527	FNL	2022	FWL	25S	33E	33	NWNE	32.0929692	-103.5795927	LEA	NEWMEXICO	NEWMEXICO	F	NMNM0024368A	3361	0	0
KOP #1 Leg	527	FNL	1609	FWL	25S	33E	33	NWNE	32.092963	-103.578342	LEA	NEWMEXICO	NEWMEXICO	F	NMNM0024368A	-6101	9486	9462
PPP #1-1 Leg	2640	FSL	2430	FWL	25S	33E	33	NWNE	32.08709	-103.581067	LEA	NEWMEXICO	FIRSTPRIN	Ŀ	NMNM0005792	-6579	11900	9940
EXIT #1 Leg	0	FNL	1590	FWL	26S	33E	4	NENW	32.0798194	-103.5806139	LEA	NEWMEXICO	FIRSTPRIN	F	NMNM089425	-6579	14500	9940
BHL #1 Leg	100	FSL	1590	FWL	26S	33E	4	SESW	32.0656775	-103.581113	LEA	NEWMEXICO	FIRSTPRIN	F	NMNM089425	-6579	19690	9940

PROPOSED CHANGES

Wellbore	NS-Foot	NS Indicator	EW-Foot	EW Indicator	Twsp	Range	Sec	Aliquot/Lot/Tr ack	Latitude	Longitude	County	State	Meridian	Lease Type	Lease Number	Elevation	TVD	MD
SHL #1 Leg	347	FNL	1942	FWL	25S	33E	33	NENW	32.093341	-103.579508	LEA	NEWMEXICO	NEWMEXICO	F	NMNM0024368A	3361	0	0
KOP #1 Leg	105	FNL	872	FWL	25S	33E	33	NWNW	32.09402658	-103.58295706	LEA	NEWMEXICO	NEWMEXICO	F	NMNM0024368A	-7537	10788	10898
PPP #1-1 Leg	100	FNL	330	FWL	25S	33E	33	NWNW	32.094030	-103.584713	LEA	NEWMEXICO	NEWMEXICO	F	NMNM0024368A	-8587	11380	11948
PPP #1-2 Leg	2640	FNL	331	FWL	25S	33E	33	NWSW	32.087049	-103.584712	LEA	NEWMEXICO	NEWMEXICO	F	NMNM0005792A	-8587	11380	14488
PPP #1-3 Leg	1320	FSL	332	FWL	25S	33E	33	swsw	32.083420	-103.584712	LEA	NEWMEXICO	NEWMEXICO	F	NMNM0005792	-8587	11380	15808
PPP #1-4 Leg	0	FNL	332	FWL	25S	33E	4	NWNW	32.079791	-103.584711	LEA	NEWMEXICO	NEWMEXICO	F	NMNM089425	-8587	11380	17128
EXIT #1 Leg	100	FSL	330	FWL	25S	33E	4	swsw	32.065561	-103.58471	LEA	NEWMEXICO	NEWMEXICO	F	NMNM089425	-8587	11380	21669
BHL #1 Leg	100	FSL	330	FWL	25S	33E	4	swsw	32.065561	-103.58471	LEA	NEWMEXICO	NEWMEXICO	F	NMNM089425	-8587	11380	21669

Drilling Plan amendments:

Sec 1 - Geologic Formations

Geologic formation depths have all changed. Please see attached drilling plans.

Section 2 - Blowout Prevention

12.25" hole size – Min required WP 2M 8.75" hole size – Min required WP 3M 6" hole size – Min required WP 5M

Section 3 - Casing

Surface casing changed from 989' MD to 976' MD.

Intermediate casing string changed from 4,912' MD to 4,980' MD.

Tapered production string changed from 5.5" & 9,486' MD to 7" & 11,648' MD (L-80 & LT&C) with 7" P-110 & BT&C) ran from 10,898' to 11,648' MD.

A new 4 ½" (P-110, BT&C) completion liner was added from 10,898 to 21,669' MD.

Section 4 - Cement

Surface cement sacks changed from 417 lead/195 tail to 410 lead/195 tail.

Intermediate cement sacks changed from 933 lead/296 tail to 948 lead/287 tail. Tail yield changed from 1.3 to 1.36.

Tapered production string changed from multiple production string cement segments to one production string segment consisting of:

Lead: 376 sx Tuned Light + LCM cement / 10.30 density & 3.64 yield.

Tail: 125 sx Class C + retarder cement / 14.80 density & 1.36 yield. TOC @ 4,780′

Tail: 127 sx Class C + LCM cement / 14.80 density & 1.34 yield. @ 4,780'.

A completion liner string was added consisting of 744 sx, 14.20 density & 1.30 yield (Tail: 50:50 (Poz:H) + Salt + Bentonite + Fluid Loss + Dispersant + SMS) TOC @ 11,448′.

Section 5 - Circulating Medium

Changed from:

0' to 989 - Spud Mud - 8.3 Min/8.8 Max 989' to 4,912' - Salt Saturated - 9.7 Min/10.2 Max

4,912' to 19,690' - Cut Brine - 8.5 Min/9 Max

To:

0' to 976' Fresh Water 7.83 Min/8.33 Max 976' to 4,980' Brine Water 9.83 Min/10.33 Max

4,980' to 11,648' Cut Brine or OBM 8.50 min/ 9.00 Max

11,648' to 21,669' OBM 9.20 min/ 9.70 Max

Section 7 - Pressure

Anticipated BHP changed from 4,651' to 5,740'.

Other Variances:

Cimarex requests to perform offline cementing. OLC procedure as follows: 1. Land casing on solid body mandrel hanger. Engage pack off and lock ring 2. Install BPV. 3. Skid rig. 4. Check for pressure and remove BPV. 5. Circulate down casing, taking returns through casing valves. 6. Pump lead and tail cement. 7. Displace cement and bump the plug. 8. Ensure floats are holding pressure. 9. RD cement crew. 10. Install BPV and TA cap.

Cimarex requests permission to skid the rig to the next well on the pad to begin operations instead of waiting 8 hours for surface cement to harden on this well. Surface cement will be pumped, and we will ensure floats hold, do a green cement test and then skid to the next well on pad. We will not perform any operations on this well until at least 8 hours and when both tail and lead slurry reach 500 psi. The mandrel hanger is made up on the last joint of 13 5/8" casing and then lowered down with and landing joint. It is then lowered down until the mandrel contacts the landing ring which is pre-welded to the conductor pipe. At this point the 13 5/8" casing is entirely supported by the conductor pipe via the landing ring/mandrel and is independent from the rig. This allows us to walk the rig away from the well and begin work on the next well while the cement is hardening. There is no way for the casing to be moved or knocked off center since it is hanging from the landing ring.

1. Geological Formations

TVD of target 11,380 Pilot Hole TD N/A

MD at TD 21,669 Deepest expected fresh water

Formation	Depth (TVD) from KB	Water/Mineral Bearing/Target Zone	Hazards
RUSTLER	926	N/A	
TOP SALT	1295	N/A	
BASE SALT	4900	N/A	
TOP DELAWARE SANDS	4930	N/A	
CHERRY CANYON	5960	N/A	
BRUSHY CANYON	7480	Hydrocarbons	
BASAL BRUSHY CANYON	8855	Hydrocarbons	
BONE SPRING LIME	9040	Hydrocarbons	
LEONARD	9065	Hydrocarbons	
AVALON	9330	Hydrocarbons	
1ST BONE SPRING SAND	10020	Hydrocarbons	
2ND BONE SPRING SAND	10575	Hydrocarbons	
3RD BONE SPRING	11380	Hydrocarbons	

2. Casing Program

Hole Size	Casing Depth From	Casing Depth To	Setting Depth TVD	Casing Size	Weight (lb/ft)	Grade	Conn.	SF Collapse	SF Burst	SF Tension
17 1/2	0	976	976	13-3/8"	48.00	H-40	ST&C	1.75	4.09	6.87
12 1/4	0	4980	4980	9-5/8"	40.00	HCK-55	LT&C	1.42	1.48	2.82
8 3/4	0	10898	10898	7"	29.00	P-110	LT&C	1.67	2.20	2.42
8 3/4	10898	11648	11380	7"	29.00	P-110	BT&C	1.60	2.11	66.46
8 3/4	10898	21669	11380	4-1/2"	11.60	P-110	BT&C	1.32	1.87	65.64
					BLM	Minimum Sa	afety Factor	1.125	1	1.6 Dry 1.8 Wet

TVD was used on all calculations.

All casing strings will be tested in accordance with Onshore Oil and Gas Order #2 III.B.1.h

Cimarex Energy Co., Red Hills Unit 49H

	Y or N
Is casing new? If used, attach certification as required in Onshore Order #1	Υ
Does casing meet API specifications? If no, attach casing specification sheet.	Υ
Is premium or uncommon casing planned? If yes attach casing specification sheet.	N
Does the above casing design meet or exceed BLM's minimum standards? If not provide justification (loading assumptions, casing design criteria).	Υ
Will the intermediate pipe be kept at a minimum 1/3 fluid filled to avoid approaching the collapse pressure rating of the casing?	Υ
Is well located within Capitan Reef?	N
If yes, does production casing cement tie back a minimum of 50' above the Reef?	N
Is well within the designated 4 string boundary.	N
Is well located in SOPA but not in R-111-P?	N
If yes, are the first 2 strings cemented to surface and 3rd string cement tied back 500' into previous casing?	N
Is well located in R-111-P and SOPA?	N
If yes, are the first three strings cemented to surface?	N
Is 2nd string set 100' to 600' below the base of salt?	N
Is well located in high Cave/Karst?	N
If yes, are there two strings cemented to surface?	N
(For 2 string wells) If yes, is there a contingency casing if lost circulation occurs?	N
Is well located in critical Cave/Karst?	N
If yes, are there three strings cemented to surface?	N
Is AC Report included?	Y

3. Cementing Program

Casing			Yld ft3/sack	H2O gal/sk	500# Comp. Strength (hours)	Slurry Description
Surface	410	13.50	1.72	9.15	15.5	Lead: Class C + Bentonite
	195	14.80	1.34	6.32	9.5	Tail: Class C + LCM
Intermediate	948	12.90	1.88	9.65	12	Lead: 35:65 (Poz:C) + Salt + Bentonite
	287	14.80	1.36	6.57	9.5	Tail: Class C + Retarder
Production	376	10.30	3.64	22.18		Lead: Tuned Light + LCM
	127	14.80	1.34	6.32	9.5	Tail: Class C + LCM
Completion System 2620 14.20 1.30 5.86 14:30 Tail: 50:50 (Poz:H) + Salt + Bentonite +		Tail: 50:50 (Poz:H) + Salt + Bentonite + Fluid Loss + Dispersant + SMS				
		-	-	-		

Casing String	тос	% Excess
Surface	0	42
Intermediate	0	49
Production	4780	25
Completion System	11448	10

Cimarex request the ability to perform casing integrity tests after plug bump of cement job.

4. Pressure Control Equipment

A variance is requested for the use of a diverter on the surface casing. See attached for schematic.

BOP installed and tested before drilling which hole?	Size	Min Required WP	Туре		Tested To
12 1/4	13 5/8	2M	Annular	Х	50% of working pressure
			Blind Ram		
			Pipe Ram		2M
			Double Ram	Х	
			Other		
8 3/4	13 5/8	3М	Annular	Х	50% of working pressure
			Blind Ram		
			Pipe Ram		3M
			Double Ram	Х	
			Other		
			Annular	Х	50% of working pressure
			Blind Ram		
			Pipe Ram	Х	5M
			Double Ram	Х	
			Other		

BOP/BOPE will be tested by an independent service company to 250 psi low and the high pressure indicated above per Onshore Order 2 requirements. The System may be upgraded to a higher pressure but still tested to the working pressure listed in the table above. If the system is upgraded all the components installed will be functional and tested.

Pipe rams will be operationally checked each 24 hour period. Blind rams will be operationally checked on each trip out of the hole. These checks will be noted on the daily tour sheets. Other accessories to the BOP equipment will include a Kelly cock and floor safety valve (inside BOP) and choke lines and choke manifold. See attached schematics.

Formation integrity test will be performed per Onshore Order #2.

On Exploratory wells or on that portion of any well approved for a 5M BOPE system or greater, a pressure integrity test of each casing shoe shall be performed. Will be tested in accordance with Onshore Oil and Gas Order #2 III.B.1.i.

A variance is requested for the use of a flexible choke line from the BOP to Choke Manifold. See attached for specs and hydrostatic test chart.

N Are anchors required by manufacturer?

5. Mud Program

Depth	Туре	Weight (ppg)	Viscosity	Water Loss
0' to 976'	Fresh Water	7.83 - 8.33	28	N/C
976' to 4980'	Brine Water	9.83 - 10.33	30-32	N/C
4980' to 11648'	Cut Brine or OBM	8.50 - 9.00	27-70	N/C
11948' to 21669'	ОВМ	9.20 - 9.70	50-70	N/C

Sufficient mud materials to maintain mud properties and meet minimum lost circulation and weight increase requirements will be kept on location at all times.

What will be used to monitor the loss or gain of fluid?	PVT/Pason/Visual Monitoring

6. Logging and Testing Procedures

Logg	Logging, Coring and Testing									
Х	Will run GR/CNL fromTD to surface (horizontal well – vertical portion of hole). Stated logs run will be in the Completion Report and submitted to the BLM.									
	No logs are planned based on well control or offset log information.									
	Drill stem test?									
	Coring?									

Additional Logs Planned	Interval

7. Drilling Conditions

Condition	
BH Pressure at deepest TVD	5740 psi
Abnormal Temperature	No

Hydrogen Sulfide (H2S) monitors will be installed prior to drilling out the surface shoe. If H2S is detected in concentrations greater than 100 ppm, the operator will comply with the provisions of Onshore Oil and Gas Order #6. If Hydrogen Sulfide is encountered, measured values and formations will be provided to the BLM.

X H2S is present

X H2S plan is attached

8. Other Facets of Operation

9. Wellhead

A multi-bowl wellhead system will be utilized.

After running the 13-3/8" surface casing, a 13 5/8" BOP/BOPE system with a minimum working pressure of 5000 psi will be installed on the wellhead system and will be pressure tested to 250 psi low followed by a 5000 psi test. Annular will be tested to 50% of working pressure. The pressure test will be repeated at least every 30 days, as per Onshore Order No. 2.

The multi-bowl wellhead will be installed by vendor's representative. A copy of the installation instructions has been sent to the BLM field office.

The wellhead will be installed by a third-party welder while being monitored by the wellhead vendor representative.

All BOP equipment will be tested utilizing a conventional test plug. Not a cup or J-packer type.

A solid steel body pack-off will be utilized after running and cementing the intermediate casing. After installation the pack-off and lower flange will be pressure tested to 5000 psi.

A solid steel body pack-off will be utilized after running and cementing the production casing. After installation the pack-off and lower flange will be pressure tested to 5000 psi.

All casing strings will be tested as per Onshore Order No.2 to atleast 0.22 psi/ft or 1,500 whichever is greater and not to exceed 70% of casing burst.

If well conditions dictate conventional slips will be set and BOPE will be tested to appropriate pressures based on permitted pressure requirements.

10. Other Variances

Cimarex requests to perform offline cementing. OLC procedure as follows: 1. Land casing on solid body mandrel hanger. Engage pack off and lock ring 2. Install BPV. 3. Skid rig. 4. Check for pressure and remove BPV. 5. Circulate down casing, taking returns through casing valves. 6. Pump lead and tail cement. 7. Displace cement and bump the plug. 8. Ensure floats are holding pressure. 9. RD cement crew. 10. Install BPV and TA cap.

Cimarex requests permission to skid the rig to the next well on the pad to begin operations instead of waiting 8 hours for surface cement to harden on this well. Surface cement will be pumped, and we will ensure floats hold, do a green cement test and then skid to the next well on pad. We will not perform any operations on this well until at least 8 hours and when both tail and lead slurry reach 500 psi. The mandrel hanger is made up on the last joint of 13 5/8" casing and then lowered down with and landing joint. It is then lowered down until the mandrel contacts the landing ring which is pre-welded to the conductor pipe. At this point the 13 5/8" casing is entirely supported by the conductor pipe via the landing ring/mandrel and is independent from the rig. This allows us to walk the rig away from the well and begin work on the next well while the cement is hardening. There is no way for the casing to be moved or knocked off center since it is hanging from the landing ring.

<u>District I</u> 1625 N. French Dr., Hobbs, NM 88240 Phone: (575) 393-6161 Fax: (575) 393-0720

District II

Strict II

Phone: (575) 748-1283 Fax: (575) 748-9720

Pictoriat III District III 1000 Rio Brazos Road, Aztec, NM 87410 Phone: (505) 334-6178 Fax: (505) 334-6170

District IV 1220 S. St. Francis Dr., Santa Fe, NM 87505 Phone: (505) 476-3460 Fax: (505) 476-3462

State of New Mexico Energy, Minerals & Natural Resources Department OIL CONSERVATION DIVISION 1220 South St. Francis Dr. Santa Fe, NM 87505

Form C-102 Revised August 1, 2011 Submit one copy to appropriate District Office

MENDED REPORT

WELL LOCATION AND ACREAGE DEDICATION PLAT

¹ API Number 30-025-4845	² Pool Code 97741	NE SPRIN	
⁴ Property Code 300545		roperty Name HILLS UNIT	⁶ Well Number 49H
⁷ ogrid №. 162683		perator Name EX ENERGY CO.OF COLORADO	⁹ Elevation 3364.1'


¹⁰ Surface Location

- 1	UL or lot no.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County
١	C	33	25S	33E		347	NORTH	1942	WEST	LEA

"Bottom Hole Location If Different From Surface

UL or lot no. M	Section 4	Township 26S	Range 33E	Lot Idn	Feet from the 100	North/South line SOUTH	Feet from the 330	East/West line WEST	County LEA
12 Dedicated Acre 320	es 13 ,	Joint or Infill	14 Conso	lidation Code	15 Order No.				

No allowable will be assigned to this completion until all interests have been consolidated or a non-standard unit has been approved by the division.



17 OPERATOR **CERTIFICATION**

I hereby certify that the information contained herein is true and complete to the best of my knowledge and belief, and that this organization either owns a working interest or unleased mineral interest in the land including unleased mineral interest in the land including the proposed bottom hole location or has a right to drill this well at this location pursuant to a contract with an owner of such a mineral or working interest, or to a voluntary pooling agreement or a compulsory pooling order heretofore entered by the division.

Brittany Gardan 6/6/2023 Signature

Brittany Gordon

Printed Nam

brittany.gordon@coterra.com

18 SURVEYOR CERTIFICATION

I hereby certify that the well location shown on this plat was plotted from field notes of actual surveys made by me or under my supervision, and that the same is true and correct to the best of my belief.

May 05, 2017

Signature and Seal of Professional Surveyor:



Date of Survey



2000

SCALE

DRAWN BY: R.J. 03-19-18

REV: 4 N.D.T. 04-25-23 (SHL MOVE)

= SURFACE HOLE LOCATION = LPP/LANDING POINT/ FIRST TAKE POINT

S00°09'48"E

S00°09'48"E

1.5

- BOTTOM HOLE LOCATION/
- NOTE:

 Distances referenced on plat to
- section lines are perpendicular. Basis of Bearing is a Transverse Mercator Projection with a Central Meridian of W103°53'00"

LAST TAKE POINT

SECTION CORNER LOCATED

Released to Imaging: 1/22/2024 11:22:02

1320.32

1320.32

Received by OCD: 12/6/2023 8:48:47 AM

Page 16 of 27

Geologic Prognosis



	Wall Information					Contact Informat	i a n
Wall Names Pad Hills Hait 40H	Well Information				Jonny Blake	Contact Informat	ion
Well Name: Red Hills Unit 49H		County: Lea			Jenny Blake	1 7000	
API #:	_	State: New Mexico			Office: (432) 57		
<u>Dev/Exp:</u> Development		ield:			Cell: (281) 639-		
	Surface Hole Inforn				Email: Jenny.Bla	ake@coterra.com	
Footages:	Section:	Township:	Range:	Direction			
347' FNL / 1942' FWL	33	25S	33E	N-S	Staci Mueller		
	Bottom Hole Inforn	nation			Office: (432) 57	1-7898	
Footages:	Section:	Township:	Range:		Cell: (406) 794-2	2287	
100' FSL / 330' FWL	4	26S	33E		Email: Staci.Mu	eller@coterra.com	
		Target In	formation				
Harkey A Shale	L	anding TVD: 11,380'		TD TVD: 11,380'			
Generated By:	Jenny Blake		Date Generated:	5/17/2023			
Est. GL Elevation:	3367			-			
Est. KB above GL	23		Rig:				
Est. KB Elevation:	3390		J				
Horizon	TVD top	TVD base	SSTVD top	Thickness	Lithology	Mineral Resource	Comments
Rustler	926	1295	2629	369	Anhydrite	Useable Water	
Top Salt/Salado	1295	4900	1360	3605	Halite	N/A	
Base Salt/Lamar	4900	4930	-1021	30	Shale	N/A	
Top Delaware Sands/Bell Canyon	4930	5960	-1067	1030	Sandstone	Natural gas, oil	_
Cherry Canyon	5960	7480	-2053	1520	Sandstone	Natural gas, oil	
Brushy Canyon	7480	8855	-4090	1375	Sandstone	Natural gas, oil	_
Basal Brushy Canyon	8855	9040	-5465	185	Sanastone	Tracarar gas, on	Hardline 100'
Bone Spring Lime	9040	9065	-5015	25	Limestone	N/A	FSL/100' FNL & 33
Leonard/Avalon Sand	9065	9330	-5115	265	Shale	Natural gas, oil	FWL/FEL
Avalon Shale	9330	10020	-5491	690	Shale	Natural gas, oil	
1st Bone Spring Sand	10020	10575	-6111	555		Natural gas, oil	
2nd Bone Spring Sand	10575	11010	-6434	435	Sandstone	Natural gas, oil	_
3rd Bone Spring Carbonate	11010	11380	-6434	370	Sandstone	Natural gas, oil	
3rd Bone Spring Carb/Harkey Target	11,380		-7990		Sanastone	rvacarar gas, on	
ora bone spring early markey ranger	11,300		7550				
Potential Geologic / Drilling Hazards: N/A							
Type Log:	30025351120000						
Offset Injection Wells:							
·							
Open Hole Logs:	n/a						
Service Provider:	, -						
Ops Contact:							
Sales Contact:							
Log Type:							
208 1960							
Mudlogging Vendor:	n/2						
widdiogging vendor:	τιγ α						

Schlumberger

Coterra Red Hills Unit 49H Rev1 kFc 24May23 Proposal Geodetic Report

Def Plan

Report Date:
Client:
Field:
Structure / Slot:
Workenboi:
UBH1 / AP#:
Survey Name:
Survey Nate:
Torr / AHD / DDI / ERD Ratio:
Coordinate Reference System:
Location Lat / Long:
Location Cat / WE / YX:
CRS Grid Convergence Angle:
Grid Scale Factor:
Version / Patch:

May 24, 2023 - 04:21 PM (UTC 0) COTERRA NNL Lea County (NAD 83) Coterra Red Hills Unit Pad 47-50 / Red Hills Unit 49H Red Hills Unit 49H Red Hills Unit 49H Unknown / Unknown Coterra Red Hills Unit 49H Rev1 kFc 24May 23 May 24, 2023 May 24, 2023 May 24, 2023 May 24, 2023 May 26, 2023 May 26

Comments	MD (ft)	Incl (°)	Azim (°)	TVD (ft)	TVDSS (ft)	VSEC (ft)	NS (ft)	EW (ft)	Northing (ftUS)	Easting (ftUS)	Latitude (°)	Longitude (°)	DLS (°/100ft)	BR (°/100ft)	TR (°/100ft)
SHL [347' FNL, 1942' FWL]	0.00 100.00	0.00	282.75 282.75	0.00 100.00	-3,387.10 -3,287.10	0.00	0.00 0.00	0.00	398,510.05 398,510.05	774,780.38 774,780.38	32.09334062 32.09334062	-103.57950765 -103.57950765	0.00	0.00	0.00
	200.00 300.00	0.00	282.75 282.75	200.00 300.00	-3,187.10 -3,087.10	0.00	0.00	0.00	398,510.05 398,510.05	774,780.38 774,780.38	32.09334062 32.09334062	-103.57950765 -103.57950765	0.00 0.00	0.00	0.00
	400.00 500.00	0.00	282.75 282.75	400.00 500.00	-2,987.10 -2,887.10	0.00	0.00	0.00	398,510.05 398,510.05	774,780.38 774,780.38	32.09334062 32.09334062	-103.57950765	0.00	0.00	0.00
	600.00	0.00	282.75	600.00	-2,787.10	0.00	0.00	0.00	398,510.05	774,780.38	32.09334062	-103.57950765	0.00	0.00	0.00
	700.00 800.00	0.00	282.75 282.75	700.00 800.00	-2,687.10 -2,587.10	0.00	0.00	0.00	398,510.05 398,510.05	774,780.38 774,780.38	32.09334062 32.09334062	-103.57950765	0.00 0.00	0.00	0.00
Rustler	900.00 926.00	0.00	282.75 282.75	900.00 926.00	-2,487.10 -2,461.10	0.00	0.00	0.00	398,510.05 398.510.05	774,780.38 774,780.38	32.09334062 32.09334062	-103.57950765 -103.57950765	0.00	0.00	0.00
	1,000.00 1,100.00	0.00	282.75 282.75	1,000.00 1,100.00	-2,387.10 -2,287.10	0.00	0.00	0.00	398,510.05 398,510.05	774,780.38 774,780.38	32.09334062	-103.57950765 -103.57950765	0.00	0.00	0.00
	1,200.00	0.00	282.75	1,200.00	-2,187.10	0.00	0.00	0.00	398,510.05	774,780.38	32.09334062	-103.57950765	0.00	0.00	0.00
Salado	1,295.00 1,300.00	0.00	282.75 282.75	1,295.00 1,300.00	-2,092.10 -2,087.10	0.00	0.00	0.00	398,510.05 398,510.05	774,780.38 774,780.38	32.09334062	-103.57950765 -103.57950765	0.00 0.00	0.00	0.00 0.00
	1,400.00 1,500.00	0.00	282.75 282.75	1,400.00 1.500.00	-1,987.10 -1,887.10	0.00	0.00	0.00	398,510.05 398.510.05	774,780.38 774,780.38		-103.57950765 -103.57950765	0.00	0.00	0.00
Nudge, Build 2°/100ft	1,600.00 1,700.00	0.00 2.00	282.75 282.75	1,600.00 1,699.98	-1,787.10 -1,687.12	0.00 -0.40	0.00 0.39	0.00 -1.70	398,510.05 398,510.44	774,780.38 774,778.68	32.09334062 32.09334171	-103.57950765 -103.57951314	0.00 2.00	0.00 2.00	0.00 0.00
	1,800.00	4.00	282.75	1,799.84	-1,587.26	-1.59	1.54	-6.81	398,511.59	774,773.57	32.09334498	-103.57952960	2.00	2.00	0.00
	1,900.00 2,000.00	6.00 8.00	282.75 282.75	1,899.45 1,998.70	-1,487.65 -1,388.40	-3.57 -6.34	3.46 6.15	-15.31 -27.19	398,513.51 398,516.20	774,765.07 774,753.19		-103.57955700 -103.57959532	2.00 2.00	2.00 2.00	0.00
	2,100.00 2,200.00	10.00 12.00	282.75 282.75	2,097.47 2,195.62	-1,289.63 -1,191.48	-9.90 -14.24	9.60 13.82	-42.45 -61.06	398,519.65 398,523.86	774,737.93 774,719.32	32.09336783 32.09337976	-103.57964450 -103.57970449	2.00 2.00	2.00 2.00	0.00
Hold	2,200.11 2,300.00	12.00 12.00	282.75 282.75	2,195.73 2,293.44	-1,191.37 -1.093.66	-14.25 -18.97	13.82 18.40	-61.08 -81.34	398,523.87 398,528.45	774,719.30 774,699.04	32.09337978		2.00 0.00	2.00	0.00
	2,400.00	12.00	282.75	2,391.25	-995.85	-23.70	22.99	-101.62	398,533.04	774,678.76	32.09340577	-103.57983526	0.00	0.00	0.00
	2,500.00 2,600.00	12.00 12.00	282.75 282.75	2,489.06 2,586.88	-898.04 -800.22	-28.43 -33.16	27.58 32.17	-121.91 -142.19	398,537.63 398,542.22	774,658.48 774,638.20	32.09341877 32.09343178	-103.57990065 -103.57996603	0.00 0.00	0.00	0.00 0.00
	2,700.00 2.800.00	12.00 12.00	282.75 282.75	2,684.69 2,782.51	-702.41 -604.59	-37.89 -42.62	36.76 41.35	-162.47 -182.75	398,546.81 398.551.40	774,617.91 774,597.63	32.09344478	-103.58003142 -103.58009680	0.00	0.00	0.00
	2,900.00	12.00	282.75	2,880.32	-506.78	-47.36	45.94	-203.04	398,555.99	774,577.35	32.09347079	-103.58016219	0.00	0.00	0.00
	3,000.00 3,100.00	12.00 12.00	282.75 282.75	2,978.13 3,075.95	-408.97 -311.15	-52.09 -56.82	50.53 55.12	-223.32 -243.60	398,560.58 398,565.17	774,557.07 774,536.79	32.09349679		0.00 0.00	0.00	0.00 0.00
	3,200.00 3,300.00	12.00 12.00	282.75 282.75	3,173.76 3,271.58	-213.34 -115.52	-61.55 -66.28	59.71 64.30	-263.88 -284.16	398,569.75 398,574.34	774,516.51 774,496.22	32.09350980 32.09352280	-103.58035834 -103.58042372	0.00	0.00	0.00
	3,400.00	12.00	282.75	3,369.39	-17.71	-71.01	68.88	-304.45	398,578.93	774,475.94	32.09353580	-103.58048911	0.00	0.00	0.00
	3,500.00 3,600.00	12.00 12.00	282.75 282.75	3,467.20 3,565.02	80.10 177.92	-75.74 -80.47	73.47 78.06	-324.73 -345.01	398,583.52 398,588.11	774,455.66 774,435.38	32.09354881 32.09356181	-103.58055449 -103.58061988	0.00 0.00	0.00	0.00
	3,700.00 3,800.00	12.00 12.00	282.75 282.75	3,662.83 3,760.65	275.73 373.55	-85.20 -89.93	82.65 87.24	-365.29 -385.58	398,592.70 398,597.29	774,415.10 774,394.82	32.09357481 32.09358781	-103.58068526 -103.58075065	0.00	0.00	0.00
	3,900.00 4,000.00	12.00 12.00	282.75 282.75	3,858.46 3,956.27	471.36 569.17	-94.66 -99.39	91.83 96.42	-405.86 -426.14	398,601.88 398,606.47	774,374.53 774,354.25	32.09360082 32.09361382	-103.58081603 -103.58088142	0.00 0.00	0.00	0.00 0.00
	4,100.00	12.00	282.75	4,054.09	666.99 764.80	-104.12	101.01	-446.42	398,611.06	774,333.97	32.09362682 32.09363983	-103.58094680	0.00	0.00	0.00
	4,200.00 4,300.00	12.00 12.00	282.75 282.75	4,151.90 4,249.72	862.62	-108.85 -113.58	105.60 110.19	-466.71 -486.99	398,615.64 398,620.23	774,313.69 774,293.41	32.09365283	-103.58101219 -103.58107757	0.00	0.00 0.00	0.00 0.00
	4,400.00 4,500.00	12.00 12.00	282.75 282.75	4,347.53 4,445.34	960.43 1,058.24	-118.31 -123.05	114.78 119.36	-507.27 -527.55	398,624.82 398,629.41	774,273.13 774,252.84		-103.58114296 -103.58120834	0.00 0.00	0.00	0.00
	4,600.00 4,700.00	12.00 12.00	282.75 282.75	4,543.16 4,640.97	1,156.06 1,253.87	-127.78 -132.51	123.95 128.54	-547.83 -568.12	398,634.00 398,638.59	774,232.56 774,212.28		-103.58127373 -103.58133911	0.00	0.00	0.00 0.00
	4,800.00	12.00	282.75	4,738.79	1,351.69	-137.24	133.13	-588.40	398,643.18	774,192.00	32.09371784	-103.58140450	0.00	0.00	0.00
.amar	4,900.00 4,964.82	12.00 12.00	282.75 282.75	4,836.60 4,900.00	1,449.50 1,512.90	-141.97 -145.03	137.72 140.70	-608.68 -621.83	398,647.77 398,650.74	774,171.72 774,158.57	32.09373927	-103.58146988 -103.58151226	0.00 0.00	0.00	0.00
iell Canyon	4,995.49 5,000.00	12.00 12.00	282.75 282.75	4,930.00 4,934.41	1,542.90 1,547.31	-146.48 -146.70	142.10 142.31	-628.05 -628.96	398,652.15 398,652.36	774,152.35 774,151.44	32.09374326 32.09374385	-103.58153232 -103.58153527	0.00	0.00	0.00
	5,100.00 5,200.00	12.00 12.00	282.75 282.75	5,032.23 5.130.04	1,645.13 1,742.94	-151.43 -156.16	146.90 151.49	-649.25 -669.53	398,656.95 398,661.53	774,131.15 774.110.87	32.09375685	-103.58160065 -103.58166604	0.00	0.00	0.00
	5,300.00	12.00	282.75	5,227.86	1,840.76	-160.89	156.08	-689.81	398,666.12	774,090.59	32.09378285	-103.58173142	0.00	0.00	0.00
	5,400.00 5,500.00	12.00 12.00	282.75 282.75	5,325.67 5,423.48	1,938.57 2,036.38	-165.62 -170.35	160.67 165.26	-710.09 -730.38	398,670.71 398,675.30	774,070.31 774,050.03	32.09379586 32.09380886	-103.58179681 -103.58186219	0.00 0.00	0.00	0.00
	5,600.00 5,700.00	12.00 12.00	282.75 282.75	5,521.30 5,619.11	2,134.20 2,232.01	-175.08 -179.81	169.85 174.43	-750.66 -770.94	398,679.89 398,684.48	774,029.74 774,009.46	32.09382186 32.09383486	-103.58192758 -103.58199297	0.00	0.00	0.00
	5,800.00	12.00	282.75	5,716.93	2,329.83	-184.54	179.02	-791.22	398,689.07	773,989.18	32.09384787	-103.58205835	0.00	0.00	0.00
	5,900.00 6,000.00	12.00 12.00	282.75 282.75	5,814.74 5,912.55	2,427.64 2,525.45	-189.27 -194.00	183.61 188.20	-811.51 -831.79	398,693.66 398,698.25	773,968.90 773,948.62	32.09386087 32.09387387	-103.58212374 -103.58218912	0.00 0.00	0.00 0.00	0.00
Cherry Canyon	6,048.51 6.100.00	12.00 12.00	282.75 282.75	5,960.00 6,010.37	2,572.90 2,623.27	-196.30 -198.73	190.43 192.79	-841.63 -852.07	398,700.47 398,702.83	773,938.78 773,928.34	32.09388018 32.09388687	-103.58222084 -103.58225451	0.00	0.00	0.00
	6,200.00 6,300.00	12.00 12.00	282.75 282.75	6,108.18 6,205.99	2,721.08 2,818.89	-203.47 -208.20	197.38 201.97	-872.35 -892.63	398,707.42 398,712.01	773,908.05 773,887.77	32.09389987 32.09391288	-103.58231989 -103.58238528	0.00 0.00	0.00	0.00
	6,400.00	12.00	282.75	6,303.81	2,916.71	-212.93	206.56	-912.92	398,716.60	773,867.49	32.09392588	-103.58245066	0.00	0.00	0.00
	6,500.00 6,600.00	12.00 12.00	282.75 282.75	6,401.62 6,499.44	3,014.52 3,112.34	-217.66 -222.39	211.15 215.74	-933.20 -953.48	398,721.19 398,725.78	773,847.21 773,826.93	32.09393888 32.09395188	-103.58251605 -103.58258143	0.00 0.00	0.00	0.00
	6,700.00 6,800.00	12.00 12.00	282.75 282.75	6,597.25 6,695.06	3,210.15 3,307.96	-227.12 -231.85	220.33 224.91	-973.76 -994.05	398,730.37 398,734.96	773,806.65 773,786.36	32.09396488	-103.58264682 -103.58271220	0.00 0.00	0.00	0.00
Drop 2°/100ft	6,873.33 6.900.00	12.00 11.47	282.75 282.75	6,766.79 6.792.90	3,379.69 3,405.80	-235.32 -236.55	228.28 229.48	-1,008.92 -1.014.21	398,738.32 398,739.52	773,771.49 773,766.20	32.09398742 32.09399081	-103.58276015 -103.58277721	0.00	0.00	0.00
	7,000.00	9.47	282.75	6,891.23	3,504.13	-240.68	233.49	-1,031.93	398,743.53	773,748.48	32.09400217	-103.58283434	2.00	-2.00	0.00
	7,100.00 7,200.00	7.47 5.47	282.75 282.75	6,990.14 7,089.50	3,603.04 3,702.40	-244.03 -246.60	236.74 239.22	-1,046.29 -1,057.28	398,746.78 398,749.27	773,734.12 773,723.13		-103.58288064 -103.58291606	2.00 2.00	-2.00 -2.00	0.00
	7,300.00 7.400.00	3.47 1.47	282.75 282.75	7,189.19 7,289.09	3,802.09 3.901.99	-248.37 -249.35	240.94 241.89	-1,064.88 -1.069.08	398,750.98 398,751.93	773,715.53 773,711.33		-103.58294056 -103.58295410	2.00 2.00	-2.00 -2.00	0.00
Hold	7,473.44	0.00	282.75	7,362.52	3,975.42	-249.56	242.10	-1,070.00	398,752.14	773,710.41	32.09402658	-103.58295706	2.00	-2.00	0.00
Brushy Canyon	7,500.00 7,590.92	0.00 0.00	282.75 282.75	7,389.08 7,480.00	4,001.98 4,092.90	-249.56 -249.56	242.10 242.10	-1,070.00 -1,070.00	398,752.14 398,752.14	773,710.41 773,710.41		-103.58295706 -103.58295706	0.00 0.00	0.00 0.00	0.00 0.00
	7,600.00 7,700.00	0.00	282.75 282.75	7,489.08 7,589.08	4,101.98 4,201.98	-249.56 -249.56	242.10 242.10	-1,070.00 -1,070.00	398,752.14 398,752.14	773,710.41 773,710.41		-103.58295706 -103.58295706	0.00 0.00	0.00	0.00
	7,800.00 7,900.00	0.00	282.75 282.75	7,689.08 7,789.08	4,301.98 4,401.98	-249.56 -249.56	242.10 242.10	-1,070.00 -1,070.00	398,752.14 398,752.14	773,710.41 773,710.41		-103.58295706 -103.58295706	0.00	0.00	0.00
	8,000.00	0.00	282.75	7,889.08	4,501.98	-249.56	242.10	-1,070.00	398,752.14	773,710.41	32.09402658	-103.58295706 -103.58295706	0.00	0.00	0.00
	8,100.00 8,200.00	0.00 0.00	282.75 282.75	7,989.08 8,089.08	4,601.98 4,701.98	-249.56 -249.56	242.10 242.10	-1,070.00 -1,070.00	398,752.14 398,752.14	773,710.41 773,710.41	32.09402658	-103.58295706	0.00 0.00	0.00 0.00	0.00 0.00
	8,300.00 8,400.00	0.00	282.75 282.75	8,189.08 8,289.08	4,801.98 4,901.98	-249.56 -249.56	242.10 242.10	-1,070.00 -1,070.00	398,752.14 398,752.14	773,710.41 773,710.41		-103.58295706 -103.58295706	0.00 0.00	0.00	0.00
	8,500.00 8,600.00	0.00	282.75 282.75	8,389.08 8,489.08	5,001.98 5.101.98	-249.56 -249.56	242.10 242.10	-1,070.00 -1,070.00	398,752.14 398,752.14	773,710.41 773,710.41	32.09402658	-103.58295706 -103.58295706	0.00	0.00	0.00
	8,700.00	0.00	282.75	8,589.08	5,201.98	-249.56	242.10	-1,070.00	398,752.14	773,710.41	32.09402658	-103.58295706	0.00	0.00	0.00
	8,800.00 8,900.00	0.00	282.75 282.75	8,689.08 8,789.08	5,301.98 5,401.98	-249.56 -249.56	242.10 242.10	-1,070.00 -1,070.00	398,752.14 398,752.14	773,710.41 773,710.41		-103.58295706 -103.58295706	0.00 0.00	0.00	0.00
Basal Brushy Canyon	8,965.92 9,000.00	0.00	282.75 282.75	8,855.00 8,889.08	5,467.90 5.501.98	-249.56 -249.56	242.10 242.10	-1,070.00 -1.070.00	398,752.14 398,752.14	773,710.41 773,710.41		-103.58295706	0.00	0.00	0.00
) ()	9,100.00	0.00	282.75	8,989.08	5,601.98	-249.56 -249.56	242.10	-1,070.00	398,752.14	773,710.41	32.09402658	-103.58295706 -103.58295706	0.00	0.00	0.00
Bone Springs Lime Leonard	9,150.92 9,175.92	0.00 0.00	282.75 282.75	9,040.00 9,065.00	5,652.90 5,677.90	-249.56	242.10 242.10	-1,070.00 -1,070.00	398,752.14 398,752.14	773,710.41 773,710.41	32.09402658	-103.58295706	0.00 0.00	0.00 0.00	0.00 0.00
	9,200.00 9,300.00	0.00	282.75 282.75	9,089.08 9,189.08	5,701.98 5.801.98	-249.56 -249.56	242.10 242.10	-1,070.00 -1.070.00	398,752.14 398,752.14	773,710.41 773,710.41	32.09402658 32.09402658	-103.58295706 -103.58295706	0.00	0.00	0.00
Avalon	9,400.00 9.440.92	0.00	282.75 282.75	9,289.08 9.330.00	5,901.98 5,942.90	-249.56 -249.56	242.10 242.10	-1,070.00 -1,070.00	398,752.14 398,752.14	773,710.41	32.09402658	-103.58295706 -103.58295706	0.00	0.00	0.00
avenur!	9,500.00	0.00	282.75	9,389.08	6,001.98	-249.56	242.10	-1,070.00	398,752.14	773,710.41 773,710.41	32.09402658	-103.58295706	0.00	0.00	0.00
	9,600.00 9,700.00	0.00	282.75 282.75	9,489.08 9,589.08	6,101.98 6,201.98	-249.56 -249.56	242.10 242.10	-1,070.00 -1,070.00	398,752.14 398,752.14	773,710.41 773,710.41	32.09402658 32.09402658	-103.58295706 -103.58295706	0.00	0.00	0.00
	9,800.00 9,900.00	0.00	282.75 282.75	9,689.08 9,789.08	6,301.98 6,401.98	-249.56 -249.56	242.10 242.10	-1,070.00	398,752.14 398,752.14	773,710.41 773,710.41	32.09402658	-103.58295706 -103.58295706	0.00	0.00	0.00
	10,000.00	0.00	282.75	9,889.08	6,501.98	-249.56	242.10	-1,070.00 -1,070.00	398,752.14	773,710.41	32.09402658	-103.58295706	0.00	0.00	0.00
1st BS SS	10,100.00 10,130.92	0.00	282.75 282.75	9,989.08 10,020.00	6,601.98 6,632.90	-249.56 -249.56	242.10 242.10	-1,070.00 -1,070.00	398,752.14 398,752.14	773,710.41 773,710.41	32.09402658	-103.58295706 -103.58295706	0.00 0.00	0.00	0.00 0.00
	10,200.00 10,300.00	0.00	282.75 282.75	10,089.08 10,189.08	6,701.98 6,801.98	-249.56 -249.56	242.10 242.10	-1,070.00 -1,070.00	398,752.14 398,752.14	773,710.41 773,710.41		-103.58295706	0.00	0.00	0.00
2nd BS Carb	10,330.92	0.00	282.75	10,220.00	6,832.90	-249.56	242.10	-1,070.00	398,752.14	773,710.41	32.09402658	-103.58295706	0.00	0.00	0.00
	10,400.00 10,500.00	0.00 0.00	282.75 282.75	10,289.08 10,389.08	6,901.98 7,001.98	-249.56 -249.56	242.10 242.10	-1,070.00 -1,070.00	398,752.14 398,752.14	773,710.41 773,710.41	32.09402658	-103.58295706 -103.58295706	0.00 0.00	0.00 0.00	0.00
2nd BS SS	10,600.00 10,685.92	0.00	282.75 282.75	10,489.08 10,575.00	7,101.98 7,187.90	-249.56 -249.56	242.10 242.10	-1,070.00 -1,070.00	398,752.14 398,752.14	773,710.41 773,710.41	32.09402658	-103.58295706 -103.58295706	0.00	0.00	0.00
	10,000.02	5.00	202.10	10,010.00	1,131.00	2-10.00	242.10	1,570.00	000,702.14	770,710.41	DE.00402000	.00.00200100	0.00	0.00	0.00

Comments	MD (ft)	inci (°)	Azim (°)	TVD (ft)	TVDSS (ft)	VSEC (ft)	NS (ft)	EW (ft)	Northing (ftUS)	Easting (ftUS)	Latitude (°)	Longitude (°)	DLS (°/100ft)	BR (°/100ft)	TR (°/100ft)
KOP, Build 10°/100ft	10,700.00 10,800.00 10,898.44	0.00 0.00 0.00	282.75 282.75 282.75	10,589.08 10,689.08 10,787.52	7,201.98 7,301.98 7,400.42	-249.56 -249.56 -249.56	242.10 242.10 242.10	-1,070.00 -1,070.00 -1,070.00	398,752.14 398,752.14 398,752.14	773,710.41 773,710.41 773,710.41		-103.58295706 -103.58295706 -103.58295706	0.00 0.00 0.00	0.00 0.00 0.00	0.00 0.00 0.00
	10,900.00 11,000.00	0.16 10.16	199.60 199.60	10,789.08 10,888.55	7,401.98 7,501.45	-249.56 -241.13	242.10 233.64	-1,070.00 -1,073.01	398,752.14 398,743.69	773,710.41 773,707.40	32.09400339	-103.58295706 -103.58296698	10.00 10.00	10.00 10.00	0.00
3rd BS Carb	11,100.00 11,126.93	20.16 22.85	199.60 199.60	10,984.95 11,010.00	7,597.85 7,622.90	-216.59 -207.32	209.04 199.75	-1,081.77 -1,085.08	398,719.09 398,709.79	773,698.64 773,695.33	32.09391045	-103.58299581 -103.58300671	10.00 10.00	10.00 10.00	0.00
	11,200.00 11,300.00 11,400.00	30.16 40.16 50.16	199.60 199.60 199.60	11,075.35 11,157.01 11,227.43	7,688.25 7,769.91 7.840.33	-176.70 -122.66 -56.11	169.05 114.87 48.16	-1,096.01 -1,115.30 -1,139.06	398,679.09 398,624.92 398,558.21	773,684.40 773,665.11 773,641.36		-103.58304269 -103.58310620 -103.58318440	10.00 10.00 10.00	10.00 10.00 10.00	0.00 0.00 0.00
	11,500.00 11,600.00	60.16 70.16	199.60 199.60	11,284.50 11,326.46	7,840.33 7,897.40 7,939.36	20.91 106.08	-29.06 -114.43	-1,166.55 -1,196.96	398,481.00 398,395.62	773,613.86 773,583.46	32.09328311	-103.58327491 -103.58337499	10.00 10.00 10.00	10.00 10.00	0.00
Build 5°/100ft	11,648.44 11,700.00	75.00 77.58	199.60 199.60	11,340.95 11,353.18	7,953.85 7,966.08	149.49 196.56	-157.96 -205.15	-1,212.45 -1,229.26	398,352.10 398,304.91	773,567.96 773,551.16	32.09292968 32.09280030	-103.58342601 -103.58348132	10.00 5.00	10.00 5.00	0.00
	11,800.00 11,900.00	82.58 87.58	199.60 199.60	11,370.40 11,378.98	7,983.30 7,991.88	289.09 382.69	-297.91 -391.74	-1,262.29 -1,295.70	398,212.15 398,118.32	773,518.13 773,484.72	32.09254595 32.09228869	-103.58359006 -103.58370004	5.00 5.00	5.00 5.00	0.00
Landing Point	11,948.44 12,000.00	90.00 90.00	199.60 199.60	11,380.00 11,380.00	7,992.90 7,992.90	428.19 476.64	-437.36 -485.93	-1,311.94 -1,329.24	398,072.70 398,024.13	773,468.48 773,451.18	32.09203043	-103.58375352 -103.58381045	5.00 0.00	5.00 0.00	0.00
	12,100.00 12,200.00	90.00 90.00	199.60 199.60	11,380.00 11,380.00	7,992.90 7,992.90	570.61 664.58	-580.14 -674.35	-1,362.79 -1,396.33	397,929.93 397,835.73	773,417.64 773,384.09		-103.58392088 -103.58403130	0.00	0.00	0.00
Turn 2°/100ft	12,300.00 12,311.44 12.400.00	90.00 90.00 90.00	199.60 199.60 197.83	11,380.00 11,380.00 11.380.00	7,992.90 7,992.90 7,992.90	758.55 769.30 852.97	-768.55 -779.33 -863.20	-1,429.88 -1,433.71 -1.462.13	397,741.52 397,730.75 397,646.87	773,350.55 773,346.71 773,318.30		-103.58414172 -103.58415435 -103.58424798	0.00 0.00 2.00	0.00 0.00 0.00	0.00 0.00 -2.00
	12,500.00 12,500.00 12,600.00	90.00 90.00 90.00	195.83 193.83	11,380.00 11,380.00 11,380.00	7,992.90 7,992.90 7.992.90	948.48 1,044.97	-958.92 -1,055.58	-1,491.08 -1,516.67	397,551.16 397,454.50	773,289.35 773,263.76	32.09073346	-103.58434359 -103.58442839	2.00 2.00 2.00	0.00	-2.00 -2.00 -2.00
	12,700.00 12,800.00	90.00 90.00	191.83 189.83	11,380.00 11,380.00	7,992.90 7,992.90	1,142.31 1,240.39	-1,153.08 -1,251.29	-1,538.87 -1,557.66	397,357.01 397,258.80	773,241.56 773,222.77	32.09020068 32.08993109	-103.58450226 -103.58456512	2.00 2.00	0.00	-2.00 -2.00
	12,900.00 13,000.00	90.00 90.00	187.83 185.83	11,380.00 11,380.00	7,992.90 7,992.90	1,339.09 1,438.29	-1,350.10 -1,449.39	-1,573.01 -1,584.90	397,159.99 397,060.71	773,207.42 773,195.53	32.08965979 32.08938711	-103.58461689 -103.58465750	2.00 2.00	0.00	-2.00 -2.00
	13,100.00 13,200.00	90.00 90.00	183.83 181.83	11,380.00 11,380.00	7,992.90 7,992.90	1,537.87 1,637.70	-1,549.03 -1,648.90	-1,593.31 -1,598.25	396,961.07 396,861.20	773,187.12 773,182.18	32.08911340 32.08883898	-103.58468691 -103.58470508	2.00 2.00	0.00	-2.00 -2.00
Hold	13,300.00 13,311.53	90.00 90.00	179.83 179.60	11,380.00 11,380.00	7,992.90 7,992.90	1,737.68 1,749.20	-1,748.89 -1,760.41	-1,599.69 -1,599.64	396,761.22 396,749.69	773,180.73 773,180.79	32.08856418 32.08853250	-103.58471199 -103.58471207	2.00 2.00	0.00	-2.00 -2.00
	13,400.00 13,500.00	90.00 90.00	179.60 179.60	11,380.00 11,380.00	7,992.90 7,992.90	1,837.68 1,937.68	-1,848.88 -1,948.88	-1,599.02 -1,598.31	396,661.22 396,561.23	773,181.41 773,182.11		-103.58471205 -103.58471202	0.00 0.00	0.00 0.00	0.00
	13,600.00 13,700.00	90.00 90.00	179.60 179.60	11,380.00 11,380.00	7,992.90 7,992.90	2,037.68 2,137.68	-2,048.88 -2,148.88	-1,597.61 -1,596.91	396,461.23 396,361.24	773,182.82 773,183.52	32.08746470	-103.58471200 -103.58471198	0.00 0.00	0.00 0.00	0.00
Pool NMNM0024368A exit to NMI	13,800.00 13,849.00	90.00 90.00	179.60 179.60	11,380.00 11,380.00	7,992.90 7,992.90	2,237.68 2,286.68	-2,248.87 -2,297.87	-1,596.21 -1,595.87	396,261.24 396,212.25	773,184.22 773,184.56	32.08705514	-103.58471195 -103.58471194	0.00	0.00	0.00
	13,900.00 14,000.00	90.00 90.00	179.60 179.60	11,380.00 11,380.00	7,992.90 7,992.90	2,337.68 2,437.68 2,537.68	-2,348.87 -2,448.87	-1,595.51 -1,594.81	396,161.25 396,061.26 395,961.26	773,184.92 773,185.62 773,186.32	32.08664008	-103.58471193 -103.58471191	0.00 0.00	0.00	0.00
	14,100.00 14,200.00 14,300.00	90.00 90.00 90.00	179.60 179.60 179.60	11,380.00 11,380.00 11,380.00	7,992.90 7,992.90 7.992.90	2,537.68 2,637.68 2,737.68	-2,548.87 -2,648.86 -2,748.86	-1,594.11 -1,593.41 -1,592.71	395,961.26 395,861.27 395,761.27	773,186.32 773,187.02 773,187.72	32.08609034 32.08581547	-103.58471189 -103.58471186 -103.58471184	0.00 0.00 0.00	0.00 0.00 0.00	0.00 0.00 0.00
	14,400.00 14,500.00	90.00 90.00	179.60 179.60	11,380.00 11,380.00	7,992.90 7,992.90	2,837.68 2,937.68	-2,848.86 -2,948.86	-1,592.00 -1,591.30	395,661.28 395,561.28	773,188.42 773,189.13	32.08554060 32.08526572	-103.58471182 -103.58471179	0.00 0.00	0.00	0.00
	14,600.00 14,700.00	90.00	179.60 179.60	11,380.00 11,380.00	7,992.90 7.992.90	3,037.68 3,137.68	-3,048.85 -3.148.85	-1,590.60 -1,589.90	395,461.29 395,361.29	773,189.83 773,190.53		-103.58471177 -103.58471175	0.00	0.00	0.00
	14,800.00 14,900.00	90.00 90.00	179.60 179.60	11,380.00 11,380.00	7,992.90 7,992.90	3,237.68 3,337.68	-3,248.85 -3,348.85	-1,589.20 -1,588.50	395,261.30 395,161.31	773,191.23 773,191.93	32.08444111	-103.58471173 -103.58471170	0.00 0.00	0.00 0.00	0.00
	15,000.00 15,100.00	90.00 90.00	179.60 179.60	11,380.00 11,380.00	7,992.90 7,992.90	3,437.68 3,537.68	-3,448.84 -3,548.84	-1,587.80 -1,587.10	395,061.31 394,961.32	773,192.63 773,193.33	32.08361650	-103.58471168 -103.58471166	0.00	0.00	0.00
Pool NMNM0005792A exit to NMI	15,169.00 15,200.00	90.00 90.00	179.60 179.60	11,380.00 11,380.00	7,992.90 7,992.90	3,606.68 3,637.68	-3,617.84 -3,648.84	-1,586.61 -1,586.39	394,892.32 394,861.32	773,193.82 773,194.03		-103.58471164 -103.58471163	0.00 0.00	0.00	0.00
	15,300.00 15,400.00	90.00 90.00	179.60 179.60	11,380.00 11,380.00	7,992.90 7,992.90	3,737.68 3,837.68	-3,748.84 -3,848.83	-1,585.69 -1,584.99	394,761.33 394,661.33	773,194.73 773,195.44	32.08279188	-103.58471161 -103.58471159	0.00	0.00	0.00
	15,500.00 15,600.00	90.00 90.00	179.60 179.60	11,380.00 11,380.00	7,992.90 7,992.90	3,937.68 4,037.68	-3,948.83 -4,048.83	-1,584.29 -1,583.59	394,561.34 394,461.34	773,196.14 773,196.84	32.08224214	-103.58471156 -103.58471154	0.00	0.00	0.00
	15,700.00 15,800.00 15,900.00	90.00 90.00 90.00	179.60 179.60 179.60	11,380.00 11,380.00 11,380.00	7,992.90 7,992.90 7,992.90	4,137.68 4,237.68 4,337.68	-4,148.83 -4,248.82 -4,348.82	-1,582.89 -1,582.19 -1,581.49	394,361.35 394,261.35 394,161.36	773,197.54 773,198.24 773,198.94	32.08196727 32.08169240 32.08141752	-103.58471152 -103.58471149 -103.58471147	0.00 0.00 0.00	0.00 0.00 0.00	0.00 0.00 0.00
	16,000.00 16.100.00	90.00 90.00	179.60 179.60	11,380.00 11,380.00 11,380.00	7,992.90 7,992.90 7.992.90	4,437.68 4,537.68	-4,448.82 -4,548.82	-1,581.49 -1,580.79 -1.580.08	394,061.37 393.961.37	773,199.64 773,200.34		-103.58471147 -103.58471145 -103.58471142	0.00	0.00	0.00
	16,200.00 16,300.00	90.00 90.00	179.60 179.60	11,380.00 11,380.00	7,992.90 7,992.90	4,637.68 4,737.68	-4,648.81 -4,748.81	-1,579.38 -1,578.68	393,861.38 393,761.38	773,201.05 773,201.75	32.08059291	-103.58471140 -103.58471138	0.00	0.00	0.00
Section 33-4 Line, Pool NMNM00	16,400.00 16,489.00	90.00 90.00	179.60 179.60	11,380.00 11,380.00	7,992.90 7,992.90	4,837.68 4,926.68	-4,848.81 -4,937.81	-1,577.98 -1,577.36	393,661.39 393,572.39	773,202.45 773,203.07	32.07979853	-103.58471135 -103.58471133	0.00	0.00	0.00
	16,500.00 16,600.00	90.00 90.00	179.60 179.60	11,380.00 11,380.00	7,992.90 7,992.90	4,937.68 5,037.68	-4,948.81 -5,048.81	-1,577.28 -1,576.58	393,561.39 393,461.40	773,203.15 773,203.85		-103.58471133 -103.58471131	0.00	0.00	0.00
	16,700.00 16,800.00	90.00 90.00	179.60 179.60	11,380.00 11,380.00	7,992.90 7,992.90	5,137.68 5,237.68	-5,148.80 -5,248.80	-1,575.88 -1,575.18	393,361.40 393,261.41	773,204.55 773,205.25	32.07894368	-103.58471128 -103.58471126	0.00 0.00	0.00	0.00 0.00
	16,900.00 17,000.00	90.00 90.00	179.60 179.60	11,380.00 11,380.00	7,992.90 7,992.90	5,337.68 5,437.68	-5,348.80 -5,448.80	-1,574.47 -1,573.77	393,161.42 393,061.42	773,205.95 773,206.65	32.07839394	-103.58471124 -103.58471121	0.00	0.00	0.00
	17,100.00 17,200.00	90.00 90.00	179.60 179.60	11,380.00 11,380.00	7,992.90 7,992.90	5,537.68 5,637.68	-5,548.79 -5,648.79	-1,573.07 -1,572.37	392,961.43 392,861.43	773,207.36 773,208.06		-103.58471119 -103.58471117	0.00	0.00	0.00
	17,300.00 17,400.00 17,500.00	90.00 90.00 90.00	179.60 179.60 179.60	11,380.00 11,380.00 11.380.00	7,992.90 7,992.90 7.992.90	5,737.68 5,837.68 5,937.68	-5,748.79 -5,848.79 -5.948.78	-1,571.67 -1,570.97 -1,570.27	392,761.44 392,661.44 392,561.45	773,208.76 773,209.46 773,210.16		-103.58471114 -103.58471112 -103.58471110	0.00 0.00 0.00	0.00 0.00 0.00	0.00 0.00 0.00
	17,600.00 17,700.00	90.00 90.00	179.60 179.60	11,380.00 11,380.00	7,992.90 7,992.90	6,037.68 6,137.68	-6,048.78 -6,148.78	-1,569.57 -1,568.87	392,461.45 392,361.46	773,210.86 773,211.56	32.07674470 32.07646983	-103.58471107 -103.58471105	0.00	0.00	0.00
	17,800.00 17,900.00	90.00 90.00	179.60 179.60	11,380.00 11,380.00	7,992.90 7,992.90	6,237.68 6,337.68	-6,248.78 -6,348.77	-1,568.16 -1,567.46	392,261.46 392,161.47	773,212.26 773,212.96	32.07619496	-103.58471103 -103.58471100	0.00	0.00	0.00
	18,000.00 18,100.00	90.00 90.00	179.60 179.60	11,380.00 11,380.00	7,992.90 7,992.90	6,437.68 6,537.68	-6,448.77 -6,548.77	-1,566.76 -1,566.06	392,061.48 391,961.48	773,213.67 773,214.37	32.07564522 32.07537035	-103.58471098 -103.58471096	0.00 0.00	0.00	0.00
	18,200.00 18,300.00	90.00 90.00	179.60 179.60	11,380.00 11,380.00	7,992.90 7,992.90	6,637.68 6,737.68	-6,648.77 -6,748.76	-1,565.36 -1,564.66	391,861.49 391,761.49	773,215.07 773,215.77		-103.58471093 -103.58471091	0.00 0.00	0.00 0.00	0.00 0.00
	18,400.00 18,500.00	90.00 90.00	179.60 179.60	11,380.00 11,380.00	7,992.90 7,992.90	6,837.68 6,937.68	-6,848.76 -6,948.76	-1,563.96 -1,563.26	391,661.50 391,561.50	773,216.47 773,217.17	32.07427086	-103.58471088 -103.58471086	0.00 0.00	0.00 0.00	0.00 0.00
	18,600.00 18,700.00	90.00 90.00	179.60 179.60	11,380.00 11,380.00	7,992.90 7,992.90	7,037.68 7,137.68	-7,048.76 -7,148.75	-1,562.55 -1,561.85	391,461.51 391,361.51	773,217.87 773,218.57	32.07372111	-103.58471084 -103.58471081	0.00	0.00	0.00
	18,800.00 18,900.00 19,000.00	90.00 90.00 90.00	179.60 179.60 179.60	11,380.00 11,380.00 11.380.00	7,992.90 7,992.90 7.992.90	7,237.68 7,337.68 7,437.68	-7,248.75 -7,348.75 -7,448.75	-1,561.15 -1,560.45 -1,559.75	391,261.52 391,161.53 391.061.53	773,219.28 773,219.98 773,220.68	32.07317137	-103.58471079 -103.58471077 -103.58471074	0.00 0.00 0.00	0.00 0.00 0.00	0.00 0.00 0.00
	19,100.00 19,200.00	90.00 90.00	179.60 179.60	11,380.00 11,380.00	7,992.90 7,992.90	7,537.68 7,637.68	-7,548.74 -7,648.74	-1,559.05 -1,558.35	390,961.54 390,861.54	773,221.38 773,222.08	32.07262163	-103.58471072	0.00 0.00	0.00	0.00
	19,300.00 19,400.00	90.00 90.00	179.60 179.60	11,380.00 11,380.00	7,992.90 7,992.90	7,737.68 7,837.68	-7,748.74 -7,848.74	-1,557.65 -1,556.95	390,761.55 390,661.55	773,222.78 773,223.48	32.07207188	-103.58471067 -103.58471065	0.00	0.00	0.00
	19,500.00 19,600.00	90.00 90.00	179.60 179.60	11,380.00 11,380.00	7,992.90 7,992.90	7,937.68 8,037.68	-7,948.73 -8,048.73	-1,556.24 -1,555.54	390,561.56 390,461.56	773,224.18 773,224.88	32.07152214	-103.58471062 -103.58471060	0.00	0.00	0.00
	19,700.00 19,800.00	90.00 90.00	179.60 179.60	11,380.00 11,380.00	7,992.90 7,992.90	8,137.68 8,237.68	-8,148.73 -8,248.73	-1,554.84 -1,554.14	390,361.57 390,261.58	773,225.59 773,226.29	32.07097239 32.07069752	-103.58471058 -103.58471055	0.00 0.00	0.00 0.00	0.00
	19,900.00 20,000.00	90.00 90.00	179.60 179.60	11,380.00 11,380.00	7,992.90 7,992.90	8,337.68 8,437.68	-8,348.72 -8,448.72	-1,553.44 -1,552.74	390,161.58 390,061.59	773,226.99 773,227.69	32.07014778	-103.58471053 -103.58471050	0.00 0.00	0.00	0.00
	20,100.00 20,200.00	90.00 90.00	179.60 179.60	11,380.00 11,380.00	7,992.90 7,992.90	8,537.68 8,637.68	-8,548.72 -8,648.72	-1,552.04 -1,551.34	389,961.59 389,861.60	773,228.39 773,229.09	32.06959803	-103.58471048 -103.58471046	0.00	0.00	0.00
	20,300.00 20,400.00	90.00 90.00	179.60 179.60	11,380.00 11,380.00	7,992.90 7,992.90	8,737.68 8,837.68	-8,748.71 -8,848.71	-1,550.63 -1,549.93	389,761.60 389,661.61	773,229.79 773,230.49	32.06904829	-103.58471043 -103.58471041	0.00 0.00	0.00	0.00
	20,500.00 20,600.00	90.00 90.00	179.60 179.60	11,380.00 11,380.00	7,992.90 7,992.90	8,937.68 9,037.68	-8,948.71 -9,048.71	-1,549.23 -1,548.53	389,561.61 389,461.62	773,231.19 773,231.90	32.06849855	-103.58471038 -103.58471036	0.00	0.00	0.00
	20,700.00 20,800.00 20,900.00	90.00 90.00 90.00	179.60 179.60 179.60	11,380.00 11,380.00 11,380.00	7,992.90 7,992.90 7.992.90	9,137.68 9,237.68 9,337.68	-9,148.70 -9,248.70 -9,348.70	-1,547.83 -1,547.13 -1,546.43	389,361.62 389,261.63 389,161.64	773,232.60 773,233.30 773,234.00	32.06794880	-103.58471034 -103.58471031 -103.58471029	0.00 0.00 0.00	0.00 0.00 0.00	0.00 0.00 0.00
	21,000.00 21,100.00	90.00 90.00 90.00	179.60 179.60 179.60	11,380.00 11,380.00 11,380.00	7,992.90 7,992.90 7.992.90	9,437.68 9,537.68	-9,348.70 -9,448.70 -9.548.69	-1,545.73 -1,545.03	389,061.64 388,961.65	773,234.70 773,235.40	32.06739906	-103.58471026 -103.58471024	0.00	0.00	0.00
	21,200.00 21,200.00 21,300.00	90.00 90.00	179.60 179.60	11,380.00 11,380.00 11,380.00	7,992.90 7,992.90 7,992.90	9,637.68 9,737.68	-9,648.69 -9,748.69	-1,544.32 -1,543.62	388,861.65 388,761.66	773,236.10 773,236.80	32.06684931	-103.58471022 -103.58471019	0.00 0.00 0.00	0.00	0.00 0.00
	21,400.00 21,500.00	90.00 90.00	179.60 179.60	11,380.00 11,380.00	7,992.90 7,992.90	9,837.68 9,937.68	-9,848.69 -9,948.68	-1,542.92 -1,542.22	388,661.66 388,561.67	773,237.51 773,238.21	32.06629957	-103.58471017 -103.58471014	0.00 0.00	0.00	0.00
Red Hills Unit 49H - BHL [100' FS	21,600.00 21,668.80	90.00 90.00	179.60 179.60	11,380.00 11,380.00	7,992.90 7,992.90	10,037.68 10,106.47	-10,048.68 -10,117.48	-1,541.52 -1,541.04	388,461.67 388,392.88	773,238.91 773,239.39		-103.58471012 -103.58471010	0.00 0.00	0.00 0.00	0.00
Survey Type:	Def	Plan													
Survey Error Model:	ISC	WSA0 3 - D 95 % 0	Confidence 2.795	55 sigma											
Survey Program: Description		Part	MD From	MD To	EOU Freq		Casing Diameter	Expected Max Inclination	Survey Tool C	ode	Borehole	/ Survey			
		· un	(ft)	(ft)	(ft)	(in)	(in)	(deg)	,						
		1	0.000	10,900.000	1/100.000	_	_	AC	001Mb_MWD		Red Hills Unit 49h	H / Coterra Red Hills	s Unit 49H Rev1 kFc	24May23	

Released to Imaging: 1/22/2024 11:22:02 AM

EOU Geometry: End MD (ft) 1 10,900.000 21,666.275

Hole Size (in)

1/100.000

Casing Size (in)

A008Mb_MWD+IFR1+MS


Red Hills Unit 49H / Coterra Red Hills Unit 49H Rev1 kFc 24May23

Schlumberger

COTERRA







PECOS DISTRICT DRILLING CONDITIONS OF APPROVAL

OPERATOR'S NAME:	Cimarex
LEASE NO.:	NMNM024368A
LOCATION:	Section 33, T.25 S, R.33 E., NMPM
COUNTY:	Lea County, New Mexico
WELL NAME & NO.:	Red Hills Unit 49H
SURFACE HOLE FOOTAGE:	347'/N & 1942'/W
BOTTOM HOLE FOOTAGE:	100'/S & 330'/W

Changes approved through engineering via **Sundry 2739382**_ on **11-28-2023**_. Any previous COAs not addressed within the updated COAs still apply.

COA

H_2S	C Yes	No							
Potash / WIPP	None	Secretary	C R-111-P	□ WIPP					
Cave / Karst	• Low	Medium	C High	Critical					
Wellhead	Conventional	• Multibowl	O Both	Diverter					
Cementing	☐ Primary Squeeze	☐ Cont. Squeeze	☐ EchoMeter	□ DV Tool					
Special Req	☐ Break Testing	☐ Water Disposal	□ COM	Unit					
Variance	▼ Flex Hose	☐ Casing Clearance	☐ Pilot Hole	☐ Capitan Reef					
Variance	☐ Four-String	☐ Offline Cementing	☐ Fluid-Filled	☐ Open Annulus					
☐ Batch APD / Sundry									

A. HYDROGEN SULFIDE

Hydrogen Sulfide (H2S) monitors shall be installed prior to drilling out the surface shoe. If H2S is detected in concentrations greater than 100 ppm, the Hydrogen Sulfide area must meet all requirements from **43 CFR 3176**, which includes equipment and personnel/public protection items. If Hydrogen Sulfide is encountered, provide measured values and formations to the BLM.

B. CASING

- 1. The 13-3/8 inch surface casing shall be set at approximately 976 feet (a minimum of 25 feet (Lea County) into the Rustler Anhydrite, above the salt, and below usable fresh water) and cemented to the surface.
 - a. If cement does not circulate to the surface, the appropriate BLM office shall be notified and a temperature survey utilizing an electronic type temperature survey with surface log readout will be used or a cement bond log shall be run to verify the top of the cement. Temperature survey will be run a minimum of six hours after pumping cement and ideally between 8-10 hours after completing the cement job.
 - b. Wait on cement (WOC) time for a primary cement job will be a minimum of $\underline{8}$

- **hours** or 500 pounds compressive strength, whichever is greater. (This is to include the lead cement)
- c. Wait on cement (WOC) time for a remedial job will be a minimum of 4 hours after bringing cement to surface or 500 pounds compressive strength, whichever is greater.
- d. If cement falls back, remedial cementing will be done prior to drilling out that string.
- 2. The minimum required fill of cement behind the 9-5/8 inch intermediate casing is:
 - Cement to surface. If cement does not circulate see B.1.a, c-d above.

Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry due to cave/karst.

- 3. The minimum required fill of cement behind the 7 inch production casing is:
 - Cement should tie-back at least **200 feet** into previous casing string. Operator shall provide method of verification.

Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry due to cave/karst.

- 4. The minimum required fill of cement behind the 4-1/2 inch production liner is:
 - Cement should tie-back **100 feet** into the previous casing. Operator shall provide method of verification.

C. PRESSURE CONTROL

- 1. Variance approved to use flex line from BOP to choke manifold. Manufacturer's specification to be readily available. No external damage to flex line. Flex line to be installed as straight as possible (no hard bends).'
- 2. Operator has proposed a multi-bowl wellhead assembly. This assembly will only be tested when installed on the surface casing. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the casing shoe shall be **5000** (**5M**) psi.
 - a. Wellhead shall be installed by manufacturer's representatives, submit documentation with subsequent sundry.
 - b. If the welding is performed by a third party, the manufacturer's representative shall monitor the temperature to verify that it does not exceed the maximum temperature of the seal.
 - c. Manufacturer representative shall install the test plug for the initial BOP test.
 - d. If the cement does not circulate and one inch operations would have been possible with a standard wellhead, the well head shall be cut off, cementing operations performed and another wellhead installed.
 - e. Whenever any seal subject to test pressure is broken, all the tests in 43 CFR 3172 must be followed.

D. SPECIAL REQUIREMENT (S)

Unit Wells

The well sign for a unit well shall include the unit number in addition to the surface and bottom hole lease numbers. This also applies to participating area numbers. If a participating area has not been established, the operator can use the general unit designation, but will replace the unit number with the participating area number when the sign is replaced.

Commercial Well Determination

A commercial well determination shall be submitted after production has been established for at least six months. (This is not necessary for secondary recovery unit wells)

GENERAL REQUIREMENTS

The BLM is to be notified in advance for a representative to witness:

- a. Spudding well (minimum of 24 hours)
- b. Setting and/or Cementing of all casing strings (minimum of 4 hours)
- c. BOPE tests (minimum of 4 hours)
 - Eddy County
 Email or call the Carlsbad Field Office, 620 East Greene St., Carlsbad, NM 88220, BLM_NM_CFO_DrillingNotifications@BLM.GOV (575) 361-2822
 - ✓ Lea CountyCall the Hobbs Field Station, 414 West Taylor, Hobbs NM 88240, (575) 689-5981
- 1. Unless the production casing has been run and cemented or the well has been properly plugged, the drilling rig shall not be removed from over the hole without prior approval.
 - a. In the event the operator has proposed to drill multiple wells utilizing a skid/walking rig. Operator shall secure the wellbore on the current well, after installing and testing the wellhead, by installing a blind flange of like pressure rating to the wellhead and a pressure gauge that can be monitored while drilling is performed on the other well(s).
 - b. When the operator proposes to set surface casing with Spudder Rig
 - Notify the BLM when moving in and removing the Spudder Rig.
 - Notify the BLM when moving in the 2nd Rig. Rig to be moved in within 90 days of notification that Spudder Rig has left the location.

- BOP/BOPE test to be conducted per **43 CFR part 3170 Subpart 3172** as soon as 2nd Rig is rigged up on well.
- 2. Floor controls are required for 3M or Greater systems. These controls will be on the rig floor, unobstructed, readily accessible to the driller and will be operational at all times during drilling and/or completion activities. Rig floor is defined as the area immediately around the rotary table; the area immediately above the substructure on which the draw works are located, this does not include the dog house or stairway area.
- 3. The record of the drilling rate along with the GR/N well log run from TD to surface (horizontal well vertical portion of hole) shall be submitted to the BLM office as well as all other logs run on the borehole 30 days from completion. If available, a digital copy of the logs is to be submitted in addition to the paper copies. The Rustler top and top and bottom of Salt are to be recorded on the Completion Report.

A. CASING

- 1. Changes to the approved APD casing program need prior approval if the items substituted are of lesser grade or different casing size or are Non-API. The Operator can exchange the components of the proposal with that of superior strength (i.e. changing from J-55 to N-80, or from 36# to 40#). Changes to the approved cement program need prior approval if the altered cement plan has less volume or strength or if the changes are substantial (i.e. Multistage tool, ECP, etc.). The initial wellhead installed on the well will remain on the well with spools used as needed.
- 2. Wait on cement (WOC) for Potash Areas: After cementing but before commencing any tests, the casing string shall stand cemented under pressure until both of the following conditions have been met: 1) cement reaches a minimum compressive strength of 500 psi for all cement blends, 2) until cement has been in place at least 24 hours. WOC time will be recorded in the driller's log. The casing intergrity test can be done (prior to the cement setting up) immediately after bumping the plug.
- 3. Wait on cement (WOC) for Water Basin: After cementing but before commencing any tests, the casing string shall stand cemented under pressure until both of the following conditions have been met: 1) cement reaches a minimum compressive strength of 500 psi at the shoe, 2) until cement has been in place at least 8 hours. WOC time will be recorded in the driller's log. See individual casing strings for details regarding lead cement slurry requirements. The casing integrity test can be done (prior to the cement setting up) immediately after bumping the plug.
- 4. Provide compressive strengths including hours to reach required 500 pounds compressive strength prior to cementing each casing string. Have well specific cement details onsite prior to pumping the cement for each casing string.

- 5. No pea gravel permitted for remedial or fall back remedial without prior authorization from the BLM engineer.
- 6. On that portion of any well approved for a 5M BOPE system or greater, a pressure integrity test of each casing shoe shall be performed. Formation at the shoe shall be tested to a minimum of the mud weight equivalent anticipated to control the formation pressure to the next casing depth or at total depth of the well. This test shall be performed before drilling more than 20 feet of new hole.
- 7. If hardband drill pipe is rotated inside casing, returns will be monitored for metal. If metal is found in samples, drill pipe will be pulled and rubber protectors which have a larger diameter than the tool joints of the drill pipe will be installed prior to continuing drilling operations.
- 8. Whenever a casing string is cemented in the R-111-P potash area, the NMOCD requirements shall be followed.
- B. PRESSURE CONTROL
- 1. All blowout preventer (BOP) and related equipment (BOPE) shall comply with well control requirements as described in 43 CFR part 3170 Subpart 3172 and API STD 53 Sec. 5.3.
- 2. If a variance is approved for a flexible hose to be installed from the BOP to the choke manifold, the following requirements apply: The flex line must meet the requirements of API 16C. Check condition of flexible line from BOP to choke manifold, replace if exterior is damaged or if line fails test. Line to be as straight as possible with no hard bends and is to be anchored according to Manufacturer's requirements. The flexible hose can be exchanged with a hose of equal size and equal or greater pressure rating. Anchor requirements, specification sheet and hydrostatic pressure test certification matching the hose in service, to be onsite for review. These documents shall be posted in the company man's trailer and on the rig floor.
- 3. 5M or higher system requires an HCR valve, remote kill line and annular to match. The remote kill line is to be installed prior to testing the system and tested to stack pressure.
- 4. If the operator has proposed a multi-bowl wellhead assembly in the APD. The following requirements must be met:
 - a. Wellhead shall be installed by manufacturer's representatives, submit documentation with subsequent sundry.
 - b. If the welding is performed by a third party, the manufacturer's representative shall monitor the temperature to verify that it does not exceed the maximum temperature of the seal.

- c. Manufacturer representative shall install the test plug for the initial BOP test.
- d. Whenever any seal subject to test pressure is broken, all the tests in 43 CFR part 3170 Subpart 3172 must be followed.
- e. If the cement does not circulate and one inch operations would have been possible with a standard wellhead, the well head shall be cut off, cementing operations performed and another wellhead installed.
- 5. The appropriate BLM office shall be notified a minimum of 4 hours in advance for a representative to witness the tests.
 - a. In a water basin, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. The casing cut-off and BOP installation can be initiated four hours after installing the slips, which will be approximately six hours after bumping the plug. For those casing strings not using slips, the minimum wait time before cut-off is eight hours after bumping the plug. BOP/BOPE testing can begin after cut-off or once cement reaches 500 psi compressive strength (including lead cement), whichever is greater. However, if the float does not hold, cut-off cannot be initiated until cement reaches 500 psi compressive strength (including lead when specified).
 - b. In potash areas, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. For all casing strings, casing cut-off and BOP installation can be initiated at twelve hours after bumping the cement plug. The BOPE test can be initiated after bumping the cement plug with the casing valve open. (only applies to single stage cement jobs, prior to the cement setting up.)
 - c. The tests shall be done by an independent service company utilizing a test plug not a cup or J-packer and can be initiated immediately with the casing valve open. The operator also has the option of utilizing an independent tester to test without a plug (i.e. against the casing) pursuant to **43 CFR part 3170 Subpart 3172** with the pressure not to exceed 70% of the burst rating for the casing. Any test against the casing must meet the WOC time for water basin (8 hours) or potash (24 hours) or 500 pounds compressive strength, whichever is greater, prior to initiating the test (see casing segment as lead cement may be critical item).
 - d. The test shall be run on a 5000 psi chart for a 2-3M BOP/BOP, on a 10000 psi chart for a 5M BOP/BOPE and on a 15000 psi chart for a 10M BOP/BOPE. If a linear chart is used, it shall be a one hour chart. A circular chart shall have a maximum 2 hour clock. If a twelve hour or twenty-four hour chart is used, tester shall make a notation that it is run with a two hour clock.
 - e. The results of the test shall be reported to the appropriate BLM office.

- f. All tests are required to be recorded on a calibrated test chart. A copy of the BOP/BOPE test chart and a copy of independent service company test will be submitted to the appropriate BLM office.
- g. The BOP/BOPE test shall include a low pressure test from 250 to 300 psi. The test will be held for a minimum of 10 minutes if test is done with a test plug and 30 minutes without a test plug. This test shall be performed prior to the test at full stack pressure.
- h. BOP/BOPE must be tested by an independent service company within 500 feet of the top of the Wolfcamp formation if the time between the setting of the intermediate casing and reaching this depth exceeds 20 days. This test does not exclude the test prior to drilling out the casing shoe as per 43 CFR part 3170 Subpart 3172.

C. DRILLING MUD

Mud system monitoring equipment, with derrick floor indicators and visual and audio alarms, shall be operating before drilling into the Wolfcamp formation, and shall be used until production casing is run and cemented.

D. WASTE MATERIAL AND FLUIDS

All waste (i.e. drilling fluids, trash, salts, chemicals, sewage, gray water, etc.) created as a result of drilling operations and completion operations shall be safely contained and disposed of properly at a waste disposal facility. No waste material or fluid shall be disposed of on the well location or surrounding area.

Porto-johns and trash containers will be on-location during fracturing operations or any other crew-intensive operations.

ZS 11/29/2023

District I
1625 N. French Dr., Hobbs, NM 88240
Phone: (575) 393-6161 Fax: (575) 393-0720

District II 811 S. First St., Artesia, NM 88210 Phone:(575) 748-1283 Fax:(575) 748-9720

District III 1000 Rio Brazos Rd., Aztec, NM 87410 Phone:(505) 334-6178 Fax:(505) 334-6170

1220 S. St Francis Dr., Santa Fe, NM 87505 Phone:(505) 476-3470 Fax:(505) 476-3462

State of New Mexico Energy, Minerals and Natural Resources Oil Conservation Division 1220 S. St Francis Dr. **Santa Fe, NM 87505**

CONDITIONS

Action 291654

CONDITIONS

Operator:	OGRID:
CIMAREX ENERGY CO.	215099
6001 Deauville Blvd	Action Number:
Midland, TX 79706	291654
	Action Type:
	[C-103] NOI Change of Plans (C-103A)

CONDITIONS

Created By		Condition Date
pkautz	None	1/22/2024