

District I
1625 N. French Dr., Hobbs, NM 88240
District II
811 S. First St., Artesia, NM 88210
District III
1000 Rio Brazos Rd., Aztec, NM 87410
District IV
1220 S. St. Francis Dr., Santa Fe, NM 87505

Oil Conservation Division
1220 South St. Francis Dr.
Santa Fe, NM 87505

Submit one copy to appropriate District Office

☐ AMENDED REPORT

I. REQUEST FOR ALLOWABLE AND AUTHORIZATION TO TRANSPORT

¹ Operator name and Address OXY USA INC. PO BOX 50250 MIDLAND, TX 79710		² OGRID Number 16696
		³ Reason for Filing Code/ Effective Date NW - 10/05/2023
⁴ API Number 30 - 025-48938	⁵ Pool Name Antelope Ridge; Wolfcamp	⁶ Pool Code 2220
⁷ Property Code 330848	⁸ Property Name Saker 6-7 Fed Com	⁹ Well Number 37H

II. ¹⁰ Surface Location

UL or lot no.	Section	Township	Range	Lot Idn	Feet from the	North/South Line	Feet from the	East/West line	County
1	6	24S	35E		180	North	920	East	Lea

¹¹ Bottom Hole Location

UL or lot no.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County
O	7	24S	35E		32	South	2263	East	Lea
¹² Lse Code F	¹³ Producing Method Code F	¹⁴ Gas Connection Date	¹⁵ C-129 Permit Number		¹⁶ C-129 Effective Date		¹⁷ C-129 Expiration Date		

III. Oil and Gas Transporters

¹⁸ Transporter OGRID	¹⁹ Transporter Name and Address	²⁰ O/G/W
237722	Centerion Pipeline L.P.	O
248749	DCP Midstream, LP	G

IV. Well Completion Data

²¹ Spud Date 06/03/2023	²² Ready Date 10/05/2023	²³ TD 22080' MD, 12139' TVD	²⁴ PBTD 22037' MD, 12135' TVD	²⁵ Perforations 12054-21917	²⁶ DHC, MC
²⁷ Hole Size		²⁸ Casing & Tubing Size		²⁹ Depth Set	³⁰ Sacks Cement
17 1/2"		13 3/8" 54.5# J-55		1086	1605sx Class C - TOC 0'
9 7/8"		7 5/8" 26.4# HCL80		11215	3136sx Class H - TOC 0'
6 3/4"		5 1/2" 20# P110		22060	734sx Class H - TOC 0'

V. Well Test Data

³¹ Date New Oil 11/16/2023	³² Gas Delivery Date 11/16/2023	³³ Test Date 11/19/2023	³⁴ Test Length 24 hours	³⁵ Tbg. Pressure 0	³⁶ Csg. Pressure 851
³⁷ Choke Size 0	³⁸ Oil 2610	³⁹ Water 3667	⁴⁰ Gas 2911		⁴¹ Test Method Flowing

⁴² I hereby certify that the rules of the Oil Conservation Division have been complied with and that the information given above is true and complete to the best of my knowledge and belief. Signature: 		OIL CONSERVATION DIVISION	
Printed name: Sarah McKinney		Approved by:	
Title: Regulatory Analyst Sr.		Title:	
E-mail Address: sarah_mckinney@oxy.com		Approval Date:	
Date: 12/05/2023	Phone: 713-215-7295		

District I
1625 N. French Dr., Hobbs, NM 88240
Phone: (575) 393-6161 Fax: (575) 393-0720
District II
811 S. First St., Artesia, NM 88210
Phone: (575) 748-1283 Fax: (575) 748-9720
District III
1000 Rio Brazos Road, Aztec, NM 87410
Phone: (505) 334-6178 Fax: (505) 334-6170
District IV
1220 S. St. Francis Dr., Santa Fe, NM 87505
Phone: (505) 476-3460 Fax: (505) 476-3462

State of New Mexico
Energy, Minerals & Natural Resources Department
OIL CONSERVATION DIVISION
1220 South St. Francis Dr.
Santa Fe, NM 87505

Form C-102
Revised August 1, 2011
Submit one copy to appropriate
District Office

☒ AMENDED REPORT

As-Drilled Plat

WELL LOCATION AND ACREAGE DEDICATION PLAT

¹ API Number 30-025-48938		² Pool Code 2220		³ Pool Name Antelope Ridge; Wolfcamp	
⁴ Property Code 330848		⁵ Property Name SAKER 6 7 FED COM			⁶ Well Number 37H
⁷ OGRID No. 16696		⁸ Operator Name OXY USA INC.			⁹ Elevation 3450.1' (NAVD 88)

¹⁰ Surface Location

UL or lot no. 1	Section 6	Township 24S	Range 35E	Lot Idn	Feet from the 180	North/South line NORTH	Feet from the 920	East/West line EAST	County LEA
--------------------	--------------	-----------------	--------------	---------	----------------------	---------------------------	----------------------	------------------------	---------------

¹¹ Bottom Hole Location If Different From Surface

UL or lot no. O	Section 7	Township 24S	Range 35E	Lot Idn	Feet from the 32	North/South line SOUTH	Feet from the 2263	East/West line EAST	County LEA
¹² Dedicated Acres 640.06		¹³ Joint or Infill Infill		¹⁴ Consolidation Code		¹⁵ Order No.			

No allowable will be assigned to this completion until all interests have been consolidated or a non-standard unit has been approved by the division.

¹⁶ NAD 83 (SURFACE HOLE LOCATION) LATITUDE = 32°15'11.97" (32.253324°) LONGITUDE = -103°24'04.03" (-103.401120°) NAD 27 (SURFACE HOLE LOCATION) LATITUDE = 32°15'11.52" (32.253199°) LONGITUDE = -103°24'02.33" (-103.400647°) STATE PLANE NAD 83 (N.M. EAST) N: 457143.81' E: 829520.67' STATE PLANE NAD 27 (N.M. EAST) N: 457084.42' E: 788336.08'	NAD 83 (AS-DRILLED KOP) LATITUDE = 32°15'12.81" (32.253559°) LONGITUDE = -103°24'18.58" (-103.405161°) NAD 27 (AS-DRILLED KOP) LATITUDE = 32°15'12.36" (32.253434°) LONGITUDE = -103°24'16.88" (-103.404688°) STATE PLANE NAD 83 (N.M. EAST) N: 457218.56' E: 828270.61' STATE PLANE NAD 27 (N.M. EAST) N: 457159.18' E: 787086.06'	NAD 83 (AS-DRILLED FTP) LATITUDE = 32°15'08.33" (32.252314°) LONGITUDE = -103°24'19.63" (-103.405453°) NAD 27 (AS-DRILLED FTP) LATITUDE = 32°15'07.88" (32.252189°) LONGITUDE = -103°24'17.93" (-103.404979°) STATE PLANE NAD 83 (N.M. EAST) N: 456764.70' E: 828184.33' STATE PLANE NAD 27 (N.M. EAST) N: 456705.34' E: 786999.77'
NAD 83 (AS-DRILLED LPP #1) LATITUDE = 32°14'21.48" (32.239299°) LONGITUDE = -103°24'19.47" (-103.405410°) NAD 27 (AS-DRILLED LPP) LATITUDE = 32°14'21.03" (32.239174°) LONGITUDE = -103°24'17.77" (-103.404937°) STATE PLANE NAD 83 (N.M. EAST) N: 452029.93' E: 828238.62' STATE PLANE NAD 27 (N.M. EAST) N: 451970.70' E: 787053.86'	NAD 83 (AS-DRILLED LPP #2) LATITUDE = 32°13'55.35" (32.232041°) LONGITUDE = -103°24'19.81" (-103.405502°) NAD 27 (AS-DRILLED LPP #2) LATITUDE = 32°13'54.90" (32.231916°) LONGITUDE = -103°24'18.11" (-103.405030°) STATE PLANE NAD 83 (N.M. EAST) N: 449389.25' E: 828232.84' STATE PLANE NAD 27 (N.M. EAST) N: 449330.08' E: 787047.97'	NAD 83 (AS-DRILLED LTP) LATITUDE = 32°13'31.14" (32.225315°) LONGITUDE = -103°24'19.54" (-103.405429°) NAD 27 (AS-DRILLED LTP) LATITUDE = 32°13'30.68" (32.225190°) LONGITUDE = -103°24'17.85" (-103.404957°) STATE PLANE NAD 83 (N.M. EAST) N: 446942.63' E: 828276.55' STATE PLANE NAD 27 (N.M. EAST) N: 446883.53' E: 787091.57'
NAD 83 (AS-DRILLED BHL) LATITUDE = 32°13'29.54" (32.224873°) LONGITUDE = -103°24'19.37" (-103.405381°) NAD 27 (AS-DRILLED BHL) LATITUDE = 32°13'29.09" (32.224747°) LONGITUDE = -103°24'17.67" (-103.404909°) STATE PLANE NAD 83 (N.M. EAST) N: 446781.62' E: 828292.92' STATE PLANE NAD 27 (N.M. EAST) N: 446722.52' E: 787107.93'		

¹⁷ OPERATOR
CERTIFICATION

I hereby certify that the information contained herein is true and complete to the best of my knowledge and belief, and that this organization either owns a working interest or unleased mineral interest in the land including the proposed bottom hole location or has a right to drill this well at this location pursuant to a contract with an owner of such a mineral or working interest, or to a voluntary pooling agreement or a compulsory pooling order heretofore entered by the division.

Sarah McKinney 12/05/2023
Signature Date

Sarah McKinney
Printed Name

sarah_mckinney@oxy.com
E-mail Address

¹⁸ SURVEYOR
CERTIFICATION

I hereby certify that the well location shown on this plat was plotted from field notes of actual surveys made by me or under my supervision, and that the same is true and correct to the best of my belief.

December 12, 2019

Date of Survey
Signature and Seal of Professional Surveyor:



Certificate Number:

LINE TABLE

LINE	DIRECTION	LENGTH
L1	S89°41'56"W	2640.30'
L2	S89°45'26"W	2646.85'


APPROXIMATE WELL BORE DISTANCE FROM FTP TO LTP	
TRACT	DISTANCE
FEE	2,645.52'
NMNM 014164	7,192.92'
TOTAL	9,838.44'

- NOTE:
- Distances referenced on plat to section lines are perpendicular.
 - Basis of Bearings is a Transverse Mercator Projection with a Central Meridian of W103°53'00" (NAD 83)
 - As-Drilled well head has not been field verified.
 - Well Bore data provided by Oxy USA Inc.



SCALE

DRAWN BY: Z.L. 10-03-23
REV: 1 Z.L. 10-16-23 (UPDATE HSU)





Oxy Saker 6-7 Fed Com 37H IFR1 to 22080ft Survey Geodetic Report



DefinitiveSurvey

Report Date: July 18, 2023 - 10:34 PM (UTC 0)
 Client: OXY
 Field: NM Lea County (NAD 83)
 Structure / Slot: Oxy Saker 6-7 Fed Com Pad Lot 1 / Saker 6-7 Fed Com Pad 37H
 Well: Saker 6-7 Fed Com 37H
 Borehole: Saker 6-7 Fed Com 37H
 UBHI / API / JobNumber: Unknown / Unknown / Unknown
 Survey Name / Version: Oxy Saker 6-7 Fed Com 37H IFR1 to 22080ft / 3
 Survey Date: July 17, 2023
 Tort / AHD / DDI / ERD Ratio: 349.434' +/- 11761.123 ft / 6.874 / 0.969
 Coordinate Reference System: NAD83 New Mexico State Plane, Eastern Zone, US Feet
 Location Lat / Long: N 32°15'11.96704", W 103°24'4.03215"
 Location Grid N/E/Y/X: N 45°143.810 RUS , E 829520.670 RUS
 CRS Grid Convergence Angle: 0.4975°
 Grid Scale Factor: 1.00000421
 Engine Version: 2023.1.0.1

Survey / DLS Computation: Minimum Curvature / Lubinski
 Vertical Section Azimuth: 186.757° (Grid North)
 Vertical Section Origin: 0.000 ft, 0.000 ft
 TVD Reference Datum: RKB
 TVD Reference Elevation: 3474.100 ft above MSL
 Seabed / Ground Elevation: 3450.100 ft above MSL
 Magnetic Declination: 6.295°
 Total Gravity Field Strength: 998.4648mgn (9.80665 Based)
 Gravity Model: GARM
 Total Magnetic Field Strength: 47528.7 nT
 Magnetic Dip Angle: 59.832°
 Declination Date: July 01, 2023
 Magnetic Declination Model: IFR1
 North Reference: Grid
 Total Corr Mag: 5.7975°
 Local Coord Referenced To: Well Head

Comments	MD (ft)	Incl (°)	Azim (°)	TVD (ft)	VSEC (ft)	NS (ft)	EW (ft)	TVDSS (ft)	DLS (°/100ft)	Northing (ftUS)	Easting (ftUS)	Latitude (N/S ° ' ")	Longitude (E/W ° ' ")	Closure (ft)	Closure Azimuth (°)
WFRP	0.00	0.00	0.00	0.00	0.00	0.00	0.00	-3,474.10		457,143.81	829,520.67	N 32°15'11.97"	W 103°24'4.03"		
SHL	24.00	0.00	0.00	24.00	0.00	0.00	0.00	-3,450.10	0.00	457,143.81	829,520.67	N 32°15'11.97"	W 103°24'4.03"	0.00	0.00
First 3rd Party Survey	173.00	1.07	4.59	172.99	-1.39	1.39	0.11	-3,301.11	0.72	457,145.20	829,520.78	N 32°15'11.98"	W 103°24'4.03"	1.39	4.59
	260.00	1.19	4.69	259.97	-3.10	3.10	0.25	-3,214.13	0.14	457,146.91	829,520.92	N 32°15'12.00"	W 103°24'4.03"	3.11	4.62
	355.00	0.70	21.56	354.96	-4.65	4.62	0.54	-3,119.14	0.59	457,148.43	829,521.21	N 32°15'12.01"	W 103°24'4.03"	4.65	6.72
	449.00	0.16	28.95	448.96	-5.33	5.27	0.82	-3,025.14	0.58	457,149.08	829,521.49	N 32°15'12.02"	W 103°24'4.02"	5.33	8.83
	543.00	0.12	104.72	542.96	-5.44	5.36	0.98	-2,931.14	0.19	457,149.17	829,521.65	N 32°15'12.02"	W 103°24'4.02"	5.45	10.34
Last 3rd Party Survey First SLB Survey	638.00	0.25	113.62	637.96	-5.36	5.25	1.26	-2,836.14	0.14	457,149.06	829,521.93	N 32°15'12.02"	W 103°24'4.02"	5.40	13.53
	732.00	0.22	71.07	731.96	-5.38	5.23	1.62	-2,742.14	0.18	457,149.04	829,522.29	N 32°15'12.02"	W 103°24'4.01"	5.47	17.24
	826.00	0.36	83.20	825.96	-5.53	5.32	2.09	-2,648.14	0.16	457,149.13	829,522.76	N 32°15'12.02"	W 103°24'4.01"	5.71	21.41
	921.00	0.08	95.19	920.95	-5.60	5.35	2.45	-2,553.15	0.30	457,149.16	829,523.12	N 32°15'12.02"	W 103°24'4.00"	5.88	24.59
	1,014.00	0.23	274.34	1,013.95	-5.59	5.36	2.33	-2,460.15	0.33	457,149.17	829,523.00	N 32°15'12.02"	W 103°24'4.00"	5.84	23.48
	1,037.00	0.32	312.48	1,036.95	-5.63	5.40	2.23	-2,437.15	0.86	457,149.21	829,522.90	N 32°15'12.02"	W 103°24'4.01"	5.85	22.45
	1,119.00	0.14	247.54	1,118.95	-5.71	5.52	1.97	-2,355.15	0.35	457,149.33	829,522.64	N 32°15'12.02"	W 103°24'4.01"	5.86	19.66
	1,212.00	0.08	216.52	1,211.95	-5.60	5.43	1.83	-2,262.15	0.09	457,149.24	829,522.50	N 32°15'12.02"	W 103°24'4.01"	5.73	18.66
	1,306.00	0.09	77.64	1,305.95	-5.57	5.39	1.86	-2,168.15	0.17	457,149.20	829,522.53	N 32°15'12.02"	W 103°24'4.01"	5.70	19.06
	1,401.00	0.10	75.35	1,400.95	-5.62	5.43	2.01	-2,073.15	0.01	457,149.24	829,522.68	N 32°15'12.02"	W 103°24'4.01"	5.79	20.37
	1,495.00	0.10	106.31	1,494.95	-5.64	5.42	2.17	-1,979.15	0.06	457,149.23	829,522.84	N 32°15'12.02"	W 103°24'4.01"	5.84	21.83
	1,587.00	0.08	189.88	1,586.95	-5.56	5.34	2.24	-1,887.15	0.13	457,149.15	829,522.91	N 32°15'12.02"	W 103°24'4.01"	5.79	22.76
	1,681.00	0.06	169.33	1,680.95	-5.45	5.22	2.24	-1,793.15	0.03	457,149.03	829,522.91	N 32°15'12.02"	W 103°24'4.01"	5.68	23.18
	1,871.00	0.08	271.05	1,870.95	-5.34	5.13	2.12	-1,603.15	0.06	457,148.94	829,522.79	N 32°15'12.02"	W 103°24'4.01"	5.55	22.48
	1,966.00	0.06	252.49	1,965.95	-5.32	5.12	2.01	-1,508.15	0.03	457,148.93	829,522.68	N 32°15'12.02"	W 103°24'4.01"	5.50	21.44
	2,060.00	0.10	16.22	2,059.95	-5.38	5.18	1.98	-1,414.15	0.15	457,148.99	829,522.65	N 32°15'12.02"	W 103°24'4.01"	5.55	20.97
	2,155.00	0.09	321.56	2,154.95	-5.51	5.32	1.96	-1,319.15	0.09	457,149.13	829,522.63	N 32°15'12.02"	W 103°24'4.01"	5.67	20.25
	2,250.00	0.09	107.45	2,249.95	-5.55	5.35	1.99	-1,224.15	0.18	457,149.16	829,522.66	N 32°15'12.02"	W 103°24'4.01"	5.71	20.36
	2,344.00	0.08	28.60	2,343.95	-5.60	5.39	2.09	-1,130.15	0.12	457,149.20	829,522.76	N 32°15'12.02"	W 103°24'4.01"	5.78	21.18
	2,439.00	0.11	12.46	2,438.95	-5.75	5.54	2.14	-1,035.15	0.04	457,149.35	829,522.81	N 32°15'12.02"	W 103°24'4.01"	5.93	21.13
	2,533.00	0.07	133.76	2,532.95	-5.80	5.58	2.20	-941.15	0.17	457,149.39	829,522.87	N 32°15'12.02"	W 103°24'4.01"	6.00	21.51
	2,628.00	0.07	160.89	2,627.95	-5.72	5.49	2.26	-846.15	0.03	457,149.30	829,522.93	N 32°15'12.02"	W 103°24'4.01"	5.94	22.39
	2,722.00	0.08	69.32	2,721.95	-5.70	5.46	2.34	-752.15	0.11	457,149.27	829,523.01	N 32°15'12.02"	W 103°24'4.00"	5.94	23.22
	2,817.00	0.07	125.81	2,816.95	-5.70	5.45	2.45	-657.15	0.08	457,149.26	829,523.12	N 32°15'12.02"	W 103°24'4.00"	5.97	24.22
	2,912.00	0.06	254.36	2,911.95	-5.65	5.40	2.45	-562.15	0.12	457,149.21	829,523.12	N 32°15'12.02"	W 103°24'4.00"	5.93	24.40
3,006.00	0.10	8.77	3,005.95	-5.71	5.47	2.41	-468.15	0.14	457,149.28	829,523.08	N 32°15'12.02"	W 103°24'4.00"	5.98	23.83	
3,101.00	0.08	73.02	3,100.95	-5.82	5.57	2.49	-373.15	0.10	457,149.38	829,523.16	N 32°15'12.02"	W 103°24'4.00"	6.10	24.10	
3,196.00	0.16	4.08	3,195.95	-5.98	5.72	2.56	-278.15	0.16	457,149.53	829,523.23	N 32°15'12.02"	W 103°24'4.00"	6.27	24.14	
3,290.00	0.11	39.82	3,289.95	-6.19	5.92	2.63	-184.15	0.10	457,149.73	829,523.30	N 32°15'12.03"	W 103°24'4.00"	6.48	23.95	
3,385.00	0.05	84.87	3,384.95	-6.27	6.00	2.73	-89.15	0.09	457,149.81	829,523.40	N 32°15'12.03"	W 103°24'4.00"	6.59	24.49	
3,480.00	0.10	108.97	3,479.95	-6.27	5.97	2.85	5.85	0.06	457,149.78	829,523.52	N 32°15'12.03"	W 103°24'4.00"	6.62	25.51	
3,574.00	0.11	198.66	3,573.95	-6.16	5.86	2.90	99.85	0.16	457,149.67	829,523.57	N 32°15'12.02"	W 103°24'4.00"	6.54	26.32	
3,669.00	0.37	146.45	3,668.95	-5.84	5.52	3.04	194.85	0.33	457,149.33	829,523.71	N 32°15'12.02"	W 103°24'4.00"	6.30	28.85	
3,764.00	0.21	106.04	3,763.95	-5.57	5.21	3.38	289.85	0.26	457,149.02	829,524.05	N 32°15'12.02"	W 103°24'3.99"	6.21	32.92	
3,859.00	0.20	35.79	3,858.95	-5.69	5.30	3.64	384.85	0.25	457,149.11	829,524.31	N 32°15'12.02"	W 103°24'3.99"	6.43	34.48	
3,953.00	0.53	62.94	3,952.95	-6.08	5.63	4.12	478.85	0.39	457,149.44	829,524.79	N 32°15'12.02"	W 103°24'3.98"	6.98	36.21	
4,048.00	0.64	60.65	4,047.94	-6.63	6.09	4.98	573.84	0.12	457,149.90	829,525.65	N 32°15'12.03"	W 103°24'3.97"	7.87	39.25	
4,143.00	0.35	30.42	4,142.94	-7.21	6.50	5.59	668.84	0.40	457,150.41	829,526.26	N 32°15'12.03"	W 103°24'3.97"	8.65	40.24	
4,237.00	0.23	40.00	4,236.94	-7.63	6.99	6.95	762.84	0.14	457,150.80	829,526.52	N 32°15'12.04"	W 103°24'3.96"	9.12	39.93	
4,326.00	0.87	234.51	4,325.93	-6.99	6.45	4.93	951.83	0.58	457,150.26	829,525.60	N 32°15'12.03"	W 103°24'3.97"	8.12	37.38	
4,521.00	0.28	256.21	4,520.93	-6.42	5.98	4.12	1,046.83	0.65	457,149.79	829,524.79	N 32°15'12.03"	W 103°24'3.98"	7.26	34.55	
4,616.00	0.51	55.44	4,615.93	-6.62	6.16	4.24	1,141.83	0.82	457,149.97	829,524.91	N 32°15'12.03"	W 103°24'3.98"	7.48	34.53	
4,710.00	0.68	63.81	4,709.92	-7.20	6.65	5.08	1,235.82	0.20	457,150.46	829,525.75	N 32°15'12.03"	W 103°24'3.97"	8.37	37.42	
4,805.00	0.37	71.94	4,804.92	-7.63	6.99	5.88	1,330.82	0.33	457,150.80	829,526.55	N 32°15'12.04"	W 103°24'3.96"	9.13	40.08	
4,900.00	0.36	56.43	4,899.91	-7.95	7.25	6.42	1,425.81	0.10	457,151.06	829,527.09	N 32°15'12.04"	W 103°24'3.96"	9.68	41.54	
4,994.00	0.13	314.00	4,993.91	-8.21	7.49	6.59	1,519.81	0.43	457,151.30	829,527.26	N 32°15'12.04"	W 103°24'3.95"	9.97	41.36	
5,089.00	0.08	178.27	5,088.91	-8.21	7.49	6.52	1,614.81	0.21	457,151.09	829,527.19	N 32°15'12.04"	W 103°24'3.96"	9.93	41.00	
5,184.00	0.37	241.81	5,183.91	-7.97	7.28	6.25	1,709.81	0.36	457,151.09	829,526.92	N 32°15'12.04"	W 103°24'3.96"	9.60	40.82	
5,278.00	1.18	241.66	5,277.90	-7.24	6.68	5.13	1,803.80	0.86	457,150.49	829,525.80	N 32°15'12.03"	W 103°24'3.97"	8.42	37.51	
5,373.00	2.19	243.75	5,372.86	-5.69	5.41	2.64	1,898.76	1.06	457,149.22	829,523.31	N 32°15'12.02"	W 103°24'4.00"	6.02	25.98	
5,468.00	3.69	245.36	5,467.73	-3.11	3.34	-1.77	1,993.63	1.58	457,147.15	829,518.90	N 32°15'12.00"	W 103°24'4.05"	3.78	332.06	
5,562.00	5.34	250.24	5,561.44	0.42	0.60	-8.63	2,087.34	1.80	457,144.41	829,512.04	N 32°15'11.97"	W 103°24'4.13"	8.66	273.95	
5,657.00	6.63	252.48	5,655.92	4.65	-2.55	-18.03	2,181.82	1.38	457,141.26	829,502.64	N 32°15'11.94"	W 103°24'4.24"	18.20	261.95	
5,752.00	7.72	254.39	5,750.17	9.34	-5.92	-29.40	2,276.07	1							

	9,349.00	12.89	277.80	9,218.17	77.38	35.67	-958.70	5,744.07	0.73	457,179.48	828,561.97	N 32°15'12.40"	W 103°24'15.19"	959.36	272.13
	9,444.00	14.53	277.96	9,310.46	76.94	38.76	-981.01	5,836.36	1.74	457,182.57	828,539.66	N 32°15'12.43"	W 103°24'15.45"	981.77	272.26
	9,538.00	14.44	279.56	9,401.47	76.12	42.34	-1,004.24	5,927.37	0.44	457,186.15	828,516.43	N 32°15'12.47"	W 103°24'15.72"	1,005.13	272.41
	9,633.00	12.27	279.48	9,493.71	75.02	46.10	-1,026.67	6,019.61	1.22	457,189.91	828,494.00	N 32°15'12.51"	W 103°24'15.98"	1,027.70	272.57
	9,728.00	12.12	280.54	9,586.38	73.84	49.72	-1,047.73	6,112.39	1.24	457,193.53	828,473.44	N 32°15'12.55"	W 103°24'16.25"	1,048.41	272.72
	9,822.00	11.25	282.26	9,678.44	72.31	53.47	-1,065.89	6,204.34	1.00	457,197.28	828,454.78	N 32°15'12.59"	W 103°24'16.44"	1,067.23	272.87
	9,917.00	10.62	282.27	9,771.71	70.58	57.30	-1,083.50	6,297.61	0.66	457,201.11	828,437.17	N 32°15'12.63"	W 103°24'16.64"	1,085.02	273.03
	10,106.00	9.99	278.86	9,957.66	68.31	63.53	-1,116.72	6,483.56	0.46	457,207.34	828,403.95	N 32°15'12.69"	W 103°24'17.03"	1,118.52	273.26
	10,201.00	9.40	280.97	10,051.31	67.44	66.27	-1,132.48	6,577.21	0.72	457,210.08	828,388.19	N 32°15'12.72"	W 103°24'17.21"	1,134.41	273.35
	10,391.00	7.12	289.11	10,239.33	63.78	73.08	-1,158.84	6,765.23	1.35	457,216.89	828,361.83	N 32°15'12.79"	W 103°24'17.52"	1,161.14	273.61
	10,486.00	6.14	291.29	10,333.69	61.24	76.85	-1,169.14	6,859.59	1.06	457,220.66	828,351.53	N 32°15'12.83"	W 103°24'17.64"	1,171.66	273.76
	10,580.00	7.47	289.01	10,427.03	58.68	80.67	-1,179.60	6,952.93	1.44	457,224.48	828,341.07	N 32°15'12.87"	W 103°24'17.76"	1,182.35	273.91
	10,675.00	5.49	291.70	10,521.42	56.20	84.36	-1,189.66	7,047.32	2.11	457,228.17	828,331.01	N 32°15'12.90"	W 103°24'17.88"	1,192.65	274.06
	10,770.00	4.55	292.00	10,616.05	54.04	87.45	-1,197.38	7,141.95	0.99	457,231.26	828,323.29	N 32°15'12.94"	W 103°24'17.97"	1,200.57	274.18
	10,864.00	5.66	272.69	10,709.68	53.39	89.07	-1,205.46	7,235.58	2.16	457,232.88	828,315.20	N 32°15'12.95"	W 103°24'18.05"	1,208.75	274.23
	10,959.00	6.97	264.06	10,804.11	54.99	86.69	-1,215.88	7,330.01	0.70	457,232.50	828,304.79	N 32°15'12.95"	W 103°24'18.15"	1,219.11	274.17
	11,053.00	7.13	257.53	10,897.40	58.16	86.84	-1,227.25	7,423.30	0.87	457,230.65	828,293.42	N 32°15'12.93"	W 103°24'18.31"	1,230.32	274.05
	11,148.00	6.33	243.12	10,991.75	63.00	83.20	-1,237.68	7,517.65	1.96	457,227.01	828,282.99	N 32°15'12.90"	W 103°24'18.44"	1,240.47	273.85
	11,201.00	5.80	241.58	11,044.45	66.16	80.60	-1,242.64	7,570.35	1.05	457,224.41	828,278.03	N 32°15'12.87"	W 103°24'18.57"	1,245.25	273.71
	11,269.00	5.11	238.76	11,112.14	70.01	77.40	-1,248.25	7,638.04	1.09	457,221.21	828,272.42	N 32°15'12.84"	W 103°24'18.66"	1,250.65	273.55
Actual KOP	11,304.00	6.22	194.60	11,146.99	72.85	74.75	-1,250.06	7,672.89	12.51	457,218.56	828,270.61	N 32°15'12.81"	W 103°24'18.58"	1,252.29	273.42
FTP / 100ft FNL Cross	11,350.00	10.65	168.44	11,192.50	79.36	68.17	-1,249.84	7,718.40	12.51	457,211.98	828,270.83	N 32°15'12.75"	W 103°24'18.58"	1,251.69	273.12
	11,361.00	11.88	165.25	11,203.28	81.38	66.08	-1,249.34	7,729.18	12.51	457,209.89	828,271.32	N 32°15'12.73"	W 103°24'18.57"	1,251.09	273.03
	11,455.00	21.15	173.21	11,293.32	106.93	39.82	-1,244.86	7,819.22	10.13	457,183.63	828,275.80	N 32°15'12.47"	W 103°24'18.52"	1,245.50	271.83
	11,549.00	9.44	181.79	11,378.92	117.02	40.70	-1,243.69	7,903.90	10.32	457,143.11	828,271.07	N 32°15'12.07"	W 103°24'18.51"	1,243.59	269.87
	11,644.00	29.74	196.42	11,455.92	200.94	53.89	-1,252.96	7,991.82	13.35	457,089.92	828,251.54	N 32°15'11.54"	W 103°24'18.53"	1,254.12	267.54
	11,739.00	47.49	200.99	11,524.67	264.93	-115.82	-1,274.13	8,050.57	8.80	457,027.99	828,246.54	N 32°15'10.93"	W 103°24'18.85"	1,279.38	264.81
	11,833.00	56.54	196.01	11,582.48	337.39	-186.03	-1,297.41	8,108.38	10.49	456,957.78	828,223.26	N 32°15'10.24"	W 103°24'19.16"	1,310.68	261.84
	11,928.00	63.82	190.81	11,629.71	419.17	-266.14	-1,316.37	8,155.61	9.01	456,877.67	828,204.30	N 32°15'9.45"	W 103°24'19.39"	1,343.00	258.57
Wolfcamp Intersection	11,965.64	64.91	190.33	11,646.00	453.03	-299.50	-1,322.59	8,171.90	3.11	456,844.31	828,198.08	N 32°15'9.12"	W 103°24'19.36"	1,356.08	257.24
	12,023.00	66.57	189.61	11,669.57	505.24	-351.00	-1,331.64	8,195.47	3.11	456,792.81	828,189.03	N 32°15'8.61"	W 103°24'19.57"	1,377.12	255.23
Enter Lateral Window	12,030.00	66.68	189.55	11,672.34	511.66	-357.34	-1,332.71	8,198.24	1.79	456,786.47	828,187.96	N 32°15'8.55"	W 103°24'19.59"	1,379.79	254.99
	12,118.00	68.10	188.80	11,706.17	592.82	-437.53	-1,345.66	8,232.07	1.79	456,706.28	828,175.91	N 32°15'7.75"	W 103°24'19.75"	1,415.00	251.99
	12,187.00	87.44	183.31	11,746.05	776.56	-620.30	-1,364.72	8,271.95	10.62	456,523.51	828,155.95	N 32°15'5.95"	W 103°24'19.99"	1,496.08	245.56
	12,402.00	89.26	177.18	11,748.79	870.86	-715.21	-1,389.42	8,321.65	6.73	456,428.60	828,155.54	N 32°15'5.01"	W 103°24'20.07"	1,541.13	242.35
	12,497.00	88.20	172.41	11,750.90	963.75	-809.77	-1,356.51	8,276.80	5.14	456,334.04	828,164.16	N 32°15'4.07"	W 103°24'19.91"	1,579.82	239.17
	12,591.00	88.40	171.81	11,753.68	1,054.65	-902.83	-1,343.61	8,279.58	0.67	456,240.97	828,177.05	N 32°15'3.15"	W 103°24'19.77"	1,618.77	236.10
	12,686.00	88.29	172.64	11,756.43	1,146.58	-996.92	-1,330.77	8,282.33	0.88	456,146.89	828,189.90	N 32°15'2.22"	W 103°24'19.53"	1,662.77	233.16
Exit Lateral Window	12,738.00	87.86	174.52	11,758.17	1,197.17	-1,048.56	-1,324.96	8,284.07	3.70	456,095.24	828,195.71	N 32°15'1.71"	W 103°24'19.57"	1,689.67	231.64
	12,781.00	87.51	176.07	11,759.91	1,239.28	-1,091.38	-1,321.43	8,285.81	3.70	456,052.43	828,199.24	N 32°15'1.28"	W 103°24'19.53"	1,713.85	230.45
	12,876.00	87.93	178.74	11,763.69	1,332.94	-1,186.20	-1,317.13	8,289.59	2.84	455,957.61	828,203.53	N 32°15'0.34"	W 103°24'19.49"	1,772.54	227.99
	12,970.00	89.19	181.82	11,766.05	1,426.29	-1,280.16	-1,317.59	8,291.95	3.54	455,863.65	828,203.07	N 32°14'59.41"	W 103°24'19.50"	1,837.08	225.83
	13,065.00	89.22	182.10	11,767.37	1,520.95	-1,375.09	-1,320.84	8,293.27	0.30	455,768.72	828,199.83	N 32°14'58.47"	W 103°24'19.55"	1,906.70	223.85
Enter Lateral Window	13,075.00	89.24	182.11	11,767.51	1,530.92	-1,385.08	-1,321.21	8,293.41	0.23	455,758.72	828,199.44	N 32°14'58.38"	W 103°24'19.56"	1,914.17	223.65
	13,160.00	89.24	181.79	11,768.92	1,615.64	-1,470.62	-1,304.42	8,294.42	0.24	455,673.15	828,196.25	N 32°14'57.64"	W 103°24'19.67"	1,943.59	222.02
	13,254.00	89.25	182.79	11,769.62	1,709.37	-1,563.92	-1,328.53	8,295.52	0.63	455,578.89	828,192.14	N 32°14'56.81"	W 103°24'19.65"	2,052.03	220.35
	13,349.00	88.88	182.29	11,771.17	1,804.10	-1,658.81	-1,332.74	8,297.07	0.65	455,484.99	828,187.93	N 32°14'55.67"	W 103°24'19.72"	2,127.88	218.78
	13,444.00	89.40	179.76	11,772.60	1,898.61	-1,753.78	-1,334.44	8,298.50	2.72	455,390.03	828,186.23	N 32°14'54.73"	W 103°24'19.75"	2,203.74	217.27
	13,538.00	88.74	178.46	11,774.12	1,991.76	-1,847.75	-1,332.98	8,300.02	1.55	455,296.05	828,187.69	N 32°14'53.80"	W 103°24'19.74"	2,278.38	215.81
	13,633.00	87.56	179.08	11,777.19	2,085.79	-1,942.68	-1,330.94	8,303.09	1.40	455,201.13	828,189.73	N 32°14'52.86"	W 103°24'19.73"	2,354.87	214.42
	13,728.00	86.67	180.99	11,780.32	2,180.08	-2,037.62	-1,331.00	8,306.22	2.32	455,106.18	828,189.67	N 32°14'51.92"	W 103°24'19.74"	2,433.82	213.15
	13,823.00	87.33	179.60	11,783.63	2,274.41	-2,132.56	-1,331.49	8,309.53	2.03	455,011.25	828,189.18	N 32°14'50.98"	W 103°24'19.75"	2,514.09	211.98
	13,918.00	88.58	180.71	11,787.02	2,368.72	-2,227.50	-1,331.75	8,312.92	1.76	454,916.31	828,188.92	N 32°14'50.04"	W 103°24'19.76"	2,595.24	210.87
	14,013.00	89.28	181.64	11,788.80	2,463.25	-2,322.46	-1,333.69	8,314.70	1.23	454,821.35	828,186.97	N 32°14'49.10"	W 103°24'19.80"	2,678.16	209.87
	14,108.00	90.00	181.61	11,788.65	2,557.86	-2,417.42	-1,336.39	8,314.55	1.71	454,726.39	828,184.28	N 32°14'48.16"	W 103°24'19.85"	2,762.21	208.93
	14,202.00	88.80	179.93	11,788.89	2,651.34	-2,511.40	-1,337.65	8,314.79	2.86	454,632.41	828,183.02	N 32°14'47.23"	W 103°24'19.85"	2,845.42	208.04
	14,297.00	87.69	178.21	11,791.80	2,745.44	-2,606.34	-1,336.11	8,317.70	2.15	454,537.47	828,184.56	N 32°14'46.29"	W 103°24'19.85"	2,928.85	207.14
	14,392.00	88.96	177.13	11,794.58	2,839.20	-2,701.21	-1,332.25	8,320.48	1.75	454,442.59	828,188.42	N 32°14'45.35"	W 103°24'19.82"	3,011.88	206.25
	14,486.00	88.23	177.83	11,796.88	2,931.95	-2,795.09	-1,328.12	8,322.78	1.08	454,348.71	828,192.55	N 32°14'44.42"	W 103°24'19.78"	3,094.58	205.42
	14,581.00	88.95	178.83	11,798.39	3,025.90	-2,890.04	-1,325.35	8,324.29	2.09	454,253.77	828,195.32	N 32°14'43.48"	W 103°24'19.76"	3,179.44	

20,548.00	83.71	182.53	11,953.86	8,928.56	-8,844.14	-1,239.61	8,479.76	2.98	448,299.65	828,281.06	N 32°13'44.56"	W 103°24'19.36"	8,930.59	187.98
20,643.00	83.74	184.15	11,964.24	9,022.82	-8,938.41	-1,245.11	8,490.14	1.70	448,205.38	828,275.55	N 32°13'43.63"	W 103°24'19.43"	9,024.72	187.93
20,737.00	84.74	183.68	11,973.67	9,116.23	-9,031.72	-1,251.50	8,499.57	1.17	448,112.07	828,269.17	N 32°13'42.71"	W 103°24'19.51"	9,118.01	187.89
20,832.00	82.59	184.84	11,984.16	9,210.56	-9,125.87	-1,258.51	8,510.06	2.57	448,017.92	828,262.16	N 32°13'41.78"	W 103°24'19.60"	9,212.24	187.85
20,926.00	81.59	184.61	11,997.09	9,303.60	-9,218.66	-1,266.18	8,522.99	1.09	447,925.13	828,254.49	N 32°13'40.86"	W 103°24'19.70"	9,305.20	187.82
21,021.00	81.56	182.53	12,011.01	9,397.43	-9,312.44	-1,272.03	8,536.91	2.17	447,831.35	828,248.64	N 32°13'39.93"	W 103°24'19.78"	9,398.92	187.78
21,115.00	83.02	178.84	12,023.63	9,490.03	-9,405.57	-1,273.14	8,549.53	4.19	447,738.22	828,247.53	N 32°13'39.01"	W 103°24'19.80"	9,491.34	187.71
21,210.00	82.43	177.23	12,035.66	9,583.18	-9,499.74	-1,269.91	8,561.56	1.79	447,644.04	828,250.76	N 32°13'38.08"	W 103°24'19.77"	9,584.25	187.61
21,305.00	83.30	177.44	12,047.46	9,676.17	-9,593.91	-1,265.53	8,573.36	0.94	447,549.88	828,255.14	N 32°13'37.15"	W 103°24'19.73"	9,677.01	187.51
21,399.00	83.24	178.24	12,058.47	9,768.39	-9,687.19	-1,262.01	8,584.37	0.85	447,456.60	828,258.66	N 32°13'36.22"	W 103°24'19.70"	9,769.05	187.42
21,494.00	82.61	178.73	12,070.18	9,861.69	-9,781.43	-1,259.51	8,596.08	0.84	447,362.35	828,261.15	N 32°13'35.29"	W 103°24'19.68"	9,862.19	187.34
21,588.00	82.44	178.54	12,082.40	9,953.95	-9,874.61	-1,257.29	8,608.30	0.27	447,269.18	828,263.37	N 32°13'34.37"	W 103°24'19.67"	9,954.33	187.26
21,683.00	83.46	177.69	12,094.06	10,047.16	-9,968.84	-1,254.19	8,619.96	1.39	447,174.95	828,266.48	N 32°13'33.44"	W 103°24'19.64"	10,047.42	187.17
21,778.00	83.02	177.70	12,105.25	10,140.32	-10,063.10	-1,250.40	8,631.15	0.46	447,080.69	828,270.27	N 32°13'32.50"	W 103°24'19.60"	10,140.49	187.08
21,872.00	84.51	177.55	12,115.46	10,232.58	-10,156.46	-1,246.53	8,641.36	1.59	446,987.33	828,274.14	N 32°13'31.58"	W 103°24'19.57"	10,232.67	187.00
21,967.00	82.64	174.85	12,126.09	10,325.37	-10,250.64	-1,240.27	8,651.99	3.44	446,893.14	828,280.39	N 32°13'30.65"	W 103°24'19.51"	10,325.40	186.90
22,012.00	83.22	173.75	12,131.62	10,368.98	-10,295.08	-1,235.84	8,657.52	2.75	446,848.71	828,284.83	N 32°13'30.21"	W 103°24'19.46"	10,368.99	186.85
22,047.00	83.68	172.90	12,135.62	10,402.80	-10,329.62	-1,231.80	8,661.52	2.75	446,814.17	828,288.87	N 32°13'29.86"	W 103°24'19.41"	10,402.80	186.80
Projection to Total Depth														
22,080.00	83.68	172.90	12,139.25	10,434.64	-10,362.16	-1,227.74	8,665.15	0.00	446,781.62	828,292.92	N 32°13'29.54"	W 103°24'19.37"	10,434.64	186.76

Survey Type: DefinitiveSurvey

Survey Error Model: ISCWSA0 2.795 sigma

Survey Program:

Description	Part	MD From (ft)	MD To (ft)	EOU Freq (ft)	Expected Max Inclination (deg)	Survey Tool Code	Borehole / Survey
	1	0.000	1,037.000	Act Stns		B005Mb_MWD+HRGM+SAG+MS	Saker 6-7 Fed Com 37H / Oxy Saker 6-7 Fed Com 37H IFR1 to 22080ft
	1	1,037.000	11,201.000	Act Stns		A010Mb_MWD+IFR1+SAG+MS	Saker 6-7 Fed Com 37H / Oxy Saker 6-7 Fed Com 37H IFR1 to 22080ft
	1	11,201.000	11,455.000	Act Stns		A009Mb_MWD+IFR1+SAG	Saker 6-7 Fed Com 37H / Oxy Saker 6-7 Fed Com 37H IFR1 to 22080ft
	1	11,455.000	22,080.000	Act Stns		A010Mb_MWD+IFR1+SAG+MS	Saker 6-7 Fed Com 37H / Oxy Saker 6-7 Fed Com 37H IFR1 to 22080ft

EOU Geometry:

End MD (ft)	Hole Size (in)	Casing Size (in)	Name
22,080.000	26.400	26.400	

Intent ☐ As Drilled ☒

API # 30-025-48938		
Operator Name: OXY USA INC.	Property Name: Saker 6-7 Fed Com	Well Number 37H

Kick Off Point (KOP)

UL 2	Section 6	Township 24S	Range 35E	Lot 2	Feet 93	From N/S North	Feet 2169	From E/W East	County Lea
Latitude 32.253559					Longitude -103.103.405161			NAD Nad83	

First Take Point (FTP)

UL 2	Section 6	Township 24S	Range 35E	Lot 2	Feet 547	From N/S North	Feet 2261	From E/W East	County Lea
Latitude 32.252314					Longitude -103.405453			NAD Nad83	

Last Take Point (LTP)

UL O	Section 7	Township 24S	Range 35E	Lot 1	Feet 194	From N/S South	Feet 2277	From E/W East	County Lea
Latitude 32.225315					Longitude -103.405429			NAD Nad83	

Is this well the defining well for the Horizontal Spacing Unit? ☐ NoIs this well an infill well? ☐ Yes

If infill is yes please provide API if available, Operator Name and well number for Defining well for Horizontal Spacing Unit.

API # 30-025-48934		
Operator Name: OXY USA INC.	Property Name: Saker 6-7 Fed Com	Well Number 33H

KZ 06/29/2018

Well Name: SAKER 6-7 FEDERAL COM	Well Location: T24S / R35E / SEC 6 / LOT 1 / 32.253324 / -103.40112	County or Parish/State: LEA / NM
Well Number: 37H	Type of Well: OIL WELL	Allottee or Tribe Name:
Lease Number: NMNM14164	Unit or CA Name:	Unit or CA Number:
US Well Number: 3002548938	Well Status: Drilling Well	Operator: OXY USA INCORPORATED

Subsequent Report

Sundry ID: 2759824

Type of Submission: Subsequent Report

Type of Action: Hydraulic Fracturing

Date Sundry Submitted: 11/06/2023

Time Sundry Submitted: 07:44

Date Operation Actually Began: 08/21/2023

Actual Procedure: RUPU 8/21/2023, RIH & Clean out to PBTD 22037'. Test production casing to 6500 psi for 30 min, good test. RIH and Perf from 12054'-21917', total 1230 holes, 0.42". Frac in 40 stages with 26,868,300 #'s sand and 466,699 bbls produced water, 45,101 bbls brackish water, RD Frac and well ready to produce on 10/5/2023. OXY USA Inc. requests a tubing exception while continuing to flow back this well. The estimated date of tubing install is 01/05/2023.

Received by OCD: 12/11/2023 1:02:48 PM

Well Name: SAKER 6-7 FEDERAL COM

Well Location: T24S / R35E / SEC 6 / LOT 1 / 32.253324 / -103.40112

County or Parish/State: LEA / NM

Well Number: 37H

Type of Well: OIL WELL

Allottee or Tribe Name:

Lease Number: NMNM14164

Unit or CA Name:

Unit or CA Number:

US Well Number: 3002548938

Well Status: Drilling Well

Operator: OXY USA INCORPORATED

Operator

I certify that the foregoing is true and correct. Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction. Electronic submission of Sundry Notices through this system satisfies regulations requiring a

Operator Electronic Signature: SARAH MCKINNEY

Signed on: NOV 06, 2023 07:44 AM

Name: OXY USA INCORPORATED

Title: Regulatory Analyst Sr

Street Address: 5 GREENWAY PLAZA SUITE 110

City: HOUSTONState: TX

Phone: (713) 215-7295

Email address: SARAH_MCKINNEY@OXY.COM

Field

Representative Name:

Street Address:

City:State:Zip:

Phone:

Email address:

BLM Point of Contact

BLM POC Name: JONATHON W SHEPARD

BLM POC Title: Petroleum Engineer

BLM POC Phone: 5752345972

BLM POC Email Address: jshepard@blm.gov

Disposition: Accepted

Disposition Date: 12/08/2023

Signature: Jonathon Shepard

Submit To Appropriate District Office Two Copies <u>District I</u> 1625 N. French Dr., Hobbs, NM 88240 <u>District II</u> 811 S. First St., Artesia, NM 88210 <u>District III</u> 1000 Rio Brazos Rd., Aztec, NM 87410 <u>District IV</u> 1220 S. St. Francis Dr., Santa Fe, NM 87505		State of New Mexico Energy, Minerals and Natural Resources Oil Conservation Division 1220 South St. Francis Dr. Santa Fe, NM 87505				Form C-105 Revised April 3, 2017				
WELL COMPLETION OR RECOMPLETION REPORT AND LOG										
4. Reason for filing: ☒ COMPLETION REPORT (Fill in boxes #1 through #31 for State and Fee wells only) ☐ C-144 CLOSURE ATTACHMENT (Fill in boxes #1 through #9, #15 Date Rig Released and #32 and/or #33; attach this and the plat to the C-144 closure report in accordance with 19.15.17.13.K NMAC)						1. WELL API NO. 30-025-48938 2. Type of Lease ☐ STATE ☐ FEE ☒ FED/INDIAN 3. State Oil & Gas Lease No.				
5. Lease Name or Unit Agreement Name Saker 6-7 Fed Com 6. Well Number: 37H										
7. Type of Completion: ☒ NEW WELL ☐ WORKOVER ☐ DEEPENING ☐ PLUGBACK ☐ DIFFERENT RESERVOIR ☐ OTHER _____										
8. Name of Operator OXY USA INC.						9. OGRID 16696				
10. Address of Operator PO Box 50250, MIDLAND, TX 79710						11. Pool name or Wildcat Antelope Ridge; Wolfcamp				
12. Location	Unit Ltr	Section	Township	Range	Lot	Feet from the	N/S Line	Feet from the	E/W Line	County
Surface:	1	6	24S	35E		180	North	920	East	Lea
BH:	O	7	24S	35E		32	South	2263	East	Lea
13. Date Spudded 06/03/2023	14. Date T.D. Reached 7/17/2023		15. Date Rig Released 7/19/2023		16. Date Completed (Ready to Produce) 10/05/2023			17. Elevations (DF and RKB, RT, GR, etc.) 3450 GR		
18. Total Measured Depth of Well 22080' MD, 12139' TVD			19. Plug Back Measured Depth 22037' MD, 12135' TVD		20. Was Directional Survey Made? Yes			21. Type Electric and Other Logs Run CBL/Gamma		
22. Producing Interval(s), of this completion - Top, Bottom, Name 12054-21917, Wolfcamp										
23. CASING RECORD (Report all strings set in well)										
CASING SIZE		WEIGHT LB./FT.		DEPTH SET		HOLE SIZE		CEMENTING RECORD		AMOUNT PULLED
13 3/8"		54.5# J-55		1086		17 1/2"		1605sx Class C		
7 5/8"		26.4# HCL80		11215		9 7/8"		3136sx Class H		
5 1/2"		20# P110		22060		6 3/4"		734sx Class H		
24. LINER RECORD										
SIZE	TOP	BOTTOM	SACKS CEMENT	SCREEN	25. TUBING RECORD					
					SIZE	DEPTH SET	PACKER SET			
26. Perforation record (interval, size, and number) 12054-21917, 0.42, 1230 Holes					27. ACID, SHOT, FRACTURE, CEMENT, SQUEEZE, ETC. DEPTH INTERVAL AMOUNT AND KIND MATERIAL USED 12054-21917 26,868,300 #'s sand, 466,699 bbls produced water, 45,101 bbls brackish water.					
28. PRODUCTION										
Date First Production 11/16/2023		Production Method (<i>Flowing, gas lift, pumping - Size and type pump</i>) Flowing				Well Status (<i>Prod. or Shut-in</i>) Producing				
Date of Test 11/19/2023	Hours Tested 24 hours	Choke Size 0	Prod'n For Test Period	Oil - Bbl 2610	Gas - MCF 2911	Water - Bbl. 3667	Gas - Oil Ratio 1115			
Flow Tubing Press.	Casing Pressure 851	Calculated 24-Hour Rate	Oil - Bbl. 2610	Gas - MCF 2911	Water - Bbl. 3667	Oil Gravity - API - (<i>Corr.</i>)				
29. Disposition of Gas (<i>Sold, used for fuel, vented, etc.</i>) Sold							30. Test Witnessed By			
31. List Attachments C104c, C102, WBD, Directional Survey, CBL										
32. If a temporary pit was used at the well, attach a plat with the location of the temporary pit.							33. Rig Release Date:			
34. If an on-site burial was used at the well, report the exact location of the on-site burial:										
Latitude _____ Longitude _____ NAD83										
I hereby certify that the information shown on both sides of this form is true and complete to the best of my knowledge and belief										
Signature 		Printed Name Sarah McKinney			Title Regulatory Analyst Sr.			Date 12/05/2023		
E-mail Address sarah_mckinney@oxy.com										

This form is to be filed with the appropriate District Office of the Division not later than 20 days after the completion of any newly-drilled or deepened well and not later than 60 days after completion of closure. When submitted as a completion report, this shall be accompanied by one copy of all electrical and radio-activity logs run on the well and a summary of all special tests conducted, including drill stem tests. All depths reported shall be measured depths. In the case of directionally drilled wells, true vertical depths shall also be reported. For multiple completions, items 11, 12 and 26-31 shall be reported for each zone.

Southeastern New Mexico		Northwestern New Mexico	
T. Rustler 734'	T. Bell Canyon	T. Ojo Alamo	T. Penn A"
T. Salado 1165'	T. Strawn	T. Kirtland	T. Penn. "B"
T. Castile 3898'	T. Atoka	T. Fruitland	T. Penn. "C"
T. Delaware 5276'	T. Miss	T. Pictured Cliffs	T. Penn. "D"
T. Cherry Canyon 6216	T. Devonian	T. Cliff House	T. Leadville
T. Brushy Canyon 7532'	T. Silurian	T. Menefee	T. Madison
T. Grayburg	T. Montoya	T. Point Lookout	T. Elbert
T. San Andres	T. Simpson	T. Mancos	T. McCracken
T. Glorieta	T. McKee	T. Gallup	T. Ignacio Otzte
T. Paddock	T. Ellenburger	Base Greenhorn	T. Granite
T. Blinebry	T. Gr. Wash	T. Dakota	
T. Tubb	T. Delaware Sand	T. Morrison	
T. Drinkard	T. Bone Springs 8799'	T. Todilto	
T. Abo	T. 1 st Bone Springs 9887'	T. Entrada	
T. Wolfcamp	T. 2 nd Bone Springs 10357'	T. Wingate	
T. Penn	T. 3 rd Bone Springs 11410'	T. Chinle	
T. Cisco (Bough C)	T. Wolfcamp 11633'	T. Permian	

No. 1, from.....to.....

No. 2, from.....to.....

No. 3, from.....to.....


No. 4, from.....to.....

Include data on rate of water inflow and elevation to which water rose in hole.

No. 1, from.....to.....feet.....
 No. 2, from.....to.....feet.....
 No. 3, from.....to.....feet.....

From	To	Thickness In Feet	Lithology

OXY USA Inc.
Saker 6-7 Fed Com 37H
API No. 30-025-48938



District I
1625 N. French Dr., Hobbs, NM 88240
Phone:(575) 393-6161 Fax:(575) 393-0720
District II
811 S. First St., Artesia, NM 88210
Phone:(575) 748-1283 Fax:(575) 748-9720
District III
1000 Rio Brazos Rd., Aztec, NM 87410
Phone:(505) 334-6178 Fax:(505) 334-6170
District IV
1220 S. St Francis Dr., Santa Fe, NM 87505
Phone:(505) 476-3470 Fax:(505) 476-3462

State of New Mexico
Energy, Minerals and Natural Resources
Oil Conservation Division
1220 S. St Francis Dr.
Santa Fe, NM 87505

ACKNOWLEDGMENTS

Action 293153

ACKNOWLEDGMENTS

Operator: OXY USA INC P.O. Box 4294 Houston, TX 772104294	OGRID: 16696
	Action Number: 293153
	Action Type: [C-104] Completion Packet (C-104C)

ACKNOWLEDGMENTS

☒	I hereby certify that the required Water Use Report has been, or will be, submitted for this wells completion.
☒	I hereby certify that the required FracFocus disclosure has been, or will be, submitted for this wells completion.

District I
1625 N. French Dr., Hobbs, NM 88240
Phone:(575) 393-6161 Fax:(575) 393-0720

District II
811 S. First St., Artesia, NM 88210
Phone:(575) 748-1283 Fax:(575) 748-9720

District III
1000 Rio Brazos Rd., Aztec, NM 87410
Phone:(505) 334-6178 Fax:(505) 334-6170

District IV
1220 S. St Francis Dr., Santa Fe, NM 87505
Phone:(505) 476-3470 Fax:(505) 476-3462

State of New Mexico
Energy, Minerals and Natural Resources
Oil Conservation Division
1220 S. St Francis Dr.
Santa Fe, NM 87505

CONDITIONS

Action 293153

CONDITIONS

Operator: OXY USA INC P.O. Box 4294 Houston, TX 772104294	OGRID: 16696
	Action Number: 293153
	Action Type: [C-104] Completion Packet (C-104C)

CONDITIONS

Created By	Condition	Condition Date
smcgrath	File 3160-4 within 10 days of BLM Approval.	2/6/2024