

1625 N. French Dr., Hobbs, NM 88240

District II

811 S. First St., Artesia, NM 88210

District III

1000 Rio Brazos Rd., Aztec, NM 87410

District IV

1220 S. St. Francis Dr., Santa Fe, NM 87505

State of New Mexico
Energy, Minerals & Natural ResourcesForm C-104
Revised August 1, 2011Oil Conservation Division
1220 South St. Francis Dr.
Santa Fe, NM 87505

Submit one copy to appropriate District Office

☐ AMENDED REPORT

I. REQUEST FOR ALLOWABLE AND AUTHORIZATION TO TRANSPORT

¹ Operator name and Address OXY USA INC. PO BOX 50250 MIDLAND, TX 79710		² OGRID Number 16696
		³ Reason for Filing Code/ Effective Date NW - 11/21/2023
⁴ API Number 30 - 025-48976	⁵ Pool Name ANTELOPE RIDGE; Wolfcamp	
		⁶ Pool Code 2220
⁷ Property Code 330861	⁸ Property Name Maltese 5 8 Fed COM	⁹ Well Number 33H

II. ¹⁰ Surface Location

UL or lot no. 1	Section 5	Township 24S	Range 35E	Lot Idn	Feet from the 180	North/South Line North	Feet from the 860	East/West line East	County Lea
--------------------	--------------	-----------------	--------------	---------	----------------------	---------------------------	----------------------	------------------------	---------------

¹¹ Bottom Hole Location

UL or lot no. O	Section 8	Township 24S	Range 35E	Lot Idn	Feet from the 19	North/South line South	Feet from the 1397	East/West line East	County Lea
¹² Lse Code F	¹³ Producing Method Code F	¹⁴ Gas Connection Date 11/29/23	¹⁵ C-129 Permit Number	¹⁶ C-129 Effective Date	¹⁷ C-129 Expiration Date				

III. Oil and Gas Transporters

¹⁸ Transporter OGRID	¹⁹ Transporter Name and Address	²⁰ O/G/W
237722	Centerion Pipeline, L.P.	O
248749	DCP Midstream, L.P.	G

IV. Well Completion Data

²¹ Spud Date 6/25/2023	²² Ready Date 11/21/2023	²³ TD 22019' MD, 12092' TVD	²⁴ PBTB 21975' MD, 12090' TVD	²⁵ Perforations 11955-21818	²⁶ DHC, MC R22665
²⁷ Hole Size	²⁸ Casing & Tubing Size	²⁹ Depth Set		³⁰ Sacks Cement	
17 1/2"	13 3/8" 54.5# J-55	1261'		1267sx Class C- TOC 0'	
9 7/8"	7 5/8" 26.4# HCL80	11202'		3165sx Class H - TOC 0'	
6 3/4"	5 1/2" 20# P110	21999'		782sx Class H - TOC 10930'	

V. Well Test Data

³¹ Date New Oil 11/29/2023	³² Gas Delivery Date 11/29/2023	³³ Test Date 12/13/2023	³⁴ Test Length 24 Hours	³⁵ Tbg. Pressure	³⁶ Csg. Pressure 691
³⁷ Choke Size 0	³⁸ Oil 2415	³⁹ Water 750	⁴⁰ Gas 2385		⁴¹ Test Method Flowing
⁴² I hereby certify that the rules of the Oil Conservation Division have been complied with and that the information given above is true and complete to the best of my knowledge and belief. Signature: <i>Sarah McKinney</i>			OIL CONSERVATION DIVISION		
Printed name: Sarah McKinney			Approved by:		
Title: Regulatory Analyst Sr.			Title:		
E-mail Address: sarah_mckinney@oxy.com			Approval Date:		
Date: 01/09/2024		Phone: 713-215-7295			

District I
1625 N. French Dr., Hobbs, NM 88240
Phone: (575) 393-6161 Fax: (575) 393-0720
District II
811 S. First St., Artesia, NM 88210
Phone: (575) 748-1283 Fax: (575) 748-9720
District III
1000 Rio Brazos Road, Aztec, NM 87410
Phone: (505) 334-6178 Fax: (505) 334-6170
District IV
1220 S. St. Francis Dr., Santa Fe, NM 87505
Phone: (505) 476-3460 Fax: (505) 476-3462

State of New Mexico
Energy, Minerals & Natural Resources Department
OIL CONSERVATION DIVISION
1220 South St. Francis Dr.
Santa Fe, NM 87505

Form C-102
Revised August 1, 2011
Submit one copy to appropriate
District Office

☒ AMENDED REPORT
As-Drilled Plat

WELL LOCATION AND ACREAGE DEDICATION PLAT

¹ API Number 30-025-48976		² Pool Code 2220	³ Pool Name ANTELOPE RIDGE; Wolfcamp	
⁴ Property Code 330861	⁵ Property Name MALTESE 5_8 FED COM			⁶ Well Number 33H
⁷ OGRID No. 16696	⁸ Operator Name OXY USA INC.			⁹ Elevation 3447.4'


¹⁰ Surface Location

UL or lot no. 1	Section 5	Township 24S	Range 35E	Lot Idn	Feet from the 180	North/South line NORTH	Feet from the 860	East/West line EAST	County LEA
--------------------	--------------	-----------------	--------------	---------	----------------------	---------------------------	----------------------	------------------------	---------------

¹¹ Bottom Hole Location If Different From Surface

UL or lot no. O	Section 8	Township 24S	Range 35E	Lot Idn	Feet from the 19	North/South line SOUTH	Feet from the 1397	East/West line EAST	County LEA
¹² Dedicated Acres 1280		¹³ Joint or Infill		¹⁴ Consolidation Code		¹⁵ Order No. R-22665			

No allowable will be assigned to this completion until all interests have been consolidated or a non-standard unit has been approved by the division.



17 OPERATOR CERTIFICATION

I hereby certify that the information contained herein is true and complete to the best of my knowledge and belief, and that this organization either owns a working interest or unleased mineral interest in the land including the proposed bottom hole location or has a right to drill this well at this location pursuant to a contract with an owner of such a mineral or working interest, or to a voluntary pooling agreement or a compulsory pooling order heretofore entered by the division.

Sarah McKinny 1/9/24
Signature Date

Sarah McKinney
Printed Name

sarah_mckinney@oxy.com
E-mail Address

18 SURVEYOR CERTIFICATION

I hereby certify that the well location shown on this plat was plotted from field notes of actual surveys made by me or under my supervision, and that the same is true and correct to the best of my belief.

December 12, 2019

Date of Survey _____
Signature and Seal of Professional Surveyor _____



Certificate Number:

LINE TABLE		
LINE	DIRECTION	LENGTH
L1	S89°42'25"W	2641.36'
L2	S89°45'04"W	2642.88'

WELL BORE DISTANCE FROM FTP TO LTP	
TRACT	DISTANCE
NMNM 014164	7,413.67'
NMNM 0001228	2,121.39'
TOTAL	9,535.06'

NAD 83 (SURFACE HOLE LOCATION)
LATITUDE = 32°15'12".00" (32.253333°)
LONGITUDE = -103°23'01.84" (-103.383844°)
NAD 27 (SURFACE HOLE LOCATION)
LATITUDE = 32°15'11.55" (32.253207°)
LONGITUDE = -103°23'00.14" (-103.383371°)
STATE PLANE NAD 83 (N.M. EAST)
N: 457193.70' E: 834861.67'
STATE PLANE NAD 27 (N.M. EAST)
N: 457134.26' E: 793676.94'

NAD 83 (AS-DRILLED KOP)
LATITUDE = 32°15'11.91" (32.253309°)
LONGITUDE = -103°27'07.13" (-103.385315°)
NAD 27 (AS-DRILLED KOP)
LATITUDE = 32°15'11.46" (32.253183°)
LONGITUDE = -103°27'05.43" (-103.384842°)
STATE PLANE NAD 83 (N.M. EAST)
N: 457181.01' E: 834406.36'
STATE PLANE NAD 27 (N.M. EAST)
N: 457121.57' E: 793222.15'

NAD 83 (AS-DRILLED FTP)
LATITUDE = 32°15'08.60" (32.252390°)
LONGITUDE = -103°23'07.86" (-103.385517°)
NAD 27 (AS-DRILLED FTP)
LATITUDE = 32°15'08.15" (32.252264°)
LONGITUDE = -103°23'06.16" (-103.385045°)
STATE PLANE NAD 83 (N.M. EAST)
N: 456846.05' E: 834347.23'
STATE PLANE NAD 27 (N.M. EAST)
N: 456786.61' E: 793162.51'

NAD 83 (AS-DRILLED LPP)
LATITUDE = 32°13'55.35" (32.232042°)
LONGITUDE = -103°23'08.50" (-103.385692°)
NAD 27 (AS-DRILLED LPP)
LATITUDE = 32°13'54.90" (32.231917°)
LONGITUDE = -103°23'06.80" (-103.385222°)
STATE PLANE NAD 83 (N.M. EAST)
N: 449443.20' E: 834358.13'
STATE PLANE NAD 27 (N.M. EAST)
N: 449383.97' E: 793173.10'

NAD 83 (AS-DRILLED LTP)
LATITUDE = 32°13'31.41" (32.225391°)
LONGITUDE = -103°23'07.89" (-103.385525°)
NAD 27 (AS-DRILLED LTP)
LATITUDE = 32°13'30.96" (32.225266°)
LONGITUDE = -103°23'06.19" (-103.385054°)
STATE PLANE NAD 83 (N.M. EAST)
N: 447023.92' E: 834431.70'
STATE PLANE NAD 27 (N.M. EAST)
N: 446964.75' E: 793246.57'

NAD 83 (AS-DRILLED BHL)
LATITUDE = 32°13'29.42" (32.224840°)
LONGITUDE = -103°23'07.82" (-103.385504°)
NAD 27 (AS-DRILLED BHL)
LATITUDE = 32°13'28.97" (32.224714°)
LONGITUDE = -103°23'06.12" (-103.385033°)
STATE PLANE NAD 83 (N.M. EAST)
N: 446823.41' E: 834439.74'
STATE PLANE NAD 27 (N.M. EAST)
N: 446764.25' E: 793254.60'

- = SURFACE HOLE LOCATION
- ◆ = AS-DRILLED KICK OFF/TAKE POINT
- ☆ = AS-DRILLED LEASE PENETRATION POINT
- ⊙ = AS-DRILLED BOTTOM HOLE LOCATION
- ▲ = SECTION CORNER LOCATED
- = LEASE LINE
- ▬ = HORIZONTAL SPACING UNIT
- = AS-DRILLED WELL BORE

- NOTE:**
- Distances referenced on plat to section lines are perpendicular.
 - Basis of Bearings is a Transverse Mercator Projection with a Central Meridian of W103°53'00" (NAD 83)
 - As-Drilled well head has not been field verified.
 - Well Bore data provided by Oxy USA Inc.



SCALE
DRAWN BY: Z.L. 11-29-23



Oxy Maltese 5-8 Fed Com 33H IFR1 to 22019ft Survey Geodetic Report



DefinitiveSurvey

Report Date: August 21, 2023 - 05:31 PM (UTC 0)
Client: OXY
Field: NM Lea County (NAD 83)
Structure / Slot: Oxy Maltese 5-8 Fed Com Pad Lot 1 / Maltese 5-8 Fed Com 33H
Well: Maltese 5-8 Fed Com 33H
Borehole: Maltese 5-8 Fed Com 33H
UBHI / API / JobNumber: Unknown / Unknown / Unknown
Survey Name / Version: Oxy Maltese 5-8 Fed Com 33H IFR1 to 22019ft / 4
Survey Date: August 20, 2023
Tort / AHD / DDI / ERD Ratio: 314.833 ° / 10991.317 ft / 6.799 / 0.909
Coordinate Reference System: NAD83 New Mexico State Plane, Eastern Zone, US Feet
Location Lat / Long: N 32°15'11.99752" , W 103°23'1.83694"
Location Grid N/E Y/X: N 457193.700 ftUS , E 834861.670 ftUS
CRS Grid Convergence Angle: 0.507°
Grid Scale Factor: 1.00000777
Engine Version: 2023.1.0.1

Survey / DLS Computation: Minimum Curvature / Lubinski
Vertical Section Azimuth: 182.330 °(Grid North)
Vertical Section Origin: 0.000 ft, 0.000 ft
TVD Reference Datum: RKB
TVD Reference Elevation: 3473.400 ft above MSL
Seabed / Ground Elevation: 3447.400 ft above MSL
Magnetic Declination: 6.323°
Total Gravity Field Strength: 998.4669mgn (9.80665 Based)
Gravity Model: GARM
Total Magnetic Field Strength: 47517.4 nT
Magnetic Dip Angle: 59.822°
Declination Date: August 02, 2023
Magnetic Declination Model: IFR1
North Reference: Grid
Total Gravity Field Strength: 5.816°
Local Coord Referenced To: Well Head

Comments	MD (ft)	Incl (°)	Azim (°)	TVD (ft)	VSEC (ft)	NS (ft)	EW (ft)	TVDSS (ft)	DLS (°/100ft)	Northing (ftUS)	Easting (ftUS)	Latitude (N S ° ' ' ')	Longitude (E W ° ' ' ')	Closure (ft)	Closure Azimuth (°)
WRP	0.00	0.00	0.00	0.00	0.00	0.00	0.00	-3,473.40		457,193.70	834,861.67	N 32°15'12.00"	W 103°23'1.84"		
SHL	25.00	0.00	0.00	25.00	0.00	0.00	0.00	-3,448.40	0.00	457,193.70	834,861.67	N 32°15'12.00"	W 103°23'1.84"	0.00	0.00
First SLB Survey	225.00	1.23	204.59	224.98	1.99	-1.95	-0.89	-3,248.42	0.62	457,191.75	834,860.78	N 32°15'11.98"	W 103°23'1.85"	2.15	204.59
	350.00	2.45	199.57	349.92	5.78	-5.69	-2.35	-3,123.48	0.98	457,188.01	834,859.32	N 32°15'11.94"	W 103°23'1.86"	6.15	202.41
	444.00	3.93	200.62	443.77	10.76	-10.60	-4.15	-3,029.63	1.58	457,183.10	834,857.52	N 32°15'11.89"	W 103°23'1.89"	11.38	201.40
	537.00	3.59	194.01	536.57	16.64	-16.41	-5.98	-2,936.83	0.59	457,177.29	834,855.69	N 32°15'11.84"	W 103°23'1.91"	17.46	200.03
	625.00	3.09	184.99	624.42	21.70	-21.44	-6.85	-2,848.98	0.82	457,172.26	834,854.82	N 32°15'11.79"	W 103°23'1.92"	22.51	197.73
	720.00	2.25	168.25	719.32	26.07	-25.82	-6.70	-2,754.08	1.20	457,167.88	834,854.97	N 32°15'11.74"	W 103°23'1.92"	26.67	194.54
	815.00	1.77	111.78	814.27	28.37	-28.19	-4.96	-2,659.13	2.05	457,165.51	834,856.71	N 32°15'11.72"	W 103°23'1.90"	28.62	189.97
	910.00	3.25	79.23	909.18	28.25	-28.23	-0.95	-2,564.22	2.10	457,165.47	834,860.72	N 32°15'11.72"	W 103°23'1.85"	28.25	181.92
	1,004.00	4.30	67.96	1,002.97	26.19	-26.41	4.94	-2,470.43	1.36	457,167.29	834,866.61	N 32°15'11.74"	W 103°23'1.78"	26.87	169.41
	1,099.00	4.29	56.93	1,097.71	22.66	-23.13	11.22	-2,375.69	0.87	457,170.57	834,872.89	N 32°15'11.77"	W 103°23'1.71"	25.71	154.13
	1,194.00	3.85	44.86	1,192.47	18.25	-18.93	16.44	-2,280.93	1.01	457,174.77	834,878.11	N 32°15'11.81"	W 103°23'1.65"	25.08	139.03
	1,383.00	0.03	100.21	1,381.33	13.58	-14.44	20.97	-2,092.07	2.03	457,179.26	834,882.64	N 32°15'11.85"	W 103°23'1.59"	25.46	124.56
	1,435.00	0.03	98.31	1,433.33	13.58	-14.45	21.00	-2,040.07	0.00	457,179.25	834,882.67	N 32°15'11.85"	W 103°23'1.59"	25.49	124.53
	1,530.00	0.06	223.98	1,528.33	13.62	-14.49	20.99	-1,945.07	0.09	457,179.21	834,882.66	N 32°15'11.85"	W 103°23'1.59"	25.50	124.62
	1,624.00	0.06	18.87	1,622.33	13.61	-14.48	20.97	-1,851.07	0.12	457,179.22	834,882.64	N 32°15'11.85"	W 103°23'1.59"	25.48	124.62
	1,719.00	0.05	133.35	1,717.33	13.59	-14.46	21.01	-1,756.07	0.10	457,179.24	834,882.68	N 32°15'11.85"	W 103°23'1.59"	25.51	124.53
	1,814.00	0.03	103.49	1,812.33	13.62	-14.49	21.07	-1,661.07	0.03	457,179.21	834,882.74	N 32°15'11.85"	W 103°23'1.59"	25.57	124.52
	1,908.00	0.02	227.88	1,906.33	13.64	-14.51	21.08	-1,567.07	0.05	457,179.19	834,882.75	N 32°15'11.85"	W 103°23'1.59"	25.59	124.54
	2,003.00	0.06	192.97	2,001.33	13.70	-14.57	21.06	-1,472.07	0.05	457,179.13	834,882.73	N 32°15'11.85"	W 103°23'1.59"	25.61	124.68
	2,098.00	0.15	134.18	2,096.33	13.83	-14.70	21.14	-1,377.07	0.14	457,179.00	834,882.81	N 32°15'11.85"	W 103°23'1.59"	25.75	124.83
	2,192.00	0.12	328.21	2,190.33	13.83	-14.71	21.17	-1,283.07	0.29	457,178.99	834,882.84	N 32°15'11.85"	W 103°23'1.59"	25.78	124.78
	2,287.00	0.05	12.02	2,285.33	13.71	-14.58	21.13	-1,188.07	0.10	457,179.12	834,882.80	N 32°15'11.85"	W 103°23'1.59"	25.67	124.61
	2,382.00	0.06	186.19	2,380.33	13.72	-14.59	21.13	-1,093.07	0.12	457,179.11	834,882.80	N 32°15'11.85"	W 103°23'1.59"	25.68	124.62
	2,477.00	0.12	155.37	2,475.33	13.86	-14.73	21.17	-998.07	0.08	457,178.97	834,882.84	N 32°15'11.85"	W 103°23'1.59"	25.79	124.83
	2,571.00	0.10	87.84	2,569.33	13.94	-14.82	21.29	-904.07	0.13	457,178.88	834,882.96	N 32°15'11.85"	W 103°23'1.59"	25.94	124.83
	2,666.00	0.10	111.91	2,664.33	13.96	-14.84	21.45	-809.07	0.04	457,178.86	834,883.12	N 32°15'11.85"	W 103°23'1.59"	26.09	124.68
	2,761.00	0.02	148.01	2,759.33	14.00	-14.89	21.54	-714.07	0.09	457,178.81	834,883.21	N 32°15'11.85"	W 103°23'1.59"	26.18	124.66
	2,856.00	0.11	117.61	2,854.33	14.05	-14.94	21.63	-619.07	0.10	457,178.76	834,883.30	N 32°15'11.85"	W 103°23'1.59"	26.29	124.65
	2,951.00	0.15	125.90	2,949.33	14.16	-15.06	21.81	-524.07	0.05	457,178.64	834,883.48	N 32°15'11.85"	W 103°23'1.58"	26.50	124.63
	3,046.00	0.14	115.76	3,044.33	14.28	-15.18	22.01	-429.07	0.03	457,178.52	834,883.68	N 32°15'11.85"	W 103°23'1.58"	26.74	124.60
	3,140.00	0.11	117.54	3,138.33	14.36	-15.28	22.20	-335.07	0.03	457,178.42	834,883.87	N 32°15'11.84"	W 103°23'1.58"	26.94	124.54
	3,235.00	0.16	153.58	3,233.33	14.52	-15.44	22.34	-240.07	0.10	457,178.26	834,884.01	N 32°15'11.84"	W 103°23'1.58"	27.15	124.65
	3,329.00	0.14	167.15	3,327.33	14.74	-15.67	22.42	-146.07	0.04	457,178.03	834,884.09	N 32°15'11.84"	W 103°23'1.58"	27.35	124.94
	3,424.00	0.10	143.86	3,422.33	14.92	-15.85	22.49	-51.07	0.07	457,177.85	834,884.16	N 32°15'11.84"	W 103°23'1.58"	27.52	125.16
	3,519.00	0.11	240.58	3,517.33	15.03	-15.96	22.46	43.93	0.17	457,177.74	834,884.13	N 32°15'11.84"	W 103°23'1.58"	27.55	125.39
	3,614.00	0.16	119.74	3,612.33	15.14	-16.07	22.50	138.93	0.25	457,177.63	834,884.17	N 32°15'11.84"	W 103°23'1.58"	27.65	125.53
	3,709.00	0.04	54.92	3,707.33	15.18	-16.11	22.64	233.93	0.16	457,177.59	834,884.31	N 32°15'11.84"	W 103°23'1.57"	27.79	125.44
	3,803.00	0.08	115.64	3,801.33	15.19	-16.12	22.73	327.93	0.07	457,177.58	834,884.40	N 32°15'11.84"	W 103°23'1.57"	27.87	125.35
	3,898.00	0.06	312.59	3,896.33	15.18	-16.12	22.75	422.93	0.15	457,177.58	834,884.42	N 32°15'11.84"	W 103°23'1.57"	27.88	125.32
	3,993.00	0.02	158.34	3,991.33	15.16	-16.10	22.72	517.93	0.08	457,177.60	834,884.39	N 32°15'11.84"	W 103°23'1.57"	27.85	125.32
	4,088.00	0.07	199.52	4,086.33	15.23	-16.17	22.71	612.93	0.06	457,177.53	834,884.38	N 32°15'11.84"	W 103°23'1.57"	27.88	125.46
	4,182.00	0.06	246.36	4,180.33	15.31	-16.24	22.64	706.93	0.06	457,177.45	834,884.31	N 32°15'11.83"	W 103°23'1.57"	27.87	125.66
	4,277.00	0.13	101.83	4,275.33	15.35	-16.29	22.70	801.93	0.19	457,177.41	834,884.37	N 32°15'11.83"	W 103°23'1.57"	27.94	125.66
	4,372.00	0.13	86.59	4,370.33	15.36	-16.30	22.92	896.93	0.04	457,177.40	834,884.59	N 32°15'11.83"	W 103°23'1.57"	28.12	125.43
	4,467.00	0.06	135.15	4,465.32	15.38	-16.33	23.06	991.92	0.11	457,177.37	834,884.73	N 32°15'11.83"	W 103°23'1.57"	28.26	125.31
	4,561.00	0.04	279.61	4,559.32	15.41	-16.36	23.06	1,085.92	0.10	457,177.34	834,884.73	N 32°15'11.83"	W 103°23'1.57"	28.28	125.35
	4,656.00	0.08	160.25	4,654.32	15.47	-16.42	23.05	1,180.92	0.11	457,177.28	834,884.72	N 32°15'11.83"	W 103°23'1.57"	28.30	125.46
	4,751.00	0.06	132.30	4,749.32	15.56	-16.51	23.11	1,275.92	0.04	457,177.19	834,884.78	N 32°15'11.83"	W 103°23'1.57"	28.40	125.55
	4,845.00	0.02	68.77	4,843.32	15.59	-16.54	23.16	1,369.92	0.06	457,177.16	834,884.83	N 32°15'11.83"	W 103°23'1		

	8,541.00	2.82	266.72	8,505.55	-31.97	47.58	-383.09	5,032.15	0.15	457,241.28	834,478.58	N 32°15'12.50"	W 103°23'6.29"	386.03	277.08
	8,635.00	2.64	263.23	8,599.45	-31.40	47.20	-387.55	5,126.05	0.26	457,240.90	834,474.12	N 32°15'12.50"	W 103°23'6.34"	390.41	276.94
	8,730.00	2.73	263.08	8,694.34	-30.69	46.67	-391.96	5,220.94	0.10	457,240.37	834,469.70	N 32°15'12.49"	W 103°23'6.40"	394.73	276.79
	8,824.00	2.64	248.58	8,788.24	-29.46	45.61	-396.20	5,314.84	0.73	457,239.31	834,465.47	N 32°15'12.48"	W 103°23'6.45"	398.82	276.57
	8,919.00	2.86	241.09	8,883.13	-27.35	43.66	-400.31	5,409.73	0.44	457,237.36	834,461.35	N 32°15'12.46"	W 103°23'6.49"	402.69	276.22
	9,014.00	2.94	238.45	8,978.01	-24.76	41.24	-404.46	5,504.61	0.16	457,234.94	834,457.20	N 32°15'12.44"	W 103°23'6.54"	406.56	275.82
	9,108.00	3.09	237.13	9,071.88	-21.96	38.60	-408.65	5,598.48	0.18	457,232.30	834,453.02	N 32°15'12.42"	W 103°23'6.59"	410.47	275.40
	9,203.00	3.96	235.81	9,166.70	-18.53	35.37	-413.51	5,693.30	0.92	457,229.07	834,448.16	N 32°15'12.38"	W 103°23'6.65"	415.02	274.89
	9,298.00	4.57	242.24	9,261.44	-14.68	31.77	-419.57	5,788.04	0.81	457,225.47	834,442.09	N 32°15'12.35"	W 103°23'6.72"	420.77	274.33
	9,392.00	4.07	243.27	9,355.17	-11.18	28.52	-425.87	5,881.77	0.54	457,222.22	834,435.80	N 32°15'12.32"	W 103°23'6.79"	426.82	273.83
	9,487.00	4.34	244.20	9,449.91	-7.85	25.44	-432.11	5,976.51	0.29	457,219.14	834,429.55	N 32°15'12.29"	W 103°23'6.87"	432.86	273.37
	9,582.00	4.38	248.65	9,544.64	-4.70	22.55	-438.73	6,071.24	0.36	457,216.25	834,422.94	N 32°15'12.26"	W 103°23'6.94"	439.31	272.94
	9,677.00	4.24	261.81	9,639.37	-2.60	20.73	-445.58	6,165.97	1.05	457,214.43	834,416.08	N 32°15'12.24"	W 103°23'7.02"	446.07	272.66
	9,771.00	4.34	266.71	9,733.11	-1.62	20.03	-452.57	6,259.71	0.40	457,213.73	834,409.09	N 32°15'12.24"	W 103°23'7.10"	453.02	272.53
	9,866.00	4.02	271.12	9,827.86	-1.20	19.89	-459.49	6,354.46	0.48	457,213.59	834,402.17	N 32°15'12.23"	W 103°23'7.19"	459.92	272.48
	9,960.00	2.71	242.30	9,921.70	-0.02	18.92	-464.75	6,448.30	2.23	457,212.62	834,396.91	N 32°15'12.23"	W 103°23'7.25"	465.14	272.33
	10,055.00	2.49	243.60	10,016.60	2.10	16.96	-468.59	6,543.20	0.24	457,210.66	834,393.08	N 32°15'12.21"	W 103°23'7.29"	468.90	272.07
	10,149.00	1.37	231.77	10,110.55	3.81	15.36	-471.30	6,637.15	1.26	457,209.06	834,390.36	N 32°15'12.19"	W 103°23'7.32"	471.55	271.87
	10,244.00	0.79	153.96	10,205.53	5.13	14.07	-471.91	6,732.13	1.50	457,207.77	834,389.76	N 32°15'12.18"	W 103°23'7.33"	472.12	271.71
	10,339.00	1.11	117.61	10,300.52	6.10	13.05	-470.81	6,827.12	0.70	457,206.75	834,390.86	N 32°15'12.17"	W 103°23'7.32"	470.99	271.59
	10,434.00	1.24	129.41	10,395.50	7.11	11.97	-469.20	6,922.10	0.29	457,205.67	834,392.47	N 32°15'12.16"	W 103°23'7.30"	469.35	271.46
	10,528.00	1.80	124.07	10,489.47	8.50	10.50	-467.19	7,016.07	0.61	457,204.20	834,394.48	N 32°15'12.14"	W 103°23'7.28"	467.30	271.29
	10,623.00	1.33	94.81	10,584.43	9.33	9.57	-464.85	7,111.03	0.96	457,203.27	834,396.81	N 32°15'12.13"	W 103°23'7.25"	464.95	271.18
	10,718.00	1.82	98.50	10,679.40	9.54	9.26	-462.26	7,206.00	0.53	457,202.96	834,399.41	N 32°15'12.13"	W 103°23'7.22"	462.35	271.15
	10,812.00	3.01	105.26	10,773.31	10.25	8.39	-458.40	7,299.91	1.30	457,202.09	834,403.26	N 32°15'12.12"	W 103°23'7.17"	458.48	271.05
	10,907.00	2.07	161.58	10,868.23	12.42	6.10	-455.46	7,394.83	2.67	457,199.80	834,406.21	N 32°15'12.10"	W 103°23'7.14"	455.50	270.77
	11,002.00	2.19	174.04	10,963.17	15.82	2.67	-454.72	7,489.77	0.50	457,196.37	834,406.94	N 32°15'12.06"	W 103°23'7.13"	454.73	270.34
	11,174.00	3.08	174.63	11,134.98	23.65	-5.20	-453.95	7,661.58	0.52	457,188.50	834,407.72	N 32°15'11.99"	W 103°23'7.12"	453.98	269.34
	11,288.00	3.78	195.10	11,248.78	30.35	-11.88	-454.64	7,775.38	1.23	457,181.82	834,407.02	N 32°15'11.92"	W 103°23'7.13"	454.80	268.50
	11,299.00	4.90	188.55	11,259.75	31.17	-12.69	-454.81	7,786.35	11.09	457,181.01	834,406.86	N 32°15'11.91"	W 103°23'7.13"	454.98	268.40
	11,382.00	13.89	174.93	11,341.56	44.60	-26.15	-454.45	7,868.16	11.09	457,167.55	834,407.21	N 32°15'11.78"	W 103°23'7.13"	455.20	266.71
	11,477.00	20.80	175.43	11,432.19	72.69	-54.35	-452.10	7,958.79	7.28	457,139.35	834,409.57	N 32°15'11.50"	W 103°23'7.11"	455.35	263.14
	11,572.00	29.33	186.05	11,518.20	112.74	-94.40	-453.21	8,044.80	10.12	457,099.30	834,408.46	N 32°15'11.10"	W 103°23'7.12"	462.94	258.23
	11,667.00	39.55	198.75	11,596.55	165.18	-146.38	-465.43	8,123.15	13.10	457,047.32	834,396.24	N 32°15'10.59"	W 103°23'7.27"	487.91	252.54
	11,761.00	42.07	196.14	11,667.69	224.48	-204.98	-483.81	8,194.29	3.24	456,988.71	834,377.86	N 32°15'10.01"	W 103°23'7.49"	525.44	247.04
	11,856.00	46.36	192.44	11,735.78	289.27	-269.17	-500.07	8,262.38	5.27	456,924.53	834,361.59	N 32°15'9.38"	W 103°23'7.69"	567.91	241.71
	11,950.00	60.80	188.84	11,791.45	363.93	-343.33	-513.78	8,318.05	15.66	456,850.37	834,347.89	N 32°15'8.65"	W 103°23'7.85"	617.94	236.25
	11,965.00	61.33	188.46	11,798.71	376.98	-356.31	-515.76	8,325.31	4.16	456,837.39	834,345.91	N 32°15'8.52"	W 103°23'7.88"	626.86	235.36
	11,995.31	62.40	187.72	11,813.00	403.57	-382.77	-519.52	8,339.60	4.16	456,810.93	834,342.15	N 32°15'8.26"	W 103°23'7.93"	645.30	233.62
	12,045.00	64.17	186.52	11,835.34	447.80	-426.81	-525.01	8,361.94	4.16	456,766.89	834,336.66	N 32°15'7.82"	W 103°23'7.99"	676.61	230.89
	12,140.00	65.59	183.72	11,875.67	533.70	-512.47	-532.67	8,402.27	3.06	456,681.23	834,328.99	N 32°15'6.97"	W 103°23'8.09"	739.17	226.11
	12,234.00	75.66	176.96	11,906.85	622.14	-600.97	-533.04	8,433.45	12.67	456,592.73	834,328.63	N 32°15'6.10"	W 103°23'8.11"	803.30	221.57
	12,329.00	86.89	171.91	11,921.25	714.96	-694.24	-523.89	8,447.85	12.93	456,499.46	834,337.78	N 32°15'5.17"	W 103°23'8.01"	869.73	217.04
	12,420.00	88.18	171.91	11,925.16	804.38	-784.25	-511.09	8,451.76	1.42	456,409.45	834,350.57	N 32°15'4.28"	W 103°23'7.87"	936.09	213.09
	12,424.00	88.24	171.91	11,925.28	808.31	-788.21	-510.53	8,451.88	1.42	456,405.49	834,351.14	N 32°15'4.24"	W 103°23'7.86"	939.10	212.93
	12,497.00	87.96	172.87	11,927.70	880.18	-860.52	-500.87	8,454.30	1.37	456,333.17	834,360.80	N 32°15'3.53"	W 103°23'7.76"	995.68	210.20
	12,592.00	92.00	180.53	11,927.74	974.63	-955.28	-495.41	8,454.34	9.11	456,238.42	834,366.26	N 32°15'2.59"	W 103°23'7.70"	1,076.09	207.41
	12,687.00	90.25	178.13	11,925.87	1,069.47	-1,050.24	-494.29	8,452.47	3.13	456,143.45	834,367.37	N 32°15'1.65"	W 103°23'7.70"	1,160.75	205.20
	12,782.00	90.86	180.10	11,924.95	1,164.31	-1,145.22	-492.83	8,451.55	2.17	456,048.47	834,368.84	N 32°15'0.71"	W 103°23'7.69"	1,246.76	203.28
	12,972.00	90.11	183.69	11,923.34	1,354.26	-1,335.08	-499.11	8,449.94	1.93	455,858.61	834,362.56	N 32°14'58.83"	W 103°23'7.79"	1,425.32	200.50
	13,057.00	91.19	183.04	11,922.38	1,439.24	-1,419.92	-504.10	8,448.98	1.48	455,773.77	834,357.57	N 32°14'57.99"	W 103°23'7.85"	1,506.75	199.55
	13,066.00	91.30	182.97	11,922.18	1,448.24	-1,428.91	-504.57	8,448.78	1.48	455,764.78	834,357.10	N 32°14'57.90"	W 103°23'7.86"	1,515.38	199.45
	13,255.00	89.67	183.14	11,920.58	1,637.21	-1,617.63	-514.64	8,447.18	0.87	455,576.06	834,347.03	N 32°14'56.04"	W 103°23'8.00"	1,697.52	197.65
	13,350.00	88.89	183.14	11,921.78	1,732.19	-1,712.48	-519.84	8,448.38	0.82	455,481.21	834,341.82	N 32°14'55.10"	W 103°23'8.07"	1,789.64	196.89
	13,540.00	89.76	182.83	11,924.02	1,922.17	-1,902.20	-529.74	8,450.62	0.49	455,291.49	834,331.93	N 32°14'53.22"	W 103°23'8.20"	1,974.59	195.56
	13,635.00	88.33	181.25	11,925.60	2,017.15	-1,997.12	-533.12	8,452.20	2.24	455,196.56	834,328.55	N 32°14'52.28"	W 103°23'8.25"	2,067.06	194.95
	13,730.00	88.76	179.18	11,928.01	2,112.05	-2,092.09	-533.47	8,454.61	2.22	455,101.60	834,328.19	N 32°14'51.34"	W 103°23'8.26"	2,159.03	194.31
	13,825.00	88.67	180.42	11,930.14	2,206.93	-2,187.06	-533.14	8,456.74	1.31	455,006.63	834,328.52	N 32°14'50.40"	W 103°23'8.27"	2,251.11	193.70
	13,919.00	89.11	179.97	11,931.96	2,300.84	-2,281.04	-533.46	8,458.56	0.67	454,912.64	834,328.20	N 32°14'49.47"	W 103°23'8.28"	2,342.59	193.16
	14,014.00	88.19	180.76	11,934.20	2,395.76	-2,376.01	-534.07	8,460.80	1.28	454,817.67	834,327.60	N 32°14'48.53"	W 103°23'8.30"	2,435.30	192.67
	14,203.00	89.07	179.85	11,938.72	2,584.58	-2,564.95	-535.07	8,465.32	0.67	454,628.73	834,326.59	N 32°14'46.66"	W 103°23'8.33"	2,620.17	191.78
	14,298.00	88.29	179.14	11,940.91	2,679.44	-2,659.92	-534.24	8,467.51	1.11	454,533.76	834,327.43	N 32°14'45.73"	W 103°23'8.33"	2,713.04	191

LTP / 100 ft FSL Cross	19,970.00	90.98	178.37	12,007.58	8,338.81	-8,325.36	-500.19	8,534.18	1.02	448,868.30	834,361.48	N 32°13'49.66"	W 103°23'8.52"	8,340.37	183.44
	20,065.00	89.60	177.62	12,007.10	8,433.53	-8,420.29	-496.86	8,533.70	1.65	448,773.36	834,364.80	N 32°13'48.72"	W 103°23'8.49"	8,434.94	183.38
	20,159.00	90.02	178.76	12,007.41	8,527.28	-8,514.24	-493.89	8,534.01	1.29	448,679.41	834,367.77	N 32°13'47.79"	W 103°23'8.46"	8,528.56	183.32
	20,254.00	90.19	179.27	12,007.24	8,622.13	-8,609.23	-492.26	8,533.84	0.57	448,584.42	834,369.41	N 32°13'46.85"	W 103°23'8.45"	8,623.29	183.27
	20,348.00	89.11	180.30	12,007.81	8,716.03	-8,703.23	-491.91	8,534.41	1.59	448,490.42	834,369.76	N 32°13'45.92"	W 103°23'8.46"	8,717.12	183.23
	20,443.00	88.18	180.04	12,010.06	8,810.93	-8,798.20	-492.19	8,536.66	1.02	448,395.45	834,369.48	N 32°13'44.98"	W 103°23'8.47"	8,811.95	183.20
	20,537.00	87.01	178.74	12,014.00	8,904.72	-8,892.11	-491.19	8,540.60	1.86	448,301.54	834,370.48	N 32°13'44.06"	W 103°23'8.47"	8,905.66	183.16
	20,632.00	86.83	177.89	12,019.11	8,999.35	-8,986.93	-488.40	8,545.71	0.91	448,206.72	834,373.27	N 32°13'43.12"	W 103°23'8.45"	9,000.19	183.11
	20,726.00	86.86	177.80	12,024.28	9,092.92	-9,080.72	-484.87	8,550.88	0.10	448,112.93	834,376.79	N 32°13'42.19"	W 103°23'8.42"	9,093.65	183.06
	20,821.00	87.16	177.06	12,029.24	9,187.45	-9,175.49	-480.62	8,555.84	0.84	448,018.16	834,381.05	N 32°13'41.25"	W 103°23'8.38"	9,188.07	183.00
	20,916.00	86.96	176.13	12,034.11	9,281.84	-9,270.20	-474.98	8,560.71	1.00	447,923.45	834,386.68	N 32°13'40.31"	W 103°23'8.32"	9,282.36	182.93
	21,010.00	86.94	175.35	12,039.11	9,375.09	-9,363.80	-468.01	8,565.71	0.83	447,829.84	834,393.66	N 32°13'39.39"	W 103°23'8.25"	9,375.49	182.86
	21,105.00	86.51	175.95	12,044.54	9,469.29	-9,458.38	-460.82	8,571.14	0.78	447,735.27	834,400.85	N 32°13'38.45"	W 103°23'8.17"	9,469.59	182.79
	21,200.00	87.16	177.36	12,049.78	9,563.68	-9,553.07	-455.28	8,576.38	1.63	447,640.58	834,406.38	N 32°13'37.51"	W 103°23'8.12"	9,563.91	182.73
	21,295.00	86.67	178.00	12,054.90	9,658.23	-9,647.85	-451.44	8,581.50	0.85	447,545.79	834,410.22	N 32°13'36.57"	W 103°23'8.08"	9,658.41	182.68
	21,389.00	86.85	178.16	12,060.21	9,751.82	-9,741.65	-448.30	8,586.81	0.26	447,452.00	834,413.37	N 32°13'35.65"	W 103°23'8.06"	9,751.96	182.63
	21,483.00	87.38	177.60	12,064.94	9,845.42	-9,835.46	-444.83	8,591.54	0.82	447,358.18	834,416.84	N 32°13'34.72"	W 103°23'8.03"	9,845.52	182.59
	21,577.00	87.82	176.83	12,068.88	9,938.96	-9,929.27	-440.26	8,595.48	0.94	447,264.37	834,421.41	N 32°13'33.79"	W 103°23'7.98"	9,939.02	182.54
	21,672.00	87.04	177.67	12,073.14	10,033.49	-10,024.06	-435.71	8,599.74	1.21	447,169.58	834,425.96	N 32°13'32.85"	W 103°23'7.94"	10,033.53	182.49
	21,766.00	86.49	177.81	12,078.44	10,127.04	-10,117.84	-432.01	8,605.04	0.60	447,075.80	834,429.66	N 32°13'31.92"	W 103°23'7.91"	10,127.06	182.44
	21,861.00	87.08	177.70	12,083.77	10,221.59	-10,212.62	-428.29	8,610.37	0.63	446,981.02	834,433.38	N 32°13'30.98"	W 103°23'7.87"	10,221.59	182.40
	21,938.00	86.64	177.72	12,087.98	10,298.22	-10,289.44	-425.22	8,614.58	0.57	446,904.20	834,436.45	N 32°13'30.22"	W 103°23'7.85"	10,298.22	182.37
	21,956.00	86.54	177.72	12,089.05	10,316.13	-10,307.39	-424.50	8,615.65	0.57	446,886.25	834,437.17	N 32°13'30.05"	W 103°23'7.84"	10,316.13	182.36
	Last Survey	21,982.00	86.71	177.64	12,090.59	10,342.00	-10,333.33	-423.45	8,617.19	0.72	446,860.31	834,438.22	N 32°13'29.79"	W 103°23'7.83"	10,342.00
Projection to Total Depth	22,019.00	86.71	177.64	12,092.71	10,378.81	-10,370.23	-421.93	8,619.31	0.00	446,823.41	834,439.74	N 32°13'29.42"	W 103°23'7.82"	10,378.81	182.33

Survey Type: DefinitiveSurvey

Survey Error Model: ISCWSA0 2.795 sigma
Survey Program:

Description	Part	MD From (ft)	MD To (ft)	EOU Freq (ft)	Expected Max Inclination (deg)	Survey Tool Code	Borehole / Survey
	1	0.000	1,194.000	Act Stns		A009Mb_MWD+IFR1+SAG	Maltese 5-8 Fed Com 33H / Oxy Maltese 5-8 Fed Com 33H IFR1 to 22019ft
	1	1,194.000	22,019.000	Act Stns		A010Mb_MWD+IFR1+SAG+MS	Maltese 5-8 Fed Com 33H / Oxy Maltese 5-8 Fed Com 33H IFR1 to 22019ft

EOU Geometry:

End MD (ft)	Hole Size (in)	Casing Size (in)	Name
22,019.000	26.400	26.400	

Intent ☐ As Drilled ☒

API # 30-025-48976		
Operator Name: OXY USA INC.	Property Name: Maltese 5 8 Federal Com	Well Number 33H

Kick Off Point (KOP)

UL 1	Section 5	Township 24S	Range 35E	Lot	Feet 188	From N/S North	Feet 1315	From E/W East	County Lea
Latitude 32.253309					Longitude -103.385315				NAD Nad83

First Take Point (FTP)

UL 1	Section 5	Township 24S	Range 35E	Lot	Feet 523	From N/S North	Feet 1379	From E/W East	County Lea
Latitude 32.252390					Longitude -103.385517				NAD Nad83

Last Take Point (LTP)

UL O	Section 8	Township 24S	Range 35E	Lot	Feet 220	From N/S South	Feet 1403	From E/W West	County Lea
Latitude 32.225391					Longitude -103.385525				NAD Nad83

Is this well the defining well for the Horizontal Spacing Unit? ☐Is this well an infill well? ☐

If infill is yes please provide API if available, Operator Name and well number for Defining well for Horizontal Spacing Unit.

API #		
Operator Name:	Property Name:	Well Number

KZ 06/29/2018

Well Name: MALTESE 5_8 FEDERAL COM	Well Location: T24S / R35E / SEC 5 / LOT 1 / 32.253332 / -103.383844	County or Parish/State: LEA / NM
Well Number: 33H	Type of Well: OIL WELL	Allottee or Tribe Name:
Lease Number: NMNM019628	Unit or CA Name:	Unit or CA Number:
US Well Number: 3002548976	Well Status: Producing Oil Well	Operator: OXY USA INCORPORATED

Subsequent Report

Sundry ID: 2767977

Type of Submission: Subsequent Report	Type of Action: Hydraulic Fracturing
Date Sundry Submitted: 01/03/2024	Time Sundry Submitted: 01:04
Date Operation Actually Began: 10/18/2023	

Actual Procedure: RUPU 10/18/2023, RIH & Clean out to PBTD 21975'. Test production casing to 6000 psi for 30 min, good test. RIH and Perf from 11955'-21818', total 2280 holes, 0.42". Frac in 40 stages with 26,799,260 #'s sand and 483,033 bbls produced water, 12461' bbls brackish water. RD Frac and well ready to produce on 11/21/2023.

Received by OCD: 3/1/2024 9:45:48 AM

Page 8 of 13

Well Name: MALTESE 5_8 FEDERAL COM	Well Location: T24S / R35E / SEC 5 / LOT 1 / 32.253332 / -103.383844	County or Parish/State: LEA / NM
Well Number: 33H	Type of Well: OIL WELL	Allottee or Tribe Name:
Lease Number: NMNM019628	Unit or CA Name:	Unit or CA Number:
US Well Number: 3002548976	Well Status: Producing Oil Well	Operator: OXY USA INCORPORATED

Operator

I certify that the foregoing is true and correct. Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction. Electronic submission of Sundry Notices through this system satisfies regulations requiring a

Operator Electronic Signature: SARAH MCKINNEY	Signed on: JAN 03, 2024 01:04 PM
Name: OXY USA INCORPORATED	
Title: Regulatory Analyst Sr	
Street Address: 5 GREENWAY PLAZA SUITE 110	
City: HOUSTON	State: TX
Phone: (713) 215-7295	
Email address: SARAH_MCKINNEY@OXY.COM	

Field

Representative Name:		
Street Address:		
City:	State:	Zip:
Phone:		
Email address:		

BLM Point of Contact

BLM POC Name: JONATHON W SHEPARD	BLM POC Title: Petroleum Engineer
BLM POC Phone: 5752345972	BLM POC Email Address: jshepard@blm.gov
Disposition: Accepted	Disposition Date: 01/10/2024
Signature: Jonathon Shepard	

Submit To Appropriate District Office Two Copies <u>District I</u> 1625 N. French Dr., Hobbs, NM 88240 <u>District II</u> 811 S. First St., Artesia, NM 88210 <u>District III</u> 1000 Rio Brazos Rd., Aztec, NM 87410 <u>District IV</u> 1220 S. St. Francis Dr., Santa Fe, NM 87505		State of New Mexico Energy, Minerals and Natural Resources Oil Conservation Division 1220 South St. Francis Dr. Santa Fe, NM 87505				Form C-105 Revised April 3, 2017				
1. WELL API NO. 30-025-48976										
2. Type of Lease ☐ STATE ☐ FEE ☒ FED/INDIAN										
3. State Oil & Gas Lease No.										
WELL COMPLETION OR RECOMPLETION REPORT AND LOG										
4. Reason for filing: ☒ COMPLETION REPORT (Fill in boxes #1 through #31 for State and Fee wells only) ☐ C-144 CLOSURE ATTACHMENT (Fill in boxes #1 through #9, #15 Date Rig Released and #32 and/or #33; attach this and the plat to the C-144 closure report in accordance with 19.15.17.13.K NMAC)						5. Lease Name or Unit Agreement Name Maltese 5 8 Fed COM				
						6. Well Number: 33H				
7. Type of Completion: ☒ NEW WELL ☐ WORKOVER ☐ DEEPENING ☐ PLUGBACK ☐ DIFFERENT RESERVOIR ☐ OTHER										
8. Name of Operator OXY USA INC.						9. OGRID 16696				
10. Address of Operator PO Box 50250, MIDLAND, TX 79710						11. Pool name or Wildcat Antelope Ridge; Wolfcamp				
12. Location	Unit Ltr	Section	Township	Range	Lot	Feet from the	N/S Line	Feet from the	E/W Line	County
Surface:	1	5	24S	35E		180	North	860	East	Lea
BH:	O	8	24S	35E		19	South	1397	East	Lea
13. Date Spudded 06/25/2023	14. Date T.D. Reached 08/18/2023		15. Date Rig Released 08/21/2023		16. Date Completed (Ready to Produce) 11/21/2023			17. Elevations (DF and RKB, RT, GR, etc.) 3447' GR		
18. Total Measured Depth of Well 22019' MD, 12092' TVD			19. Plug Back Measured Depth 21975' MD, 12090' TVD		20. Was Directional Survey Made? Yes			21. Type Electric and Other Logs Run CBL/GAMMA		
22. Producing Interval(s), of this completion - Top, Bottom, Name 11955-21818, Wolfspring										
23. CASING RECORD (Report all strings set in well)										
CASING SIZE		WEIGHT LB./FT.		DEPTH SET		HOLE SIZE		CEMENTING RECORD		AMOUNT PULLED
13 3/8"		54.5# J-55		1261'		17 1/2"		1267sx Class C- TOC 0'		
7 5/8"		26.4# HCL80		11202'		9 7/8"		3165sx Class H - TOC 0'		
5 1/2"		20# P110		21999'		6 3/4"		782sx Class H - TOC 10930'		
24. LINER RECORD										
SIZE	TOP	BOTTOM	SACKS CEMENT	SCREEN	25. TUBING RECORD					
					SIZE	DEPTH SET	PACKER SET			
26. Perforation record (interval, size, and number) 11955-21818, 0.42", 2280 holes					27. ACID, SHOT, FRACTURE, CEMENT, SQUEEZE, ETC.					
					DEPTH INTERVAL		AMOUNT AND KIND MATERIAL USED			
					11955-21818		483,033 bbls produced water, 12461 bbls			
							brackish water, 26,799,260 #'s sand.			
28. PRODUCTION										
Date First Production 11/29/2023		Production Method (Flowing, gas lift, pumping - Size and type pump) Flowing				Well Status (Prod. or Shut-in) Producing				
Date of Test 12/13/2023	Hours Tested 24 Hours	Choke Size 0	Prod'n For Test Period	Oil - Bbl 2415	Gas - MCF 2385	Water - Bbl. 750	Gas - Oil Ratio 988			
Flow Tubing Press.	Casing Pressure 691	Calculated 24-Hour Rate	Oil - Bbl. 2415	Gas - MCF 2385	Water - Bbl. 750	Oil Gravity - API - (Corr.)				
29. Disposition of Gas (Sold, used for fuel, vented, etc.) Sold							30. Test Witnessed By			
31. List Attachments C104c, C102, WBD, Directional Survey, CBL										
32. If a temporary pit was used at the well, attach a plat with the location of the temporary pit.							33. Rig Release Date:			
34. If an on-site burial was used at the well, report the exact location of the on-site burial:										
Latitude _____ Longitude _____ NAD83										
I hereby certify that the information shown on both sides of this form is true and complete to the best of my knowledge and belief										
Signature 		Printed Name Sarah McKinney		Title Regulatory Analyst Sr.			Date 01/10/2024			
E-mail Address sarah_mckinney@oxy.com										

This form is to be filed with the appropriate District Office of the Division not later than 20 days after the completion of any newly-drilled or deepened well and not later than 60 days after completion of closure. When submitted as a completion report, this shall be accompanied by one copy of all electrical and radio-activity logs run on the well and a summary of all special tests conducted, including drill stem tests. All depths reported shall be measured depths. In the case of directionally drilled wells, true vertical depths shall also be reported. For multiple completions, items 11, 12 and 26-31 shall be reported for each zone.

Southeastern New Mexico		Northwestern New Mexico	
T. Rustler 994'	T. Bell Canyon	T. Ojo Alamo	T. Penn A"
T. Salado 1348'	T. Strawn	T. Kirtland	T. Penn. "B"
T. Castile 3956'	T. Atoka	T. Fruitland	T. Penn. "C"
T. Delaware 4860'	T. Miss	T. Pictured Cliffs	T. Penn. "D"
T. Cherry Canyon 6097'	T. Devonian	T. Cliff House	T. Leadville
T. Brushy Canyon 7623'	T. Silurian	T. Menefee	T. Madison
T. Grayburg	T. Montoya	T. Point Lookout	T. Elbert
T. San Andres	T. Simpson	T. Mancos	T. McCracken
T. Glorieta	T. McKee	T. Gallup	T. Ignacio Otzte
T. Paddock	T. Ellenburger	Base Greenhorn	T. Granite
T. Blinebry	T. Gr. Wash	T. Dakota	
T. Tubb	T. Delaware Sand	T. Morrison	
T. Drinkard	T. Bone Springs 8910'	T. Todilto	
T. Abo	T. 1 st Bone Springs 9973'	T. Entrada	
T. Wolfcamp	T. 2 nd Bone Springs 10501'	T. Wingate	
T. Penn	T. 3 rd Bone Springs 11636'	T. Chinle	
T. Cisco (Bough C)	T. Wolfcamp 11948'	T. Permian	


No. 1, from.....to.....
No. 2, from.....to.....
No. 3, from.....to.....
No. 4, from.....to.....

Include data on rate of water inflow and elevation to which water rose in hole.

No. 1, from.....to.....feet.....
 No. 2, from.....to.....feet.....
 No. 3, from.....to.....feet.....

From	To	Thickness In Feet	Lithology

OXY USA Inc.
Maltese 5 8 Fed Com 33H
API No. 30-025-48976



District I
1625 N. French Dr., Hobbs, NM 88240
Phone:(575) 393-6161 Fax:(575) 393-0720
District II
811 S. First St., Artesia, NM 88210
Phone:(575) 748-1283 Fax:(575) 748-9720
District III
1000 Rio Brazos Rd., Aztec, NM 87410
Phone:(505) 334-6178 Fax:(505) 334-6170
District IV
1220 S. St Francis Dr., Santa Fe, NM 87505
Phone:(505) 476-3470 Fax:(505) 476-3462

State of New Mexico
Energy, Minerals and Natural Resources
Oil Conservation Division
1220 S. St Francis Dr.
Santa Fe, NM 87505

ACKNOWLEDGMENTS

Action 319338

ACKNOWLEDGMENTS

Operator: OXY USA INC P.O. Box 4294 Houston, TX 772104294	OGRID: 16696
	Action Number: 319338
	Action Type: [C-104] Completion Packet (C-104C)

ACKNOWLEDGMENTS

☒	I hereby certify that the required Water Use Report has been, or will be, submitted for this wells completion.
☒	I hereby certify that the required FracFocus disclosure has been, or will be, submitted for this wells completion.

District I
1625 N. French Dr., Hobbs, NM 88240
Phone:(575) 393-6161 Fax:(575) 393-0720
District II
811 S. First St., Artesia, NM 88210
Phone:(575) 748-1283 Fax:(575) 748-9720
District III
1000 Rio Brazos Rd., Aztec, NM 87410
Phone:(505) 334-6178 Fax:(505) 334-6170
District IV
1220 S. St Francis Dr., Santa Fe, NM 87505
Phone:(505) 476-3470 Fax:(505) 476-3462

State of New Mexico
Energy, Minerals and Natural Resources
Oil Conservation Division
1220 S. St Francis Dr.
Santa Fe, NM 87505

CONDITIONS

Action 319338

CONDITIONS

Operator: OXY USA INC P.O. Box 4294 Houston, TX 772104294	OGRID: 16696
	Action Number: 319338
	Action Type: [C-104] Completion Packet (C-104C)

CONDITIONS

Created By	Condition	Condition Date
smcgrath	File 3160-4 within 10 days of BLM Approval.	3/1/2024