

District I
1625 N. French Dr., Hobbs, NM 88240
District II
811 S. First St., Artesia, NM 88210
District III
1000 Rio Brazos Rd., Aztec, NM 87410
District IV
1220 S. St. Francis Dr., Santa Fe, NM 87505

State of New Mexico
Energy, Minerals & Natural Resources

Form C-104
Revised August 1, 2011

Oil Conservation Division
1220 South St. Francis Dr.
Santa Fe, NM 87505

Submit one copy to appropriate District Office

☐ AMENDED REPORT

I. REQUEST FOR ALLOWABLE AND AUTHORIZATION TO TRANSPORT

¹ Operator name and Address OXY USA INC. PO BOX 50250 MIDLAND, TX 79710		² OGRID Number 16696
		³ Reason for Filing Code/ Effective Date NW - 10/31/2023
⁴ API Number 30 - 025-48978	⁵ Pool Name Antelope Ridge; Wolfcamp	
	⁶ Pool Code 2220	
⁷ Property Code 330861	⁸ Property Name Maltese 5 8 Fed COM	⁹ Well Number 35H

II. ¹⁰ Surface Location

UL or lot no.	Section	Township	Range	Lot Idn	Feet from the	North/South Line	Feet from the	East/West line	County
3	5	24S	35E		475	North	1510	West	Lea

¹¹ Bottom Hole Location

UL or lot no.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County
M	8	24S	35E		31	South	1303	West	Lea
¹² Lse Code F	¹³ Producing Method Code F	¹⁴ Gas Connection Date 11/26/2023	¹⁵ C-129 Permit Number		¹⁶ C-129 Effective Date		¹⁷ C-129 Expiration Date		

III. Oil and Gas Transporters

¹⁸ Transporter OGRID	¹⁹ Transporter Name and Address	²⁰ O/G/W
237722	Centerion Pipeline, L.P.	O
248749	DCP Midstream, L.P.	G

IV. Well Completion Data

²¹ Spud Date 6/25/2023	²² Ready Date 10/31/2023	²³ TD 21969' MD; 12139' TVD	²⁴ PBTD 21926' MD, 12137' TVD	²⁵ Perforations 12005'-21790'	²⁶ DHC, MC
²⁷ Hole Size		²⁸ Casing & Tubing Size		²⁹ Depth Set	³⁰ Sacks Cement
17 1/2"		13 3/8" 54.5# J-55		1132'	1193 sx - TOC 0'
12 1/4"		7 5/8" 26.4# HCL80		11074'	6209 sx - TOC 0'
6 3/4"		5 1/2" 20# P110		21949'	780 sx - est.TOC 10783'

V. Well Test Data

³¹ Date New Oil 11/26/2023	³² Gas Delivery Date 11/26/2023	³³ Test Date 12/4/2023	³⁴ Test Length 24 hours	³⁵ Tbg. Pressure	³⁶ Csg. Pressure 1275
³⁷ Choke Size 0	³⁸ Oil 3273	³⁹ Water 5251	⁴⁰ Gas 3032		⁴¹ Test Method Flowing

⁴² I hereby certify that the rules of the Oil Conservation Division have been complied with and that the information given above is true and complete to the best of my knowledge and belief. Signature: 		OIL CONSERVATION DIVISION	
Printed name: Sarah McKinney		Approved by: PATRICIA MARTINEZ	
Title: Regulatory Analyst Sr.		Title: PETROLEUM SPECIALIST	
E-mail Address: sarah_mckinney@oxy.com		Approval Date: 4/23/2024	
Date: 01/08/2024	Phone: 713-215-7295		

District I
1625 N. French Dr., Hobbs, NM 88240
Phone: (575) 393-6161 Fax: (575) 393-0720
District II
811 S. First St., Artesia, NM 88210
Phone: (575) 748-1283 Fax: (575) 748-9720
District III
1000 Rio Brazos Road, Aztec, NM 87410
Phone: (505) 334-6178 Fax: (505) 334-6170
District IV
1220 S. St. Francis Dr., Santa Fe, NM 87505
Phone: (505) 476-3460 Fax: (505) 476-3462

State of New Mexico
Energy, Minerals & Natural Resources Department
OIL CONSERVATION DIVISION
1220 South St. Francis Dr.
Santa Fe, NM 87505

Form C-102
Revised August 1, 2011
Submit one copy to appropriate
District Office

☒ AMENDED REPORT

As-Drilled Plat

WELL LOCATION AND ACREAGE DEDICATION PLAT

¹ API Number 30-025-48978	² Pool Code 2220	³ Pool Name Antelope Ridge; Wolfcamp
⁴ Property Code 330861	⁵ Property Name MALTESE 5 8 FED COM	⁶ Well Number 35H
⁷ OGRID No. 16696	⁸ Operator Name OXY USA INC.	⁹ Elevation 3454.2' (NAVD 88)

¹⁰ Surface Location

UL or lot no. 3	Section 5	Township 24S	Range 35E	Lot Idn	Feet from the 475	North/South line NORTH	Feet from the 1510	East/West line WEST	County LEA
--------------------	--------------	-----------------	--------------	---------	----------------------	---------------------------	-----------------------	------------------------	---------------

¹¹ Bottom Hole Location If Different From Surface

UL or lot no. M	Section 8	Township 24S	Range 35E	Lot Idn	Feet from the 31	North/South line SOUTH	Feet from the 1303	East/West line WEST	County LEA
¹² Dedicated Acres 1280	¹³ Joint or Infill	¹⁴ Consolidation Code	¹⁵ Order No. R-22665						


No allowable will be assigned to this completion until all interests have been consolidated or a non-standard unit has been approved by the division.

NAD 83 (SURFACE HOLE LOCATION) LATITUDE = 32°15'09.06" (32.252517°) LONGITUDE = -103°23'35.74" (-103.393260°) NAD 27 (SURFACE HOLE LOCATION) LATITUDE = 32°15'08.61" (32.252392°) LONGITUDE = -103°23'34.03" (-103.392787°) STATE PLANE NAD 83 (N.M. EAST) N: 456871.47' E: 831953.21' STATE PLANE NAD 27 (N.M. EAST) N: 456812.07' E: 790768.56'	NAD 83 (AS-DRILLED KOP) LATITUDE = 32°15'12.88" (32.253577°) LONGITUDE = -103°23'37.81" (-103.393837°) NAD 27 (AS-DRILLED KOP) LATITUDE = 32°15'12.42" (32.253451°) LONGITUDE = -103°23'36.11" (-103.393364°) STATE PLANE NAD 83 (N.M. EAST) N: 457255.25' E: 831771.38' STATE PLANE NAD 27 (N.M. EAST) N: 457195.83' E: 790586.74'	NAD 83 (AS-DRILLED FTP) LATITUDE = 32°15'07.91" (32.252198°) LONGITUDE = -103°23'37.79" (-103.393831°) NAD 27 (AS-DRILLED FTP) LATITUDE = 32°15'07.46" (32.252072°) LONGITUDE = -103°23'36.09" (-103.393358°) STATE PLANE NAD 83 (N.M. EAST) N: 456753.67' E: 831777.77' STATE PLANE NAD 27 (N.M. EAST) N: 456694.27' E: 790593.11'
NAD 83 (AS-DRILLED LPP #1) LATITUDE = 32°14'21.48" (32.239301°) LONGITUDE = -103°23'37.89" (-103.393858°) NAD 27 (AS-DRILLED LPP #1) LATITUDE = 32°14'21.03" (32.239176°) LONGITUDE = -103°23'36.19" (-103.393386°) STATE PLANE NAD 83 (N.M. EAST) N: 452061.82' E: 831810.35' STATE PLANE NAD 27 (N.M. EAST) N: 452002.55' E: 790625.50'	NAD 83 (AS-DRILLED LPP #2) LATITUDE = 32°14'16.74" (32.237982°) LONGITUDE = -103°23'37.75" (-103.393819°) NAD 27 (AS-DRILLED LPP #2) LATITUDE = 32°14'16.28" (32.237857°) LONGITUDE = -103°23'36.05" (-103.393346°) STATE PLANE NAD 83 (N.M. EAST) N: 451581.97' E: 831826.76' STATE PLANE NAD 27 (N.M. EAST) N: 451522.71' E: 790641.89'	NAD 83 (AS-DRILLED LPP #3) LATITUDE = 32°14'10.07" (32.236129°) LONGITUDE = -103°23'37.74" (-103.393817°) NAD 27 (AS-DRILLED LPP #3) LATITUDE = 32°14'09.61" (32.236004°) LONGITUDE = -103°23'36.04" (-103.393345°) STATE PLANE NAD 83 (N.M. EAST) N: 450907.95' E: 831833.09' STATE PLANE NAD 27 (N.M. EAST) N: 450848.71' E: 790648.20'
NAD 83 (AS-DRILLED LPP #4) LATITUDE = 32°14'03.67" (32.234352°) LONGITUDE = -103°23'37.74" (-103.393816°) NAD 27 (AS-DRILLED LPP #4) LATITUDE = 32°14'03.21" (32.234226°) LONGITUDE = -103°23'36.04" (-103.393344°) STATE PLANE NAD 83 (N.M. EAST) N: 450261.19' E: 831839.17' STATE PLANE NAD 27 (N.M. EAST) N: 450201.97' E: 790654.25'	NAD 83 (AS-DRILLED LPP #5) LATITUDE = 32°13'55.35" (32.232043°) LONGITUDE = -103°23'37.63" (-103.393786°) NAD 27 (AS-DRILLED LPP #5) LATITUDE = 32°13'54.90" (32.231917°) LONGITUDE = -103°23'35.93" (-103.393314°) STATE PLANE NAD 83 (N.M. EAST) N: 449421.35' E: 831855.87' STATE PLANE NAD 27 (N.M. EAST) N: 449362.15' E: 790670.91'	NAD 83 (AS-DRILLED LTP) LATITUDE = 32°13'31.30" (32.225361°) LONGITUDE = -103°23'37.89" (-103.393859°) NAD 27 (AS-DRILLED LTP) LATITUDE = 32°13'30.85" (32.225236°) LONGITUDE = -103°23'36.20" (-103.393388°) STATE PLANE NAD 83 (N.M. EAST) N: 446990.29' E: 831854.31' STATE PLANE NAD 27 (N.M. EAST) N: 446931.15' E: 790669.24'
NAD 83 (AS-DRILLED BHL) LATITUDE = 32°13'29.54" (32.224871°) LONGITUDE = -103°23'37.87" (-103.393854°) NAD 27 (AS-DRILLED BHL) LATITUDE = 32°13'29.08" (32.224745°) LONGITUDE = -103°23'36.18" (-103.393382°) STATE PLANE NAD 83 (N.M. EAST) N: 446812.01' E: 831857.67' STATE PLANE NAD 27 (N.M. EAST) N: 446752.87' E: 790672.60'		

**¹⁷ OPERATOR
CERTIFICATION**
I hereby certify that the information contained herein is true and complete to the best of my knowledge and belief, and that this organization either owns a working interest or unleased mineral interest in the land including the proposed bottom hole location or has a right to drill this well at this location pursuant to a contract with an owner of such a mineral or working interest, or to a voluntary pooling agreement or a compulsory pooling order heretofore entered by the division.
Sarah McKinney 1/8/24
Signature Date
Sarah McKinney
Printed Name
sarah_mckinney@oxy.com
E-mail Address

**¹⁸ SURVEYOR
CERTIFICATION**
I hereby certify that the well location shown on this plat was plotted from field notes of actual surveys made by me or under my supervision, and that the same is true and correct to the best of my belief.
December 12, 2019
Date of Survey
Signature and Seal of Professional Surveyor:

Certificate Number:



NOTE:
• Distances referenced on plat to section lines are perpendicular.
• Basis of Bearing is a Transverse Mercator Projection with a Central Meridian of W103°53'00" (NAD 83)
• As-Drilled well head has not been field verified.
• Wellbore data provided by Oxy USA Inc.

2000' 1000' 0' 2000'
SCALE
DRAWN BY: N.R. 11-03-23



Oxy Maltese 5-8 Fed Com 35H IFR1 to 21969ft Survey Geodetic Report

DefinitiveSurvey

Report Date:	August 18, 2023 - 08:39 PM (UTC 0)	Survey / DLS Computation:	Minimum Curvature / Lubinski
Client:	OXY	Vertical Section Azimuth:	180.544 °(Grid North)
Field:	NM Lea County (NAD 83)	Vertical Section Origin:	0.000 ft, 0.000 ft
Structure / Slot:	Oxy Maltese 5-8 Fed Com Pad Lot 3 / Maltese 5-8 Fed Com 35H	TVD Reference Datum:	RKB
Well:	Maltese 5-8 Fed Com 35H	TVD Reference Elevation:	3479.200 ft above MSL
Borehole:	Maltese 5-8 Fed Com 35H	Seabed / Ground Elevation:	3454.200 ft above MSL
UBHI / API / JobNumber:	Unknown / Unknown / Unknown	Magnetic Declination:	6.308°
Survey Name / Version:	Maltese 5-8 Fed Com 35H IFR1 to 21969ft / 3	Total Gravity Field Strength:	998.4651mgn (9.80665 Based)
Survey Date:	August 18, 2023	Gravity Model:	GARM
Tort / AHD / DDI / ERD Ratio:	277.659 ° / 10909.768 ft / 6.739 / 0.899	Total Magnetic Field Strength:	47516.7 nT
Coordinate Reference System:	NAD83 New Mexico State Plane, Eastern Zone, US Feet	Magnetic Dip Angle:	59.823°
Location Lat / Long:	N 32°15'9.06243", W 103°23'35.73561"	Declination Date:	August 01, 2023
Location Grid N/E Y/X:	N 456871.470 ftUS , E 831953.210 ftUS	Magnetic Declination Model:	IFR1
CRS Grid Convergence Angle:	0.502°	North Reference:	Grid
Grid Scale Factor:	1.00000582	Total Grid mag North Scale:	5.806°
Engine Version:	2023.1.0.1	Local Coord Referenced To:	Well Head

Comments	MD (ft)	Incl (°)	Azim (°)	TVD (ft)	VSEC (ft)	NS (ft)	EW (ft)	TVDSS (ft)	DLS (°/100ft)	Northing (ftUS)	Easting (ftUS)	Latitude (N/S ° ' '')	Longitude (E/W ° ' '')	Closure (ft)	Closure Azimuth (°)
WRP	0.00	0.00	0.00	0.00	0.00	0.00	0.00	-3,479.20		456,871.47	831,953.21	N 32°15'9.06"	W 103°23'35.74"		
SHL	25.00	0.00	0.00	25.00	0.00	0.00	0.00	-3,454.20	0.00	456,871.47	831,953.21	N 32°15'9.06"	W 103°23'35.74"	0.00	0.00
First SLB Survey	174.00	0.22	29.35	174.00	-0.25	0.25	0.14	-3,305.20	0.15	456,871.72	831,953.35	N 32°15'9.06"	W 103°23'35.73"	0.29	29.35
	352.00	0.25	50.99	352.00	-0.80	0.79	0.61	-3,127.20	0.05	456,872.26	831,953.82	N 32°15'9.07"	W 103°23'35.73"	1.00	37.59
	447.00	0.11	88.83	447.00	-0.93	0.92	0.86	-3,032.20	0.19	456,872.39	831,954.07	N 32°15'9.07"	W 103°23'35.73"	1.26	43.00
	541.00	0.69	224.84	541.00	-0.53	0.52	0.55	-2,938.20	0.82	456,871.99	831,953.76	N 32°15'9.07"	W 103°23'35.73"	0.76	46.51
	636.00	0.52	189.21	635.99	0.31	-0.31	0.08	-2,843.21	0.43	456,871.16	831,953.29	N 32°15'9.06"	W 103°23'35.73"	0.32	165.30
	731.00	0.95	229.70	730.98	1.25	-1.24	-0.59	-2,748.22	0.68	456,870.23	831,952.62	N 32°15'9.05"	W 103°23'35.74"	1.37	205.39
	826.00	0.86	208.00	825.97	2.39	-2.38	-1.52	-2,653.23	0.37	456,869.09	831,951.69	N 32°15'9.04"	W 103°23'35.75"	2.83	212.64
	920.00	0.56	207.76	919.96	3.43	-3.41	-2.07	-2,559.24	0.32	456,868.06	831,951.14	N 32°15'9.03"	W 103°23'35.76"	3.99	211.26
	1,015.00	0.69	210.85	1,014.96	4.34	-4.31	-2.58	-2,464.24	0.14	456,867.16	831,950.63	N 32°15'9.02"	W 103°23'35.77"	5.02	210.89
	1,056.00	0.83	200.67	1,055.95	4.83	-4.80	-2.81	-2,423.25	0.47	456,866.67	831,950.40	N 32°15'9.02"	W 103°23'35.77"	5.56	210.34
	1,242.00	0.85	243.96	1,241.94	6.71	-6.67	-4.53	-2,237.26	0.33	456,864.80	831,948.68	N 32°15'9.00"	W 103°23'35.79"	8.06	214.17
	1,337.00	0.13	272.67	1,336.93	7.02	-6.97	-5.27	-2,142.27	0.78	456,864.50	831,947.94	N 32°15'8.99"	W 103°23'35.80"	8.74	217.07
	1,431.00	0.13	285.55	1,430.93	6.99	-6.94	-5.48	-2,048.27	0.03	456,864.53	831,947.73	N 32°15'8.99"	W 103°23'35.80"	8.84	218.28
	1,526.00	0.21	195.15	1,525.93	7.13	-7.08	-5.63	-1,953.27	0.26	456,864.39	831,947.58	N 32°15'8.99"	W 103°23'35.80"	9.04	218.48
	1,621.00	0.17	213.12	1,620.93	7.42	-7.36	-5.75	-1,858.27	0.08	456,864.11	831,947.46	N 32°15'8.99"	W 103°23'35.80"	9.34	217.97
	1,716.00	0.13	311.03	1,715.93	7.47	-7.41	-5.91	-1,763.27	0.24	456,864.06	831,947.30	N 32°15'8.99"	W 103°23'35.81"	9.48	218.55
	1,810.00	0.14	293.25	1,809.93	7.35	-7.30	-6.09	-1,669.27	0.05	456,864.17	831,947.12	N 32°15'8.99"	W 103°23'35.81"	9.50	219.86
	1,904.00	0.14	94.98	1,903.93	7.32	-7.26	-6.08	-1,575.27	0.29	456,864.21	831,947.13	N 32°15'8.99"	W 103°23'35.81"	9.47	219.96
	1,999.00	0.15	150.74	1,998.93	7.43	-7.38	-5.91	-1,480.27	0.14	456,864.09	831,947.30	N 32°15'8.99"	W 103°23'35.81"	9.45	218.68
	2,094.00	0.12	295.95	2,093.93	7.50	-7.44	-5.94	-1,385.27	0.27	456,864.03	831,947.27	N 32°15'8.99"	W 103°23'35.81"	9.52	218.57
	2,188.00	0.16	157.19	2,187.93	7.58	-7.52	-5.97	-1,291.27	0.28	456,863.95	831,947.24	N 32°15'8.99"	W 103°23'35.81"	9.60	218.45
	2,283.00	0.13	312.85	2,282.93	7.63	-7.57	-6.00	-1,196.27	0.30	456,863.90	831,947.21	N 32°15'8.99"	W 103°23'35.81"	9.66	218.40
	2,378.00	0.16	325.16	2,377.93	7.45	-7.39	-6.16	-1,101.27	0.05	456,864.08	831,947.05	N 32°15'8.99"	W 103°23'35.81"	9.62	219.80
	2,473.00	0.09	275.12	2,472.93	7.33	-7.27	-6.31	-1,006.27	0.13	456,864.20	831,946.90	N 32°15'8.99"	W 103°23'35.81"	9.63	220.92
SHL	2,567.00	0.15	55.24	2,566.93	7.26	-7.20	-6.28	-912.27	0.24	456,864.27	831,946.93	N 32°15'8.99"	W 103°23'35.81"	9.55	221.10
	2,662.00	0.14	103.47	2,661.93	7.21	-7.15	-6.06	-817.27	0.13	456,864.32	831,947.15	N 32°15'8.99"	W 103°23'35.81"	9.38	220.29
	2,757.00	0.14	192.42	2,756.93	7.35	-7.29	-5.97	-722.27	0.21	456,864.18	831,947.24	N 32°15'8.99"	W 103°23'35.81"	9.43	219.33
	2,852.00	0.13	323.84	2,851.93	7.38	-7.32	-6.06	-627.27	0.26	456,864.15	831,947.15	N 32°15'8.99"	W 103°23'35.81"	9.50	219.64
	2,947.00	0.13	75.70	2,946.93	7.26	-7.21	-6.02	-532.27	0.23	456,864.26	831,947.19	N 32°15'8.99"	W 103°23'35.81"	9.39	219.89
	3,042.00	0.17	41.37	3,041.93	7.13	-7.07	-5.83	-437.27	0.10	456,864.40	831,947.38	N 32°15'8.99"	W 103°23'35.80"	9.16	219.47
	3,137.00	0.08	239.45	3,136.93	7.06	-7.00	-5.79	-342.27	0.26	456,864.47	831,947.42	N 32°15'8.99"	W 103°23'35.80"	9.08	219.59
	3,231.00	0.17	53.14	3,230.93	7.00	-6.95	-5.73	-248.27	0.27	456,864.52	831,947.48	N 32°15'8.99"	W 103°23'35.80"	9.01	219.52
	3,326.00	0.10	189.73	3,325.93	7.00	-6.95	-5.64	-153.27	0.27	456,864.52	831,947.57	N 32°15'8.99"	W 103°23'35.80"	8.95	219.04
	3,421.00	0.24	231.16	3,420.93	7.21	-7.15	-5.80	-58.27	0.19	456,864.32	831,947.41	N 32°15'8.99"	W 103°23'35.80"	9.21	219.05
	3,516.00	0.13	128.02	3,515.93	7.40	-7.35	-5.87	36.73	0.31	456,864.12	831,947.34	N 32°15'8.99"	W 103°23'35.80"	9.41	218.65
	3,611.00	0.12	7.62	3,610.93	7.37	-7.31	-5.78	131.73	0.23	456,864.16	831,947.43	N 32°15'8.99"	W 103°23'35.80"	9.32	218.30
	3,706.00	0.16	123.21	3,705.93	7.34	-7.29	-5.65	226.73	0.25	456,864.18	831,947.56	N 32°15'8.99"	W 103°23'35.80"	9.22	217.80
	3,800.00	0.16	60.79	3,799.93	7.35	-7.30	-5.43	320.73	0.18	456,864.17	831,947.78	N 32°15'8.99"	W 103°23'35.80"	9.09	216.65
	3,895.00	0.15	86.39	3,894.93	7.27	-7.22	-5.19	415.73	0.07	456,864.25	831,948.02	N 32°15'8.99"	W 103°23'35.80"	8.89	215.69
	3,990.00	0.23	53.76	3,989.93	7.15	-7.10	-4.91	510.73	0.14	456,864.37	831,948.30	N 32°15'8.99"	W 103°23'35.79"	8.63	214.66
	4,085.00	0.10	144.12	4,084.93	7.10	-7.06	-4.71	605.73	0.26	456,864.41	831,948.50	N 32°15'8.99"	W 103°23'35.79"	8.48	213.71
	4,179.00	0.22	125.23	4,178.93	7.27	-7.23	-4.51	699.73	0.14	456,864.24	831,948.70	N 32°15'8.99"	W 103°23'35.79"	8.52	211.98
	4,274.00	0.13	200.62	4,273.93	7.47	-7.43	-4.40	794.73	0.24	456,864.04	831,948.81	N 32°15'8.99"	W 103°23'35.79"	8.64	210.63
	4,369.00	0.27	143.03	4,368.92	7.75	-7.71	-4.30	889.72	0.24	456,863.76	831,948.91	N 32°15'8.99"	W 103°23'35.79"	8.83	209.16
	4,464.00	0.22	121.43	4,463.92	8.02	-7.99	-4.01	984.72	0.11	456,863.48	831,949.20	N 32°15'8.98"	W 103°23'35.78"	8.94	206.68
	4,558.00	0.25	46.20	4,557.92	7.97	-7.94	-3.71	1,078.72	0.31	456,863.53	831,949.50	N 32°15'8.98"	W 103°23'35.78"	8.76	205.06
	4,653.00	0.18	72.83	4,652.92	7.78	-7.75	-3.42	1,173.72	0.13	456,863.72	831,949.79	N 32°15'8.99"	W 103°23'35.78"	8.47	203.81
	4,747.00	0.16	90.53	4,746.92	7.74	-7.71	-3.15	1,267.72	0.06	456,863.76	831,950.06	N 32°15'8.99"	W 103°23'35.77"	8.33	202.21
	4,842.00	0.04	315.95	4,841.92	7.71	-7.69	-3.04	1,362.72	0.20	456,863.78	831,950.17	N 32°15'8.99"	W 103°23'35.77"	8.27	201.57
	4,937.00	0.21	344.08	4,936.92	7.52	-7.50	-3.11	1,457.72	0.18	456,863.97	831,950.10	N 32°15'8.99"	W 103°23'35.77"	8.11	202.53
	5,031.00	0.07	358.05</												

Actual KOP	8,724.00	9.24	337.31	8,693.04	-347.47	349.09	-169.89	5,213.84	0.58	457,220.57	831,783.32	N 32°15'12.53"	W 103°23'37.68"	388.24	334.05
	8,819.00	7.58	342.64	8,787.02	-360.44	362.11	-174.70	5,307.82	1.93	457,233.58	831,778.51	N 32°15'12.66"	W 103°23'37.73"	402.05	334.25
	8,914.00	5.29	342.53	8,881.41	-370.57	372.27	-177.88	5,402.21	2.41	457,243.74	831,775.32	N 32°15'12.76"	W 103°23'37.77"	412.59	334.46
	9,008.00	3.49	344.14	8,975.13	-377.43	379.16	-179.97	5,495.93	1.92	457,250.63	831,773.24	N 32°15'12.83"	W 103°23'37.79"	419.70	334.61
	9,102.00	1.66	349.10	9,069.03	-381.51	383.25	-181.01	5,589.83	1.96	457,254.72	831,772.20	N 32°15'12.87"	W 103°23'37.80"	423.84	334.72
	9,197.00	0.73	74.03	9,164.02	-383.03	384.77	-180.69	5,684.82	1.85	457,256.24	831,772.52	N 32°15'12.89"	W 103°23'37.80"	425.08	334.85
	9,293.00	0.61	127.37	9,260.01	-382.90	384.62	-179.69	5,780.81	0.64	457,256.10	831,773.52	N 32°15'12.88"	W 103°23'37.79"	424.53	334.96
	9,388.00	0.13	72.18	9,355.01	-382.63	384.35	-179.19	5,875.81	0.58	457,255.82	831,774.02	N 32°15'12.88"	W 103°23'37.78"	424.07	335.00
	9,483.00	0.29	55.76	9,450.01	-382.80	384.52	-178.89	5,970.81	0.18	457,255.99	831,774.32	N 32°15'12.88"	W 103°23'37.78"	424.09	335.05
	9,578.00	0.16	352.44	9,545.01	-383.07	384.78	-178.70	6,065.81	0.27	457,256.26	831,774.51	N 32°15'12.89"	W 103°23'37.78"	424.26	335.09
	9,672.00	0.11	83.24	9,639.01	-383.21	384.93	-178.63	6,159.81	0.21	457,256.40	831,774.58	N 32°15'12.89"	W 103°23'37.78"	424.35	335.11
	9,767.00	0.05	67.44	9,734.01	-383.24	384.95	-178.50	6,254.81	0.07	457,256.42	831,774.71	N 32°15'12.89"	W 103°23'37.77"	424.32	335.12
	9,862.00	0.06	323.03	9,829.01	-383.30	385.01	-178.49	6,349.81	0.09	457,256.48	831,774.71	N 32°15'12.89"	W 103°23'37.77"	424.37	335.13
	9,957.00	0.05	340.49	9,924.01	-383.37	385.09	-178.54	6,444.81	0.02	457,256.56	831,774.67	N 32°15'12.89"	W 103°23'37.78"	424.46	335.13
	10,052.00	0.07	236.14	10,019.01	-383.38	385.09	-178.60	6,539.81	0.10	457,256.56	831,774.61	N 32°15'12.89"	W 103°23'37.78"	424.49	335.12
	10,147.00	0.09	151.55	10,114.01	-383.28	385.00	-178.61	6,634.81	0.11	457,256.47	831,774.60	N 32°15'12.89"	W 103°23'37.78"	424.41	335.11
	10,242.00	0.11	43.95	10,209.01	-383.28	385.00	-178.51	6,729.81	0.17	457,256.47	831,774.70	N 32°15'12.89"	W 103°23'37.77"	424.37	335.12
	10,337.00	0.08	247.68	10,304.01	-383.32	385.04	-178.51	6,824.81	0.20	457,256.51	831,774.70	N 32°15'12.89"	W 103°23'37.77"	424.40	335.13
	10,431.00	0.01	182.70	10,398.01	-383.29	385.00	-178.57	6,918.81	0.08	457,256.47	831,774.64	N 32°15'12.89"	W 103°23'37.78"	424.40	335.12
	10,526.00	0.09	9.43	10,493.01	-383.35	385.07	-178.56	7,013.81	0.11	457,256.54	831,774.65	N 32°15'12.89"	W 103°23'37.78"	424.45	335.12
	10,621.00	0.13	300.04	10,588.01	-383.48	385.20	-178.64	7,108.81	0.14	457,256.67	831,774.57	N 32°15'12.89"	W 103°23'37.78"	424.60	335.12
	10,716.00	0.12	280.77	10,683.01	-383.55	385.27	-178.83	7,203.81	0.05	457,256.74	831,774.38	N 32°15'12.89"	W 103°23'37.78"	424.75	335.10
	10,811.00	0.36	263.73	10,778.01	-383.53	385.25	-179.23	7,298.81	0.26	457,256.73	831,773.98	N 32°15'12.89"	W 103°23'37.78"	424.90	335.05
	10,906.00	0.51	292.50	10,873.00	-383.66	385.38	-179.92	7,393.80	0.27	457,256.85	831,773.29	N 32°15'12.89"	W 103°23'37.79"	425.31	334.97
	11,001.00	0.21	216.01	10,968.00	-383.67	385.40	-180.41	7,488.80	0.53	457,256.88	831,772.80	N 32°15'12.89"	W 103°23'37.80"	425.54	334.92
11,059.00	0.70	238.27	11,026.00	-383.40	385.13	-180.77	7,546.80	0.88	457,256.60	831,772.44	N 32°15'12.89"	W 103°23'37.80"	425.45	334.86	
11,125.00	1.45	214.96	11,091.99	-382.49	384.24	-181.59	7,612.79	1.29	457,255.71	831,771.62	N 32°15'12.88"	W 103°23'37.81"	424.99	334.70	
11,139.00	2.79	202.66	11,105.98	-382.03	383.78	-181.83	7,626.78	10.02	457,255.25	831,771.38	N 32°15'12.88"	W 103°23'37.81"	424.67	334.65	
11,220.00	10.85	193.15	11,186.34	-372.75	374.52	-184.32	7,707.14	10.02	457,245.99	831,768.89	N 32°15'12.78"	W 103°23'37.84"	417.42	333.80	
FTP / 100ft FNL Cross	11,226.00	11.07	192.73	11,192.23	-371.64	373.41	-184.58	7,713.03	3.88	457,244.88	831,768.63	N 32°15'12.77"	W 103°23'37.85"	416.54	333.70
	11,314.00	14.33	188.08	11,278.07	-352.58	354.38	-187.97	7,798.87	3.88	457,225.85	831,765.24	N 32°15'12.59"	W 103°23'37.89"	401.15	332.06
	11,409.00	26.26	179.06	11,367.03	-319.79	321.60	-189.28	7,887.83	12.95	457,193.07	831,763.92	N 32°15'12.26"	W 103°23'37.91"	373.17	329.52
	11,504.00	35.62	179.10	11,448.42	-271.02	272.82	-188.50	7,969.22	9.85	457,144.29	831,764.71	N 32°15'11.78"	W 103°23'37.90"	331.61	325.36
	11,599.00	44.00	177.29	11,521.34	-210.31	212.09	-186.51	8,042.14	8.90	457,083.56	831,766.70	N 32°15'11.18"	W 103°23'37.89"	282.43	318.67
	11,694.00	47.42	176.72	11,587.67	-142.45	144.19	-182.94	8,108.47	3.63	457,015.66	831,770.27	N 32°15'10.51"	W 103°23'37.85"	232.94	308.24
	11,788.00	50.86	176.30	11,649.15	-71.54	73.24	-178.61	8,169.95	3.68	456,944.71	831,774.60	N 32°15'9.80"	W 103°23'37.81"	193.04	292.30
	11,883.00	59.86	178.99	11,703.10	6.43	-4.77	-175.50	8,223.90	9.75	456,866.70	831,777.71	N 32°15'9.03"	W 103°23'37.78"	175.57	268.44
	11,978.00	73.04	180.29	11,740.98	93.31	-91.66	-175.00	8,261.78	13.93	456,779.81	831,778.21	N 32°15'8.17"	W 103°23'37.78"	197.55	242.36
	12,073.00	78.34	181.62	11,764.45	185.33	-183.66	-176.55	8,285.25	5.74	456,687.81	831,776.66	N 32°15'7.26"	W 103°23'37.81"	254.76	223.87
	12,167.00	83.36	181.65	11,779.39	278.09	-276.40	-179.20	8,300.19	5.34	456,595.07	831,774.01	N 32°15'6.34"	W 103°23'37.85"	329.40	212.96
	12,262.00	93.86	183.62	11,781.70	372.86	-371.13	-183.56	8,302.50	11.24	456,500.34	831,769.65	N 32°15'5.41"	W 103°23'37.91"	414.05	206.32
	12,339.00	94.85	184.01	11,775.85	449.51	-447.74	-188.67	8,296.65	1.38	456,423.73	831,764.54	N 32°15'4.65"	W 103°23'37.98"	485.87	202.82

	19,929.00	86.85	181.54	11,936.82	8,031.63	-8,031.03	-101.36	8,457.62	0.07	448,840.41	831,851.85	N 32°13'49.61"	W 103°23'37.73"	8,031.67	180.72
	20,023.00	87.51	180.32	11,941.45	8,125.51	-8,124.90	-102.89	8,462.25	1.47	448,746.54	831,850.32	N 32°13'48.68"	W 103°23'37.76"	8,125.55	180.73
	20,118.00	87.08	180.22	11,945.93	8,220.40	-8,219.79	-103.33	8,466.73	0.46	448,651.65	831,849.88	N 32°13'47.74"	W 103°23'37.78"	8,220.44	180.72
	20,213.00	88.10	180.61	11,949.93	8,315.32	-8,314.70	-104.02	8,470.73	1.15	448,556.73	831,849.19	N 32°13'46.80"	W 103°23'37.79"	8,315.35	180.72
	20,308.00	86.77	179.04	11,954.18	8,410.21	-8,409.60	-103.73	8,474.98	2.16	448,461.83	831,849.48	N 32°13'45.86"	W 103°23'37.80"	8,410.24	180.71
	20,403.00	85.83	178.98	11,960.31	8,504.98	-8,504.39	-102.09	8,481.11	0.99	448,367.05	831,851.12	N 32°13'44.92"	W 103°23'37.79"	8,505.00	180.69
	20,498.00	85.36	178.88	11,967.61	8,599.66	-8,599.09	-100.32	8,488.41	0.51	448,272.34	831,852.89	N 32°13'43.99"	W 103°23'37.78"	8,599.68	180.67
	20,593.00	85.28	178.73	11,975.36	8,694.30	-8,693.76	-98.35	8,496.16	0.18	448,177.68	831,854.86	N 32°13'43.05"	W 103°23'37.77"	8,694.31	180.65
	20,687.00	85.42	179.11	11,982.98	8,787.95	-8,787.43	-96.58	8,503.78	0.43	448,084.01	831,856.63	N 32°13'42.12"	W 103°23'37.76"	8,787.96	180.63
	20,782.00	82.42	179.14	11,993.04	8,882.38	-8,881.87	-95.14	8,513.84	3.16	447,989.56	831,858.07	N 32°13'41.19"	W 103°23'37.75"	8,882.38	180.61
	20,878.00	82.41	179.74	12,005.71	8,977.52	-8,977.03	-94.21	8,526.51	0.62	447,894.41	831,859.00	N 32°13'40.25"	W 103°23'37.75"	8,977.52	180.60
	20,973.00	82.14	179.56	12,018.48	9,071.64	-9,071.16	-93.64	8,539.28	0.34	447,800.27	831,859.57	N 32°13'39.31"	W 103°23'37.75"	9,071.65	180.59
	21,069.00	81.93	179.71	12,031.78	9,166.71	-9,166.24	-93.03	8,552.58	0.27	447,705.20	831,860.18	N 32°13'38.37"	W 103°23'37.75"	9,166.71	180.58
	21,164.00	82.20	181.21	12,044.90	9,260.79	-9,260.32	-93.79	8,565.70	1.59	447,611.11	831,859.42	N 32°13'37.44"	W 103°23'37.77"	9,260.79	180.58
	21,259.00	82.52	181.56	12,057.53	9,354.94	-9,354.45	-96.06	8,578.33	0.50	447,516.99	831,857.15	N 32°13'36.51"	W 103°23'37.81"	9,354.94	180.59
	21,354.00	83.56	181.43	12,069.04	9,449.23	-9,448.72	-98.52	8,589.84	1.10	447,422.72	831,854.69	N 32°13'35.58"	W 103°23'37.85"	9,449.23	180.60
	21,448.00	82.62	180.39	12,080.35	9,542.54	-9,542.02	-100.01	8,601.15	1.49	447,329.41	831,853.20	N 32°13'34.66"	W 103°23'37.87"	9,542.54	180.60
	21,543.00	82.04	180.43	12,093.03	9,636.69	-9,636.17	-100.68	8,613.83	0.61	447,235.27	831,852.53	N 32°13'33.72"	W 103°23'37.89"	9,636.69	180.60
	21,638.00	82.94	180.12	12,105.44	9,730.87	-9,730.35	-101.13	8,626.24	1.00	447,141.08	831,852.08	N 32°13'32.79"	W 103°23'37.90"	9,730.87	180.60
	21,733.00	82.75	178.82	12,117.28	9,825.11	-9,824.60	-100.26	8,638.08	1.37	447,046.83	831,852.95	N 32°13'31.86"	W 103°23'37.90"	9,825.11	180.58
	21,827.00	82.98	178.44	12,128.95	9,918.33	-9,917.85	-98.03	8,649.75	0.47	446,953.58	831,855.18	N 32°13'30.94"	W 103°23'37.89"	9,918.33	180.57
LTP / 100 ft FSL Cross	21,900.00	86.46	179.08	12,135.67	9,990.98	-9,990.51	-96.46	8,656.47	4.85	446,880.92	831,856.75	N 32°13'30.22"	W 103°23'37.88"	9,990.98	180.55
Final Survey	21,922.00	87.51	179.27	12,136.83	10,012.94	-10,012.48	-96.14	8,657.63	4.85	446,858.96	831,857.07	N 32°13'30.00"	W 103°23'37.87"	10,012.94	180.55
Projection to Total Depth	21,969.00	87.51	179.27	12,138.87	10,059.88	-10,059.43	-95.54	8,659.67	0.00	446,812.00	831,857.67	N 32°13'29.54"	W 103°23'37.87"	10,059.88	180.54

Survey Type: DefinitiveSurvey

Survey Error Model: ISCWSA0 2.795 sigma
Survey Program:

Description	Part	MD From (ft)	MD To (ft)	EOU Freq (ft)	Expected Max Inclination (deg)	Survey Tool Code	Borehole / Survey
	1	0.000	1,056.000	Act Stns		A005Mb_MWD+IFR1	Maltese 5-8 Fed Com 35H / Maltese 5-8 Fed Com 35H IFR1 to 21969ft
	1	1,056.000	9,197.000	Act Stns		A010Mb_MWD+IFR1+SAG+MS	Maltese 5-8 Fed Com 35H / Maltese 5-8 Fed Com 35H IFR1 to 21969ft
	1	9,197.000	9,767.000	Act Stns		A005Mb_MWD+IFR1	Maltese 5-8 Fed Com 35H / Maltese 5-8 Fed Com 35H IFR1 to 21969ft
	1	9,767.000	21,969.000	Act Stns		A010Mb_MWD+IFR1+SAG+MS	Maltese 5-8 Fed Com 35H / Maltese 5-8 Fed Com 35H IFR1 to 21969ft

EOU Geometry:

End MD (ft)	Hole Size (in)	Casing Size (in)	Name
21,969.000	26.400	26.400	

Intent ☐ As Drilled ☒

API # 30-025-48978		
Operator Name: Oxy USA Inc.	Property Name: Maltese 5 8 Fed Com	Well Number 35H

Kick Off Point (KOP)

UL 3	Section 5	Township 24S	Range 35E	Lot	Feet 90	From N/S North	Feet 1332	From E/W West	County Lea
Latitude 32.253577					Longitude -103.393837			NAD Nad83	

First Take Point (FTP)

UL 3	Section 5	Township 24S	Range 35E	Lot	Feet 591	From N/S North	Feet 1333	From E/W West	County Lea
Latitude 32.252198					Longitude -103.393831			NAD Nad83	

Last Take Point (LTP)

UL M	Section 8	Township 24S	Range 35E	Lot	Feet 210	From N/S South	Feet 1301	From E/W West	County Lea
Latitude 32.225361					Longitude -103.393859			NAD Nad83	

Is this well the defining well for the Horizontal Spacing Unit? ☐ NoIs this well an infill well? ☐

If infill is yes please provide API if available, Operator Name and well number for Defining well for Horizontal Spacing Unit.

API #		
Operator Name:	Property Name:	Well Number

KZ 06/29/2018

Well Name: MALTESE 5_8 FEDERAL COM	Well Location: T24S / R35E / SEC 5 / NENW /	County or Parish/State:
Well Number: 35H	Type of Well: OIL WELL	Allottee or Tribe Name:
Lease Number: NMNM14164	Unit or CA Name:	Unit or CA Number:
US Well Number: 3002548978	Well Status: Producing Oil Well	Operator: OXY USA INCORPORATED

Subsequent Report

Sundry ID: 2761258

Type of Submission: Subsequent Report	Type of Action: Hydraulic Fracturing
Date Sundry Submitted: 11/13/2023	Time Sundry Submitted: 11:01
Date Operation Actually Began: 10/03/2023	

Actual Procedure: RUPU 10/03/2023, RIH & Clean out to PBTD 21925'. Test production casing to 7700 psi for 30 min. RIH and Perf from 12005'-21790', total 2376 holes, 0.42". Frac in 39 stages with 26,618,180 #'s sand and 484,631 bbls produced water, 8,348 bbls brackish water, RD Frac and well ready to produce on 10/31/2023. OXY USA Inc. requests a tubing exception while continuing to flow back this well. The estimated date of tubing install is 1/31/2024.

Well Name: MALTESE 5_8 FEDERAL COM	Well Location: T24S / R35E / SEC 5 / NENW /	County or Parish/State:
Well Number: 35H	Type of Well: OIL WELL	Allottee or Tribe Name:
Lease Number: NMNM14164	Unit or CA Name:	Unit or CA Number:
US Well Number: 3002548978	Well Status: Producing Oil Well	Operator: OXY USA INCORPORATED

Operator

I certify that the foregoing is true and correct. Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction. Electronic submission of Sundry Notices through this system satisfies regulations requiring a

Operator Electronic Signature: SARAH MCKINNEY

Signed on: NOV 13, 2023 11:01 AM

Name: OXY USA INCORPORATED

Title: Regulatory Analyst Sr

Street Address: 5 GREENWAY PLAZA SUITE 110

City: HOUSTON **State:** TX

Phone: (713) 215-7295

Email address: SARAH_MCKINNEY@OXY.COM

Field

Representative Name:

Street Address:

City: **State:** **Zip:**

Phone:

Email address:

BLM Point of Contact

BLM POC Name: JONATHON W SHEPARD

BLM POC Title: Petroleum Engineer

BLM POC Phone: 5752345972

BLM POC Email Address: jshepard@blm.gov

Disposition: Accepted

Disposition Date: 12/14/2023

Signature: Jonathon Shepard

Submit To Appropriate District Office Two Copies <u>District I</u> 1625 N. French Dr., Hobbs, NM 88240 <u>District II</u> 811 S. First St., Artesia, NM 88210 <u>District III</u> 1000 Rio Brazos Rd., Aztec, NM 87410 <u>District IV</u> 1220 S. St. Francis Dr., Santa Fe, NM 87505		State of New Mexico Energy, Minerals and Natural Resources Oil Conservation Division 1220 South St. Francis Dr. Santa Fe, NM 87505				Form C-105 Revised April 3, 2017				
		1. WELL API NO. 30-025-48978								
		2. Type of Lease ☐ STATE ☐ FEE ☒ FED/INDIAN								
		3. State Oil & Gas Lease No.								
WELL COMPLETION OR RECOMPLETION REPORT AND LOG										
4. Reason for filing: ☒ COMPLETION REPORT (Fill in boxes #1 through #31 for State and Fee wells only) ☐ C-144 CLOSURE ATTACHMENT (Fill in boxes #1 through #9, #15 Date Rig Released and #32 and/or #33; attach this and the plat to the C-144 closure report in accordance with 19.15.17.13.K NMAC)						5. Lease Name or Unit Agreement Name Maltese 5 8 Fed COM				
						6. Well Number: 35H				
7. Type of Completion: ☒ NEW WELL ☐ WORKOVER ☐ DEEPENING ☐ PLUGBACK ☐ DIFFERENT RESERVOIR ☐ OTHER _____										
8. Name of Operator OXY USA INC.						9. OGRID 16696				
10. Address of Operator PO Box 50250, MIDLAND, TX 79710						11. Pool name or Wildcat Antelope Ridge; Wolfcamp				
12. Location	Unit Ltr	Section	Township	Range	Lot	Feet from the	N/S Line	Feet from the	E/W Line	County
Surface:	3	5	24S	35E		475	North	1510	West	Lea
BH:	M	8	24S	35E		31	South	1303	West	Lea
13. Date Spudded 06/25/2023	14. Date T.D. Reached 8/17/2023		15. Date Rig Released 8/19/2023			16. Date Completed (Ready to Produce) 10/31/2023		17. Elevations (DF and RKB, RT, GR, etc.)		3454' GR
18. Total Measured Depth of Well			19. Plug Back Measured Depth 21926' MD, 12137' TVD			20. Was Directional Survey Made? Yes		21. Type Electric and Other Logs Run CBL/GAMMA		
22. Producing Interval(s), of this completion - Top, Bottom, Name 12005'-21790', Wolfcamp										
23. CASING RECORD (Report all strings set in well)										
CASING SIZE		WEIGHT LB./FT.		DEPTH SET		HOLE SIZE		CEMENTING RECORD		AMOUNT PULLED
13 3/8"		54.5# J-55		1132'		17 1/2"		1193 sx - TOC 0'		
7 5/8"		26.4# HCL80		11074'		12 1/4"		6209 sx - TOC 0'		
5 1/2"		20# P110		21949'		6 3/4"		780 sx - est.TOC 10783'		
24. LINER RECORD										25. TUBING RECORD
SIZE	TOP	BOTTOM	SACKS CEMENT	SCREEN	SIZE	DEPTH SET		PACKER SET		
26. Perforation record (interval, size, and number) 12005'-21790', 0.42, 2376 holes					27. ACID, SHOT, FRACTURE, CEMENT, SQUEEZE, ETC.					
					DEPTH INTERVAL		AMOUNT AND KIND MATERIAL USED			
					12005'-21790'		484,631 bbls produced water, 8348 bbls			
							brackish water, 26,618,180 #'s sand.			
28. PRODUCTION										
Date First Production 11/26/2023		Production Method (<i>Flowing, gas lift, pumping - Size and type pump</i>) Flowing				Well Status (<i>Prod. or Shut-in</i>) Producing				
Date of Test 12/04/2023	Hours Tested 24 hours	Choke Size 0	Prod'n For Test Period	Oil - Bbl 3273	Gas - MCF 3032	Water - Bbl. 5251	Gas - Oil Ratio 926			
Flow Tubing Press.	Casing Pressure 1275	Calculated 24-Hour Rate	Oil - Bbl. 3273	Gas - MCF 3032	Water - Bbl. 5251	Oil Gravity - API - (<i>Corr.</i>)				
29. Disposition of Gas (<i>Sold, used for fuel, vented, etc.</i>) Sold							30. Test Witnessed By			
31. List Attachments C104c, C102, WBD, Directional Survey, CBL										
32. If a temporary pit was used at the well, attach a plat with the location of the temporary pit.							33. Rig Release Date:			
34. If an on-site burial was used at the well, report the exact location of the on-site burial:										
Latitude _____ Longitude _____ NAD83										
I hereby certify that the information shown on both sides of this form is true and complete to the best of my knowledge and belief										
Signature 		Printed Name Sarah McKinney		Title Regulatory Analyst Sr.		Date 01/08/2024				
E-mail Address sarah_mckinney@oxy.com										

This form is to be filed with the appropriate District Office of the Division not later than 20 days after the completion of any newly-drilled or deepened well and not later than 60 days after completion of closure. When submitted as a completion report, this shall be accompanied by one copy of all electrical and radio-activity logs run on the well and a summary of all special tests conducted, including drill stem tests. All depths reported shall be measured depths. In the case of directionally drilled wells, true vertical depths shall also be reported. For multiple completions, items 11, 12 and 26-31 shall be reported for each zone.

Southeastern New Mexico		Northwestern New Mexico	
T. Rustler 831'	T. Bell Canyon	T. Ojo Alamo	T. Penn A"
T. Salado 1188'	T. Strawn	T. Kirtland	T. Penn. "B"
T. Castile 4011'	T. Atoka	T. Fruitland	T. Penn. "C"
T. Delaware 5231'	T. Miss	T. Pictured Cliffs	T. Penn. "D"
T. Cherry Canyon 6224'	T. Devonian	T. Cliff House	T. Leadville
T. Brushy Canyon 7549'	T. Silurian	T. Menefee	T. Madison
T. Grayburg	T. Montoya	T. Point Lookout	T. Elbert
T. San Andres	T. Simpson	T. Mancos	T. McCracken
T. Glorieta	T. McKee	T. Gallup	T. Ignacio Otzte
T. Paddock	T. Ellenburger	Base Greenhorn	T. Granite
T. Blinebry	T. Gr. Wash	T. Dakota	
T. Tubb	T. Delaware Sand	T. Morrison	
T. Drinkard	T. Bone Springs 8889'	T. Todilto	
T. Abo	T. 1 st Bone Springs 9998'	T. Entrada	
T. Wolfcamp	T. 2 nd Bone Springs 10448'	T. Wingate	
T. Penn	T. 3 rd Bone Springs 11548'	T. Chinle	
T. Cisco (Bough C)	T. Wolfcamp 12074'	T. Permian	

No. 1, from.....to.....

No. 2, from.....to.....

No. 3, from.....to.....


No. 4, from.....to.....

Include data on rate of water inflow and elevation to which water rose in hole.

No. 1, from.....to.....feet.....
 No. 2, from.....to.....feet.....
 No. 3, from.....to.....feet.....

From	To	Thickness In Feet	Lithology

OXY USA Inc.
Maltese 5 8 Fed Com 35H
API No. 30-025-48978



Perfs @ 12005'-21790' TD- 21969' MD; 12139' TVD

District I
1625 N. French Dr., Hobbs, NM 88240
Phone:(575) 393-6161 Fax:(575) 393-0720
District II
811 S. First St., Artesia, NM 88210
Phone:(575) 748-1283 Fax:(575) 748-9720
District III
1000 Rio Brazos Rd., Aztec, NM 87410
Phone:(505) 334-6178 Fax:(505) 334-6170
District IV
1220 S. St Francis Dr., Santa Fe, NM 87505
Phone:(505) 476-3470 Fax:(505) 476-3462

State of New Mexico
Energy, Minerals and Natural Resources
Oil Conservation Division
1220 S. St Francis Dr.
Santa Fe, NM 87505

ACKNOWLEDGMENTS

Action 336357

ACKNOWLEDGMENTS

Operator: OXY USA INC P.O. Box 4294 Houston, TX 772104294	OGRID: 16696
	Action Number: 336357
	Action Type: [C-104] Completion Packet (C-104C)

ACKNOWLEDGMENTS

☒	I hereby certify that the required Water Use Report has been, or will be, submitted for this wells completion.
☒	I hereby certify that the required FracFocus disclosure has been, or will be, submitted for this wells completion.

District I
1625 N. French Dr., Hobbs, NM 88240
Phone:(575) 393-6161 Fax:(575) 393-0720
District II
811 S. First St., Artesia, NM 88210
Phone:(575) 748-1283 Fax:(575) 748-9720
District III
1000 Rio Brazos Rd., Aztec, NM 87410
Phone:(505) 334-6178 Fax:(505) 334-6170
District IV
1220 S. St Francis Dr., Santa Fe, NM 87505
Phone:(505) 476-3470 Fax:(505) 476-3462

State of New Mexico
Energy, Minerals and Natural Resources
Oil Conservation Division
1220 S. St Francis Dr.
Santa Fe, NM 87505

CONDITIONS

Action 336357

CONDITIONS

Operator: OXY USA INC P.O. Box 4294 Houston, TX 772104294	OGRID: 16696
	Action Number: 336357
	Action Type: [C-104] Completion Packet (C-104C)

CONDITIONS

Created By	Condition	Condition Date
plmartinez	File 3160-4 Completion Report within 10 days of BLM approval.	4/23/2024