

U.S. Department of the Interior BUREAU OF LAND MANAGEMENT

Sundry Print Report
05/13/2024

Well Name: SAN JUAN 28-6 UNIT Well Location: T28N / R6W / SEC 19 /

NENW / 36.650406 / -107.510593

County or Parish/State: RIO

ARRIBA / NM

Well Number: 159F

Type of Well: CONVENTIONAL GAS

WELL

Allottee or Tribe Name:

Lease Number: NMSF080430B

Unit or CA Name: SAN JUAN 28-6

UNIT--DK

Unit or CA Number: NMNM78412C

US Well Number: 3003930251

Operator: HILCORP ENERGY

COMPANY

#### **Notice of Intent**

Sundry ID: 2789491

Type of Submission: Notice of Intent

Type of Action: Recompletion

Date Sundry Submitted: 05/10/2024

Time Sundry Submitted: 08:49

Date proposed operation will begin: 05/15/2024

**Procedure Description:** Revised NOI: Hilcorp Energy Company requests permission to recomplete the subject well in the Mesaverde formation and downhole commingle with the existing Dakota formation. Please see the attached procedure, current and proposed wellbore diagram, plat and natural gas management plan. A closed loop system will be used. Hilcorp will contact the FFO Surface group within 90 days after the well has been recompleted, before any interim reclamation work, to conduct the onsite. A reclamation plan will be submitted after the onsite. \*\*Revised MV perf range 5047' - 6077'.

#### **Surface Disturbance**

Is any additional surface disturbance proposed?: No

#### **NOI Attachments**

#### **Procedure Description**

San\_Juan\_28\_6\_Unit\_159F\_MV\_Rev2\_20240510090624.pdf

Well Name: SAN JUAN 28-6 UNIT Well Location: T28N / R6W / SEC 19 / County or Parish/State: RIO

NENW / 36.650406 / -107.510593

ARRIBA / NM

Well Number: 159F Type of Well: CONVENTIONAL GAS

WELL

Allottee or Tribe Name:

Lease Number: NMSF080430B

Unit or CA Name: SAN JUAN 28-6

UNIT--DK

Unit or CA Number: NMNM78412C

**US Well Number:** 3003930251

Operator: HILCORP ENERGY

COMPANY

#### Operator

I certify that the foregoing is true and correct. Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction. Electronic submission of Sundry Notices through this system satisfies regulations requiring a

Operator Electronic Signature: CHERYLENE WESTON Signed on: MAY 10, 2024 09:06 AM

Name: HILCORP ENERGY COMPANY

Title: Operations/Regulatory Tech - Sr

Street Address: 1111 TRAVIS STREET

City: HOUSTON State: TX

Phone: (713) 289-2615

Email address: CWESTON@HILCORP.COM

#### **Field**

Representative Name:

Street Address:

City: State: Zip:

Phone:

Email address:

#### **BLM Point of Contact**

BLM POC Name: MATTHEW H KADE BLM POC Title: Petroleum Engineer

BLM POC Phone: 5055647736 BLM POC Email Address: MKADE@BLM.GOV

**Disposition:** Approved **Disposition Date:** 05/13/2024

Signature: Matthew Kade



## San Juan 28-6 Unit 159F RECOMPLETION SUNDRY

Prepared by:	Matthew Esz
Preparation Date:	May 9, 2024

	WELL INFORMATION						
Well Name:	San Juan 28-6 Unit 159F	State:	NM				
API #:	3003930251	County:					
Area:	10	Location:					
Route:	1008	Latitude:					
Spud Date:	September 4, 2007	Longitude:					

#### PROJECT DESCRIPTION

Perforate, fracture, and comingle the Mesa Verde with the existing Dakota zone.

CONTACTS							
Title	Name	Office Phone #	Cell Phone #				
Engineer	Matthew Esz		770-843-9226				
Area Foreman	Ryan Frost						
Lead							
Artificial Lift Tech							
Operator							




# HILCORP ENERGY COMPANY San Juan 28-6 Unit 159F RECOMPLETION SUNDRY

#### JOB PROCEDURES

- 1. MIRU service rig and associated equipment; test BOP.
- 2. TOOH with 2-3/8" tubing set at 7,765'.
- 3. Set a 4-1/2" plug at +/- 7,633' to isolate the Dakota.
- 4. Will not run CBL, sufficent cement based on CBL from 10/12/2007.
- 5. Load the hole and pressure test the casing.
- 6. N/D BOP, N/U frac stack and pressure test frac stack.
- 7 Perforate and frac Mesa Verde formation from 5047' 6077'.
- 8. Nipple down frac stack, nipple up BOP and test.
- 9. TIH with a mill and drill out top isolation plug and  ${\color{red}{\textbf{Mesa}}}\ {\color{red}{\textbf{Verde}}}$  frac plug.
- 10. Clean out to **Dakota** isolation plug.
- 11. Drill out Dakota isolation plug and cleanout to PBTD at 7,825'. TOOH.
- 12. TIH and land production tubing. Get a commingled **Dakota/Mesa Verde** flow rate.




# HILCORP ENERGY COMPANY San Juan 28-6 Unit 159F RECOMPLETION SUNDRY





# HILCORP ENERGY COMPANY San Juan 28-6 Unit 159F RECOMPLETION SUNDRY



Form C-102 August 1, 2011

Permit 364288

#### District I

1625 N. French Dr., Hobbs, NM 88240 Phone:(575) 393-6161 Fax:(575) 393-0720

District II

811 S. First St., Artesia, NM 88210 Phone:(575) 748-1283 Fax:(575) 748-9720 **District III** 

1000 Rio Brazos Rd., Aztec, NM 87410 Phone:(505) 334-6178 Fax:(505) 334-6170 **District IV** 

1220 S. St Francis Dr., Santa Fe, NM 87505 Phone:(505) 476-3470 Fax:(505) 476-3462

# State of New Mexico Energy, Minerals and Natural Resources Oil Conservation Division 1220 S. St Francis Dr. Santa Fe, NM 87505

#### WELL LOCATION AND ACREAGE DEDICATION PLAT

1, API Number 30-039-30251	2, Pool Code 72319	3, Pool Name BLANCO-MESAVERDE (PRORATED GAS)
4. Property Code 318710	5. Property Name SAN JUAN 28 6 UNIT	6. Well No. 159F
7. OGRID No. 372171	8. Operator Name HILCORP ENERGY COMPANY	9. Elevation 6648


#### 10. Surface Location

ſ	UL - Lot		Section	Township	Range		Lot Idn	Feet From	N/S Line	Feet From	E/W Line	County	
		C	19	28	N	06W		1305	N	1535	W	RIO	1
												ARRIBA	

#### 11. Bottom Hole Location If Different From Surface

UL - Lot	Section	Township	Range	Lot <b>Id</b> n	Feet From	N/S Line	Feet From	E/W Line	County
	12. Dedicated Acres 262.76		13. Joint or Infill		14. Consolidatio	n Code		15. Order No.	

#### NO ALLOWABLE WILL BE ASSIGNED TO THIS COMPLETION UNTIL ALL INTERESTS HAVE BEEN CONSOLIDATED OR A NON-STANDARD UNIT HAS BEEN APPROVED BY THE DIVISION



#### **OPERATOR CERTIFICATION**

I hereby certify that the information contained herein is true and complete to the best of my knowledge and belief, and that this organization either owns a working interest or unleased mineral interest in the land including the proposed bottom hole location(s) or has a right to drill this well at this location pursuant to a contract with an owner of such a mineral or working interest, or to a voluntary pooling agreement or a compulsory pooling order heretofore entered by the division.

E-Signed By: Cherylene Weston

Title: Operations/Regulatory Tech-Sr.

Date: 4/22/2024

#### **SURVEYOR CERTIFICATION**

I hereby certify that the well location shown on this plat was plotted from field notes of actual surveys made by me or under my supervision, and that the same is true and correct to the best of my belief.

Surveyed By:

David Russell

Date of Survey:

Certificate Number: 10201

#### State of New Mexico Energy, Minerals and Natural Resources Department

Submit Electronically Via E-permitting

Oil Conservation Division 1220 South St. Francis Dr. Santa Fe, NM 87505

## NATURAL GAS MANAGEMENT PLAN

This Natural Gas Management Plan must be submitted with each Application for Permit to Drill (APD) for a new or recompleted well.

#### Section 1 – Plan Description Effective May 25, 2021

I. Operator: Hilcorp E	nergy Compan	У	OGRID:	372171 Date		04 / 22 /2	2024_
II. Type: 🗵 Original [	☐ Amendment	due to □ 19.15.27	7.9.D(6)(a) NMAC	C □ 19.15.27.9.D(	(6)(b) NMAC □	Other.	
If Other, please describe	e:						
III. Well(s): Provide the be recompleted from a s					wells proposed to	be drilled o	or proposed to
Well Name	API	ULSTR	Footages	Anticipated Oil BBL/D	Anticipated Gas MCF/D	Produc	cipated ced Water BL/D
SJ 28-6 Unit 159F	3003930251	C-19-28N-06W	1305 FNL, 1535 FW	L 1.1 bbl/d	476 mcf/d	0.5	bbl/d
IV. Central Delivery Point Name: Chaco-Blanco Processing Plant [See 19.15.27.9(D)(1) NMAC]  V. Anticipated Schedule: Provide the following information for each new or recompleted well or set of wells proposed to be drilled or proposed to be recompleted from a single well pad or connected to a central delivery point.							
Well Name	API	Spud Date	TD Reached Date	Completion Commencement			st Production Date
SJ 28-6 Unit 159F	3003930251					20	024
VI. Separation Equipment:   Attach a complete description of how Operator will size separation equipment to optimize gas capture.  VII. Operational Practices:   Attach a complete description of the actions Operator will take to comply with the requirements of Subsection A through F of 19.15.27.8 NMAC.  VIII. Best Management Practices:   Attach a complete description of Operator's best management practices to minimize venting during active and planned maintenance.							

### Section 2 – Enhanced Plan EFFECTIVE APRIL 1, 2022

Beginning April 1, 2022, an operator that is not in compliance with its statewide natural gas capture requirement for the applicable reporting area must complete this section.

🗵 Operator certifies that it is not required to complete this section because Operator is in compliance with its statewide natural gas capture requirement for the applicable reporting area.

#### IX. Anticipated Natural Gas Production:

Well	API	Anticipated Average Natural Gas Rate MCF/D	Anticipated Volume of Natural Gas for the First Year MCF

#### X. Natural Gas Gathering System (NGGS):

Operator	System	ULSTR of Tie-in	Anticipated Gathering Start Date	Available Maximum Daily Capacity of System Segment Tie-in

XI. Map. $\square$ Attach an accurate and legible map depicting the location of the well(s), the anticipated pipeline route(s) connecting the
production operations to the existing or planned interconnect of the natural gas gathering system(s), and the maximum daily capacity of
the segment or portion of the natural gas gathering system(s) to which the well(s) will be connected.

XII. Line Capacity. The natural	gas gathering system	□ will □ will:	not have capacity t	to gather 10	00% of the anticipate	ed natural gas
production volume from the well	prior to the date of firs	st production.				

XIII. Line Pressure. Operator $\Box$ does $\Box$ does not anticipate that its existing well(s) connected to the same segment, or portion, or	of the
natural gas gathering system(s) described above will continue to meet anticipated increases in line pressure caused by the new wel	

$\neg$	Attach One	matan'a mlar	n to monoo	. mno direction	in maamamaa	to the incre	ased line press	~~~
	Affach One	rator's niai	n to manage	e production	in response	to the incre	ased line nress	uire

XIV. Confidentiality: 🗆 O	perator asserts co	nfidentiality pur	suant to Se	ection 71-2-8	NMSA 197	8 for the in	formation p	provided in
Section 2 as provided in Para	graph (2) of Subse	ection D of 19.15	5.27.9 NMA	C, and attach	es a full des	cription of th	ne specific i	nformation
for which confidentiality is as	sserted and the bas	sis for such asser	rtion.					

(h)

(i)

## Section 3 - Certifications <u>Effective May 25, 2021</u>

Operator certifies that, after reasonable inquiry and based on the available information at the time of submittal: 🗵 Operator will be able to connect the well(s) to a natural gas gathering system in the general area with sufficient capacity to transport one hundred percent of the anticipated volume of natural gas produced from the well(s) commencing on the date of first production, taking into account the current and anticipated volumes of produced natural gas from other wells connected to the pipeline gathering system; or ☐ Operator will not be able to connect to a natural gas gathering system in the general area with sufficient capacity to transport one hundred percent of the anticipated volume of natural gas produced from the well(s) commencing on the date of first production, taking into account the current and anticipated volumes of produced natural gas from other wells connected to the pipeline gathering system. If Operator checks this box, Operator will select one of the following: Well Shut-In. ☐ Operator will shut-in and not produce the well until it submits the certification required by Paragraph (4) of Subsection D of 19.15.27.9 NMAC; or Venting and Flaring Plan.  $\square$  Operator has attached a venting and flaring plan that evaluates and selects one or more of the potential alternative beneficial uses for the natural gas until a natural gas gathering system is available, including: power generation on lease; (a) power generation for grid; **(b)** (c) compression on lease; (d) liquids removal on lease; (e) reinjection for underground storage; **(f)** reinjection for temporary storage; reinjection for enhanced oil recovery; **(g)** 

## Section 4 - Notices

1. If, at any time after Operator submits this Natural Gas Management Plan and before the well is spud:

other alternative beneficial uses approved by the division.

fuel cell production; and

- (a) Operator becomes aware that the natural gas gathering system it planned to connect the well(s) to has become unavailable or will not have capacity to transport one hundred percent of the production from the well(s), no later than 20 days after becoming aware of such information, Operator shall submit for OCD's approval a new or revised venting and flaring plan containing the information specified in Paragraph (5) of Subsection D of 19.15.27.9 NMAC; or
- (b) Operator becomes aware that it has, cumulatively for the year, become out of compliance with its baseline natural gas capture rate or natural gas capture requirement, no later than 20 days after becoming aware of such information, Operator shall submit for OCD's approval a new or revised Natural Gas Management Plan for each well it plans to spud during the next 90 days containing the information specified in Paragraph (2) of Subsection D of 19.15.27.9 NMAC, and shall file an update for each Natural Gas Management Plan until Operator is back in compliance with its baseline natural gas capture rate or natural gas capture requirement.
- 2. OCD may deny or conditionally approve an APD if Operator does not make a certification, fails to submit an adequate venting and flaring plan which includes alternative beneficial uses for the anticipated volume of natural gas produced, or if OCD determines that Operator will not have adequate natural gas takeaway capacity at the time a well will be spud.

I certify that, after reasonable inquiry, the statements in and attached to this Natural Gas Management Plan are true and correct to the best of my knowledge and acknowledge that a false statement may be subject to civil and criminal penalties under the Oil and Gas Act.

Signature:	Cherylene Weston
Printed Name:	Cherylene Weston
Title:	Operations/Regulatory Tech-Sr.
E-mail Address:	cweston@hilcorp.com
Date:	4/22/2024
Phone:	713-289-2615
	OIL CONSERVATION DIVISION
	(Only applicable when submitted as a standalone form)
Approved By:	
Title:	
Approval Date:	
Conditions of A <sub>1</sub>	pproval:

#### VI. Separation Equipment:

Hilcorp Energy Company (HEC or Operator) production facilities include separation equipment designed to efficiently separate gas from liquid phases to optimize gas capture based on projected and estimated volumes from the targeted pool of our recomplete project. HEC will utilize flowback separation equipment and production separation equipment designed and built to industry specifications after the recomplete to optimize gas capture and send gas to sales or flare based on analytical composition. HEC operates facilities that are typically one-well facilities. Production separation equipment is upgraded prior to well being completed, if determined to be undersized or inadequate. This equipment is already on-site and tied into our sales gas lines prior to the recomplete operations.

#### VII. Operational Practices:

- 1. Subsection (A) Venting and Flaring of Natural Gas
  - HEC understands the requirements of NMAC 19.15.27.8 which outlines that the venting and flaring of natural gas during drilling, completion or production operations that constitutes waste as defined in 19.15.2 are prohibited.
- 2. Subsection (B) Venting and Flaring during drilling operations
  - This gas capture plan isn't for a well being drilled.
- 3. Subsection (C) Venting and flaring during completion or recompletion
  - Flowlines will be routed for flowback fluids into a completion or storage tank and if feasible under well conditions, flare rather than vent and commence operation of a separator as soon as it is technically feasible for a separator to function.
  - At any point in the well life (completion, production, inactive) an audio, visual and olfactory inspection be performed at prescribed intervals (weekly or monthly) pursuant to Subsection D of 19.15.27.8 NMAC, to confirm that all production equipment is operating properly and there are no leaks or releases.
- 4. Subsection (D) Venting and flaring during production operations
  - At any point in the well life (completion, production, inactive) an audio, visual and olfactory inspection be performed at prescribed intervals (weekly or monthly) pursuant to Subsection D of 19.15.27.8 NMAC, to confirm that all production equipment is operating properly and there are no leaks or releases.
  - Monitor manual liquid unloading for wells on-site or in close proximity (<30 minutes' drive time), take reasonable actions to achieve a stabilized rate and pressure at the earliest practical time, and take reasonable actions to minimize venting to the maximum extent practicable.
  - $\circ$  HEC will not vent or flare except during the approved activities listed in NMAC 19.15.27.8 (D) 1- $\alpha$
- 5. Subsection (E) Performance standards
  - All tanks and separation equipment are designed for maximum throughput and pressure to minimize waste.
  - If a flare is utilized during production operations it will have a continuous pilot and is located more than 100 feet from any known well or storage tanks.
  - At any point in the well life (completion, production, inactive) an audio, visual and olfactory inspection be performed at prescribed intervals (weekly or monthly) pursuant to Subsection D of 19.15.27.8 NMAC, to confirm that all production equipment is operating properly and there are no leaks or releases.

- 6. Subsection (F) Measurement or estimation of vented and flared natural gas
  - Measurement equipment is installed to measure the volume of natural gas flared from process piping.
  - When measurement isn't practicable, estimation of vented and flared natural gas will be completed as noted in 19.15.27.8 (F) 5-6.

#### VIII. Best Management Practices:

- 1. Operator has adequate storage and takeaway capacity for wells it chooses to recomplete as the flowlines at the sites are already in place and tied into a gathering system.
- 2. Operator will flare rather than vent vessel blowdown gas when technically feasible during active and/or planned maintenance to equipment on-site.
- 3. Operator combusts natural gas that would otherwise be vented or flared, when technically feasible.
- 4. Operator will shut in wells in the event of a takeaway disruption, emergency situation, or other operations where venting or flaring may occur due to equipment failures.

District I
1625 N. French Dr., Hobbs, NM 88240
Phone: (575) 393-6161 Fax: (575) 393-0720

District II 811 S. First St., Artesia, NM 88210 Phone:(575) 748-1283 Fax:(575) 748-9720

District III 1000 Rio Brazos Rd., Aztec, NM 87410 Phone:(505) 334-6178 Fax:(505) 334-6170

1220 S. St Francis Dr., Santa Fe, NM 87505 Phone:(505) 476-3470 Fax:(505) 476-3462

**State of New Mexico Energy, Minerals and Natural Resources Oil Conservation Division** 1220 S. St Francis Dr. **Santa Fe, NM 87505** 

CONDITIONS

Action 343778

#### **CONDITIONS**

Operator:	OGRID:
HILCORP ENERGY COMPANY	372171
1111 Travis Street	Action Number:
Houston, TX 77002	343778
	Action Type:
	[C-103] NOI Recompletion (C-103E)

#### CONDITIONS

Created By	Condition	Condition Date
dmcclure	Notify NMOCD 24 Hours Prior to beginning operations.	5/13/2024
dmcclure	DHC required	5/13/2024
dmcclure	All conducted logs shall be submitted to the Division as a [UF-WL] EP Well Log Submission (WellLog).	5/13/2024
dmcclure	The appropriate compliance officer supervisor shall be consulted and remedial action conducted as directed if the cement sheath around the casing is not adequate to protect the casing and isolate strata from: (a) the uppermost perforation in each added pool to at least 150 feet above that perforation; and (b) the lowermost perforation in each added pool to at least 100 feet below that perforation.	5/13/2024