



U.S. Department of the Interior
Bureau of Land Management

Application for Permit to Drill

APD Package Report

Date Printed: 05/10/2024 01:30 PM

APD ID: 10400085709

Well Status: AAPD

APD Received Date: 06/24/2022 07:29 AM

Well Name: LITTLE RASCALS 17/18 WOI

Operator: MEWBOURNE OIL COMPANY

Well Number: 2H

APD Package Report Contents

- Form 3160-3
- Operator Certification Report
- Application Report
- Application Attachments
 - Well Plat: 1 file(s)
- Drilling Plan Report
- Drilling Plan Attachments
 - Blowout Prevention Choke Diagram Attachment: 3 file(s)
 - Blowout Prevention BOP Diagram Attachment: 2 file(s)
 - Casing Taperd String Specs: 2 file(s)
 - Casing Design Assumptions and Worksheet(s): 4 file(s)
 - Hydrogen sulfide drilling operations plan: 1 file(s)
 - Proposed horizontal/directional/multi-lateral plan submission: 2 file(s)
 - Other Facets: 2 file(s)
- SUPO Report
- SUPO Attachments
 - Existing Road Map: 1 file(s)
 - New Road Map: 1 file(s)
 - Attach Well map: 1 file(s)
 - Production Facilities map: 2 file(s)
 - Water source and transportation map: 1 file(s)
 - Construction Materials source location attachment: 1 file(s)
 - Well Site Layout Diagram: 1 file(s)
 - Other SUPO Attachment: 2 file(s)
- PWD Report
- PWD Attachments
 - None

- Bond Report
- Bond Attachments
 - None

Form 3160-3
(June 2015)UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

APPLICATION FOR PERMIT TO DRILL OR REENTER

FORM APPROVED
OMB No. 1004-0137
Expires: January 31, 2018

5. Lease Serial No.

NMNM415688A

6. If Indian, Allottee or Tribe Name

7. If Unit or CA Agreement, Name and No.

8. Lease Name and Well No.

LITTLE RASCALS 17/18 W0IL FED COM

2H

9. API Well No.

30-015-55067

10. Field and Pool, or Exploratory

PURPLE SAGE WOLFACMP/WOLFCAM

11. Sec., T. R. M. or Blk. and Survey or Area

SEC 17/T22S/R28E/NMP

1a. Type of work: ☒ DRILL ☐ REENTER

1b. Type of Well: ☐ Oil Well ☒ Gas Well ☐ Other

1c. Type of Completion: ☐ Hydraulic Fracturing ☒ Single Zone ☐ Multiple Zone

2. Name of Operator
MEWBOURNE OIL COMPANY3a. Address
P O BOX 5270, HOBBS, NM 882413b. Phone No. (include area code)
(575) 393-5905

4. Location of Well (Report location clearly and in accordance with any State requirements. *)

At surface SESE / 940 FSL / 205 FEL / LAT 32.3879514 / LONG -104.1019989

At proposed prod. zone NWSW / 1340 FSL / 330 FWL / LAT 32.3892084 / LONG -104.133464

14. Distance in miles and direction from nearest town or post office*
20 miles12. County or Parish
EDDY13. State
NM15. Distance from proposed*
location to nearest
property or lease line, ft.
(Also to nearest drig. unit line, if any)
205 feet

16. No of acres in lease

17. Spacing Unit dedicated to this well

160.77

18. Distance from proposed location*
to nearest well, drilling, completed,
applied for, on this lease, ft. 30 feet19. Proposed Depth
9326 feet / 19174 feet

20. BLM/BIA Bond No. in file

FED: NM 1693

21. Elevations (Show whether DF, KDB, RT, GL, etc.)
3078 feet22. Approximate date work will start*
07/27/202223. Estimated duration
60 days

24. Attachments

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No. 1, and the Hydraulic Fracturing rule per 43 CFR 3162.3-3 (as applicable)

1. Well plat certified by a registered surveyor.
2. A Drilling Plan.
3. A Surface Use Plan (if the location is on National Forest System Lands, the SUPO must be filed with the appropriate Forest Service Office).

4. Bond to cover the operations unless covered by an existing bond on file (see Item 20 above).
5. Operator certification.
6. Such other site specific information and/or plans as may be requested by the BLM.

25. Signature
(Electronic Submission)Name (Printed/Typed)
BRADLEY BISHOP / Ph: (575) 393-5905Date
06/24/2022Title
RegulatoryApproved by (Signature)
(Electronic Submission)Name (Printed/Typed)
CODY LAYTON / Ph: (575) 234-5959Date
05/10/2024Title
Assistant Field Manager Lands & MineralsOffice
Carlsbad Field Office

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Conditions of approval, if any, are attached.

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Continued on page 2)

*(Instructions on page 2)



INSTRUCTIONS

GENERAL: This form is designed for submitting proposals to perform certain well operations, as indicated on Federal and Indian lands and leases for action by appropriate Federal agencies, pursuant to applicable Federal laws and regulations. Any necessary special instructions concerning the use of this form and the number of copies to be submitted, particularly with regard to local, area, or regional procedures and practices, either are shown below or will be issued by, or may be obtained from local Federal offices.

ITEM I: If the proposal is to redrill to the same reservoir at a different subsurface location or to a new reservoir, use this form with appropriate notations. Consult applicable Federal regulations concerning subsequent work proposals or reports on the well.

ITEM 4: Locations on Federal or Indian land should be described in accordance with Federal requirements. Consult local Federal offices for specific instructions.

ITEM 14: Needed only when location of well cannot readily be found by road from the land or lease description. A plat, or plats, separate or on the reverse side, showing the roads to, and the surveyed location of, the well, and any other required information, should be furnished when required by Federal agency offices.

ITEMS 15 AND 18: If well is to be, or has been directionally drilled, give distances for subsurface location of hole in any present or objective productive zone.

ITEM 22: Consult applicable Federal regulations, or appropriate officials, concerning approval of the proposal before operations are started.

ITEM 24: If the proposal will involve hydraulic fracturing operations, you must comply with 43 CFR 3162.3-3, including providing information about the protection of usable water. Operators should provide the best available information about all formations containing water and their depths. This information could include data and interpretation of resistivity logs run on nearby wells. Information may also be obtained from state or tribal regulatory agencies and from local BLM offices.

NOTICES

The Privacy Act of 1974 and regulation in 43 CFR 2.48(d) provide that you be furnished the following information in connection with information required by this application.

AUTHORITY: 30 U.S.C. 181 et seq., 25 U.S.C. 396; 43 CFR 3160

PRINCIPAL PURPOSES: The information will be used to: (1) process and evaluate your application for a permit to drill a new oil, gas, or service well or to reenter a plugged and abandoned well; and (2) document, for administrative use, information for the management, disposal and use of National Resource Lands and resources including (a) analyzing your proposal to discover and extract the Federal or Indian resources encountered; (b) reviewing procedures and equipment and the projected impact on the land involved; and (c) evaluating the effects of the proposed operation on the surface and subsurface water and other environmental impacts.

ROUTINE USE: Information from the record and/or the record will be transferred to appropriate Federal, State, and local or foreign agencies, when relevant to civil, criminal or regulatory investigations or prosecution, in connection with congressional inquiries and for regulatory responsibilities.

EFFECT OF NOT PROVIDING INFORMATION: Filing of this application and disclosure of the information is mandatory only if you elect to initiate a drilling or reentry operation on an oil and gas lease.

The Paperwork Reduction Act of 1995 requires us to inform you that:

The BLM connects this information to an evaluation of the technical, safety, and environmental factors involved with drilling for oil and/or gas on Federal and Indian oil and gas leases. This information will be used to analyze and approve applications. Response to this request is mandatory only if the operator elects to initiate drilling or reentry operations on an oil and gas lease. The BLM would like you to know that you do not have to respond to this or any other Federal agency-sponsored information collection unless it displays a currently valid OMB control number.

BURDEN HOURS STATEMENT: Public reporting burden for this form is estimated to average 8 hours per response, including the time for reviewing instructions, gathering and maintaining data, and completing and reviewing the form. Direct comments regarding the burden estimate or any other aspect of this form to U.S. Department of the Interior, Bureau of Land Management (1004-0137), Bureau Information Connection Clearance Officer (WO-630), 1849 C Street, N.W., Mail Stop 401 LS, Washington, D.C. 20240.

Additional Operator Remarks

Location of Well

0. SHL: SESE / 940 FSL / 205 FEL / TWSP: 22S / RANGE: 28E / SECTION: 17 / LAT: 32.3879514 / LONG: -104.1019989 (TVD: 0 feet, MD: 0 feet)

PPP: NESE / 1340 FSL / 330 FEL / TWSP: 22S / RANGE: 28E / SECTION: 17 / LAT: 32.3890566 / LONG: -104.1024011 (TVD: 9430 feet, MD: 9580 feet)

BHL: NWSW / 1340 FSL / 330 FWL / TWSP: 22S / RANGE: 28E / SECTION: 18 / LAT: 32.3892084 / LONG: -104.133464 (TVD: 9326 feet, MD: 19174 feet)

BLM Point of Contact

Name: PAMELLA HERNANDEZ

Title: LIE

Phone: (575) 234-5954

Email: PHERNANDEZ@BLM.GOV

CONFIDENTIAL

Review and Appeal Rights

A person contesting a decision shall request a State Director review. This request must be filed within 20 working days of receipt of the Notice with the appropriate State Director (see 43 CFR 3165.3). The State Director review decision may be appealed to the Interior Board of Land Appeals, 801 North Quincy Street, Suite 300, Arlington, VA 22203 (see 43 CFR 3165.4). Contact the above listed Bureau of Land Management office for further information.

CONFIDENTIAL

**PECOS DISTRICT
SURFACE USE
CONDITIONS OF APPROVAL**

MEWBOURNE OIL COMPANY

Eddy County

North Pad

Little Rascals 17/18 W0AD FED COM 1H

Little Rascals 17/18 W0HE FED COM 2H

Little Rascals 17/18 W0HE FED COM 3H

Lease Number NMLC0067186

South Pad

Little Rascals 17/18 W0PM FED COM 1H

Little Rascals 17/18 W0IL FED COM 2H

Little Rascals 17/18 W0IL FED COM 3H

Lease Number NMNM0415688A

TABLE OF CONTENTS

Standard Conditions of Approval (COA) apply to this APD. If any deviations to these standards exist or special COAs are required, the section with the deviation or requirement will be checked below.

- ☐ **General Provisions**
- ☐ **Permit Expiration**
- ☐ **Archaeology, Paleontology, and Historical Sites**
- ☐ **Noxious Weeds**
- ☒ **Special Requirements**
 - Watershed
 - Cave/Karst
- ☐ **Construction**
 - Notification
 - Topsoil
 - Closed Loop System
 - Federal Mineral Material Pits
 - Well Pads
 - Roads
- ☐ **Road Section Diagram**
- ☐ **Production (Post Drilling)**
 - Well Structures & Facilities
- ☐ **Interim Reclamation**
- ☐ **Final Abandonment & Reclamation**

I. GENERAL PROVISIONS

The approval of the Application For Permit To Drill (APD) is in compliance with all applicable laws and regulations: 43 Code of Federal Regulations 3160, the lease terms, Onshore Oil and Gas Orders, Notices To Lessees, New Mexico Oil Conservation Division (NMOCD) Rules, National Historical Preservation Act As Amended, and instructions and orders of the Authorized Officer. Any request for a variance shall be submitted to the Authorized Officer on Form 3160-5, Sundry Notices and Report on Wells.

II. PERMIT EXPIRATION

If the permit terminates prior to drilling and drilling cannot be commenced within 60 days after expiration, an operator is required to submit Form 3160-5, Sundry Notices and Reports on Wells, requesting surface reclamation requirements for any surface disturbance. However, if the operator will be able to initiate drilling within 60 days after the expiration of the permit, the operator must have set the conductor pipe in order to allow for an extension of 60 days beyond the expiration date of the APD. (Filing of a Sundry Notice is required for this 60 day extension.)

III. ARCHAEOLOGICAL, PALEONTOLOGY & HISTORICAL SITES

Any cultural and/or paleontological resource discovered by the operator or by any person working on the operator's behalf shall immediately report such findings to the Authorized Officer. The operator is fully accountable for the actions of their contractors and subcontractors. The operator shall suspend all operations in the immediate area of such discovery until written authorization to proceed is issued by the Authorized Officer. An evaluation of the discovery shall be made by the Authorized Officer to determine the appropriate actions that shall be required to prevent the loss of significant cultural or scientific values of the discovery. The operator shall be held responsible for the cost of the proper mitigation measures that the Authorized Officer assesses after consultation with the operator on the evaluation and decisions of the discovery. Any unauthorized collection or disturbance of cultural or paleontological resources may result in a shutdown order by the Authorized Officer.

IV. NOXIOUS WEEDS

The operator shall be held responsible if noxious weeds become established within the areas of operations. Weed control shall be required on the disturbed land where noxious weeds exist, which includes the roads, pads, associated pipeline corridor, and adjacent land affected by the establishment of weeds due to this action. The operator shall consult with the Authorized Officer for

acceptable weed control methods, which include following EPA and BLM requirements and policies.

V. SPECIAL REQUIREMENT(S)

Hydrology

The entire well pad will be bermed to prevent oil, salt, and other chemical contaminants from leaving the well pad. Topsoil shall not be used to construct the berm. No water flow from the uphill side(s) of the pad shall be allowed to enter the well pad. The berm shall be maintained through the life of the well and after interim reclamation has been completed. Any water erosion that may occur due to the construction of the well pad during the life of the well will be quickly corrected and proper measures will be taken to prevent future erosion.

Tank battery locations will be lined and bermed. A 20 mil permanent liner will be installed with a 4 oz. felt backing to prevent tears or punctures. Tank battery berms must be large enough to contain 1 ½ times the content of the largest tank or 24 hour production, whichever is greater. Automatic shut off, check valves, or similar systems will be installed for tanks to minimize the effects of catastrophic line failures used in production or drilling.

A leak detection plan will be submitted to the BLM Carlsbad Field Office for approval prior to pipeline installation. The method could incorporate gauges to detect pressure drops, situating valves and lines so they can be visually inspected periodically or installing electronic sensors to alarm when a leak is present. The leak detection plan will incorporate an automatic shut off system that will be installed for proposed pipelines to minimize the effects of an undesirable event.

Cave/Karst Surface Mitigation

The following stipulations will be applied to minimize impacts during construction, drilling and production:

Construction:

General Construction:

- No blasting
- The BLM, Carlsbad Field Office, will be informed immediately if any subsurface drainage channels, cave passages, or voids are penetrated during construction, and no additional construction shall occur until clearance has been issued by the Authorized Officer.
- All linear surface disturbance activities will avoid sinkholes and other karst features to lessen the possibility of encountering near surface voids

during construction, minimize changes to runoff, and prevent untimely leaks and spills from entering the karst drainage system.

- All spills or leaks will be reported to the BLM immediately for their immediate and proper treatment.

Pad Construction:

- The pad will be constructed and leveled by adding the necessary fill and caliche – no blasting.
- The entire perimeter of the well pad will be bermed to prevent oil, salt, and other chemical contaminants from leaving the well pad.
- The compacted berm shall be constructed at a minimum of 12 inches high with impermeable mineral material (e.g., caliche).
- No water flow from the uphill side(s) of the pad shall be allowed to enter the well pad.
- The topsoil stockpile shall be located outside the bermed well pad.
- Topsoil, either from the well pad or surrounding area, shall not be used to construct the berm.
- No storm drains, tubing or openings shall be placed in the berm.
- If fluid collects within the bermed area, the fluid must be vacuumed into a safe container and disposed of properly at a state approved facility.
- The integrity of the berm shall be maintained around the surfaced pad throughout the life of the well and around the downsized pad after interim reclamation has been completed.
- Any access road entering the well pad shall be constructed so that the integrity of the berm height surrounding the well pad is not compromised (i.e. an access road crossing the berm cannot be lower than the berm height).
- Following a rain event, all fluids will vacuumed off of the pad and hauled off-site and disposed at a proper disposal facility.

Tank Battery Construction:

- The pad will be constructed and leveled by adding the necessary fill and caliche – no blasting.
- All tank battery locations and facilities will be lined and bermed.
- The liner should be at least 20 mil in thickness and installed with a 4 oz. felt backing, or equivalent, to prevent tears or punctures.
- Tank battery berms must be large enough to contain 1 ½ times the content of the largest tank.

Road Construction:

- Turnout ditches and drainage leadoffs will not be constructed in such a manner as to alter the natural flow of water into or out of cave or karst features.
- Special restoration stipulations or realignment may be required if subsurface features are discovered during construction.

Buried Pipeline/Cable Construction:

- Rerouting of the buried line(s) may be required if a subsurface void is encountered during construction to minimize the potential subsidence/collapse of the feature(s) as well as the possibility of leaks/spills entering the karst drainage system.

Powerline Construction:

- Smaller powerlines will be routed around sinkholes and other karst features to avoid or lessen the possibility of encountering near surface voids and to minimize changes to runoff or possible leaks and spills from entering karst systems.
- Larger powerlines will adjust their pole spacing to avoid cave and karst features.
- Special restoration stipulations or realignment may be required if subsurface voids are encountered.

Surface Flowlines Installation:

- Flowlines will be routed around sinkholes and other karst features to minimize the possibility of leaks/spills from entering the karst drainage system.

Leak Detection System:

- A method of detecting leaks is required. The method could incorporate gauges to measure loss, siting valves and lines so they can be visually inspected, or installing electronic sensors to alarm when a leak is present.
- A leak detection plan will be submitted to BLM that incorporates an automatic shut off system (see below) to minimize the effects of an undesirable event that could negatively sensitive cave/karst resources.
- Well heads, pipelines (surface and buried), storage tanks, and all supporting equipment should be monitored regularly after installation to promptly identify and fix leaks.

Automatic Shut-off Systems:

- Automatic shut off, check valves, or similar systems will be installed for pipelines and tanks to minimize the effects of catastrophic line failures used in production or drilling.

Cave/Karst Subsurface Mitigation

The following stipulations will be applied to protect cave/karst and groundwater concerns:

Closed Loop System:

- A closed loop system using steel tanks will be utilized during drilling – no pits
- All fluids and cuttings will be hauled off-site and disposed of properly at an authorized site

Rotary Drilling with Fresh Water:

- Fresh water will be used as a circulating medium in zones where caves or karst features are expected. SEE ALSO: Drilling COAs for this well.

Directional Drilling:

- The kick off point for directional drilling will occur at least 100 feet below the bottom of the cave occurrence zone. SEE ALSO: Drilling COAs for this well.

Lost Circulation:

- ALL lost circulation zones between surface and the base of the cave occurrence zone will be logged and reported in the drilling report.
- If a void of four feet or more and circulation losses greater than 70 percent occur simultaneously while drilling in any cave-bearing zone, regardless of the type of drilling machinery used, the BLM will be notified immediately by the operator. The BLM will assess the situation and work with the operator on corrective actions to resolve the problem.

Abandonment Cementing:

- Additional plugging conditions of approval may be required upon well abandonment in high and medium karst potential occurrence zones.
- The BLM will assess the situation and work with the operator to ensure proper plugging of the wellbore.

Pressure Testing:

- The operator will perform annual pressure monitoring on all casing annuli and reported in a sundry notice.
- If the test results indicated a casing failure has occurred, remedial action will be undertaken to correct the problem to the BLM's approval.

VI. CONSTRUCTION

A. NOTIFICATION

The BLM shall administer compliance and monitor construction of the access road and well pad. Notify the Carlsbad Field Office at (575) 234-5909 at least 3 working days prior to commencing construction of the access road and/or well pad.

When construction operations are being conducted on this well, the operator shall have the approved APD and Conditions of Approval (COA) on the well site and they shall be made available upon request by the Authorized Officer.

B. TOPSOIL

The operator shall strip the top portion of the soil (root zone) from the entire well pad area and stockpile the topsoil along the edge of the well pad as depicted in the APD. The root zone is typically six (6) inches in depth. All the stockpiled topsoil will be redistributed over the interim reclamation areas. Topsoil shall not be used for berming the pad or facilities. For final reclamation, the topsoil shall be spread over the entire pad area for seeding preparation.

Other subsoil (below six inches) stockpiles must be completely segregated from the topsoil stockpile. Large rocks or subsoil clods (not evident in the surrounding terrain) must be buried within the approved area for interim and final reclamation.

C. CLOSED LOOP SYSTEM

Tanks are required for drilling operations: No Pits.

The operator shall properly dispose of drilling contents at an authorized disposal site.

D. FEDERAL MINERAL MATERIALS PIT

Payment shall be made to the BLM prior to removal of any federal mineral materials. Call the Carlsbad Field Office at (575) 234-5972.

E. WELL PAD SURFACING

Surfacing of the well pad is not required.

If the operator elects to surface the well pad, the surfacing material may be required to be removed at the time of reclamation. The well pad shall be constructed in a manner which creates the smallest possible surface disturbance, consistent with safety and operational needs.

F. EXCLOSURE FENCING (CELLARS & PITS)

Exclosure Fencing

The operator will install and maintain exclosure fencing for all open well cellars to prevent access to public, livestock, and large forms of wildlife before and after drilling operations until the pit is free of fluids and the operator initiates backfilling. (For examples of exclosure fencing design, refer to BLM's Oil and Gas Gold Book, Exclosure Fence Illustrations, Figure 1, Page 18.)

G. ON LEASE ACCESS ROADS

Road Width

The access road shall have a driving surface that creates the smallest possible surface disturbance and does not exceed fourteen (14) feet in width. The maximum width of surface disturbance, when constructing the access road, shall not exceed twenty-five (25) feet.

Surfacing

Surfacing material is not required on the new access road driving surface. If the operator elects to surface the new access road or pad, the surfacing material may be required to be removed at the time of reclamation.

Where possible, no improvements should be made on the unsurfaced access road other than to remove vegetation as necessary, road irregularities, safety issues, or to fill low areas that may sustain standing water.

The Authorized Officer reserves the right to require surfacing of any portion of the access road at any time deemed necessary. Surfacing may be required in the event the road deteriorates, erodes, road traffic increases, or it is determined to be beneficial for future field development. The surfacing depth and type of material will be determined at the time of notification.

Crowning

Crowning shall be done on the access road driving surface. The road crown shall have a grade of approximately 2% (i.e., a 1" crown on a 14' wide road). The road shall conform to Figure 1; cross section and plans for typical road construction.

Ditching

Ditching shall be required on both sides of the road.

Turnouts


Vehicle turnouts shall be constructed on the road. Turnouts shall be intervisible with interval spacing distance less than 1000 feet. Turnouts shall conform to Figure 1; cross section and plans for typical road construction.

Drainage

Drainage control systems shall be constructed on the entire length of road (e.g. ditches, sidehill outslowing and inslaping, lead-off ditches, culvert installation, and low water crossings).

A typical lead-off ditch has a minimum depth of 1 foot below and a berm of 6 inches above natural ground level. The berm shall be on the down-slope side of the lead-off ditch.

Cross Section of a Typical Lead-off Ditch



All lead-off ditches shall be graded to drain water with a 1 percent minimum to 3 percent maximum ditch slope. The spacing interval are variable for lead-off ditches and shall be determined according to the formula for spacing intervals of lead-off ditches, but may be amended depending upon existing soil types and centerline road slope (in %);

Formula for Spacing Interval of Lead-off Ditches

Example - On a 4% road slope that is 400 feet long, the water flow shall drain water into a lead-off ditch. Spacing interval shall be determined by the following formula:

$$400 \text{ foot road with } 4\% \text{ road slope: } \frac{400'}{4\%} + 100' = 200' \text{ lead-off ditch interval}$$

Cattle guards

An appropriately sized cattle guard sufficient to carry out the project shall be installed and maintained at fence/road crossings. Any existing cattle guards on the access road route shall be repaired or replaced if they are damaged or have deteriorated beyond practical use. The operator shall be responsible for the condition of the existing cattle guards that are in place and are utilized during lease operations.

Fence Requirement

Where entry is granted across a fence line, the fence shall be braced and tied off on both sides of the passageway prior to cutting. The operator shall notify the private surface landowner or the grazing allotment holder prior to crossing any fences.

Public Access

Public access on this road shall not be restricted by the operator without specific written approval granted by the Authorized Officer.

- Construction Steps
1. Salvage topsoil

2. Construct road

3. Redistribute topsoil

4. Revegetate slopes




Figure 1. Cross-sections and plans for typical road sections representative of BLM resource or FS local and higher-class roads.

VII. PRODUCTION (POST DRILLING)

A. WELL STRUCTURES & FACILITIES

Placement of Production Facilities

Production facilities should be placed on the well pad to allow for maximum interim recontouring and revegetation of the well location.

Exclosure Netting (Open-top Tanks)

Immediately following active drilling or completion operations, the operator will take actions necessary to prevent wildlife and livestock access, including avian wildlife, to all open-topped tanks that contain or have the potential to contain salinity sufficient to cause harm to wildlife or livestock, hydrocarbons, or Resource Conservation and Recovery Act of 1976-exempt hazardous substances. At a minimum, the operator will net, screen, or cover open-topped tanks to exclude wildlife and livestock and prevent mortality. If the operator uses netting, the operator will cover and secure the open portion of the tank to prevent wildlife entry. The operator will net, screen, or cover the tanks until the operator removes the tanks from the location or the tanks no longer contain substances that could be harmful to wildlife or livestock. Use a maximum netting mesh size of 1 ½ inches. The netting must not be in contact with fluids and must not have holes or gaps.

Chemical and Fuel Secondary Containment and Exclosure Screening

The operator will prevent all hazardous, poisonous, flammable, and toxic substances from coming into contact with soil and water. At a minimum, the operator will install and maintain an impervious secondary containment system for any tank or barrel containing hazardous, poisonous, flammable, or toxic substances sufficient to contain the contents of the tank or barrel and any drips, leaks, and anticipated precipitation. The operator will dispose of fluids within the containment system that do not meet applicable state or U. S. Environmental Protection Agency livestock water standards in accordance with state law; the operator must not drain the fluids to the soil or ground. The operator will design, construct, and maintain all secondary containment systems to prevent wildlife and livestock exposure to harmful substances. At a minimum, the operator will install effective wildlife and livestock exclosure systems such as fencing, netting, expanded metal mesh, lids, and grate covers. Use a maximum netting mesh size of 1 ½ inches.

Open-Vent Exhaust Stack Exclosures

The operator will construct, modify, equip, and maintain all open-vent exhaust stacks on production equipment to prevent birds and bats from entering, and to discourage perching, roosting, and nesting. (*Recommended exclosure structures on open-vent exhaust stacks are in the shape of a cone.*) Production

equipment includes, but may not be limited to, tanks, heater-treaters, separators, dehydrators, flare stacks, in-line units, and compressor mufflers.

Containment Structures

Proposed production facilities such as storage tanks and other vessels will have a secondary containment structure that is constructed to hold the capacity of 1.5 times the largest tank, plus freeboard to account for precipitation, unless more stringent protective requirements are deemed necessary.

Painting Requirement

All above-ground structures including meter housing that are not subject to safety requirements shall be painted a flat non-reflective paint color, **Shale Green** from the BLM Standard Environmental Color Chart (CC-001: June 2008).

VIII. INTERIM RECLAMATION

During the life of the development, all disturbed areas not needed for active support of production operations should undergo interim reclamation in order to minimize the environmental impacts of development on other resources and uses.

Within six (6) months of well completion, operators should work with BLM surface management specialists (Jim Amos: 575-234-5909) to devise the best strategies to reduce the size of the location. Interim reclamation should allow for remedial well operations, as well as safe and efficient removal of oil and gas.

During reclamation, the removal of caliche is important to increasing the success of revegetating the site. Removed caliche that is free of contaminants may be used for road repairs, fire walls or for building other roads and locations. In order to operate the well or complete workover operations, it may be necessary to drive, park and operate on restored interim vegetation within the previously disturbed area. Disturbing revegetated areas for production or workover operations will be allowed. If there is significant disturbance and loss of vegetation, the area will need to be revegetated. Communicate with the appropriate BLM office for any exceptions/exemptions if needed.

All disturbed areas after they have been satisfactorily prepared need to be reseeded with the seed mixture provided below.

Upon completion of interim reclamation, the operator shall submit a Sundry Notices and Reports on Wells, Subsequent Report of Reclamation (Form 3160-5).

IX. FINAL ABANDONMENT & RECLAMATION

At final abandonment, well locations, production facilities, and access roads must undergo "final" reclamation so that the character and productivity of the land are restored.

Earthwork for final reclamation must be completed within six (6) months of well plugging. All pads, pits, facility locations and roads must be reclaimed to a satisfactory revegetated, safe, and stable condition, unless an agreement is made with the landowner or BLM to keep the road and/or pad intact.

After all disturbed areas have been satisfactorily prepared, these areas need to be revegetated with the seed mixture provided below. Seeding should be accomplished by drilling on the contour whenever practical or by other approved methods. Seeding may need to be repeated until revegetation is successful, as determined by the BLM.

Operators shall contact a BLM surface protection specialist prior to surface abandonment operations for site specific objectives (Jim Amos: 575-234-5909).

Seed Mixture 2, for Sandy Sites

The holder shall seed all disturbed areas with the seed mixture listed below. The seed mixture shall be planted in the amounts specified in pounds of pure live seed (PLS)* per acre. There shall be no primary or secondary noxious weeds in the seed mixture. Seed will be tested and the viability testing of seed will be done in accordance with State law (s) and within nine (9) months prior to purchase. Commercial seed will be either certified or registered seed. The seed container will be tagged in accordance with State law(s) and available for inspection by the authorized officer.

Seed will be planted using a drill equipped with a depth regulator to ensure proper depth of planting where drilling is possible. The seed mixture will be evenly and uniformly planted over the disturbed area (smaller/heavier seeds have a tendency to drop the bottom of the drill and are planted first). The holder shall take appropriate measures to ensure this does not occur. Where drilling is not possible, seed will be broadcast and the area shall be raked or chained to cover the seed. When broadcasting the seed, the pounds per acre are to be doubled. The seeding will be repeated until a satisfactory stand is established as determined by the authorized officer. Evaluation of growth will not be made before completion of at least one full growing season after seeding.

Species to be planted in pounds of pure live seed* per acre:

<u>Species</u>	<u>lb/acre</u>
Sand dropseed (<i>Sporobolus cryptandrus</i>)	1.0
Sand love grass (<i>Eragrostis trichodes</i>)	1.0
Plains bristlegrass (<i>Setaria macrostachya</i>)	2.0

*Pounds of pure live seed:

Pounds of seed x percent purity x percent germination = pounds pure live seed

PECOS DISTRICT DRILLING CONDITIONS OF APPROVAL

OPERATOR'S NAME:	MEWBOURNE OIL COMPANY
WELL NAME & NO.:	LITTLE RASCALS 17/18 W0IL FED COM 2H
APD ID:	10400085709
SURFACE HOLE FOOTAGE:	940'/S & 205'/E
BOTTOM HOLE FOOTAGE:	1340'/S & 330'/W
SURFACE LOCATION:	Section 17, T.22 S., R.28 E. NMP.
COUNTY:	Eddy County, New Mexico

COA

H ₂ S	<input checked="" type="radio"/> Yes	<input type="radio"/> No	
Potash	<input checked="" type="radio"/> None	<input type="radio"/> Secretary	<input type="radio"/> R-111-P
Cave/Karst Potential	<input type="radio"/> Low	<input checked="" type="radio"/> Medium	<input type="radio"/> High
Cave/Karst Potential	<input type="radio"/> Critical		
Variance	<input type="radio"/> None	<input checked="" type="radio"/> Flex Hose	<input type="radio"/> Other
Wellhead	<input type="radio"/> Conventional	<input checked="" type="radio"/> Multibowl	<input type="radio"/> Both
Other	<input type="checkbox"/> 4 String	<input type="checkbox"/> Capitan Reef	<input type="checkbox"/> WIPP
Other	<input type="checkbox"/> Fluid Filled	<input type="checkbox"/> Pilot Hole	<input type="checkbox"/> Open Annulus
Special Requirements	<input type="checkbox"/> Water Disposal	<input checked="" type="checkbox"/> COM	<input type="checkbox"/> Unit

A. HYDROGEN SULFIDE

A Hydrogen Sulfide (H₂S) Drilling Plan shall be activated **AT SPUD**. As a result, the Hydrogen Sulfide area must meet **43 CFR 3176** requirements, which includes equipment and personnel/public protection items. If Hydrogen Sulfide is encountered, please provide measured values and formations to the BLM.

B. CASING DESIGN

1. The **13-3/8** inch surface casing shall be set at approximately **300 ft.** (a minimum of 70 feet (Eddy County) into the Rustler Anhydrite and above the salt) and cemented to the surface. **NOTE:** Surface casing set depth was adjusted based on the BLM geologist recommendation: *The operator proposes to set surface casing at 735 feet, which will be too far into the salt. Instead, set casing just below the karst aquifer at approximately 300 feet. If salt is encountered, set casing at least 25 feet above the salt.*
 - a. If cement does not circulate to the surface, the appropriate BLM office shall be notified and a temperature survey utilizing an electronic-type temperature survey with surface log readout will be used or a cement bond log shall be run to verify the top of the cement. Temperature survey will be run a minimum of six hours after pumping cement and ideally between 8-10 hours after

- completing the cement job.
- b. Wait on cement (WOC) time for a primary cement job will be a minimum of **8 hours** or **500 psi compressive strength**, whichever is greater. (This is to include the lead cement)
 - c. Wait on cement (WOC) time for a remedial job will be a minimum of 4 hours after bringing cement to surface or 500 psi compressive strength, whichever is greater.
 - d. If cement falls back, remedial cementing will be done prior to drilling out that string.
2. The **9-5/8** inch intermediate casing shall be set in a competent bed at approximately **2,425 ft.** The minimum required fill of cement behind the **9-5/8** inch intermediate casing is:
- **Cement to surface.** If cement does not circulate see B.1.a, c-d above. Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry due to **Cave/Karst**.

Note: Excess cement volume is below the CFO's recommendation of 25%. More cement might be needed.

- ❖ In Medium Cave/Karst Areas if cement does not circulate to surface on the first two casing strings, the cement on the 3rd casing string must come to surface.

3. Operator has proposed to set **7 in.** production casing at approximately **9,590 ft.** The minimum required fill of cement behind the **7 in.** production casing is:

Option 1 (Single Stage): Cement should tie-back **at least 200 feet** into previous casing string. Operator shall provide method of verification. Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry due to **Cave/Karst**.

Option 2 (Two-stage): Operator has proposed a DV tool, the depth may be adjusted as long as the cement is changed proportionally. The DV tool may be cancelled if cement circulates to surface on the first stage.

- a. **First stage to DV tool:** Cement to circulate. If cement does not circulate off the DV tool, contact the appropriate BLM office before proceeding with second stage cement job.
- b. **Second stage above DV tool:** Cement should tie-back **at least 200 feet** into previous casing string. Operator shall provide method of verification. If cement does not circulate, contact the appropriate BLM office. Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry due to **Cave/Karst**.

Note: Excess cement volume for the 2nd stage is below the CFO's recommendation of 25%. More cement might be needed.

4. The minimum required fill of cement behind the **4-1/2 in.** production liner is:

- Cement should tie-back **at least 100 feet** into previous casing string. Operator shall provide method of verification.

C. PRESSURE CONTROL

1. Variance approved to use **flex line** from BOP to choke manifold. Manufacturer's specification to be readily available. No external damage to flex line. Flex line to be installed as straight as possible (no hard bends).
2. Operator has proposed a multi-bowl wellhead assembly. This assembly will only be tested when installed on the surface casing. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the surface casing shoe shall be **5000 (5M) psi**. Before drilling the surface casing shoe out, the BOP/BOPE and annular preventer shall be pressure-tested in accordance with **title 43 CFR 3172 and API Standard 53**.
 - a. Wellhead shall be installed by manufacturer's representatives, submit documentation with subsequent sundry.
 - b. If the welding is performed by a third party, the manufacturer's representative shall monitor the temperature to verify that it does not exceed the maximum temperature of the seal.
 - c. Manufacturer representative shall install the test plug for the initial BOP test.
 - d. If the cement does not circulate and one-inch operations would have been possible with a standard wellhead, the well head shall be cut off, cementing operations performed and another wellhead installed.
 - e. Whenever any seal subject to test pressure is broken, all the tests in the **title 43 CFR 3172.6(b)(9)** must be followed.

D. SPECIAL REQUIREMENT (S)

Communitization Agreement

- The operator will submit a Communitization Agreement to the Santa Fe Office, 301 Dinosaur Trail Santa Fe, New Mexico 87508, at least 90 days before the anticipated date of first production from a well subject to a spacing order issued by the New Mexico Oil Conservation Division. The Communitization Agreement will include the signatures of all working interest owners in all Federal and Indian leases subject to the Communitization Agreement (i.e., operating rights owners and lessees of record), or certification that the operator has obtained the written signatures of all such owners and will make those signatures available to the BLM immediately upon request.
- If the operator does not comply with this condition of approval, the BLM may take enforcement actions that include, but are not limited to, those specified in 43 CFR 3163.1.

- In addition, the well sign shall include the surface and bottom hole lease numbers. When the Communitization Agreement number is known, it shall also be on the sign.

GENERAL REQUIREMENTS

The BLM is to be notified in advance for a representative to witness:

- a. Spudding well (minimum of 24 hours)
- b. Setting and/or Cementing of all casing strings (minimum of 4 hours)
- c. BOPE tests (minimum of 4 hours)

☒ Eddy County

EMAIL or call the Carlsbad Field Office, 620 East Greene St., Carlsbad, NM 88220,

BLM_NM_CFO_DrillingNotifications@BLM.GOV

(575) 361-2822

☒ Lea County

Call the Hobbs Field Station, 414 West Taylor, Hobbs NM 88240, (575) 689-5981

1. Unless the production casing has been run and cemented or the well has been properly plugged, the drilling rig shall not be removed from over the hole without prior approval.
 - a. In the event the operator has proposed to drill multiple wells utilizing a skid/walking rig. Operator shall secure the wellbore on the current well, after installing and testing the wellhead, by installing a blind flange of like pressure rating to the wellhead and a pressure gauge that can be monitored while drilling is performed on the other well(s).
 - b. When the operator proposes to set surface casing with Spudder Rig
 - Notify the BLM when moving in and removing the Spudder Rig.
 - Notify the BLM when moving in the 2nd Rig. Rig to be moved in within 90 days of notification that Spudder Rig has left the location.
 - BOP/BOPE test to be conducted per **title 43 CFR 3172**
 - as soon as 2nd Rig is rigged up on well.
2. Floor controls are required for 3M or Greater systems. These controls will be on the rig floor, unobstructed, readily accessible to the driller and will be operational at all times during drilling and/or completion activities. Rig floor is defined as the area immediately around the rotary table; the area immediately above the substructure on which the draw works are located, this does not include the dog house or stairway area.

3. The record of the drilling rate along with the GR/N well log run from TD to surface (horizontal well – vertical portion of hole) shall be submitted to the BLM office as well as all other logs run on the borehole 30 days from completion. If available, a digital copy of the logs is to be submitted in addition to the paper copies. The Rustler top and top and bottom of Salt are to be recorded on the Completion Report.

A. CASING

1. Changes to the approved APD casing program need prior approval if the items substituted are of lesser grade or different casing size or are Non-API. The Operator can exchange the components of the proposal with that of superior strength (i.e. changing from J-55 to N-80, or from 36# to 40#). Changes to the approved cement program need prior approval if the altered cement plan has less volume or strength or if the changes are substantial (i.e. Multistage tool, ECP, etc.). The initial wellhead installed on the well will remain on the well with spools used as needed.
2. Wait on cement (WOC) for Potash Areas: After cementing but before commencing any tests, the casing string shall stand cemented under pressure until both of the following conditions have been met: 1) cement reaches a minimum compressive strength of 500 psi for all cement blends, 2) until cement has been in place at least 24 hours. WOC time will be recorded in the driller's log. The casing integrity test can be done (prior to the cement setting up) immediately after bumping the plug.
3. Wait on cement (WOC) for Water Basin: After cementing but before commencing any tests, the casing string shall stand cemented under pressure until both of the following conditions have been met: 1) cement reaches a minimum compressive strength of 500 psi at the shoe, 2) until cement has been in place at least 8 hours. WOC time will be recorded in the driller's log. See individual casing strings for details regarding lead cement slurry requirements. The casing integrity test can be done (prior to the cement setting up) immediately after bumping the plug.
4. Provide compressive strengths including hours to reach required 500 pounds compressive strength prior to cementing each casing string. Have well specific cement details onsite prior to pumping the cement for each casing string.
5. No pea gravel permitted for remedial or fall back remedial without prior authorization from the BLM engineer.
6. On that portion of any well approved for a 5M BOPE system or greater, a pressure integrity test of each casing shoe shall be performed. Formation at the shoe shall be tested to a minimum of the mud weight equivalent anticipated to control the formation pressure to the next casing depth or at total depth of the well. This test shall be performed before drilling more than 20 feet of new hole.

7. If hardband drill pipe is rotated inside casing, returns will be monitored for metal. If metal is found in samples, drill pipe will be pulled and rubber protectors which have a larger diameter than the tool joints of the drill pipe will be installed prior to continuing drilling operations.
8. Whenever a casing string is cemented in the R-111-P potash area, the NMOC requirements shall be followed.

B. PRESSURE CONTROL

1. All blowout preventer (BOP) and related equipment (BOPE) shall comply with well control requirements as described in the **title 43 CFR 3172** and **API STD 53 Sec. 5.3**.
2. If a variance is approved for a flexible hose to be installed from the BOP to the choke manifold, the following requirements apply: The flex line must meet the requirements of API 16C. Check condition of flexible line from BOP to choke manifold, replace if exterior is damaged or if line fails test. Line to be as straight as possible with no hard bends and is to be anchored according to Manufacturer's requirements. The flexible hose can be exchanged with a hose of equal size and equal or greater pressure rating. Anchor requirements, specification sheet and hydrostatic pressure test certification matching the hose in service, to be onsite for review. These documents shall be posted in the company man's trailer and on the rig floor.
3. 5M or higher system requires an HCR valve, remote kill line and annular to match. The remote kill line is to be installed prior to testing the system and tested to stack pressure.
4. If the operator has proposed a multi-bowl wellhead assembly in the APD. The following requirements must be met:
 - a. Wellhead shall be installed by manufacturer's representatives, submit documentation with subsequent sundry.
 - b. If the welding is performed by a third party, the manufacturer's representative shall monitor the temperature to verify that it does not exceed the maximum temperature of the seal.
 - c. Manufacturer representative shall install the test plug for the initial BOP test.
 - d. Whenever any seal subject to test pressure is broken, all the tests in the **title 43 CFR 3172.6(b)(9)** must be followed.
 - e. If the cement does not circulate and one-inch operations would have been possible with a standard wellhead, the well head shall be cut off, cementing operations performed and another wellhead installed.
5. The appropriate BLM office shall be notified a minimum of 4 hours in advance for a representative to witness the tests.

- a. In a water basin, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. The casing cut-off and BOP installation can be initiated four hours after installing the slips, which will be approximately six hours after bumping the plug. For those casing strings not using slips, the minimum wait time before cut-off is eight hours after bumping the plug. BOP/BOPE testing can begin after cut-off or once cement reaches 500 psi compressive strength (including lead cement), whichever is greater. However, if the float does not hold, cut-off cannot be initiated until cement reaches 500 psi compressive strength (including lead when specified).
- b. In potash areas, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. For all casing strings, casing cut-off and BOP installation can be initiated at twelve hours after bumping the cement plug. The BOPE test can be initiated after bumping the cement plug with the casing valve open. (only applies to single stage cement jobs, prior to the cement setting up.)
- c. The tests shall be done by an independent service company utilizing a test plug not a cup or J-packer and can be initiated immediately with the casing valve open. The operator also has the option of utilizing an independent tester to test without a plug (i.e. against the casing) pursuant to **43 CFR 3172** with the pressure not to exceed 70% of the burst rating for the casing. Any test against the casing must meet the WOC time for water basin (8 hours) or potash (24 hours) or 500 pounds compressive strength, whichever is greater, prior to initiating the test (see casing segment as lead cement may be critical item).
- d. The test shall be run on a 5000-psi chart for a 2-3M BOP/BOP, on a 10000-psi chart for a 5M BOP/BOPE and on a 15000-psi chart for a 10M BOP/BOPE. If a linear chart is used, it shall be a one-hour chart. A circular chart shall have a maximum 2-hour clock. If a twelve hour or twenty-four-hour chart is used, tester shall make a notation that it is run with a two-hour clock.
- e. The results of the test shall be reported to the appropriate BLM office.
- f. All tests are required to be recorded on a calibrated test chart. A copy of the BOP/BOPE test chart and a copy of independent service company test will be submitted to the appropriate BLM office.
- g. The BOP/BOPE test shall include a low-pressure test from 250 to 300 psi. The test will be held for a minimum of 10 minutes if test is done with a test plug and 30 minutes without a test plug. This test shall be performed prior to the test at full stack pressure.
- h. BOP/BOPE must be tested by an independent service company within 500 feet of the top of the Wolfcamp formation if the time between the setting of

the intermediate casing and reaching this depth exceeds 20 days. This test does not exclude the test prior to drilling out the casing shoe as per **43 CFR 3172**.

C. DRILLING MUD

Mud system monitoring equipment, with derrick floor indicators and visual and audio alarms, shall be operating before drilling into the Wolfcamp formation, and shall be used until production casing is run and cemented.

D. WASTE MATERIAL AND FLUIDS

All waste (i.e. drilling fluids, trash, salts, chemicals, sewage, gray water, etc.) created as a result of drilling operations and completion operations shall be safely contained and disposed of properly at a waste disposal facility. No waste material or fluid shall be disposed of on the well location or surrounding area. Porto-johns and trash containers will be on-location during fracturing operations or any other crew-intensive operations.

SA 12/22/2023



U.S. Department of the Interior
BUREAU OF LAND MANAGEMENT

Operator Certification Data Report

05/10/2024

Operator

I hereby certify that I, or someone under my direct supervision, have inspected the drill site and access route proposed herein; that I am familiar with the conditions which currently exist; that I have full knowledge of state and Federal laws applicable to this operation; that the statements made in this APD package are, to the best of my knowledge, true and correct; and that the work associated with the operations proposed herein will be performed in conformity with this APD package and the terms and conditions under which it is approved. I also certify that I, or the company I represent, am responsible for the operations conducted under this application. These statements are subject to the provisions of 18 U.S.C. 1001 for the filing of false statements.

NAME: Bradley Bishop

Signed on: 06/24/2022

Title: Regulatory

Street Address: PO Box 5270

City: Hobbs

State: NM

Zip: 88260

Phone: (575)393-5905

Email address: bbishop@mewbourne.com

Field

Representative Name:

Street Address:

City:

State:

Zip:

Phone:

Email address:



U.S. Department of the Interior
BUREAU OF LAND MANAGEMENT

Application Data

05/10/2024

APD ID: 10400085709**Submission Date:** 06/24/2022

Highlighted data
reflects the most
recent changes
[Show Final Text](#)

Operator Name: MEWBOURNE OIL COMPANY**Well Name:** LITTLE RASCALS 17/18 W0IL FED COM**Well Number:** 2H**Well Type:** CONVENTIONAL GAS WELL**Well Work Type:** Drill

Section 1 - General

APD ID: 10400085709**Tie to previous NOS?** N**Submission Date:** 06/24/2022**BLM Office:** Carlsbad**User:** Bradley Bishop**Title:** Regulatory**Federal/Indian APD:** FED**Is the first lease penetrated for production Federal or Indian?** FED**Lease number:** NMNM415688A**Lease Acres:****Surface access agreement in place?****Allotted?****Reservation:****Agreement in place?** NO**Federal or Indian agreement:****Agreement number:****Agreement name:****Keep application confidential?** Y**Permitting Agent?** NO**APD Operator:** MEWBOURNE OIL COMPANY**Operator letter of**

Operator Info

Operator Organization Name: MEWBOURNE OIL COMPANY**Operator Address:** P O BOX 5270**Zip:** 88241**Operator PO Box:****Operator City:** HOBBS**State:** NM**Operator Phone:** (575)393-5905**Operator Internet Address:**

Section 2 - Well Information

Well in Master Development Plan? NO**Master Development Plan name:****Well in Master SUPO?** NO**Master SUPO name:****Well in Master Drilling Plan?** NO**Master Drilling Plan name:****Well Name:** LITTLE RASCALS 17/18 W0IL FED COM**Well Number:** 2H**Well API Number:****Field/Pool or Exploratory?** Field and Pool**Field Name:** PURPLE SAGE
WOLFACMP**Pool Name:** WOLFCAMP

Operator Name: MEWBOURNE OIL COMPANY**Well Name:** LITTLE RASCALS 17/18 W0IL FED COM**Well Number:** 2H**Is the proposed well in an area containing other mineral resources?** USEABLE WATER,NATURAL GAS,OIL**Is the proposed well in a Helium production area?** N**Use Existing Well Pad?** N**New surface disturbance?****Type of Well Pad:** MULTIPLE WELL**Multiple Well Pad Name:** Little Rascals 17/18 IL & PM Fed Com wells**Number:** 5**Well Class:** HORIZONTAL**Number of Legs:** 1**Well Work Type:** Drill**Well Type:** CONVENTIONAL GAS WELL**Describe Well Type:****Well sub-Type:** APPRAISAL**Describe sub-type:****Distance to town:** 20 Miles**Distance to nearest well:** 30 FT**Distance to lease line:** 205 FT**Reservoir well spacing assigned acres Measurement:** 160.77 Acres**Well plat:** LittleRascals17_18W0ILFedCom2H_wellplat_20220527082114.pdf**Well work start Date:** 07/27/2022**Duration:** 60 DAYS**Section 3 - Well Location Table****Survey Type:** RECTANGULAR**Describe Survey Type:****Datum:** NAD83**Vertical Datum:** NAVD88**Survey number:****Reference Datum:** GROUND LEVEL

Wellbore	NS-Foot	NS Indicator	EW-Foot	EW Indicator	Twsp	Range	Section	Aliquot/Lot/Tract	Latitude	Longitude	County	State	Meridian	Lease Type	Lease Number	Elevation	MD	TVD	Will this well produce from this
SHL Leg #1	940	FSL	205	FEL	22S	28E	17	Aliquot SESE	32.3879514	- 104.1019989	EDD Y	NEW MEXI CO	NEW MEXI CO	F	NMNM 0415668A	3078	0	0	Y
KOP Leg #1	1340	FSL	10	FEL	22S	28E	17	Aliquot NESE	32.3890514	- 104.101364	EDD Y	NEW MEXI CO	NEW MEXI CO	F	NMNM 0415668A	- 5885	8979	8963	Y

Operator Name: MEWBOURNE OIL COMPANY**Well Name:** LITTLE RASCALS 17/18 W01L FED COM**Well Number:** 2H

Wellbore	NS-Foot	NS Indicator	EW-Foot	EW Indicator	Twsp	Range	Section	Aliquot/Lot/Tract	Latitude	Longitude	County	State	Meridian	Lease Type	Lease Number	Elevation	MD	TVD	Will this well produce from this
PPP Leg #1-1	134 0	FSL	330	FEL	22S	28E	17	Aliquot NESE	32.38905 66	- 104.1024 011	EDD Y	NEW MEXI CO	NEW MEXI CO	F	NMNM 041566 8A	- 635 2	958 0	943 0	Y
EXIT Leg #1	134 0	FSL	330	FW L	22S	28E	18	Aliquot NWS W	32.38920 84	- 104.1334 64	EDD Y	NEW MEXI CO	NEW MEXI CO	F	NMNM 041566 8A	- 624 8	191 74	932 6	Y
BHL Leg #1	134 0	FSL	330	FW L	22S	28E	18	Aliquot NWS W	32.38920 84	- 104.1334 64	EDD Y	NEW MEXI CO	NEW MEXI CO	F	NMNM 041566 8A	- 624 8	191 74	932 6	Y

District I
1625 N. French Dr., Hobbs, NM 88240
Phone: (575) 393-6161 Fax: (575) 393-0720
District II
811 S. First St., Artesia, NM 88210
Phone: (575) 748-1283 Fax: (575) 748-9720
District III
1000 Rio Brazos Road, Aztec, NM 87410
Phone: (505) 334-6178 Fax: (505) 334-6170
District IV
1220 S. St. Francis Dr., Santa Fe, NM 87505
Phone: (505) 476-3460 Fax: (505) 476-3462

State of New Mexico
Energy, Minerals & Natural Resources Department
OIL CONSERVATION DIVISION
1220 South St. Francis Dr.
Santa Fe, NM 87505

Form C-102
Revised August 1, 2011
Submit one copy to appropriate
District Office

☐ AMENDED REPORT

WELL LOCATION AND ACREAGE DEDICATION PLAT

¹ API Number		² Pool Code 98220		³ Pool Name PURPLE SAGE WOLFCAMP					
⁴ Property Code		⁵ Property Name LITTLE RASCALS 17/18 WOIL FED COM						⁶ Well Number 2H	
⁷ GRID NO. 14744		⁸ Operator Name MEWBOURNE OIL COMPANY						⁹ Elevation 3078'	
¹⁰ Surface Location									
UL or lot no. P	Section 17	Township 22S	Range 28E	Lot Idn	Feet from the 940	North/South line SOUTH	Feet From the 205	East/West line EAST	County EDDY
¹¹ Bottom Hole Location If Different From Surface									
UL or lot no. 10	Section 18	Township 22S	Range 28E	Lot Idn	Feet from the 1340	North/South line SOUTH	Feet from the 330	East/West line WEST	County EDDY
¹² Dedicated Acres 640		¹³ Joint or Infill		¹⁴ Consolidation Code		¹⁵ Order No.			

No allowable will be assigned to this completion until all interest have been consolidated or a non-standard unit has been approved by the division.

¹⁶ GEODETIC DATA NAD 83 GRID - NM EAST SURFACE LOCATION N: 504945.4 - E: 612744.9 LAT: 32.3879513° N LONG: 104.1019989° W BOTTOM HOLE N: 505383.1 - E: 603031.5 LAT: 32.3892085° N LONG: 104.1334641° W CORNER DATA NAD 83 GRID - NM EAST A: FOUND BRASS CAP "1916" N: 504054.4 - E: 602698.6 B: FOUND BRASS CAP "1916" N: 506707.9 - E: 602704.7		C: FOUND BRASS CAP "1916" N: 509363.5 - E: 602706.8 D: FOUND BRASS CAP "1943" N: 509311.6 - E: 607636.8 E: FOUND BRASS CAP "1943" N: 509316.0 - E: 610289.4 F: FOUND BRASS CAP "1943" N: 509353.8 - E: 612951.3 G: FOUND BRASS CAP "1943" N: 506679.8 - E: 612950.3 H: FOUND BRASS CAP "1943" N: 504006.3 - E: 612949.6 I: FOUND BRASS CAP "1943" N: 503997.0 - E: 610302.1 J: FOUND BRASS CAP "1943" N: 503984.6 - E: 607656.7		K: FOUND BRASS CAP "1943" N: 503977.8 - E: 605000.8 L: FOUND BRASS CAP "1943" N: 506648.9 - E: 607647.2 LOT ACREAGE LOT 5: 36.06 AC. LOT 6: 34.85 AC. LOT 7: 35.81 AC. LOT 8: 36.98 AC. LOT 9: 37.77 AC. LOT 10: 36.69 AC. LOT 11: 37.61 AC. LOT 12: 38.66 AC		¹⁷ OPERATOR CERTIFICATION I hereby certify that the information contained herein is true and complete to the best of my knowledge and belief, and that this organization either owns a working interest or unleased mineral interest in the land including the proposed bottom hole location or has a right to drill this well at this location pursuant to a contract with an owner of such a mineral or working interest, or to a voluntary pooling agreement or a compulsory pooling order heretofore entered by the division. Signature <u>Bradley Bishop</u> Date <u>6-21-19</u> Printed Name <u>BRADLEY BISHOP</u> E-mail Address <u>BBISHOP@MEWBOURNE.COM</u>	
¹⁸ SURVEYOR CERTIFICATION I hereby certify that the well location shown on this plat was plotted from field notes of actual surveys made by me or under my supervision, and that the same is true and correct to the best of my belief. <u>05-17-2019</u> Date of Survey Signature and Seal of Professional Surveyor <u>Robert M. Howett</u> 19680 Certificate Number							

PROJECT AREA **PRODUCING AREA**

LOT 6 LOT 5 LOT 7 LOT 8 LOT 9 LOT 10 LOT 11 LOT 12

330' B.H. 1340' 205 S.L. 940'

N 88°05'48" W 2303.91' (K) S 89°51'18" W 2656.33' (J) S 89°43'52" W 2645.96' (I) S 89°47'54" W 2648.01' (H)

RRC-Job No: LS19050599



Drilling Plan Data Report

05/10/2024

U.S. Department of the Interior
BUREAU OF LAND MANAGEMENT

APD ID: 10400085709

Submission Date: 06/24/2022

Highlighted data
reflects the most
recent changes

Operator Name: MEWBOURNE OIL COMPANY

Well Name: LITTLE RASCALS 17/18 W01L FED COM

Well Number: 2H

Well Type: CONVENTIONAL GAS WELL

Well Work Type: Drill

[Show Final Text](#)

Section 1 - Geologic Formations

Formation ID	Formation Name	Elevation	True Vertical	Measured Depth	Lithologies	Mineral Resources	Producing Formatio
13409999	UNKNOWN	3078	28	28	OTHER : Top Soil	NONE	N
13410012	TOP SALT	2293	785	785	SALT	NONE	N
13410000	BOTTOM SALT	828	2250	2250	SALT	NONE	N
13410005	LAMAR	578	2500	2500	LIMESTONE	NATURAL GAS, OIL	N
13410010	BELL CANYON	498	2580	2580	SANDSTONE	NATURAL GAS, OIL	N
13410013	CHERRY CANYON	-272	3350	3350	SANDSTONE	NATURAL GAS, OIL	N
13410014	MANZANITA	-422	3500	3500	LIMESTONE	NATURAL GAS, OIL	N
13409998	BONE SPRING	-2922	6000	6000	LIMESTONE, SHALE	NATURAL GAS, OIL	N
13410001	BONE SPRING 1ST	-3882	6960	6960	SANDSTONE	NATURAL GAS, OIL	N
13410002	BONE SPRING 2ND	-4562	7640	7640	SANDSTONE	NATURAL GAS, OIL	N
13410018	BONE SPRING 3RD	-5852	8930	8930	SANDSTONE	NATURAL GAS, OIL	N
13410019	WOLFCAMP	-6182	9260	9260	LIMESTONE, SANDSTONE, SHALE	NATURAL GAS, OIL	Y

Section 2 - Blowout Prevention

Pressure Rating (PSI): 5M

Rating Depth: 19174

Equipment: Annular, Pipe Ram, Blind Ram

Requesting Variance? YES

Variance request: A variance is requested for the use of a flexible choke line from the BOP to the choke manifold. Anchors are not required by manufacturer. A variance is also requested for the use of a multibowl wellhead. Please see attached schematics.

Operator Name: MEWBOURNE OIL COMPANY**Well Name:** LITTLE RASCALS 17/18 W0IL FED COM**Well Number:** 2H

Testing Procedure: BOP/BOPE will be tested by an independent service company to 250 psi low and the high pressure indicated above per Onshore Order 2 requirements. The System may be upgraded to a higher pressure but still tested to the working pressure listed in the table above. If the system is upgraded all the components installed will be functional and tested. Pipe rams will be operationally checked each 24 hour period. Blind rams will be operationally checked on each trip out of the hole. These checks will be noted on the daily tour sheets. Other accessories to the BOP equipment will include a Kelly cock and floor safety valve (inside BOP) and choke lines and choke manifold. See attached schematics.

Choke Diagram Attachment:

Little_Rascals_17_18_W0IL_Fed_Com_2H_5M_BOPE_Choke_Diagram_20220613095731.pdf

Little_Rascals_17_18_W0IL_Fed_Com_2H_Flex_Line_Specs_20220613095731.pdf

Little_Rascals_17_18_W0IL_Fed_Com_2H_Flex_Line_Specs_API_16C_20220613095732.pdf

BOP Diagram Attachment:

Little_Rascals_17_18_W0IL_Fed_Com_2H_5M_BOPE_Schematic_20220613095738.pdf

Little_Rascals_17_18_W0IL_Fed_Com_2H_5M_Mutli_Bowl_WH_20220613095739.pdf

Section 3 - Casing

Casing ID	String Type	Hole Size	Csg Size	Condition	Standard	Tapered String	Top Set MD	Bottom Set MD	Top Set TVD	Bottom Set TVD	Top Set MSL	Bottom Set MSL	Calculated casing length MD	Grade	Weight	Joint Type	Collapse SF	Burst SF	Joint SF Type	Joint SF	Body SF Type	Body SF
1	SURFACE	17.5	13.375	NEW	API	N	0	735	0	735	3106	2371	735	H-40	48	ST&C	2.29	5.14	DRY	9.13	DRY	15.33
2	INTERMEDIATE	12.25	9.625	NEW	API	N	0	2425	0	2425	3713	681	2425	J-55	36	LT&C	1.6	2.79	DRY	5.19	DRY	6.46
3	PRODUCTION	8.75	7.0	NEW	API	N	0	9590	0	9433	3713	-6327	9590	HCP-110	26	LT&C	1.32	1.68	DRY	2.78	DRY	3.33
4	LINER	6.125	4.5	NEW	API	N	8978	19173	8963	9326	-5857	-6220	10195	P-110	13.5	LT&C	1.67	1.94	DRY	2.46	DRY	3.07

Casing Attachments

Operator Name: MEWBOURNE OIL COMPANY**Well Name:** LITTLE RASCALS 17/18 W0IL FED COM**Well Number:** 2H**Casing Attachments**

Casing ID: 1 **String** SURFACE**Inspection Document:****Spec Document:****Tapered String Spec:**

Sand_Chute_4_B2AP_Fed_Com_1H__Surf_Tapered_String_Diagram_20180223140851.pdf

Casing Design Assumptions and Worksheet(s):Little_Rascals_17_18_W0IL_Fed_Com_2H_Csg_Assumptions_20220613100427.pdf

Casing ID: 2 **String** INTERMEDIATE**Inspection Document:****Spec Document:****Tapered String Spec:**

Sand_Chute_4_B2AP_Fed_Com_1H_Inter_Tapered_String_Diagram_20180223140923.pdf

Casing Design Assumptions and Worksheet(s):Little_Rascals_17_18_W0IL_Fed_Com_2H_Csg_Assumptions_20220613100438.pdf

Casing ID: 3 **String** PRODUCTION**Inspection Document:****Spec Document:****Tapered String Spec:****Casing Design Assumptions and Worksheet(s):**Little_Rascals_17_18_W0IL_Fed_Com_2H_Csg_Assumptions_20220613100450.pdf

Operator Name: MEWBOURNE OIL COMPANY

Well Name: LITTLE RASCALS 17/18 W0IL FED COM

Well Number: 2H

Casing Attachments

Casing ID: 4 String LINER

Inspection Document:

Spec Document:

Tapered String Spec:

Casing Design Assumptions and Worksheet(s):

Little_Rascals_17_18_W0IL_Fed_Com_2H_Csg_Assumptions_20220613100411.pdf

Section 4 - Cement

String Type	Lead/Tail	Stage Tool Depth	Top MD	Bottom MD	Quantity(sx)	Yield	Density	Cu Ft	Excess%	Cement type	Additives
SURFACE	Lead		0	398	360	2.12	12.5	763	100	Class C	Salt, Gel, Extender, LCM
SURFACE	Tail		285	735	200	1.34	14.8	268	100	Class C	Retarder
INTERMEDIATE	Lead		0	1617	320	2.12	12.5	678	25	Class C	Salt, Gel, Extender, LCM
INTERMEDIATE	Tail		1617	2425	200	1.34	14.8	268	25	Class C	Retarder
PRODUCTION	Lead	3500	2225	2609	50	2.12	12.5	106	25	Class C	Gel, Retarder, Defoamer, Extender
PRODUCTION	Tail		2609	3500	100	1.34	14.8	134	25	Class C	Gel, Retarder, Defoamer, Extender
PRODUCTION	Lead	3500	3500	6503	320	2.12	12.5	678	25	Class C	Gel, Retarder, Defoamer, Extender
PRODUCTION	Tail		6503	9590	400	1.18	15.6	472	25	Class H	Retarder, Fluid Loss, Defoamer
LINER	Lead		8978	19173	410	2.97	11.2	1218	25	Class C	Salt, Gel, Fluid Loss, Retarder, Dispersant, Defoamer, Anti-Settling Agent

Operator Name: MEWBOURNE OIL COMPANY

Well Name: LITTLE RASCALS 17/18 W0IL FED COM

Well Number: 2H

Section 5 - Circulating Medium

Mud System Type: Closed

Will an air or gas system be Used? NO

Description of the equipment for the circulating system in accordance with Onshore Order #2:

Diagram of the equipment for the circulating system in accordance with Onshore Order #2:

Describe what will be on location to control well or mitigate other conditions: Lost circulation material Sweeps Mud scavengers in surface hole

Describe the mud monitoring system utilized: Visual monitoring

Circulating Medium Table

Top Depth	Bottom Depth	Mud Type	Min Weight (lbs/gal)	Max Weight (lbs/gal)	Density (lbs/cu ft)	Gel Strength (lbs/100 sqft)	PH	Viscosity (CP)	Salinity (ppm)	Filtration (cc)	Additional Characteristics
0	735	SPUD MUD	8.6	8.8							
735	2425	SALT SATURATED	10	10							
2425	9590	WATER-BASED MUD	8.5	9.5							
9590	19173	OIL-BASED MUD	10	12							

Section 6 - Test, Logging, Coring

List of production tests including testing procedures, equipment and safety measures:

Pason/PVT/Visual Monitoring. Will run GR/CNL from KOP (8978') to surface (horizontal well vertical portion of hole). Stated logs run will be in the Completion Report and submitted to the BLM.

List of open and cased hole logs run in the well:

COMPENSATED NEUTRON LOG,DIRECTIONAL SURVEY,GAMMA RAY LOG,MEASUREMENT WHILE DRILLING,MUD LOG/GEOLOGIC LITHOLOGY LOG,

Coring operation description for the well:

None

Operator Name: MEWBOURNE OIL COMPANY

Well Name: LITTLE RASCALS 17/18 W0IL FED COM

Well Number: 2H

Section 7 - Pressure

Anticipated Bottom Hole Pressure: 6151

Anticipated Surface Pressure: 4076

Anticipated Bottom Hole Temperature(F): 150

Anticipated abnormal pressures, temperatures, or potential geologic hazards? NO

Describe:

Contingency Plans geohazards description:

Contingency Plans geohazards

Hydrogen Sulfide drilling operations plan required? YES

Hydrogen sulfide drilling operations

Little_Rascals_17_18_W0IL_Fed_Com_2H_H2S_Plan_20220613101353.pdf

Section 8 - Other Information

Proposed horizontal/directional/multi-lateral plan submission:

Little_Rascals_17_18_W0IL_Fed_Com_2H_Dir_plan_20220613101820.pdf

Little_Rascals_17_18_W0IL_Fed_Com_2H_Dir_plot_20220613101820.pdf

Other proposed operations facets description:


Other proposed operations facets attachment:

Little_Rascals_17_18_W0IL_Fed_Com_2H_Add_Info_20220613101836.pdf

Little_Rascals_17_18_W0IL_Fed_Com_2H_Drlg_Program_20220613101848.pdf

Other Variance attachment:

5M BOPE & Closed Loop Equipment Schematic



Drawing not to scale



GATES E & S NORTH AMERICA, INC.
134 44TH STREET
CORPUS CHRISTI, TEXAS 78405

PHONE: 361-887-9807
FAX: 361-887-0812
EMAIL: Tim.Cantu@gates.com
WEB: www.gates.com

10K CEMENTING ASSEMBLY PRESSURE TEST CERTIFICATE


Customer :	AUSTIN DISTRIBUTING	Test Date:	4/30/2015
Customer Ref. :	4060578	Hose Serial No.:	D-043015-7
Invoice No. :	500506	Created By:	JUSTIN CROPPER
Product Description:	10K3.548.0CK4.1/1610KFLGE/E LE		
End Fitting 1 :	4 1/16 10K FLG	End Fitting 2 :	4 1/16 10K FLG
Gates Part No. :	4773-6290	Assembly Code :	L36554102914D-043015-7
Working Pressure :	10,000 PSI	Test Pressure :	15,000 PSI

Gates E & S North America, Inc. certifies that the following hose assembly has been tested to the Gates Oilfield Roughneck Agreement/Specification requirements and passed the 15 minute hydrostatic test per API Spec 7K/Q1, Fifth Edition, June 2010, Test pressure 9.6.7 and per Table 9 to 15,000 psi in accordance with this product number. Hose burst pressure 9.6.7.2 exceeds the minimum of 2.5 times the working pressure per Table 9.

Quality Manager :	QUALITY	Production:	PRODUCTION
Date :	4/30/2015	Date :	4/30/2015
Signature :	<i>Justin Cropper</i>	Signature :	<i>Justin Cropper</i>

Form PTC - 01 Rev.0/2







GATES ENGINEERING & SERVICES NORTH AMERICA
7603 Prairie Oak Dr.
Houston, TX 77086

PHONE: (281) 602 - 4119
FAX:
EMAIL: Troy.Schmidt@gates.com
WEB: www.gates.com

10K CHOKE & KILL ASSEMBLY PRESSURE TEST CERTIFICATE

Customer:	A-7 AUSTIN INC DBA AUSTIN HOSE	Test Date:	8/20/2018
Customer Ref.:	4101901	Hose Serial No.:	H-082018-10
Invoice No.:	511956	Created By:	Moosa Naqvi
Product Description:	10KF3.035.0CK41/1610KFLGFXDxFLT L/E		
End Fitting 1:	4 1/16 in. Fixed Flange	End Fitting 2:	4 1/16 in. Float Flange
Gates Part No.:	68503010-9721632	Assembly Code:	L40695052218H-082018-10
Working Pressure:	10,000 psi.	Test Pressure:	15,000 psi.

Gates Engineering & Services North America certifies that the following hose assembly has successfully passed all pressure testing requirements set forth in Gates specifications: GTS-04-052 (for 5K assemblies) or GTS-04-053 (10K assemblies), which include reference to Specification API 16C (2nd Edition); sections 7.5.4, 7.5.9, and 10.8.7. A test graph will accompany this test certificate to illustrate conformity to test requirements.


Quality: QUALITY
Date : 8/20/2018
Signature : *Moosa Naqvi*

Production: PRODUCTION
Date : 8/20/2018
Signature : *[Signature]*

Form PTC - 01 Rev.0 2




Hydril "GK"
13 5/8" 5M




Hydril "GK"


Cameron Type U
13 5/8" 5M



4 1/2" x 5 7/8" VBR



BLIND RAMS



MUD CROSS

H.C.R.




7" RAMS



13 5/8" 5M

13 5/8" 5M

13 5/8" 5M





13-5/8" MN-DS Wellhead System




MEWBOURNE
OIL COMPANY

C7585
Rev. 02

NOTE: All dimensions on this drawing are estimated measurements and should be evaluated by engineering.


Cuffing Hanger 57" conductor cut-off

Sand Chute 4 B2AP Fed Com #1H
Surface Csg



Casing	SF Collapse	SF Burst	SF Jt Tension	SF Body Tension
48# H-40	1.13	2.53	3.11	7.71
54.5# J-55	1.16	2.81	15.4	25.55

Sand Chute 4 B2AP Fed Com #1H
Intermediate Casing



Casing	SF Collapse	SF Burst	SF Jt Tension	SF Body Tension
36# J-55	1.13	1.96	1.92	4.54
40# J-55	1.13	1.73	4.67	16.75
40# N-80	1.13	2.09	10.00	25.76
40# HCL-80	1.30	1.77	21.96	24.03

Mewbourne Oil Company, Little Rascals 17/18 W01L Fed Com #2H**Sec 17, T22S, R28E****SL: 940' FSL & 205' FEL, Sec 17****BHL: 1340' FSL & 330' FWL, Sec 18****2. Casing Program**

Hole Size	Casing Interval		Csg. Size	Weight (lbs)	Grade	Conn.	SF Collapse	SF Burst	SF Jt Tension	SF Body Tension
	From	To								
17.5"	0'	735'	13.375"	48	H40	STC	2.29	5.14	9.13	15.33
12.25"	0'	2425'	9.625"	36	J55	LTC	1.6	2.79	5.19	6.46
8.75"	0'	9590'	7"	26	HCP110	LTC	1.32	1.68	2.78	3.33
6.125"	8978'	19173'	4.5"	13.5	P110	LTC	1.91	2.22	2.46	3.07
				BLM Minimum Safety Factor			1.125	1	1.6 Dry 1.8 Wet	1.6 Dry 1.8 Wet

All casing strings will be tested in accordance with Onshore Oil and Gas Order #2 III.B.1.h
Must have table for contingency casing

	Y or N
Is casing new? If used, attach certification as required in Onshore Order #1	Y
Is casing API approved? If no, attach casing specification sheet.	Y
Is premium or uncommon casing planned? If yes attach casing specification sheet.	N
Does the above casing design meet or exceed BLM's minimum standards? If not provide justification (loading assumptions, casing design criteria).	Y
Will the pipe be kept at a minimum 1/3 fluid filled to avoid approaching the collapse pressure rating of the casing?	Y
Is well located within Capitan Reef?	N
If yes, does production casing cement tie back a minimum of 50' above the Reef?	
Is well within the designated 4 string boundary.	
Is well located in SOPA but not in R-111-P?	N
If yes, are the first 2 strings cemented to surface and 3 rd string cement tied back 500' into previous casing?	
Is well located in R-111-P and SOPA?	N
If yes, are the first three strings cemented to surface?	
Is 2 nd string set 100' to 600' below the base of salt?	
Is well located in high Cave/Karst?	N
If yes, are there two strings cemented to surface?	
(For 2 string wells) If yes, is there a contingency casing if lost circulation occurs?	
Is well located in critical Cave/Karst?	N
If yes, are there three strings cemented to surface?	

Mewbourne Oil Company, Little Rascals 17/18 W01L Fed Com #2H**Sec 17, T22S, R28E****SL: 940' FSL & 205' FEL, Sec 17****BHL: 1340' FSL & 330' FWL, Sec 18****2. Casing Program**

Hole Size	Casing Interval		Csg. Size	Weight (lbs)	Grade	Conn.	SF Collapse	SF Burst	SF Jt Tension	SF Body Tension
	From	To								
17.5"	0'	735'	13.375"	48	H40	STC	2.29	5.14	9.13	15.33
12.25"	0'	2425'	9.625"	36	J55	LTC	1.6	2.79	5.19	6.46
8.75"	0'	9590'	7"	26	HCP110	LTC	1.32	1.68	2.78	3.33
6.125"	8978'	19173'	4.5"	13.5	P110	LTC	1.91	2.22	2.46	3.07
				BLM Minimum Safety Factor			1.125	1	1.6 Dry 1.8 Wet	1.6 Dry 1.8 Wet

All casing strings will be tested in accordance with Onshore Oil and Gas Order #2 III.B.1.h
Must have table for contingency casing

	Y or N
Is casing new? If used, attach certification as required in Onshore Order #1	Y
Is casing API approved? If no, attach casing specification sheet.	Y
Is premium or uncommon casing planned? If yes attach casing specification sheet.	N
Does the above casing design meet or exceed BLM's minimum standards? If not provide justification (loading assumptions, casing design criteria).	Y
Will the pipe be kept at a minimum 1/3 fluid filled to avoid approaching the collapse pressure rating of the casing?	Y
Is well located within Capitan Reef?	N
If yes, does production casing cement tie back a minimum of 50' above the Reef?	
Is well within the designated 4 string boundary.	
Is well located in SOPA but not in R-111-P?	N
If yes, are the first 2 strings cemented to surface and 3 rd string cement tied back 500' into previous casing?	
Is well located in R-111-P and SOPA?	N
If yes, are the first three strings cemented to surface?	
Is 2 nd string set 100' to 600' below the base of salt?	
Is well located in high Cave/Karst?	N
If yes, are there two strings cemented to surface?	
(For 2 string wells) If yes, is there a contingency casing if lost circulation occurs?	
Is well located in critical Cave/Karst?	N
If yes, are there three strings cemented to surface?	

Mewbourne Oil Company, Little Rascals 17/18 W01L Fed Com #2H**Sec 17, T22S, R28E****SL: 940' FSL & 205' FEL, Sec 17****BHL: 1340' FSL & 330' FWL, Sec 18****2. Casing Program**

Hole Size	Casing Interval		Csg. Size	Weight (lbs)	Grade	Conn.	SF Collapse	SF Burst	SF Jt Tension	SF Body Tension
	From	To								
17.5"	0'	735'	13.375"	48	H40	STC	2.29	5.14	9.13	15.33
12.25"	0'	2425'	9.625"	36	J55	LTC	1.6	2.79	5.19	6.46
8.75"	0'	9590'	7"	26	HCP110	LTC	1.32	1.68	2.78	3.33
6.125"	8978'	19173'	4.5"	13.5	P110	LTC	1.91	2.22	2.46	3.07
				BLM Minimum Safety Factor			1.125	1	1.6 Dry 1.8 Wet	1.6 Dry 1.8 Wet

All casing strings will be tested in accordance with Onshore Oil and Gas Order #2 III.B.1.h
Must have table for contingency casing

	Y or N
Is casing new? If used, attach certification as required in Onshore Order #1	Y
Is casing API approved? If no, attach casing specification sheet.	Y
Is premium or uncommon casing planned? If yes attach casing specification sheet.	N
Does the above casing design meet or exceed BLM's minimum standards? If not provide justification (loading assumptions, casing design criteria).	Y
Will the pipe be kept at a minimum 1/3 fluid filled to avoid approaching the collapse pressure rating of the casing?	Y
Is well located within Capitan Reef?	N
If yes, does production casing cement tie back a minimum of 50' above the Reef?	
Is well within the designated 4 string boundary.	
Is well located in SOPA but not in R-111-P?	N
If yes, are the first 2 strings cemented to surface and 3 rd string cement tied back 500' into previous casing?	
Is well located in R-111-P and SOPA?	N
If yes, are the first three strings cemented to surface?	
Is 2 nd string set 100' to 600' below the base of salt?	
Is well located in high Cave/Karst?	N
If yes, are there two strings cemented to surface?	
(For 2 string wells) If yes, is there a contingency casing if lost circulation occurs?	
Is well located in critical Cave/Karst?	N
If yes, are there three strings cemented to surface?	

Mewbourne Oil Company, Little Rascals 17/18 W01L Fed Com #2H**Sec 17, T22S, R28E****SL: 940' FSL & 205' FEL, Sec 17****BHL: 1340' FSL & 330' FWL, Sec 18****2. Casing Program**

Hole Size	Casing Interval		Csg. Size	Weight (lbs)	Grade	Conn.	SF Collapse	SF Burst	SF Jt Tension	SF Body Tension
	From	To								
17.5"	0'	735'	13.375"	48	H40	STC	2.29	5.14	9.13	15.33
12.25"	0'	2425'	9.625"	36	J55	LTC	1.6	2.79	5.19	6.46
8.75"	0'	9590'	7"	26	HCP110	LTC	1.32	1.68	2.78	3.33
6.125"	8978'	19173'	4.5"	13.5	P110	LTC	1.91	2.22	2.46	3.07
				BLM Minimum Safety Factor			1.125	1	1.6 Dry 1.8 Wet	1.6 Dry 1.8 Wet

All casing strings will be tested in accordance with Onshore Oil and Gas Order #2 III.B.1.h
Must have table for contingency casing

	Y or N
Is casing new? If used, attach certification as required in Onshore Order #1	Y
Is casing API approved? If no, attach casing specification sheet.	Y
Is premium or uncommon casing planned? If yes attach casing specification sheet.	N
Does the above casing design meet or exceed BLM's minimum standards? If not provide justification (loading assumptions, casing design criteria).	Y
Will the pipe be kept at a minimum 1/3 fluid filled to avoid approaching the collapse pressure rating of the casing?	Y
Is well located within Capitan Reef?	N
If yes, does production casing cement tie back a minimum of 50' above the Reef?	
Is well within the designated 4 string boundary.	
Is well located in SOPA but not in R-111-P?	N
If yes, are the first 2 strings cemented to surface and 3 rd string cement tied back 500' into previous casing?	
Is well located in R-111-P and SOPA?	N
If yes, are the first three strings cemented to surface?	
Is 2 nd string set 100' to 600' below the base of salt?	
Is well located in high Cave/Karst?	N
If yes, are there two strings cemented to surface?	
(For 2 string wells) If yes, is there a contingency casing if lost circulation occurs?	
Is well located in critical Cave/Karst?	N
If yes, are there three strings cemented to surface?	

Hydrogen Sulfide Drilling Operations Plan **Mewbourne Oil Company**

1. General Requirements

Rule 118 does not apply to this well because MOC has researched this area and no high concentrations of H₂S were found. MOC will have on location and working all H₂S safety equipment before the Delaware formation for purposes of safety and insurance requirements.

2. Hydrogen Sulfide Training

All personnel, whether regularly assigned, contracted, or employed on an unscheduled basis, will have received training from a qualified instructor in the following areas prior to entering the drilling pad area of the well:

1. The hazards and characteristics of hydrogen sulfide gas.
2. The proper use of personal protective equipment and life support systems.
3. The proper use of hydrogen sulfide detectors, alarms, warning systems, briefing areas, evacuation procedures.
4. The proper techniques for first aid and rescue operations.

Additionally, supervisory personnel will be trained in the following areas:

- 1 The effects of hydrogen sulfide on metal components. If high tensile tubular systems are utilized, supervisory personnel will be trained in their special maintenance requirements.
- 2 Corrective action and shut in procedures, blowout prevention, and well control procedures while drilling a well.
- 3 The contents of the Hydrogen Sulfide Drilling Operations Plan.

There will be an initial training session prior to encountering a known hydrogen sulfide source. The initial training session shall include a review of the site specific Hydrogen Sulfide Drilling Operations Plan.

3. Hydrogen Sulfide Safety Equipment and Systems

All hydrogen sulfide safety equipment and systems will be installed, tested, and operational prior to drilling below the 9 5/8" intermediate casing.

1. Well Control Equipment
 - A. Choke manifold with minimum of one adjustable choke/remote choke.
 - B. Blowout preventers equipped with blind rams and pipe rams to accommodate all pipe sizes with properly sized closing unit
 - C. Auxiliary equipment including annular type blowout preventer.
2. Protective Equipment for Essential Personnel

Thirty minute self contained work unit located in the dog house and at briefing areas.

Additionally: If H₂S is encountered in concentrations less than 10 ppm, fans will be placed in work areas to prevent the accumulation of hazardous amounts of poisonous gas. If higher concentrations of H₂S are detected the well will be shut in and a rotating head, mud/gas separator, remote choke and flare line with igniter will be installed.

3. Hydrogen Sulfide Protection and Monitoring Equipment
Two portable hydrogen sulfide monitors positioned on location for optimum coverage and detection. The units shall have audible sirens to notify personnel when hydrogen sulfide levels exceed 20 PPM.
4. Visual Warning Systems
 - A. Wind direction indicators as indicated on the wellsite diagram.
 - B. Caution signs shall be posted on roads providing access to location. Signs shall be painted a high visibility color with lettering of sufficient size to be readable at reasonable distances from potentially contaminated areas.

4. **Mud Program**

The mud program has been designed to minimize the amount of hydrogen sulfide entrained in the mud system. Proper mud weight, safe drilling practices, and the use of hydrogen sulfide scavengers will minimize hazards while drilling the well.

5. **Metallurgy**

All tubular systems, wellheads, blowout preventers, drilling spools, kill lines, choke manifolds, and valves shall be suitable for service in a hydrogen sulfide environment when chemically treated.

6. **Communications**

State & County Officials phone numbers are posted on rig floor and supervisors trailer. Communications in company vehicles and toolpushers are either two way radios or cellular phones.

7. **Well Testing**

Drill stem testing is not an anticipated requirement for evaluation of this well. If a drill stem test is required, it will be conducted with a minimum number of personnel in the immediate vicinity. The test will be conducted during daylight hours only.

8. **Emergency Phone Numbers**

Eddy County Sheriff's Office	911 or 575-887-7551
Ambulance Service	911 or 575-885-2111
Carlsbad Fire Dept	911 or 575-885-2111
Loco Hills Volunteer Fire Dept.	911 or 575-677-3266
Closest Medical Facility - Columbia Medical Center of Carlsbad	575-492-5000

Mewbourne Oil Company	Hobbs District Office	575-393-5905
	Fax	575-397-6252
	2nd Fax	575-393-7259

District Manager	Robin Terrell	575-390-4816
Drilling Superintendent	Frosty Lathan	575-390-4103
	Bradley Bishop	575-390-6838
Drilling Foreman	Wesley Noseff	575-441-0729

Mewbourne Oil Company

Eddy County, New Mexico NAD 83

Little Rascals 17/18 W0IL Fed Com #2H

Sec 17, T22S, R28E

SHL: 940' FSL & 205' FEL, Sec 17

BHL: 1340' FSL & 330' FWL, Sec 18

Plan: Design #1

Standard Planning Report

15 July, 2019

Planning Report

Database:	Hobbs	Local Co-ordinate Reference:	Site Little Rascals 17/18 W0IL Fed Com #2H
Company:	Mewbourne Oil Company	TVD Reference:	WELL @ 3106.0usft (Original Well Elev)
Project:	Eddy County, New Mexico NAD 83	MD Reference:	WELL @ 3106.0usft (Original Well Elev)
Site:	Little Rascals 17/18 W0IL Fed Com #2H	North Reference:	Grid
Well:	Sec 17, T22S, R28E	Survey Calculation Method:	Minimum Curvature
Wellbore:	BHL: 1340' FSL & 330' FWL, Sec 18		
Design:	Design #1		

Project	Eddy County, New Mexico NAD 83		
Map System:	US State Plane 1983	System Datum:	Mean Sea Level
Geo Datum:	North American Datum 1983		
Map Zone:	New Mexico Eastern Zone		

Site		Little Rascals 17/18 W0IL Fed Com #2H				
Site Position:		Northing:	504,945.40 usft	Latitude:	32.3879514	
From:	Map	Easting:	612,744.90 usft	Longitude:	-104.1019989	
Position Uncertainty:		0.0 usft	Slot Radius:	13-3/16 "	Grid Convergence:	0.12 °

Well	Sec 17, T22S, R28E					
Well Position	+N/-S	0.0 usft	Northing:	504,945.40 usft	Latitude:	32.3879514
	+E/-W	0.0 usft	Easting:	612,744.90 usft	Longitude:	-104.1019989
Position Uncertainty		0.0 usft	Wellhead Elevation:	3,106.0 usft	Ground Level:	3,078.0 usft

Wellbore	BHL: 1340' FSL & 330' FWL, Sec 18				
Magnetics	Model Name	Sample Date	Declination (°)	Dip Angle (°)	Field Strength (nT)
	IGRF200510	12/31/2009	8.00	60.30	48,835

Design	Design #1			
Audit Notes:				
Version:	Phase:	PROTOTYPE	Tie On Depth:	0.0
Vertical Section:	Depth From (TVD) (usft)	+N/-S (usft)	+E/-W (usft)	Direction (°)
	0.0	0.0	0.0	272.58

Plan Sections										
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)	TFO (°)	Target
0.0	0.00	0.00	0.0	0.0	0.0	0.00	0.00	0.00	0.00	
2,425.0	0.00	0.00	2,425.0	0.0	0.0	0.00	0.00	0.00	0.00	
2,696.1	4.07	25.97	2,695.9	8.6	4.2	1.50	1.50	0.00	25.97	
8,707.5	4.07	25.97	8,692.1	392.0	190.9	0.00	0.00	0.00	0.00	
8,978.6	0.00	0.07	8,963.0	400.6	195.1	1.50	-1.50	0.00	180.00	KOP: 1340' FSL & 10
9,771.4	90.83	270.21	9,463.0	402.5	-312.2	11.46	11.46	0.00	-89.79	
19,173.6	90.83	270.21	9,326.0	437.7	-9,713.4	0.00	0.00	0.00	0.00	BHL: 3140' FSL & 330'

Planning Report

Database:	Hobbs	Local Co-ordinate Reference:	Site Little Rascals 17/18 W0IL Fed Com #2H
Company:	Mewbourne Oil Company	TVD Reference:	WELL @ 3106.0usft (Original Well Elev)
Project:	Eddy County, New Mexico NAD 83	MD Reference:	WELL @ 3106.0usft (Original Well Elev)
Site:	Little Rascals 17/18 W0IL Fed Com #2H	North Reference:	Grid
Well:	Sec 17, T22S, R28E	Survey Calculation Method:	Minimum Curvature
Wellbore:	BHL: 1340' FSL & 330' FWL, Sec 18		
Design:	Design #1		

Planned Survey									
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
0.0	0.00	0.00	0.0	0.0	0.0	0.0	0.00	0.00	0.00
SHL: 940' FSL & 205' FEL (17)									
100.0	0.00	0.00	100.0	0.0	0.0	0.0	0.00	0.00	0.00
200.0	0.00	0.00	200.0	0.0	0.0	0.0	0.00	0.00	0.00
300.0	0.00	0.00	300.0	0.0	0.0	0.0	0.00	0.00	0.00
400.0	0.00	0.00	400.0	0.0	0.0	0.0	0.00	0.00	0.00
500.0	0.00	0.00	500.0	0.0	0.0	0.0	0.00	0.00	0.00
600.0	0.00	0.00	600.0	0.0	0.0	0.0	0.00	0.00	0.00
700.0	0.00	0.00	700.0	0.0	0.0	0.0	0.00	0.00	0.00
800.0	0.00	0.00	800.0	0.0	0.0	0.0	0.00	0.00	0.00
900.0	0.00	0.00	900.0	0.0	0.0	0.0	0.00	0.00	0.00
1,000.0	0.00	0.00	1,000.0	0.0	0.0	0.0	0.00	0.00	0.00
1,100.0	0.00	0.00	1,100.0	0.0	0.0	0.0	0.00	0.00	0.00
1,200.0	0.00	0.00	1,200.0	0.0	0.0	0.0	0.00	0.00	0.00
1,300.0	0.00	0.00	1,300.0	0.0	0.0	0.0	0.00	0.00	0.00
1,400.0	0.00	0.00	1,400.0	0.0	0.0	0.0	0.00	0.00	0.00
1,500.0	0.00	0.00	1,500.0	0.0	0.0	0.0	0.00	0.00	0.00
1,600.0	0.00	0.00	1,600.0	0.0	0.0	0.0	0.00	0.00	0.00
1,700.0	0.00	0.00	1,700.0	0.0	0.0	0.0	0.00	0.00	0.00
1,800.0	0.00	0.00	1,800.0	0.0	0.0	0.0	0.00	0.00	0.00
1,900.0	0.00	0.00	1,900.0	0.0	0.0	0.0	0.00	0.00	0.00
2,000.0	0.00	0.00	2,000.0	0.0	0.0	0.0	0.00	0.00	0.00
2,100.0	0.00	0.00	2,100.0	0.0	0.0	0.0	0.00	0.00	0.00
2,200.0	0.00	0.00	2,200.0	0.0	0.0	0.0	0.00	0.00	0.00
2,300.0	0.00	0.00	2,300.0	0.0	0.0	0.0	0.00	0.00	0.00
2,400.0	0.00	0.00	2,400.0	0.0	0.0	0.0	0.00	0.00	0.00
2,425.0	0.00	0.00	2,425.0	0.0	0.0	0.0	0.00	0.00	0.00
2,500.0	1.13	25.97	2,500.0	0.7	0.3	-0.3	1.50	1.50	0.00
2,600.0	2.63	25.97	2,599.9	3.6	1.8	-1.6	1.50	1.50	0.00
2,696.1	4.07	25.97	2,695.9	8.6	4.2	-3.8	1.50	1.50	0.00
2,700.0	4.07	25.97	2,699.8	8.9	4.3	-3.9	0.00	0.00	0.00
2,800.0	4.07	25.97	2,799.5	15.3	7.4	-6.7	0.00	0.00	0.00
2,900.0	4.07	25.97	2,899.3	21.6	10.5	-9.6	0.00	0.00	0.00
3,000.0	4.07	25.97	2,999.0	28.0	13.6	-12.4	0.00	0.00	0.00
3,100.0	4.07	25.97	3,098.8	34.4	16.8	-15.2	0.00	0.00	0.00
3,200.0	4.07	25.97	3,198.5	40.8	19.9	-18.0	0.00	0.00	0.00
3,300.0	4.07	25.97	3,298.3	47.2	23.0	-20.8	0.00	0.00	0.00
3,400.0	4.07	25.97	3,398.0	53.5	26.1	-23.6	0.00	0.00	0.00
3,500.0	4.07	25.97	3,497.7	59.9	29.2	-26.4	0.00	0.00	0.00
3,600.0	4.07	25.97	3,597.5	66.3	32.3	-29.3	0.00	0.00	0.00
3,700.0	4.07	25.97	3,697.2	72.7	35.4	-32.1	0.00	0.00	0.00
3,800.0	4.07	25.97	3,797.0	79.0	38.5	-34.9	0.00	0.00	0.00
3,900.0	4.07	25.97	3,896.7	85.4	41.6	-37.7	0.00	0.00	0.00
4,000.0	4.07	25.97	3,996.5	91.8	44.7	-40.5	0.00	0.00	0.00
4,100.0	4.07	25.97	4,096.2	98.2	47.8	-43.3	0.00	0.00	0.00
4,200.0	4.07	25.97	4,196.0	104.5	50.9	-46.2	0.00	0.00	0.00
4,300.0	4.07	25.97	4,295.7	110.9	54.0	-49.0	0.00	0.00	0.00
4,400.0	4.07	25.97	4,395.5	117.3	57.1	-51.8	0.00	0.00	0.00
4,500.0	4.07	25.97	4,495.2	123.7	60.2	-54.6	0.00	0.00	0.00
4,600.0	4.07	25.97	4,595.0	130.0	63.3	-57.4	0.00	0.00	0.00
4,700.0	4.07	25.97	4,694.7	136.4	66.4	-60.2	0.00	0.00	0.00
4,800.0	4.07	25.97	4,794.5	142.8	69.5	-63.0	0.00	0.00	0.00
4,900.0	4.07	25.97	4,894.2	149.2	72.7	-65.9	0.00	0.00	0.00
5,000.0	4.07	25.97	4,994.0	155.6	75.8	-68.7	0.00	0.00	0.00

Planning Report

Database:	Hobbs	Local Co-ordinate Reference:	Site Little Rascals 17/18 W01L Fed Com #2H
Company:	Mewbourne Oil Company	TVD Reference:	WELL @ 3106.0usft (Original Well Elev)
Project:	Eddy County, New Mexico NAD 83	MD Reference:	WELL @ 3106.0usft (Original Well Elev)
Site:	Little Rascals 17/18 W01L Fed Com #2H	North Reference:	Grid
Well:	Sec 17, T22S, R28E	Survey Calculation Method:	Minimum Curvature
Wellbore:	BHL: 1340' FSL & 330' FWL, Sec 18		
Design:	Design #1		

Planned Survey									
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
5,100.0	4.07	25.97	5,093.7	161.9	78.9	-71.5	0.00	0.00	0.00
5,200.0	4.07	25.97	5,193.5	168.3	82.0	-74.3	0.00	0.00	0.00
5,300.0	4.07	25.97	5,293.2	174.7	85.1	-77.1	0.00	0.00	0.00
5,400.0	4.07	25.97	5,393.0	181.1	88.2	-79.9	0.00	0.00	0.00
5,500.0	4.07	25.97	5,492.7	187.4	91.3	-82.8	0.00	0.00	0.00
5,600.0	4.07	25.97	5,592.5	193.8	94.4	-85.6	0.00	0.00	0.00
5,700.0	4.07	25.97	5,692.2	200.2	97.5	-88.4	0.00	0.00	0.00
5,800.0	4.07	25.97	5,792.0	206.6	100.6	-91.2	0.00	0.00	0.00
5,900.0	4.07	25.97	5,891.7	212.9	103.7	-94.0	0.00	0.00	0.00
6,000.0	4.07	25.97	5,991.5	219.3	106.8	-96.8	0.00	0.00	0.00
6,100.0	4.07	25.97	6,091.2	225.7	109.9	-99.6	0.00	0.00	0.00
6,200.0	4.07	25.97	6,190.9	232.1	113.0	-102.5	0.00	0.00	0.00
6,300.0	4.07	25.97	6,290.7	238.4	116.1	-105.3	0.00	0.00	0.00
6,400.0	4.07	25.97	6,390.4	244.8	119.2	-108.1	0.00	0.00	0.00
6,500.0	4.07	25.97	6,490.2	251.2	122.3	-110.9	0.00	0.00	0.00
6,600.0	4.07	25.97	6,589.9	257.6	125.4	-113.7	0.00	0.00	0.00
6,700.0	4.07	25.97	6,689.7	263.9	128.5	-116.5	0.00	0.00	0.00
6,800.0	4.07	25.97	6,789.4	270.3	131.7	-119.4	0.00	0.00	0.00
6,900.0	4.07	25.97	6,889.2	276.7	134.8	-122.2	0.00	0.00	0.00
7,000.0	4.07	25.97	6,988.9	283.1	137.9	-125.0	0.00	0.00	0.00
7,100.0	4.07	25.97	7,088.7	289.5	141.0	-127.8	0.00	0.00	0.00
7,200.0	4.07	25.97	7,188.4	295.8	144.1	-130.6	0.00	0.00	0.00
7,300.0	4.07	25.97	7,288.2	302.2	147.2	-133.4	0.00	0.00	0.00
7,400.0	4.07	25.97	7,387.9	308.6	150.3	-136.2	0.00	0.00	0.00
7,500.0	4.07	25.97	7,487.7	315.0	153.4	-139.1	0.00	0.00	0.00
7,600.0	4.07	25.97	7,587.4	321.3	156.5	-141.9	0.00	0.00	0.00
7,700.0	4.07	25.97	7,687.2	327.7	159.6	-144.7	0.00	0.00	0.00
7,800.0	4.07	25.97	7,786.9	334.1	162.7	-147.5	0.00	0.00	0.00
7,900.0	4.07	25.97	7,886.7	340.5	165.8	-150.3	0.00	0.00	0.00
8,000.0	4.07	25.97	7,986.4	346.8	168.9	-153.1	0.00	0.00	0.00
8,100.0	4.07	25.97	8,086.2	353.2	172.0	-155.9	0.00	0.00	0.00
8,200.0	4.07	25.97	8,185.9	359.6	175.1	-158.8	0.00	0.00	0.00
8,300.0	4.07	25.97	8,285.7	366.0	178.2	-161.6	0.00	0.00	0.00
8,400.0	4.07	25.97	8,385.4	372.3	181.3	-164.4	0.00	0.00	0.00
8,500.0	4.07	25.97	8,485.2	378.7	184.4	-167.2	0.00	0.00	0.00
8,600.0	4.07	25.97	8,584.9	385.1	187.6	-170.0	0.00	0.00	0.00
8,707.5	4.07	25.97	8,692.1	392.0	190.9	-173.1	0.00	0.00	0.00
8,800.0	2.68	25.97	8,784.5	396.8	193.3	-175.2	1.50	-1.50	0.00
8,900.0	1.18	25.97	8,884.4	399.9	194.7	-176.5	1.50	-1.50	0.00
8,978.6	0.00	0.07	8,963.0	400.6	195.1	-176.9	1.50	-1.50	0.00
KOP: 1340' FSL & 10 FEL (17)									
9,000.0	2.45	270.21	8,984.4	400.6	194.6	-176.4	11.46	11.46	0.00
9,050.0	8.18	270.21	9,034.2	400.6	190.0	-171.8	11.46	11.46	0.00
9,100.0	13.91	270.21	9,083.2	400.7	180.4	-162.2	11.46	11.46	0.00
9,150.0	19.64	270.21	9,131.1	400.7	166.0	-147.8	11.46	11.46	0.00
9,200.0	25.37	270.21	9,177.2	400.8	146.9	-128.7	11.46	11.46	0.00
9,250.0	31.10	270.21	9,221.3	400.9	123.2	-105.1	11.46	11.46	0.00
9,300.0	36.83	270.21	9,262.7	401.0	95.3	-77.2	11.46	11.46	0.00
9,350.0	42.56	270.21	9,301.2	401.1	63.4	-45.3	11.46	11.46	0.00
9,400.0	48.28	270.21	9,336.3	401.2	27.8	-9.7	11.46	11.46	0.00
9,450.0	54.01	270.21	9,367.6	401.4	-11.1	29.2	11.46	11.46	0.00
9,500.0	59.74	270.21	9,394.9	401.5	-53.0	71.0	11.46	11.46	0.00
9,550.0	65.47	270.21	9,417.9	401.7	-97.4	115.3	11.46	11.46	0.00

Planning Report

Database:	Hobbs	Local Co-ordinate Reference:	Site Little Rascals 17/18 W0IL Fed Com #2H
Company:	Mewbourne Oil Company	TVD Reference:	WELL @ 3106.0usft (Original Well Elev)
Project:	Eddy County, New Mexico NAD 83	MD Reference:	WELL @ 3106.0usft (Original Well Elev)
Site:	Little Rascals 17/18 W0IL Fed Com #2H	North Reference:	Grid
Well:	Sec 17, T22S, R28E	Survey Calculation Method:	Minimum Curvature
Wellbore:	BHL: 1340' FSL & 330' FWL, Sec 18		
Design:	Design #1		

Planned Survey									
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
9,580.0	68.91	270.21	9,429.6	401.8	-125.0	143.0	11.46	11.46	0.00
FTP: 1340' FSL & 330' FEL (17)									
9,600.0	71.20	270.21	9,436.4	401.9	-143.8	161.7	11.46	11.46	0.00
9,650.0	76.93	270.21	9,450.1	402.0	-191.9	209.8	11.46	11.46	0.00
9,700.0	82.66	270.21	9,459.0	402.2	-241.1	258.9	11.46	11.46	0.00
9,750.0	88.39	270.21	9,462.9	402.4	-290.9	308.7	11.46	11.46	0.00
9,771.1	90.81	270.21	9,463.0	402.5	-312.0	329.8	11.46	11.46	0.00
LP: 1340' FSL & 517' FEL (17)									
9,771.4	90.83	270.21	9,463.0	402.5	-312.2	330.0	11.46	11.46	0.00
9,800.0	90.83	270.21	9,462.6	402.6	-340.9	358.6	0.00	0.00	0.00
9,900.0	90.83	270.21	9,461.1	403.0	-440.9	458.6	0.00	0.00	0.00
10,000.0	90.83	270.21	9,459.7	403.4	-540.8	558.5	0.00	0.00	0.00
10,100.0	90.83	270.21	9,458.2	403.7	-640.8	658.4	0.00	0.00	0.00
10,200.0	90.83	270.21	9,456.8	404.1	-740.8	758.3	0.00	0.00	0.00
10,300.0	90.83	270.21	9,455.3	404.5	-840.8	858.2	0.00	0.00	0.00
10,400.0	90.83	270.21	9,453.8	404.9	-940.8	958.1	0.00	0.00	0.00
10,500.0	90.83	270.21	9,452.4	405.2	-1,040.8	1,058.0	0.00	0.00	0.00
10,600.0	90.83	270.21	9,450.9	405.6	-1,140.8	1,157.9	0.00	0.00	0.00
10,700.0	90.83	270.21	9,449.5	406.0	-1,240.8	1,257.8	0.00	0.00	0.00
10,800.0	90.83	270.21	9,448.0	406.4	-1,340.8	1,357.7	0.00	0.00	0.00
10,900.0	90.83	270.21	9,446.6	406.7	-1,440.7	1,457.6	0.00	0.00	0.00
11,000.0	90.83	270.21	9,445.1	407.1	-1,540.7	1,557.5	0.00	0.00	0.00
11,100.0	90.83	270.21	9,443.6	407.5	-1,640.7	1,657.4	0.00	0.00	0.00
11,200.0	90.83	270.21	9,442.2	407.8	-1,740.7	1,757.3	0.00	0.00	0.00
11,300.0	90.83	270.21	9,440.7	408.2	-1,840.7	1,857.2	0.00	0.00	0.00
11,400.0	90.83	270.21	9,439.3	408.6	-1,940.7	1,957.1	0.00	0.00	0.00
11,500.0	90.83	270.21	9,437.8	409.0	-2,040.7	2,057.0	0.00	0.00	0.00
11,600.0	90.83	270.21	9,436.4	409.3	-2,140.7	2,156.9	0.00	0.00	0.00
11,700.0	90.83	270.21	9,434.9	409.7	-2,240.7	2,256.8	0.00	0.00	0.00
11,800.0	90.83	270.21	9,433.4	410.1	-2,340.6	2,356.7	0.00	0.00	0.00
11,900.0	90.83	270.21	9,432.0	410.5	-2,440.6	2,456.6	0.00	0.00	0.00
12,000.0	90.83	270.21	9,430.5	410.8	-2,540.6	2,556.5	0.00	0.00	0.00
12,100.0	90.83	270.21	9,429.1	411.2	-2,640.6	2,656.4	0.00	0.00	0.00
12,200.0	90.83	270.21	9,427.6	411.6	-2,740.6	2,756.3	0.00	0.00	0.00
12,300.0	90.83	270.21	9,426.2	412.0	-2,840.6	2,856.3	0.00	0.00	0.00
12,400.0	90.83	270.21	9,424.7	412.3	-2,940.6	2,956.2	0.00	0.00	0.00
12,500.0	90.83	270.21	9,423.2	412.7	-3,040.6	3,056.1	0.00	0.00	0.00
12,600.0	90.83	270.21	9,421.8	413.1	-3,140.6	3,156.0	0.00	0.00	0.00
12,700.0	90.83	270.21	9,420.3	413.5	-3,240.5	3,255.9	0.00	0.00	0.00
12,800.0	90.83	270.21	9,418.9	413.8	-3,340.5	3,355.8	0.00	0.00	0.00
12,900.0	90.83	270.21	9,417.4	414.2	-3,440.5	3,455.7	0.00	0.00	0.00
13,000.0	90.83	270.21	9,416.0	414.6	-3,540.5	3,555.6	0.00	0.00	0.00
13,100.0	90.83	270.21	9,414.5	415.0	-3,640.5	3,655.5	0.00	0.00	0.00
13,200.0	90.83	270.21	9,413.0	415.3	-3,740.5	3,755.4	0.00	0.00	0.00
13,300.0	90.83	270.21	9,411.6	415.7	-3,840.5	3,855.3	0.00	0.00	0.00
13,400.0	90.83	270.21	9,410.1	416.1	-3,940.5	3,955.2	0.00	0.00	0.00
13,500.0	90.83	270.21	9,408.7	416.5	-4,040.5	4,055.1	0.00	0.00	0.00
13,600.0	90.83	270.21	9,407.2	416.8	-4,140.4	4,155.0	0.00	0.00	0.00
13,700.0	90.83	270.21	9,405.8	417.2	-4,240.4	4,254.9	0.00	0.00	0.00
13,800.0	90.83	270.21	9,404.3	417.6	-4,340.4	4,354.8	0.00	0.00	0.00
13,900.0	90.83	270.21	9,402.8	418.0	-4,440.4	4,454.7	0.00	0.00	0.00
14,000.0	90.83	270.21	9,401.4	418.3	-4,540.4	4,554.6	0.00	0.00	0.00
14,100.0	90.83	270.21	9,399.9	418.7	-4,640.4	4,654.5	0.00	0.00	0.00
14,200.0	90.83	270.21	9,398.5	419.1	-4,740.4	4,754.4	0.00	0.00	0.00

Planning Report



Database:	Hobbs	Local Co-ordinate Reference:	Site Little Rascals 17/18 W0IL Fed Com #2H
Company:	Mewbourne Oil Company	TVD Reference:	WELL @ 3106.0usft (Original Well Elev)
Project:	Eddy County, New Mexico NAD 83	MD Reference:	WELL @ 3106.0usft (Original Well Elev)
Site:	Little Rascals 17/18 W0IL Fed Com #2H	North Reference:	Grid
Well:	Sec 17, T22S, R28E	Survey Calculation Method:	Minimum Curvature
Wellbore:	BHL: 1340' FSL & 330' FWL, Sec 18		
Design:	Design #1		

Planned Survey										
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)	
14,300.0	90.83	270.21	9,397.0	419.5	-4,840.4	4,854.3	0.00	0.00	0.00	
14,400.0	90.83	270.21	9,395.6	419.8	-4,940.4	4,954.2	0.00	0.00	0.00	
14,500.0	90.83	270.21	9,394.1	420.2	-5,040.3	5,054.1	0.00	0.00	0.00	
14,600.0	90.83	270.21	9,392.6	420.6	-5,140.3	5,154.0	0.00	0.00	0.00	
14,700.0	90.83	270.21	9,391.2	421.0	-5,240.3	5,254.0	0.00	0.00	0.00	
14,800.0	90.83	270.21	9,389.7	421.3	-5,340.3	5,353.9	0.00	0.00	0.00	
14,900.0	90.83	270.21	9,388.3	421.7	-5,440.3	5,453.8	0.00	0.00	0.00	
15,000.0	90.83	270.21	9,386.8	422.1	-5,540.3	5,553.7	0.00	0.00	0.00	
15,100.0	90.83	270.21	9,385.4	422.4	-5,640.3	5,653.6	0.00	0.00	0.00	
15,200.0	90.83	270.21	9,383.9	422.8	-5,740.3	5,753.5	0.00	0.00	0.00	
15,300.0	90.83	270.21	9,382.4	423.2	-5,840.2	5,853.4	0.00	0.00	0.00	
15,400.0	90.83	270.21	9,381.0	423.6	-5,940.2	5,953.3	0.00	0.00	0.00	
15,500.0	90.83	270.21	9,379.5	423.9	-6,040.2	6,053.2	0.00	0.00	0.00	
15,600.0	90.83	270.21	9,378.1	424.3	-6,140.2	6,153.1	0.00	0.00	0.00	
15,700.0	90.83	270.21	9,376.6	424.7	-6,240.2	6,253.0	0.00	0.00	0.00	
15,800.0	90.83	270.21	9,375.2	425.1	-6,340.2	6,352.9	0.00	0.00	0.00	
15,900.0	90.83	270.21	9,373.7	425.4	-6,440.2	6,452.8	0.00	0.00	0.00	
16,000.0	90.83	270.21	9,372.2	425.8	-6,540.2	6,552.7	0.00	0.00	0.00	
16,100.0	90.83	270.21	9,370.8	426.2	-6,640.2	6,652.6	0.00	0.00	0.00	
16,200.0	90.83	270.21	9,369.3	426.6	-6,740.1	6,752.5	0.00	0.00	0.00	
16,300.0	90.83	270.21	9,367.9	426.9	-6,840.1	6,852.4	0.00	0.00	0.00	
16,400.0	90.83	270.21	9,366.4	427.3	-6,940.1	6,952.3	0.00	0.00	0.00	
16,500.0	90.83	270.21	9,365.0	427.7	-7,040.1	7,052.2	0.00	0.00	0.00	
16,600.0	90.83	270.21	9,363.5	428.1	-7,140.1	7,152.1	0.00	0.00	0.00	
16,700.0	90.83	270.21	9,362.0	428.4	-7,240.1	7,252.0	0.00	0.00	0.00	
16,800.0	90.83	270.21	9,360.6	428.8	-7,340.1	7,351.9	0.00	0.00	0.00	
16,900.0	90.83	270.21	9,359.1	429.2	-7,440.1	7,451.8	0.00	0.00	0.00	
17,000.0	90.83	270.21	9,357.7	429.6	-7,540.1	7,551.7	0.00	0.00	0.00	
17,100.0	90.83	270.21	9,356.2	429.9	-7,640.0	7,651.7	0.00	0.00	0.00	
17,200.0	90.83	270.21	9,354.8	430.3	-7,740.0	7,751.6	0.00	0.00	0.00	
17,300.0	90.83	270.21	9,353.3	430.7	-7,840.0	7,851.5	0.00	0.00	0.00	
17,400.0	90.83	270.21	9,351.8	431.1	-7,940.0	7,951.4	0.00	0.00	0.00	
17,500.0	90.83	270.21	9,350.4	431.4	-8,040.0	8,051.3	0.00	0.00	0.00	
17,600.0	90.83	270.21	9,348.9	431.8	-8,140.0	8,151.2	0.00	0.00	0.00	
17,700.0	90.83	270.21	9,347.5	432.2	-8,240.0	8,251.1	0.00	0.00	0.00	
17,800.0	90.83	270.21	9,346.0	432.6	-8,340.0	8,351.0	0.00	0.00	0.00	
17,900.0	90.83	270.21	9,344.6	432.9	-8,440.0	8,450.9	0.00	0.00	0.00	
18,000.0	90.83	270.21	9,343.1	433.3	-8,539.9	8,550.8	0.00	0.00	0.00	
18,100.0	90.83	270.21	9,341.6	433.7	-8,639.9	8,650.7	0.00	0.00	0.00	
18,200.0	90.83	270.21	9,340.2	434.1	-8,739.9	8,750.6	0.00	0.00	0.00	
18,300.0	90.83	270.21	9,338.7	434.4	-8,839.9	8,850.5	0.00	0.00	0.00	
18,400.0	90.83	270.21	9,337.3	434.8	-8,939.9	8,950.4	0.00	0.00	0.00	
18,500.0	90.83	270.21	9,335.8	435.2	-9,039.9	9,050.3	0.00	0.00	0.00	
18,600.0	90.83	270.21	9,334.4	435.6	-9,139.9	9,150.2	0.00	0.00	0.00	
18,700.0	90.83	270.21	9,332.9	435.9	-9,239.9	9,250.1	0.00	0.00	0.00	
18,800.0	90.83	270.21	9,331.4	436.3	-9,339.9	9,350.0	0.00	0.00	0.00	
18,900.0	90.83	270.21	9,330.0	436.7	-9,439.8	9,449.9	0.00	0.00	0.00	
19,000.0	90.83	270.21	9,328.5	437.1	-9,539.8	9,549.8	0.00	0.00	0.00	
19,100.0	90.83	270.21	9,327.1	437.4	-9,639.8	9,649.7	0.00	0.00	0.00	
19,173.6	90.83	270.21	9,326.0	437.7	-9,713.4	9,723.3	0.00	0.00	0.00	
BHL: 3140' FSL & 330' FWL (18)										

Planning Report

Database:	Hobbs	Local Co-ordinate Reference:	Site Little Rascals 17/18 W0IL Fed Com #2H
Company:	Mewbourne Oil Company	TVD Reference:	WELL @ 3106.0usft (Original Well Elev)
Project:	Eddy County, New Mexico NAD 83	MD Reference:	WELL @ 3106.0usft (Original Well Elev)
Site:	Little Rascals 17/18 W0IL Fed Com #2H	North Reference:	Grid
Well:	Sec 17, T22S, R28E	Survey Calculation Method:	Minimum Curvature
Wellbore:	BHL: 1340' FSL & 330' FWL, Sec 18		
Design:	Design #1		

Design Targets									
Target Name									
- hit/miss target	Dip Angle	Dip Dir.	TVD	+N/-S	+E/-W	Northing	Easting	Latitude	Longitude
- Shape	(°)	(°)	(usft)	(usft)	(usft)	(usft)	(usft)		
SHL: 940' FSL & 205' FE - plan hits target center - Point	0.00	0.07	0.0	0.0	0.0	504,945.40	612,744.90	32.3879514	-104.1019989
KOP: 1340' FSL & 10 FE - plan hits target center - Point	0.00	0.07	8,963.0	400.6	195.1	505,346.00	612,940.00	32.3890514	-104.1013640
BHL: 3140' FSL & 330' F - plan hits target center - Point	0.00	0.07	9,326.0	437.7	-9,713.4	505,383.10	603,031.50	32.3892084	-104.1334640
FTP: 1340' FSL & 330' F - plan hits target center - Point	0.00	0.07	9,429.6	401.8	-125.0	505,347.20	612,619.90	32.3890566	-104.1024011
LP: 1340' FSL & 517' FE - plan hits target center - Point	0.00	0.07	9,463.0	402.5	-312.0	505,347.90	612,432.90	32.3890596	-104.1030069



Intent ☒ As Drilled ☐

API #		
Operator Name: Mewbourne Oil Co.	Property Name: Little Rascals 17/18 W0IL Fed Com	Well Number 2H

Kick Off Point (KOP)

UL I	Section 17	Township 22S	Range 28E	Lot	Feet 1340	From N/S S	Feet 10	From E/W E	County Eddy
Latitude 32.3890514					Longitude -104.1013640			NAD 83	

First Take Point (FTP)

UL I	Section 17	Township 22S	Range 28E	Lot	Feet 1340	From N/S S	Feet 330	From E/W E	County Eddy
Latitude 32.3890566					Longitude -104.1024011			NAD 83	

Last Take Point (LTP)

UL L	Section 18	Township 22S	Range 28E	Lot	Feet 1340	From N/S S	Feet 330	From E/W W	County Eddy
Latitude 32.3892084					Longitude -104.1334640			NAD 83	

Is this well the defining well for the Horizontal Spacing Unit? ☐ NIs this well an infill well? ☐ Y

If infill is yes please provide API if available, Operator Name and well number for Defining well for Horizontal Spacing Unit.

API #		
Operator Name: Mewbourne Oil Company	Property Name: Little Rascals 17/18 W0IL Fed Com	Well Number 3H

KZ 06/29/2018

Mewbourne Oil Company, Little Rascals 17/18 W01L Fed Com #2H**Sec 17, T22S, R28E****SL: 940' FSL & 205' FEL, Sec 17****BHL: 1340' FSL & 330' FWL, Sec 18****1. Geologic Formations**

TVD of target	9326'	Pilot hole depth	NA
MD at TD:	18893'	Deepest expected fresh water:	50'

Basin

Formation	Depth (TVD) from KB	Water/Mineral Bearing/ Target Zone?	Hazards*
Quaternary Fill	Surface		
Rustler			
Top of Salt	785		
Base of Salt	2250		
Lamar	2500		
Bell Canyon	2580	Oil/Gas	
Cherry Canyon	3350	Oil/Gas	
Manzanita Marker	3500	Oil/Gas	
Brushy Canyon			
Bone Spring	6000	Oil/Gas	
1 st Bone Spring Sand	6960	Oil/Gas	
2 nd Bone Spring Sand	7640	Oil/Gas	
3 rd Bone Spring Sand	8930	Oil/Gas	
Abo			
Wolfcamp	9260	Target Zone	
Devonian			
Fusselman			
Ellenburger			
Granite Wash			

*H2S, water flows, loss of circulation, abnormal pressures, etc.

Mewbourne Oil Company, Little Rascals 17/18 W01L Fed Com #2H**Sec 17, T22S, R28E****SL: 940' FSL & 205' FEL, Sec 17****BHL: 1340' FSL & 330' FWL, Sec 18****2. Casing Program**

Hole Size	Casing Interval		Csg. Size	Weight (lbs)	Grade	Conn.	SF Collapse	SF Burst	SF Jt Tension	SF Body Tension
	From	To								
17.5"	0'	735'	13.375"	48	H40	STC	2.29	5.14	9.13	15.33
12.25"	0'	2425'	9.625"	36	J55	LTC	1.6	2.79	5.19	6.46
8.75"	0'	9590'	7"	26	HCP110	LTC	1.32	1.68	2.78	3.33
6.125"	8978'	19173'	4.5"	13.5	P110	LTC	1.91	2.22	2.46	3.07
BLM Minimum Safety Factor							1.125	1	1.6 Dry 1.8 Wet	1.6 Dry 1.8 Wet

All casing strings will be tested in accordance with Onshore Oil and Gas Order #2 III.B.1.h

Must have table for contingency casing

	Y or N
Is casing new? If used, attach certification as required in Onshore Order #1	Y
Is casing API approved? If no, attach casing specification sheet.	Y
Is premium or uncommon casing planned? If yes attach casing specification sheet.	N
Does the above casing design meet or exceed BLM's minimum standards? If not provide justification (loading assumptions, casing design criteria).	Y
Will the pipe be kept at a minimum 1/3 fluid filled to avoid approaching the collapse pressure rating of the casing?	Y
Is well located within Capitan Reef?	N
If yes, does production casing cement tie back a minimum of 50' above the Reef?	
Is well within the designated 4 string boundary.	
Is well located in SOPA but not in R-111-P?	N
If yes, are the first 2 strings cemented to surface and 3 rd string cement tied back 500' into previous casing?	
Is well located in R-111-P and SOPA?	N
If yes, are the first three strings cemented to surface?	
Is 2 nd string set 100' to 600' below the base of salt?	
Is well located in high Cave/Karst?	N
If yes, are there two strings cemented to surface?	
(For 2 string wells) If yes, is there a contingency casing if lost circulation occurs?	
Is well located in critical Cave/Karst?	N
If yes, are there three strings cemented to surface?	

Mewbourne Oil Company, Little Rascals 17/18 W01L Fed Com #2H**Sec 17, T22S, R28E****SL: 940' FSL & 205' FEL, Sec 17****BHL: 1340' FSL & 330' FWL, Sec 18****3. Cementing Program**

Casing	# Sks	Wt. lb/ gal	Yld ft3/ sack	H ₂ O gal/ sk	500# Comp. Strength (hours)	Slurry Description
Surf.	360	12.5	2.12	11	10	Lead: Class C + Salt + Gel + Extender + LCM
	200	14.8	1.34	6.3	8	Tail: Class C + Retarder
Inter.	320	12.5	2.12	11	10	Lead: Class C + Salt + Gel + Extender + LCM
	200	14.8	1.34	6.3	8	Tail: Class C + Retarder
Prod. Stg 1	320	12.5	2.12	11	9	Lead: Class C + Gel + Retarder + Defoamer + Extender
	400	15.6	1.18	5.2	10	Tail: Class H + Retarder + Fluid Loss + Defoamer
ECP/DV Tool @ 3500'						
Prod. Stg 2	50	12.5	2.12	11	9	Lead: Class C + Gel + Retarder + Defoamer + Extender
	100	14.8	1.34	6.3	8	Tail: Class C + Retarder
Liner	410	11.2	2.97	18	16	Class C + Salt + Gel + Fluid Loss + Retarder + Dispersant + Defoamer + Anti-Settling Agent

A copy of cement test will be available on location at time of cement job providing pump times & compressive strengths.

Casing String	TOC	% Excess
Surface	0'	100%
Intermediate	0'	25%
Production	2425'	25%
Liner	8978'	25%

Mewbourne Oil Company, Little Rascals 17/18 W01L Fed Com #2H**Sec 17, T22S, R28E****SL: 940' FSL & 205' FEL, Sec 17****BHL: 1340' FSL & 330' FWL, Sec 18****4. Pressure Control Equipment**

Variance: None

BOP installed and tested before drilling which hole?	Size?	System Rated WP	Type	✓	Tested to:
12-1/4"	13-5/8"	5M	Annular	X	2500#
			Blind Ram	X	5000#
			Pipe Ram	X	
			Double Ram		
			Other*		

*Specify if additional ram is utilized.

BOP/BOPE will be tested by an independent service company to 250 psi low and the high pressure indicated above per Onshore Order 2 requirements. The System may be upgraded to a higher pressure but still tested to the working pressure listed in the table above. If the system is upgraded all the components installed will be functional and tested.

Pipe rams will be operationally checked each 24 hour period. Blind rams will be operationally checked on each trip out of the hole. These checks will be noted on the daily tour sheets. Other accessories to the BOP equipment will include a Kelly cock and floor safety valve (inside BOP) and choke lines and choke manifold. See attached schematics.

X	Formation integrity test will be performed per Onshore Order #2. On Exploratory wells or on that portion of any well approved for a 5M BOPE system or greater, a pressure integrity test of each casing shoe shall be performed. Will be tested in accordance with Onshore Oil and Gas Order #2 III.B.1.i.
Y	A variance is requested for the use of a flexible choke line from the BOP to Choke Manifold. See attached for specs and hydrostatic test chart.
N	Are anchors required by manufacturer?
Y	A multibowl wellhead is being used. The BOP will be tested per Onshore Order #2 after installation on the surface casing which will cover testing requirements for a maximum of 30 days. If any seal subject to test pressure is broken the system must be tested. • Provide description here: See attached schematic.

Mewbourne Oil Company, Little Rascals 17/18 W01L Fed Com #2H**Sec 17, T22S, R28E****SL: 940' FSL & 205' FEL, Sec 17****BHL: 1340' FSL & 330' FWL, Sec 18****5. Mud Program**

Depth		Type	Weight (ppg)	Viscosity	Water Loss
From	To				
0'	735'	FW Gel	8.6-8.8	28-34	N/C
735'	2425'	Saturated Brine	10.0	28-34	N/C
2425'	9433'	Cut Brine	8.6-9.5	28-34	N/C
9433'	9441'	OBM	10.0-13.0	30-40	<10cc

Sufficient mud materials to maintain mud properties and meet minimum lost circulation and weight increase requirements will be kept on location at all times.

What will be used to monitor the loss or gain of fluid?	Pason/PVT/Visual Monitoring
---------------------------------------------------------	-----------------------------

6. Logging and Testing Procedures

Logging, Coring and Testing.	
X	Will run GR/CNL from KOP (8978') to surface (horizontal well – vertical portion of hole). Stated logs run will be in the Completion Report and submitted to the BLM.
	No Logs are planned based on well control or offset log information.
	Drill stem test? If yes, explain
	Coring? If yes, explain

Additional logs planned		Interval
X	Gamma Ray	8978' (KOP) to TD
	Density	
	CBL	
	Mud log	
	PEX	

Mewbourne Oil Company, Little Rascals 17/18 W01L Fed Com #2H**Sec 17, T22S, R28E****SL: 940' FSL & 205' FEL, Sec 17****BHL: 1340' FSL & 330' FWL, Sec 18****7. Drilling Conditions**

Condition	Specify what type and where?
BH Pressure at deepest TVD	6378 psi
Abnormal Temperature	No

Mitigation measure for abnormal conditions. Describe. **Lost circulation material/sweeps/mud scavengers in surface hole.**

Hydrogen Sulfide (H2S) monitors will be installed prior to drilling out the surface shoe. If H2S is detected in concentrations greater than 100 ppm, the operator will comply with the provisions of Onshore Oil and Gas Order #6. If Hydrogen Sulfide is encountered, measured values and formations will be provided to the BLM.	
	H2S is present
X	H2S Plan attached

8. Other facets of operation

Is this a walking operation? If yes, describe.

Will be pre-setting casing? If yes, describe.

Attachments

☐ Directional Plan

☐ Other, describe



U.S. Department of the Interior
BUREAU OF LAND MANAGEMENT

SUPO Data Report

05/10/2024

APD ID: 10400085709

Submission Date: 06/24/2022

Highlighted data
reflects the most
recent changes
[Show Final Text](#)

Operator Name: MEWBOURNE OIL COMPANY

Well Name: LITTLE RASCALS 17/18 W0IL FED COM

Well Number: 2H

Well Type: CONVENTIONAL GAS WELL

Well Work Type: Drill

Section 1 - Existing Roads

Will existing roads be used? YES

Existing Road Map:

LittleRascals17_18W0ILFedCom2H_existingroadmap_20220527082143.pdf

Existing Road Purpose: ACCESS,FLUID TRANSPORT

Row(s) Exist? NO

ROW ID(s)

ID:

Do the existing roads need to be improved? NO

Existing Road Improvement Description:

Existing Road Improvement Attachment:

Section 2 - New or Reconstructed Access Roads

Will new roads be needed? YES

New Road Map:

LittleRascals17_18W0ILFedCom2H_newroadmap_20220527082155.pdf

New road type: RESOURCE

Length: 156.23 Feet

Width (ft.): 30

Max slope (%): 3

Max grade (%): 3

Army Corp of Engineers (ACOE) permit required? N

ACOE Permit Number(s):

New road travel width: 14

New road access erosion control: none

New road access plan or profile prepared? N

New road access plan

Operator Name: MEWBOURNE OIL COMPANY**Well Name:** LITTLE RASCALS 17/18 W0IL FED COM**Well Number:** 2H**Access road engineering design?** N**Access road engineering design****Turnout?** N**Access surfacing type:** OTHER**Access topsoil source:** OFFSITE**Access surfacing type description:** caliche**Access onsite topsoil source depth:****Offsite topsoil source description:** Topsoil will be on edge of lease road**Onsite topsoil removal process:****Access other construction information:** none**Access miscellaneous information:** none**Number of access turnouts:****Access turnout map:**

Drainage Control

New road drainage crossing: OTHER**Drainage Control comments:** none**Road Drainage Control Structures (DCS) description:** none**Road Drainage Control Structures (DCS) attachment:**

Access Additional Attachments

Section 3 - Location of Existing Wells

Existing Wells Map? YES**Attach Well map:**

LittleRascals17_18W0ILFedCom2H_existingwellmap_20220527082224.pdf

Section 4 - Location of Existing and/or Proposed Production Facilities

Submit or defer a Proposed Production Facilities plan? SUBMIT

Production Facilities description: 1 3.5 buried steel flowline with a working pressure of 250#. 1 3.5 buried steel gas line for gas lift purposes with a working pressure of 250#. 1 1 buried gas supply line with a working pressure of 150#. These lines will be installed in one ditch following the attached route approximately 3166' in length. An overhead electric line will be installed within 15 of the flowline route. OHEL will be up to 22900 volts.

Production Facilities map:

LittleRascals17_18W0ILFedCom2H_flowlinemap_20220527082238.pdf

LittleRascals17_18W0ILFedCom2H_productionfacilitymap_20220527082238.pdf

Operator Name: MEWBOURNE OIL COMPANY**Well Name:** LITTLE RASCALS 17/18 W0IL FED COM**Well Number:** 2H

Section 5 - Location and Types of Water Supply

Water Source Table

Water source type: IRRIGATION

Water source use type: DUST CONTROL
SURFACE CASING
INTERMEDIATE/PRODUCTION
CASING
STIMULATION

Source latitude: 32.416241**Source longitude:** -104.15351**Source datum:** NAD83

Water source permit type: WATER WELL
PRIVATE CONTRACT

Water source transport method: TRUCKING**Source land ownership:** PRIVATE**Source transportation land ownership:** FEDERAL**Water source volume (barrels):** 1940**Source volume (acre-feet):** 0.2500526**Source volume (gal):** 81480

Water source and transportation

LittleRascals17_18W0ILFedCom2H_watersourceandtransmap_20220527084107.pdf

Water source comments:**New water well?** N

New Water Well Info

Well latitude:**Well Longitude:****Well datum:****Well target aquifer:****Est. depth to top of aquifer(ft):****Est thickness of aquifer:****Aquifer comments:****Aquifer documentation:****Well depth (ft):****Well casing type:**

Operator Name: MEWBOURNE OIL COMPANY**Well Name:** LITTLE RASCALS 17/18 W0IL FED COM**Well Number:** 2H**Well casing outside diameter (in.):****Well casing inside diameter (in.):****New water well casing?****Used casing source:****Drilling method:****Drill material:****Grout material:****Grout depth:****Casing length (ft.):****Casing top depth (ft.):****Well Production type:****Completion Method:****Water well additional information:****State appropriation permit:****Additional information attachment:**

Section 6 - Construction Materials

Using any construction materials: YES**Construction Materials description:** Caliche**Construction Materials source location**

LittleRascals17_18W0ILFedCom2H_calichesourceandtransmap_20220527084117.pdf

Section 7 - Methods for Handling

Waste type: DRILLING**Waste content description:** Drill cuttings**Amount of waste:** 940 barrels**Waste disposal frequency :** One Time Only**Safe containment description:** Drill cuttings will be properly contained in steel tanks (20 yard roll off bins.)**Safe containmant attachment:****Waste disposal type:** HAUL TO COMMERCIAL FACILITY**Disposal location ownership:** PRIVATE**Disposal type description:****Disposal location description:** NMOCD approved waste disposal locations are CRI or Lea Land, both facilities are located on HWY 62/180, Sec. 27 T20S R32E.**Waste type:** SEWAGE**Waste content description:** Human waste & grey water**Amount of waste:** 1500 gallons**Waste disposal frequency :** Weekly**Safe containment description:** 2,000 gallon plastic container**Safe containmant attachment:****Waste disposal type:** HAUL TO COMMERCIAL FACILITY**Disposal location ownership:** PRIVATE

Operator Name: MEWBOURNE OIL COMPANY**Well Name:** LITTLE RASCALS 17/18 W0IL FED COM**Well Number:** 2H**Disposal type description:****Disposal location description:** City of Carlsbad Water Treatment facility**Waste type:** GARBAGE**Waste content description:** Garbage & trash**Amount of waste:** 1500 pounds**Waste disposal frequency :** One Time Only**Safe containment description:** Enclosed trash trailer**Safe containmant attachment:****Waste disposal type:** HAUL TO COMMERCIAL FACILITY **Disposal location ownership:** PRIVATE**Disposal type description:****Disposal location description:** Waste Management facility in Carlsbad.

Reserve Pit

Reserve Pit being used? NO**Temporary disposal of produced water into reserve pit?** NO**Reserve pit length (ft.)****Reserve pit width (ft.)****Reserve pit depth (ft.)****Reserve pit volume (cu. yd.)****Is at least 50% of the reserve pit in cut?****Reserve pit liner****Reserve pit liner specifications and installation description**

Cuttings Area

Cuttings Area being used? NO**Are you storing cuttings on location?** N**Description of cuttings location****Cuttings area length (ft.)****Cuttings area width (ft.)****Cuttings area depth (ft.)****Cuttings area volume (cu. yd.)****Is at least 50% of the cuttings area in cut?****WCuttings area liner****Cuttings area liner specifications and installation description**

Operator Name: MEWBOURNE OIL COMPANY**Well Name:** LITTLE RASCALS 17/18 W0IL FED COM**Well Number:** 2H

Section 8 - Ancillary

Are you requesting any Ancillary Facilities?: N**Ancillary Facilities****Comments:**

Section 9 - Well Site

Well Site Layout Diagram:

LittleRascals17_18W0ILFedCom2H_wellsitelayout_20220527084130.pdf

Comments:

Section 10 - Plans for Surface Reclamation

Type of disturbance: New Surface Disturbance**Multiple Well Pad Name:** Little Rascals 17/18 IL & PM Fed Com wells**Multiple Well Pad Number:** 5**Recontouring****Drainage/Erosion control construction:** None**Drainage/Erosion control reclamation:** None

Well pad proposed disturbance (acres): 4.78	Well pad interim reclamation (acres): 1.97	Well pad long term disturbance (acres): 2.81
Road proposed disturbance (acres): 0.11	Road interim reclamation (acres): 0	Road long term disturbance (acres): 0
Powerline proposed disturbance (acres): 0	Powerline interim reclamation (acres): 0	Powerline long term disturbance (acres): 0
Pipeline proposed disturbance (acres): 2.18	Pipeline interim reclamation (acres): 0	Pipeline long term disturbance (acres): 0
Other proposed disturbance (acres): 3.673	Other interim reclamation (acres): 0	Other long term disturbance (acres): 0
Total proposed disturbance: 10.743	Total interim reclamation: 1.97	Total long term disturbance: 2.81

Disturbance Comments: In areas to be heavily disturbed, the top 6 inches of soil material, will be stripped and stockpiled on the perimeter of the well location to keep topsoil viable, and to make redistribution of topsoil more efficient during interim reclamation. Stockpiled topsoil should include vegetative material. Topsoil will be clearly segregated and stored separately from subsoils. Contaminated soil will not be stockpiled, but properly treated and handled prior to topsoil salvaging.

Reconstruction method: The areas planned for interim reclamation will then be recontoured to the original contour if feasible, or if not feasible, to an interim contour that blends with the surrounding topography as much as possible. Where applicable, the fill material of the well pad will be backfilled into the cut to bring the area back to the original contour. The interim cut and fill slopes prior to re-seeding will not be steeper than a 3:1 ratio, unless the adjacent native topography is steeper. Note: Constructed slopes may be much steeper during drilling, but will be recontoured to the above ratios during interim reclamation.

Topsoil redistribution: Topsoil will be evenly respread and aggressively revegetated over the entire disturbed area not needed for all-weather operations including cuts & fills. To seed the area, the proper BLM seed mixture, free of noxious weeds, will be used.

Operator Name: MEWBOURNE OIL COMPANY

Well Name: LITTLE RASCALS 17/18 W0IL FED COMWell Number: 2H

Soil treatment: NA

Existing Vegetation at the well pad: Various brush & grasses

Existing Vegetation at the well pad

Existing Vegetation Community at the road: Various brush & grasses

Existing Vegetation Community at the road

Existing Vegetation Community at the pipeline: NA

Existing Vegetation Community at the pipeline

Existing Vegetation Community at other disturbances: NA

Existing Vegetation Community at other disturbances

Non native seed used? N

Non native seed description:

Seedling transplant description:

Will seedlings be transplanted for this project? N

Seedling transplant description

Will seed be harvested for use in site reclamation? N

Seed harvest description:

Seed harvest description attachment:

Seed

Seed Table

Seed Summary	
Seed Type	Pounds/Acre

Total pounds/Acre:

Seed reclamation

Operator Contact/Responsible Official

First Name:

Last Name:

Phone:

Email:

Operator Name: MEWBOURNE OIL COMPANY**Well Name:** LITTLE RASCALS 17/18 W01L FED COM**Well Number:** 2H

Seedbed prep: Final seedbed preparation will consist of contour cultivating to a depth of 4 to 6 inches within 24 hours prior to seeding, dozer tracking, or other imprinting in order to break the soil crust and create seed germination micro-sites.

Seed BMP: To seed the area, the proper BLM seed mixture, free of noxious weeds, will be used.

Seed method: drilling or broadcasting seed over entire reclaimed area.

Existing invasive species? N

Existing invasive species treatment description:

Existing invasive species treatment

Weed treatment plan description: NA

Weed treatment plan

Monitoring plan description: vii. All reclaimed areas will be monitored periodically to ensure that revegetation occurs, that the area is not redisturbed, and that erosion and invasive/noxious weeds are controlled.

Monitoring plan

Success standards: regrowth within 1 full growing season of reclamation.

Pit closure description: NA

Pit closure attachment:

Section 11 - Surface Ownership

Disturbance type: EXISTING ACCESS ROAD

Describe:

Surface Owner: BUREAU OF LAND MANAGEMENT

Other surface owner description:

BIA Local Office:

BOR Local Office:

COE Local Office:

DOD Local Office:

NPS Local Office:

State Local Office:

Military Local Office:

USFWS Local Office:

Other Local Office:

USFS Region:

USFS Forest/Grassland:

USFS Ranger District:

Operator Name: MEWBOURNE OIL COMPANY

Well Name: LITTLE RASCALS 17/18 W01L FED COM

Well Number: 2H

Disturbance type: WELL PAD

Describe:

Surface Owner: BUREAU OF LAND MANAGEMENT

Other surface owner description:

BIA Local Office:

BOR Local Office:

COE Local Office:

DOD Local Office:

NPS Local Office:

State Local Office:

Military Local Office:

USFWS Local Office:

Other Local Office:

USFS Region:

USFS Forest/Grassland:

USFS Ranger District:

Disturbance type: NEW ACCESS ROAD

Describe:

Surface Owner: BUREAU OF LAND MANAGEMENT

Other surface owner description:

BIA Local Office:

BOR Local Office:

COE Local Office:

DOD Local Office:

NPS Local Office:

State Local Office:

Military Local Office:

USFWS Local Office:

Other Local Office:

USFS Region:

USFS Forest/Grassland:

USFS Ranger District:

Operator Name: MEWBOURNE OIL COMPANY**Well Name:** LITTLE RASCALS 17/18 W0IL FED COM**Well Number:** 2H**Section 12 - Other****Right of Way needed?** N**Use APD as ROW?****ROW Type(s):****ROW****SUPO Additional Information:** NONE**Use a previously conducted onsite?** Y

Previous Onsite information: MAY 17 2019 Met w/RRC Surveying & staked location @ 1340' FSL & 205' FEL, Sec 17, T22S, R28E, Eddy Co., NM. This location was unacceptable due to FEMA floodplain. Re-staked location @ 940' FSL & 205' FEL, Sec 17, T22S, R28E, Eddy Co., NM. (Elevation @ 3078'). Pad is 400 x 520. Topsoil W. Approx. 2700 of new road off the NW corner to MOC Little Rascals AD pad. A 400' x 400' battery will be off site to the NW along existing lease road. Reclaim all sides 60'. Will require arch study. Will require BLM on-site. Lat. 32.38795129 N, Long -104.10199886 W NAD83.


Other SUPO

LittleRascals17_18W0ILFedCom2H_NGMP_20220526155716.pdf

LittleRascals17_18W0ILFedCom2H_interimreclamationdiagram_20220527084305.pdf

VICINITY MAP

NOT TO SCALE



SECTION 17, TWP. 22 SOUTH, RGE. 28 EAST,
N. M. P. M., EDDY COUNTY, NEW MEXICO

OPERATOR: Mewbourne Oil Company LOCATION: 940' FSL & 205' FEL
LEASE: Little Rascals 17/18 WOIL Fed Com ELEVATION: 3078'
WELL NO.: 2H

Copyright 2016 - All Rights Reserved


RRC

NO.	REVISION	DATE
JOB NO.: LS19050599		
DWG. NO.: 19050599-3		

701 S. CECIL ST., HOBBS, NM 88240 (575) 964-8200

SCALE: N. T. S.
DATE: 05-17-2019
SURVEYED BY: ML/JC
DRAWN BY: KAKN
APPROVED BY: RMH
SHEET: 1 OF 1

MEWBOURNE OIL COMPANY
PROPOSED ACCESS ROAD FOR THE LITTLE RASCAL 17/18 FED COM WELLS
SECTION 17, T22S, R28E
N. M. P. M., EDDY COUNTY, NEW MEXICO



NO.	REVISION	DATE
JOB NO.:	LS19050592	
DWG. NO.:	19050592-6	





701 S. CECIL ST., HOBBS, NM 88240 (575) 964-8200




SCALE: 1" = 1000'
DATE: 05-17-2019
SURVEYED BY: ML/JC
DRAWN BY: KAKN
APPROVED BY: RMH
SHEET: 1 OF 1

LITTLE RASCALS 17/18 W0IL FED COM #2H
EXISTING WELL MAP





MEWBOURNE OIL COMPANY
PROPOSED BATTERY FOR THE LITTLE RASCAL 17/18 FED COM WELLS
SECTION 17, T22S, R28E,
N. M. P. M., EDDY CO., NEW MEXICO



A tract of land situated within Section 17, Township 22 South, Range 28 East, N. M. P. M. Eddy County, New Mexico, across B. L. M. land, and being more particularly described by metes and bounds as follows:

BEGINNING at a point which bears, S 51°08'46" W, 1,794.41 feet from a brass cap, stamped "1943", found for the Northeast quarter corner of Section 17 and being S 49°18'19" E, 1,668.49 feet from a brass cap, stamped "1943", found for the North quarter corner of Section 17;

Thence S 45°05'24" E, 400.00 feet, to a point;

Thence S 44°54'36" W, 400.00 feet, to a point;

Thence N 45°05'24" W, 400.00 feet, to a point;

Thence N 44°54'36" E, 400.00 feet, to the Point of Beginning.

Said tract of land contains 160,000.00 square feet or 3.673 acres, more or less, and is allocated by forties as follows:

NW/4 NE/4	38,532.11 Sq. Ft.	0.885 Acres
NE/4 NE/4	12,349.81 Sq. Ft.	0.283 Acres
SW/4 NE/4	74,919.07 Sq. Ft.	1.720 Acres
SE/4 NE/4	34,199.01 Sq. Ft.	0.785 Acres

SCALE: 1" = 1000'
 0 500' 1000'

BEARINGS ARE GRID NAD 83
 NM EAST
 DISTANCES ARE HORIZ. GROUND.

LEGEND

() RECORD DATA - GLO

◆ FOUND MONUMENT
 AS NOTED

P. O. B. POINT OF BEGINNING

I, R. M. Howett, a N. M. Professional Surveyor, hereby certify that I prepared this plat from an actual survey made on the ground under my direct supervision, said survey and plat meet the Min. Stds. for Land Surveying in the State of N. M. and are true and correct to the best of my knowledge and belief.

Robert M. Howett
 Robert M. Howett NM PS 19680



Copyright 2016 - All Rights Reserved

NO.	REVISION	DATE
JOB NO.:	LS19050592	
DWG. NO.:	19050592-5	



701 S. CECIL ST., HOBBS, NM 88240 (575) 964-8200

SCALE: 1" = 1000'
DATE: 05-17-2019
SURVEYED BY: ML/JC
DRAWN BY: KAKN
APPROVED BY: RMH
SHEET: 1 OF 1





SCALE: 1" = 100'
DATE: 05-17-2019
SURVEYED BY: ML/JC
DRAWN BY: KAKN
APPROVED BY: RMH
SHEET: 1 OF 1

Page 5

State of New Mexico
Energy, Minerals and Natural Resources Department

Submit Electronically
Via E-permitting

Oil Conservation Division
1220 South St. Francis Dr.
Santa Fe, NM 87505

NATURAL GAS MANAGEMENT PLAN

This Natural Gas Management Plan must be submitted with each Application for Permit to Drill (APD) for a new or recompleted well.

Section 1 – Plan Description

Effective May 25, 2021

I. Operator: Mewbourne Oil Co. **OGRID:** 14744 **Date:** 5/2/22

II. Type: ☒ Original ☐ Amendment due to ☐ 19.15.27.9.D(6)(a) NMAC ☐ 19.15.27.9.D(6)(b) NMAC ☐ Other.

If Other, please describe: _____

III. Well(s): Provide the following information for each new or recompleted well or set of wells proposed to be drilled or proposed to be recompleted from a single well pad or connected to a central delivery point.

Well Name	API	ULSTR	Footages	Anticipated Oil BBL/D	Anticipated Gas MCF/D	Anticipated Produced Water BBL/D
Little Rascals 17/18 W0IL Fed Com #2H		P 17 22S 28E	940' FSL x 205' FEL	2000	1500	1000

IV. Central Delivery Point Name: Little Rascals 17/18 W0IL Fed Com #2H [See 19.15.27.9(D)(1) NMAC]

V. Anticipated Schedule: Provide the following information for each new or recompleted well or set of wells proposed to be drilled or proposed to be recompleted from a single well pad or connected to a central delivery point.

Well Name	API	Spud Date	TD Reached Date	Completion Commencement Date	Initial Flow Back Date	First Production Date
Little Rascals 17/18 W0IL Fed Com #2H		7/2/22	8/2/22	9/2/22	9/17/22	9/17/22

VI. Separation Equipment: ☒ Attach a complete description of how Operator will size separation equipment to optimize gas capture.

VII. Operational Practices: ☒ Attach a complete description of the actions Operator will take to comply with the requirements of Subsection A through F of 19.15.27.8 NMAC.

VIII. Best Management Practices: ☒ Attach a complete description of Operator's best management practices to minimize venting during active and planned maintenance.

Section 2 – Enhanced Plan
EFFECTIVE APRIL 1, 2022

Beginning April 1, 2022, an operator that is not in compliance with its statewide natural gas capture requirement for the applicable reporting area must complete this section.

☒ Operator certifies that it is not required to complete this section because Operator is in compliance with its statewide natural gas capture requirement for the applicable reporting area.

IX. Anticipated Natural Gas Production:

Well	API	Anticipated Average Natural Gas Rate MCF/D	Anticipated Volume of Natural Gas for the First Year MCF

X. Natural Gas Gathering System (NGGS):

Operator	System	ULSTR of Tie-in	Anticipated Gathering Start Date	Available Maximum Daily Capacity of System Segment Tie-in

XI. Map. ☐ Attach an accurate and legible map depicting the location of the well(s), the anticipated pipeline route(s) connecting the production operations to the existing or planned interconnect of the natural gas gathering system(s), and the maximum daily capacity of the segment or portion of the natural gas gathering system(s) to which the well(s) will be connected.

XII. Line Capacity. The natural gas gathering system ☐ will ☐ will not have capacity to gather 100% of the anticipated natural gas production volume from the well prior to the date of first production.

XIII. Line Pressure. Operator ☐ does ☐ does not anticipate that its existing well(s) connected to the same segment, or portion, of the natural gas gathering system(s) described above will continue to meet anticipated increases in line pressure caused by the new well(s).

☐ Attach Operator's plan to manage production in response to the increased line pressure.

XIV. Confidentiality: ☐ Operator asserts confidentiality pursuant to Section 71-2-8 NMSA 1978 for the information provided in Section 2 as provided in Paragraph (2) of Subsection D of 19.15.27.9 NMAC, and attaches a full description of the specific information for which confidentiality is asserted and the basis for such assertion.

Section 3 - Certifications

Effective May 25, 2021

Operator certifies that, after reasonable inquiry and based on the available information at the time of submittal:

☒ Operator will be able to connect the well(s) to a natural gas gathering system in the general area with sufficient capacity to transport one hundred percent of the anticipated volume of natural gas produced from the well(s) commencing on the date of first production, taking into account the current and anticipated volumes of produced natural gas from other wells connected to the pipeline gathering system; or

☐ Operator will not be able to connect to a natural gas gathering system in the general area with sufficient capacity to transport one hundred percent of the anticipated volume of natural gas produced from the well(s) commencing on the date of first production, taking into account the current and anticipated volumes of produced natural gas from other wells connected to the pipeline gathering system.

If Operator checks this box, Operator will select one of the following:

Well Shut-In. ☐ Operator will shut-in and not produce the well until it submits the certification required by Paragraph (4) of Subsection D of 19.15.27.9 NMAC; or

Venting and Flaring Plan. ☐ Operator has attached a venting and flaring plan that evaluates and selects one or more of the potential alternative beneficial uses for the natural gas until a natural gas gathering system is available, including:

- (a) power generation on lease;
- (b) power generation for grid;
- (c) compression on lease;
- (d) liquids removal on lease;
- (e) reinjection for underground storage;
- (f) reinjection for temporary storage;
- (g) reinjection for enhanced oil recovery;
- (h) fuel cell production; and
- (i) other alternative beneficial uses approved by the division.

Section 4 - Notices

1. If, at any time after Operator submits this Natural Gas Management Plan and before the well is spud:

(a) Operator becomes aware that the natural gas gathering system it planned to connect the well(s) to has become unavailable or will not have capacity to transport one hundred percent of the production from the well(s), no later than 20 days after becoming aware of such information, Operator shall submit for OCD's approval a new or revised venting and flaring plan containing the information specified in Paragraph (5) of Subsection D of 19.15.27.9 NMAC; or

(b) Operator becomes aware that it has, cumulatively for the year, become out of compliance with its baseline natural gas capture rate or natural gas capture requirement, no later than 20 days after becoming aware of such information, Operator shall submit for OCD's approval a new or revised Natural Gas Management Plan for each well it plans to spud during the next 90 days containing the information specified in Paragraph (2) of Subsection D of 19.15.27.9 NMAC, and shall file an update for each Natural Gas Management Plan until Operator is back in compliance with its baseline natural gas capture rate or natural gas capture requirement.

2. OCD may deny or conditionally approve an APD if Operator does not make a certification, fails to submit an adequate venting and flaring plan which includes alternative beneficial uses for the anticipated volume of natural gas produced, or if OCD determines that Operator will not have adequate natural gas takeaway capacity at the time a well will be spud.

Page 8

I certify that, after reasonable inquiry, the statements in and attached to this Natural Gas Management Plan are true and correct to the best of my knowledge and acknowledge that a false statement may be subject to civil and criminal penalties under the Oil and Gas Act.

Signature:	<i>Bradley Bishop</i>
Printed Name:	BRADLEY BISHOP
Title:	REGULATORY MANAGER
E-mail Address:	BBISHOP@MEWBOURNE.COM
Date:	5/2/22
Phone:	575-393-5905
OIL CONSERVATION DIVISION (Only applicable when submitted as a standalone form)	
Approved By:	
Title:	
Approval Date:	
Conditions of Approval:	

Mewbourne Oil Company


Natural Gas Management Plan – Attachment

- VI. Separation equipment will be sized by construction engineering staff based on stated manufacturer daily throughput capacities and anticipated daily production rates to ensure adequate capacity. Closed vent system piping, compression needs, and VRUs will be sized utilizing ProMax modelling software to ensure adequate capacity for anticipated production volumes and conditions.
- VII. Mewbourne Oil Company (MOC) will take following actions to comply with the regulations listed in 19.15.27.8 :
- A. MOC will maximize the recovery of natural gas by minimizing the waste, as defined by 19.15.2 NMAC, of natural gas through venting and flaring. MOC will ensure that well(s) will be connected to a natural gas gathering system with sufficient capacity to transport natural gas. If there is no adequate takeaway for the gas, well(s) will be shut in until the natural gas gathering system is available.
 - B. All drilling operations will be equipped with a rig flare located at least 100 ft from the nearest surface hole. Rig flare will be utilized to combust any natural gas that is brought to surface during normal drilling operations. In the case of emergency venting or flaring the volumes will be estimated and reported appropriately.
 - C. During completion operations any natural gas brought to surface will be flared. Immediately following the finish of completion operations, all well flow will be directed to permanent separation equipment. Produced natural gas from separation equipment will be sent to sales. It is not anticipated that gas will not meet pipeline standards. However, if natural gas does not meet gathering pipeline quality specifications, MOC will flare the natural gas for 60 days or until the natural gas meets the pipeline quality specifications, whichever is sooner. MOC will ensure that the flare is sized properly and is equipped with automatic igniter or continuous pilot. The gas sample will analyzed twice per week and the gas will be routed into a gathering system as soon as pipeline specifications are met.
 - D. Natural gas will not be flared with the exceptions and provisions listed in the 19.15.27.8 D.(1) through (4). If there is no adequate takeaway for the separator gas, well(s) will be shut in until the natural gas gathering system is available with exception of emergency or malfunction situations. Venting and/or flaring volumes will be estimated and reported appropriately.
 - E. MOC will comply with the performance standards requirements and provisions listed in 19.15.27.8 E.(1) through (8). All equipment will be designed and sized to handle maximum anticipated pressures and throughputs in order to minimize the waste. Production storage tanks constructed after May 25, 2021 will be equipped with automatic gauging system. Flares constructed after May 25, 2021 will be equipped with automatic igniter or continuous pilot. Flares will be located at least 100' from the well and storage tanks unless otherwise approved by the division. MOC will conduct AVO inspections as described in 19.15.27.8 E (5) (a) with frequencies specified in 19.15.27.8 E (5) (b) and (c). All emergencies will be resolved as quickly and safely as feasible to minimize waste.
 - F. The volume of natural gas that is vented or flared as the result of malfunction or emergency during drilling and completions operations will be estimated. The volume of natural gas that is vented, flared or beneficially used during production operations, will be measured or estimated. MOC will install equipment to measure

the volume of natural gas flared from existing process piping or a flowline piped from equipment such as high pressure separators, heater treaters, or vapor recovery units associated with a well or facility associated with a well authorized by an APD issued after May 25, 2021 that has an average daily production greater than 60 Mcf/day. If metering is not practicable due to circumstances such as low flow rate or low pressure venting and flaring, MOC will estimate the volume of vented or flared natural gas. Measuring equipment will conform to industry standards and will not be designed or equipped with a manifold that allows the diversion of natural gas around the metering element except for the sole purpose of inspecting and servicing the measurement equipment.

- VIII. For maintenance activities involving production equipment and compression, venting will be limited to the depressurization of the subject equipment to ensure safe working conditions. For maintenance of production and compression equipment the associated producing wells will be shut in to eliminate venting. For maintenance of VRUs all gas normally routed to the VRU will be routed to flare to eliminate venting.

**MEWBOURNE OIL COMPANY
LITTLE RASCALS 17/18 WOIL FED COM #2H
(940' FSL & 205' FEL)
SECTION 17, T22S, R28E
N. M. P. M., EDDY COUNTY, NEW MEXICO**



DIRECTIONS TO LOCATION

From the intersection of CR-607 (Old Post Rd.) and CR-605 (Refinery Rd.);
Go Northwest on CR-605 approx. 2.7 miles to a lease road on the right;
Turn right and go Northeast approx. 0.5 miles to a lease road on the right;
Turn right and go South approx. 0.2 miles to a lease road on the left;
Turn left and go Northeast approx. 1.6 miles to a proposed road on the right;
Turn right and go South approx. 676 feet to proposed road on the South end of proposed pad;
Continue South approx. 0.5 miles to location on the left.


THIS IS NOT A BOUNDARY SURVEY, APPARENT PROPERTY CORNERS AND PROPERTY LINES ARE SHOWN FOR INFORMATION ONLY. BOUNDARY DATA IS SHOWN FROM A PREVIOUS SURVEY REFERENCED HEREON.

I, R. M. Howett, a N. M. Professional Surveyor, hereby certify that I prepared this unclassified survey of a well location from an actual survey made on the ground under my direct supervision, said survey and plat meet the Min. Stds. for Land Surveying in the State of N. M. and are true and correct to the best of my knowledge and belief.

Robert M. Howett

Robert M. Howett NM PS 19680

SCALE: 1" = 100'
0 50 100
BEARINGS ARE
NAD 83 GRID - NM EAST
DISTANCES ARE GROUND



Copyright 2016 - All Rights Reserved

NO.	REVISION	DATE
JOB NO.:	LS19050599	
DWG. NO.:	19050599-4	



701 S. CECIL ST., HOBBS, NM 88240 (575) 964-8200

SCALE: 1" = 100'
DATE: 05-17-2019
SURVEYED BY: ML/JC
DRAWN BY: KAKN
APPROVED BY: RMH
SHEET: 1 OF 1



U.S. Department of the Interior
BUREAU OF LAND MANAGEMENT

PWD Data Report

05/10/2024

APD ID: 10400085709

Submission Date: 06/24/2022

Operator Name: MEWBOURNE OIL COMPANY

Well Name: LITTLE RASCALS 17/18 W0IL FED COM

Well Number: 2H

Well Type: CONVENTIONAL GAS WELL

Well Work Type: Drill

Section 1 - General

Would you like to address long-term produced water disposal? NO

Section 2 - Lined

Would you like to utilize Lined Pit PWD options? N

Produced Water Disposal (PWD) Location:

PWD surface owner:

PWD disturbance (acres):

Lined pit PWD on or off channel:

Lined pit PWD discharge volume (bbl/day):

Lined pit

Pit liner description:

Pit liner manufacturers

Precipitated solids disposal:

Describe precipitated solids disposal:

Precipitated solids disposal

Lined pit precipitated solids disposal schedule:

Lined pit precipitated solids disposal schedule

Lined pit reclamation description:

Lined pit reclamation

Leak detection system description:

Leak detection system

Operator Name: MEWBOURNE OIL COMPANY

Well Name: LITTLE RASCALS 17/18 W01L FED COM

Well Number: 2H

Lined pit Monitor description:

Lined pit Monitor

Lined pit: do you have a reclamation bond for the pit?

Is the reclamation bond a rider under the BLM bond?

Lined pit bond number:

Lined pit bond amount:

Additional bond information

Section 3 - Unlined

Would you like to utilize Unlined Pit PWD options? N

Produced Water Disposal (PWD) Location:

PWD disturbance (acres):

PWD surface owner:

Unlined pit PWD on or off channel:

Unlined pit PWD discharge volume (bbl/day):

Unlined pit

Precipitated solids disposal:

Describe precipitated solids disposal:

Precipitated solids disposal

Unlined pit precipitated solids disposal schedule:

Unlined pit precipitated solids disposal schedule

Unlined pit reclamation description:

Unlined pit reclamation

Unlined pit Monitor description:

Unlined pit Monitor

Do you propose to put the produced water to beneficial use?

Beneficial use user

Estimated depth of the shallowest aquifer (feet):

Does the produced water have an annual average Total Dissolved Solids (TDS) concentration equal to or less than that of the existing water to be protected?

TDS lab results:

Geologic and hydrologic

State

Unlined Produced Water Pit Estimated

Unlined pit: do you have a reclamation bond for the pit?

Operator Name: MEWBOURNE OIL COMPANY**Well Name:** LITTLE RASCALS 17/18 W0IL FED COM**Well Number:** 2H**Is the reclamation bond a rider under the BLM bond?****Unlined pit bond number:****Unlined pit bond amount:****Additional bond information****Section 4 -****Would you like to utilize Injection PWD options?** N**Produced Water Disposal (PWD) Location:****PWD surface owner:****PWD disturbance (acres):****Injection PWD discharge volume (bbl/day):****Injection well mineral owner:****Injection well type:****Injection well number:****Injection well name:****Assigned injection well API number?****Injection well API number:****Injection well new surface disturbance (acres):****Minerals protection information:****Mineral protection****Underground Injection Control (UIC) Permit?****UIC Permit****Section 5 - Surface****Would you like to utilize Surface Discharge PWD options?** N**Produced Water Disposal (PWD) Location:****PWD surface owner:****PWD disturbance (acres):****Surface discharge PWD discharge volume (bbl/day):****Surface Discharge NPDES Permit?****Surface Discharge NPDES Permit attachment:****Surface Discharge site facilities information:****Surface discharge site facilities map:****Section 6 -****Would you like to utilize Other PWD options?** N**Produced Water Disposal (PWD) Location:****PWD surface owner:****PWD disturbance (acres):****Other PWD discharge volume (bbl/day):**

Operator Name: MEWBOURNE OIL COMPANY

Well Name: LITTLE RASCALS 17/18 W0IL FED COM

Well Number: 2H

Other PWD type description:

Other PWD type

Have other regulatory requirements been met?

Other regulatory requirements



U.S. Department of the Interior
BUREAU OF LAND MANAGEMENT

Bond Info Data

05/10/2024

APD ID: 10400085709

Submission Date: 06/24/2022

Operator Name: MEWBOURNE OIL COMPANY

Well Name: LITTLE RASCALS 17/18 W0IL FED COM

Well Number: 2H

Well Type: CONVENTIONAL GAS WELL

Well Work Type: Drill

Highlighted data
reflects the most
recent changes
[Show Final Text](#)

Bond

Federal/Indian APD: FED

BLM Bond number: NM 1693

BIA Bond number:

Do you have a reclamation bond? NO

Is the reclamation bond a rider under the BLM bond?

Is the reclamation bond BLM or Forest Service?

BLM reclamation bond number:

Forest Service reclamation bond number:

Forest Service reclamation bond

Reclamation bond number:

Reclamation bond amount:

Reclamation bond rider amount:

Additional reclamation bond information

District I
1625 N. French Dr., Hobbs, NM 88240
Phone: (575) 393-6161 Fax: (575) 393-0720
District II
811 S. First St., Artesia, NM 88210
Phone: (575) 748-1283 Fax: (575) 748-9720
District III
1000 Rio Brazos Road, Aztec, NM 87410
Phone: (505) 334-6178 Fax: (505) 334-6170
District IV
1220 S. St. Francis Dr., Santa Fe, NM 87505
Phone: (505) 476-3460 Fax: (505) 476-3462

State of New Mexico
Energy, Minerals & Natural Resources Department
OIL CONSERVATION DIVISION
1220 South St. Francis Dr.
Santa Fe, NM 87505

Form C-102
Revised August 1, 2011
Submit one copy to appropriate
District Office

☐ AMENDED REPORT

WELL LOCATION AND ACREAGE DEDICATION PLAT

¹ API Number 30-015-55067		² Pool Code 98220		³ Pool Name PURPLE SAGE WOLFCAMP					
⁴ Property Code 335899		⁵ Property Name LITTLE RASCALS 17/18 WOIL FED COM						⁶ Well Number 2H	
⁷ OGRID NO. 14744		⁸ Operator Name MEWBOURNE OIL COMPANY						⁹ Elevation 3078'	
¹⁰ Surface Location									
UL or lot no. P	Section 17	Township 22S	Range 28E	Lot Idn	Feet from the 940	North/South line SOUTH	Feet From the 205	East/West line EAST	County EDDY
¹¹ Bottom Hole Location If Different From Surface									
UL or lot no. 10	Section 18	Township 22S	Range 28E	Lot Idn	Feet from the 1340	North/South line SOUTH	Feet from the 330	East/West line WEST	County EDDY
¹² Dedicated Acres 640		¹³ Joint or Infill		¹⁴ Consolidation Code		¹⁵ Order No.			

No allowable will be assigned to this completion until all interest have been consolidated or a non-standard unit has been approved by the division.

¹⁶ GEODETIC DATA NAD 83 GRID - NM EAST ¹⁷ SURFACE LOCATION N: 504945.4 - E: 612744.9 LAT: 32.3879513° N LONG: 104.1019989° W ¹⁸ BOTTOM HOLE N: 505383.1 - E: 603031.5 LAT: 32.3892085° N LONG: 104.1334641° W ¹⁹ CORNER DATA NAD 83 GRID - NM EAST A: FOUND BRASS CAP "1916" N: 504054.4 - E: 602698.6 B: FOUND BRASS CAP "1916" N: 506707.9 - E: 602704.7		C: FOUND BRASS CAP "1916" N: 509363.5 - E: 602706.8 D: FOUND BRASS CAP "1943" N: 509311.6 - E: 607636.8 E: FOUND BRASS CAP "1943" N: 509316.0 - E: 610289.4 F: FOUND BRASS CAP "1943" N: 509353.8 - E: 612951.3 G: FOUND BRASS CAP "1943" N: 506679.8 - E: 612950.3 H: FOUND BRASS CAP "1943" N: 504006.3 - E: 612949.6 I: FOUND BRASS CAP "1943" N: 503997.0 - E: 610302.1 J: FOUND BRASS CAP "1943" N: 503984.6 - E: 607656.7		K: FOUND BRASS CAP "1943" N: 503977.8 - E: 605000.8 L: FOUND BRASS CAP "1943" N: 506648.9 - E: 607647.2 ²⁰ LOT ACREAGE LOT 5: 36.06 AC. LOT 6: 34.85 AC. LOT 7: 35.81 AC. LOT 8: 36.98 AC. LOT 9: 37.77 AC. LOT 10: 36.69 AC. LOT 11: 37.61 AC. LOT 12: 38.66 AC		²¹ OPERATOR CERTIFICATION I hereby certify that the information contained herein is true and complete to the best of my knowledge and belief, and that this organization either owns a working interest or unleased mineral interest in the land including the proposed bottom hole location or has a right to drill this well at this location pursuant to a contract with an owner of such a mineral or working interest, or to a voluntary pooling agreement or a compulsory pooling order heretofore entered by the division. Signature <u>Bradley Bishop</u> Date <u>6-21-19</u> Printed Name <u>BRADLEY BISHOP</u> E-mail Address <u>BBISHOP@MEWBOURNE.COM</u>	
²² SURVEYOR CERTIFICATION I hereby certify that the well location shown on this plat was plotted from field notes of actual surveys made by me or under my supervision, and that the same is true and correct to the best of my belief. <u>05-17-2019</u> Date of Survey Signature and Seal of Professional Surveyor <u>Robert M. Howett</u> ²³ 19680 Certificate Number							

PROJECT AREA (Red outline) and **PRODUCING AREA** (Blue outline) are shown on the plat. The plat includes lot numbers 6 through 12 and various survey measurements.

RRC-Job No: LS19050599

Page 5

State of New Mexico
Energy, Minerals and Natural Resources Department

Submit Electronically
Via E-permitting

Oil Conservation Division
1220 South St. Francis Dr.
Santa Fe, NM 87505

NATURAL GAS MANAGEMENT PLAN

This Natural Gas Management Plan must be submitted with each Application for Permit to Drill (APD) for a new or recompleted well.

Section 1 – Plan Description

Effective May 25, 2021

I. Operator: Mewbourne Oil Co. **OGRID:** 14744 **Date:** 5/2/22

II. Type: ☒ Original ☐ Amendment due to ☐ 19.15.27.9.D(6)(a) NMAC ☐ 19.15.27.9.D(6)(b) NMAC ☐ Other.

If Other, please describe: _____

III. Well(s): Provide the following information for each new or recompleted well or set of wells proposed to be drilled or proposed to be recompleted from a single well pad or connected to a central delivery point.

Well Name	API	ULSTR	Footages	Anticipated Oil BBL/D	Anticipated Gas MCF/D	Anticipated Produced Water BBL/D
Little Rascals 17/18 W0IL Fed Com #2H		P 17 22S 28E	940' FSL x 205' FEL	2000	1500	1000

IV. Central Delivery Point Name: Little Rascals 17/18 W0IL Fed Com #2H [See 19.15.27.9(D)(1) NMAC]

V. Anticipated Schedule: Provide the following information for each new or recompleted well or set of wells proposed to be drilled or proposed to be recompleted from a single well pad or connected to a central delivery point.

Well Name	API	Spud Date	TD Reached Date	Completion Commencement Date	Initial Flow Back Date	First Production Date
Little Rascals 17/18 W0IL Fed Com #2H		7/2/22	8/2/22	9/2/22	9/17/22	9/17/22

VI. Separation Equipment: ☒ Attach a complete description of how Operator will size separation equipment to optimize gas capture.

VII. Operational Practices: ☒ Attach a complete description of the actions Operator will take to comply with the requirements of Subsection A through F of 19.15.27.8 NMAC.

VIII. Best Management Practices: ☒ Attach a complete description of Operator's best management practices to minimize venting during active and planned maintenance.

Section 2 – Enhanced Plan
EFFECTIVE APRIL 1, 2022

Beginning April 1, 2022, an operator that is not in compliance with its statewide natural gas capture requirement for the applicable reporting area must complete this section.

☒ Operator certifies that it is not required to complete this section because Operator is in compliance with its statewide natural gas capture requirement for the applicable reporting area.

IX. Anticipated Natural Gas Production:

Well	API	Anticipated Average Natural Gas Rate MCF/D	Anticipated Volume of Natural Gas for the First Year MCF

X. Natural Gas Gathering System (NGGS):

Operator	System	ULSTR of Tie-in	Anticipated Gathering Start Date	Available Maximum Daily Capacity of System Segment Tie-in

XI. Map. ☐ Attach an accurate and legible map depicting the location of the well(s), the anticipated pipeline route(s) connecting the production operations to the existing or planned interconnect of the natural gas gathering system(s), and the maximum daily capacity of the segment or portion of the natural gas gathering system(s) to which the well(s) will be connected.

XII. Line Capacity. The natural gas gathering system ☐ will ☐ will not have capacity to gather 100% of the anticipated natural gas production volume from the well prior to the date of first production.

XIII. Line Pressure. Operator ☐ does ☐ does not anticipate that its existing well(s) connected to the same segment, or portion, of the natural gas gathering system(s) described above will continue to meet anticipated increases in line pressure caused by the new well(s).

☐ Attach Operator's plan to manage production in response to the increased line pressure.

XIV. Confidentiality: ☐ Operator asserts confidentiality pursuant to Section 71-2-8 NMSA 1978 for the information provided in Section 2 as provided in Paragraph (2) of Subsection D of 19.15.27.9 NMAC, and attaches a full description of the specific information for which confidentiality is asserted and the basis for such assertion.

Section 3 - Certifications**Effective May 25, 2021**

Operator certifies that, after reasonable inquiry and based on the available information at the time of submittal:

☒ Operator will be able to connect the well(s) to a natural gas gathering system in the general area with sufficient capacity to transport one hundred percent of the anticipated volume of natural gas produced from the well(s) commencing on the date of first production, taking into account the current and anticipated volumes of produced natural gas from other wells connected to the pipeline gathering system; or

☐ Operator will not be able to connect to a natural gas gathering system in the general area with sufficient capacity to transport one hundred percent of the anticipated volume of natural gas produced from the well(s) commencing on the date of first production, taking into account the current and anticipated volumes of produced natural gas from other wells connected to the pipeline gathering system.

If Operator checks this box, Operator will select one of the following:

Well Shut-In. ☐ Operator will shut-in and not produce the well until it submits the certification required by Paragraph (4) of Subsection D of 19.15.27.9 NMAC; or

Venting and Flaring Plan. ☐ Operator has attached a venting and flaring plan that evaluates and selects one or more of the potential alternative beneficial uses for the natural gas until a natural gas gathering system is available, including:

- (a) power generation on lease;
- (b) power generation for grid;
- (c) compression on lease;
- (d) liquids removal on lease;
- (e) reinjection for underground storage;
- (f) reinjection for temporary storage;
- (g) reinjection for enhanced oil recovery;
- (h) fuel cell production; and
- (i) other alternative beneficial uses approved by the division.

Section 4 - Notices

1. If, at any time after Operator submits this Natural Gas Management Plan and before the well is spud:

(a) Operator becomes aware that the natural gas gathering system it planned to connect the well(s) to has become unavailable or will not have capacity to transport one hundred percent of the production from the well(s), no later than 20 days after becoming aware of such information, Operator shall submit for OCD's approval a new or revised venting and flaring plan containing the information specified in Paragraph (5) of Subsection D of 19.15.27.9 NMAC; or

(b) Operator becomes aware that it has, cumulatively for the year, become out of compliance with its baseline natural gas capture rate or natural gas capture requirement, no later than 20 days after becoming aware of such information, Operator shall submit for OCD's approval a new or revised Natural Gas Management Plan for each well it plans to spud during the next 90 days containing the information specified in Paragraph (2) of Subsection D of 19.15.27.9 NMAC, and shall file an update for each Natural Gas Management Plan until Operator is back in compliance with its baseline natural gas capture rate or natural gas capture requirement.

2. OCD may deny or conditionally approve an APD if Operator does not make a certification, fails to submit an adequate venting and flaring plan which includes alternative beneficial uses for the anticipated volume of natural gas produced, or if OCD determines that Operator will not have adequate natural gas takeaway capacity at the time a well will be spud.

Page 8

I certify that, after reasonable inquiry, the statements in and attached to this Natural Gas Management Plan are true and correct to the best of my knowledge and acknowledge that a false statement may be subject to civil and criminal penalties under the Oil and Gas Act.

Signature:	<i>Bradley Bishop</i>
Printed Name:	BRADLEY BISHOP
Title:	REGULATORY MANAGER
E-mail Address:	BBISHOP@MEWBOURNE.COM
Date:	5/2/22
Phone:	575-393-5905
OIL CONSERVATION DIVISION (Only applicable when submitted as a standalone form)	
Approved By:	
Title:	
Approval Date:	
Conditions of Approval:	

Mewbourne Oil Company

Natural Gas Management Plan – Attachment

- VI. Separation equipment will be sized by construction engineering staff based on stated manufacturer daily throughput capacities and anticipated daily production rates to ensure adequate capacity. Closed vent system piping, compression needs, and VRUs will be sized utilizing ProMax modelling software to ensure adequate capacity for anticipated production volumes and conditions.
- VII. Mewbourne Oil Company (MOC) will take following actions to comply with the regulations listed in 19.15.27.8 :
- A. MOC will maximize the recovery of natural gas by minimizing the waste, as defined by 19.15.2 NMAC, of natural gas through venting and flaring. MOC will ensure that well(s) will be connected to a natural gas gathering system with sufficient capacity to transport natural gas. If there is no adequate takeaway for the gas, well(s) will be shut in until the natural gas gathering system is available.
 - B. All drilling operations will be equipped with a rig flare located at least 100 ft from the nearest surface hole. Rig flare will be utilized to combust any natural gas that is brought to surface during normal drilling operations. In the case of emergency venting or flaring the volumes will be estimated and reported appropriately.
 - C. During completion operations any natural gas brought to surface will be flared. Immediately following the finish of completion operations, all well flow will be directed to permanent separation equipment. Produced natural gas from separation equipment will be sent to sales. It is not anticipated that gas will not meet pipeline standards. However, if natural gas does not meet gathering pipeline quality specifications, MOC will flare the natural gas for 60 days or until the natural gas meets the pipeline quality specifications, whichever is sooner. MOC will ensure that the flare is sized properly and is equipped with automatic igniter or continuous pilot. The gas sample will analyzed twice per week and the gas will be routed into a gathering system as soon as pipeline specifications are met.
 - D. Natural gas will not be flared with the exceptions and provisions listed in the 19.15.27.8 D.(1) through (4). If there is no adequate takeaway for the separator gas, well(s) will be shut in until the natural gas gathering system is available with exception of emergency or malfunction situations. Venting and/or flaring volumes will be estimated and reported appropriately.
 - E. MOC will comply with the performance standards requirements and provisions listed in 19.15.27.8 E.(1) through (8). All equipment will be designed and sized to handle maximum anticipated pressures and throughputs in order to minimize the waste. Production storage tanks constructed after May 25, 2021 will be equipped with automatic gauging system. Flares constructed after May 25, 2021 will be equipped with automatic igniter or continuous pilot. Flares will be located at least 100' from the well and storage tanks unless otherwise approved by the division. MOC will conduct AVO inspections as described in 19.15.27.8 E (5) (a) with frequencies specified in 19.15.27.8 E (5) (b) and (c). All emergencies will be resolved as quickly and safely as feasible to minimize waste.
 - F. The volume of natural gas that is vented or flared as the result of malfunction or emergency during drilling and completions operations will be estimated. The volume of natural gas that is vented, flared or beneficially used during production operations, will be measured or estimated. MOC will install equipment to measure

the volume of natural gas flared from existing process piping or a flowline piped from equipment such as high pressure separators, heater treaters, or vapor recovery units associated with a well or facility associated with a well authorized by an APD issued after May 25, 2021 that has an average daily production greater than 60 Mcf/day. If metering is not practicable due to circumstances such as low flow rate or low pressure venting and flaring, MOC will estimate the volume of vented or flared natural gas. Measuring equipment will conform to industry standards and will not be designed or equipped with a manifold that allows the diversion of natural gas around the metering element except for the sole purpose of inspecting and servicing the measurement equipment.

- VIII. For maintenance activities involving production equipment and compression, venting will be limited to the depressurization of the subject equipment to ensure safe working conditions. For maintenance of production and compression equipment the associated producing wells will be shut in to eliminate venting. For maintenance of VRUs all gas normally routed to the VRU will be routed to flare to eliminate venting.



U.S. Department of the Interior
BUREAU OF LAND MANAGEMENT

Drilling Plan Data Report

05/10/2024

APD ID: 10400085709

Submission Date: 06/24/2022

Highlighted data
reflects the most
recent changes

Operator Name: MEWBOURNE OIL COMPANY

Well Name: LITTLE RASCALS 17/18 W01L FED COM

Well Number: 2H

Well Type: CONVENTIONAL GAS WELL

Well Work Type: Drill

[Show Final Text](#)

Section 1 - Geologic Formations

Formation ID	Formation Name	Elevation	True Vertical	Measured Depth	Lithologies	Mineral Resources	Producing Formatio
13409999	UNKNOWN	3078	28	28	OTHER : Top Soil	NONE	N
13410012	TOP SALT	2293	785	785	SALT	NONE	N
13410000	BOTTOM SALT	828	2250	2250	SALT	NONE	N
13410005	LAMAR	578	2500	2500	LIMESTONE	NATURAL GAS, OIL	N
13410010	BELL CANYON	498	2580	2580	SANDSTONE	NATURAL GAS, OIL	N
13410013	CHERRY CANYON	-272	3350	3350	SANDSTONE	NATURAL GAS, OIL	N
13410014	MANZANITA	-422	3500	3500	LIMESTONE	NATURAL GAS, OIL	N
13409998	BONE SPRING	-2922	6000	6000	LIMESTONE, SHALE	NATURAL GAS, OIL	N
13410001	BONE SPRING 1ST	-3882	6960	6960	SANDSTONE	NATURAL GAS, OIL	N
13410002	BONE SPRING 2ND	-4562	7640	7640	SANDSTONE	NATURAL GAS, OIL	N
13410018	BONE SPRING 3RD	-5852	8930	8930	SANDSTONE	NATURAL GAS, OIL	N
13410019	WOLFCAMP	-6182	9260	9260	LIMESTONE, SANDSTONE, SHALE	NATURAL GAS, OIL	Y

Section 2 - Blowout Prevention

Pressure Rating (PSI): 5M

Rating Depth: 19174

Equipment: Annular, Pipe Ram, Blind Ram

Requesting Variance? YES

Variance request: A variance is requested for the use of a flexible choke line from the BOP to the choke manifold. Anchors are not required by manufacturer. A variance is also requested for the use of a multibowl wellhead. Please see attached schematics.

Operator Name: MEWBOURNE OIL COMPANY**Well Name:** LITTLE RASCALS 17/18 W0IL FED COM**Well Number:** 2H

Testing Procedure: BOP/BOPE will be tested by an independent service company to 250 psi low and the high pressure indicated above per Onshore Order 2 requirements. The System may be upgraded to a higher pressure but still tested to the working pressure listed in the table above. If the system is upgraded all the components installed will be functional and tested. Pipe rams will be operationally checked each 24 hour period. Blind rams will be operationally checked on each trip out of the hole. These checks will be noted on the daily tour sheets. Other accessories to the BOP equipment will include a Kelly cock and floor safety valve (inside BOP) and choke lines and choke manifold. See attached schematics.

Choke Diagram Attachment:

Little_Rascals_17_18_W0IL_Fed_Com_2H_5M_BOPE_Choke_Diagram_20220613095731.pdf

Little_Rascals_17_18_W0IL_Fed_Com_2H_Flex_Line_Specs_20220613095731.pdf

Little_Rascals_17_18_W0IL_Fed_Com_2H_Flex_Line_Specs_API_16C_20220613095732.pdf

BOP Diagram Attachment:

Little_Rascals_17_18_W0IL_Fed_Com_2H_5M_BOPE_Schematic_20220613095738.pdf

Little_Rascals_17_18_W0IL_Fed_Com_2H_5M_Mutli_Bowl_WH_20220613095739.pdf

Section 3 - Casing

Casing ID	String Type	Hole Size	Csg Size	Condition	Standard	Tapered String	Top Set MD	Bottom Set MD	Top Set TVD	Bottom Set TVD	Top Set MSL	Bottom Set MSL	Calculated casing length MD	Grade	Weight	Joint Type	Collapse SF	Burst SF	Joint SF Type	Joint SF	Body SF Type	Body SF
1	SURFACE	17.5	13.375	NEW	API	N	0	735	0	735	3106	2371	735	H-40	48	ST&C	2.29	5.14	DRY	9.13	DRY	15.33
2	INTERMEDIATE	12.25	9.625	NEW	API	N	0	2425	0	2425	3713	681	2425	J-55	36	LT&C	1.6	2.79	DRY	5.19	DRY	6.46
3	PRODUCTION	8.75	7.0	NEW	API	N	0	9590	0	9433	3713	-6327	9590	HCP-110	26	LT&C	1.32	1.68	DRY	2.78	DRY	3.33
4	LINER	6.125	4.5	NEW	API	N	8978	19173	8963	9326	-5857	-6220	10195	P-110	13.5	LT&C	1.67	1.94	DRY	2.46	DRY	3.07

Casing Attachments

Operator Name: MEWBOURNE OIL COMPANY**Well Name:** LITTLE RASCALS 17/18 W0IL FED COM**Well Number:** 2H**Casing Attachments**

Casing ID: 1 **String** SURFACE**Inspection Document:****Spec Document:****Tapered String Spec:**

Sand_Chute_4_B2AP_Fed_Com_1H__Surf_Tapered_String_Diagram_20180223140851.pdf

Casing Design Assumptions and Worksheet(s):Little_Rascals_17_18_W0IL_Fed_Com_2H_Csg_Assumptions_20220613100427.pdf

Casing ID: 2 **String** INTERMEDIATE**Inspection Document:****Spec Document:****Tapered String Spec:**

Sand_Chute_4_B2AP_Fed_Com_1H_Inter_Tapered_String_Diagram_20180223140923.pdf

Casing Design Assumptions and Worksheet(s):Little_Rascals_17_18_W0IL_Fed_Com_2H_Csg_Assumptions_20220613100438.pdf

Casing ID: 3 **String** PRODUCTION**Inspection Document:****Spec Document:****Tapered String Spec:****Casing Design Assumptions and Worksheet(s):**Little_Rascals_17_18_W0IL_Fed_Com_2H_Csg_Assumptions_20220613100450.pdf

Operator Name: MEWBOURNE OIL COMPANY

Well Name: LITTLE RASCALS 17/18 W0IL FED COM

Well Number: 2H

Casing Attachments

Casing ID: 4 String LINER

Inspection Document:

Spec Document:

Tapered String Spec:

Casing Design Assumptions and Worksheet(s):

Little_Rascals_17_18_W0IL_Fed_Com_2H_Csg_Assumptions_20220613100411.pdf

Section 4 - Cement

String Type	Lead/Tail	Stage Tool Depth	Top MD	Bottom MD	Quantity(sx)	Yield	Density	Cu Ft	Excess%	Cement type	Additives
SURFACE	Lead		0	398	360	2.12	12.5	763	100	Class C	Salt, Gel, Extender, LCM
SURFACE	Tail		285	735	200	1.34	14.8	268	100	Class C	Retarder
INTERMEDIATE	Lead		0	1617	320	2.12	12.5	678	25	Class C	Salt, Gel, Extender, LCM
INTERMEDIATE	Tail		1617	2425	200	1.34	14.8	268	25	Class C	Retarder
PRODUCTION	Lead	3500	2225	2609	50	2.12	12.5	106	25	Class C	Gel, Retarder, Defoamer, Extender
PRODUCTION	Tail		2609	3500	100	1.34	14.8	134	25	Class C	Gel, Retarder, Defoamer, Extender
PRODUCTION	Lead	3500	3500	6503	320	2.12	12.5	678	25	Class C	Gel, Retarder, Defoamer, Extender
PRODUCTION	Tail		6503	9590	400	1.18	15.6	472	25	Class H	Retarder, Fluid Loss, Defoamer
LINER	Lead		8978	19173	410	2.97	11.2	1218	25	Class C	Salt, Gel, Fluid Loss, Retarder, Dispersant, Defoamer, Anti-Settling Agent

Operator Name: MEWBOURNE OIL COMPANY

Well Name: LITTLE RASCALS 17/18 W0IL FED COM

Well Number: 2H

Section 5 - Circulating Medium

Mud System Type: Closed

Will an air or gas system be Used? NO

Description of the equipment for the circulating system in accordance with Onshore Order #2:

Diagram of the equipment for the circulating system in accordance with Onshore Order #2:

Describe what will be on location to control well or mitigate other conditions: Lost circulation material Sweeps Mud scavengers in surface hole

Describe the mud monitoring system utilized: Visual monitoring

Circulating Medium Table

Top Depth	Bottom Depth	Mud Type	Min Weight (lbs/gal)	Max Weight (lbs/gal)	Density (lbs/cu ft)	Gel Strength (lbs/100 sqft)	PH	Viscosity (CP)	Salinity (ppm)	Filtration (cc)	Additional Characteristics
0	735	SPUD MUD	8.6	8.8							
735	2425	SALT SATURATED	10	10							
2425	9590	WATER-BASED MUD	8.5	9.5							
9590	19173	OIL-BASED MUD	10	12							

Section 6 - Test, Logging, Coring

List of production tests including testing procedures, equipment and safety measures:

Pason/PVT/Visual Monitoring. Will run GR/CNL from KOP (8978') to surface (horizontal well vertical portion of hole). Stated logs run will be in the Completion Report and submitted to the BLM.

List of open and cased hole logs run in the well:

COMPENSATED NEUTRON LOG,DIRECTIONAL SURVEY,GAMMA RAY LOG,MEASUREMENT WHILE DRILLING,MUD LOG/GEOLOGIC LITHOLOGY LOG,

Coring operation description for the well:

None

Operator Name: MEWBOURNE OIL COMPANY

Well Name: LITTLE RASCALS 17/18 W0IL FED COM

Well Number: 2H

Section 7 - Pressure

Anticipated Bottom Hole Pressure: 6151

Anticipated Surface Pressure: 4076

Anticipated Bottom Hole Temperature(F): 150

Anticipated abnormal pressures, temperatures, or potential geologic hazards? NO

Describe:

Contingency Plans geohazards description:

Contingency Plans geohazards

Hydrogen Sulfide drilling operations plan required? YES

Hydrogen sulfide drilling operations

Little_Rascals_17_18_W0IL_Fed_Com_2H_H2S_Plan_20220613101353.pdf

Section 8 - Other Information

Proposed horizontal/directional/multi-lateral plan submission:

Little_Rascals_17_18_W0IL_Fed_Com_2H_Dir_plan_20220613101820.pdf

Little_Rascals_17_18_W0IL_Fed_Com_2H_Dir_plot_20220613101820.pdf

Other proposed operations facets description:


Other proposed operations facets attachment:

Little_Rascals_17_18_W0IL_Fed_Com_2H_Add_Info_20220613101836.pdf

Little_Rascals_17_18_W0IL_Fed_Com_2H_Drlg_Program_20220613101848.pdf

Other Variance attachment:

5M BOPE & Closed Loop Equipment Schematic



Drawing not to scale



GATES E & S NORTH AMERICA, INC.
134 44TH STREET
CORPUS CHRISTI, TEXAS 78405

PHONE: 361-887-9807
FAX: 361-887-0812
EMAIL: Tim.Cantu@gates.com
WEB: www.gates.com

10K CEMENTING ASSEMBLY PRESSURE TEST CERTIFICATE

Customer :	AUSTIN DISTRIBUTING	Test Date:	4/30/2015
Customer Ref. :	4060578	Hose Serial No.:	D-043015-7
Invoice No. :	500506	Created By:	JUSTIN CROPPER
Product Description:	10K3.548.0CK4.1/1610KFLGE/E LE		
End Fitting 1 :	4 1/16 10K FLG	End Fitting 2 :	4 1/16 10K FLG
Gates Part No. :	4773-6290	Assembly Code :	L36554102914D-043015-7
Working Pressure :	10,000 PSI	Test Pressure :	15,000 PSI

Gates E & S North America, Inc. certifies that the following hose assembly has been tested to the Gates Oilfield Roughneck Agreement/Specification requirements and passed the 15 minute hydrostatic test per API Spec 7K/Q1, Fifth Edition, June 2010, Test pressure 9.6.7 and per Table 9 to 15,000 psi in accordance with this product number. Hose burst pressure 9.6.7.2 exceeds the minimum of 2.5 times the working pressure per Table 9.

Quality Manager :

Date :

Signature :

QUALITY
4/30/2015
<i>Justin Cropper</i>

Production:


Date :

Signature :

PRODUCTION
4/30/2015
<i>Justin Cropper</i>

Form PTC - 01 Rev.02







GATES ENGINEERING & SERVICES NORTH AMERICA
7603 Prairie Oak Dr.
Houston, TX 77086

PHONE: (281) 602 - 4119
FAX:
EMAIL: Troy.Schmidt@gates.com
WEB: www.gates.com

10K CHOKE & KILL ASSEMBLY PRESSURE TEST CERTIFICATE

Customer:	A-7 AUSTIN INC DBA AUSTIN HOSE	Test Date:	8/20/2018
Customer Ref.:	4101901	Hose Serial No.:	H-082018-10
Invoice No.:	511956	Created By:	Moosa Naqvi
Product Description:	10KF3.035.0CK41/1610KFLGFXDxFLT L/E		
End Fitting 1:	4 1/16 in. Fixed Flange	End Fitting 2:	4 1/16 in. Float Flange
Gates Part No.:	68503010-9721632	Assembly Code:	L40695052218H-082018-10
Working Pressure:	10,000 psi.	Test Pressure:	15,000 psi.



Gates Engineering & Services North America certifies that the following hose assembly has successfully passed all pressure testing requirements set forth in Gates specifications: GTS-04-052 (for 5K assemblies) or GTS-04-053 (10K assemblies), which include reference to Specification API 16C (2nd Edition); sections 7.5.4, 7.5.9, and 10.8.7. A test graph will accompany this test certificate to illustrate conformity to test requirements.

Quality:	QUALITY	Production:	PRODUCTION
Date :	8/20/2018	Date :	8/20/2018
Signature :		Signature :	

Form PTC - 01 Rev.0 2




Hydril "GK"
13 5/8" 5M




Hydril "GK"


Cameron Type U
13 5/8" 5M



4 1/2" x 5 7/8" VBR




BLIND RAMS



MUD CROSS

H.C.R.




7" RAMS



13 5/8" 5M

13 5/8" 5M

13 5/8" 5M





13-5/8" MN-DS Wellhead System




C7585
Rev. 02

NOTE: All dimensions on this drawing are estimated measurements and should be evaluated by engineering.


Cuffing Hanger 57" conductor cut-off

Sand Chute 4 B2AP Fed Com #1H
Surface Csg



Casing	SF Collapse	SF Burst	SF Jt Tension	SF Body Tension
48# H-40	1.13	2.53	3.11	7.71
54.5# J-55	1.16	2.81	15.4	25.55

Sand Chute 4 B2AP Fed Com #1H
Intermediate Casing



Casing	SF Collapse	SF Burst	SF Jt Tension	SF Body Tension
36# J-55	1.13	1.96	1.92	4.54
40# J-55	1.13	1.73	4.67	16.75
40# N-80	1.13	2.09	10.00	25.76
40# HCL-80	1.30	1.77	21.96	24.03

Mewbourne Oil Company, Little Rascals 17/18 W01L Fed Com #2H**Sec 17, T22S, R28E****SL: 940' FSL & 205' FEL, Sec 17****BHL: 1340' FSL & 330' FWL, Sec 18****2. Casing Program**

Hole Size	Casing Interval		Csg. Size	Weight (lbs)	Grade	Conn.	SF Collapse	SF Burst	SF Jt Tension	SF Body Tension
	From	To								
17.5"	0'	735'	13.375"	48	H40	STC	2.29	5.14	9.13	15.33
12.25"	0'	2425'	9.625"	36	J55	LTC	1.6	2.79	5.19	6.46
8.75"	0'	9590'	7"	26	HCP110	LTC	1.32	1.68	2.78	3.33
6.125"	8978'	19173'	4.5"	13.5	P110	LTC	1.91	2.22	2.46	3.07
				BLM Minimum Safety Factor			1.125	1	1.6 Dry 1.8 Wet	1.6 Dry 1.8 Wet

All casing strings will be tested in accordance with Onshore Oil and Gas Order #2 III.B.1.h
Must have table for contingency casing

	Y or N
Is casing new? If used, attach certification as required in Onshore Order #1	Y
Is casing API approved? If no, attach casing specification sheet.	Y
Is premium or uncommon casing planned? If yes attach casing specification sheet.	N
Does the above casing design meet or exceed BLM's minimum standards? If not provide justification (loading assumptions, casing design criteria).	Y
Will the pipe be kept at a minimum 1/3 fluid filled to avoid approaching the collapse pressure rating of the casing?	Y
Is well located within Capitan Reef?	N
If yes, does production casing cement tie back a minimum of 50' above the Reef?	
Is well within the designated 4 string boundary.	
Is well located in SOPA but not in R-111-P?	N
If yes, are the first 2 strings cemented to surface and 3 rd string cement tied back 500' into previous casing?	
Is well located in R-111-P and SOPA?	N
If yes, are the first three strings cemented to surface?	
Is 2 nd string set 100' to 600' below the base of salt?	
Is well located in high Cave/Karst?	N
If yes, are there two strings cemented to surface?	
(For 2 string wells) If yes, is there a contingency casing if lost circulation occurs?	
Is well located in critical Cave/Karst?	N
If yes, are there three strings cemented to surface?	

Mewbourne Oil Company, Little Rascals 17/18 W01L Fed Com #2H**Sec 17, T22S, R28E****SL: 940' FSL & 205' FEL, Sec 17****BHL: 1340' FSL & 330' FWL, Sec 18****2. Casing Program**

Hole Size	Casing Interval		Csg. Size	Weight (lbs)	Grade	Conn.	SF Collapse	SF Burst	SF Jt Tension	SF Body Tension
	From	To								
17.5"	0'	735'	13.375"	48	H40	STC	2.29	5.14	9.13	15.33
12.25"	0'	2425'	9.625"	36	J55	LTC	1.6	2.79	5.19	6.46
8.75"	0'	9590'	7"	26	HCP110	LTC	1.32	1.68	2.78	3.33
6.125"	8978'	19173'	4.5"	13.5	P110	LTC	1.91	2.22	2.46	3.07
				BLM Minimum Safety Factor			1.125	1	1.6 Dry 1.8 Wet	1.6 Dry 1.8 Wet

All casing strings will be tested in accordance with Onshore Oil and Gas Order #2 III.B.1.h
Must have table for contingency casing

	Y or N
Is casing new? If used, attach certification as required in Onshore Order #1	Y
Is casing API approved? If no, attach casing specification sheet.	Y
Is premium or uncommon casing planned? If yes attach casing specification sheet.	N
Does the above casing design meet or exceed BLM's minimum standards? If not provide justification (loading assumptions, casing design criteria).	Y
Will the pipe be kept at a minimum 1/3 fluid filled to avoid approaching the collapse pressure rating of the casing?	Y
Is well located within Capitan Reef?	N
If yes, does production casing cement tie back a minimum of 50' above the Reef?	
Is well within the designated 4 string boundary.	
Is well located in SOPA but not in R-111-P?	N
If yes, are the first 2 strings cemented to surface and 3 rd string cement tied back 500' into previous casing?	
Is well located in R-111-P and SOPA?	N
If yes, are the first three strings cemented to surface?	
Is 2 nd string set 100' to 600' below the base of salt?	
Is well located in high Cave/Karst?	N
If yes, are there two strings cemented to surface?	
(For 2 string wells) If yes, is there a contingency casing if lost circulation occurs?	
Is well located in critical Cave/Karst?	N
If yes, are there three strings cemented to surface?	

Mewbourne Oil Company, Little Rascals 17/18 W01L Fed Com #2H**Sec 17, T22S, R28E****SL: 940' FSL & 205' FEL, Sec 17****BHL: 1340' FSL & 330' FWL, Sec 18****2. Casing Program**

Hole Size	Casing Interval		Csg. Size	Weight (lbs)	Grade	Conn.	SF Collapse	SF Burst	SF Jt Tension	SF Body Tension
	From	To								
17.5"	0'	735'	13.375"	48	H40	STC	2.29	5.14	9.13	15.33
12.25"	0'	2425'	9.625"	36	J55	LTC	1.6	2.79	5.19	6.46
8.75"	0'	9590'	7"	26	HCP110	LTC	1.32	1.68	2.78	3.33
6.125"	8978'	19173'	4.5"	13.5	P110	LTC	1.91	2.22	2.46	3.07
				BLM Minimum Safety Factor			1.125	1	1.6 Dry 1.8 Wet	1.6 Dry 1.8 Wet

All casing strings will be tested in accordance with Onshore Oil and Gas Order #2 III.B.1.h
Must have table for contingency casing

	Y or N
Is casing new? If used, attach certification as required in Onshore Order #1	Y
Is casing API approved? If no, attach casing specification sheet.	Y
Is premium or uncommon casing planned? If yes attach casing specification sheet.	N
Does the above casing design meet or exceed BLM's minimum standards? If not provide justification (loading assumptions, casing design criteria).	Y
Will the pipe be kept at a minimum 1/3 fluid filled to avoid approaching the collapse pressure rating of the casing?	Y
Is well located within Capitan Reef?	N
If yes, does production casing cement tie back a minimum of 50' above the Reef?	
Is well within the designated 4 string boundary.	
Is well located in SOPA but not in R-111-P?	N
If yes, are the first 2 strings cemented to surface and 3 rd string cement tied back 500' into previous casing?	
Is well located in R-111-P and SOPA?	N
If yes, are the first three strings cemented to surface?	
Is 2 nd string set 100' to 600' below the base of salt?	
Is well located in high Cave/Karst?	N
If yes, are there two strings cemented to surface?	
(For 2 string wells) If yes, is there a contingency casing if lost circulation occurs?	
Is well located in critical Cave/Karst?	N
If yes, are there three strings cemented to surface?	

Mewbourne Oil Company, Little Rascals 17/18 W01L Fed Com #2H**Sec 17, T22S, R28E****SL: 940' FSL & 205' FEL, Sec 17****BHL: 1340' FSL & 330' FWL, Sec 18****2. Casing Program**

Hole Size	Casing Interval		Csg. Size	Weight (lbs)	Grade	Conn.	SF Collapse	SF Burst	SF Jt Tension	SF Body Tension
	From	To								
17.5"	0'	735'	13.375"	48	H40	STC	2.29	5.14	9.13	15.33
12.25"	0'	2425'	9.625"	36	J55	LTC	1.6	2.79	5.19	6.46
8.75"	0'	9590'	7"	26	HCP110	LTC	1.32	1.68	2.78	3.33
6.125"	8978'	19173'	4.5"	13.5	P110	LTC	1.91	2.22	2.46	3.07
				BLM Minimum Safety Factor			1.125	1	1.6 Dry 1.8 Wet	1.6 Dry 1.8 Wet

All casing strings will be tested in accordance with Onshore Oil and Gas Order #2 III.B.1.h
Must have table for contingency casing

	Y or N
Is casing new? If used, attach certification as required in Onshore Order #1	Y
Is casing API approved? If no, attach casing specification sheet.	Y
Is premium or uncommon casing planned? If yes attach casing specification sheet.	N
Does the above casing design meet or exceed BLM's minimum standards? If not provide justification (loading assumptions, casing design criteria).	Y
Will the pipe be kept at a minimum 1/3 fluid filled to avoid approaching the collapse pressure rating of the casing?	Y
Is well located within Capitan Reef?	N
If yes, does production casing cement tie back a minimum of 50' above the Reef?	
Is well within the designated 4 string boundary.	
Is well located in SOPA but not in R-111-P?	N
If yes, are the first 2 strings cemented to surface and 3 rd string cement tied back 500' into previous casing?	
Is well located in R-111-P and SOPA?	N
If yes, are the first three strings cemented to surface?	
Is 2 nd string set 100' to 600' below the base of salt?	
Is well located in high Cave/Karst?	N
If yes, are there two strings cemented to surface?	
(For 2 string wells) If yes, is there a contingency casing if lost circulation occurs?	
Is well located in critical Cave/Karst?	N
If yes, are there three strings cemented to surface?	

Mewbourne Oil Company

Eddy County, New Mexico NAD 83

Little Rascals 17/18 W0IL Fed Com #2H

Sec 17, T22S, R28E

SHL: 940' FSL & 205' FEL, Sec 17

BHL: 1340' FSL & 330' FWL, Sec 18

Plan: Design #1

Standard Planning Report

15 July, 2019

Planning Report

Database:	Hobbs	Local Co-ordinate Reference:	Site Little Rascals 17/18 W0IL Fed Com #2H
Company:	Mewbourne Oil Company	TVD Reference:	WELL @ 3106.0usft (Original Well Elev)
Project:	Eddy County, New Mexico NAD 83	MD Reference:	WELL @ 3106.0usft (Original Well Elev)
Site:	Little Rascals 17/18 W0IL Fed Com #2H	North Reference:	Grid
Well:	Sec 17, T22S, R28E	Survey Calculation Method:	Minimum Curvature
Wellbore:	BHL: 1340' FSL & 330' FWL, Sec 18		
Design:	Design #1		

Project	Eddy County, New Mexico NAD 83		
Map System:	US State Plane 1983	System Datum:	Mean Sea Level
Geo Datum:	North American Datum 1983		
Map Zone:	New Mexico Eastern Zone		

Site	Little Rascals 17/18 W0IL Fed Com #2H					
Site Position:		Northing:	504,945.40 usft	Latitude:	32.3879514	
From:	Map	Easting:	612,744.90 usft	Longitude:	-104.1019989	
Position Uncertainty:		0.0 usft	Slot Radius:	13-3/16 "	Grid Convergence:	0.12 °

Well	Sec 17, T22S, R28E					
Well Position	+N/-S	0.0 usft	Northing:	504,945.40 usft	Latitude:	32.3879514
	+E/-W	0.0 usft	Easting:	612,744.90 usft	Longitude:	-104.1019989
Position Uncertainty		0.0 usft	Wellhead Elevation:	3,106.0 usft	Ground Level:	3,078.0 usft

Wellbore	BHL: 1340' FSL & 330' FWL, Sec 18				
Magnetics	Model Name	Sample Date	Declination (°)	Dip Angle (°)	Field Strength (nT)
	IGRF200510	12/31/2009	8.00	60.30	48,835

Design	Design #1			
Audit Notes:				
Version:	Phase:	PROTOTYPE	Tie On Depth:	0.0
Vertical Section:	Depth From (TVD) (usft)	+N/-S (usft)	+E/-W (usft)	Direction (°)
	0.0	0.0	0.0	272.58

Plan Sections										
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)	TFO (°)	Target
0.0	0.00	0.00	0.0	0.0	0.0	0.00	0.00	0.00	0.00	
2,425.0	0.00	0.00	2,425.0	0.0	0.0	0.00	0.00	0.00	0.00	
2,696.1	4.07	25.97	2,695.9	8.6	4.2	1.50	1.50	0.00	25.97	
8,707.5	4.07	25.97	8,692.1	392.0	190.9	0.00	0.00	0.00	0.00	
8,978.6	0.00	0.07	8,963.0	400.6	195.1	1.50	-1.50	0.00	180.00	KOP: 1340' FSL & 10
9,771.4	90.83	270.21	9,463.0	402.5	-312.2	11.46	11.46	0.00	-89.79	
19,173.6	90.83	270.21	9,326.0	437.7	-9,713.4	0.00	0.00	0.00	0.00	BHL: 3140' FSL & 330'

Planning Report

Database:	Hobbs	Local Co-ordinate Reference:	Site Little Rascals 17/18 W0IL Fed Com #2H
Company:	Mewbourne Oil Company	TVD Reference:	WELL @ 3106.0usft (Original Well Elev)
Project:	Eddy County, New Mexico NAD 83	MD Reference:	WELL @ 3106.0usft (Original Well Elev)
Site:	Little Rascals 17/18 W0IL Fed Com #2H	North Reference:	Grid
Well:	Sec 17, T22S, R28E	Survey Calculation Method:	Minimum Curvature
Wellbore:	BHL: 1340' FSL & 330' FWL, Sec 18		
Design:	Design #1		

Planned Survey									
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
0.0	0.00	0.00	0.0	0.0	0.0	0.0	0.00	0.00	0.00
SHL: 940' FSL & 205' FEL (17)									
100.0	0.00	0.00	100.0	0.0	0.0	0.0	0.00	0.00	0.00
200.0	0.00	0.00	200.0	0.0	0.0	0.0	0.00	0.00	0.00
300.0	0.00	0.00	300.0	0.0	0.0	0.0	0.00	0.00	0.00
400.0	0.00	0.00	400.0	0.0	0.0	0.0	0.00	0.00	0.00
500.0	0.00	0.00	500.0	0.0	0.0	0.0	0.00	0.00	0.00
600.0	0.00	0.00	600.0	0.0	0.0	0.0	0.00	0.00	0.00
700.0	0.00	0.00	700.0	0.0	0.0	0.0	0.00	0.00	0.00
800.0	0.00	0.00	800.0	0.0	0.0	0.0	0.00	0.00	0.00
900.0	0.00	0.00	900.0	0.0	0.0	0.0	0.00	0.00	0.00
1,000.0	0.00	0.00	1,000.0	0.0	0.0	0.0	0.00	0.00	0.00
1,100.0	0.00	0.00	1,100.0	0.0	0.0	0.0	0.00	0.00	0.00
1,200.0	0.00	0.00	1,200.0	0.0	0.0	0.0	0.00	0.00	0.00
1,300.0	0.00	0.00	1,300.0	0.0	0.0	0.0	0.00	0.00	0.00
1,400.0	0.00	0.00	1,400.0	0.0	0.0	0.0	0.00	0.00	0.00
1,500.0	0.00	0.00	1,500.0	0.0	0.0	0.0	0.00	0.00	0.00
1,600.0	0.00	0.00	1,600.0	0.0	0.0	0.0	0.00	0.00	0.00
1,700.0	0.00	0.00	1,700.0	0.0	0.0	0.0	0.00	0.00	0.00
1,800.0	0.00	0.00	1,800.0	0.0	0.0	0.0	0.00	0.00	0.00
1,900.0	0.00	0.00	1,900.0	0.0	0.0	0.0	0.00	0.00	0.00
2,000.0	0.00	0.00	2,000.0	0.0	0.0	0.0	0.00	0.00	0.00
2,100.0	0.00	0.00	2,100.0	0.0	0.0	0.0	0.00	0.00	0.00
2,200.0	0.00	0.00	2,200.0	0.0	0.0	0.0	0.00	0.00	0.00
2,300.0	0.00	0.00	2,300.0	0.0	0.0	0.0	0.00	0.00	0.00
2,400.0	0.00	0.00	2,400.0	0.0	0.0	0.0	0.00	0.00	0.00
2,425.0	0.00	0.00	2,425.0	0.0	0.0	0.0	0.00	0.00	0.00
2,500.0	1.13	25.97	2,500.0	0.7	0.3	-0.3	1.50	1.50	0.00
2,600.0	2.63	25.97	2,599.9	3.6	1.8	-1.6	1.50	1.50	0.00
2,696.1	4.07	25.97	2,695.9	8.6	4.2	-3.8	1.50	1.50	0.00
2,700.0	4.07	25.97	2,699.8	8.9	4.3	-3.9	0.00	0.00	0.00
2,800.0	4.07	25.97	2,799.5	15.3	7.4	-6.7	0.00	0.00	0.00
2,900.0	4.07	25.97	2,899.3	21.6	10.5	-9.6	0.00	0.00	0.00
3,000.0	4.07	25.97	2,999.0	28.0	13.6	-12.4	0.00	0.00	0.00
3,100.0	4.07	25.97	3,098.8	34.4	16.8	-15.2	0.00	0.00	0.00
3,200.0	4.07	25.97	3,198.5	40.8	19.9	-18.0	0.00	0.00	0.00
3,300.0	4.07	25.97	3,298.3	47.2	23.0	-20.8	0.00	0.00	0.00
3,400.0	4.07	25.97	3,398.0	53.5	26.1	-23.6	0.00	0.00	0.00
3,500.0	4.07	25.97	3,497.7	59.9	29.2	-26.4	0.00	0.00	0.00
3,600.0	4.07	25.97	3,597.5	66.3	32.3	-29.3	0.00	0.00	0.00
3,700.0	4.07	25.97	3,697.2	72.7	35.4	-32.1	0.00	0.00	0.00
3,800.0	4.07	25.97	3,797.0	79.0	38.5	-34.9	0.00	0.00	0.00
3,900.0	4.07	25.97	3,896.7	85.4	41.6	-37.7	0.00	0.00	0.00
4,000.0	4.07	25.97	3,996.5	91.8	44.7	-40.5	0.00	0.00	0.00
4,100.0	4.07	25.97	4,096.2	98.2	47.8	-43.3	0.00	0.00	0.00
4,200.0	4.07	25.97	4,196.0	104.5	50.9	-46.2	0.00	0.00	0.00
4,300.0	4.07	25.97	4,295.7	110.9	54.0	-49.0	0.00	0.00	0.00
4,400.0	4.07	25.97	4,395.5	117.3	57.1	-51.8	0.00	0.00	0.00
4,500.0	4.07	25.97	4,495.2	123.7	60.2	-54.6	0.00	0.00	0.00
4,600.0	4.07	25.97	4,595.0	130.0	63.3	-57.4	0.00	0.00	0.00
4,700.0	4.07	25.97	4,694.7	136.4	66.4	-60.2	0.00	0.00	0.00
4,800.0	4.07	25.97	4,794.5	142.8	69.5	-63.0	0.00	0.00	0.00
4,900.0	4.07	25.97	4,894.2	149.2	72.7	-65.9	0.00	0.00	0.00
5,000.0	4.07	25.97	4,994.0	155.6	75.8	-68.7	0.00	0.00	0.00

Planning Report

Database:	Hobbs	Local Co-ordinate Reference:	Site Little Rascals 17/18 W0IL Fed Com #2H
Company:	Mewbourne Oil Company	TVD Reference:	WELL @ 3106.0usft (Original Well Elev)
Project:	Eddy County, New Mexico NAD 83	MD Reference:	WELL @ 3106.0usft (Original Well Elev)
Site:	Little Rascals 17/18 W0IL Fed Com #2H	North Reference:	Grid
Well:	Sec 17, T22S, R28E	Survey Calculation Method:	Minimum Curvature
Wellbore:	BHL: 1340' FSL & 330' FWL, Sec 18		
Design:	Design #1		

Planned Survey									
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
5,100.0	4.07	25.97	5,093.7	161.9	78.9	-71.5	0.00	0.00	0.00
5,200.0	4.07	25.97	5,193.5	168.3	82.0	-74.3	0.00	0.00	0.00
5,300.0	4.07	25.97	5,293.2	174.7	85.1	-77.1	0.00	0.00	0.00
5,400.0	4.07	25.97	5,393.0	181.1	88.2	-79.9	0.00	0.00	0.00
5,500.0	4.07	25.97	5,492.7	187.4	91.3	-82.8	0.00	0.00	0.00
5,600.0	4.07	25.97	5,592.5	193.8	94.4	-85.6	0.00	0.00	0.00
5,700.0	4.07	25.97	5,692.2	200.2	97.5	-88.4	0.00	0.00	0.00
5,800.0	4.07	25.97	5,792.0	206.6	100.6	-91.2	0.00	0.00	0.00
5,900.0	4.07	25.97	5,891.7	212.9	103.7	-94.0	0.00	0.00	0.00
6,000.0	4.07	25.97	5,991.5	219.3	106.8	-96.8	0.00	0.00	0.00
6,100.0	4.07	25.97	6,091.2	225.7	109.9	-99.6	0.00	0.00	0.00
6,200.0	4.07	25.97	6,190.9	232.1	113.0	-102.5	0.00	0.00	0.00
6,300.0	4.07	25.97	6,290.7	238.4	116.1	-105.3	0.00	0.00	0.00
6,400.0	4.07	25.97	6,390.4	244.8	119.2	-108.1	0.00	0.00	0.00
6,500.0	4.07	25.97	6,490.2	251.2	122.3	-110.9	0.00	0.00	0.00
6,600.0	4.07	25.97	6,589.9	257.6	125.4	-113.7	0.00	0.00	0.00
6,700.0	4.07	25.97	6,689.7	263.9	128.5	-116.5	0.00	0.00	0.00
6,800.0	4.07	25.97	6,789.4	270.3	131.7	-119.4	0.00	0.00	0.00
6,900.0	4.07	25.97	6,889.2	276.7	134.8	-122.2	0.00	0.00	0.00
7,000.0	4.07	25.97	6,988.9	283.1	137.9	-125.0	0.00	0.00	0.00
7,100.0	4.07	25.97	7,088.7	289.5	141.0	-127.8	0.00	0.00	0.00
7,200.0	4.07	25.97	7,188.4	295.8	144.1	-130.6	0.00	0.00	0.00
7,300.0	4.07	25.97	7,288.2	302.2	147.2	-133.4	0.00	0.00	0.00
7,400.0	4.07	25.97	7,387.9	308.6	150.3	-136.2	0.00	0.00	0.00
7,500.0	4.07	25.97	7,487.7	315.0	153.4	-139.1	0.00	0.00	0.00
7,600.0	4.07	25.97	7,587.4	321.3	156.5	-141.9	0.00	0.00	0.00
7,700.0	4.07	25.97	7,687.2	327.7	159.6	-144.7	0.00	0.00	0.00
7,800.0	4.07	25.97	7,786.9	334.1	162.7	-147.5	0.00	0.00	0.00
7,900.0	4.07	25.97	7,886.7	340.5	165.8	-150.3	0.00	0.00	0.00
8,000.0	4.07	25.97	7,986.4	346.8	168.9	-153.1	0.00	0.00	0.00
8,100.0	4.07	25.97	8,086.2	353.2	172.0	-155.9	0.00	0.00	0.00
8,200.0	4.07	25.97	8,185.9	359.6	175.1	-158.8	0.00	0.00	0.00
8,300.0	4.07	25.97	8,285.7	366.0	178.2	-161.6	0.00	0.00	0.00
8,400.0	4.07	25.97	8,385.4	372.3	181.3	-164.4	0.00	0.00	0.00
8,500.0	4.07	25.97	8,485.2	378.7	184.4	-167.2	0.00	0.00	0.00
8,600.0	4.07	25.97	8,584.9	385.1	187.6	-170.0	0.00	0.00	0.00
8,707.5	4.07	25.97	8,692.1	392.0	190.9	-173.1	0.00	0.00	0.00
8,800.0	2.68	25.97	8,784.5	396.8	193.3	-175.2	1.50	-1.50	0.00
8,900.0	1.18	25.97	8,884.4	399.9	194.7	-176.5	1.50	-1.50	0.00
8,978.6	0.00	0.07	8,963.0	400.6	195.1	-176.9	1.50	-1.50	0.00
KOP: 1340' FSL & 10 FEL (17)									
9,000.0	2.45	270.21	8,984.4	400.6	194.6	-176.4	11.46	11.46	0.00
9,050.0	8.18	270.21	9,034.2	400.6	190.0	-171.8	11.46	11.46	0.00
9,100.0	13.91	270.21	9,083.2	400.7	180.4	-162.2	11.46	11.46	0.00
9,150.0	19.64	270.21	9,131.1	400.7	166.0	-147.8	11.46	11.46	0.00
9,200.0	25.37	270.21	9,177.2	400.8	146.9	-128.7	11.46	11.46	0.00
9,250.0	31.10	270.21	9,221.3	400.9	123.2	-105.1	11.46	11.46	0.00
9,300.0	36.83	270.21	9,262.7	401.0	95.3	-77.2	11.46	11.46	0.00
9,350.0	42.56	270.21	9,301.2	401.1	63.4	-45.3	11.46	11.46	0.00
9,400.0	48.28	270.21	9,336.3	401.2	27.8	-9.7	11.46	11.46	0.00
9,450.0	54.01	270.21	9,367.6	401.4	-11.1	29.2	11.46	11.46	0.00
9,500.0	59.74	270.21	9,394.9	401.5	-53.0	71.0	11.46	11.46	0.00
9,550.0	65.47	270.21	9,417.9	401.7	-97.4	115.3	11.46	11.46	0.00

Planning Report

Database:	Hobbs	Local Co-ordinate Reference:	Site Little Rascals 17/18 W01L Fed Com #2H
Company:	Mewbourne Oil Company	TVD Reference:	WELL @ 3106.0usft (Original Well Elev)
Project:	Eddy County, New Mexico NAD 83	MD Reference:	WELL @ 3106.0usft (Original Well Elev)
Site:	Little Rascals 17/18 W01L Fed Com #2H	North Reference:	Grid
Well:	Sec 17, T22S, R28E	Survey Calculation Method:	Minimum Curvature
Wellbore:	BHL: 1340' FSL & 330' FWL, Sec 18		
Design:	Design #1		

Planned Survey									
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
9,580.0	68.91	270.21	9,429.6	401.8	-125.0	143.0	11.46	11.46	0.00
FTP: 1340' FSL & 330' FEL (17)									
9,600.0	71.20	270.21	9,436.4	401.9	-143.8	161.7	11.46	11.46	0.00
9,650.0	76.93	270.21	9,450.1	402.0	-191.9	209.8	11.46	11.46	0.00
9,700.0	82.66	270.21	9,459.0	402.2	-241.1	258.9	11.46	11.46	0.00
9,750.0	88.39	270.21	9,462.9	402.4	-290.9	308.7	11.46	11.46	0.00
9,771.1	90.81	270.21	9,463.0	402.5	-312.0	329.8	11.46	11.46	0.00
LP: 1340' FSL & 517' FEL (17)									
9,771.4	90.83	270.21	9,463.0	402.5	-312.2	330.0	11.46	11.46	0.00
9,800.0	90.83	270.21	9,462.6	402.6	-340.9	358.6	0.00	0.00	0.00
9,900.0	90.83	270.21	9,461.1	403.0	-440.9	458.6	0.00	0.00	0.00
10,000.0	90.83	270.21	9,459.7	403.4	-540.8	558.5	0.00	0.00	0.00
10,100.0	90.83	270.21	9,458.2	403.7	-640.8	658.4	0.00	0.00	0.00
10,200.0	90.83	270.21	9,456.8	404.1	-740.8	758.3	0.00	0.00	0.00
10,300.0	90.83	270.21	9,455.3	404.5	-840.8	858.2	0.00	0.00	0.00
10,400.0	90.83	270.21	9,453.8	404.9	-940.8	958.1	0.00	0.00	0.00
10,500.0	90.83	270.21	9,452.4	405.2	-1,040.8	1,058.0	0.00	0.00	0.00
10,600.0	90.83	270.21	9,450.9	405.6	-1,140.8	1,157.9	0.00	0.00	0.00
10,700.0	90.83	270.21	9,449.5	406.0	-1,240.8	1,257.8	0.00	0.00	0.00
10,800.0	90.83	270.21	9,448.0	406.4	-1,340.8	1,357.7	0.00	0.00	0.00
10,900.0	90.83	270.21	9,446.6	406.7	-1,440.7	1,457.6	0.00	0.00	0.00
11,000.0	90.83	270.21	9,445.1	407.1	-1,540.7	1,557.5	0.00	0.00	0.00
11,100.0	90.83	270.21	9,443.6	407.5	-1,640.7	1,657.4	0.00	0.00	0.00
11,200.0	90.83	270.21	9,442.2	407.8	-1,740.7	1,757.3	0.00	0.00	0.00
11,300.0	90.83	270.21	9,440.7	408.2	-1,840.7	1,857.2	0.00	0.00	0.00
11,400.0	90.83	270.21	9,439.3	408.6	-1,940.7	1,957.1	0.00	0.00	0.00
11,500.0	90.83	270.21	9,437.8	409.0	-2,040.7	2,057.0	0.00	0.00	0.00
11,600.0	90.83	270.21	9,436.4	409.3	-2,140.7	2,156.9	0.00	0.00	0.00
11,700.0	90.83	270.21	9,434.9	409.7	-2,240.7	2,256.8	0.00	0.00	0.00
11,800.0	90.83	270.21	9,433.4	410.1	-2,340.6	2,356.7	0.00	0.00	0.00
11,900.0	90.83	270.21	9,432.0	410.5	-2,440.6	2,456.6	0.00	0.00	0.00
12,000.0	90.83	270.21	9,430.5	410.8	-2,540.6	2,556.5	0.00	0.00	0.00
12,100.0	90.83	270.21	9,429.1	411.2	-2,640.6	2,656.4	0.00	0.00	0.00
12,200.0	90.83	270.21	9,427.6	411.6	-2,740.6	2,756.3	0.00	0.00	0.00
12,300.0	90.83	270.21	9,426.2	412.0	-2,840.6	2,856.3	0.00	0.00	0.00
12,400.0	90.83	270.21	9,424.7	412.3	-2,940.6	2,956.2	0.00	0.00	0.00
12,500.0	90.83	270.21	9,423.2	412.7	-3,040.6	3,056.1	0.00	0.00	0.00
12,600.0	90.83	270.21	9,421.8	413.1	-3,140.6	3,156.0	0.00	0.00	0.00
12,700.0	90.83	270.21	9,420.3	413.5	-3,240.5	3,255.9	0.00	0.00	0.00
12,800.0	90.83	270.21	9,418.9	413.8	-3,340.5	3,355.8	0.00	0.00	0.00
12,900.0	90.83	270.21	9,417.4	414.2	-3,440.5	3,455.7	0.00	0.00	0.00
13,000.0	90.83	270.21	9,416.0	414.6	-3,540.5	3,555.6	0.00	0.00	0.00
13,100.0	90.83	270.21	9,414.5	415.0	-3,640.5	3,655.5	0.00	0.00	0.00
13,200.0	90.83	270.21	9,413.0	415.3	-3,740.5	3,755.4	0.00	0.00	0.00
13,300.0	90.83	270.21	9,411.6	415.7	-3,840.5	3,855.3	0.00	0.00	0.00
13,400.0	90.83	270.21	9,410.1	416.1	-3,940.5	3,955.2	0.00	0.00	0.00
13,500.0	90.83	270.21	9,408.7	416.5	-4,040.5	4,055.1	0.00	0.00	0.00
13,600.0	90.83	270.21	9,407.2	416.8	-4,140.4	4,155.0	0.00	0.00	0.00
13,700.0	90.83	270.21	9,405.8	417.2	-4,240.4	4,254.9	0.00	0.00	0.00
13,800.0	90.83	270.21	9,404.3	417.6	-4,340.4	4,354.8	0.00	0.00	0.00
13,900.0	90.83	270.21	9,402.8	418.0	-4,440.4	4,454.7	0.00	0.00	0.00
14,000.0	90.83	270.21	9,401.4	418.3	-4,540.4	4,554.6	0.00	0.00	0.00
14,100.0	90.83	270.21	9,399.9	418.7	-4,640.4	4,654.5	0.00	0.00	0.00
14,200.0	90.83	270.21	9,398.5	419.1	-4,740.4	4,754.4	0.00	0.00	0.00

Planning Report



Database:	Hobbs	Local Co-ordinate Reference:	Site Little Rascals 17/18 W01L Fed Com #2H
Company:	Mewbourne Oil Company	TVD Reference:	WELL @ 3106.0usft (Original Well Elev)
Project:	Eddy County, New Mexico NAD 83	MD Reference:	WELL @ 3106.0usft (Original Well Elev)
Site:	Little Rascals 17/18 W01L Fed Com #2H	North Reference:	Grid
Well:	Sec 17, T22S, R28E	Survey Calculation Method:	Minimum Curvature
Wellbore:	BHL: 1340' FSL & 330' FWL, Sec 18		
Design:	Design #1		

Planned Survey										
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)	
14,300.0	90.83	270.21	9,397.0	419.5	-4,840.4	4,854.3	0.00	0.00	0.00	
14,400.0	90.83	270.21	9,395.6	419.8	-4,940.4	4,954.2	0.00	0.00	0.00	
14,500.0	90.83	270.21	9,394.1	420.2	-5,040.3	5,054.1	0.00	0.00	0.00	
14,600.0	90.83	270.21	9,392.6	420.6	-5,140.3	5,154.0	0.00	0.00	0.00	
14,700.0	90.83	270.21	9,391.2	421.0	-5,240.3	5,254.0	0.00	0.00	0.00	
14,800.0	90.83	270.21	9,389.7	421.3	-5,340.3	5,353.9	0.00	0.00	0.00	
14,900.0	90.83	270.21	9,388.3	421.7	-5,440.3	5,453.8	0.00	0.00	0.00	
15,000.0	90.83	270.21	9,386.8	422.1	-5,540.3	5,553.7	0.00	0.00	0.00	
15,100.0	90.83	270.21	9,385.4	422.4	-5,640.3	5,653.6	0.00	0.00	0.00	
15,200.0	90.83	270.21	9,383.9	422.8	-5,740.3	5,753.5	0.00	0.00	0.00	
15,300.0	90.83	270.21	9,382.4	423.2	-5,840.2	5,853.4	0.00	0.00	0.00	
15,400.0	90.83	270.21	9,381.0	423.6	-5,940.2	5,953.3	0.00	0.00	0.00	
15,500.0	90.83	270.21	9,379.5	423.9	-6,040.2	6,053.2	0.00	0.00	0.00	
15,600.0	90.83	270.21	9,378.1	424.3	-6,140.2	6,153.1	0.00	0.00	0.00	
15,700.0	90.83	270.21	9,376.6	424.7	-6,240.2	6,253.0	0.00	0.00	0.00	
15,800.0	90.83	270.21	9,375.2	425.1	-6,340.2	6,352.9	0.00	0.00	0.00	
15,900.0	90.83	270.21	9,373.7	425.4	-6,440.2	6,452.8	0.00	0.00	0.00	
16,000.0	90.83	270.21	9,372.2	425.8	-6,540.2	6,552.7	0.00	0.00	0.00	
16,100.0	90.83	270.21	9,370.8	426.2	-6,640.2	6,652.6	0.00	0.00	0.00	
16,200.0	90.83	270.21	9,369.3	426.6	-6,740.1	6,752.5	0.00	0.00	0.00	
16,300.0	90.83	270.21	9,367.9	426.9	-6,840.1	6,852.4	0.00	0.00	0.00	
16,400.0	90.83	270.21	9,366.4	427.3	-6,940.1	6,952.3	0.00	0.00	0.00	
16,500.0	90.83	270.21	9,365.0	427.7	-7,040.1	7,052.2	0.00	0.00	0.00	
16,600.0	90.83	270.21	9,363.5	428.1	-7,140.1	7,152.1	0.00	0.00	0.00	
16,700.0	90.83	270.21	9,362.0	428.4	-7,240.1	7,252.0	0.00	0.00	0.00	
16,800.0	90.83	270.21	9,360.6	428.8	-7,340.1	7,351.9	0.00	0.00	0.00	
16,900.0	90.83	270.21	9,359.1	429.2	-7,440.1	7,451.8	0.00	0.00	0.00	
17,000.0	90.83	270.21	9,357.7	429.6	-7,540.1	7,551.7	0.00	0.00	0.00	
17,100.0	90.83	270.21	9,356.2	429.9	-7,640.0	7,651.7	0.00	0.00	0.00	
17,200.0	90.83	270.21	9,354.8	430.3	-7,740.0	7,751.6	0.00	0.00	0.00	
17,300.0	90.83	270.21	9,353.3	430.7	-7,840.0	7,851.5	0.00	0.00	0.00	
17,400.0	90.83	270.21	9,351.8	431.1	-7,940.0	7,951.4	0.00	0.00	0.00	
17,500.0	90.83	270.21	9,350.4	431.4	-8,040.0	8,051.3	0.00	0.00	0.00	
17,600.0	90.83	270.21	9,348.9	431.8	-8,140.0	8,151.2	0.00	0.00	0.00	
17,700.0	90.83	270.21	9,347.5	432.2	-8,240.0	8,251.1	0.00	0.00	0.00	
17,800.0	90.83	270.21	9,346.0	432.6	-8,340.0	8,351.0	0.00	0.00	0.00	
17,900.0	90.83	270.21	9,344.6	432.9	-8,440.0	8,450.9	0.00	0.00	0.00	
18,000.0	90.83	270.21	9,343.1	433.3	-8,539.9	8,550.8	0.00	0.00	0.00	
18,100.0	90.83	270.21	9,341.6	433.7	-8,639.9	8,650.7	0.00	0.00	0.00	
18,200.0	90.83	270.21	9,340.2	434.1	-8,739.9	8,750.6	0.00	0.00	0.00	
18,300.0	90.83	270.21	9,338.7	434.4	-8,839.9	8,850.5	0.00	0.00	0.00	
18,400.0	90.83	270.21	9,337.3	434.8	-8,939.9	8,950.4	0.00	0.00	0.00	
18,500.0	90.83	270.21	9,335.8	435.2	-9,039.9	9,050.3	0.00	0.00	0.00	
18,600.0	90.83	270.21	9,334.4	435.6	-9,139.9	9,150.2	0.00	0.00	0.00	
18,700.0	90.83	270.21	9,332.9	435.9	-9,239.9	9,250.1	0.00	0.00	0.00	
18,800.0	90.83	270.21	9,331.4	436.3	-9,339.9	9,350.0	0.00	0.00	0.00	
18,900.0	90.83	270.21	9,330.0	436.7	-9,439.8	9,449.9	0.00	0.00	0.00	
19,000.0	90.83	270.21	9,328.5	437.1	-9,539.8	9,549.8	0.00	0.00	0.00	
19,100.0	90.83	270.21	9,327.1	437.4	-9,639.8	9,649.7	0.00	0.00	0.00	
19,173.6	90.83	270.21	9,326.0	437.7	-9,713.4	9,723.3	0.00	0.00	0.00	
BHL: 3140' FSL & 330' FWL (18)										

Planning Report

Database:	Hobbs	Local Co-ordinate Reference:	Site Little Rascals 17/18 W0IL Fed Com #2H
Company:	Mewbourne Oil Company	TVD Reference:	WELL @ 3106.0usft (Original Well Elev)
Project:	Eddy County, New Mexico NAD 83	MD Reference:	WELL @ 3106.0usft (Original Well Elev)
Site:	Little Rascals 17/18 W0IL Fed Com #2H	North Reference:	Grid
Well:	Sec 17, T22S, R28E	Survey Calculation Method:	Minimum Curvature
Wellbore:	BHL: 1340' FSL & 330' FWL, Sec 18		
Design:	Design #1		

Design Targets									
Target Name									
- hit/miss target	Dip Angle	Dip Dir.	TVD	+N/-S	+E/-W	Northing	Easting	Latitude	Longitude
- Shape	(°)	(°)	(usft)	(usft)	(usft)	(usft)	(usft)		
SHL: 940' FSL & 205' FE - plan hits target center - Point	0.00	0.07	0.0	0.0	0.0	504,945.40	612,744.90	32.3879514	-104.1019989
KOP: 1340' FSL & 10 FE - plan hits target center - Point	0.00	0.07	8,963.0	400.6	195.1	505,346.00	612,940.00	32.3890514	-104.1013640
BHL: 3140' FSL & 330' F - plan hits target center - Point	0.00	0.07	9,326.0	437.7	-9,713.4	505,383.10	603,031.50	32.3892084	-104.1334640
FTP: 1340' FSL & 330' F - plan hits target center - Point	0.00	0.07	9,429.6	401.8	-125.0	505,347.20	612,619.90	32.3890566	-104.1024011
LP: 1340' FSL & 517' FE - plan hits target center - Point	0.00	0.07	9,463.0	402.5	-312.0	505,347.90	612,432.90	32.3890596	-104.1030069



Intent ☒ As Drilled ☐

API #		
Operator Name: Mewbourne Oil Co.	Property Name: Little Rascals 17/18 W0IL Fed Com	Well Number 2H

Kick Off Point (KOP)

UL I	Section 17	Township 22S	Range 28E	Lot	Feet 1340	From N/S S	Feet 10	From E/W E	County Eddy
Latitude 32.3890514					Longitude -104.1013640			NAD 83	

First Take Point (FTP)

UL I	Section 17	Township 22S	Range 28E	Lot	Feet 1340	From N/S S	Feet 330	From E/W E	County Eddy
Latitude 32.3890566					Longitude -104.1024011			NAD 83	

Last Take Point (LTP)

UL L	Section 18	Township 22S	Range 28E	Lot	Feet 1340	From N/S S	Feet 330	From E/W W	County Eddy
Latitude 32.3892084					Longitude -104.1334640			NAD 83	

Is this well the defining well for the Horizontal Spacing Unit? ☐ NIs this well an infill well? ☐ Y

If infill is yes please provide API if available, Operator Name and well number for Defining well for Horizontal Spacing Unit.

API #		
Operator Name: Mewbourne Oil Company	Property Name: Little Rascals 17/18 W0IL Fed Com	Well Number 3H

KZ 06/29/2018

PECOS DISTRICT DRILLING CONDITIONS OF APPROVAL

OPERATOR'S NAME:	MEWBOURNE OIL COMPANY
WELL NAME & NO.:	LITTLE RASCALS 17/18 W0IL FED COM 2H
APD ID:	10400085709
SURFACE HOLE FOOTAGE:	940'/S & 205'/E
BOTTOM HOLE FOOTAGE:	1340'/S & 330'/W
SURFACE LOCATION:	Section 17, T.22 S., R.28 E. NMP.
COUNTY:	Eddy County, New Mexico

COA

H ₂ S	<input checked="" type="radio"/> Yes	<input type="radio"/> No	
Potash	<input checked="" type="radio"/> None	<input type="radio"/> Secretary	<input type="radio"/> R-111-P
Cave/Karst Potential	<input type="radio"/> Low	<input checked="" type="radio"/> Medium	<input type="radio"/> High
Cave/Karst Potential	<input type="radio"/> Critical		
Variance	<input type="radio"/> None	<input checked="" type="radio"/> Flex Hose	<input type="radio"/> Other
Wellhead	<input type="radio"/> Conventional	<input checked="" type="radio"/> Multibowl	<input type="radio"/> Both
Other	<input type="checkbox"/> 4 String	<input type="checkbox"/> Capitan Reef	<input type="checkbox"/> WIPP
Other	<input type="checkbox"/> Fluid Filled	<input type="checkbox"/> Pilot Hole	<input type="checkbox"/> Open Annulus
Special Requirements	<input type="checkbox"/> Water Disposal	<input checked="" type="checkbox"/> COM	<input type="checkbox"/> Unit

A. HYDROGEN SULFIDE

A Hydrogen Sulfide (H₂S) Drilling Plan shall be activated **AT SPUD**. As a result, the Hydrogen Sulfide area must meet **43 CFR 3176** requirements, which includes equipment and personnel/public protection items. If Hydrogen Sulfide is encountered, please provide measured values and formations to the BLM.

B. CASING DESIGN

1. The **13-3/8** inch surface casing shall be set at approximately **300 ft.** (a minimum of 70 feet (Eddy County) into the Rustler Anhydrite and above the salt) and cemented to the surface. **NOTE:** Surface casing set depth was adjusted based on the BLM geologist recommendation: *The operator proposes to set surface casing at 735 feet, which will be too far into the salt. Instead, set casing just below the karst aquifer at approximately 300 feet. If salt is encountered, set casing at least 25 feet above the salt.*
 - a. If cement does not circulate to the surface, the appropriate BLM office shall be notified and a temperature survey utilizing an electronic-type temperature survey with surface log readout will be used or a cement bond log shall be run to verify the top of the cement. Temperature survey will be run a minimum of six hours after pumping cement and ideally between 8-10 hours after

- completing the cement job.
- b. Wait on cement (WOC) time for a primary cement job will be a minimum of **8 hours** or **500 psi compressive strength**, whichever is greater. (This is to include the lead cement)
 - c. Wait on cement (WOC) time for a remedial job will be a minimum of 4 hours after bringing cement to surface or 500 psi compressive strength, whichever is greater.
 - d. If cement falls back, remedial cementing will be done prior to drilling out that string.
2. The **9-5/8** inch intermediate casing shall be set in a competent bed at approximately **2,425 ft.** The minimum required fill of cement behind the **9-5/8** inch intermediate casing is:
- **Cement to surface.** If cement does not circulate see B.1.a, c-d above. Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry due to **Cave/Karst**.

Note: Excess cement volume is below the CFO's recommendation of 25%. More cement might be needed.

- ❖ In Medium Cave/Karst Areas if cement does not circulate to surface on the first two casing strings, the cement on the 3rd casing string must come to surface.

3. Operator has proposed to set **7 in.** production casing at approximately **9,590 ft.** The minimum required fill of cement behind the **7 in.** production casing is:

Option 1 (Single Stage): Cement should tie-back **at least 200 feet** into previous casing string. Operator shall provide method of verification. Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry due to **Cave/Karst**.

Option 2 (Two-stage): Operator has proposed a DV tool, the depth may be adjusted as long as the cement is changed proportionally. The DV tool may be cancelled if cement circulates to surface on the first stage.

- a. **First stage to DV tool:** Cement to circulate. If cement does not circulate off the DV tool, contact the appropriate BLM office before proceeding with second stage cement job.
- b. **Second stage above DV tool:** Cement should tie-back **at least 200 feet** into previous casing string. Operator shall provide method of verification. If cement does not circulate, contact the appropriate BLM office. Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry due to **Cave/Karst**.

Note: Excess cement volume for the 2nd stage is below the CFO's recommendation of 25%. More cement might be needed.

4. The minimum required fill of cement behind the **4-1/2 in.** production liner is:

- Cement should tie-back **at least 100 feet** into previous casing string. Operator shall provide method of verification.

C. PRESSURE CONTROL

1. Variance approved to use **flex line** from BOP to choke manifold. Manufacturer's specification to be readily available. No external damage to flex line. Flex line to be installed as straight as possible (no hard bends).
2. Operator has proposed a multi-bowl wellhead assembly. This assembly will only be tested when installed on the surface casing. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the surface casing shoe shall be **5000 (5M) psi**. Before drilling the surface casing shoe out, the BOP/BOPE and annular preventer shall be pressure-tested in accordance with **title 43 CFR 3172 and API Standard 53**.
 - a. Wellhead shall be installed by manufacturer's representatives, submit documentation with subsequent sundry.
 - b. If the welding is performed by a third party, the manufacturer's representative shall monitor the temperature to verify that it does not exceed the maximum temperature of the seal.
 - c. Manufacturer representative shall install the test plug for the initial BOP test.
 - d. If the cement does not circulate and one-inch operations would have been possible with a standard wellhead, the well head shall be cut off, cementing operations performed and another wellhead installed.
 - e. Whenever any seal subject to test pressure is broken, all the tests in the **title 43 CFR 3172.6(b)(9)** must be followed.

D. SPECIAL REQUIREMENT (S)

Communitization Agreement

- The operator will submit a Communitization Agreement to the Santa Fe Office, 301 Dinosaur Trail Santa Fe, New Mexico 87508, at least 90 days before the anticipated date of first production from a well subject to a spacing order issued by the New Mexico Oil Conservation Division. The Communitization Agreement will include the signatures of all working interest owners in all Federal and Indian leases subject to the Communitization Agreement (i.e., operating rights owners and lessees of record), or certification that the operator has obtained the written signatures of all such owners and will make those signatures available to the BLM immediately upon request.
- If the operator does not comply with this condition of approval, the BLM may take enforcement actions that include, but are not limited to, those specified in 43 CFR 3163.1.

- In addition, the well sign shall include the surface and bottom hole lease numbers. When the Communitization Agreement number is known, it shall also be on the sign.

GENERAL REQUIREMENTS

The BLM is to be notified in advance for a representative to witness:

- a. Spudding well (minimum of 24 hours)
- b. Setting and/or Cementing of all casing strings (minimum of 4 hours)
- c. BOPE tests (minimum of 4 hours)

☒ Eddy County

EMAIL or call the Carlsbad Field Office, 620 East Greene St., Carlsbad, NM 88220,

BLM_NM_CFO_DrillingNotifications@BLM.GOV
(575) 361-2822

☒ Lea County

Call the Hobbs Field Station, 414 West Taylor, Hobbs NM 88240, (575) 689-5981

1. Unless the production casing has been run and cemented or the well has been properly plugged, the drilling rig shall not be removed from over the hole without prior approval.
 - a. In the event the operator has proposed to drill multiple wells utilizing a skid/walking rig. Operator shall secure the wellbore on the current well, after installing and testing the wellhead, by installing a blind flange of like pressure rating to the wellhead and a pressure gauge that can be monitored while drilling is performed on the other well(s).
 - b. When the operator proposes to set surface casing with Spudder Rig
 - Notify the BLM when moving in and removing the Spudder Rig.
 - Notify the BLM when moving in the 2nd Rig. Rig to be moved in within 90 days of notification that Spudder Rig has left the location.
 - BOP/BOPE test to be conducted per **title 43 CFR 3172**
 - as soon as 2nd Rig is rigged up on well.
2. Floor controls are required for 3M or Greater systems. These controls will be on the rig floor, unobstructed, readily accessible to the driller and will be operational at all times during drilling and/or completion activities. Rig floor is defined as the area immediately around the rotary table; the area immediately above the substructure on which the draw works are located, this does not include the dog house or stairway area.

3. The record of the drilling rate along with the GR/N well log run from TD to surface (horizontal well – vertical portion of hole) shall be submitted to the BLM office as well as all other logs run on the borehole 30 days from completion. If available, a digital copy of the logs is to be submitted in addition to the paper copies. The Rustler top and top and bottom of Salt are to be recorded on the Completion Report.

A. CASING

1. Changes to the approved APD casing program need prior approval if the items substituted are of lesser grade or different casing size or are Non-API. The Operator can exchange the components of the proposal with that of superior strength (i.e. changing from J-55 to N-80, or from 36# to 40#). Changes to the approved cement program need prior approval if the altered cement plan has less volume or strength or if the changes are substantial (i.e. Multistage tool, ECP, etc.). The initial wellhead installed on the well will remain on the well with spools used as needed.
2. Wait on cement (WOC) for Potash Areas: After cementing but before commencing any tests, the casing string shall stand cemented under pressure until both of the following conditions have been met: 1) cement reaches a minimum compressive strength of 500 psi for all cement blends, 2) until cement has been in place at least 24 hours. WOC time will be recorded in the driller's log. The casing integrity test can be done (prior to the cement setting up) immediately after bumping the plug.
3. Wait on cement (WOC) for Water Basin: After cementing but before commencing any tests, the casing string shall stand cemented under pressure until both of the following conditions have been met: 1) cement reaches a minimum compressive strength of 500 psi at the shoe, 2) until cement has been in place at least 8 hours. WOC time will be recorded in the driller's log. See individual casing strings for details regarding lead cement slurry requirements. The casing integrity test can be done (prior to the cement setting up) immediately after bumping the plug.
4. Provide compressive strengths including hours to reach required 500 pounds compressive strength prior to cementing each casing string. Have well specific cement details onsite prior to pumping the cement for each casing string.
5. No pea gravel permitted for remedial or fall back remedial without prior authorization from the BLM engineer.
6. On that portion of any well approved for a 5M BOPE system or greater, a pressure integrity test of each casing shoe shall be performed. Formation at the shoe shall be tested to a minimum of the mud weight equivalent anticipated to control the formation pressure to the next casing depth or at total depth of the well. This test shall be performed before drilling more than 20 feet of new hole.

7. If hardband drill pipe is rotated inside casing, returns will be monitored for metal. If metal is found in samples, drill pipe will be pulled and rubber protectors which have a larger diameter than the tool joints of the drill pipe will be installed prior to continuing drilling operations.
8. Whenever a casing string is cemented in the R-111-P potash area, the NMOC requirements shall be followed.

B. PRESSURE CONTROL

1. All blowout preventer (BOP) and related equipment (BOPE) shall comply with well control requirements as described in the **title 43 CFR 3172** and **API STD 53 Sec. 5.3**.
2. If a variance is approved for a flexible hose to be installed from the BOP to the choke manifold, the following requirements apply: The flex line must meet the requirements of API 16C. Check condition of flexible line from BOP to choke manifold, replace if exterior is damaged or if line fails test. Line to be as straight as possible with no hard bends and is to be anchored according to Manufacturer's requirements. The flexible hose can be exchanged with a hose of equal size and equal or greater pressure rating. Anchor requirements, specification sheet and hydrostatic pressure test certification matching the hose in service, to be onsite for review. These documents shall be posted in the company man's trailer and on the rig floor.
3. 5M or higher system requires an HCR valve, remote kill line and annular to match. The remote kill line is to be installed prior to testing the system and tested to stack pressure.
4. If the operator has proposed a multi-bowl wellhead assembly in the APD. The following requirements must be met:
 - a. Wellhead shall be installed by manufacturer's representatives, submit documentation with subsequent sundry.
 - b. If the welding is performed by a third party, the manufacturer's representative shall monitor the temperature to verify that it does not exceed the maximum temperature of the seal.
 - c. Manufacturer representative shall install the test plug for the initial BOP test.
 - d. Whenever any seal subject to test pressure is broken, all the tests in the **title 43 CFR 3172.6(b)(9)** must be followed.
 - e. If the cement does not circulate and one-inch operations would have been possible with a standard wellhead, the well head shall be cut off, cementing operations performed and another wellhead installed.
5. The appropriate BLM office shall be notified a minimum of 4 hours in advance for a representative to witness the tests.

- a. In a water basin, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. The casing cut-off and BOP installation can be initiated four hours after installing the slips, which will be approximately six hours after bumping the plug. For those casing strings not using slips, the minimum wait time before cut-off is eight hours after bumping the plug. BOP/BOPE testing can begin after cut-off or once cement reaches 500 psi compressive strength (including lead cement), whichever is greater. However, if the float does not hold, cut-off cannot be initiated until cement reaches 500 psi compressive strength (including lead when specified).
- b. In potash areas, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. For all casing strings, casing cut-off and BOP installation can be initiated at twelve hours after bumping the cement plug. The BOPE test can be initiated after bumping the cement plug with the casing valve open. (only applies to single stage cement jobs, prior to the cement setting up.)
- c. The tests shall be done by an independent service company utilizing a test plug not a cup or J-packer and can be initiated immediately with the casing valve open. The operator also has the option of utilizing an independent tester to test without a plug (i.e. against the casing) pursuant to **43 CFR 3172** with the pressure not to exceed 70% of the burst rating for the casing. Any test against the casing must meet the WOC time for water basin (8 hours) or potash (24 hours) or 500 pounds compressive strength, whichever is greater, prior to initiating the test (see casing segment as lead cement may be critical item).
- d. The test shall be run on a 5000-psi chart for a 2-3M BOP/BOP, on a 10000-psi chart for a 5M BOP/BOPE and on a 15000-psi chart for a 10M BOP/BOPE. If a linear chart is used, it shall be a one-hour chart. A circular chart shall have a maximum 2-hour clock. If a twelve hour or twenty-four-hour chart is used, tester shall make a notation that it is run with a two-hour clock.
- e. The results of the test shall be reported to the appropriate BLM office.
- f. All tests are required to be recorded on a calibrated test chart. A copy of the BOP/BOPE test chart and a copy of independent service company test will be submitted to the appropriate BLM office.
- g. The BOP/BOPE test shall include a low-pressure test from 250 to 300 psi. The test will be held for a minimum of 10 minutes if test is done with a test plug and 30 minutes without a test plug. This test shall be performed prior to the test at full stack pressure.
- h. BOP/BOPE must be tested by an independent service company within 500 feet of the top of the Wolfcamp formation if the time between the setting of

the intermediate casing and reaching this depth exceeds 20 days. This test does not exclude the test prior to drilling out the casing shoe as per **43 CFR 3172**.

C. DRILLING MUD

Mud system monitoring equipment, with derrick floor indicators and visual and audio alarms, shall be operating before drilling into the Wolfcamp formation, and shall be used until production casing is run and cemented.

D. WASTE MATERIAL AND FLUIDS

All waste (i.e. drilling fluids, trash, salts, chemicals, sewage, gray water, etc.) created as a result of drilling operations and completion operations shall be safely contained and disposed of properly at a waste disposal facility. No waste material or fluid shall be disposed of on the well location or surrounding area. Porto-johns and trash containers will be on-location during fracturing operations or any other crew-intensive operations.

SA 12/22/2023

Hydrogen Sulfide Drilling Operations Plan
Mewbourne Oil Company

1. General Requirements

Rule 118 does not apply to this well because MOC has researched this area and no high concentrations of H₂S were found. MOC will have on location and working all H₂S safety equipment before the Delaware formation for purposes of safety and insurance requirements.

2. Hydrogen Sulfide Training

All personnel, whether regularly assigned, contracted, or employed on an unscheduled basis, will have received training from a qualified instructor in the following areas prior to entering the drilling pad area of the well:

1. The hazards and characteristics of hydrogen sulfide gas.
2. The proper use of personal protective equipment and life support systems.
3. The proper use of hydrogen sulfide detectors, alarms, warning systems, briefing areas, evacuation procedures.
4. The proper techniques for first aid and rescue operations.

Additionally, supervisory personnel will be trained in the following areas:

- 1 The effects of hydrogen sulfide on metal components. If high tensile tubular systems are utilized, supervisory personnel will be trained in their special maintenance requirements.
- 2 Corrective action and shut in procedures, blowout prevention, and well control procedures while drilling a well.
- 3 The contents of the Hydrogen Sulfide Drilling Operations Plan.

There will be an initial training session prior to encountering a known hydrogen sulfide source. The initial training session shall include a review of the site specific Hydrogen Sulfide Drilling Operations Plan.

3. Hydrogen Sulfide Safety Equipment and Systems

All hydrogen sulfide safety equipment and systems will be installed, tested, and operational prior to drilling below the 9 5/8" intermediate casing.

1. Well Control Equipment
 - A. Choke manifold with minimum of one adjustable choke/remote choke.
 - B. Blowout preventers equipped with blind rams and pipe rams to accommodate all pipe sizes with properly sized closing unit
 - C. Auxiliary equipment including annular type blowout preventer.
2. Protective Equipment for Essential Personnel

Thirty minute self contained work unit located in the dog house and at briefing areas.

Additionally: If H₂S is encountered in concentrations less than 10 ppm, fans will be placed in work areas to prevent the accumulation of hazardous amounts of poisonous gas. If higher concentrations of H₂S are detected the well will be shut in and a rotating head, mud/gas separator, remote choke and flare line with igniter will be installed.

3. Hydrogen Sulfide Protection and Monitoring Equipment
Two portable hydrogen sulfide monitors positioned on location for optimum coverage and detection. The units shall have audible sirens to notify personnel when hydrogen sulfide levels exceed 20 PPM.
4. Visual Warning Systems
 - A. Wind direction indicators as indicated on the wellsite diagram.
 - B. Caution signs shall be posted on roads providing access to location. Signs shall be painted a high visibility color with lettering of sufficient size to be readable at reasonable distances from potentially contaminated areas.

4. **Mud Program**

The mud program has been designed to minimize the amount of hydrogen sulfide entrained in the mud system. Proper mud weight, safe drilling practices, and the use of hydrogen sulfide scavengers will minimize hazards while drilling the well.

5. **Metallurgy**

All tubular systems, wellheads, blowout preventers, drilling spools, kill lines, choke manifolds, and valves shall be suitable for service in a hydrogen sulfide environment when chemically treated.

6. **Communications**

State & County Officials phone numbers are posted on rig floor and supervisors trailer. Communications in company vehicles and toolpushers are either two way radios or cellular phones.

7. **Well Testing**

Drill stem testing is not an anticipated requirement for evaluation of this well. If a drill stem test is required, it will be conducted with a minimum number of personnel in the immediate vicinity. The test will be conducted during daylight hours only.

8. **Emergency Phone Numbers**

Eddy County Sheriff's Office	911 or 575-887-7551
Ambulance Service	911 or 575-885-2111
Carlsbad Fire Dept	911 or 575-885-2111
Loco Hills Volunteer Fire Dept.	911 or 575-677-3266
Closest Medical Facility - Columbia Medical Center of Carlsbad	575-492-5000

Mewbourne Oil Company	Hobbs District Office	575-393-5905
	Fax	575-397-6252
	2nd Fax	575-393-7259

District Manager	Robin Terrell	575-390-4816
Drilling Superintendent	Frosty Lathan	575-390-4103
	Bradley Bishop	575-390-6838
Drilling Foreman	Wesley Noseff	575-441-0729

Operator Name: MEWBOURNE OIL COMPANY**Well Name:** LITTLE RASCALS 17/18 W01L FED COM**Well Number:** 2H**Disposal type description:****Disposal location description:** City of Carlsbad Water Treatment facility**Waste type:** GARBAGE**Waste content description:** Garbage & trash**Amount of waste:** 1500 pounds**Waste disposal frequency :** One Time Only**Safe containment description:** Enclosed trash trailer**Safe containmant attachment:****Waste disposal type:** HAUL TO COMMERCIAL FACILITY **Disposal location ownership:** PRIVATE**Disposal type description:****Disposal location description:** Waste Management facility in Carlsbad.

Reserve Pit

Reserve Pit being used? NO**Temporary disposal of produced water into reserve pit?** NO**Reserve pit length (ft.)****Reserve pit width (ft.)****Reserve pit depth (ft.)****Reserve pit volume (cu. yd.)****Is at least 50% of the reserve pit in cut?****Reserve pit liner****Reserve pit liner specifications and installation description**

Cuttings Area

Cuttings Area being used? NO**Are you storing cuttings on location?** N**Description of cuttings location****Cuttings area length (ft.)****Cuttings area width (ft.)****Cuttings area depth (ft.)****Cuttings area volume (cu. yd.)****Is at least 50% of the cuttings area in cut?****WCuttings area liner****Cuttings area liner specifications and installation description**

Operator Name: MEWBOURNE OIL COMPANY

Well Name: LITTLE RASCALS 17/18 W0IL FED COM

Well Number: 2H

Section 8 - Ancillary

Are you requesting any Ancillary Facilities?: N

Ancillary Facilities

Comments:

Section 9 - Well Site

Well Site Layout Diagram:

LittleRascals17_18W0ILFedCom2H_wellsitelayout_20220527084130.pdf

Comments:

Section 10 - Plans for Surface Reclamation

Type of disturbance: New Surface Disturbance

Multiple Well Pad Name: Little Rascals 17/18 IL & PM Fed Com wells

Multiple Well Pad Number: 5

Recontouring

Drainage/Erosion control construction: None

Drainage/Erosion control reclamation: None

Well pad proposed disturbance (acres): 4.78	Well pad interim reclamation (acres): 1.97	Well pad long term disturbance (acres): 2.81
Road proposed disturbance (acres): 0.11	Road interim reclamation (acres): 0	Road long term disturbance (acres): 0
Powerline proposed disturbance (acres): 0	Powerline interim reclamation (acres): 0	Powerline long term disturbance (acres): 0
Pipeline proposed disturbance (acres): 2.18	Pipeline interim reclamation (acres): 0	Pipeline long term disturbance (acres): 0
Other proposed disturbance (acres): 3.673	Other interim reclamation (acres): 0	Other long term disturbance (acres): 0
Total proposed disturbance: 10.743	Total interim reclamation: 1.97	Total long term disturbance: 2.81

Disturbance Comments: In areas to be heavily disturbed, the top 6 inches of soil material, will be stripped and stockpiled on the perimeter of the well location to keep topsoil viable, and to make redistribution of topsoil more efficient during interim reclamation. Stockpiled topsoil should include vegetative material. Topsoil will be clearly segregated and stored separately from subsoils. Contaminated soil will not be stockpiled, but properly treated and handled prior to topsoil salvaging.

Reconstruction method: The areas planned for interim reclamation will then be recontoured to the original contour if feasible, or if not feasible, to an interim contour that blends with the surrounding topography as much as possible. Where applicable, the fill material of the well pad will be backfilled into the cut to bring the area back to the original contour. The interim cut and fill slopes prior to re-seeding will not be steeper than a 3:1 ratio, unless the adjacent native topography is steeper. Note: Constructed slopes may be much steeper during drilling, but will be recontoured to the above ratios during interim reclamation.

Topsoil redistribution: Topsoil will be evenly respread and aggressively revegetated over the entire disturbed area not needed for all-weather operations including cuts & fills. To seed the area, the proper BLM seed mixture, free of noxious weeds, will be used.

District I
1625 N. French Dr., Hobbs, NM 88240
Phone:(575) 393-6161 Fax:(575) 393-0720
District II
811 S. First St., Artesia, NM 88210
Phone:(575) 748-1283 Fax:(575) 748-9720
District III
1000 Rio Brazos Rd., Aztec, NM 87410
Phone:(505) 334-6178 Fax:(505) 334-6170
District IV
1220 S. St Francis Dr., Santa Fe, NM 87505
Phone:(505) 476-3470 Fax:(505) 476-3462

State of New Mexico
Energy, Minerals and Natural Resources
Oil Conservation Division
1220 S. St Francis Dr.
Santa Fe, NM 87505

CONDITIONS

Action 343052

CONDITIONS

Operator: MEWBOURNE OIL CO P.O. Box 5270 Hobbs, NM 88241	OGRID:
	14744
	Action Number: 343052
	Action Type: [C-101] BLM - Federal/Indian Land Lease (Form 3160-3)

CONDITIONS

Created By	Condition	Condition Date
ward.rikala	Notify OCD 24 hours prior to casing & cement	5/28/2024
ward.rikala	Will require a File As Drilled C-102 and a Directional Survey with the C-104	5/28/2024
ward.rikala	Once the well is spud, to prevent ground water contamination through whole or partial conduits from the surface, the operator shall drill without interruption through the fresh water zone or zones and shall immediately set in cement the water protection string	5/28/2024
ward.rikala	Cement is required to circulate on both surface and intermediate1 strings of casing	5/28/2024
ward.rikala	If cement does not circulate on any string, a CBL is required for that string of casing	5/28/2024
ward.rikala	Oil base muds are not to be used until fresh water zones are cased and cemented providing isolation from the oil or diesel. This includes synthetic oils. Oil based mud, drilling fluids and solids must be contained in a steel closed loop system	5/28/2024
ward.rikala	Well can not be produced until the well name is changed per proper naming convention.	5/28/2024