Bureau of Land Management

VAFMSS

Application for Permit to Drill

APD Package Report

APD ID: 10400100853

APD Received Date: 09/23/2024 12:46 PM

Well Number: 201H Operator: XTO PERMIAN OPERATING LLC

Date Printed: 05/19/2025 03:20 PM

Received by OCD: 9/19/2025 11:43:28 AM

Well Status: AAPD Well Name: POKER LAKE UNIT 18-30 BL

APD Package Report Contents

- Form 3160-3

- Operator Certification Report

- Application Report

- Application Attachments

-- Well Plat: 1 file(s)

- Drilling Plan Report

- Drilling Plan Attachments

-- Blowout Prevention Choke Diagram Attachment: 1 file(s)

-- Blowout Prevention BOP Diagram Attachment: 1 file(s)

Casing Spec Documents: 2 file(s)

Casing Taperd String Specs: 1 file(s)

Casing Design Assumptions and Worksheet(s): 1 file(s)

- Hydrogen sulfide drilling operations plan: 1 file(s)

-- Proposed horizontal/directional/multi-lateral plan submission: 2 file(s)

Other Facets: 4 file(s)

-- Other Variances: 4 file(s)

SUPO Report

- SUPO Attachments

-- Existing Road Map: 1 file(s)

-- Attach Well map: 1 file(s)

-- Production Facilities map: 1 file(s)

-- Water source and transportation map: 1 file(s)

-- Well Site Layout Diagram: 2 file(s)

Recontouring attachment: 1 file(s)

-- Other SUPO Attachment: 1 file(s)

- PWD Report

- PWD Attachments

-- None

Bond ReportBond AttachmentsNone

*(Instructions on page 2)

| Form 3160-3 (June 2015) UNITED STATES | | FORM APPROVED OMB No. 1004-0137 Expires: January 31, 2018 | |
|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------|----------------------------------------------------------------------|-------------------|
| DEPARTMENT OF THE INTERIOR BUREAU OF LAND MANAGEMENT | TERIOR GEMENT | 5. Lease Serial No. NMLC065705B | |
| APPLICATION FOR PERMIT TO DRILL OR REENTER | ILL OR REENTER | 6. If Indian, Allotee or Tribe Name | |
| | | | |
| | REENTER | 7. If Unit or CA Agreement, Name and No. NMNM071016X/POKER LAKE UNIT | nd No. KE UNIT |
| letion: Hydraulic Fracturing | Single Zone V Multiple Zone | 8. Lease Name and Well No. POKER LAKE UNIT 18-30 BD | |
| | | 201Н | > |
| 2. Name of Operator XTO PERMIAN OPERATING LLC | | 9. API-Well No. 30-015-57272 | |
| 3a. Address 3b. Phone No. (i. 6401 HOLIDAY HILL ROAD BLDG 5, MIDLAND, TX 7970 (432) 683-2277 | 3b. Phone No. (include area code) (432) 683-2277 | 10. Field and Pool, or Exploratory PIERCE CROSSING/BONE SPRING, EA | ING, EA: |
| 4. Location of Well (Report location clearly and in accordance with any State requirements.*) At surface NWNE / 265 FNL / 2365 FEL / LAT 32.136718 / LONG -103.919737 | h any State requirements.*) 8 / LONG -103.919737 | 11. Sec., T. R. M. or Blk. and Survey or Area SEC 18/T25S/R30E/NMP | y or Area |
| At proposed prod. zone SWNE / 2646 FNL / 2010 FEL / LAT 32.100949 / LONG -103.918534 | AT 32.100949 / LONG -103.918534 | | |
| 14. Distance in miles and direction from nearest town or post office* | * | 12. County or Parish 13. State EDDY NM | ate |
| 15. Distance from proposed* | 16. No of acres in lease 17. Spacii | 17. Spacing Unit dedicated to this well | |

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No. 1, and the Hydraulic Fracturing rule per 43 CFR 3162.3-3 (as applicable)

24. Attachments

23. Estimated duration 45 days

22. Approximate date work will start* 10/03/2025

21. Elevations (Show whether DF, KDB, RT, GL, etc.)

3180 feet

18. Distance from proposed location* to nearest well, drilling, completed, 30 feet applied for, on this lease, ft.

(Also to nearest drig. unit line, if any)

property or lease line, ft.

20, BLM/BIA Bond No. in file

400.0

265 feet

FED: COB000050

10072 feet / 22955 feet

19. Proposed Depth

- 1. Well plat certified by a registered surveyor.
 - A Drilling Plan.
- 3. A Surface Use Plan (if the location is on National Forest System Lands, the SUPO must be filed with the appropriate Forest Service Office).
- Bond to cover the operations unless covered by an existing bond on file (see Item 20 above).

 - 5. Operator certification.
 6. Such other site specific information and/or plans as may be requested by the BLM.

| 25. Signature (Electronic Submission) | | Name (<i>Printed/Typed)</i> SAMANTHA WEIS / Ph. (432) 682-8873 | Date 09/23/2024 |
|------------------------------------------|--|----------------------------------------------------------------------|--------------------|
| Title | | | |
| Dermitting Advisor | | | |

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon. Date 05/19/2025 Name (*Printed/Typed*) CODY LAYTON / Ph: (575) 234-5959 Carlsbad Field Office Office Assistant Field Manager Lands & Minerals Approved by (Signature) (Electronic Submission)

Conditions of approval, if any, are attached.

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.



(Continued on page 2)

INSTRUCTIONS

Indian lands and leases for action by appropriate Federal agencies, pursuant to applicable Federal laws and regulations. Any GENERAL: This form is designed for submitting proposals to perform certain well operations, as indicated on Federal and regard to local, area, or regional procedures and practices, either are shown below or will be issued by, or may be obtained necessary special instructions concerning the use of this form and the number of copies to be submitted, particularly with from local Federal offices. ITEM I: If the proposal is to redrill to the same reservoir at a different subsurface location or to a new reservoir, use this form with appropriate notations. Consult applicable Federal regulations concerning subsequent work proposals or reports on the well.

ITEM 4: Locations on Federal or Indian land should be described in accordance with Federal requirements. Consult local Federal offices for specific instructions. ITEM 14: Needed only when location of well cannot readily be found by road from the land or lease description. A plat, or plats, separate or on the reverse side, showing the roads to, and the surveyed location of, the wen, and any other required information, should be furnished when required by Federal agency offices.

ITEMS 15 AND 18: If well is to be, or has been directionany drilled, give distances for subsurface location of hole in any present or objective productive zone.

ITEM 22: Consult applicable Federal regulations, or appropriate officials, concerning approval of the proposal before operations are started ITEM 24: If the proposal will involve hydraulic fracturing operations, you must comply with 43 CFR 3162.3-3, including providing information about the protection of usable water. Operators should provide the best available information about all formations containing water and their depths. This information could include data and interpretation of resistivity logs run on nearby wells. Information may also be obtained from state or tribal regulatory agencies and from local BLM offices.

NOTICES

The Privacy Act of 1974 and regulation in 43 CFR 2,48(d) provide that you be furnished the following information in connection with information required by this application.

AUTHORITY: 30 U.S.C. 181 et seq., 25 U.S.C. 396; 43 CFR 3160

information for the management, disposal and use of National Resource Lands and resources including (a) analyzing your proposal to discover and extract the Federal or Indian resources encountered; (b) reviewing procedures and equipment and the projected impact on the land involved; and (c) evaluating the effects of the proposed operation on the surface and PRINCIPAL PURPOSES: The information will be used to: (1) process and evaluate your application for a permit to drill a new oil, gas, or service wen or to reenter a plugged and abandoned well; and (2) document, for administrative use, subsurface water and other environmental impacts.

local or foreign agencies, when relevant to civil, criminal or regulatory investigations or prosecution, in connection with ROUTINE USE: Information from the record and/or the record win be transferred to appropriate Federal, State, and congressional inquiries and for regulatory responsibilities.

EFFECT OF NOT PROVIDING INFORMATION: Filing of this application and disclosure of the information is mandatory only if you elect to initiate a drilling or reentry operation on an oil and gas lease.

The Paperwork Reduction Act of 1995 requires us to inform you that:

drilling for oil and/or gas on Federal and Indian oil and gas leases. This information will be used to analyze and approve applications. Response to this request is mandatory only if the operator elects to initiate drilling or reentry operations on oil and gas lease. The BLM would like you to know that you do not have to respond to this or any other Federal agency-The BLM conects this information to anow evaluation of the technical, safety, and environmental factors involved with sponsored information collection unless it displays a currently valid OMB control number.

including the time for reviewing instructions, gathering and maintaining data, and completing and reviewing the form. Direct Management (1004-0137), Bureau Information Conection Clearance Officer (WO-630), 1849 C Street, N.W., Mail Stop 401 comments regarding the burden estimate or any other aspect of this form to U.S. Department of the Interior, Bureau of Land BURDEN HOURS STATEMENT: Public reporting burden for this form is estimated to average 8 hours per response, LS, Washington, D.C. 20240. (Form 3160-3, page 2)

Additional Operator Remarks

Location of Well

BHL: SWNE / 2646 FNL / 2010 FEL / TWSP: 25S / RANGE: 30E / SECTION: 30 / LAT: 32.100949 / LONG: -103.918534 (TVD: 10072 feet, MD: 22955 feet) PPP: NWNE / 100 FNL / 2010 FEL / TWSP: 25S / RANGE: 30E / SECTION: 18 / LAT: 32.137172 / LONG: -103.918591 (TVD: 10072 feet, MD: 10495 feet) PPP: NWNE / 0 FSL / 2011 FEL / TWSP: 25S / RANGE: 30E / SECTION: 19 / LAT: 32.122834 / LONG: -103.918569 (TVD: 10072 feet, MD: 15700 feet) 0. SHL: NWNE / 265 FNL / 2365 FEL / TWSP: 25S / RANGE: 30E / SECTION: 18 / LAT: 32.136718 / LONG: -103.919737 (TVD: 0 feet, MD: 0 feet)


BLM Point of Contact

Name: MARIAH HUGHES

Title: Land Law Examiner

Phone: (575) 234-5972

Email: mhughes@blm.gov



Review and Appeal Rights

20 working days of receipt of the Notice with the appropriate State Director (see 43 CFR 3165.3). The Quincy Street, Suite 300, Arlington, VA 22203 (see 43 CFR 3165.4). Contact the above listed Bureau A person contesting a decision shall request a State Director review. This request must be filed within State Director review decision may be appealed to the Interior Board of Land Appeals, 801 North of Land Management office for further information.



PECOS DISTRICT SURFACE USE CONDITIONS OF APPROVAL

OPERATOR'S NAME: XTO Permian Operating LLC

LEASE NO.: NMLC 065705, NMLC065705B

COUNTY:

Eddy County, New Mexico

117.11.

Poker Lake Unit 18-19 BD 106H

Poker Lake Unit 18-19 BD 127H

Poker Lake Unit 18-30 BD 200H

Poker Lake Unit 18-30 BD 201H

Poker Lake Unit 18-30 BD 202H

Poker Lake Unit 18-30 BD 203H

Poker Lake Unit 18-19 BD 204H Poker Lake Unit 18-19 BD 205H Poker Lake Unit 18-19 BD 206H

Poker Lake Unit 18-19 BD 207H Poker Lake Unit 18-19 BD 208H Poker Lake Unit 18-19 BD 209H

Page 1 of 24

TABLE OF CONTENTS

Page 2 of 24

5.1.2 Exclosure Netting (Open-top Tanks) 5.1.1 Placement of Production Facilities 5.1.3. Chemical and Fuel Secondary Containment and Exclosure Screening SURFACE PIPELINES..... 5.1.5. Containment Structures ON LEASE ACESS ROAD..... 4.5.1 Fence Requirement...... RANGLAND MITIGATION FOR PIPELINES 6.2 EROSION CONTROL...... 4.5.3 Livestock Watering Requirement WELL STRUCTURES & FACILITIES...... 5.1.4. Open-Vent Exhaust Stack Exclosures BURIED PIPELINES..... PRODUCTION (POST DRILLING)..... 6.1 ROAD AND SITE RECLAMATION WELL PAD & SURFACING TOPSOIL 6.3 INTERIM RECLAMATION Road Width Ditching 3.7.6 3.7.7 3.7.3 3.7.4 3.7.5 δ. 6.

6.4 FINAL ABANDONMENT & RECLAMATION.....

SOIL SPECIFIC SEED MIXTURE

GENERAL PROVISIONS

Released to Imaging: 9/19/2025 3:18:06 PM

location during construction, drilling and reclamation activity. Any request for a variance shall be submitted to the The failure of the operator to comply with these requirements may result in the assessment of liquidated damages or penalties pursuant to 43 CFR 3163.1 or 3163.2. A copy of these conditions of approval shall be present on the Authorized Officer on Form 3160-5, Sundry Notices and Report on Wells.

ARCHAEOLOGICAL, PALEONTOLOGY & HISTORICAL SITES

prevent the loss of significant scientific values. The operator shall be responsible for the cost of evaluation and any Any cultural resource (historic or prehistoric site or object) discovered by the operator, or any person working on Authorized Officer, in conjunction with a BLM Cultural Resource Specialist, to determine appropriate actions to authorization to proceed is issued by the Authorized Officer. An evaluation of the discovery will be made by the the operator's behalf, on the public or federal land shall be immediately reported to the Authorized Officer. The decision as to the proper mitigation measures will be made by the Authorized Officer after consulting with the operator shall suspend all operations in the immediate area (within 100ft) of such discovery until written

approval, the BLM Authorized Officer will notify the operator of the following conditions and the duration traditional, religious, and cultural significance tied to a certain group of individuals. Though there are currently designated TCPs within the project area or within a mile of the project area, but it is possible for a TCP to be designated after the approval of this project. If a TCP is designated in the project area after the project's Traditional Cultural Properties (TCPs) are protected by NHPA as codified in 36 CFR 800 for possessing for which these conditions are required.

- 1. Temporary halting of all construction, drilling, and production activities to lower noise.
- Temporary shut-off of all artificial lights at night.

The operator is hereby obligated to comply with procedures established in the Native American Graves Protection the discovery. The written notification should include the geographic location by county and state, the contents of Officer will be notified immediately. The BLM will then be required to be notified, in writing, within 24 hours of discovery and a conformation that all activity within 100ft of the discovery has ceased and work will not resume remains, associated funerary objects, sacred objects, and objects of cultural patrimony discovered during project until written certification is issued. All work on the entire project must halt for a minimum of 3 days and work the discovery, and the steps taken to protect said discovery. You must also include any potential threats to the work. If any human skeletal remains, funerary objects, sacred objects, or objects of cultural patrimony are discovered at any time during construction, all construction activities shall halt and a BLM-CFO Authorized and Repatriation Act (NAGPRA), specifically NAGPRA Subpart B regarding discoveries, to protect human cannot resume until an Authorized Officer grants permission to do so. Any paleontological resource discovered by the operator, or any person working on the operator's behalf, on public or Federal land shall be immediately reported to the Authorized Officer. The operator shall suspend all operations in the immediate area of such discovery until written authorization to proceed is issued by the Authorized Officer. The operator will be responsible for the cost of evaluation and any decision as to the proper mitigation measures will be made by the Authorized Officer after consulting with the operator.

.2. RANGELAND RESOURCES

1.2.1. Cattleguards

responsible for the condition of the existing cattleguard(s) that are in place and are utilized during lease operations. Where a permanent cattleguard is approved, an appropriately sized cattleguard(s) sufficient to carry out the project shall be installed and maintained at fence crossing(s). Any existing cattleguard(s) on the access road shall be repaired or replaced if they are damaged or have deteriorated beyond practical use. The operator shall be gate shall be constructed on one side of the cattleguard and fastened securely to H-braces.

Page 4 of 24

1.2.2. Fence Requirement

operator shall notify the private surface landowner or the grazing allotment holder prior to crossing any fence(s). Where entry granted across a fence line, the fence must be braced and tied off on both sides of the passageway prior to cutting. Once the work is completed, the fence will be restored to its prior condition, or better. The

1.2.3. Livestock Watering Requirement

234-5972) and the private surface landowner or the grazing allotment holder if any damage occurs to structures that Any damage to structures that provide water to livestock throughout the life of the well, caused by operations from the well site, must be immediately corrected by the operator. The operator must notify the BLM office (575provide water to livestock.

.3. NOXIOUS WEEDS

The operator shall be held responsible if noxious weeds become established within the areas of operations. Weed operator shall consult with the Authorized Officer for acceptable weed control methods, which include following associated pipeline corridor, and adjacent land affected by the establishment of weeds due to this action. The control shall be required on the disturbed land where noxious weeds exist, which includes the roads, pads, EPA, New Mexico Department of Agriculture, and BLM requirements and policies.

1.3.1 African Rue (Peganum harmala)

chemical and decrease chances of developing herbicide resistance. After spraying, the operator or necessary parties connection to any dirt working activities or disturbances to the site being sprayed. Spraying of African Rue shall be (Imazapyr) and 2% Roundup (Glyphosate) along with a nonionic surfactant. Any other chemicals or combinations stages. Spraying shall not be conducted after flowering when plant is fruiting. This will ensure optimal intake of shall be approved by the BLM Noxious Weeds Coordinator prior to treatment. African Rue shall be sprayed in done on immature plants at initial growth through flowering and mature plants between budding and flowering attempt to kill or remove African Rue the proper mix of chemical is needed. The mix consists of 2% Arsenal The spraying of African Rue must be completed by a licensed or certified applicator. In order to complete. The operator may contact the Environmental Protection Department or the BLM Noxious Weed must contact the Carlsbad Field Office to inspect the effectiveness of the application treatment to the plant No ground disturbing activities can take place until the inspection by the authorized officer is Coordinator at (575) 234-5972 or BLM_NM_CFO_NoxiousWeeds@blm.gov.

followed. All equipment should be washed off using a power washer in a designated containment area. The containment area shall be bermed to allow for containment of the seed to prevent it from entering any open areas of feet and just large enough to get equipment inside it to be washed off. This will allow all seeds to be in a centrally the nearby landscape. The containment area shall be excavated near or adjacent to the well pad at a depth of three Management Practices: In addition to spraying for African Rue, good management practices should be ocated area that can be treated at a later date if the need arises.

1.4. LIGHT POLLUTION

1.4.1. Downfacing

All permanent lighting will be pointed straight down at the ground in order to prevent light spill beyond the edge of approved surface disturbance.

1.4.2. Shielding

All permanent lighting will use full cutoff luminaires, which are fully shielded (i.e., not emitting direct or indirect light above an imaginary horizontal plane passing through the lowest part of the light source).

Page 5 of 24

1.4.3. Lighting Color

Lighting shall be 3,500 Kelvin or less (Warm White) except during drilling, completion, and workover operations. No bluish-white lighting shall be used in permanent outdoor lighting.

. SPECIAL REQUIREMENTS

1. WATERSHED

allowed to enter the well pad. The integrity of the berm shall be maintained around the surfaced pad throughout the life of the well and around the downsized pad after interim reclamation has been completed. Any water erosion that Topsoil shall not be used to construct the berm. No water flow from the uphill side(s) of the pad shall be pad. The compacted berm shall be constructed at a minimum of 12 inches with impermeable mineral material (e.g. may occur due to the construction of the well pad during the life of the well will be quickly corrected and proper measures will be taken to prevent future erosion. Stockpiling of topsoil is required. The topsoil shall be stockpiled in an appropriate location to prevent loss of soil due to water or wind erosion and not used for berming or erosion control. If fluid collects within the bermed area, the fluid must be vacuumed into a safe container and disposed of The entire well pad(s) will be bermed to prevent oil, salt, and other chemical contaminants from leaving the well properly at a state approved facility.

2.1.1. Tank Battery

½ times the content of the largest tank or 24-hourproduction, whichever is greater (displaced volume from all tanks backing to prevent tears or punctures. Secondary containment holding capacity must be large enough to contain 1 Tank battery locations will be lined and bermed. A 20-mil permanent liner will be installed with a 4 oz. felt within the berms MUST be subtracted from total volume of containment in calculating holding capacity). Automatic shut off, check valves, or similar systems will be installed for tanks to minimize the effects of catastrophic line failures used in production or drilling.

2.1.2. Buried/Surface Line(s)

When crossing ephemeral drainages, the pipeline(s) will be buried to a minimum depth of 48 inches from the top of and vegetation have stabilized. Water bars must be placed within the corridor to divert and dissipate surface runoff. downstream sides of the pipeline crossing. In addition, curled (weed free) wood/straw fiber wattles/logs and/or silt fences must be placed on the downstream side for sediment control during construction and maintained until soils pipe to ground level. Erosion control methods such as gabions and/or rock aprons must be placed on both up and A pipeline access road is not permitted to cross ephemeral drainages. Traffic must be diverted to a preexisting route. Additional seeding may be required in floodplains and drainages to restore energy dissipating vegetation.

Prior to pipeline installation/construction a leak detection plan will be developed. The method(s) could incorporate installing electronic sensors to alarm when a leak is present. The leak detection plan will incorporate an automatic shut off system that will be installed for proposed pipelines to minimize the effects of an undesirable event. gauges to detect pressure drops, situating valves and lines so they can be visually inspected periodically or

2.1.3. Electric Line(s)

Any water erosion that may occur due to the construction of overhead electric line and during the life of the power line will be quickly corrected and proper measures will be taken to prevent future erosion. A power pole must not be placed in drainages, playas, wetlands, riparian areas, or floodplains and must span across the features at distance away that does not promote further erosion.

2.1.4. Temporary Use Fresh Water Frac Line(s)

Once the temporary use exceeds the timeline of 180 days and/or with a 90 day extension status; further analysis will be required if the applicant pursues to turn the temporary pipeline into a permanent pipeline.

Page 6 of 24

2.3 WILDLIFE

2.3.2. Texas Hornshell Mussel

Oil and Gas and Associated Infrastructure Mitigation Measures for Zone D – CCA Boundary Requirements:

- Provide CEHMM with the permit, lease, or other authorization form BLM, if applicable
- Provide CEHMM with plats or other electronic media describing the new surface disturbance for the project.

2.4 VISUAL RESOURCE MANAGEMENT

.5.1 VRM IV

Above-ground structures including meter housing that are not subject to safety requirements are painted a flat nonreflective paint color, Shale Green from the BLM Standard Environmental Color Chart (CC-001: June 2008) Above-ground structures including meter housing that are not subject to safety requirements are painted a flat non-reflective paint color, Shale Green from the BLM Standard Environmental Color Chart (CC-001: June 2008).

3. CONSTRUCTION REQUIRENMENTS

.1 CONSTRCUTION NOTIFICATION

Carlsbad Field Office at BLM_NM_CFO_Construction_Reclamation@blm.gov at least 3 working days prior to The BLM shall administer compliance and monitor construction of the access road and well pad. Notify the commencing construction of the access road and/or well pad.

When construction operations are being conducted on this well, the operator shall have the approved APD and COAs on the well site and they shall be made available upon request by the Authorized Officer.

2 TOPSOIL

The operator shall strip the topsoil (the A horizon) from the entire well pad area and stockpile the topsoil along the edge of the well pad as depicted in the APD. No more than the top 6 inches of topsoil shall be removed. All the Topsoil shall not be used for berming the pad or facilities. For final reclamation, the topsoil shall be spread over the entire pad area for seeding stockpiled topsoil will be redistributed over the interim reclamation areas.

Other subsoil (the B horizon and below) stockpiles must be completely segregated from the topsoil stockpile. Large rocks or subsoil clods (not evident in the surrounding terrain) must be buried within the approved area for interim and final reclamation.

.3 CLOSED LOOP SYSTEM

Tanks are required for drilling operations: No reserve pits will be used for drill cuttings. The operator shall properly dispose of drilling contents at an authorized disposal site.

3.4 FEDERAL MINERAL PIT

Payment shall be made to the BLM prior to removal of any federal mineral materials. Call the Carlsbad Field Office at (575) 234-5972

3.5 WELL PAD & SURFACING

Any surfacing material used to surface the well pad will be removed at the time of interim and final reclamation.

Page 7 of 24

.6 EXCLOSURE FENCING (CELLARS & PITS)

livestock, and large forms of wildlife before and after drilling operations until the well cellar is free of fluids and the operator initiates backfilling. (For examples of exclosure fencing design, refer to BLM's Oil and Gas Gold The operator will install and maintain exclosure fencing for all open well cellars to prevent access to public, Book, Exclosure Fence Illustrations, Figure 1, Page 18.)

wildlife before and after drilling operations until the well cellar is free of fluids and the operator. Use a maximum The operator will also install and maintain mesh netting for all open well cellars to prevent access to smaller netting mesh size of 1 ½ inches. The netting must not have holes or gaps.

3.7 ON LEASE ACESS ROAD

7.1 Road Width

The access road shall have a driving surface that creates the smallest possible surface disturbance and does not exceed fourteen (14) feet in width. The maximum width of surface disturbance, when constructing the access road, shall not exceed twenty-five (25) feet.

7.2 Surfacing

Surfacing material is not required on the new access road driving surface. If the operator elects to surface the new access road or pad, the surfacing material may be required to be removed at the time of reclamation. Where possible, no improvements will be made on the unsurfaced access road other than to remove vegetation as necessary, road irregularities, safety issues, or to fill low areas that may sustain standing water. The Authorized Officer reserves the right to require surfacing of any portion of the access road at any time deemed necessary. Surfacing may be required in the event the road deteriorates, erodes, road traffic increases, or it is determined to be beneficial for future field development. The surfacing depth and type of material will be determined at the time of notification.

7.3 Crowning

Crowning shall be done on the access road driving surface. The road crown shall have a grade of approximately 2% (i.e., a 1" crown on a 14' wide road). The road shall conform to Figure 1; cross section and plans for typical road construction.

3.7.4 Ditching

Ditching shall be required on both sides of the road

3.7.5 Turnouts

Vehicle turnouts shall be constructed on the road. Turnouts shall be intervisible with interval spacing distance less than 1000 feet. Turnouts shall conform to Figure 1; cross section and plans for typical road construction.

3.7.6 Drainage

Drainage control systems shall be constructed on the entire length of road (e.g. ditches, sidehill outsloping and insloping, leadoff ditches, culvert installation, and low water crossings). A typical lead-off ditch has a minimum depth of 1 foot below and a berm of 6 inches above natural ground level. The berm shall be on the down-slope side of the lead-off ditch.

Cross Section of a Typical Lead-off Ditch

Page 8 of 24



All lead-off ditches shall be graded to drain water with a 1 percent minimum to 3 percent maximum ditch slope. The spacing interval are variable for lead-off ditches and shall be determined according to the formula for spacing intervals of lead-off ditches, but may be amended depending upon existing soil types and centerline road slope (in

Formula for Spacing Interval of Lead-off Ditches

Example - On a 4% road slope that is 400 feet long, the water flow shall drain water into a lead-off ditch. Spacing interval shall be determined by the following formula:

400' + 100' = 200' lead-off ditch interval 400 foot road with 4% road slope:

Δ

3.7.7 Public Access

Public access on this road shall not be restricted by the operator without specific written approval granted by the Authorized Officer.

Page 9 of 24




Figure 1. Cross-sections and plans for typical road sections representative of BLM resource or FS local and higher-class roads.

Page 10 of 24

4. PIPELINES

- The BLM, Carlsbad Field Office, will be informed immediately if any subsurface drainage channels, passages, or voids are intersected by trenching, and no pipe will be laid in the trench at that point until clearance has been issued by the Authorized Officer.
- and lines so they can be visually inspected periodically or installing electronic sensors to alarm when The method could incorporate gauges to detect pressure drops, situating values A leak detection plan will be submitted to the BLM Carlsbad Field Office for approval prior to leak is present. The leak detection plan will incorporate an automatic shut off system that will be installed for proposed pipelines to minimize the effects of an undesirable event. pipeline installation.
- Regular monitoring is required to quickly identify leaks for their immediate and proper treatment.
- All spills or leaks will be reported to the BLM immediately for their immediate and proper treatment.

4.1 BURIED PIPELINES

survey plat and/or map, will be on location during construction. BLM personnel may request a copy of your permit during construction to ensure compliance with all stipulations. A copy of the application (APD, or Sundry Notice) and attachments, including conditions of approval,

Operator agrees to comply with the following stipulations to the satisfaction of the Authorized Officer:

- The Operator shall indemnify the United States against any liability for damage to life or property arising from the occupancy or use of public lands under this APD. _;
- 761.193.) Additionally, any release of toxic substances (leaks, spills, etc.) in excess of the reportable quantity established by 40 CFR Part 117 shall be reported as required by the Comprehensive required or requested by any Federal agency or State government as a result of a reportable release or used, generated by or stored on the pipeline corridor or on facilities authorized under this APD. (See enacted or promulgated. In any event, the operator shall comply with the Toxic Substances Control Act of 1976 as amended, 15 USC 2601 et seq. (1982) with regards to any toxic substances that are spill of any toxic substances shall be furnished to the authorized officer concurrent with the filing The Operator shall comply with all applicable Federal laws and regulations existing or hereafter Environmental Response, Compensation, and Liability Act, section 102b. A copy of any report 40 CFR Part 702-799 and especially, provisions on polychlorinated biphenyls, 40 CFR 761.1the reports to the involved Federal agency or State government. \ddot{c}
- Resource Conservation and Recovery Act, 42 U.S.C.6901, et seq.) on the Pipeline corridor (unless the The operator agrees to indemnify the United States against any liability arising from the release of any release or threatened release is wholly unrelated to the operator's activity on the pipeline corridor), resulting from the activity of the Operator on the pipeline corridor. This agreement applies without Environmental Response, Compensation and Liability Act of 1980, 42 U.S.C. 9601, et seq. or the hazardous substance or hazardous waste (as these terms are defined in the Comprehensive regard to whether a release is caused by the operator, its agent, or unrelated third parties. \ddot{s}
- or other pollutant is discharged from the pipeline system, impacting Federal lands, the control and total If, during any phase of the construction, operation, maintenance, or termination of the pipeline, any oil responsibility of operator, regardless of fault. Upon failure of operator to control, dispose of, or clean clean up the discharge and restore the area, including where appropriate, the aquatic environment and Federal lands, the Authorized Officer may take such measures as he deems necessary to control and up such discharge on or affecting Federal lands, or to repair all damages resulting therefrom, on the removal, disposal, and cleaning up of such oil or other pollutant, wherever found, shall be the 4.

Page 11 of 24

Such action by the Authorized Officer shall not relieve operator of any responsibility as provided herein. fish and wildlife habitats, at the full expense of the operator.

- All construction and maintenance activity will be confined to the authorized pipeline corridor. 5
- The pipeline will be buried with a minimum cover of 36 inches between the top of the pipe and ground 6.
- The maximum allowable disturbance for construction in this pipeline corridor will be 30 feet: ۲.
- operations will not exceed 20 feet. The trench is included in this area. (Blading is defined as the Blading of vegetation within the pipeline corridor will be allowed: maximum width of blading complete removal of brush and ground vegetation.)
- Clearing of brush species within the pipeline corridor will be allowed: maximum width of clearing operations will not exceed 30 feet. The trench and bladed area are included in this area. (Clearing is defined as the removal of brush while leaving ground vegetation (grasses, weeds, etc.) intact. Clearing is best accomplished by holding the blade 4 to 6 inches above the ground surface.)
- The remaining area of the pipeline corridor (if any) shall only be disturbed by compressing the vegetation. (Compressing can be caused by vehicle tires, placement of equipment, etc.)
- The operator shall stockpile an adequate amount of topsoil where blading is allowed. The topsoil to be inches in depth. The topsoil will be segregated from other spoil stripped is approximately 6 inches in depth. The topsoil will be segregated from other spoi piles from trench construction. The topsoil will be evenly distributed over the bladed area for the preparation of seeding. ∞:
- surrounding landscape. The backfilled soil shall be compacted, and a 6-inch berm will be left over the approved by the Authorized Officer. The entire pipeline corridor shall be recontoured to match the Vegetation, soil, and rocks left as a result of construction or maintenance activity will be randomly scattered on this pipeline corridor and will not be left in rows, piles, or berms, unless otherwise ditch line to allow for settling back to grade. 9.
- and at all road crossings. At a minimum, signs will state the operator's name, BLM serial number, and The pipeline will be identified by signs at the point of origin and completion of the pipeline corridor the product being transported. All signs and information thereon will be posted in a permanent, conspicuous manner, and will be maintained in a legible condition for the life of the pipeline. 10.
- determined necessary by the Authorized Officer in consultation with the operator before maintenance The operator shall not use the pipeline route as a road for purposes other than routine maintenance as used as a roadway. As determined necessary during the life of the pipeline, the Authorized Officer begins. The operator will take whatever steps are necessary to ensure that the pipeline route is not may ask the operator to construct temporary deterrence structures. 11.
- includes associated roads, pipeline corridor and adjacent land affected by the establishment of weeds due to this action. The operator shall consult with the Authorized Officer for acceptable weed control operations. Weed control shall be required on the disturbed land where noxious weeds exist, which The operator shall be held responsible if noxious weeds become established within the areas of methods, which include following EPA and BLM requirements and policies. 12.
- entrapped. At a minimum, the operator will construct and maintain escape ramps, ladders, or other methods of avian and terrestrial wildlife escape in the trenches according to the following criteria: otherwise fenced, screened, or netted to prevent livestock, wildlife, and humans from becoming Escape Ramps - The operator will construct and maintain pipeline/utility trenches [that are not 13.

Page 12 of 24

- before the trench is backfilled, the contractor/operator shall inspect the trench for wildlife, remove Any trench left open for eight (8) hours or less is not required to have escape ramps; however, all trapped wildlife, and release them alive at least 100 yards from the trench. ಡ
- trench is backfilled, the contractor/operator shall inspect the trench for wildlife, remove all trapped wildlife, and release them alive at least 100 yards from the trench. 30-degree slope and spaced no more than 500 feet apart) shall be placed in the trench. Before the For trenches left open for eight (8) hours or more, earthen escape ramps (built at no more than a <u>ب</u>

Released to Imaging: 9/19/2025 3:18:06 PM

SURFACE PIPELINES

A copy of the APD and attachments, including stipulations, survey plat(s) and/or map(s), shall be on location during construction. BLM personnel may request to review a copy of your permit during construction to ensure compliance with all stipulations.

Operator agrees to comply with the following stipulations to the satisfaction of the Authorized Officer:

- Operator shall indemnify the United States against any liability for damage to life or property arising from the occupancy or use of public lands under this APD. _;
- promulgated. In any event, Operator shall comply with the Toxic Substances Control Act of 1976 as amended, 15 USC § 2601 et seq. (1982) with regard to any toxic substances that are used, generated by Operator shall comply with all applicable Federal laws and regulations existing or hereafter enacted or or stored on the pipeline corridoror on facilities authorized under this APD (see 40 CFR, Part 702-799 and in particular, provisions on polychlorinated biphenyls, 40 CFR 761.1-761.193). Additionally, any Federal agency or State government as a result of a reportable release or spill of any toxic substances shall be furnished to the Authorized Officer concurrent with the filing of the reports to the involved release of toxic substances (leaks, spills, etc.) in excess of the reportable quantity established by 40 Compensation, and Liability Act, section 102b. A copy of any report required or requested by any CFR, Part 117 shall be reported as required by the Comprehensive Environmental Response, Federal agency or State government. \vec{c}
- Resource Conservation and Recovery Act, 42 U.S.C. 6901, et seq.) on the Pipeline corridor (unless the corridor), or resulting from the activity of the Operator on the pipeline corridor. This provision applies release or threatened release is wholly unrelated to activity of the Operator's activity on the Pipeline Environmental Response, Compensation and Liability Act of 1980, 42 U.S.C. § 9601, et seq. or the Operator agrees to indemnify the United States against any liability arising from the release of any without regard to whether a release is caused by Operator, its agent, or unrelated third parties. hazardous substance or hazardous waste (as these terms are defined in the Comprehensive 3
- Sec. 2883.1-4. Operator shall be held to a standard of strict liability for damage or injury to the United Operator shall be liable for damage or injury to the United States to the extent provided by 43 CFR States resulting from pipe rupture, fire, or spills caused or substantially aggravated by any of the following within the pipeline corridor or permit area: 4.
- Activities of Operator including, but not limited to: construction, operation, maintenance, and termination of the facility; ಚ
- Activities of other parties including, but not limited to: Ъ.
 - (1) Land clearing
- Earth-disturbing and earth-moving work 000

 - Vandalism and sabotage
- Acts of God

The maximum limitation for such strict liability damages shall not exceed one million dollars (\$1,000,000)

Page 13 of 24

for any one event, and any liability in excess of such amount shall be determined by the ordinary rules of negligence of the jurisdiction in which the damage or injury occurred. This section shall not impose strict liability for damage or injury resulting primarily from an act of war or from the negligent acts or omissions of the United States.

- If, during any phase of the construction, operation, maintenance, or termination of the pipeline, any oil, control and total removal, disposal, and cleaning up of such oil, salt water, or other pollutant, wherever aquatic environment and fish and wildlife habitats, at the full expense of Operator. Such action by the found, shall be the responsibility of Operator, regardless of fault. Upon failure of Operator to control, dispose of, or clean up such discharge on or affecting Federal lands, or to repair all damages resulting necessary to control and clean up the discharge and restore the area, including, where appropriate, the salt water, or other pollutant is discharged from the pipeline system, impacting Federal lands, the therefrom, on the Federal lands, the Authorized Officer may take such measures as they deem Authorized Officer shall not relieve Operator of any responsibility as provided herein. 5.
- All construction and maintenance activity shall be confined to the authorized pipeline corridor width of 30-feet. If the pipeline route follows an existing road or buried pipeline corridor, the surface pipeline shall be installed no farther than 10 feet from the edge of the road or buried pipeline corridor. If immediately adjacent to the outer surface pipeline. All construction and maintenance activity shall be existing surface pipelines prevent this distance, the proposed surface pipeline shall be installed confined to existing roads or pipeline corridors. 6.
- No blading or clearing of any vegetation shall be allowed unless approved in writing by the Authorized ۲.
- Operator shall install the pipeline on the surface in such a manner that will minimize suspension of the pipeline across low areas in the terrain. In hummocky of duney areas, the pipeline shall be "snaked" around hummocks and dunes rather than suspended across these features. ∞:
- Burial of the pipe will continue for 20 feet on each side of each crossing. The condition of the road, upon completion of construction, shall be returned to at least its former state with no bumps or dips The pipeline shall be buried with a minimum of 6 inches under all roads, "two-tracks," and trails. remaining in the road surface. 6
- improvements prior to disturbing them. When necessary to pass through a fence line, the fence shall be The operator is required to promptly repair improvements to at least their former state. Functional use The operator shall minimize disturbance to existing fences and other improvements on public lands. of these improvements will be maintained at all times. The operator will contact the owner of any braced on both sides of the passageway prior to cutting of the fence. No permanent gates will be allowed unless approved by the Authorized Officer. 10.
- will install such structures as are suitable for the specific soil conditions being encountered and which In those areas where erosion control structures are required to stabilize soil conditions, the operator are in accordance with sound resource management practices. 11:
- simulates "Standard Environmental Colors" Shale Green, Munsell Soil Color No. 5Y 4/2; designated Excluding the pipe, all above-ground structures not subject to safety requirement shall be painted by the operator to blend with the natural color of the landscape. The paint used shall be a color which by the Rocky Mountain Five State Interagency Committee. 12.
- and at all road crossings. At a minimum, signs will state the operator's name, BLM serial number, and The pipeline will be identified by signs at the point of origin and completion of the pipeline corridor the product being transported. Signs will be maintained in a legible condition for the life of the 13.



- The operator shall not use the pipeline route as a road for purposes other than routine maintenance as determined necessary by the Authorized Officer in consultation with the operator. The operator will take whatever steps are necessary to ensure that the pipeline route is not used as a roadway. 4.
- includes the roads, powerline corridor, and adjacent land affected by the establishment of weeds due to operations. Weed control shall be required on the disturbed land where noxious weeds exist, which The operator shall be held responsible if noxious weeds become established within the areas of this action. The operator shall consult with the Authorized Officer for acceptable weed control methods, which include following EPA and BLM requirements and policies. 15.
- Surface pipelines shall be less than or equal to 4 inches and a working pressure below 125 psi. 16.

3 OVERHEAD ELECTRIC LINES

location during construction. BLM personnel may request to you a copy of your permit during A copy of the APD and attachments, including stipulations, survey plat and/or map, will be on construction to ensure compliance with all stipulations. Operator agrees to comply with the following stipulations to the satisfaction of the Authorized Officer:

- The operator shall indemnify the United States against any liability for damage to life or property arising from the occupancy or use of public lands under this APD.
- corridor. (See 40 CFR, Part 702-799 and especially, provisions on polychlorinated biphenyls, 40 CFR any report required or requested by any Federal agency or State government as a result of a reportable used, generated by or stored on the powerline corridor or on facilities authorized under this powerline release or spill of any toxic substances shall be furnished to the authorized officer concurrent with the Comprehensive Environmental Response, Compensation, and Liability Act, section 102b. A copy of enacted or promulgated. In any event, the operator shall comply with the Toxic Substances Control Act of 1976 as amended, 15 USC 2601 et seq. (1982) with regards to any toxic substances that are 761.1-761.193.) Additionally, any release of toxic substances (leaks, spills, etc.) in excess of the The operator shall comply with all applicable Federal laws and regulations existing or hereafter reportable quantity established by 40 CFR, Part 117 shall be reported as required by the filing of the reports to the involved Federal agency or State government. ri
- The operator agrees to indemnify the United States against any liability arising from the release of any Resource Conservation and Recovery Act, 42 U.S.C. 6901, et seq.) on the Powerline corridor(unless corridor), or resulting from the activity of the Operator on the powerline corridor. This agreement Environmental Response, Compensation and Liability Act of 1980, 42 U.S.C. 9601, et seq. or the applies without regard to whether a release is caused by the operator, its agent, or unrelated third the release or threatened release is wholly unrelated to the operator's activity on the powerline hazardous substance or hazardous waste (as these terms are defined in the Comprehensive 3
- There will be no clearing or blading of the powerline corridor unless otherwise agreed to in writing by the Authorized Officer. 4.
- placed on this powerline corridor, should they be necessary to ensure the safety of large perching birds. Practices for Avian Protection on Power lines: The State of the Art in 2006" Edison Electric Institute, Such modifications and/or additions shall be made by the operator without liability or expense to the Officer. The BLM reserves the right to require modification or additions to all powerline structures roosting, and nesting. Such proof shall be provided by a raptor expert approved by the Authorized APLIC, and the California Energy Commission 2006. The operator shall assume the burden and Power lines shall be constructed and designed in accordance to standards outlined in "Suggested expense of proving that pole designs not shown in the above publication deter raptor perching, United States. δ.

Page 15 of 24

- Raptor deterrence will consist of but not limited to the following: triangle perch discouragers shall be placed on each side of the cross arms and a nonconductive perching deterrence shall be placed on all vertical poles that extend past the cross arms. 6.
- The operator is required to promptly repair improvements to at least their former state. Functional use improvements prior to disturbing them. When necessary to pass through a fence line, the fence shall The operator shall minimize disturbance to existing fences and other improvements on public lands. of these improvements will be maintained at all times. The operator will contact the owner of any be braced on both sides of the passageway prior to cutting the fence. No permanent gates will be allowed unless approved by the Authorized Officer. ۲,
- manner where the power line crosses roads and at all serviced facilities. Numbers will be at least two inches high and will be affixed to the pole nearest the road crossing and at the facilities served. The BLM serial number assigned to this authorization shall be posted in a permanent, conspicuous ∞
- Upon cancellation, relinquishment, or expiration of this APD, the operator shall comply with those abandonment procedures as prescribed by the Authorized Officer. 6
- days of abandonment, relinquishment, cancellation, or expiration of this APD, whichever comes first. abandonment, relinquishment, or termination of use of the serviced facility or facilities or within 180 This will not apply where the power line extends service to an active, adjoining facility or facilities. All surface structures (poles, lines, transformers, etc.) shall be removed within 180 days of 10.

11. Special Stipulations:

For reclamation remove poles, lines, transformer, etc. and dispose of properly. Fill in any holes from the poles removed.

4.4 RANGLAND MITIGATION FOR PIPELINES

4.5.1 Fence Requirement

prior condition, or better. The operator shall notify the private surface landowner or the grazing allotment passageway with H-braces prior to cutting. Once the work is completed, the fence will be restored to its Where entry is granted across a fence line, the fence must be braced and tied off on both sides of the operator prior to crossing any fence(s).

4.5.2 Cattleguards

An appropriately sized cattleguard(s) sufficient to carry out the project shall be installed and maintained at are damaged or have deteriorated beyond practical use. The operator shall be responsible for the condition road-fence crossing(s). Any existing cattleguard(s) on the access road shall be repaired or replaced if they of the existing cattleguard(s) that are in place and are utilized during lease operations. A gate shall be constructed on one side of the cattleguard and fastened securely to H-braces.

4.5.3 Livestock Watering Requirement

Structures that provide water to livestock, such as windmills, pipelines, drinking troughs, and earthen reservoirs, will be avoided by moving the proposed action.

operations from the well site, must be immediately corrected by the operator. The operator must notify the BLM office (575-234-5972) and the private surface landowner or the grazing allotment operator if any Any damage to structures that provide water to livestock throughout the life of the well, caused by damage occurs to structures that provide water to livestock.

- Livestock operators will be contacted, and adequate crossing facilities will be provided as needed to ensure livestock are not prevented from reaching water sources because of the open trench.
- Wildlife and livestock trails will remain open and passable by adding soft plugs (areas where the trench is excavated and replaced with minimal compaction) during the construction phase. Soft plugs with ramps on either side will be left at all well-defined livestock and wildlife trails along

Page 16 of 24

the open trench to allow passage across the trench and provide a means of escape for livestock and wildlife that may enter the trench.

cannot be backfilled immediately will have escape ramps (wooden) placed at no more than 2,500 Operator will avoid leaving trenches open overnight to the extent possible and open trenches that Trenches will be backfilled as soon as feasible to minimize the amount of open trench. The feet intervals and sloped no more than 45 degrees.

5. PRODUCTION (POST DRILLING)

5.1 WELL STRUCTURES & FACILITIES

5.1.1 Placement of Production Facilities

Production facilities must be placed on the well pad to allow for maximum interim recontouring and revegetation of the well location.

5.1.2 Exclosure Netting (Open-top Tanks)

maximum netting mesh size of 1 1/2 inches. The netting must not be in contact with fluids and must not have prevent wildlife and livestock access, including avian wildlife, to all open-topped tanks that contain or have the potential to contain salinity sufficient to cause harm to wildlife or livestock, hydrocarbons, or Resource Immediately following active drilling or completion operations, the operator will take actions necessary to Conservation and Recovery Act of 1976-exempt hazardous substances. At a minimum, the operator will operator uses netting, the operator will cover and secure the open portion of the tank to prevent wildlife entry. The operator will net, screen, or cover the tanks until the operator removes the tanks from the ocation or the tanks no longer contain substances that could be harmful to wildlife or livestock. Use a net, screen, or cover open-topped tanks to exclude wildlife and livestock and prevent mortality. If the holes or gaps.

5.1.3. Chemical and Fuel Secondary Containment and Exclosure Screening

containment system for any tank or barrel containing hazardous, poisonous, flammable, or toxic substances Environmental Protection Agency livestock water standards in accordance with state law; the operator must The operator will dispose of fluids within the containment system that do not meet applicable state or U. S. contact with soil and water. At a minimum, the operator will install and maintain an impervious secondary operator will install effective wildlife and livestock exclosure systems such as fencing, netting, expanded sufficient to contain the contents of the tank or barrel and any drips, leaks, and anticipated precipitation. not drain the fluids to the soil or ground. The operator will design, construct, and maintain all secondary The operator will prevent all hazardous, poisonous, flammable, and toxic substances from coming into containment systems to prevent wildlife and livestock exposure to harmful substances. At a minimum, metal mesh, lids, and grate covers. Use a maximum netting mesh size of 1 1/2 inches.

5.1.4. Open-Vent Exhaust Stack Exclosures

equipment includes, but may not be limited to, tanks, heater-treaters, separators, dehydrators, flare stacks, (Recommended exclosure structures on open-vent exhaust stacks are in the shape of a cone.) Production equipment to prevent birds and bats from entering, and to discourage perching, roosting, and nesting. The operator will construct, modify, equip, and maintain all open-vent exhaust stacks on production in-line units, and compressor mufflers.

5.1.5. Containment Structures

structure that is constructed to hold the capacity of 1.5 times the largest tank, plus freeboard to account for Proposed production facilities such as storage tanks and other vessels will have a secondary containment precipitation, unless more stringent protective requirements are deemed necessary.

Page 17 of 24

6. RECLAMATION

Stipulations required by the Authorized Officer on specific actions may differ from the following general guidelines

6.1 ROAD AND SITE RECLAMATION

contaminants are indicated then testing will be required for chlorides and applicable contaminate anomalies Federal, State and Local statutes, regulations, and ordinances) and seeded to the specifications in sections for final disposal determination (disposed of in a manner approved by the Authorized Officer within Any roads constructed during the life of the well will have the caliche removed or linear burial. If 6.5 and 6.6.

6.2 EROSION CONTROL

down-slope. The surface must be left rough in order to catch and contain rainfall on-site. Any trenches between windrows must be ripped to a depth of at least 12", unless bedrock is encountered. Any large boulders pulled up during ripping must be deep-buried on location. Ripping must be perpendicular to perpendicular to down-slope drainage; steeper slopes will require greater windrow density. Topsoil Install erosion control berms, windrows, and hummocks. Windrows must be level and constructed resulting from erosion cause by run-off shall be addressed immediately.

6.3 INTERIM RECLAMATION

During the life of the development, all disturbed areas not needed for active support of production operations must undergo interim reclamation in order to minimize the environmental impacts of development on other resources and uses. Within six (6) months of well completion, operators must work with BLM surface protection specialists (BLM_NM_CFO_Construction_Reclamation@blm.gov) to devise the best strategies to reduce the size of the location. Interim reclamation must allow for remedial well operations, as well as safe and efficient removal of oil and gas.

order to operate the well or complete workover operations, it may be necessary to drive, park and operate on During reclamation, the removal of caliche and any other surface material is required. Removed caliche that is free of contaminants may be used for road repairs, fire walls or for building other roads and locations. In restored interim vegetation within the previously disturbed area. Disturbing revegetated areas for production or workover operations will be allowed. If there is significant disturbance and loss of vegetation, the area will need to be revegetated. Communicate with the appropriate BLM office for any exceptions/exemptions All disturbed areas after they have been satisfactorily prepared need to be reseeded with the seed mixture provided in section 6.6. Upon completion of interim reclamation, the operator shall submit a Sundry Notice, Subsequent Report of Reclamation (Form 3160-5)

6.4 FINAL ABANDONMENT & RECLAMATION

Prior to surface abandonment, the operator shall submit a Notice of Intent Sundry Notice and reclamation

At final abandonment, well locations, production facilities, and access roads must undergo "final" reclamation so that the character and productivity of the land are restored.

Page 18 of 24

Earthwork for final reclamation must be completed within six (6) months of well plugging. All pads, pits, facility locations and roads must be reclaimed to a satisfactory revegetated, safe, and stable condition, unless an agreement is made with the landowner or BLM to keep the road and/or pad intact.

by the BLM. After earthwork and seeding is completed, the operator is required to submit a Sundry Notice, mixture provided below. Seeding will be accomplished by drilling on the contour whenever practical or by After all disturbed areas have been satisfactorily prepared, these areas need to be revegetated with the seed other approved methods. Seeding may need to be repeated until revegetation is successful, as determined Subsequent Report of Reclamation.

Operators shall contact a BLM surface protection specialist prior to surface abandonment operations for site specific objectives (BLM_NM_CFO_Construction_Reclamation@blm.gov).

6.5 SEEDING TECHNIQUES

ripped or dragged to aid in covering the seed. The seed mixture shall be evenly and uniformly planted over Seeds shall be hydro-seeded, mechanically drilled, or broadcast, with the broadcast-seeded area raked, the disturbed area.

6.6 SOIL SPECIFIC SEED MIXTURE

Commercial seed will be either certified or registered seed. The seed container will be tagged in accordance shall be planted in the amounts specified in pounds of pure live seed (PLS)* per acre. There shall be no primary or secondary noxious weeds in the seed mixture. Seed will be tested and the viability testing of The lessee/permitee shall seed all disturbed areas with the seed mixture listed below. The seed mixture seed will be done in accordance with State law(s) and within nine (9) months prior to purchase. with State law(s) and available for inspection by the Authorized Officer.

uniformly planted over the disturbed area. Smaller/heavier seeds tend to drop the bottom of the drill and are regulator to ensure proper depth of planting where drilling is possible. The seed mixture will be evenly and planted first; the operator shall take appropriate measures to ensure this does not occur. Where drilling is Seed land application will be accomplished by mechanical planting using a drill equipped with a depth not possible, seed will be broadcast and the area shall be raked or chained to cover the seed. When broadcasting the seed, the pounds per acre are to be doubled. The seeding will be repeated until a satisfactory BLM or Soil Conservation District stand is established as determined by the Authorized Officer. Evaluation of growth will not be made before completion of at least one full growing season after seeding or until several months of precipitation have occurred, enabling a full four months of growth, with one or more seed generations being established.

Page 19 of 24

Seed Mixture 2, for Sandy Site

Species to be planted in pounds of pure live seed* per acre:

| l <u>b/acre</u> | 1.0 | 1.0 | 2.0 |
|-----------------|----------------------------------------|----------------------------------------|--------------------------------------------|
| Species | Sand dropseed (Sporobolus cryptandrus) | Sand love grass (Eragrostis trichodes) | Plains bristlegrass (Setaria macrostachya) |

*Pounds of pure live seed:

Pounds of seed x percent purity x percent germination = pounds pure live seed

Page 20 of 24

DRILLING PLAN: BLM COMPLIANCE (Supplement to BLM 3160-3)

POKER LAKE UNIT 18-30 BD 201H
Projected TD: 22955.29' MD / 10072' TVD
SHL: 265' FNL & 2365' FEL , Section 18, T25S, R30E
BHL: 2646' FNL & 2010' FEL , Section 30, T25S, R30E
EDDY County, NM XTO Energy Inc.

1. Geologic Name of Surface Formation

Quaternary

2. Estimated Tops of Geological Markers & Depths of Anticipated Fresh Water, Oil or Gas

| Water/Oil/Gas | 10072' | Target/Land Curve |
|---------------|------------------|-------------------|
| Water/Oil/Gas | 9373' | 3rd Bone Spring |
| Water/Oil/Gas | 8503' | 2nd Bone Spring |
| Water/Oil/Gas | 8057 | 1st Bone Spring |
| Water/Oil/Gas | 7462' | Avalon |
| Water | 7295' | Bone Spring |
| Water/Oil/Gas | 2697 | Brushy Canyon |
| Water | 3532' | Delaware |
| Water | 3313' | Base of Salt |
| Water | 1146' | Top of Salt |
| Water | 714' | Rustler |
| Water/Oil/Gas | Well Depth (TVD) | Formation |

*** Hydrocarbons @ Brushy Canyon
*** Groundwater depth 40' (per NM State Engineers Office).

sands will be protected by setting 9.625 inch casing @ 814' (332' above the salt) and circulating cement back to surface. The intermediate will isolate from the top of salt down to the next casing seat by setting 7.625 inch casing at 9169.81' and cemented to surface. A 6.75 inch curve and 6.75 inch lateral hole will be drilled to 22955.29 MD/TD and 5.5 inch production casing will be set at TD and cemented back up in the intermediate shoe (estimated TOC formations are expected to yield oil, gas or fresh water in measurable volumes. The surface fresh water No other

3. Casing Design

| 12.25 0' – 814' 9.625 40 J-55 BTC New 1.74 7.73 19. 8.75 0' – 4000' 7.625 29.7 RY P-110 Flush Joint New 3.03 2.86 2.0 8.75 4000' – 9169.81' 7.625 29.7 HC L-80 Flush Joint New 2.20 2.50 2.6 6.75 0' – 9069.81' 5.5 20 RY P-110 Semi-flush' New 1.05 2.31 2.1 6.75 22955.29' 5.5 20 RY P-110 Taln HTQ New 1.05 2.08 2.1 | Hole Size | Depth | op Csg | Weight | Grade | Collar | New/Used | SF Burst | SF SF urst Collapse 7 | SF Tension |
|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------|-------------------------|--------|--------|----------|------------------------------|----------|-------------|-----------------------|---------------|
| 0'-4000' 7.625 29.7 RY P-110 Flush Joint New 3.03 2.86 4000'- 9169.81' 7.625 29.7 HC L-80 Flush Joint New 2.20 2.50 0'-9069.81' 5.5 20 RY P-110 Semi-flush' Freedom HTQ New 1.05 2.31 9069.81'- 22955.29' 5.5 20 RY P-110 Semi-flush' Taln HTQ New 1.05 2.08 | 12.25 | 0' – 814' | 9.625 | 40 | J-55 | ВТС | | 1.74 | 7.73 | 19.35 |
| 4000'- 7.625 29.7 HC L-80 Flush Joint New 2.20 2.50 0'-9069.81'- 5.5 20 RY P-110 Semi-premium/ Freedom HTQ New 1.05 2.31 9069.81'- 5.5 20 RY P-110 Semi-flush/ Semi-flush/ TQ New 1.05 2.08 | 8.75 | 0, – 4000, | 7.625 | 29.7 | RY P-110 | Flush Joint | New | 3.03 | 2.86 | 2.05 |
| 0′ – 9069.81′ – 9069.81′ – 20 RY P-110 Semi-premium/Freedom HTQ New 1.05 2.31 9069.81′ – 22955.29′ – 25 20 RY P-110 Semi-flush/TQ New 1.05 2.08 | 8.75 | 4000' – 9169.81' | 7.625 | 29.7 | HC L-80 | Flush Joint | New | 2.20 | | 2.64 |
| 9069.81'- 5.5 20 RY P-110 Semi-flush/ New 1.05 2.08 | 6.75 | 0' – 9069.81' | 5.5 | 20 | RY P-110 | Semi-premium/ Freedom HTQ | New | 1.05 | 2.31 | 2.16 |
| | 6.75 | 9069.81' - 22955.29' | 2.5 | 20 | RY P-110 | Semi-flush/ Taln HTQ | | 1.05 | | 2.16 |

XTO requests the option to utilize a spudder rig (Atlas Copco RD20 or Equivalent) to set and cement

Wellhead:

XTO will utilize a 3 string Multi-bowl system..

4. Cement Program

requests the option to offline cement and remediate (if needed) surface and intermediate casing strings XTO will ensure well is static with no pressure on the csg annulus, as with all other casing strings where batch drilling operations occur before The TA cap will also be installed when applicable per Cactus procedure and pressure inside the casing will be monitored via the valve on the TA cap as per standard batch drilling ops. Offline cement operations will then be conducted after the rig is moved off the current well to the next well in the where batch drilling is approved and if unplanned remediation is needed. moving off the rig.

Surface Casing: 9.625, 40 New BTC, J-55 casing to be set at +/- 814'

Lead: 170 sxs EconoCem-HLTRRC (mixed at 10.5 ppg, 1.87 ft3/sx, 10.13 gal/sx water)

Tail: 130 sxs Class C + 2% CaCl (mixed at 14.8 ppg, 1.35 ft3/sx, 6.39 gal/sx water)

Surface Top of Cement: 900 psi 12-hr = Compressives:

TOC: Surface

24 hr = 1500 psi

Optional Lead: 300 sxs Class C (mixed at 10.5 ppg, 2.77 ft3/sx, 15.59 gal/sx water) Intermediate Casing: 7.625, 29.7 New casing to be set at +/- 9169.81'

TOC: Brushy Canyon @ 5697

Tail: 320 sxs Class C (mixed at 14.8 ppg, 1.35 ft3/sx, 6.39 gal/sx water)

Compressives:

12-hr =

24 hr = 1150 psi 900 psi

Lead: 0 sxs Class C (mixed at 12.9 ppg, 2.16 ft3/sx, 9.61 gal/sx water)

Tail: 640 sxs Class C (mixed at 14.8 ppg, 1.33 ft3/sx, 6.39 gal/sx water) Top of Cement:

0

24 hr = 1150 psi900 psi

12-hr =

being pumped conventionally with the calculated top of cement at the Brush Canyon (5697') and the second be verified by Echo-meter. If necessary, a top out consisting of 1,500 sack of Class C cement + 3% Salt + 1% PreMag-M + 6% Bentonite Gel (2.30 yld, 12.91 ppg) will be executed as a contingency. If cement is still unable to circulate to surface, another Echo-meter run will be performed for cement top verification. cement is not visually confirmed to circulate to surface, the final cement top after the second stage job will cement job on the 7-5/8" intermediate casing string with the first stage stage performed as a bradenhead squeeze with planned cement from the Brushy Canyon to surface. If XTO requests to pump a two stage

XTO will report to the BLM the volume of fluid (limited to 5 bbls) used to flush intermediate casing valves following backside cementing procedures.

XTO requests to pump an Optional Lead if well conditions dictate in an attempt to bring cement inside the first intermediate casing. If cement reaches the desired height, the BLM will be notified and the second stage bradenhead squeeze and subsequent TOC verification will be negated.

approval from BLM when unplanned remediation is needed and batch drilling is approved. In the event the bradenhead is conducted, we will ensure the first stage cement job is cemented properly and the well is drilling operations occur before moving off the rig. The TA cap will also be installed per Cactus procedure and pressure inside the casing will be monitored via the valve on the TA cap as per standard batch drilling static with floats holding and no pressure on the csg annulus as with all other casing strings where batch and TOC verification offline as option to conduct the bradenhead squeeze

Production Casing: 5.5, 20 New Semi-Flush, RY P-110 casing to be set at +/- 22955.29

Lead: 20 sxs NeoCem (mixed at 11.5 ppg, 2.69 ft3/sx, 15.00 gal/sx water) Top of Cement: Tail: 970 sxs VersaCem (mixed at 13.2 ppg, 1.51 ft3/sx, 8.38 gal/sx water) Top of Cement: Compressives: 12-hr = 800 psi

8869.81 feet 9369.81 feet

5. Pressure Control Equipment

Once the permanent WH is installed on the casing, the blow out preventer equipment (BOP) will consist of a 5M Hydril Annular and a 10M Triple Ram BOP.

All BOP testing will be done by an independent service company. Operator will test as per 43 CFR3172

A variance is requested to allow use of a flex hose as the choke line from the BOP to the Choke Manifold.

XTO requests a variance to be able to batch drill this well if necessary. In doing so, XTO will set casing and ensure that the well is cemented properly (unless approval is given for offline cementing) and the well is static. With floats holding, no pressure on the csg annulus, and the installation of a 10K TA cap as per Cactus recommendations, XTO will contact the BLM to skid the rig to drill the remaining wells on the pad. Once surface and both intermediate strings are all completed, XTO will begin drilling the production hole on each of the wells.

A variance is requested to **ONLY** test broken pressure seals on the BOP equipment when moving from wellhead to wellhead which is in compliance with API Standard 53.

XTO requests a variance to utilize a spudder rig.

6. Proposed Mud Circulation System

| IVAGUENI | 8-13 STST | M. d Time | ММ | Viscosity | Fluid Loss | Additional |
|-------------------------|-----------|-----------------------------------------------------------------|---------------|-----------|------------|----------------------------------------------|
| IN ERVAL | | wind i ype | (bdd) | (sec/qt) | (cc) | Comments |
| 0' - 814' | 12.25 | FW/Native 8.4-8.9 | 8.4-8.9 | 35-40 | NC | Fresh water or native water |
| 814' - 9169.81' | 8.75 | Saturated brine for salt interval / Direct Emulsion | 9-9.5 | 30-32 | NC | Fully saturated salt across salado / salt |
| 9169.81' - 22955.29' | 6.75 | ОВМ | OBM 10.2-10.7 | 50-60 | NC - 20 | N/A |

The necessary mud products for weight addition and fluid loss control will be on location at all times.

recorded on a daily drilling report after mudding up. A Pason or Totco will be used to detect changes in loss or gain of mud volume. A mud test will be performed every 24 hours to determine: density, viscosity, strength, filtration and pH as necessary. Use available solids controls equipment to help keep mud weight down after mud up. Rig up solids control equipment to operate as a closed loop system. Spud with fresh water/native mud. Drill out from under surface casing with Saturated Salt. A saturated salt brine mud will be used while drilling through the salt formation. Use fibrous materials as needed to control seepage and lost circulation. Pump viscous sweeps as needed for hole cleaning. Pump speed will be

7. Auxiliary Well Control and Monitoring Equipment

- A Kelly cock will be in the drill string at all times.

 A full opening drill pipe stabbing valve having appropriate connections will be on the rig floor at all times.

 H2S monitors will be on location when drilling below the 9.625 casing. N B A

8. Logging, Coring and Testing Program

Open hole logging will not be done on this well.

detect any H2S occurrences. Should these circumstances be encountered the operator and drilling contractor are prepared to take all necessary steps to ensure safety of all personnel and environment. Lost circulation could occur but is not expected to be a serious problem in this area and hole seepage will be compensated for by additions of small amounts of LCM in the drilling fluid. 9. Abnormal Pressures and Temperatures / Potential Hazards None Anticipated. BHT of 165 to 185 F is anticipated. No H2S is expected but monitors will be in place to

10. Anticipated Starting Date and Duration of Operations Anticipated spud date will be after BLM approval. Move in operations and drilling is expected to take 40

DRILLING CONDITIONS OF APPROVAL PECOS DISTRICT

OPERATOR'S NAME:XTO Permian Operating LLCWELL NAME & NO.:Poker Lake Unit 18-30 BD 201HLOCATION:Section 18, T.25S., R.30E.

COUNTY: Eddy County

COA

| H2S | Yes | ○ No | |
|----------------------|-----------------------|--------------|----------------|
| Potash | None None | © Secretary | © R-111-P |
| Cave/Karst Potential | mo _T | © Medium | ○ High |
| Cave/Karst Potential | © Critical | | |
| Variance | © None | Flex Hose | Other |
| Wellhead | © Conventional | • Multibowl | ○ Both |
| Wellhead Variance | © Diverter | | |
| Other | □4 String | Capitan Reef | WIPP |
| Other | Fluid Filled | Pilot Hole | Doen Annulus |
| Cementing | ▼ Contingency | EchoMeter | Primary Cement |
| | Cement Squeeze | | Squeeze |
| Special Requirements | Water Disposal | COM | ✓ Unit |
| Special Requirements | Batch Sundry | | |
| Special Requirements | ▼ Break Testing | V Offline | Casing |
| Variance | | Cementing | Clearance |

A. HYDROGEN SULFIDE

the Hydrogen Sulfide area must meet 43 CFR part 3170 requirements, which includes A Hydrogen Sulfide (H2S) Drilling Plan shall be activated AT SPUD. As a result, If Hydrogen Sulfide is encountered, please provide measured values and formations to the BLM. equipment and personnel/public protection items.

Possibility of water flows in the Salado

Abnormal pressures may be encountered within the 3rd Bone Spring and Wolfcamp Possibility of lost circulation in the Red Beds, Rustler, and Delaware. Formations.

B. CASING

- The 9-5/8 inch surface casing shall be set at approximately 814 feet (a minimum of 70 feet (Eddy County) into the Rustler Anhydrite, above the salt, and below usable fresh water) and cemented to the surface. The surface hole shall be 12-1/4 inch in diameter.
- to verify the top of the cement. Temperature survey will be run a minimum of survey with surface log readout will be used or a cement bond log shall be run be notified and a temperature survey utilizing an electronic type temperature If cement does not circulate to the surface, the appropriate BLM office shall six hours after pumping cement and ideally between 8-10 hours after completing the cement job. ಕ
 - Wait on cement (WOC) time for a primary cement job will be a minimum of hours or 500 pounds compressive strength, whichever is greater. (This is to include the lead cement) Ъ.
- Wait on cement (WOC) time for a remedial job will be a minimum of 4 hours after bringing cement to surface or 500 pounds compressive strength, whichever is greater. ပ
- If cement falls back, remedial cementing will be done prior to drilling out that ġ
- The minimum required fill of cement behind the 7-5/8 inch intermediate casing is: 7
- Cement to surface. If cement does not circulate see B.1.a, c-d above.

in the annulus Or operator shall run a CBL from TD of the 7-5/8" casing to surface cementing stage. Operator must run Echo-meter to verify Cement Slurry/Fluid top Operator has proposed to pump down 9-5/8" X 7-5/8" annulus after primary after the second stage BH to verify TOC.

top of the cement slurry between second stage BH and top out. Operator must run Submit results to the BLM. No displacement fluid/wash out shall be utilized at the one CBL per Well Pad.

If cement does not reach surface, the next casing string must come to surface.

Operator must use a limited flush fluid volume of 1 bbl following backside cementing procedures.

- The minimum required fill of cement behind the 5-1/2 inch production casing is: 3
- Cement should tie-back at least 200 feet into previous casing string. Operator shall provide method of verification.

Released to Imaging: 9/19/2025 3:18:06 PM

S. PRESSURE CONTROL

- specification to be readily available. No external damage to flex line. Flex line to be Variance approved to use flex line from BOP to choke manifold. Manufacturer's installed as straight as possible (no hard bends).
- tested when installed on the 9-5/8 inch surface casing. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the Operator has proposed a multi-bowl wellhead assembly. This assembly will only be surface casing shoe shall be 5000 (5IM) psi. $\vec{\alpha}$
- Wellhead shall be installed by manufacturer's representatives, submit documentation with subsequent sundry.
- If the welding is performed by a third party, the manufacturer's representative shall monitor the temperature to verify that it does not exceed the maximum temperature of the seal. ب
 - Manufacturer representative shall install the test plug for the initial BOP test. ပ
 - possible with a standard wellhead, the well head shall be cut off, cementing If the cement does not circulate and one inch operations would have been operations performed and another wellhead installed. ġ.
 - Whenever any seal subject to test pressure is broken, all the tests in 43 CFR **3172** i must be followed. \mathbf{o}

). SPECIAL REQUIREMENT (S)

Unit Wells

designation, but will replace the unit number with the participating area number when the The well sign for a unit well shall include the unit number in addition to the surface and bottom hole lease numbers. This also applies to participating area numbers. If a participating area has not been established, the operator can use the general unit sign is replaced.

Commercial Well Determination

A commercial well determination shall be submitted after production has been established for at least six months.

SPECIAL REQUIREMENT (S) E.

BOPE Break Testing Variance

- BOPE Break Testing is ONLY permitted for 5M BOPE or less. (Annular preventer must be tested to a minimum of 70% of BOPE working pressure and shall be higher than the MASP)
 - BOPE Break Testing is NOT permitted to drilling the production hole section.
- Variance only pertains to the intermediate hole-sections and no deeper than the Bone Springs formation.
 - While in transfer between wells, the BOPE shall be secured by the hydraulic carrier or cradle.
- Engineer (575-706-2779) prior to the commencement of any BOPE Break Testing Any well control event while drilling require notification to the BLM Petroleum operations.
- A full BOPE test is required prior to drilling the first deep intermediate hole section. If any subsequent hole interval is deeper than the first, a full BOPE test will be required. (200' TVD tolerance between intermediate shoes is allowable)
- The BLM is to be contacted (575-361-2822 Eddy County) 4 hours prior to BOPE
- As a minimum, a full BOPE test shall be performed at 21-day intervals.
- In the event any repairs or replacement of the BOPE is required, the BOPE shall test as per **43** CFR 3172.
- If in the event break testing is not utilized, then a full BOPE test would be conducted

Offline Cementing

Contact the BLM prior to the commencement of any offline cementing procedure.

GENERAL REOUIREMENTS

The BLM is to be notified in advance for a representative to witness:

- Spudding well (minimum of 24 hours)
- Setting and/or Cementing of all casing strings (minimum of 4 hours) BOPE tests (minimum of 4 hours) Ъ.
- X Eddy County

EMAIL or call the Carlsbad Field Office, 620 East Greene St., Carlsbad, NM 88220,

NM_CFO_DrillingNotifications@BLM.GOV BLM_NM_CF((575) 361-2822

Call the Hobbs Field Station, 414 West Taylor, Hobbs NM 88240, (575) 689-5981

Page 4 of 9

Approval Date: 05/19/2025

- properly plugged, the drilling rig shall not be removed from over the hole without Unless the production casing has been run and cemented or the well has been prior approval _;
- pressure rating to the wellhead and a pressure gauge that can be monitored after installing and testing the wellhead, by installing a blind flange of like skid/walking rig. Operator shall secure the wellbore on the current well, In the event the operator has proposed to drill multiple wells utilizing a while drilling is performed on the other well(s).
- When the operator proposes to set surface casing with Spudder Rig Ъ.
- Notify the BLM when moving in and removing the Spudder Rig.
- Notify the BLM when moving in the 2nd Rig. Rig to be moved in within 90 days of notification that Spudder Rig has left the location.
- BOP/BOPE test to be conducted per 43 CFR 3172 as soon as 2nd Rig is rigged up on well. Ξ.
- at all times during drilling and/or completion activities. Rig floor is defined as the the rig floor, unobstructed, readily accessible to the driller and will be operational Floor controls are required for 3M or Greater systems. These controls will be on substructure on which the draw works are located, this does not include the dog area immediately around the rotary table; the area immediately above the house or stairway area. 7
- spacer and drilling mud. The results should be documented in the driller's log and verified with a visual check and density or pH check to differentiate cement from For intervals in which cement to surface is required, cement to surface should be daily reports. ω.

A. CASING

API. The Operator can exchange the components of the proposal with that of superior strength (i.e. changing from J-55 to N-80, or from 36# to 40#). substantial (i.e. Multistage tool, ECP, etc.). The initial wellhead installed Changes to the approved APD casing program need prior approval if the items substituted are of lesser grade or different casing size or are Nonaltered cement plan has less volume or strength or if the changes are Changes to the approved cement program need prior approval if the on the well will remain on the well with spools used as needed.

- reaches a minimum compressive strength of 500 psi for all cement blends pressure until both of the following conditions have been met: 1) cement of both lead and tail cement, 2) until cement has been in place at least $\frac{8}{8}$ Wait on cement (WOC) for Potash Areas: After cementing but before integrity test can be done (prior to the cement setting up) immediately commencing any tests, the casing string shall stand cemented under hours. WOC time will be recorded in the driller's log. The casing after bumping the plug. \ddot{c}
 - cement slurry requirements. The casing integrity test can be done (prior to pressure until both of the following conditions have been met: 1) cement cement has been in place at least 8 hours. WOC time will be recorded in reaches a minimum compressive strength of 500 psi at the shoe, 2) until the driller's log. See individual casing strings for details regarding lead Wait on cement (WOC) for Water Basin: After cementing but before commencing any tests, the casing string shall stand cemented under the cement setting up) immediately after bumping the plug. 3
 - pounds compressive strength prior to cementing each casing string. Have well specific cement details onsite prior to pumping the cement for each Provide compressive strengths including hours to reach required 500 casing string. 4.
 - No pea gravel permitted for remedial or fall back remedial without prior authorization from the BLM engineer. S.
- anticipated to control the formation pressure to the next casing depth or at On that portion of any well approved for a 5M BOPE system or greater, a pressure integrity test of each casing shoe shall be performed. Formation total depth of the well. This test shall be performed before drilling more at the shoe shall be tested to a minimum of the mud weight equivalent than 20 feet of new hole. 6.
- If hardband drill pipe is rotated inside casing, returns will be monitored for metal. If metal is found in samples, drill pipe will be pulled and rubber protectors which have a larger diameter than the tool joints of the drill pipe will be installed prior to continuing drilling operations. 7.
 - Whenever a casing string is cemented in the R-111-Q potash area, the NMOCD requirements shall be followed. ∞

B. PRESSURE CONTROL

All blowout preventer (BOP) and related equipment (BOPE) shall comply with well control requirements as described in 43 CFR 3172

Page 6 of 9

Approval Date: 05/19/2025

- from BOP to choke manifold, replace if exterior is damaged or if line fails Anchor requirements, specification sheet and hydrostatic pressure These documents shall be posted in the company man's trailer and on the must meet the requirements of API 16C. Check condition of flexible line If a variance is approved for a flexible hose to be installed from the BOP can be exchanged with a hose of equal size and equal or greater pressure to the choke manifold, the following requirements apply: The flex line anchored according to Manufacturer's requirements. The flexible hose test. Line to be as straight as possible with no hard bends and is to be test certification matching the hose in service, to be onsite for review. \ddot{c}
- to match. The remote kill line is to be installed prior to testing the system 5M or higher system requires an HCR valve, remote kill line and annular and tested to stack pressure.
- If the operator has proposed a multi-bowl wellhead assembly in the APD. The following requirements must be met: 4.
- Wellhead shall be installed by manufacturer's representatives, submit documentation with subsequent sundry.
- representative shall monitor the temperature to verify that it does If the welding is performed by a third party, the manufacturer's not exceed the maximum temperature of the seal. :=
- Manufacturer representative shall install the test plug for the initial BOP test. Ξ.
 - Whenever any seal subject to test pressure is broken, all the tests in 43 CFR 3172.6(b)(9) must be followed. .<u>`</u>
- have been possible with a standard wellhead, the well head shall be If the cement does not circulate and one inch operations would cut off, cementing operations performed and another wellhead installed. >
- The appropriate BLM office shall be notified a minimum of 4 hours in advance for a representative to witness the tests. 5
- In a water basin, for all casing strings utilizing slips, these are to be which will be approximately six hours after bumping the plug. For can begin after cut-off or once cement reaches 500 psi compressive those casing strings not using slips, the minimum wait time before cut-off is eight hours after bumping the plug. BOP/BOPE testing strength (including lead cement), whichever is greater. However, set as soon as the crew and rig are ready and any fallback cement installation can be initiated four hours after installing the slips, remediation has been done. The casing cut-off and BOP

- if the float does not hold, cut-off cannot be initiated until cement reaches 500 psi compressive strength (including lead when specified)
- and BOP installation can be initiated at twelve hours after bumping the cement plug. The BOPE test can be initiated after bumping the In potash areas, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. For all casing strings, casing cut-off cement plug with the casing valve open. (only applies to single stage cement jobs, prior to the cement setting up.) :=;
 - immediately with the casing valve open. The operator also has the against the casing) pursuant to 43 CFR 3172 with the pressure not option of utilizing an independent tester to test without a plug (i.e. to exceed 70% of the burst rating for the casing. Any test against compressive strength, whichever is greater, prior to initiating the the casing must meet the WOC time for 8 hours or 500 pounds test (see casing segment as lead cement may be critical item). utilizing a test plug not a cup or J-packer and can be initiated The tests shall be done by an independent service company Ξ.
- If a twelve hour or twenty-four hour chart is used, tester shall make The test shall be run on a 5000 psi chart for a 2-3M BOP/BOP, on a 10000 psi chart for a 5M BOP/BOPE and on a 15000 psi chart for a 10M BOP/BOPE. If a linear chart is used, it shall be a one hour chart. A circular chart shall have a maximum 2 hour clock. a notation that it is run with a two hour clock. . .
- The results of the test shall be reported to the appropriate BLM $\dot{>}$
- All tests are required to be recorded on a calibrated test chart. A service company test will be submitted to the appropriate BLM copy of the BOP/BOPE test chart and a copy of independent ۲.
- 300 psi. The test will be held for a minimum of 10 minutes if test The BOP/BOPE test shall include a low pressure test from 250 to is done with a test plug and 30 minutes without a test plug. This test shall be performed prior to the test at full stack pressure. ΥΠ.
- depth exceeds 20 days. This test does not exclude the test prior to within 500 feet of the top of the Wolfcamp formation if the time between the setting of the intermediate casing and reaching this BOP/BOPE must be tested by an independent service company drilling out the casing shoe as per 43 CFR 3172. VIII.

C. DRILLING MUD

audio alarms, shall be operating before drilling into the Wolfcamp formation, and Mud system monitoring equipment, with derrick floor indicators and visual and shall be used until production casing is run and cemented.

D. WASTE MATERIAL AND FLUIDS

contained and disposed of properly at a waste disposal facility. No waste material created as a result of drilling operations and completion operations shall be safely or fluid shall be disposed of on the well location or surrounding area. Porto-johns and trash containers will be on-location during fracturing operations or any other All waste (i.e. drilling fluids, trash, salts, chemicals, sewage, gray water, etc.) crew-intensive operations.

JS 4/28/2025

Page 9 of 9

Approval Date: 05/19/2025



Operator Certification Data Report

U.S. Department of the Interior BUREAU OF LAND MANAGEMENT

Operator

knowledge, true and correct; and that the work associated with the operations proposed herein will be performed in conformity with this APD package and the terms and conditions under which it is approved. I also certify that I, or the company I represent, am responsible for the operations conducted under this application. These statements are subject to the provisions of 18 U.S.C. 1001 for the filing of false statements. proposed herein; that I am familiar with the conditions which currently exist; that I have full knowledge of state and Federal laws applicable to this operation; that the statements made in this APD package are, to the best of my I hereby certify that I, or someone under my direct supervision, have inspected the drill site and access route

NAME: SIVAPRAKASH SELVAM

Signed on: 09/23/2024

Title: Regulatory Clerk

Street Address: 22777 SPRINGWOODS VILLAGE PARKWAY

City: SPRING State: TX

Zip: 77389

Phone: (720)539-1673

Email address: SIVAPRAKASH.SELVAM1@EXXONMOBIL.COM

Field

Representative Name:

Street Address:

City: State:

Zip:

Phone:

Email address:

AFMSS

U.S. Department of the Interior BUREAU OF LAND MANAGEMENT

APD ID: 10400100853

Operator Name: XTO PERMIAN OPERATING LLC

Well Name: POKER LAKE UNIT 18-30 BD

Well Type: OIL WELL

Submission Date: 09/23/2024

Highlighted data reflects the most recent changes Show Final Text

Application Data 05/19/2025

Well Work Type: Drill Well Number: 201H

Section 1 - General

Tie to previous NOS? N 10400100853 APD ID:

User: SIVAPRAKASH SELVAM BLM Office: Carlsbad

Is the first lease penetrated for production Federal or Indian? FED Federal/Indian APD: FED

Submission Date: 09/23/2024

Title: Regulatory Clerk

Lease Acres:

Lease number: NMLC065705B

Reservation: Allotted? Surface access agreement in place? Federal or Indian agreement: FEDERAL

Agreement number: NMNM71016X Agreement in place? YES

Agreement name: POKER LAKE UNIT

Keep application confidential? Y

Permitting Agent? NO

APD Operator: XTO PERMIAN OPERATING LLC

Operator letter of

Zip: 79707

Operator Organization Name: XTO PERMIAN OPERATING LLC

Operator Info

Operator Address: 6401 HOLIDAY HILL ROAD BLDG 5

Operator PO Box:

Operator City: MIDLAND

State: TX

Operator Phone: (432)683-2277

Operator Internet Address:

Section 2 - Well Information

Master Development Plan name: Well in Master Development Plan? NO

Well in Master Drilling Plan? NO Well in Master SUPO? NO

Well Name: POKER LAKE UNIT 18-30 BD

Field/Pool or Exploratory? Field and Pool

Master Drilling Plan name:

Master SUPO name:

Well Number: 201H

Well API Number:

Pool Name: BONE SPRING, EAST Field Name: PIERCE CROSSING

Page 1 of 3

Operator Name: XTO PERMIAN OPERATING LLC

Well Name: POKER LAKE UNIT 18-30 BD

Well Number: 201H

is the proposed well in an area containing other mineral resources? USEABLE WATER, NATURAL GAS, OIL

New surface disturbance? N Use Existing Well Pad? Y Is the proposed well in a Helium production area? N

Type of Well Pad: MULTIPLE WELL

Number: A Multiple Well Pad Name: POKER LAKE UNIT 18-19 18-30 BD

Number of Legs: 1

Well Work Type: Drill

Well Class: HORIZONTAL

Well Type: OIL WELL

Describe Well Type:

Well sub-Type: INFILL

Describe sub-type:

Distance to lease line: 265 FT Distance to nearest well: 30 FT Distance to town:

Reservoir well spacing assigned acres Measurement: 400 Acres

618.013003.32_10_XTO_POKER_LAKE_UNIT_18_30_BD_201H_C_102_FINAL_09_12_2024_202503101 Well plat:

44253.pdf

Duration: 45 DAYS Well work start Date: 10/03/2025

Section 3 - Well Location Table

Survey Type: RECTANGULAR

Describe Survey Type:

Datum: NAD83

Survey number:

Vertical Datum: NAVD88

Reference Datum: GROUND LEVEL

| Vill this well produce | |
|------------------------|------------------------------------------------|
| αΛ | 935 |
| а | 937 |
| levation | 318 0 - 617 6 |
| sase Number | NMLC0 318 65705B 0 NMLC0 - 65705B 617 |
| зге Туре | [₽] L L |
| eridian | NEW MEXI CO NEW MEXI CO |
| tate | > <i>▽</i> > <i>▽</i> |
| Лjuno | EDD Y |
| əpnjibuc | - EI |
| atifude | 32.13671 8 32.13671 8 8 |
| liquot/Lot/Tract | VNE VNE quot |
| ection | |
| suge | 1,, |
| dsw | 25S 25S 25S |
| W Indicator | H FEL |
| Joo7-W | 11, 11 |
| S Indicator | |
| foo7-2 | 1 |
| ellbore | SHL Leg KOP Ceg H1 |

Page 2 of 3


Operator Name: XTO PERMIAN OPERATING LLC

Well Name: POKER LAKE UNIT 18-30 BD

Well Number: 201H

| Will this well produce from this | > | > | > | > |
|----------------------------------|---------------------|---------------------|---------------------|---------------------|
| ΠVT | 100 72 | 100 72 | 100 72 | 100 72 |
| MD | 104 95 | 157 00 | 229 00 | 229 55 |
| noijsvəl∃ | - 689 2 | - 689 2 | - 689 2 | - 689 2 |
| Lease Number | NMLC0 65705B | NMLC0 70341 | NMLC0 70125 | NMLC0 70125 |
| Гезге Туре | Ц | IL. | Щ | ш 🧀 |
| Meridian | NEW MEXI CO | NEW MEXI CO | NEW MEXI CO | NEW MEXI CO |
| State | NEW MEXI CO | NEW MEXI CO | NEW MEXI CO | NEW MEXI CO |
| County | EDD Y | EDD | EDD | EDD |
| Pongitude | - 103.9185 91 | - 103.9185 69 | - 103.9185 35 | - 103.9185 34 |
| Latitude | 32.13717 2 | 32.12283 4 | 32.10119 7 | 32.10094 9 |
| Pliquot/Lot/Tract | Aliquot NWNE | Aliquot NWNE | Aliquot | Aliquot |
| Section | 18 | 19 | 30 | 30 |
| Range | 30E | 30E | 30E | 30E |
| dswT | 25S | 25S | 25S | 25S |
| EW Indicator | FEL | FEL | FEL | FEL |
| FW-Foot | 201 0 | 201 | 201 0 | 201 0 |
| NS Indicator | FNL | FSL | N N N | FN |
| too-Foot | 100 | 0 | 255 6 | 264 6 |
| Wellbore | PPP Leg #1-1 | PPP Leg #1-2 | EXIT Leg #1 | BHL Leg #1 |

| API Number: 330-015- Pool Code API Number: Pool Code 300-015- Pool Code OGRID No. Surface Owner: □State □Tee □Tribal 図Federal Code: □ State □Tee □Tribal 図Federal B 18 Lot Decirion Colspan="6">Township Range Lot Colspan="6">Colspan="6">Lot A00.00 Infill or Defining Well Defining A00.00 Infill or Defining Well Defining A00.00 Infill or Defining Well Defining B 18 Z5S 30E Lot B 18 Township Range Lot B 18 Township Range Lot B 18 Colspan="6">Colspan="6">Colspan="6">Colspan="6">C | | | Submita Type: Type: | EAST Well Numbe Ground Leve | Report 201H 2 Elevation 3,180' County EDDY EDDY EDDY EDDY EDDY EDDY |
|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------|
| Pool Code [96473] Property Name Prop | Pool | NINFORMATION Name PIERCE CROSSINC UNIT 18-30 BD DPERATING, LLC. Mineral Owner: State R. from EW 2,365 FEL 2,365 FEL 2,010 FEL Coverlapping Spacing Unit NO No Not Setbacks are under C No State (KOP) Ft. from EW La 2,365 FEL Noint (KOP) Ft. from EW La 2,365 FEL Noint (KOP) Ft. from EW La 2,365 FEL Point (FTP) | ### Type: Type: Type: Lude | IG, EAST Well Number Ground Level 1 A S A Ground Level 1 A | O1H O1H County EDDY EDDY EDDY EDDY EDDY EDDY EDDY |
| Property Namn Property Namn Operator Nam Operator Nam Operator Nam Operator Nam Operator Nam Sange | Pool | Name PIERCE CROSSINC UNIT 18-30 BD DPERATING, LLC. Mineral Owner: State E. Location Ft. from E/W 2,365 FEL Coverlapping Spacing Unit DO Well Setbacks are under C Pr. from E/W 2,365 FEL Point (KOP) Ft. from E/W 1,2,365 FEL Point (FTP) | ## BONE SPRII E Consolidate Consolidat | IG, EAST Well Number Ground Level J 3, Federal 103.919737 IO3.918534 IO3.918537 | County County EDDY EDDY EDDY EDDY EDDY EDDY |
| Property Namm Property Namm Operator Namm Operator Namm Range 25S 30E 30E 25S 30E | POKER LAKE XTO PERMIAN C Surface Ho Ft. from N/S 2,646 FNL Ft. from N/S Ft. from N/S | Name PIERCE CROSSINC UNIT 18-30 BD DPERATING, LLC. Mineral Owner: □State le Location Ft. from E/W 2,365 FEL Coverlapping Spacing Unit COVERTIFY Definit (KOP) Ft. from E/W COVERTIFY C | ## BONE SPRII Consolidate | Cy EAST State 103.919737 | County County EDDY EDDY EDDY EDDY EDDY EDDY |
| Property Name | POKER LAKE XTO PERMIAN C | UNIT 18-30 BD PERATING, LLC. Mineral Owner: State Location Ft. from E/W 2,365 FEL 2,010 FEL Overlapping Spacing Unit NO Well Setbacks are under C Well Setbacks are under C S,365 FEL La 2,3165 FEL La 2,3165 FEL Point (KOP) Ft. from E/W La 2,365 FEL Point (FTP) | | Well Number 3, 3, 3, 2, 2, 3, 3, 3, | County County EDDY EDDY EDDY EDDY EDDY EDDY EDDY EDDY |
| Operator Name | Surface Ho Surface Ho Ft. from N/S 265 FNL Bottom Ho Ft. from N/S 2,646 FNL Kick Off P Ft. from N/S 265 FNL Ft. from N/S Ff. from N/S Ff. from N/S Ff. from N/S | PERATING, LLC. Mineral Owner: State Location Ft. from E/W 2,365 FEL 2,010 FEL Coverlapping Spacing Unit Coverlapping Spaci | | Ground Level 3, 3, 5 5 5 5 5 5 5 5 5 | Elevation 7,180' County EDDY EDDY EDDY EDDY EDDY |
| wnship Range 25S 30E 25S 30E 25S 30E miship Range 25S 30E 25S 30E 25S 30E 25S 30E 25S 30E | | Mineral Owner: State E. Location Pt. from E/W 2,365 FEL 2,010 FEL Coverlapping Spacing Unit Cove | | ongitude 103.919737 103.918534 ion Code Mycs □ No | County EDDY EDDY EDDY EDDY |
| Township Range 30E | | Ft. from E/W | | ongitude 103.919737 103.918534 ion Code MYes □ No | County EDDY County County EDDY |
| 1 | | Ft. from EW 2,365 FEL 1e Location Rt. from EW 2,010 FEL Overlapping Spacing Unit no well Setbacks are under C well Setbacks are Lagonint (KOP) Ft. from EW 2,365 FEL Point (FTP) | | ongitude 103.919737 103.918534 ion Code ⊠ Yes □ No | County County County County EDDY |
| Township Range 30E | 10 7 | Location Ft. from EW 2,010 FEL 2,010 FEL Overlapping Spacing Unit no Well Setbacks are under C Well Setbacks are under C 2,365 FEL Point (FTP) | | ongitude 103.918534 103.918534 Ion Code Ion Code Ion Code Ion Code Ion Code | County County EDDY EDDY EDDY |
| nn Township Range 25S 30E Infill Infill Infill Range 3 25S 30E 3 25S 30E | | Ft. from E/W 2,010 FEL 2,010 FEL Overlapping Spacing Unit no Nell Setbacks are under C well Setbacks are Lt. from E/W Ft. from E/W 2,365 FEL Point (FTP) | | ongitude 103.918534 ion Code | EDDY County County EDDY |
| 25S 30E | - 9 | 2,010 FEL 2,010 FEL Overlapping Spacing Unit no Well Setbacks are under C oint (KOP) Ft. from E/W 2,365 FEL Point (FTP) | | 103.918534 103.918534 In Code | EDDY County EDDY |
| Infill or Defining Well Infill or Defining Well Infill Inf | 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 | Overlapping Spacing Unit No Well Setbacks are under C oint (KOP) Ft. from E/W 2,365 FEL Point (FTP) | | ion Code No Yes □ No Longitude | County |
| Township Range 1 | Ft. from 265 | Well Serbacks are under C oint (KOP) Ft. from E/W 2,365 FEL Point (FTP) | | No N | County |
| Township Range | Kick Off P Ft. from N/S 265 FNL First Take | oint (KOP) Ft. from E/W 2,365 FEL Point (FTP) | | ongitude | County |
| Township Range Township Range 25S 30E 25S 30E | Kiek Off P | ≥ FEL | 36718 | ongitude 103.919737 | County |
| 25S 30E Township Range Township Range | 265 FNL First Take | | 36718 | 103.919737 | EDDY |
| Township Range 25S 30E Township Range | First Take Ft. from N/S | | | | |
| Township Range 25S 30E | Ft. from N/S | | | | |
| 25S 30E Township Range | | Ft. from E/W | Latitude | Longitude | County |
| Township Range | 100 FNL | 2,010 FEL | 32.137172 | -103.918591 | EDDY |
| Township Range | Last Take I | | • | - | |
| | Ft. from N/S | | | Longitude | County |
| 30 25S 30E | 2,556 FNL | 2,010 FEL | 32.101197 -1 | -103.918535 | EDDY |
| | | | Ground Elevation | | |
| NMNM-071016X Spacing U | Spacing Unit Type: Morizontal Vertical | I 🗖 Vertical | | 3,180 | |
| OPERATOR CERTIFICATIONS | SI | SURVEYOR CERTIFICATIONS | ONS | | |
| eby certify that the information contained herein is true a of my knowledge and belief, and, if the well is vertical or | | I hereby certify that the well location shown on this plat was plotted from field notes of actual surveys made by me or under my supervision, and that the same is true and | ocation shown on this p under my supervision, | plat was plotted fr. , and that the same | om field notes of e is true and |
| that this organization either owns a working interest or unleased mineral interest in the land including the proposed bottom hole location or has a right to drill this at this location pursuant to a contract with an owner of a working interest or unleased mineral interest, or a voluntary pooling agreement or a computsory | | vrect to the best of my belie | Ą | MOTTIO " | /- |
| ng order of heretofore entered by the division. | | | N. | AN MEXICO VAN MEN | MARP |
| If this well is a horizontal well, I further certify that this organization has received the consent of at least one lessee or owner of a working interest or unlesseed mineral interest in each tract (in the target pool or information) in which any part of the well's completed interval will be located or obtained a compulsory pooling order from the division. | nization has cing interest or information) in d or obtained a | `` | PROF | PROF | FYOR |
| ALDA 9/23/24 | | | | SONAL SONAL | 14ne |
| Signature Date | | Signature and Seal of Professional Surveyor | ional Surveyor | | |
| Adrian Baker | | ARK DILLON HARP 23786 | | 9/12/2024 | |
| Printed Name | | Certificate Number | Date of Survey | | |
| adrianDakei @exxonninoni.com Email Address | | | | | |



Page 1 of 6

VAFMSS

Drilling Plan Data Report

BUREAU OF LAND MANAGEMENT U.S. Department of the Interior

APD ID: 10400100853

Operator Name: XTO PERMIAN OPERATING LLC

Well Name: POKER LAKE UNIT 18-30 BD

Well Type: OIL WELL

Highlighted data reflects the most ecent changes

Submission Date: 09/23/2024

Show Final Text

Well Work Type: Drill Well Number: 201H

- Geologic Formations - Section

| Producing Formatio | Z | z | z | z | z | z | > | > | > | > | > |
|-----------------------------|---------------|-------------------------|----------|--------------|------------------------------------------------|------------------------------------------------|------------------------------------------------|------------------------------------------------|------------------------------------------------|------------------------------------------------|------------------------------------------------|
| Mineral Resources Producing | USEABLE WATER | USEABLE WATER | NONE | NONE | NATURAL GAS, OIL, OTHER : Produced water |
| sejpolodji I | ALLUVIUM | ANHYDRITE, SANDSTONE | SALT | SALT | LIMESTONE, SANDSTONE | SANDSTONE | LIMESTONE, SANDSTONE | LIMESTONE, SANDSTONE | LIMESTONE, SANDSTONE | LIMESTONE, SANDSTONE | LIMESTONE, SANDSTONE |
| Measured | 0 | 714 | 1146 | 3313 | 3532 | 2697 | 7295 | 8057 | 8503 | 9373 | 9748 |
| True Vertical Measured | 0 | 714 | 1146 | 3313 | 3532 | 5697 | 7295 | 8057 | 8503 | 9373 | 9748 |
| Flevation | 3180 | 2466 | 2034 | -133 | -352 | -2517 | -4115 | -4877 | -5323 | -6193 | -6568 |
| Formation Name | QUATERNARY | RUSTLER | SALADO | BASE OF SALT | DELAWARE | BRUSHY CANYON | BONE SPRING | BONE SPRING 1ST | BONE SPRING 2ND | BONE SPRING 3RD | BONE SPRING 3RD |
| Formation | 15648103 | 15648104 | 15648105 | 15648106 | 15648107 | 15648108 | 15648109 | 15648110 | 15648111 | 15648112 | 15648102 |

- Blowout Prevention Section 2

Pressure Rating (PSI): 5M

Rating Depth: 10072

Equipment: Once the permanent WH is installed on the surface casing, the BOP equipment will have a 5M Hydril Annular & a 10M Triple Ram BOP. XTO will use a Multi-Bowl System which is attached Requesting Variance? YES

Variance request: XTO requests a variance to allow the use of a flex hose. See attached. XTO requests a variance to be able to batch drill this well if necessary. XTO requests a variance to utilize a spudder rig. See attached. XTO requests a break test variance. See attached

Testing Procedure: All BOP testing will be done by an independent service company. Operator will test as per 43 CFR

Page 2 of 6

Operator Name: XTO PERMIAN OPERATING LLC

Well Name: POKER LAKE UNIT 18-30 BD

Well Number: 201H

Choke Diagram Attachment:

POKER_LAKE_UNIT_18_19_

BOP Diagram Attachment:

18_30_BD__5M10M_BOP_20250306130925.pdf POKER_LAKE_UNIT_18_19

_10MCM_20250306130901.pdf

18_30_BD

Section 3 - Casing

| Body SF | 19.3 | 2.64 | 2.16 |
|--------------------------------|----------------------|-----------------------------|------------------------------|
| Body SF Type | DRY | DRY | DRY |
| 48 Iniol | 19.3 5 | 2.64 | 2.16 |
| Joint SF Type | 7.73 1.74 DRY | DRY | 2.08 1.05 DRY |
| Burst SF | 1.74 | 2.2 | 1.05 |
| Collapse SF | 7.73 | 2.5 | 2.08 |
| Joint Type | BUTT | FJ | OTHER - TPN/ Wedge 441 |
| Meight | 40 | 29.7 | 20 |
| Grade | J-55 , | L-80 29.7 | |
| Calculated casing length MD | 814 | | -6892 22955 P- |
| Bottom Set MSL | 2366 | -5976 9170 | -6892 |
| Top Set MSL | 3180 | 3180 | 10072 3180 |
| Bottom Set TVD | 814 | 9156 | 10072 |
| QVT fə2 qoT | 0 | 0 | 0 |
| Bottom Set MD | 814 | 9170 | 22955 0 |
| Top Set MD | 0 | 0 | 0 |
| Tapered String | z | > | > |
| Standard | API | API | NON API |
| noiiibno | NEW | NEW | NEW |
| Size GsJ | 9.625 | 7.625 | 5.5 |
| əzi2 əloH | 12.2 5 | 8.75 | 6.75 |
| String Type | 1 SURFACE 12.2 9.625 | INTERMED 8.75 7.625 IATE | PRODUCTI ON |
| Ol gnissO | _ | 7 | က |
| | | | |

Casing Attachments

Casing ID: 1 String SURFACE

Inspection Document:

Spec Document:

Tapered String Spec:

Casing Design Assumptions and Worksheet(s):

Operator Name: XTO PERMIAN OPERATING LLC

Well Name: POKER LAKE UNIT 18-30 BD

Well Number: 201H

Casing Attachments

Casing ID: 2 String INTERMEDIATE

Inspection Document:

Spec Document:

Tapered String Spec:

Casing Design Assumptions and Worksheet(s):

Casing ID: 3 String

Inspection Document:

PRODUCTION

Spec Document:

TPN_5.500_20.00_0.361_P110_ICY_20250306131529.pdf

Wedge_441__5.500__20.00_0.361_P110_ICY_20250306131528.pdf

Tapered String Spec:

POKER_LAKE_UNIT_18_30_BD_201H_CSG_20250306132615.pdf

Casing Design Assumptions and Worksheet(s):

POKER_LAKE_UNIT_18_30_BD_201H_CSG_20250306132640.pdf

Section 4 - Cement

| səvitibbA | NA | 2% CaCl | NA | NA |
|--------------|---------------------|---------|--------------|--------------|
| Cement type | EconoCem- HLTRRC | Class C | 100 Class C | 100 Class C |
| Excess% | 100 | 100 | 100 | 100 |
| Cu Ft | 10.5 317.9 | 175.5 | 851.2 | 432 |
| Density | 10.5 | 14.8 | 14.8 851.2 | 14.8 |
| bləiY | 1.87 | 1.35 | 1.33 | 1.35 |
| Quantity(sx) | 170 | 130 | 640 | 320 |
| GM mottoB | 814 | 814 | 5697 | 9170 |
| □M qoT | 0 | 0 | 0 | 5697 |
| Stage Tool | | | | |
| lisT\bs9J | Lead | Tail | Lead | Tail |
| String Type | SURFACE | SURFACE | INTERMEDIATE | INTERMEDIATE |

Operator Name: XTO PERMIAN OPERATING LLC

Well Name: POKER LAKE UNIT 18-30 BD

Well Number: 201H

| səvitibbA | NA | NA |
|---------------------|------------|---------------------|
| Cement type | NeoCem | VersaCem |
| Excess% | 30 | 30 |
| Cu Ft | 53.8 | 1464. 7 |
| Density | 11.5 | 1.51 13.2 1464 7 |
| bl⊖iY | 2.69 | 1.51 |
| Quantity(sx) | 20 | 970 |
| GM mottoB | 9370 | 9370 2295 5 |
| dΜ qoT | 8870 9370 | 9370 |
| Stage Tool Depth | | |
| lisT\bs9J | Lead | Tail |
| 9dyT gnint <i>S</i> | PRODUCTION | PRODUCTION |

Section 5 - Circulating Medium

Mud System Type: Closed

Will an air or gas system be Used? NO

Description of the equipment for the circulating system in accordance with 43 CFR 3172:

Diagram of the equipment for the circulating system in accordance with 43 CFR 3172:

Describe what will be on location to control well or mitigate other conditions: The necessary mud products for weight addition and fluid loss control will be on location at all times.

volume. A mud test will be performed every 24 hours to determine: density, viscosity, strength, filtration and pH as necessary. Use available solids controls equipment to help keep mud weight down after mud up. Rig up solids control equipment to Describe the mud monitoring system utilized: Spud with fresh water/native mud. Drill out from under surface casing with recorded on a daily drilling report after mudding up. A Pason or Totco will be used to detect changes in loss or gain of mud Saturated Salt solution. Saturated Salt mud will be used while drilling through the salt formation. Use fibrous materials as needed to control seepage and lost circulation. Pump viscous sweeps as needed for hole cleaning. Pump speed will be operate as a closed loop system.

Circulating Medium Table

| esiterietisese Characteristics | | | |
|--------------------------------|--------------------|---------------------------------------------------------------------|------------------|
| Filtration (cc) | | | |
| (mqq) (tinits) | | | |
| Viscosity (CP) | | | |
| Н | | | |
| Gel Strength (lbs/100 sqft) | | | |
| Density (lbs/cu ft) | | | |
| (lsg/sdl) tdgiaW xsM | 8.9 | 9.5 | 10.7 |
| Min Weight (Ibs/gal) | 8.4 | 6 | 10.2 |
| θd√T buM | WATER-BASED MUD | OTHER: Saturated Salt for Salt Interval/Direct Emulsion | OIL-BASED MUD |
| Bottom Depth | 814 | 9170 | 9170 2295 |
| Тор Depth | 0 | 814 | 9170 |

Page 4 of 6

Page 5 of 6

Operator Name: XTO PERMIAN OPERATING LLC

Well Name: POKER LAKE UNIT 18-30 BD

Well Number: 201H

Section 6 - Test, Logging, Coring

List of production tests including testing procedures, equipment and safety measures:

Open hole logging will not be done on this well.

List of open and cased hole logs run in the well:

GAMMA RAY LOG, CEMENT BOND LOG, DIRECTIONAL SURVEY, MEASUREMENT WHILE DRILLING, MUD LOG/GEOLOGICAL LITHOLOGY LOG,

Coring operation description for the well:

No Coring is planned for the well.

Section 7 - Pressure

Anticipated Bottom Hole Pressure: 5604

Anticipated Bottom Hole Temperature(F): 185

Anticipated abnormal pressures, temperatures, or potential geologic hazards? N ${\sf O}$

Anticipated Surface Pressure: 3388

Describe:

Contingency Plans geoharzards description:

Contingency Plans geohazards

Hydrogen Sulfide drilling operations plan required? YES

Hydrogen sulfide drilling operations

XTO_Energy_H2S_Plan_Updated_20240827051401.pdf

Section 8 - Other Information

Proposed horizontal/directional/multi-lateral plan submission:

POKER_LAKE_UNIT_18_30_BD_201H_DD_20240905113117.pdf

Section_and_Plan_View_1__20250310130308.pdf Poker_Lake_Unit_18_30_BD_201H_Formation_

Other proposed operations facets description:

proposed operations facets attachment: Other

POKER_LAKE_UNIT_18_30_BD_201H_CMT_20240905113039.pdf

_18_30_BD_MBS_9.625_x_7.625_3String_20240827064007.pdf POKER_LAKE_UNIT_18_19_

H2S_Diagram_POKER_LAKE_UNIT_18_19___18_30_BD_20250307104843.pdf

18_30_BD_NGMP_Form_20250311142454.pdf POKER_LAKE_UNIT_18_19_

Other Variance request(s)?:

Other Variance attachment:

_18_30_BD__OLCV_20240905101924.pdf POKER_LAKE_UNIT_18_19_


BOP_Break_Test_Variance_20240827064431.pdf


Well Name: POKER LAKE UNIT 18-30 BD

Operator Name: XTO PERMIAN OPERATING LLC

Well Number: 201H

Spudder_Rig_Request_20240827064424.pdf Updated_Flex_Hose_20240827064426.pdf





Tenaris

TenarisHydril Wedge



| Coupling | Pipe Body |
|----------------------|----------------------|
| Grade: P110-1CY | Grade: P1104CY |
| Body: White | 1st Band: White |
| 1st Band: Pale Green | 2nd Band: Pale Green |
| 2nd Band: - | 3rd Band: Pale Green |
| 3rd Band: - | 4th Band: - |
| | 5th Band: - |
| | |

Printed on: 01-08-2025

| Outside Diameter | 5.500 in. | .500 in. Wall Thickness | 0.361 in. | Grade | P110-ICY |
|------------------------------------------|-------------------|-------------------------|--------------|-------|----------|
| Min, Wall Trickness Connection OD Option | 87.50% REGULAR | Pipe Body Lint | Arl Standard | Jype | Casing |

| Data |
|------|
| Body |
| Pipe |

| Collapse Pressure | | Nominal ID 4.778 in. |
|------------------------------|------------------------------------------|----------------------------|
| SMYS | 4.653 in. OD Tolerance API | Drift 4.653 in. |
| Min. Internal Yield Pressure | 20.00 lb/ft Plain End Weight 19.83 lb/ft | Nominal Weight 20.00 lb/ft |
| Body Yield Strength | 5.500 in. Wall Thickness 0.361 in. | Nominal OD 5.500 in. |
| Performance | | Geometry |
| | | |

Connection Data

12,300 psi

729 x1000 lb 14,360 psi 125,000 psi

| | Performance | |
|-----------|----------------------------|----------------|
| 5.852 in. | Tension Efficiency | 81.50 % |
| 8.714 in. | Joint Yield Strength | 594 x1000 lb |
| 4.778 in. | Internal Pressure Capacity | 14,360 psi |
| 3.780 in. | Compression Efficiency | 81.50 % |
| 3.40 | Compression Strength | 594 x1000 lb |
| Regular | Max. Allowable Bending | 84.76 °/100 ft |
| | External Pressure Capacity | 12,300 psi |

| Make-Up Torques | |
|-------------------------|--------------|
| Minimum | 15,000 ft-lb |
| Optimum | 16,000 ft-lb |
| Maximum | 19,200 ft-lb |
| | |
| Operation Limit Torques | |
| Operating Torque | 36,000 ft-lb |
| Yield Torque | 42,000 ft-lb |
| | |
| Buck-On | |
| Minimum | 19,200 ft-lb |
| Maximum | 20,700 ft-lb |
| | |

Connection OD Option

Threads per inch

Coupling Length

Connection ID Make-up Loss

Connection OD

Geometry

Notes

This connection is fully interchangeable with:

Wedge 44(18 - 5.5 in. - 0.394 (17 00) in. (lb/ft),

Wedge 44(18 - 5.5 in. - 0.394 (17 00)), 0.351 (20,00) / 0.415 (23,00) in. (lb/ft)

Connections with Dopeless® Technology are fully compatible with the same connection in its doped version

For the lastest performance data, always visit our website: www.tenaris.com For further information on concepts indicated in this datasheet, download the Datasheet Manual from www.tenaris.com

Tenaris has issued this document for general information only, and the information in this document, including, without limitation, any pictures, drawings or designs ("information") is not interpreted to constitute professional or any other type of advice or recommendation and is provided on an "as is" basis. No warranty is given. Tenaris has not independently verified any information —if any provided by the user in connection with, or for the purpose of, the Information contained hereunder. The use of the Information is at user's own risk and Tenaris does not assume any responsibility or liability of any kind for any loss, damage or injury resulting from or in connection with any information contained hereunder or any use thereof. The Information in this document is subject to change or modification without notice. Innaris's products and services are subject to Tenaris's standard terms and conditions or denaise or modification without notice. Innaris's products and services are subject to Tenaris's contract of sale or services, as the case maybe, between petitioner and Tenaris. For more complete information please contact a Tenaris's representative or visit our website at www.tenaris.com. ©lenaris subject by the production of the services.

TPN Tenaris



| Coupling | Pipe Body |
|----------------------|----------------------|
| Grade: P1104CY | Grade: P1104CY |
| Body: White | 1st Band: White |
| 1st Band: Pale Green | 2nd Band: Pale Green |
| 2nd Band: - | 3rd Band: Pale Green |
| 3rd Band: - | 4th Band: - |
| | 5th Band: - |
| | 6th Band: - |

Printed on: 04/23/2024

| Customer | XTO ENERGY INC. Wall Thickness | | 0.361 in. Grade | rade | P110-ICY |
|----------------------|--------------------------------|-----------------|------------------------|------|----------|
| Outside Diameter | 5.500 in. | Pipe Body Driff | API Standard Type | уре | Casing |
| Min. Wall Thickness | 87.50 % | | | | |
| Connection OD Option | REGULAR | | | | |
| | | | | | |

| ata |
|-----|
| Ö |
| ģ |
| B |
| Φ |

| | Performance | Body Yield Strength | Min. Internal Yield Pressure | SMYS | Collapse Pressure | |
|----------------|-------------|-------------------------------------------|------------------------------|----------------------------|----------------------|--|
| | | 5.500 in. Wall Thickness 0.361 in. | Plain End Weight 19.83 lb/ft | 4.653 in. OD Tolerance API | | |
| Pipe Body Data | Geometry | Nominal OD 5.500 in. V | Nominal Weight 20.00 lb/ft P | Drift 4.653 in. C | Nominal ID 4.778 in. | |

| | Performance |
|-------|-----------------------------------------|
| Ti. | Body Yield Strength 729 x1000 lb |
| lb/ft | Min, Internal Yield Pressure 14,360 psi |
| API | SMYS 125,000 psi |
| | Collapse Pressure 12,300 psi |
| | |

Connection Data

| External Pressure Capacit | | |
|----------------------------|-----------|----------------------|
| Max. Allowable Bending | Regular | Connection OD Option |
| Compression Strength | 5 | Threads per inch |
| Compression Efficiency | 4.204 in. | Make-up Loss |
| Internal Pressure Capacity | 4.778 in. | Connection ID |
| Joint Yield Strength | 8.408 in. | Coupling Length |
| Tension Efficiency | 6.300 in. | Connection OD |
| Performance | | Geometry |
| | | colliection Data |

| 5 | 12,300 psi | ernal Pressure Capacity |
|---------------------|--------------|-------------------------|
| Vield Torci is | 10017 #01 | C. Allowable Deliuling |
| Operaung rorque | # 001/0 | Allowoblo Bonding |
| Onorrafing Toron | 129 AT000 ID | ipression ou engui |
| | 729 ×10001b | opression Strenoth |
| Operation I mit Tor | 100 % | npression Efficiency |
| Maximum | 14,360 psi | rnal Pressure Capacity |
| Optimum | 729 x1000 lb | nt Yield Strength |
| Minimum | 100 % | sion Efficiency |
| Make-Up Torques | | erformance |

29,300 ft-lb 32,500 ft-lb

21,100 ft-lb 22,600 ft-lb 24,100 ft-lb

Notes

For the lastest performance data, always visit our website: www.tenaris.com For further information on concepts indicated in this datasheet, download the Datasheet Manual from www.tenaris.com

PI-0/CII-3 Tenaris has issued this document for general information only, and the information in this document, including, without limitation, any pictures, drawings or designs ("Information") is not intended to constitute professional or any other type of advice or recommendation and is provided on an "as is" basis. No warranty is given. Tenaris has not independently verified any information —if any provided by the user in connection with, or for the purpose of, the Information contained hereunder. The use of the Information is at user's own risk and Tenaris does not assume any responsibility or flability of any kind for any loss, damage or injury resulting from, or in commedion with any Information contained hereunder or any use thereof. The Information in this document is subject to change or modification without notice. Flantaris is products and services are subject to Tenaris's standard terms and conditions or document in the respective contracts of sale or services, as the case maybe, between petitioner and Tenaris. For more complete information please contact a Tenaris's representative or visit our website at www.tenaris.com. ©Tenaris 2024. All rights reserved.

Casing Assumptions

Casing Design

| SF Tension | 19.35 | 2.05 | 2.64 | 2.16 | 2.16 |
|-------------------------|-----------|-------------|---------------------|------------------------------|-------------------------------|
| SF SF Burst Collapse | 7.73 | 2.86 | 2.50 | 2.31 | 2.08 |
| SF Burst | 1.74 | 3.03 | 2.20 | 1.05 | 1.05 |
| New/Used | New | New | New | New | New |
| Collar | BTC | Flush Joint | Flush Joint | Semi-Premium/ TPN | RY P-110 ICY Semi-Flush/Wedge |
| Grade | J-55 | RY P-110 | HC L-80 | RY P-110 ICY Semi-Premium/ | RY P-110 ICY |
| Weight | 40 | 29.7 | 29.7 | 20 | 20 |
| OD Csg | 9.625 | 7.625 | 7.625 | 5.5 | 5.5 |
| Depth | 0' - 814' | 0, - 4000, | 4000' – 9169.81' | 0' - 9069.81' | 9069.81' - |
| Hole Size | 12.25 | 8.75 | 8.75 | 6.75 | 6.75 |

Casing Assumptions

Casing Design

| SF Tension | 19.35 | 2.05 | 2.64 | 2.16 | 2.16 |
|-------------------------|-----------|-------------|---------------------|------------------------------|-------------------------------|
| SF SF Burst Collapse | 7.73 | 2.86 | 2.50 | 2.31 | 2.08 |
| SF Burst | 1.74 | 3.03 | 2.20 | 1.05 | 1.05 |
| New/Used | New | New | New | New | New |
| Collar | BTC | Flush Joint | Flush Joint | Semi-Premium/ TPN | RY P-110 ICY Semi-Flush/Wedge |
| Grade | J-55 | RY P-110 | HC L-80 | RY P-110 ICY Semi-Premium/ | RY P-110 ICY |
| Weight | 40 | 29.7 | 29.7 | 20 | 20 |
| OD Csg | 9.625 | 7.625 | 7.625 | 5.5 | 5.5 |
| Depth | 0' - 814' | 0, - 4000, | 4000' – 9169.81' | 0' - 9069.81' | 9069.81' - |
| Hole Size | 12.25 | 8.75 | 8.75 | 6.75 | 6.75 |



HYDROGEN SULFIDE (H2S) CONTINGENCY PLAN

Assumed 100 ppm ROE = 3000

100 ppm H2S concentration shall trigger activation of this plan.

Emergency Procedures

In the event of a release of gas containing H₂S, the first responder(s) must

- Isolate the area and prevent entry by other persons into the 100 ppm ROE.
- Evacuate any public places encompassed by the 100 ppm ROE. Be equipped with H_2S monitors and air packs in order to control the release. Use the "buddy system" to ensure no injuries occur during the response
- Take precautions to avoid personal injury during this operation. Contact operator and/or local officials to aid in operation. See list of phone numbers
- Have received training in the o Detection of H₂S, and
- Measures for protection against the gas, 0
- Equipment used for protection and emergency response.

<u>Ignition of Gas source</u>

NMOCD and local officials. Additionally, the NM State Police may become involved. NM State Police shall be the Incident Command on scene of any major release. Take care to protect against exposure to Sulfur Dioxide (SO₂). Intentional ignition must be coordinated with the Should control of the well be considered lost and ignition considered, take care to protect downwind whenever this is an ignition of the gas.

Characteristics of H₂S and SO₂

| Lethal Concentration | mdd 009 | 1000 ppm |
|-----------------------------------|------------------|-----------------|
| Hazardous Limit | 100 ppm/hr 6 | N/A |
| Threshold Limit Hazardous Limit | 10 ppm | 2 ppm |
| fic Gravity | 1.189 Air = I | 2.21 Air = I |
| Chemical Speci | H ₂ S | SO ₂ |
| Common Name | Hydrogen Sulfide | Sulfur Dioxide |

Contacting Authorities

prepared for use during a release. (Operator Name)'s response must be in coordination with the State of New Mexico's "Hazardous Materials Emergency Response Plan" (HMER). possible but no later than 4 hours. Agencies will ask for information such as type and volume of including directions to site. The following call list of essential and potential responders has been response to a major release. Additionally, the OCD must be notified of the release as soon as release, wind direction, location of release, etc. Be prepared with all information available personnel must liaison with local and state agencies to ensure a proper All XTO location

CARLSBAD OFFICE - EDDY & LEA COUNTIES

| 3104 E. Greene St., Carlsbad, NM 88220 Carlsbad, NM | 575-887-7329 |
|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------|
| WID Dacus, Drilling Manager Will Dacus, Drilling Supervisor Brian Dunn, Drilling Supervisor Robert Bartels, Construction Execution Planner Andy Owens, EH & S Manager Frank Fuentes, Production Foreman | 832-948-5021 832-653-0490 406-478-3617 903-245-2602 575-689-3363 |
| SHERIFF DEPARTMENTS: Eddy County Lea County | <i>575</i> -887-7551 <i>575</i> -396-3611 |
| NEW MEXICO STATE POLICE: | 575-392-5588 |
| FIRE DEPARTMENTS: Carlsbad Eunice Hobbs Jal Lovington | 911 575-885-2111 575-394-2111 575-397-9308 575-396-2359 |
| HOSPITALS: Carlsbad Medical Emergency Eunice Medical Emergency Hobbs Medical Emergency Jal Medical Emergency Lovington Medical Emergency | 911 575-885-2111 575-394-2112 575-397-9308 575-395-2221 575-396-2359 |
| AGENT NOTIFICATIONS: For Lea County: Bureau of Land Management – Hobbs New Mexico Oil Conservation Division – Hobbs | <i>575-</i> 393-3612 <i>575-</i> 393-6161 |
| For Eddy County: Bureau of Land Management - Carlsbad New Mexico Oil Conservation Division - Artesia | 575-234-5972 575-748-1283 |

Site:

Slot:

Bone Spring 3 Shale

Poker Lake Unit 18-30

BD 201H

Well Plan Report - Poker Lake Unit 18-30 BD 201H

Measured Depth: 22955.29 ft

TVD RKB: 10072.00 ft

Location

Cartographic New Mexico East -Reference System: NAD 27 Northing: Easting: RKB: 3212.00 ft 3180.00 ft North Reference: Grid

413660.78 ft 628172.77 ft

Ground Level:

Convergence Angle: 0.22 Deg

Plan Sections Poker Lake Unit 18-30 BD 201H

| Measured | | | TVD | | | Build | Turn | Dogleg |
|----------|-------------|---------|----------|-----------|----------|---------------|-------------|--------------------|
| Depth | Inclination | Azimuth | RKB | Y Offset | X Offset | Rate | Rate | Rate |
| (ft) | (Deg) | (Deg) | (ft) | (ft) | (ft) | (Deg/100ft) | (Deg/100ft) | (Deg/100ft) Target |
| 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| 1100.00 | 0.00 | 0.00 | 1100.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| 1307.59 | 4.15 | 64.82 | 1307.40 | 3.20 | 6.80 | 2.00 | 0.00 | 2.00 |
| 6506.42 | 4.15 | 64.82 | 6492.60 | 163.32 | 347.43 | 0.00 | 0.00 | 0.00 |
| 6714.01 | 0.00 | 0.00 | 6700.00 | 166.52 | 354.23 | - 2.00 | 0.00 | 2.00 |
| 9369.81 | 0.00 | 0.00 | 9355.80 | 166.52 | 354.23 | 0.00 | 0.00 | 0.00 |
| 10494.81 | 90.00 | 179.71 | 10072.00 | -549.67 | 357.90 | 8.00 | 0.00 | 8.00 |
| 10494.82 | 90.00 | 179.71 | 10072.00 | -549.68 | 357.91 | 0.00 | 0.00 | 0.00 |
| 22865.28 | 90.00 | 179.71 | 10072.00 | -12919.98 | 421.43 | 0.00 | 0.00 | 0.00 LTP 12 |
| 22955.29 | 90.00 | 179.71 | 10072.00 | -13009.98 | 421.89 | 0.00 | 0.00 | 0.00 BHL 2 |

Position Uncertainty Poker Lake Unit 18-30 BD 201H

| Measured | | | TVD | Highside | | Lateral | | Vertical | | Magnitude | Semi- major | Semi- minor | Semi- minor | Tool |
|----------|-------------|---------|----------|----------|-------|---------|-------|----------|-------|-----------|----------------|----------------|----------------|---------------------------|
| Depth | Inclination | Azimuth | RKB | Error | Bias | Error | Bias | Error | Bias | of Bias | Error | Error | Azimuth | Used |
| (ft) | (°) | (°) | (ft) | (ft) | (ft) | (ft) | (ft) | (ft) | (ft) | (ft) | (ft) | (ft) | (°) | |
| 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | XOMR2_OWSG MWD+IFR1+MS |
| 100.000 | 0.000 | 0.000 | 100.000 | 0.358 | 0.000 | 0.179 | 0.000 | 2.300 | 0.000 | 0.000 | 0.358 | 0.179 | 90.000 | XOMR2_OWSG MWD+IFR1+MS |
| 200.000 | 0.000 | 0.000 | 200.000 | 0.717 | 0.000 | 0.538 | 0.000 | 2.309 | 0.000 | 0.000 | 0.717 | 0.538 | 90.000 | XOMR2_OWSG MWD+IFR1+MS |
| 300.000 | 0.000 | 0.000 | 300.000 | 1.075 | 0.000 | 0.896 | 0.000 | 2.325 | 0.000 | 0.000 | 1.075 | 0.896 | 90.000 | XOMR2_OWSG MWD+IFR1+MS |
| 400.000 | 0.000 | 0.000 | 400.000 | 1.434 | 0.000 | 1.255 | 0.000 | 2.346 | 0.000 | 0.000 | 1.434 | 1.255 | 90.000 | XOMR2_OWSG MWD+IFR1+MS |
| 500.000 | 0.000 | 0.000 | 500.000 | 1.792 | 0.000 | 1.613 | 0.000 | 2.373 | 0.000 | 0.000 | 1.792 | 1.613 | 90.000 | XOMR2_OWSG MWD+IFR1+MS |
| 600.000 | 0.000 | 0.000 | 600.000 | 2.151 | 0.000 | 1.972 | 0.000 | 2.405 | 0.000 | 0.000 | 2.151 | 1.972 | 90.000 | XOMR2_OWSG MWD+IFR1+MS |
| 700.000 | 0.000 | 0.000 | 700.000 | 2.509 | 0.000 | 2.330 | 0.000 | 2.441 | 0.000 | 0.000 | 2.509 | 2.330 | 90.000 | XOMR2_OWSG MWD+IFR1+MS |
| 800.000 | 0.000 | 0.000 | 800.000 | 2.868 | 0.000 | 2.689 | 0.000 | 2.483 | 0.000 | 0.000 | 2.868 | 2.689 | 90.000 | XOMR2_OWSG MWD+IFR1+MS |
| 900.000 | 0.000 | 0.000 | 900.000 | 3.226 | 0.000 | 3.047 | 0.000 | 2.528 | 0.000 | 0.000 | 3.226 | 3.047 | 90.000 | XOMR2_OWSG MWD+IFR1+MS |
| 1000.000 | 0.000 | 0.000 | 1000.000 | 3.585 | 0.000 | 3.405 | 0.000 | 2.577 | 0.000 | 0.000 | 3.585 | 3.405 | 90.000 | XOMR2_OWSG MWD+IFR1+MS |
| 1100.000 | 0.000 | 0.000 | 1100.000 | 3.943 | 0.000 | 3.764 | 0.000 | 2.630 | 0.000 | 0.000 | 3.943 | 3.764 | 90.000 | XOMR2_OWSG MWD+IFR1+MS |
| 1200.000 | 2.000 | 64.822 | 1199.980 | 4.149 | 0.000 | 4.265 | 0.000 | 2.686 | 0.000 | 0.000 | 4.297 | 4.117 | 90.100 | XOMR2_OWSG MWD+IFR1+MS |
| 1307.585 | 4.152 | 64.822 | 1307.403 | 4.518 | 0.000 | 4.641 | 0.000 | 2.747 | 0.000 | 0.000 | 4.674 | 4.494 | 90.455 | XOMR2_OWSG MWD+IFR1+MS |
| 1400.000 | 4.152 | 64.822 | 1399.576 | 4.842 | 0.000 | 4.966 | 0.000 | 2.803 | 0.000 | 0.000 | 5.000 | 4.818 | 90.680 | XOMR2_OWSG MWD+IFR1+MS |
| 1500.000 | 4.152 | 64.822 | 1499.313 | 5.195 | 0.000 | 5.318 | 0.000 | 2.868 | 0.000 | 0.000 | 5.353 | 5.169 | 90.744 | XOMR2_OWSG MWD+IFR1+MS |
| 1600.000 | 4.152 | 64.822 | 1599.051 | 5.548 | 0.000 | 5.672 | 0.000 | 2.936 | 0.000 | 0.000 | 5.707 | 5.521 | 90.836 | XOMR2_OWSG MWD+IFR1+MS |
| 1700.000 | 4.152 | 64.822 | 1698.789 | 5.903 | 0.000 | 6.026 | 0.000 | 3.006 | 0.000 | 0.000 | 6.062 | 5.874 | 90.951 | XOMR2_OWSG MWD+IFR1+MS |

| 1800.000 | 4.152 | 64.822 | 1798.526 | 6.259(| 0.000 | 6.381 | 0.000 | 3.079 | 0.000 | 0.000 | 6.418 | 6.228 | 91.082 | XOMR2_OWSG MWD+IFR1+MS |
|----------|-------|--------|----------|----------|-------|--------|-------|-------|-------|-------|--------|--------|--------|---------------------------|
| 1900.000 | 4.152 | 64.822 | 1898.264 | 6.615 (| 0.000 | 6.736 | 0.000 | 3.154 | 0.000 | 0.000 | 6.774 | 6.582 | 91.228 | XOMR2_OWSG MWD+IFR1+MS |
| 2000.000 | 4.152 | 64.822 | 1998.001 | 6.972 | 0.000 | 7.093 | 0.000 | 3.230 | 0.000 | 0.000 | 7.131 | 6.938 | 91.384 | XOMR2_OWSG MWD+IFR1+MS |
| 2100.000 | 4.152 | 64.822 | 2097.739 | 7.329 | 0.000 | 7.449 | 0.000 | 3.309 | 0.000 | 0.000 | 7.488 | 7.293 | 91.550 | XOMR2_OWSG MWD+IFR1+MS |
| 2200.000 | 4.152 | 64.822 | 2197.477 | 7.687 | 0.000 | 7.806 | 0.000 | 3.389 | 0.000 | 0.000 | 7.846 | 7.649 | 91.724 | XOMR2_OWSG MWD+IFR1+MS |
| 2300.000 | 4.152 | 64.822 | 2297.214 | 8.045 (| 0.000 | 8.163 | 0.000 | 3.472 | 0.000 | 0.000 | 8.204 | 8.006 | 91.903 | XOMR2_OWSG MWD+IFR1+MS |
| 2400.000 | 4.152 | 64.822 | 2396.952 | 8.404 (| 0.000 | 8.520 | 0.000 | 3.555 | 0.000 | 0.000 | 8.562 | 8.363 | 92.087 | XOMR2_OWSG MWD+IFR1+MS |
| 2500.000 | 4.152 | 64.822 | 2496.689 | 8.762(| 0.000 | 8.878 | 0.000 | 3.641 | 0.000 | 0.000 | 8.920 | 8.720 | 92.276 | XOMR2_OWSG MWD+IFR1+MS |
| 2600.000 | 4.152 | 64.822 | 2596.427 | 9.122(| 0.000 | 9.236 | 0.000 | 3.728 | 0.000 | 0.000 | 9.279 | 9.077 | 92.467 | XOMR2_OWSG MWD+IFR1+MS |
| 2700.000 | 4.152 | 64.822 | 2696.165 | 9.481 (| 0.000 | 9.594 | 0.000 | 3.816 | 0.000 | 0.000 | 9.638 | 9.434 | 92.661 | XOMR2_OWSG MWD+IFR1+MS |
| 2800.000 | 4.152 | 64.822 | 2795.902 | 9.840 (| 0.000 | 9.952 | 0.000 | 3.906 | 0.000 | 0.000 | 9.997 | 9.792 | 92.857 | XOMR2_OWSG MWD+IFR1+MS |
| 2900.000 | 4.152 | 64.822 | 2895.640 | 10.200 | 0.000 | 10.311 | 0.000 | 3.998 | 0.000 | 0.000 | 10.357 | 10.150 | 93.054 | XOMR2_OWSG MWD+IFR1+MS |
| 3000.000 | 4.152 | 64.822 | 2995.377 | 10.560 (| 0.000 | 10.669 | 0.000 | 4.091 | 0.000 | 0.000 | 10.716 | 10.508 | 93.253 | XOMR2_OWSG MWD+IFR1+MS |
| 3100.000 | 4.152 | 64.822 | 3095.115 | 10.920 | 0.000 | 11.028 | 0.000 | 4.185 | 0.000 | 0.000 | 11.076 | 10.866 | 93.452 | XOMR2_OWSG MWD+IFR1+MS |
| 3200.000 | 4.152 | 64.822 | 3194.852 | 11.280 (| 0.000 | 11.387 | 0.000 | 4.281 | 0.000 | 0.000 | 11.435 | 11.225 | 93.652 | XOMR2_OWSG MWD+IFR1+MS |
| 3300.000 | 4.152 | 64.822 | 3294.590 | 11.641 (| 0.000 | 11.746 | 0.000 | 4.378 | 0.000 | 0.000 | 11.795 | 11.583 | 93.851 | XOMR2_OWSG MWD+IFR1+MS |
| 3400.000 | 4.152 | 64.822 | 3394.328 | 12.001 | 0.000 | 12.105 | 0.000 | 4.477 | 0.000 | 0.000 | 12.155 | 11.942 | 94.051 | XOMR2_OWSG MWD+IFR1+MS |
| 3500.000 | 4.152 | 64.822 | 3494.065 | 12.361 (| 0.000 | 12.464 | 0.000 | 4.577 | 0.000 | 0.000 | 12.515 | 12.300 | 94.251 | XOMR2_OWSG MWD+IFR1+MS |
| 3600.000 | 4.152 | 64.822 | 3593.803 | 12.722(| 0.000 | 12.823 | 0.000 | 4.678 | 0.000 | 0.000 | 12.875 | 12.659 | 94.450 | XOMR2_OWSG MWD+IFR1+MS |
| 3700.000 | 4.152 | 64.822 | 3693.540 | 13.083(| 0.000 | 13.182 | 0.000 | 4.781 | 0.000 | 0.000 | 13.236 | 13.018 | 94.649 | XOMR2_OWSG MWD+IFR1+MS |

| 3800.000 | 4.152 | 64.822 | 3793.278 | 13.444 0.000 | 13.541 | 0.000 | 4.886 | 0.000 | 0.000 | 13.596 | 13.377 | 94.847 | XOMR2_OWSG MWD+IFR1+MS |
|----------|-------|--------|----------|--------------|--------|-------|-------|-------|-------|--------|--------|--------|---------------------------|
| 3900.000 | 4.152 | 64.822 | 3893.016 | 13.804 0.000 | 13.901 | 0.000 | 4.992 | 0.000 | 0.000 | 13.956 | 13.736 | 95.044 | XOMR2_OWSG MWD+IFR1+MS |
| 4000.000 | 4.152 | 64.822 | 3992.753 | 14.165 0.000 | 14.260 | 0.000 | 5.100 | 0.000 | 0.000 | 14.317 | 14.095 | 95.241 | XOMR2_OWSG MWD+IFR1+MS |
| 4100.000 | 4.152 | 64.822 | 4092.491 | 14.526 0.000 | 14.620 | 0.000 | 5.209 | 0.000 | 0.000 | 14.677 | 14.454 | 95.436 | XOMR2_OWSG MWD+IFR1+MS |
| 4200.000 | 4.152 | 64.822 | 4192.228 | 14.887 0.000 | 14.979 | 0.000 | 5.320 | 0.000 | 0.000 | 15.038 | 14.813 | 95.631 | XOMR2_OWSG MWD+IFR1+MS |
| 4300.000 | 4.152 | 64.822 | 4291.966 | 15.248 0.000 | 15.339 | 0.000 | 5.432 | 0.000 | 0.000 | 15.398 | 15.172 | 95.825 | XOMR2_OWSG MWD+IFR1+MS |
| 4400.000 | 4.152 | 64.822 | 4391.703 | 15.609 0.000 | 15.698 | 0.000 | 5.546 | 0.000 | 0.000 | 15.759 | 15.531 | 96.017 | XOMR2_OWSG MWD+IFR1+MS |
| 4500.000 | 4.152 | 64.822 | 4491.441 | 15.971 0.000 | 16.058 | 0.000 | 5.662 | 0.000 | 0.000 | 16.120 | 15.891 | 96.208 | XOMR2_OWSG MWD+IFR1+MS |
| 4600.000 | 4.152 | 64.822 | 4591.179 | 16.332 0.000 | 16.417 | 0.000 | 5.780 | 0.000 | 0.000 | 16.480 | 16.250 | 96.398 | XOMR2_OWSG MWD+IFR1+MS |
| 4700.000 | 4.152 | 64.822 | 4690.916 | 16.693 0.000 | 16.777 | 0.000 | 5.899 | 0.000 | 0.000 | 16.841 | 16.609 | 96.587 | XOMR2_OWSG MWD+IFR1+MS |
| 4800.000 | 4.152 | 64.822 | 4790.654 | 17.054 0.000 | 17.137 | 0.000 | 6.021 | 0.000 | 0.000 | 17.202 | 16.969 | 96.775 | XOMR2_OWSG MWD+IFR1+MS |
| 4900.000 | 4.152 | 64.822 | 4890.391 | 17.416 0.000 | 17.497 | 0.000 | 6.144 | 0.000 | 0.000 | 17.563 | 17.328 | 96.961 | XOMR2_OWSG MWD+IFR1+MS |
| 5000.000 | 4.152 | 64.822 | 4990.129 | 17.777 0.000 | 17.856 | 0.000 | 6.269 | 0.000 | 0.000 | 17.923 | 17.688 | 97.146 | XOMR2_OWSG MWD+IFR1+MS |
| 5100.000 | 4.152 | 64.822 | 5089.867 | 18.138 0.000 | 18.216 | 0.000 | 6.396 | 0.000 | 0.000 | 18.284 | 18.047 | 97.329 | XOMR2_OWSG MWD+IFR1+MS |
| 5200.000 | 4.152 | 64.822 | 5189.604 | 18.500 0.000 | 18.576 | 0.000 | 6.524 | 0.000 | 0.000 | 18.645 | 18.407 | 97.512 | XOMR2_OWSG MWD+IFR1+MS |
| 5300.000 | 4.152 | 64.822 | 5289.342 | 18.861 0.000 | 18.936 | 0.000 | 6.655 | 0.000 | 0.000 | 19.006 | 18.766 | 97.693 | XOMR2_OWSG MWD+IFR1+MS |
| 5400.000 | 4.152 | 64.822 | 5389.079 | 19.223 0.000 | 19.296 | 0.000 | 6.788 | 0.000 | 0.000 | 19.367 | 19.126 | 97.872 | XOMR2_OWSG MWD+IFR1+MS |
| 5500.000 | 4.152 | 64.822 | 5488.817 | 19.584 0.000 | 19.656 | 0.000 | 6.923 | 0.000 | 0.000 | 19.728 | 19.485 | 98.051 | XOMR2_OWSG MWD+IFR1+MS |
| 5600.000 | 4.152 | 64.822 | 5588.554 | 19.946 0.000 | 20.016 | 0.000 | 7.060 | 0.000 | 0.000 | 20.089 | 19.845 | 98.228 | XOMR2_OWSG MWD+IFR1+MS |
| 5700.000 | 4.152 | 64.822 | 5688.292 | 20.307 0.000 | 20.375 | 0.000 | 7.199 | 0.000 | 0.000 | 20.450 | 20.204 | 98.404 | XOMR2_OWSG MWD+IFR1+MS |
| | | | | | | | | | | | | | |

| 5800.000 | 4.152 | 64.822 | 5788.030 | 20.669 0.000 | 20.735 | 0.000 | 7.340 | 0.000 | 0.000 | 20.812 | 20.564 | 98.578 | XOMR2_OWSG MWD+IFR1+MS |
|----------|-------|--------|----------|--------------|--------|-------|--------|-------|-------|--------|--------|--------|---------------------------|
| 5900.000 | 4.152 | 64.822 | 5887.767 | 21.031 0.000 | 21.095 | 0.000 | 7.483 | 0.000 | 0.000 | 21.173 | 20.924 | 98.751 | XOMR2_OWSG MWD+IFR1+MS |
| 6000.000 | 4.152 | 64.822 | 5987.505 | 21.392 0.000 | 21.455 | 0.000 | 7.629 | 0.000 | 0.000 | 21.534 | 21.283 | 98.923 | XOMR2_OWSG MWD+IFR1+MS |
| 6100.000 | 4.152 | 64.822 | 6087.242 | 21.754 0.000 | 21.815 | 0.000 | 7.777 | 0.000 | 0.000 | 21.895 | 21.643 | 99.093 | XOMR2_OWSG MWD+IFR1+MS |
| 6200.000 | 4.152 | 64.822 | 6186.980 | 22.115 0.000 | 22.175 | 0.000 | 7.927 | 0.000 | 0.000 | 22.256 | 22.002 | 99.262 | XOMR2_OWSG MWD+IFR1+MS |
| 6300.000 | 4.152 | 64.822 | 6286.718 | 22.477 0.000 | 22.535 | 0.000 | 8.079 | 0.000 | 0.000 | 22.617 | 22.362 | 99.430 | XOMR2_OWSG MWD+IFR1+MS |
| 6400.000 | 4.152 | 64.822 | 6386.455 | 22.839 0.000 | 22.895 | 0.000 | 8.234 | 0.000 | 0.000 | 22.979 | 22.722 | 99.597 | XOMR2_OWSG MWD+IFR1+MS |
| 6506.421 | 4.152 | 64.822 | 6492.597 | 23.224 0.000 | 23.279 | 0.000 | 8.401 | 0.000 | 0.000 | 23.363 | 23.105 | 99.773 | XOMR2_OWSG MWD+IFR1+MS |
| 6600.000 | 2.280 | 64.822 | 6586.024 | 23.559 0.000 | 23.615 | 0.000 | 8.550 | 0.000 | 0.000 | 23.700 | 23.440 | 99.882 | XOMR2_OWSG MWD+IFR1+MS |
| 6700.000 | 0.280 | 64.822 | 6685.994 | 23.889 0.000 | 23.971 | 0.000 | 8.710 | 0.000 | 0.000 | 24.057 | 23.797 | 99.930 | XOMR2_OWSG MWD+IFR1+MS |
| 6714.006 | 0.000 | 0.000 | 6700.000 | 24.099 0.000 | 23.854 | 0.000 | 8.733 | 0.000 | 0.000 | 24.106 | 23.846 | 99.914 | XOMR2_OWSG MWD+IFR1+MS |
| 6800.000 | 0.000 | 0.000 | 6785.994 | 24.400 0.000 | 24.154 | 0.000 | 8.871 | 0.000 | 0.000 | 24.407 | 24.146 | 99.723 | XOMR2_OWSG MWD+IFR1+MS |
| 6900.000 | 0.000 | 0.000 | 6885.994 | 24.750 0.000 | 24.502 | 0.000 | 9.034 | 0.000 | 0.000 | 24.757 | 24.495 | 99.509 | XOMR2_OWSG MWD+IFR1+MS |
| 7000.000 | 0.000 | 0.000 | 6985.994 | 25.100 0.000 | 24.851 | 0.000 | 9.200 | 0.000 | 0.000 | 25.107 | 24.845 | 99.301 | XOMR2_OWSG MWD+IFR1+MS |
| 7100.000 | 0.000 | 0.000 | 7085.994 | 25.451 0.000 | 25.201 | 0.000 | 9.368 | 0.000 | 0.000 | 25.457 | 25.194 | 99.100 | XOMR2_OWSG MWD+IFR1+MS |
| 7200.000 | 0.000 | 0.000 | 7185.994 | 25.801 0.000 | 25.550 | 0.000 | 9.539 | 0.000 | 0.000 | 25.808 | 25.544 | 98.906 | XOMR2_OWSG MWD+IFR1+MS |
| 7300.000 | 0.000 | 0.000 | 7285.994 | 26.152 0.000 | 25.900 | 0.000 | 9.712 | 0.000 | 0.000 | 26.158 | 25.894 | 98.718 | XOMR2_OWSG MWD+IFR1+MS |
| 7400.000 | 0.000 | 0.000 | 7385.994 | 26.503 0.000 | 26.250 | 0.000 | 9.888 | 0.000 | 0.000 | 26.509 | 26.244 | 98.536 | XOMR2_OWSG MWD+IFR1+MS |
| 7500.000 | 0.000 | 0.000 | 7485.994 | 26.855 0.000 | 26.600 | 0.000 | 10.067 | 0.000 | 0.000 | 26.860 | 26.595 | 98.360 | XOMR2_OWSG MWD+IFR1+MS |
| 7600.000 | 0.000 | 0.000 | 7585.994 | 27.206 0.000 | 26.951 | 0.000 | 10.249 | 0.000 | 0.000 | 27.212 | 26.945 | 98.189 | XOMR2_OWSG MWD+IFR1+MS |

| 7700.000 | 0.000 | 0.000 | 7685.994 | 27.558 0.000 | 27.301 | 0.000 | 10.433 | 0.000 | 0.000 | 27.563 | 27.296 | 98.024 | XOMR2_OWSG MWD+IFR1+MS |
|----------|--------|---------|----------|--------------|--------|--------|--------|-------|-------|--------|--------|--------|---------------------------|
| 7800.000 | 0.000 | 0.000 | 7785.994 | 27.910 0.000 | 27.652 | 0.000 | 10.620 | 0.000 | 0.000 | 27.915 | 27.647 | 97.863 | XOMR2_OWSG MWD+IFR1+MS |
| 7900.000 | 0.000 | 0.000 | 7885.994 | 28.262 0.000 | 28.003 | 0.000 | 10.810 | 0.000 | 0.000 | 28.267 | 27.999 | 97.707 | XOMR2_OWSG MWD+IFR1+MS |
| 8000.000 | 0.000 | 0.000 | 7985.994 | 28.614 0.000 | 28.355 | 0.000 | 11.002 | 0.000 | 0.000 | 28.619 | 28.350 | 97.556 | XOMR2_OWSG MWD+IFR1+MS |
| 8100.000 | 0.000 | 0.000 | 8085.994 | 28.967 0.000 | 28.706 | 0.000 | 11.197 | 0.000 | 0.000 | 28.971 | 28.702 | 97.409 | XOMR2_OWSG MWD+IFR1+MS |
| 8200.000 | 0.000 | 0.000 | 8185.994 | 29.319 0.000 | 29.058 | 0.000 | 11.395 | 0.000 | 0.000 | 29.324 | 29.053 | 97.266 | XOMR2_OWSG MWD+IFR1+MS |
| 8300.000 | 0.000 | 0.000 | 8285.994 | 29.672 0.000 | 29.409 | 0.000 | 11.596 | 0.000 | 0.000 | 29.676 | 29.405 | 97.127 | XOMR2_OWSG MWD+IFR1+MS |
| 8400.000 | 0.000 | 0.000 | 8385.994 | 30.025 0.000 | 29.761 | 0.000 | 11.800 | 0.000 | 0.000 | 30.029 | 29.757 | 96.992 | XOMR2_OWSG MWD+IFR1+MS |
| 8500.000 | 0.000 | 0.000 | 8485.994 | 30.378 0.000 | 30.113 | 0.000 | 12.006 | 0.000 | 0.000 | 30.382 | 30.110 | 96.861 | XOMR2_OWSG MWD+IFR1+MS |
| 8600.000 | 0.000 | 0.000 | 8585.994 | 30.731 0.000 | 30.466 | 0.000 | 12.216 | 0.000 | 0.000 | 30.734 | 30.462 | 96.733 | XOMR2_OWSG MWD+IFR1+MS |
| 8700.000 | 0.000 | 0.000 | 8685.994 | 31.084 0.000 | 30.818 | 0.000 | 12.428 | 0.000 | 0.000 | 31.088 | 30.814 | 96.609 | XOMR2_OWSG MWD+IFR1+MS |
| 8800.000 | 0.000 | 0.000 | 8785.994 | 31.437 0.000 | 31.171 | 0.000 | 12.643 | 0.000 | 0.000 | 31.441 | 31.167 | 96.488 | XOMR2_OWSG MWD+IFR1+MS |
| 8900.000 | 0.000 | 0.000 | 8885.994 | 31.791 0.000 | 31.523 | 0.000 | 12.861 | 0.000 | 0.000 | 31.794 | 31.520 | 96.371 | XOMR2_OWSG MWD+IFR1+MS |
| 9000.000 | 0.000 | 0.000 | 8985.994 | 32.144 0.000 | 31.876 | 0.000 | 13.082 | 0.000 | 0.000 | 32.147 | 31.873 | 96.256 | XOMR2_OWSG MWD+IFR1+MS |
| 9100.000 | 0.000 | 0.000 | 9085.994 | 32.498 0.000 | 32.229 | 0.000 | 13.306 | 0.000 | 0.000 | 32.501 | 32.226 | 96.144 | XOMR2_OWSG MWD+IFR1+MS |
| 9200.000 | 0.000 | 0.000 | 9185.994 | 32.852 0.000 | 32.582 | 0.000 | 13.532 | 0.000 | 0.000 | 32.855 | 32.579 | 96.035 | XOMR2_OWSG MWD+IFR1+MS |
| 9300.000 | 0.000 | 0.000 | 9285.994 | 33.205 0.000 | 32.935 | 0.000 | 13.762 | 0.000 | 0.000 | 33.208 | 32.932 | 95.929 | XOMR2_OWSG MWD+IFR1+MS |
| 9369.806 | 0.000 | 0.000 | 9355.800 | 33.453 0.000 | 33.182 | 0.000 | 13.924 | 0.000 | 0.000 | 33.455 | 33.179 | 95.857 | XOMR2_OWSG MWD+IFR1+MS |
| 9400.000 | 2.416 | 179.706 | 9385.985 | 33.508 0.000 | 33.285 | -0.000 | 13.994 | 0.000 | 0.000 | 33.558 | 33.282 | 95.824 | XOMR2_OWSG MWD+IFR1+MS |
| 9500.000 | 10.416 | 179.706 | 9485.278 | 33.322 0.000 | 33.608 | -0.000 | 14.223 | 0.000 | 0.000 | 33.878 | 33.605 | 95.697 | XOMR2_OWSG MWD+IFR1+MS |

| 9600.000 | 18.416 | 179.706 | 9582.051 | 32.597 | 0.000 | 33.919 | -0.000 | 14.440 | 0.000 | 0.000 | 34.183 | 33.916 | 95.608 | XOMR2_OWSG MWD+IFR1+MS |
|-----------|--------|---------|-----------|--------|-------|--------|--------|--------|-------|-------|--------|--------|-----------------|---------------------------|
| 9700.000 | 26.416 | 179.706 | 9674.421 | 31.358 | 0.000 | 34.214 | -0.000 | 14.641 | 0.000 | 0.000 | 34.464 | 34.212 | 95.817 | XOMR2_OWSG MWD+IFR1+MS |
| 9800.000 | 34.416 | 179.706 | 9760.588 | 29.650 | 0.000 | 34.491 | -0.000 | 14.827 | 0.000 | 0.000 | 34.713 | 34.488 | 96.695 | XOMR2_OWSG MWD+IFR1+MS |
| 9900.000 | 42.416 | 179.706 | 9838.877 | 27.544 | 0.000 | 34.747 | -0.000 | 14.997 | 0.000 | 0.000 | 34.926 | 34.742 | 99.063 | XOMR2_OWSG MWD+IFR1+MS |
| 10000.000 | 50.416 | 179.706 | 9907.763 | 25.140 | 0.000 | 34.980 | -0.000 | 15.157 | 0.000 | 0.000 | 35.102 | 34.970 | 105.383 | XOMR2_OWSG MWD+IFR1+MS |
| 10100.000 | 58.416 | 179.706 | 9965.906 | 22.583 | 0.000 | 35.188 | -0.000 | 15.315 | 0.000 | 0.000 | 35.252 | 35.160 | 123.262 | XOMR2_OWSG MWD+IFR1+MS |
| 10200.000 | 66.416 | 179.706 | 10012.174 | 20.077 | 0.000 | 35.371 | -0.000 | 15.479 | 0.000 | 0.000 | 35.405 | 35.283 | -32.231 | XOMR2_OWSG MWD+IFR1+MS |
| 10300.000 | 74.416 | 179.706 | 10045.667 | 17.911 | 0.000 | 35.527 | -0.000 | 15.656 | 0.000 | 0.000 | 35.555 | 35.348 | -21.931 | XOMR2_OWSG MWD+IFR1+MS |
| 10400.000 | 82.416 | 179.706 | 10065.732 | 16.456 | 0.000 | 35.656 | -0.000 | 15.852 | 0.000 | 0.000 | 35.686 | 35.377 | -18.533 | XOMR2_OWSG MWD+IFR1+MS |
| 10494.806 | 90.000 | 179.706 | 10071.997 | 16.057 | 0.000 | 35.751 | -0.000 | 16.057 | 0.000 | 0.000 | 35.787 | 35.383 | -17.726 | XOMR2_OWSG MWD+IFR1+MS |
| 10494.817 | 90.000 | 179.706 | 10071.997 | 16.057 | 0.000 | 35.751 | -0.000 | 16.057 | 0.000 | 0.000 | 35.787 | 35.384 | - 17.752 | XOMR2_OWSG MWD+IFR1+MS |
| 10500.000 | 90.000 | 179.706 | 10071.997 | 16.069 | 0.000 | 35.755 | -0.000 | 16.069 | 0.000 | 0.000 | 35.791 | 35.384 | -17.750 | XOMR2_OWSG MWD+IFR1+MS |
| 10600.000 | 90.000 | 179.706 | 10071.997 | 16.314 | 0.000 | 35.850 | -0.000 | 16.314 | 0.000 | 0.000 | 35.893 | 35.382 | -17.314 | XOMR2_OWSG MWD+IFR1+MS |
| 10700.000 | 90.000 | 179.706 | 10071.997 | 16.594 | 0.000 | 35.961 | -0.000 | 16.594 | 0.000 | 0.000 | 36.010 | 35.383 | -16.629 | XOMR2_OWSG MWD+IFR1+MS |
| 10800.000 | 90.000 | 179.706 | 10071.997 | 16.905 | 0.000 | 36.087 | -0.000 | 16.905 | 0.000 | 0.000 | 36.141 | 35.385 | - 15.847 | XOMR2_OWSG MWD+IFR1+MS |
| 10900.000 | 90.000 | 179.706 | 10071.997 | 17.246 | 0.000 | 36.230 | -0.000 | 17.246 | 0.000 | 0.000 | 36.288 | 35.389 | - 15.045 | XOMR2_OWSG MWD+IFR1+MS |
| 11000.000 | 90.000 | 179.706 | 10071.997 | 17.615 | 0.000 | 36.388 | -0.000 | 17.615 | 0.000 | 0.000 | 36.449 | 35.394 | - 14.264 | XOMR2_OWSG MWD+IFR1+MS |
| 11100.000 | 90.000 | 179.706 | 10071.997 | 18.011 | 0.000 | 36.561 | -0.000 | 18.011 | 0.000 | 0.000 | 36.625 | 35.400 | - 13.522 | XOMR2_OWSG MWD+IFR1+MS |
| 11200.000 | 90.000 | 179.706 | 10071.997 | 18.432 | 0.000 | 36.750 | -0.000 | 18.432 | 0.000 | 0.000 | 36.815 | 35.407 | - 12.828 | XOMR2_OWSG MWD+IFR1+MS |
| 11300.000 | 90.000 | 179.706 | 10071.997 | 18.877 | 0.000 | 36.953 | -0.000 | 18.877 | 0.000 | 0.000 | 37.020 | 35.415 | - 12.184 | XOMR2_OWSG MWD+IFR1+MS |

| 11400.000 | 90.000 | 179.706 | 10071.997 | 19.343 0. | .000 | 37.171 | -0.000 | 19.343 | 0.000 | 0.000 | 37.239 | 35.425 | -11.588 | XOMR2_OWSG MWD+IFR1+MS |
|-----------|--------|---------|-----------|-----------|------|--------|--------|--------|-------|-------|--------|--------|-----------------|---------------------------|
| 11500.000 | 90.000 | 179.706 | 10071.997 | 19.829 0. | .000 | 37.404 | -0.000 | 19.829 | 0.000 | 0.000 | 37.473 | 35.435 | - 11.040 | XOMR2_OWSG MWD+IFR1+MS |
| 11600.000 | 90.000 | 179.706 | 10071.997 | 20.333 0. | .000 | 37.650 | -0.000 | 20.333 | 0.000 | 0.000 | 37.720 | 35.446 | -10.534 | XOMR2_OWSG MWD+IFR1+MS |
| 11700.000 | 90.000 | 179.706 | 10071.997 | 20.855 0. | .000 | 37.911 | -0.000 | 20.855 | 0.000 | 0.000 | 37.981 | 35.458 | -10.067 | XOMR2_OWSG MWD+IFR1+MS |
| 11800.000 | 90.000 | 179.706 | 10071.997 | 21.394 0. | .000 | 38.185 | -0.000 | 21.394 | 0.000 | 0.000 | 38.255 | 35.470 | -9.637 | XOMR2_OWSG MWD+IFR1+MS |
| 11900.000 | 90.000 | 179.706 | 10071.997 | 21.947 0. | .000 | 38.472 | -0.000 | 21.947 | 0.000 | 0.000 | 38.543 | 35.484 | -9.239 | XOMR2_OWSG MWD+IFR1+MS |
| 12000.000 | 90.000 | 179.706 | 10071.997 | 22.513 0. | .000 | 38.772 | -0.000 | 22.513 | 0.000 | 0.000 | 38.843 | 35.498 | -8.871 | XOMR2_OWSG MWD+IFR1+MS |
| 12100.000 | 90.000 | 179.706 | 10071.997 | 23.093 0. | .000 | 39.085 | -0.000 | 23.093 | 0.000 | 0.000 | 39.156 | 35.513 | -8.529 | XOMR2_OWSG MWD+IFR1+MS |
| 12200.000 | 90.000 | 179.706 | 10071.997 | 23.684 0. | .000 | 39.410 | -0.000 | 23.684 | 0.000 | 0.000 | 39.481 | 35.529 | -8.212 | XOMR2_OWSG MWD+IFR1+MS |
| 12300.000 | 90.000 | 179.706 | 10071.997 | 24.287 0. | .000 | 39.747 | -0.000 | 24.287 | 0.000 | 0.000 | 39.819 | 35.545 | -7.917 | XOMR2_OWSG MWD+IFR1+MS |
| 12400.000 | 90.000 | 179.706 | 10071.997 | 24.899 0. | .000 | 40.096 | -0.000 | 24.899 | 0.000 | 0.000 | 40.167 | 35.562 | -7.642 | XOMR2_OWSG MWD+IFR1+MS |
| 12500.000 | 90.000 | 179.706 | 10071.997 | 25.521 0. | .000 | 40.457 | -0.000 | 25.521 | 0.000 | 0.000 | 40.528 | 35.580 | -7.385 | XOMR2_OWSG MWD+IFR1+MS |
| 12600.000 | 90.000 | 179.706 | 10071.997 | 26.152 0. | .000 | 40.829 | -0.000 | 26.152 | 0.000 | 0.000 | 40.899 | 35.598 | -7.144 | XOMR2_OWSG MWD+IFR1+MS |
| 12700.000 | 90.000 | 179.706 | 10071.997 | 26.790 0. | .000 | 41.211 | -0.000 | 26.790 | 0.000 | 0.000 | 41.281 | 35.617 | -6.919 | XOMR2_OWSG MWD+IFR1+MS |
| 12800.000 | 90.000 | 179.706 | 10071.997 | 27.437 0. | .000 | 41.604 | -0.000 | 27.437 | 0.000 | 0.000 | 41.674 | 35.637 | -6.707 | XOMR2_OWSG MWD+IFR1+MS |
| 12900.000 | 90.000 | 179.706 | 10071.997 | 28.090 0. | .000 | 42.008 | -0.000 | 28.090 | 0.000 | 0.000 | 42.077 | 35.658 | -6.508 | XOMR2_OWSG MWD+IFR1+MS |
| 13000.000 | 90.000 | 179.706 | 10071.997 | 28.750 0. | .000 | 42.421 | -0.000 | 28.750 | 0.000 | 0.000 | 42.490 | 35.679 | -6.320 | XOMR2_OWSG MWD+IFR1+MS |
| 13100.000 | 90.000 | 179.706 | 10071.997 | 29.416 0. | .000 | 42.844 | -0.000 | 29.416 | 0.000 | 0.000 | 42.913 | 35.701 | -6.143 | XOMR2_OWSG MWD+IFR1+MS |
| 13200.000 | 90.000 | 179.706 | 10071.997 | 30.088 0. | .000 | 43.276 | -0.000 | 30.088 | 0.000 | 0.000 | 43.345 | 35.723 | -5.976 | XOMR2_OWSG MWD+IFR1+MS |
| 13300.000 | 90.000 | 179.706 | 10071.997 | 30.766 0. | .000 | 43.718 | -0.000 | 30.766 | 0.000 | 0.000 | 43.786 | 35.747 | -5.818 | XOMR2_OWSG MWD+IFR1+MS |

| 13400.000 | 90.000 | 179.706 | 10071.997 | 31.448 | 0.000 | 44.168 | -0.000 | 31.448 | 0.000 | 0.000 | 44.235 | 35.770 | -5.668 | XOMR2_OWSG MWD+IFR1+MS |
|-----------|--------|---------|-----------|--------|-------|--------|--------|--------|-------|-------|--------|--------|--------|---------------------------|
| 13500.000 | 90.000 | 179.706 | 10071.997 | 32.135 | 0.000 | 44.627 | -0.000 | 32.135 | 0.000 | 0.000 | 44.694 | 35.795 | -5.526 | XOMR2_OWSG MWD+IFR1+MS |
| 13600.000 | 90.000 | 179.706 | 10071.997 | 32.826 | 0.000 | 45.094 | -0.000 | 32.826 | 0.000 | 0.000 | 45.161 | 35.820 | -5.391 | XOMR2_OWSG MWD+IFR1+MS |
| 13700.000 | 90.000 | 179.706 | 10071.997 | 33.521 | 0.000 | 45.570 | -0.000 | 33.521 | 0.000 | 0.000 | 45.635 | 35.846 | -5.263 | XOMR2_OWSG MWD+IFR1+MS |
| 13800.000 | 90.000 | 179.706 | 10071.997 | 34.221 | 0.000 | 46.053 | -0.000 | 34.221 | 0.000 | 0.000 | 46.118 | 35.872 | -5.141 | XOMR2_OWSG MWD+IFR1+MS |
| 13900.000 | 90.000 | 179.706 | 10071.997 | 34.924 | 0.000 | 46.543 | -0.000 | 34.924 | 0.000 | 0.000 | 46.608 | 35.899 | -5.024 | XOMR2_OWSG MWD+IFR1+MS |
| 14000.000 | 90.000 | 179.706 | 10071.997 | 35.630 | 0.000 | 47.041 | -0.000 | 35.630 | 0.000 | 0.000 | 47.105 | 35.927 | -4.913 | XOMR2_OWSG MWD+IFR1+MS |
| 14100.000 | 90.000 | 179.706 | 10071.997 | 36.339 | 0.000 | 47.547 | -0.000 | 36.339 | 0.000 | 0.000 | 47.610 | 35.955 | -4.807 | XOMR2_OWSG MWD+IFR1+MS |
| 14200.000 | 90.000 | 179.706 | 10071.997 | 37.052 | 0.000 | 48.059 | -0.000 | 37.052 | 0.000 | 0.000 | 48.121 | 35.984 | -4.706 | XOMR2_OWSG MWD+IFR1+MS |
| 14300.000 | 90.000 | 179.706 | 10071.997 | 37.767 | 0.000 | 48.577 | -0.000 | 37.767 | 0.000 | 0.000 | 48.639 | 36.014 | -4.608 | XOMR2_OWSG MWD+IFR1+MS |
| 14400.000 | 90.000 | 179.706 | 10071.997 | 38.486 | 0.000 | 49.102 | -0.000 | 38.486 | 0.000 | 0.000 | 49.164 | 36.044 | -4.516 | XOMR2_OWSG MWD+IFR1+MS |
| 14500.000 | 90.000 | 179.706 | 10071.997 | 39.206 | 0.000 | 49.634 | -0.000 | 39.206 | 0.000 | 0.000 | 49.695 | 36.075 | -4.426 | XOMR2_OWSG MWD+IFR1+MS |
| 14600.000 | 90.000 | 179.706 | 10071.997 | 39.929 | 0.000 | 50.171 | -0.000 | 39.929 | 0.000 | 0.000 | 50.231 | 36.107 | -4.341 | XOMR2_OWSG MWD+IFR1+MS |
| 14700.000 | 90.000 | 179.706 | 10071.997 | 40.655 | 0.000 | 50.714 | -0.000 | 40.655 | 0.000 | 0.000 | 50.774 | 36.139 | -4.259 | XOMR2_OWSG MWD+IFR1+MS |
| 14800.000 | 90.000 | 179.706 | 10071.997 | 41.382 | 0.000 | 51.263 | -0.000 | 41.382 | 0.000 | 0.000 | 51.322 | 36.172 | -4.180 | XOMR2_OWSG MWD+IFR1+MS |
| 14900.000 | 90.000 | 179.706 | 10071.997 | 42.112 | 0.000 | 51.817 | -0.000 | 42.112 | 0.000 | 0.000 | 51.876 | 36.205 | -4.104 | XOMR2_OWSG MWD+IFR1+MS |
| 15000.000 | 90.000 | 179.706 | 10071.997 | 42.844 | 0.000 | 52.377 | -0.000 | 42.844 | 0.000 | 0.000 | 52.435 | 36.239 | -4.031 | XOMR2_OWSG MWD+IFR1+MS |
| 15100.000 | 90.000 | 179.706 | 10071.997 | 43.577 | 0.000 | 52.942 | -0.000 | 43.577 | 0.000 | 0.000 | 53.000 | 36.274 | -3.961 | XOMR2_OWSG MWD+IFR1+MS |
| 15200.000 | 90.000 | 179.706 | 10071.997 | 44.312 | 0.000 | 53.512 | -0.000 | 44.312 | 0.000 | 0.000 | 53.569 | 36.309 | -3.894 | XOMR2_OWSG MWD+IFR1+MS |
| 15300.000 | 90.000 | 179.706 | 10071.997 | 45.049 | 0.000 | 54.086 | -0.000 | 45.049 | 0.000 | 0.000 | 54.143 | 36.345 | -3.828 | XOMR2_OWSG MWD+IFR1+MS |

| 15400.000 | 90.000 | 179.706 | 10071.997 | 45.788 | 0.000 | 54.666 | -0.000 | 45.788 | 0.000 | 0.000 | 54.722 | 36.381 | -3.765 | XOMR2_OWSG MWD+IFR1+MS |
|-----------|--------|---------|-----------|--------|-------|--------|--------|--------|-------|-------|--------|--------|--------|---------------------------|
| 15500.000 | 90.000 | 179.706 | 10071.997 | 46.528 | 0.000 | 55.249 | -0.000 | 46.528 | 0.000 | 0.000 | 55.305 | 36.418 | -3.705 | XOMR2_OWSG MWD+IFR1+MS |
| 15600.000 | 90.000 | 179.706 | 10071.997 | 47.269 | 0.000 | 55.838 | -0.000 | 47.269 | 0.000 | 0.000 | 55.892 | 36.456 | -3.646 | XOMR2_OWSG MWD+IFR1+MS |
| 15700.000 | 90.000 | 179.706 | 10071.997 | 48.012 | 0.000 | 56.430 | -0.000 | 48.012 | 0.000 | 0.000 | 56.484 | 36.495 | -3.589 | XOMR2_OWSG MWD+IFR1+MS |
| 15800.000 | 90.000 | 179.706 | 10071.997 | 48.756 | 0.000 | 57.027 | -0.000 | 48.756 | 0.000 | 0.000 | 57.080 | 36.533 | -3.534 | XOMR2_OWSG MWD+IFR1+MS |
| 15900.000 | 90.000 | 179.706 | 10071.997 | 49.501 | 0.000 | 57.627 | -0.000 | 49.501 | 0.000 | 0.000 | 57.680 | 36.573 | -3.481 | XOMR2_OWSG MWD+IFR1+MS |
| 16000.000 | 90.000 | 179.706 | 10071.997 | 50.248 | 0.000 | 58.231 | -0.000 | 50.248 | 0.000 | 0.000 | 58.284 | 36.613 | -3.430 | XOMR2_OWSG MWD+IFR1+MS |
| 16100.000 | 90.000 | 179.706 | 10071.997 | 50.996 | 0.000 | 58.840 | -0.000 | 50.996 | 0.000 | 0.000 | 58.892 | 36.654 | -3.380 | XOMR2_OWSG MWD+IFR1+MS |
| 16200.000 | 90.000 | 179.706 | 10071.997 | 51.744 | 0.000 | 59.451 | -0.000 | 51.744 | 0.000 | 0.000 | 59.503 | 36.695 | -3.332 | XOMR2_OWSG MWD+IFR1+MS |
| 16300.000 | 90.000 | 179.706 | 10071.997 | 52.494 | 0.000 | 60.067 | -0.000 | 52.494 | 0.000 | 0.000 | 60.118 | 36.737 | -3.285 | XOMR2_OWSG MWD+IFR1+MS |
| 16400.000 | 90.000 | 179.706 | 10071.997 | 53.245 | 0.000 | 60.685 | -0.000 | 53.245 | 0.000 | 0.000 | 60.736 | 36.780 | -3.240 | XOMR2_OWSG MWD+IFR1+MS |
| 16500.000 | 90.000 | 179.706 | 10071.997 | 53.997 | 0.000 | 61.307 | -0.000 | 53.997 | 0.000 | 0.000 | 61.358 | 36.823 | -3.196 | XOMR2_OWSG MWD+IFR1+MS |
| 16600.000 | 90.000 | 179.706 | 10071.997 | 54.750 | 0.000 | 61.933 | -0.000 | 54.750 | 0.000 | 0.000 | 61.982 | 36.866 | -3.153 | XOMR2_OWSG MWD+IFR1+MS |
| 16700.000 | 90.000 | 179.706 | 10071.997 | 55.503 | 0.000 | 62.561 | -0.000 | 55.503 | 0.000 | 0.000 | 62.610 | 36.911 | -3.112 | XOMR2_OWSG MWD+IFR1+MS |
| 16800.000 | 90.000 | 179.706 | 10071.997 | 56.258 | 0.000 | 63.192 | -0.000 | 56.258 | 0.000 | 0.000 | 63.241 | 36.955 | -3.071 | XOMR2_OWSG MWD+IFR1+MS |
| 16900.000 | 90.000 | 179.706 | 10071.997 | 57.013 | 0.000 | 63.826 | -0.000 | 57.013 | 0.000 | 0.000 | 63.875 | 37.001 | -3.032 | XOMR2_OWSG MWD+IFR1+MS |
| 17000.000 | 90.000 | 179.706 | 10071.997 | 57.769 | 0.000 | 64.464 | -0.000 | 57.769 | 0.000 | 0.000 | 64.512 | 37.047 | -2.994 | XOMR2_OWSG MWD+IFR1+MS |
| 17100.000 | 90.000 | 179.706 | 10071.997 | 58.526 | 0.000 | 65.103 | -0.000 | 58.526 | 0.000 | 0.000 | 65.151 | 37.094 | -2.957 | XOMR2_OWSG MWD+IFR1+MS |
| 17200.000 | 90.000 | 179.706 | 10071.997 | 59.284 | 0.000 | 65.746 | -0.000 | 59.284 | 0.000 | 0.000 | 65.793 | 37.141 | -2.921 | XOMR2_OWSG MWD+IFR1+MS |
| 17300.000 | 90.000 | 179.706 | 10071.997 | 60.042 | 0.000 | 66.391 | -0.000 | 60.042 | 0.000 | 0.000 | 66.438 | 37.188 | -2.886 | XOMR2_OWSG MWD+IFR1+MS |

| 17400.000 | 90.000 179.7 | 706 10071.997 | 60.801 0.000 | 67.039 -0.000 | 60.801 0.000 | 0.000 | 67.085 | 37.237 | -2.852 XOMR2_OWSG MWD+IFR1+MS |
|-----------|--------------|---------------|--------------|---------------|--------------|-------|--------|--------|----------------------------------|
| 17500.000 | 90.000 179.7 | 706 10071.997 | 61.561 0.000 | 67.689 -0.000 | 61.561 0.000 | 0.000 | 67.735 | 37.286 | -2.818 XOMR2_OWSG MWD+IFR1+MS |
| 17600.000 | 90.000 179.7 | 706 10071.997 | 62.321 0.000 | 68.341 -0.000 | 62.321 0.000 | 0.000 | 68.387 | 37.335 | -2.786 XOMR2_OWSG MWD+IFR1+MS |
| 17700.000 | 90.000 179.7 | 706 10071.997 | 63.082 0.000 | 68.996 -0.000 | 63.082 0.000 | 0.000 | 69.041 | 37.385 | -2.754 XOMR2_OWSG MWD+IFR1+MS |
| 17800.000 | 90.000 179.7 | 706 10071.997 | 63.843 0.000 | 69.653 -0.000 | 63.843 0.000 | 0.000 | 69.698 | 37.436 | -2.723 XOMR2_OWSG MWD+IFR1+MS |
| 17900.000 | 90.000 179.7 | 706 10071.997 | 64.605 0.000 | 70.312 -0.000 | 64.605 0.000 | 0.000 | 70.357 | 37.487 | -2.693 XOMR2_OWSG MWD+IFR1+MS |
| 18000.000 | 90.000 179.7 | 706 10071.997 | 65.368 0.000 | 70.974 -0.000 | 65.368 0.000 | 0.000 | 71.018 | 37.539 | -2.664 XOMR2_OWSG MWD+IFR1+MS |
| 18100.000 | 90.000 179.7 | 706 10071.997 | 66.131 0.000 | 71.637 -0.000 | 66.131 0.000 | 0.000 | 71.681 | 37.591 | -2.635 XOMR2_OWSG MWD+IFR1+MS |
| 18200.000 | 90.000 179.7 | 706 10071.997 | 66.894 0.000 | 72.303 -0.000 | 66.894 0.000 | 0.000 | 72.346 | 37.644 | -2.607 XOMR2_OWSG MWD+IFR1+MS |
| 18300.000 | 90.000 179.7 | 706 10071.997 | 67.658 0.000 | 72.970 -0.000 | 67.658 0.000 | 0.000 | 73.013 | 37.697 | -2.580 XOMR2_OWSG MWD+IFR1+MS |
| 18400.000 | 90.000 179.7 | 706 10071.997 | 68.423 0.000 | 73.639 -0.000 | 68.423 0.000 | 0.000 | 73.682 | 37.751 | -2.553 XOMR2_OWSG MWD+IFR1+MS |
| 18500.000 | 90.000 179.7 | 706 10071.997 | 69.188 0.000 | 74.311 -0.000 | 69.188 0.000 | 0.000 | 74.352 | 37.805 | -2.527 XOMR2_OWSG MWD+IFR1+MS |
| 18600.000 | 90.000 179.7 | 706 10071.997 | 69.953 0.000 | 74.984 -0.000 | 69.953 0.000 | 0.000 | 75.025 | 37.860 | -2.502 XOMR2_OWSG MWD+IFR1+MS |
| 18700.000 | 90.000 179.7 | 706 10071.997 | 70.719 0.000 | 75.658 -0.000 | 70.719 0.000 | 0.000 | 75.699 | 37.916 | -2.477 XOMR2_OWSG MWD+IFR1+MS |
| 18800.000 | 90.000 179.7 | 706 10071.997 | 71.485 0.000 | 76.335 -0.000 | 71.485 0.000 | 0.000 | 76.375 | 37.972 | -2.453 XOMR2_OWSG MWD+IFR1+MS |
| 18900.000 | 90.000 179.7 | 706 10071.997 | 72.252 0.000 | 77.013 -0.000 | 72.252 0.000 | 0.000 | 77.053 | 38.028 | -2.429 XOMR2_OWSG MWD+IFR1+MS |
| 19000.000 | 90.000 179.7 | 706 10071.997 | 73.019 0.000 | 77.692 -0.000 | 73.019 0.000 | 0.000 | 77.733 | 38.085 | -2.406 XOMR2_OWSG MWD+IFR1+MS |
| 19100.000 | 90.000 179.7 | 706 10071.997 | 73.786 0.000 | 78.374 -0.000 | 73.786 0.000 | 0.000 | 78.413 | 38.143 | -2.383 XOMR2_OWSG MWD+IFR1+MS |
| 19200.000 | 90.000 179.7 | 706 10071.997 | 74.554 0.000 | 79.057 -0.000 | 74.554 0.000 | 0.000 | 79.096 | 38.201 | -2.361 XOMR2_OWSG MWD+IFR1+MS |
| 19300.000 | 90.000 179.7 | 706 10071.997 | 75.322 0.000 | 79.741 -0.000 | 75.322 0.000 | 0.000 | 79.780 | 38.260 | -2.339 XOMR2_OWSG MWD+IFR1+MS |

| 19400.000 | 90.000 179.706 1007 | 1.997 76.090 0.000 | 80.427 -0.000 | 76.090 0.000 | 0.000 | 80.465 | 38.319 | -2.317 XOMR2_OWSG MWD+IFR1+MS |
|-----------|---------------------|--------------------|---------------|--------------|-------|--------|--------|----------------------------------|
| 19500.000 | 90.000 179.706 1007 | 1.997 76.859 0.000 | 81.114 -0.000 | 76.859 0.000 | 0.000 | 81.152 | 38.379 | -2.296 XOMR2_OWSG MWD+IFR1+MS |
| 19600.000 | 90.000 179.706 1007 | 1.997 77.628 0.000 | 81.802 -0.000 | 77.628 0.000 | 0.000 | 81.840 | 38.439 | -2.276 XOMR2_OWSG MWD+IFR1+MS |
| 19700.000 | 90.000 179.706 1007 | 1.997 78.397 0.000 | 82.492 -0.000 | 78.397 0.000 | 0.000 | 82.530 | 38.500 | -2.256 XOMR2_OWSG MWD+IFR1+MS |
| 19800.000 | 90.000 179.706 1007 | 1.997 79.167 0.000 | 83.183 -0.000 | 79.167 0.000 | 0.000 | 83.221 | 38.561 | -2.236 XOMR2_OWSG MWD+IFR1+MS |
| 19900.000 | 90.000 179.706 1007 | 1.997 79.937 0.000 | 83.876 -0.000 | 79.937 0.000 | 0.000 | 83.913 | 38.623 | -2.217 XOMR2_OWSG MWD+IFR1+MS |
| 20000.000 | 90.000 179.706 1007 | 1.997 80.707 0.000 | 84.570 -0.000 | 80.707 0.000 | 0.000 | 84.607 | 38.686 | -2.198 XOMR2_OWSG MWD+IFR1+MS |
| 20100.000 | 90.000 179.706 1007 | 1.997 81.478 0.000 | 85.265 -0.000 | 81.478 0.000 | 0.000 | 85.301 | 38.748 | -2.179 XOMR2_OWSG MWD+IFR1+MS |
| 20200.000 | 90.000 179.706 1007 | 1.997 82.249 0.000 | 85.961 -0.000 | 82.249 0.000 | 0.000 | 85.997 | 38.812 | -2.161 XOMR2_OWSG MWD+IFR1+MS |
| 20300.000 | 90.000 179.706 1007 | 1.997 83.020 0.000 | 86.658 -0.000 | 83.020 0.000 | 0.000 | 86.694 | 38.875 | -2.143 XOMR2_OWSG MWD+IFR1+MS |
| 20400.000 | 90.000 179.706 1007 | 1.997 83.791 0.000 | 87.357 -0.000 | 83.791 0.000 | 0.000 | 87.392 | 38.940 | -2.126 XOMR2_OWSG MWD+IFR1+MS |
| 20500.000 | 90.000 179.706 1007 | 1.997 84.563 0.000 | 88.056 -0.000 | 84.563 0.000 | 0.000 | 88.092 | 39.005 | -2.109 XOMR2_OWSG MWD+IFR1+MS |
| 20600.000 | 90.000 179.706 1007 | 1.997 85.335 0.000 | 88.757 -0.000 | 85.335 0.000 | 0.000 | 88.792 | 39.070 | -2.092 XOMR2_OWSG MWD+IFR1+MS |
| 20700.000 | 90.000 179.706 1007 | 1.997 86.107 0.000 | 89.459 -0.000 | 86.107 0.000 | 0.000 | 89.494 | 39.136 | -2.075 XOMR2_OWSG MWD+IFR1+MS |
| 20800.000 | 90.000 179.706 1007 | 1.997 86.879 0.000 | 90.161 -0.000 | 86.879 0.000 | 0.000 | 90.196 | 39.202 | -2.059 XOMR2_OWSG MWD+IFR1+MS |
| 20900.000 | 90.000 179.706 1007 | 1.997 87.651 0.000 | 90.865 -0.000 | 87.651 0.000 | 0.000 | 90.900 | 39.269 | -2.043 XOMR2_OWSG MWD+JFR1+MS |
| 21000.000 | 90.000 179.706 1007 | 1.997 88.424 0.000 | 91.570 -0.000 | 88.424 0.000 | 0.000 | 91.604 | 39.336 | -2.027 XOMR2_OWSG MWD+JFR1+MS |
| 21100.000 | 90.000 179.706 1007 | 1.997 89.197 0.000 | 92.276 -0.000 | 89.197 0.000 | 0.000 | 92.310 | 39.404 | -2.012 XOMR2_OWSG MWD+JFR1+MS |
| 21200.000 | 90.000 179.706 1007 | 1.997 89.970 0.000 | 92.982 -0.000 | 89.970 0.000 | 0.000 | 93.016 | 39.472 | -1.997 XOMR2_OWSG MWD+IFR1+MS |
| 21300.000 | 90.000 179.706 1007 | 1.997 90.744 0.000 | 93.690 -0.000 | 90.744 0.000 | 0.000 | 93.723 | 39.541 | -1.982 XOMR2_OWSG MWD+IFR1+MS |

| 21400.000 | 90.000 | 179.706 | 10071.997 | 91.517 | 0.000 | 94.398 | -0.000 | 91.517 | 0.000 | 0.000 | 94.432 | 39.610 | -1.967 | XOMR2_OWSG MWD+IFR1+MS |
|-----------|--------|---------|-----------|---------|-------|---------|--------|---------|-------|-------|---------|--------|--------|---------------------------|
| 21500.000 | 90.000 | 179.706 | 10071.997 | 92.291 | 0.000 | 95.108 | -0.000 | 92.291 | 0.000 | 0.000 | 95.141 | 39.680 | -1.953 | XOMR2_OWSG MWD+IFR1+MS |
| 21600.000 | 90.000 | 179.706 | 10071.997 | 93.065 | 0.000 | 95.818 | -0.000 | 93.065 | 0.000 | 0.000 | 95.851 | 39.750 | -1.939 | XOMR2_OWSG MWD+IFR1+MS |
| 21700.000 | 90.000 | 179.706 | 10071.997 | 93.839 | 0.000 | 96.529 | -0.000 | 93.839 | 0.000 | 0.000 | 96.561 | 39.820 | -1.925 | XOMR2_OWSG MWD+IFR1+MS |
| 21800.000 | 90.000 | 179.706 | 10071.997 | 94.613 | 0.000 | 97.241 | -0.000 | 94.613 | 0.000 | 0.000 | 97.273 | 39.891 | -1.911 | XOMR2_OWSG MWD+IFR1+MS |
| 21900.000 | 90.000 | 179.706 | 10071.997 | 95.388 | 0.000 | 97.953 | -0.000 | 95.388 | 0.000 | 0.000 | 97.985 | 39.963 | -1.898 | XOMR2_OWSG MWD+IFR1+MS |
| 22000.000 | 90.000 | 179.706 | 10071.997 | 96.162 | 0.000 | 98.667 | -0.000 | 96.162 | 0.000 | 0.000 | 98.699 | 40.035 | -1.885 | XOMR2_OWSG MWD+IFR1+MS |
| 22100.000 | 90.000 | 179.706 | 10071.997 | 96.937 | 0.000 | 99.381 | -0.000 | 96.937 | 0.000 | 0.000 | 99.413 | 40.107 | -1.872 | XOMR2_OWSG MWD+IFR1+MS |
| 22200.000 | 90.000 | 179.706 | 10071.997 | 97.712 | 0.000 | 100.096 | -0.000 | 97.712 | 0.000 | 0.000 | 100.127 | 40.180 | -1.859 | XOMR2_OWSG MWD+IFR1+MS |
| 22300.000 | 90.000 | 179.706 | 10071.997 | 98.487 | 0.000 | 100.812 | -0.000 | 98.487 | 0.000 | 0.000 | 100.843 | 40.253 | -1.846 | XOMR2_OWSG MWD+IFR1+MS |
| 22400.000 | 90.000 | 179.706 | 10071.997 | 99.262 | 0.000 | 101.528 | -0.000 | 99.262 | 0.000 | 0.000 | 101.559 | 40.327 | -1.834 | XOMR2_OWSG MWD+IFR1+MS |
| 22500.000 | 90.000 | 179.706 | 10071.997 | 100.038 | 0.000 | 102.245 | -0.000 | 100.038 | 0.000 | 0.000 | 102.276 | 40.401 | -1.822 | XOMR2_OWSG MWD+IFR1+MS |
| 22600.000 | 90.000 | 179.706 | 10071.997 | 100.813 | 0.000 | 102.963 | -0.000 | 100.813 | 0.000 | 0.000 | 102.994 | 40.476 | -1.810 | XOMR2_OWSG MWD+IFR1+MS |
| 22700.000 | 90.000 | 179.706 | 10071.997 | 101.589 | 0.000 | 103.682 | -0.000 | 101.589 | 0.000 | 0.000 | 103.712 | 40.551 | -1.798 | XOMR2_OWSG MWD+IFR1+MS |
| 22800.000 | 90.000 | 179.706 | 10071.997 | 102.365 | 0.000 | 104.401 | -0.000 | 102.365 | 0.000 | 0.000 | 104.431 | 40.627 | -1.786 | XOMR2_OWSG MWD+IFR1+MS |
| 22865.281 | 90.000 | 179.706 | 10072.000 | 102.871 | 0.000 | 104.870 | -0.000 | 102.871 | 0.000 | 0.000 | 104.900 | 40.676 | -1.779 | XOMR2_OWSG MWD+IFR1+MS |
| 22900.000 | 90.000 | 179.706 | 10072.000 | 103.141 | 0.000 | 105.120 | -0.000 | 103.141 | 0.000 | 0.000 | 105.150 | 40.703 | -1.775 | XOMR2_OWSG MWD+IFR1+MS |
| 22955.287 | 90.000 | 179.706 | 10072.000 | 103.570 | 0.000 | 105.518 | -0.000 | 103.570 | 0.000 | 0.000 | 105.548 | 40.745 | -1.769 | XOMR2_OWSG MWD+IFR1+MS |


Plan Targets


Poker Lake Unit 18-30 BD 201H

Measured Depth Grid Northing Grid Easting TVD MSL Target Shape

| Target Name | (ft) | (ft) | (ft) | (ft) | |
|-------------|----------|-----------|-----------|-----------|-------|
| FTP 2 | 10199.14 | 413827.30 | 628527.00 | 6860.00 C | IRCLE |
| LTP 12 | 22865.28 | 400740.80 | 628594.20 | 6860.00 C | IRCLE |
| BHL 2 | 22955.28 | 400650.80 | 628594.80 | 6860.00 C | IRCLE |

Poker Lake Unit 18-30 BD 201H





| Formation | TVDSS (feet) | TVD (feet) |
|--------------------------|------------------------|------------|
| Rustler | 2,498' | 714' |
| Salado | 2,066' | 1,146' |
| Base of Salt | -101' | 3,313' |
| Delaware | -320' | 3,532' |
| Cherry Canyon | -1,228* | 4,440' |
| Brushy Canyon | -2,485' | 5,697' |
| Basal Brushy Canyon | -3,867' | 7,079 |
| Bone Spring Lm. | -4,083' | 7,295' |
| Avalon Shale | -4,250° | 7,462' |
| Lower Avalon Shale | -4,669' | 7,881 |
| 1st Bone Spring Lime | -4,845' | 8,057 |
| 1st Bone Spring Sand | -5,053' | 8,265 |
| 2nd Bone Spring Shale | -5,291' | 8,503' |
| 2nd Bone Spring Lime | -5,383' | 8,595' |
| 2nd Bone Spring Sand | -5,852' | 9,064 |
| 2nd Bone Spring T/B Carb | -6,013' | 9,225' |
| 3rd Bone Spring Lime | -6, <mark>1</mark> 61' | 9,373' |
| Harkey | -6,498' | 9,710 |
| 3rd Bone Spring Shale | -6,536' | 9,748' |
| Landing | -6,860' | 10,072 |
| 3rd Bone Spring Sand | -6,926' | 10,138' |
| Wolfcamp | -7,276' | 10,488' |

Cement Variance Request

Intermediate Casing:


+ 3% Salt + 1% PreMag-M + 6% Bentonite Gel (2.30 yld, 12.91 ppg) will be executed as a contingency. If cement is still unable to circulate to surface, another Echo-meter run will be performed for cement top XTO requests to pump a two stage cement job on the 7-5/8" intermediate casing string with the first stage being pumped conventionally with the calculated top of cement at the Brush Canyon (5697') and the second stage performed as a bradenhead squeeze with planned cement from the Brushy Canyon to surface. If cement is not visually confirmed to circulate to surface, the final cement top after the second stage job will be verified by Echo-meter. If necessary, a top out consisting of 1,500 sack of Class C cement verification.

XTO will report to the BLM the volume of fluid (limited to 5 bbls) used to flush intermediate casing valves following backside cementing procedures.

first intermediate casing. If cement reaches the desired height, the BLM will be notified and the second XTO requests to pump an Optional Lead if well conditions dictate in an attempt to bring cement inside the stage bradenhead squeeze and subsequent TOC verification will be negated. XTO requests the option to conduct the bradenhead squeeze and TOC verification offline as per standard approval from BLM when unplanned remediation is needed and batch drilling is approved. In the event the bradenhead is conducted, we will ensure the first stage cement job is cemented properly and the well is static with floats holding and no pressure on the csg annulus as with all other casing strings where batch drilling operations occur before moving off the rig. The TA cap will also be installed per Cactus procedure and pressure inside the casing will be monitored via the valve on the TA cap as per standard batch drilling


Production Casing:

strings where batch drilling is approved and if unplanned remediation is needed. XTO will ensure well is static with no pressure on the csg annulus, as with all other casing strings where batch drilling operations XTO requests the option to offline cement and remediate (if needed) surface and intermediate casing occur before moving off the rig. The TA cap will also be installed when applicable per Cactus procedure and pressure inside the casing will be monitored via the valve on the TA cap as per standard batch drilling ops. Offline cement operations will then be conducted after the rig is moved off the current well to the next well in the batch sequence.



| | | ALL DIMENSIO | NS APPROX I MATE |
|-----------------------------------------------------------------------------------------------------------------|-----------|-------------------------------|-------------------------|
| CACTUS WELLHEAD LLC | | XTO ENERGY IN DELAWARE BAS | _ |
| 20" x 9-5/8" x 7-5/8" x 5-1/2" MBU-T-CFL-R-DBLO Wellhead | DRAWN | VJK | 31MAR22 |
| | APPRV | | |
| With 11" 10M x 7-1/16" 15M CTH-DBLHPS Tubing Head And 9-5/8", 7-5/8" & 5-1/2" Pin Bottom Mandrel Casing Hangers | DRAWING N | o. HBE000 | 0479 |

INFORMATION CONTAINED HEREIN IS THE PROPERTY OF CACTUS WELLHEAD, LLC. REPRODUCTION, DISCLOSURE, OR USE THEREOF IS PERMISSIBLE ONLY AS PROVIDED BY CONTRACT OR AS EXPRESSLY AUTHORIZED BY CACTUS WELLHEAD, LLC.



Page 1 of 6

Energy, Minerals and Natural Resources Department State of New Mexico

Submit Electronically Via E-permitting

Santa Fe, NM 87505

1220 South St. Francis Dr. Oil Conservation Division

NATURAL GAS MANAGEMENT PLAN

This Natural Gas Management Plan must be submitted with each Application for Permit to Drill (APD) for a new or recompleted well.

| 373075 Date: | | $9.15.27.9.D(6)(b)$ NMAC \square Other. |
|---------------------------------|------------------|------------------------------------------------------------------------------------------------|
| XTO PERMIAN OPERATING, LLCOGRID | | \square Amendment due to \square 19.15.27.9.D(6)(a) NMAC \square 19.15.27.9.D(6)(b) NMAC |
| I. Operator: | _07_/_29_/_2024_ | II. Type: ⊠ Original |

III. Well(s): Provide the following information for each new or recompleted well or set of wells proposed to be drilled or proposed to be recompleted from a single well pad or connected to a central delivery point.

If Other, please describe:

| 3 yr Anticipated decline Water BBL/D | 400 | 700 | 400 | 006 | 400 | 006 | 400 | 006 | 1,100 |
|--------------------------------------------------|------------------------------------|------------------------------------|------------------------------------|------------------------------------|-----------------------------------|-----------------------------------|-----------------------------------|-----------------------------------|-----------------------------------|
| Anticipated Produced Water BBL/D | 1,250 | 3,750 | 1,250 | 4,250 | 1,500 | 4,250 | 1,500 | 4,250 | 4,750 |
| 3 yr Anticipated decline Gas MCF/D | 006 | 006 | 006 | 1,200 | 1,000 | 1,200 | 1,000 | 1,200 | 1,400 |
| Anticipa ted Gas MCF/D | 1,500 | 2,750 | 1,500 | 3,000 | 1,750 | 3,000 | 1,750 | 3,000 | 3,500 |
| 3 yr Anticipated decline Oil BBL/D | 125 | 125 | 125 | 175 | 150 | 175 | 150 | 175 | 200 |
| Anticip ated Oil BBL/D | 200 | 1,100 | 200 | 1,200 | 009 | 1,200 | 009 | 1,200 | 1,300 |
| Footages | 1434 FSL; 1904 FWL | 1433 FSL; 1934 FWL | 1432 FSL; 1964 FWL | 1431 FSL; 1994 FWL | 1430 FSL; 2024 FWL | 1813 FSL; 1604 FEL | 1813 FSL; 1574 FEL | 1813 FSL; 1544 FEL | 1813 FSL; 1514 FEL |
| ULSTR | 20 T25S R30E | 20 T25S R30E | 20 T25S R30E | 20 T25S R30E | 20 T25S R30E | 20 T25S R30E | 20 T25S R30E | 20 T25S R30E | 20 T25S R30E |
| API | TBD | TBD | TBD | TBD | TBD | TBD | ТВD | TBD | TBD |
| Well Name | Poker Lake Unit 20-17 BD 201 | Poker Lake Unit 20-17 BD 202 | Poker Lake Unit 20-17 BD 203 | Poker Lake Unit 20-17 BD 204 | Poker Lake Unit 20-8 BD 205 | Poker Lake Unit 20-8 BD 206 | Poker Lake Unit 20-8 BD 207 | Poker Lake Unit 20-8 BD 208 | Poker Lake Unit 20-8 BD 209 |

| 006 | 006 | 400 | 006 | 400 | 700 | 400 | 700 | 400 | 700 | 009 |
|-----------------------------------|-------------------------------------|-------------------------------------|-------------------------------------|-------------------------------------|-------------------------------------|-------------------------------------|-------------------------------------|-------------------------------------|-------------------------------------|-------------------------------------|
| 4,750 | 4,250 | 1,500 | 4,250 | 1,500 | 3,750 | 1,250 | 3,750 | 1,250 | 3,750 | 4,000 |
| 2,700 | 1,200 | 1,000 | 1,200 | 1,000 | 006 | 006 | 006 | 006 | 006 | 1,700 |
| 7,250 | 3,000 | 1,750 | 3,000 | 1,750 | 2,750 | 1,500 | 2,750 | 1,500 | 2,750 | 5,500 |
| 75 | 175 | 150 | 175 | 150 | 125 | 125 | 125 | 125 | 125 | 50 |
| 009 | 1,200 | 009 | 1,200 | 009 | 1,100 | 500 | 1,100 | 500 | 1,100 | 200 |
| 1813 FSL; 1484 FEL | 265 FNL; 2395 FEL | 265 FNL; 2365 FEL | 265 FNL; 2335 FEL | 265 FNL; 2305 FEL | 265 FNL; 2275 FEL | 265 FNL; 1935 FEL | 265 FNL; 1905 FEL | 265 FNL; 1875 FEL | 265 FNL; 1845 FEL | 265 FNL; 1815 FEL |
| 20 T25S R30E | 18 T25S R30E |
| TBD | TBD | TBD | TBD | TBD | TBD | TBD | TBD | TBD | TBD | TBD |
| Poker Lake Unit 20-8 BD 210 | Poker Lake Unit 18-30 BD 200H | Poker Lake Unit 18-30 BD 201H | Poker Lake Unit 18-30 BD 202H | Poker Lake Unit 18-30 BD 203H | Poker Lake Unit 18-19 BD 204H | Poker Lake Unit 18-19 BD 205H | Poker Lake Unit 18-19 BD 206H | Poker Lake Unit 18-19 BD 207H | Poker Lake Unit 18-19 BD 208H | Poker Lake Unit 18-19 BD 209H |

PLU Brushy Draw 18 (PLU 18-30/18-19) and PLU Brushy Draw 20 (PLU 20-17/20-8) IV. Central Delivery Point Name:_ [See 19.15.27.9(D)(1) NMAC]

V. Anticipated Schedule: Provide the following information for each new or recompleted well or set of wells proposed to be drilled or First Production TBD TBD TBD Initial Flow Back Date TBD TBD TBD Completion Commencement Date proposed to be recompleted from a single well pad or connected to a central delivery point.

Well Name | API | Spud Date | TD Reached | Completic TBD TBD TBD TD Reached Date TBD TBD TBD August 2025 August 2025 August 2025 Spud Date TBD TBD TBD Poker Lake Unit 20**-**17 BD 201 Poker Lake Unit 20-17 BD 202 Poker Lake Unit 20-17 BD 203 Poker Lake Unit 20-17 BD 204

TBD Page 2 of 6

TBD

TBD

TBD

August 2025

TBD

TBD

TBD

TBD

TBD

August 2025

TBD

Poker Lake Unit 20-8 BD 205 Poker Lake Unit 20-8 BD 206 Poker Lake Unit 20-8 BD 207

TBD

TBD

TBD

TBD

August 2025

TBD

TBD

TBD

TBD

TBD

August 2025

TBD

Page 3 of 6

| Poker Lake Unit 20-8 BD 208 | 1 | 2000 tormer A | e de la composition della comp | Agt | TBD | rat |
|----------------------------------|-----|---------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----|-----|-----|
| | IBD | August 2025 | IBD | IBD | IBD | IBD |
| Poker Lake Unit 20-8 BD 209 | TBD | August 2025 | TBD | TBD | TBD | TBD |
| Poker Lake Unit 20-8 BD 210 | TBD | August 2025 | TBD | TBD | TBD | TBD |
| Poker Lake Unit 18-30 BD 200H | TBD | October 2025 | TBD | TBD | TBD | TBD |
| Poker Lake Unit 18-30 BD 201H | TBD | October 2025 | TBD | TBD | ΠBD | TBD |
| Poker Lake Unit 18-30 BD 202H | TBD | October 2025 | TBD | TBD | ΠBD | TBD |
| Poker Lake Unit 18-30 BD 203H | TBD | October 2025 | TBD | TBD | ПВП | TBD |
| Poker Lake Unit 18-19 BD 204H | TBD | October 2025 | TBD | TBD | ПВП | TBD |
| Poker Lake Unit 18-19 BD 205H | TBD | October 2025 | ТВD | TBD | ПВП | TBD |
| Poker Lake Unit 18-19 BD 206H | TBD | October 2025 | TBD | TBD | TBD | TBD |
| Poker Lake Unit 18-19 BD 207H | TBD | October 2025 | TBD | TBD | TBD | TBD |
| Poker Lake Unit 18-19 BD 208H | TBD | October 2025 | ТВD | TBD | ΠBD | TBD |
| Poker Lake Unit 18-19 BD 209H | TBD | October 2025 | TBD | TBD | TBD | TBD |

VI. Separation Equipment: 🗵 Attach a complete description of how Operator will size separation equipment to optimize gas capture.

VII. Operational Practices: A Attach a complete description of the actions Operator will take to comply with the requirements of Subsection A through F of 19.15.27.8 NMAC.

VIII. Best Management Practices:

Attach a complete description of Operator's best management practices to minimize venting during active and planned maintenance.

Section 2 – Enhanced Plan EFFECTIVE APRIL 1,2022

Beginning April 1, 2022, an operator that is not in compliance with its statewide natural gas capture requirement for the applicable reporting area must complete this section.

■ Operator certifies that it is not required to complete this section because Operator is in compliance with its statewide natural gas. capture requirement for the applicable reporting area.

IX. Anticipated Natural Gas Production:

| Anticipated Volume of Natural Gas for the First Year MCF | |
|-------------------------------------------------------------|--|
| Anticipated Average Natural Gas Rate MCF/D | |
| API | |
| Well | |

X. Natural Gas Gathering System (NGGS):

| | | |
|-----------------------------------------------------------|------|--|
| Available Maximum Daily Capacity of System Segment Tie-in | | |
| Anticipated Gathering Start Date | | |
| ULSTR of Tie-in | | |
| System | | |
| Operator | | |

XI. Map. \square Attach an accurate and legible map depicting the location of the well(s), the anticipated pipeline route(s) connecting the production operations to the existing or planned interconnect of the natural gas gathering system (s), and the maximum daily capacity of the segment or portion of the natural gas gathering system(s) to which the well(s) will be connected

XII. Line Capacity. The natural gas gathering system \square will \square will not have capacity to gather 100% of the anticipated natural gas production volume from the well prior to the date of first production. XIII. Line Pressure. Operator 🗆 does 🗀 does not anticipate that its existing well(s) connected to the same segment, or portion, of the natural gas gathering system(s) described above will continue to meet anticipated increases in line pressure caused by the new well(s).

☐ Attach Operator's plan to manage production in response to the increased line pressure.

☐ Operator asserts confidentiality pursuant to Section 71-2-8 NMSA 1978 for the information provided in Section 2 as provided in Paragraph (2) of Subsection D of 19.15.27.9 NMAC, and attaches a full description of the specific information for which confidentiality is asserted and the basis for such assertion. XIV. Confidentiality:

Section 3 - Certifications Effective May 25, 202

Operator certifies that, after reasonable inquiry and based on the available information at the time of submittal:

hundred percent of the anticipated volume of natural gas produced from the well(s) commencing on the date of first production, taking taking into account the current and anticipated volumes of produced natural gas from other wells connected to the pipeline ga thering Solution Solutio one hundred percent of the anticipated volume of natural gas produced from the well(s) commencing on the date of first production, Operator will not be able to connect to a natural gas gathering system in the general area with sufficient capacity to transport one into account the current and anticipated volumes of produced natural gas from other wells connected to the pipeline gathering system.

Well Shut-In. \square Operator will shut-in and not produce the well until it submits the certification required by Paragraph (4) of Subsection D of 19.15.27.9 NMAC; or

If Operator checks this box, Operator will select one of the following:

Venting and Flaring Plan.

Operator has attached a venting and flaring plan that evaluates and selects one or more of the potential alternative beneficial uses for the natural gas until a natural gas gathering system is available, including:

(a) power generation on lease;

power generation for grid;

compression on lease;

reinjection for underground storage;

reinjection for temporary storage;

reinjection for enhanced oil recovery; fuel cell production; and

other alternative beneficial uses approved by the division.

Section 4


1. If, at any time after Operator submits this Natural Gas Management Plan and before the well is spud:

Operator becomes aware that the natural gas gathering system it planned to connect the well(s) to has become unavailable or will not have capacity to transport one hundred percent of the production from the well(s), no later than 20 days after becoming aware of such information, Operator shall submit for OCD's approval a new or revised venting and flaring plan containing the information specified in Paragraph (5) of Subsection D of 19.15.27.9 NMAC; or Operator becomes aware that it has, cumulatively for the year, become out of compliance with its baseline natural gas for OCD's approvala new or revised Natural Gas Management Plan for each well it plans to spud during the next 90 days containing the information specified in Paragraph (2) of Subsection D of 19.15.27.9 NMAC, and shall file an update for each Natural Gas capture rate or natural gas capture requirement, no later than 20 days after becoming aware of such information, Operator shall submit Management Plan until Operator is back in compliance with its baseline natural gas capture rate or natural gas capture requirement.

flaring plan which includes alternative beneficial uses for the anticipated volume of natural gas produced, or if OCD determines that 2. OCD may deny or conditionally approve an APD if Operator does not make a certification, fails to submit an adequate venting and Operator will not have a dequate natural gas ta kea way capacity at the time a well will be spud.

Page 6 of 6

I certify that, after reasonable inquiry, the statements in and attached to this Natural Gas Management Plan are true and correct to the best of my knowledge and acknowledge that a false statement may be subject to civil and criminal penalties under the Oil (Only applicable when submitted as a standalone form) OIL CONSERVATION DIVISION **Environmental and Regulatory Advisor** nicj100@gmail.com 432-2363808 Adrian Baker 9/9/2024 Conditions of Approval: E-mail Address: and Gas Act. Approval Date: Printed Name: Approved By: Signature: Phone: Title: Date: Title:



VI. Separation Equipment:

XTO Permian Operating LLC. utilizes a "stage separation" process in which oil and gas separation is separation process is to attain maximum recovery of liquid hydrocarbons from the fluids and allow Hydrocarbon liquids are produced into a high-pressure inlet separator, then carried through one or Compression units to capture gas off the staged separation and send it to the sales pipeline. This maximum capture of produced gas into the sales pipeline. XTO utilizes a series of Low-Pressure more lower pressure separation vessels before entering the storage tanks. The purpose of this process minimizes the amount of flash gas that enters the end-stage storage tanks that is carried out through a series of separators operating at successively reduced pressures. subsequently vented or flared.

VII. Operational Practices

XTO Permian Operating LLC will employ best management practices and control technologies to maximize the recovery and minimize waste of natural gas through venting and flaring.

- technically feasible. If flaring is deemed technically in-feasible, XTO will employ best management During drilling operations, XTO will utilize flares to capture and control natural gas, where practices to minimize or reduce venting to the extent possible.
- During completions operations, XTO will utilize Green Completion methods to capture gas produced during well completions that is otherwise vented or flared. If capture is technically inflowback. Upon indication of first measurable hydrocarbon volumes, XTO Permian Operating feasible, flares will be used to control flow back fluids entering into frac tanks during initial LLCwill turn operations to onsite separation vessels and flow to the gathering pipeline.
- During production operations, XTO Permian Operating LLC will take every practical effort to minimize waste of natural gas through venting and flaring by:
- Designing and constructing facilities in a manner consistent to achieve maximum capture and control of hydrocarbon liquids & produced gas
- Utilizing a closed-loop capture system to collect, and route produced gas to sales line via low pressure compression, or to a flare/combustor
- Flaring in lieu of venting, where technically feasible
- Utilizing auto-ignitors or continuous pilots, with thermocouples connected to Scada, to quickly detect and resolve issues related to malfunctioning flares/combustors
- Employ the use of automatic tank gauging to minimize storage tank venting during loading
- Installing air-driven or electric-driven pneumatics & combustion engines, where technically feasible to minimize venting to the atmosphere
- Confirm equipment is properly maintained and repaired through a preventative maintenance and repair program to ensure equipment meets all manufacturer specifications

Conduct and document AVO inspections on the frequency set forth in Part 27 to detect and repair any onsite leaks as quickly and efficiently as is feasible. •

VIII. Best Management Practices during Maintenance

venting to the atmosphere. XTO will work with third-party operators during scheduled maintenance facilities permitted under NOI permits have no provisions to allow high pressure flaring and highof downstream pipeline or processing plants to address those events ahead of time to minimize pressure flaring is only allowed in disruption scenarios so long as the duration is less than eight hours. When technically feasible, flaring during maintenance activities will be utilized in lieu of XTO Permian Operating LLC. will utilize best management practices to minimize venting during venting. Actions considered include identifying alternative capture approaches or planning to active and planned maintenance activities. XTO is operating under guidance that production temporarily reduce production or shut in the well to address these circumstances.

XTO Permian Operating, LLC Offline Cementing Variance Request

a XTO requests the option to cement the surface and intermediate casing strings offline as prudent batch drilling efficiency of acreage development.


1. Cement Program

No changes to the cement program will take place for offline cementing.

2. Offline Cementing Procedure


The operational sequence will be as follows. If a well control event occurs, the BLM will be contacted for approval prior to conducting offline cementing operations.

- Run casing as per normal operations. While running casing, conduct negative pressure test and confirm integrity of the float equipment (float collar and shoe)
- Land casing with mandrel
- Fill pipe with kill weight fluid, do not circulate through floats and confirm well is static 3 5
 - Set annular packoff shown below and pressure test to confirm integrity of the seal Pressure ratings of wellhead components and valves is 5,000 psi. 4
- After confirmation of both annular barriers and internal barriers, nipple down BOP δ.
- If any barrier fails to test, the BOP stack will not be nippled down until after the cement job is completed with cement 500ft above the highest formation capable of flow with kill weight mud above or after it has achieved 50-psi compressive strength if kill weight fluid cannot be verified. and install cap flange.



Annular packoff with both external and internal seals


XTO Permian Operating, LLC Offline Cementing Variance Request



Wellhead diagram during skidding operations

- Skid rig to next well on pad.
- Confirm well is static before removing cap flange, flange will not be removed and offline cementing operations will not commence until well is under control. If well is not static, party pump truck will kill well prior to cementing or nippling up for further remediation. casing outlet valves will provide access to both the casing ID and annulus. Rig or third 6.
 - Well Control Plan
- control of the wellbore prior to cementing, if wellbore conditions do not The Drillers Method will be the primary well control method to regain permit the drillers method other methods of well control may be used
- Rig pumps or a 3rd party pump will be tied into the upper casing valve to pump down the casing ID :=
- A high pressure return line will be rigged up to lower casing valve and run to choke manifold to control annular pressure :≓
 - Once influx is circulated out of the hole, kill weight mud will be circulated <u>.</u>
 - Well will be confirmed static
- Once confirmed static, cap flange will be removed to allow for offline cementing operations to commence ۲.
 - Install offline cement tool ∞. *e*.
 - Rig up cement equipment

XTO Permian Operating, LLC Offline Cementing Variance Request



Wellhead diagram during offline cementing operations

- 10. Circulate bottoms up with cement truck
- a. If gas is present on bottoms up, well will be shut in and returns rerouted through gas buster to handle entrained gas
 - Max anticipated time before circulating with cement truck is 6 hrs
 - 11. Perform cement job taking returns from the annulus wellhead valve
 - 12. Confirm well is static and floats are holding after cement job
- 13. Remove cement equipment, offline cement tools and install night cap with pressure gauge for monitoring.

Subject: Request for a Variance Allowing break Testing of the Blowout Preventer Equipment (BOPE)

XTO Energy requests a variance to ONLY test broken pressure seals on the BOPE and function test BOP when skidding a drilling rig between multiple wells on a pad.

Background

test of the affected component. CFR Title 43 Part 3170 states, "Some situation may exist either on a wellby- well basis or field-wide basis whereby it is commonly accepted practice to vary a particular minimum Energy feels the break testing the BOPE is such a situation. Therefore, as per CFR Title 43 Part 3170, XTO Onshore Oil and Gas Order CFR Title 43 Part 3170, Drilling Operations, Sections III.A.2.i.iv.B states that interpretation of the Bureau of Land Management (BLM) requires a complete BOP test and not just a standard(s) established in this order. This situation can be resolved by requesting a variance...". XTO the BOP test must be performed whenever any seal subject to test pressure is broken. The current Energy submits this request for the variance.

Supporting Documentation

regulating BLM onshore drilling operations for over 30 years. During this time there have been significant was originally released. The XTO Energy drilling rig fleet has many modern upgrades that allow the intact changes in drilling technology. BLM continues to use the variance request process to allow for the use of stack components apart. These technologies have been used extensively offshore, and other regulators, incorporate quick connects facilitating release of the BOP from the wellhead without breaking any BOP modern technology and acceptable engineering practices that have arisen since CFR Title 43 Part 3170 CFR Title 43 Part 3170 became effective on December 19, 1988 and has remained the standard for BOP stack to be moved between well slots on a multi-well pad, as well as, wellhead designs that API, and many operators around the world have endorsed break testing as safe and reliable.



Figure 1: Winch System attached to BOP Stack



Figure 2: BOP Winch System

American Petroleum Institute (API) standards, specification and recommended practices are considered "A pressure test of the pressure containing component shall be performed following the disconnection 3170recognizes API recommended Practices (RP) 53 in its original development. API Standard 53, Well recognizes break testing as an acceptable practice. Specifically, API Standard 53, Section 5.3.7.1 states the industry standard and are consistently utilized and referenced by the industry. CFR Title 43 Part Control Equipment Systems for Drilling Wells (Fifth Edition, December 2018, Annex C, Table C.4) or repair, limited to the affected component." See Table C.4 below for reference.

| | 1 | Pressure Test- | Pressure Test—High Pressuread |
|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------|
| Component to be Pressure Tested | Pressure Test—Low Pressure ^{ac} psig (MPa) | Change Out of Component, Elastomer, or Ring Gasket | No Change Out of Component, Elastomer, or Ring Gasket |
| Annular preventer ⁶ | 250 to 350 (1.72 to 2.41) | RWP of annular preventer | MASP or 70% annular RWP, whichever is lower. |
| Fixed pipe, variable bore, blind, and BSR preventers ^{bd} | 250 to 350 (1.72 to 2.41) | RWP of ram preventer or wellhead system, whichever is lower | dII |
| Choke and kill line and BOP side outlet valves below ram preventers (both sides) | 250 to 350 (1.72 to 2.41) | RWP of side outlet valve or wellhead system, whichever is lower | ΠP |
| Choke manifold—upstream of chokes* | 250 to 350 (1.72 to 2.41) | RWP of ram preventers or wellhead system, whichever is lower | ШР |
| Choke manifold—downstream of chokes ^e | 250 to 350 (1.72 to 2.41) | RWP of valve(s), line(s), or MASP for the well program, whichever is lower | MASP for the well program, |
| Kelly, kelly valves, drill pipe safety valves, IBOPs | 250 to 350 (1.72 to 2.41) | MASP for the well program | |
| ³ Pressure test evaluation periods shall be a minimum of five minutes. No visible leaks. The pressure shall remain stable during the evaluation period. The pressure shall not decrease below the intended *Amnular(s) and VBR(s) shall be pressure tested on the largest and smallest OD drill pipe to be used in well program. | hall be a minimum of five minutes. during the evaluation period. The pissure tested on the largest and sma | ressure test evaluation periods shall be a minimum of five minutes. No visible leaks. The pressure shall remain stable during the evaluation period. The pressure shall not decrease below the intended test pressure. The pressure shall remain stable during the evaluation period. The pressure shall remain stable pressure tested on the largest and smallest OD drill pipe to be used in well program. | e intended test pressure. program. |
| For pad drilling operations, moving from one wellnead to another within the 21 days, pressure testing is required for pressure-containing and pressure-controlling connections when the integrity of a pressure seal is broken. | or pad drilling operations, moving from one wellhead to another within the 21 day pressure-controlling connections when the integrity of a pressure seal is broken. | the 21 days, pressure testing is recilis broken. | quired for pressure-containing |
| 6 For surface offshore operations, the ram BOPs shall be pressure tested with the ram locks engaged and the closing and locking pressure which during the initial test. For land operations, the ram BOPs shall be pressure tested with the ram locks engaged and the closing and vertex of the closing and | e ram BOPs shall be pressure test and operations, the ram BOPs sha | or surface offshore operations, the ram BOPs shall be pressure tested with the ram locks engaged and the closing and locking pressure wented during the initial fest. For land operations, the ram BOPs shall be pressure tested with the ram locks engaged and the closing and | the closing and locking press |

The Bureau of Safety and Environmental Enforcement (BSEE), Department of Interior, has also utilized the API standards, specification and best practices in the development of its offshore oil and gas regulations and incorporates them by reference within its regulations.

Break testing has been approved by the BLM in the past with other operators based on the detailed information provided in this document. XTO Energy feels break testing and our current procedures meet the intent of CFR Title 43 Part 317 Oand that of CFR Title 43 Part 3170 (Every 21 days). In addition to function testing the annular, pipe rams and often exceed it. There has been no evidence that break testing results in more components failing than seen on full BOP tests. XTO Energy's internal standards requires complete BOPE tests more often than blind rams after

each BOP nipple up, XTO Energy performs a choke drill with the rig crew prior to drilling out every casing shoe. This is additional training for the rig crew that exceeds the requirements of the CFR Title 43 Part

Procedures

- The summary below will be referenced in the APD or Sundry Notice and receive approval prior XTO Energy will use this document for our break testing plan for New Mexico Delaware basin. to implementing this variance ۲i
- XTO Energy will perform BOP break testing on multi-wells pads where multiple intermediate sections can be drilled and cased within the 21-day BOP test window. 5.
- . A full BOP test will be conducted on the first well on the pad.
- The first intermediate hole section drilled on the pad will be the deepest. All of the remaining hole sections will be the same depth or shallower.
- Our Lower WC targets set the intermediate casing shoe no deeper than the Wolfcamp B.
- Our Upper WC targets set the intermediate casing shoe shallower than the Wolfcamp B.

A Full BOP test will be required if the intermediate hole section being drilled has a MASP


A full BOP test will be required prior to drilling any production hole.

over 5M.

- After performing a complete BOP test on the first well, the intermediate hole section will be drilled and cased, two breaks would be made on the BOP equipment. 'n
 - Between the HCV valve and choke line connection
 -). Between the BOP quick connect and the wellhead
- The BOP is then lifted and removed from the wellhead by a hydraulic system. 4.
- After skidding to the next well, the BOP is moved to the wellhead by the same hydraulic system and installed. 5.
- The connections mentioned in 3a and 3b will then be reconnected. 6.
 - 7. Install test plug into the wellhead using test joint or drill pipe.
- A shell test is performed against the upper pipe rams testing the two breaks. œ.
- The shell test will consist of a 250 psi low test and a high test to the value submitted in the APD or Sundry (e.g. 5,000 psi or 10,000psi). 6
- Function test will be performed on the following components: lower pipe rams, blind rams, and annular. 10.

- 11. For a multi-well pad the same two breaks on the BOP would be made and on the next wells and steps 4 through 10 would be repeated.
- A second break test would only be done if the intermediate hole section being drilled could not be completed within the 21 day BOP test window. 12.

Note: Picture below highlights BOP components that will be tested during batch operations




Summary

drilling operation, moving from one wellhead to another within 21 days, pressure testing is required for wellhead to wellhead which is in compliance with API Standard 53. API Standard 53 states, that for pad A variance is requested to **ONLY** test broken pressure seals on the BOP equipment when moving from pressure-containing and pressure-controlling connections when the integrity of a pressure seal is broken.

The BOP will be secured by a hydraulic carrier or cradle. The BLM will be contacted if a Well Control event occurs prior to the commencement of a BOPE Break Testing operation. Based on discussions with the BLM on February 27th 2020 and the supporting documentation submitted to the BLM, we will request permission to ONLY retest broken pressure seals if the following conditions are met:

- After a full BOP test is conducted on the first well on the pad.
- 2. The first intermediate hole section drilled on the pad will be the deepest. All of the remaining hole sections will be the same depth or shallower.
- 3. Full BOP test will be required if the intermediate hole section being drilled has a MASP over 5M.
- 4. Full BOP test will be required prior to drilling the production hole.



XTO respectfully requests approval to utilize a spudder rig to pre-set surface casing.

- Description of Operations:
- following all of the applicable rules and regulations (OnShore Order 2, all COAs and After drilling the surface hole section, the spudder rig will run casing and cement NMOCD regulations).

Spudder rig will move in to drill the surface hole and pre-set surface casing on the well.

- Solids control will be handled entirely on a closed loop basis. No earth pits will be The spudder rig will utilize fresh water-based mud to drill the surface hole to TD. used. Þ.
- The wellhead will be installed and tested as soon as the surface casing is cut off and WOC time has been reached. $\ddot{\circ}$
- A blind flange at the same pressure rating as the wellhead will be installed to seal the wellbore. Pressure will be monitored with needle valves installed on two wing valves. က
- A means for intervention will be maintained while the drilling rig is not over the well.
- Spudder rig operations are expected to take 2-3 days per well on the pad. 4
- The BLM will be contacted and notified 24 hours prior to commencing spudder rig operations. 5
- Drilling Operations will begin with a larger rig and a BOP stack equal to or greater than the pressure rating that was permitted will be nippled up and tested on the wellhead before drilling operations resume on each well. 6
- The larger rig will move back onto the location within 90 days from the point at which the wells are secured and the spudder rig is moved off location.
- The BLM will be notified 24 hours before the larger rig moves back on the pre-set locations Þ.
- XTO will have supervision on the rig to ensure compliance with all BLM and NMOCD regulations and to oversee operations. ζ.
- Once the rig is removed, XTO will secure the wellhead area by placing a guard rail around the cellar area. œί



BLACK GOLD®

GATES ENGINEERING & SERVICES NORTH AMERICA

7603 Prairie Oak Dr. Houston, TX. 77086

PHONE: +1 (281) 602-4100

EMAIL: gesna.quality@gates.com +1 (281) 602-4147

www.gates.com/oilandgas WEB:

02-10-2024 HOSE CHOKE

OF CONFORMANCE CERTIFICATE

INSTAMED

MEW

Order referenced herein, and are in Conformance with applicable specifications, and that Records of hydrostatically tested at Gates Engineering & Services North America facilities in Houston, TX, This is to verify that the items detailed below meet the requirements of the Customer's Purchase Required Tests are on file and subject to examination. The following items were inspected and

NABORS DRILLING TECHNOLOGIES USA DBA NABORS DRILLING USA 15582803 (TAG NABORS PO #15582803 SN 74621 ASSET 66-1531) IMR RETEST SN 74621 ASSET #66-1531 CUSTOMER P.O.#: CUSTOMER P/N: CUSTOMER:

RETEST OF CUSTOMER 3" X 45 FT 16C CHOKE & KILL HOSE ASSEMBLY C/W 4 1/16" 10K FLANGES PART DESCRIPTION:

529480

SALES ORDER #: QUANTITY: 74621 H3-012524-1 SERIAL #:

SIGNATURE:

TITLE:

QUALITY ASSURANCE

DATE:

1/25/2024

Released to Imaging: 9/19/2025 3:18:06 PM

H3-15/16

1/25/2024 11:48:06 AM

| REP(| 1 | • |
|----------|----------|------------------------|
| TEST REP | | Nabors Industries Inc. |
| Jales | CUSTOMER | Company: |

| CUSTOMER | | | TEST OBJECT | |
|-------------------------|------------------------|--------------|----------------|------------------|
| Company: | Nabors Industries Inc. | istries Inc. | Serial number: | H3-012524-1 |
| | | | Lot number: | |
| Production description: | 74621/66-1531 | 531 | Description: | 74621/66-1531 |
| Sales order #: | 529480 | | | |
| Customer reference: | FG1213 | | Hose ID: | 3" 16C CK |
| | | | Part number: | |
| TEST INFORMATION | | | | |
| Test procedure: | GTS-04-053 | | Fitting 1: | 3.0 x 4-1/16 10K |
| Test pressure: | 15000.00 | psi | Part number; | |
| Test pressure hold: | 3600.00 | sec | Description: | |
| Work pressure: | 10000.00 | isd | | |
| Work pressure hold: | 900.00 | sec | Fitting 2: | 3.0 × 4-1/16 10K |
| Length difference: | 0.00 | % | Part number: | |
| Length difference: | 0.00 | inch | Description: | |
| | | | | |




Length measurement result:

Pressure test result:

Visual check:

feet

Length:



H3-15/16 1/25/2024 11:48:06 AM


| S-25-A-W 110D3PHO 2023-06-06 2024-06-06 S-25-A-W 110IQWDG 2023-05-16 2024-05-16 Comment | 110D3PHO 2023-06-06 110IQWDG 2023-05-16 | 110D3PHO 2023-06-06 110IQWDG 2023-05-16 | S-25-A-W S-25-A-W | 110D3PHO 110IQWDG | 2023-06-06 2023-05-16 | 2024-05-16 |
|-----------------------------------------------------------------------------------------|--------------------------------------------|--------------------------------------------|----------------------|----------------------|--------------------------|------------|
| 110lQWDG 2023-05-16 | 110lQWDG 2023-05-16 | 110lQWDG 2023-05-16 | S-25-A-W | 110lQWDG | 2023-05-16 | 2024-05-16 |
| Comment | Comment | Comment | | | | |
| | | | Comment | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Released to Imaging: 9/19/2025 3:18:06 PM

GAUGE TRACEABILITY



Released to Imaging: 9/19/2025 3:18:06 PM









Released to Imaging: 9/19/2025 3:18:06 PM

U.S. Department of the Interior BUREAU OF LAND MANAGEMENT

APD ID: 10400100853

Submission Date: 09/23/2024

Operator Name: XTO PERMIAN OPERATING LLC

Well Name: POKER LAKE UNIT 18-30 BD

Well Type: OIL WELL

Well Work Type: Drill Well Number: 201H

Show Final Text

Highlighted data reflects the most recent changes

SUPO Data Report

- Existing Roads Section 1

Will existing roads be used? YES

Existing Road Map:

POKER_LAKE_UNIT_18_30_BD_201H_EXISTING_ROAD_MAP_20250306132801.pdf

Existing Road Purpose: ACCESS

Row(s) Exist? NO

ROW ID(s)

≘

Do the existing roads need to be improved? NO

Existing Road Improvement Description:

Existing Road Improvement Attachment:

Section 2 - New or Reconstructed Access Roads

Will new roads be needed? NO

Section 3 - Location of Existing Wells

Existing Wells Map? YES

Existing Well map Attachment:

Operator Name: XTO PERMIAN OPERATING LLC

Well Name: POKER LAKE UNIT 18-30 BD

Well Number: 201H

18 30 BD_1Mile Radius_Map_20240905080544.pdf POKER_LAKE_UNIT_18_19

Location of Existing and/or Proposed Production Facilities Section 4

Submit or defer a Proposed Production Facilities plan? SUBMIT

facilities designed. The containment berms will be constructed of compacted 24 caliche, be sufficiently impervious, away from disturbance is needed. D. Disposal Facilities. Produced water will be hauled from location to a commercial or private disposal facility as needed. E. Flare. - Check in facility plot attached. F. Aboveground Structures. All permanent (on site six months or longer) aboveground structures constructed or installed on location and not subject to safety requirements will be painted earth-tone colors such as BLM Standard Environmental Color Chart (CC-001: June 2008) that reduce the visual impacts of **Production Facilities description:** A. Production Facilities. No New facility is required for the Poker Lake Unit 18-30/18-19 BD wells. Once drilled and completed, the wells will flow to the Poker Lake Unit 18-30/18-19 BD battery. B. Flowlines. No further flowlines disturbance is requested. C. Gas Pipeline. No Gas Sales line is required for this well. No additional surface cut or fill areas. H. Electrical. No additional electrical is required for this well. No additional surface disturbance is needed. I. the built environment. G. Containment Berms. Containment berms will be constructed completely around any production Facility Description-Kindly see the facility plot attached

Production Facilities map:

618.013003.03_XTO_PLU_18_BD_EXISTING_CVB_FINAL_10_04_2024_20250311091154.pdf

Section 5 - Location and Types of Water Supply

ater Source Table

Water source type: OTHER

Describe type: Raw produced water

Water source use type: INTERMEDIATE/PRODUCTION

CASING

Source latitude:

Source longitude:

Source datum:

City:

Water source permit type: PRIVATE CONTRACT

Water source transport method: PIPELINE

Source land ownership: COMMERCIAL

Source transportation land ownership: FEDERAL

Source volume (acre-feet): 70.89120298 Water source volume (barrels): 550000

Source volume (gal): 23100000

Operator Name: XTO PERMIAN OPERATING LLC

Well Name: POKER LAKE UNIT 18-30 BD

Well Number: 201H

Water source type: OTHER

Describe type: Fresh Water

Water source use type: DUST CONTROL

SURFACE CASING

STIMULATION

Source longitude: Source latitude:

Source datum:

City:

Water source permit type: PRIVATE CONTRACT

Water source transport method: TRUCKING

Source land ownership: COMMERCIAL

Source transportation land ownership: FEDERAL

Source volume (acre-feet): 70.89120298 Water source volume (barrels): 550000

Source volume (gal): 23100000

Water source type: RECYCLED

INTERMEDIATE/PRODUCTION Water source use type:

CASING

Source longitude:

Source latitude:

Source datum:

City:

Water source permit type: PRIVATE CONTRACT

Water source transport method: PIPELINE

Source land ownership: COMMERCIAL

Source transportation land ownership: FEDERAL

Source volume (acre-feet): 70.89120298 Water source volume (barrels): 550000

Water source and transportation

POKER_LAKE_UNIT_18_30_BD_201H_VICINITY_MAP_20250306132910.pdf

Program. Water composition depends on the mud type needed per formation to protect useable water. Fresh water is trucked to location for use in surface casing drilling and cementing. All other water is either brackish or raw produced water that is all piped from either a pipeline or a pond (32.1483028, -103.922338) to the drilling location. Anticipated water usage for drilling includes an estimated 50,000 barrels of water to drill a horizontal well in a combination of fresh water and brine as detailed in Page 3 of 12 Water source comments: The well will be drilled using a combination of water mud systems as outlined in the Drilling the mud program in

Page 4 of 12

Operator Name: XTO PERMIAN OPERATING LLC

Well Name: POKER LAKE UNIT 18-30 BD

Well Number: 201H

and completion schedules. Well completion is expected to require approximately 550,000 barrels of water per horizontal well. length of horizontal sections, and the losses that may occur during the operation. Temporary water lines will be permitted via a Temporary Water Line Approved Decision letter and/or any necessary Right of Way Grants as needed based on drilling circulation or wash out that may occur. Actual water volumes used during operations will depend on the depth of the well, the drilling plans. These volumes are calculated for ∼1.5bbls per foot of hole drilled with excess to accommodate any lost Actual water volumes used during operations will depend on the depth of the well and length of horizontal sections

New water well? N

New Water Well Info

Well datum: Well Longitude: Well latitude:

Well target aquifer:

Est thickness of aquifer: Est. depth to top of aquifer(ft):

Aquifer comments:

Aquifer documentation:

Well casing type: Well depth (ft):

Well casing inside diameter (in.): Well casing outside diameter (in.):

casing source: **Used** New water well casing?

Drill material:

Drilling method:

Casing top depth (ft.):

Casing length (ft.):

Grout material:

Grout depth:

Completion Method: Well Production type:

Water well additional information:

State appropriation permit:

Additional information attachment:

Section 6 - Construction Materials

Using any construction materials: YES

Construction Materials description: Caliche Pit Location: 32.128730, -103.906308

Construction Materials source location

Section 7 - Methods for Handling

Waste type: SEWAGE

drilling and completion activities, or as required, the toilet holding tanks will be pumped and the contents there of disposed of in an approved sewage disposal facility. All state and local laws and regulations pertaining to the disposal of human and solid waste will be complied with. This equipment will be properly maintained during the drilling and completion operations and will Waste content description: Portable, self-contained toilets will be provided for human waste disposal. Upon completion of be removed when all operations are complete.

gallons Amount of waste: 250

Waste disposal frequency : Weekly

Page 5 of 12

Operator Name: XTO PERMIAN OPERATING LLC

Well Name: POKER LAKE UNIT 18-30 BD

Well Number: 201H

of drilling and completion activities, or as required, the toilet holding tanks will be pumped and the contents there of disposed **Safe containment description:** Portable, self-contained toilets will be provided for human waste disposal. Upon completion of in an approved sewage disposal facility. All state and local laws and regulations pertaining to the disposal of human and solid waste will be complied with. This equipment will be properly maintained during the drilling and completion operations and will be removed when all operations are complete.

Safe containmant attachment:

Disposal location ownership: COMMERCIAL Waste disposal type: HAUL TO COMMERCIAL

Disposal type description:

Disposal location description: A licensed 3rd party contractor to haul and dispose of human waste.

Waste type: DRILLING

Waste content description: CUTTINGS

Amount of waste: 2100

Waste disposal frequency: One Time Only

Drill cuttings will be held in roll-off Safe containment description: The well will be drilled utilizing a closed-loop mud system. Drill cuttings veryle mud boxes and taken to a New Mexico Oil Conservation Division (NMOCD) approved disposal site.

Safe containmant attachment:

Disposal location ownership: COMMERCIAL Waste disposal type: HAUL TO COMMERCIAL

Disposal type description:

Disposal location description: R360 Environmental Solutions 4507 W Carlsbad Hwy, Hobbs, NM 88240

Waste type: DRILLING

Waste content description: FLUID

barrels Amount of waste: 500

Waste disposal frequency: One Time Only

Safe containment description: Steel mud boxes

Safe containmant attachment:

Disposal location ownership: COMMERCIAL Waste disposal type: HAUL TO COMMERCIAL

Disposal type description:

Disposal location description: R360 Environmental Solutions 4507 W Carlsbad Hwy, Hobbs, NM 88240

Waste type: GARBAGE

Immediately after drilling all debris and other waste materials on and around the well location not contained in the trash cage cleaned up and removed from the location. No potentially adverse materials or substances will be left on the location. portable dumpster or trash cage, to prevent scattering and will be removed and deposited in an approve sanitary landfill **Waste content description:** All garbage, junk and non-flammable waste materials will be contained in a self-contained

spunod Amount of waste: 250

Waste disposal frequency : Weekly

Well Name: POKER LAKE UNIT 18-30 BD

Well Number: 201H

Immediately after drilling all debris and other waste materials on and around the well location not contained in the trash cage will be cleaned up and removed from the location. No potentially adverse materials or substances will be left on the location. **Safe containment description:** All garbage, junk and non-flammable waste materials will be contained in a self-contained, portable dumpster or trash cage, to prevent scattering and will be removed and deposited in an approve sanitary landfill.

Safe containmant attachment:

Disposal location ownership: COMMERCIAL Waste disposal type: HAUL TO COMMERCIAL

FACILITY

Disposal type description:

Disposal location description: A licensed 3rd party contractor will be used to haul and dispose of garbage.

Reserve Pit

Reserve Pit being used? NO

Temporary disposal of produced water into reserve pit? NO

Reserve pit length (ft.)

Reserve pit width (ft.)

Reserve pit depth (ft.)

Reserve pit volume (cu. yd.)

Is at least 50% of the reserve pit in cut?

Reserve pit liner

Reserve pit liner specifications and installation description

Cuttings Area

Cuttings Area being used? NO

Are you storing cuttings on location? extstyle Y

Produced Fluids. Water produced from the well will be held temporarily in steel tanks and then taken to a NMOCD approved Drilling Fluids. These will be contained in steel mud pits and then taken to a NMOCD approved commercial disposal facility. Description of cuttings location Cuttings. The well will be drilled utilizing a closed-loop mud system. Drill cuttings will be held in roll-off style mud boxes and taken to a New Mexico Oil Conservation Division (NMOCD) approved disposal site. commercial disposal facility. Oil produced during operations will be stored in s until sold

Cuttings area length (ft.)

Cuttings area width (ft.)

Cuttings area volume (cu. yd.) Cuttings area depth (ft.)

Is at least 50% of the cuttings area in cut?

Cuttings area liner

Cuttings area liner specifications and installation description

Well Name: POKER LAKE UNIT 18-30 BD

Well Number: 201H

- Ancillary Section 8

Are you requesting any Ancillary Facilities?: N

Ancillary Facilities

Comments:

- Well Site တ Section

Well Site Layout Diagram:

POKER_LAKE_UNIT_18_30_BD_201H_WELL_SITE_PLAT_20250306133104.pdf

201H RL 20250307105453.pdf POKER_LAKE_UNIT_18_30_BD_

Comments: Multi-well Pad.

Plans for Surface Section 10

Multiple Well Pad Name: POKER LAKE UNIT 18-19 18-30 BD Type of disturbance: No New Surface Disturbance

Multiple Well Pad Number: A

Recontouring

18_30_BD_PAD_A_INTERIM_RECLAMATION_FINAL_UPDATED_20250417124519.pdf 18_19 Drainage/Erosion control construction: Initial seedbed preparation will consist of recontouring to the appropriate interim or final reclamation standard. All compacted areas to be seeded will be ripped to a minimum depth of 18 inches with a minimum furrow spacing of 2 feet, followed by recontouring the surface and then evenly spreading the stockpiled topsoil. Prior to seeding, the seedbed will be scarified to a depth of no less than 4-6 inches.

Drainage/Erosion control reclamation: Erosion features are equal to or less than surrounding area and erosion control is sufficient so that water naturally infiltrates into the soil and gullying, head cutting, slumping, and deep or excessive rills (greater than 3 inches) are not observed.

Road long term disturbance (acres): 0 Well pad interim reclamation (acres): 0 Well pad long term disturbance Well pad proposed disturbance

Road interim reclamation (acres): 0 Road proposed disturbance (acres):

Powerline proposed disturbance

Pipeline proposed disturbance

Powerline long term disturbance Pipeline long term disturbance (acres): 0 Powerline interim reclamation (acres): Pipeline interim reclamation (acres): 0 0

(acres): 0 Other interim reclamation (acres): 0 acres):

Other long term disturbance (acres): 0 Other proposed disturbance (acres):

Total long term disturbance: 0 Total interim reclamation: 0 Total proposed disturbance: 0

Disturbance Comments:

landform will be restored for all disturbed areas including well pads, production facilities, roads, pipelines, and utility corridors Reconstruction method: The original stock piled topsoil will be spread over the areas being reclaimed and the original as close as possible to the original topography. The location will then be ripped and seeded.

Page 8 of 12

Operator Name: XTO PERMIAN OPERATING LLC

Well Name: POKER LAKE UNIT 18-30 BD

Well Number: 201H

landform will be restored for all disturbed areas including well pads, production facilities, roads, pipelines, and utility corridors **Fopsoil redistribution:** The original stock piled topsoil will be spread over the areas being reclaimed and the original as close as possible to the original topography. The location will then be ripped and seeded.

Soil treatment: A self-sustaining, vigorous, diverse, native (or otherwise approved) plant community will be established on the site with a density sufficient to control erosion and invasion by non-native plants and to re-establish wildlife habitat or forage production. At a minimum, the established plant community will consist of species included in the seed mix and/or

are found on alluvial fans and floodplains and form in mixed alluvium. The Simona Bippus soils are dominant to the east and Vegetation at the well pad: Soils are classified as Simona Gravelly Fine Sandy Loam and Simona-Bippus Simona soils are found on alluvial fans and plans and form in mixed alluvium and/or Aeolian sands. Bippus soils the Simona Gravelly Fine Sandy Loams are dominant to the West. Dominant vegetation species include mesquite, sumac snakeweed, and various forbs and grasses. Ground cover is minimal, offering 90 percent visibility. Existing Vegetation at the well pad: Soils are classified as Simona Gravelly desirable species occurring in the surrounding natural vegetation.

Existing Vegetation at the well pad

Existing Vegetation Community at the road: Soils are classified as Simona Gravelly Fine Sandy Loam and Simona-Bippus are found on alluvial fans and floodplains and form in mixed alluvium. The Simona Bippus soils are dominant to the east and Simona soils are found on alluvial fans and plans and form in mixed alluvium and/or Aeolian sands. Bippus soils the Simona Gravelly Fine Sandy Loams are dominant to the West. Dominant vegetation species include mesquite, sumac snakeweed, and various forbs and grasses. Ground cover is minimal, offering 90 percent visibility. Complex.

Existing Vegetation Community at the road

Bippus Complex. Simona soils are found on alluvial fans and plans and form in mixed alluvium and/or Aeolian sands. Bippus soils are found on alluvial fans and floodplains and form in mixed alluvium. The Simona Bippus soils are dominant to the east **Existing Vegetation Community at the pipeline**: Soils are classified as Simona Gravelly Fine Sandy Loam and Simonaand the Simona Gravelly Fine Sandy Loams are dominant to the West. Dominant vegetation species include mesquite, sumac snakeweed, and various forbs and grasses. Ground cover is minimal, offering 90 percent visibility.

Existing Vegetation Community at the pipeline

Simona-Bippus Complex. Simona soils are found on alluvial fans and plans and form in mixed alluvium and/or Aeolian sands. Bippus soils are found on alluvial fans and floodplains and form in mixed alluvium. The Simona Bippus soils are dominant to Existing Vegetation Community at other disturbances: Soils are classified as Simona Gravelly Fine Sandy Loam and the east and the Simona Gravelly Fine Sandy Loams are dominant to the West. Dominant vegetation species include mesquite, sumac snakeweed, and various forbs and grasses. Ground cover is minimal, offering 90 percent visibility.

Existing Vegetation Community at other disturbances

Non native seed used? N

Non native seed description:

Seedling transplant description:

Will seedlings be transplanted for this project? N

Seedling transplant description attachment:

Will seed be harvested for use in site reclamation? N

Seed harvest description:

Seed harvest description attachment:

Page 9 of 12

Operator Name: XTO PERMIAN OPERATING LLC

Well Name: POKER LAKE UNIT 18-30 BD

Well Number: 201H

Seed

Seed Table

Seed Summary

Total pounds/Acre:

Pounds/Acre

Seed Type

Seed reclamation

Last Name: Hankins Operator Contact/Responsible Official First Name: Bobby

Phone: (970)629-5213

standard. All compacted areas to be seeded will be ripped to a minimum depth of 18 inches with a minimum furrow spacing of 2 feet, followed by recontouring the surface and then evenly spreading the stockpiled topsoil. Prior to seeding, the seedbed will be scarified to a depth of no less than 4-6 inches. If the site is to be broadcast seeded, the surface will be left Seedbed prep: Initial seedbed preparation will consist of recontouring to the appropriate interim or final reclamation

Email: bobby.hankins@exxonmobil.com

Seed BMP: If broadcast seeding is to be used and is delayed, final seedbed preparation will consist of contour cultivating to a depth of 4-6 inches within 24 hours prior to seeding, dozer tracking, or other imprinting to break the soil crust and create seed germination micro-sites.

rough enough to trap seed and snow, control erosion, and increase water infiltration.

Seed method: Seeding will be conducted no more than two weeks following completion of final seedbed preparation. A certified weed-free seed mix designed by the BLM to meet reclamation standards will be used.

Existing invasive species? N

Existing invasive species treatment description:

Existing invasive species treatment

Weed treatment plan description: Weed control for all phases will be through the use of approved pesticides and herbicides according to applicable State, Federal and local laws

Weed treatment plan

additional methods are required to monitor invasive and noxious weeds, appropriate BLM authorities will be contacted with Monitoring plan description: Monitoring of invasive and noxious weeds will be visual and as-needed. If it is determined a plan of action for approval prior to implementation. Weed treatment plan

Monitoring plan

Success standards: 100% compliance with applicable regulations.

Pit closure description: There will be no reserve pit as each well will be drilled utilizing a closed loop mud system. The closed loop system will meet the NMOCD requirements 19.15.17.

- Surface Section

Well Name: POKER LAKE UNIT 18-30 BD

Well Number: 201H

Disturbance type: EXISTING ACCESS ROAD

Describe:

Surface Owner: BUREAU OF LAND MANAGEMENT

Other surface owner description:

BIA Local Office:

BOR Local Office:

COE Local Office:

DOD Local Office:

State Local Office:

NPS Local Office:

Military Local Office:

USFWS Local Office:

Other Local Office: USFS Region: **USFS Forest/Grassland:**

USFS Ranger District:

Disturbance type: WELL PAD

Describe:

Surface Owner: BUREAU OF LAND MANAGEMENT

Other surface owner description:

BIA Local Office:

BOR Local Office:

COE Local Office:

DOD Local Office:

NPS Local Office:

State Local Office:

Military Local Office:

USFWS Local Office:

Other Local Office:

USFS Region:

USFS Forest/Grassland:

USFS Ranger District:

Page 11 of 12

Operator Name: XTO PERMIAN OPERATING LLC

Well Name: POKER LAKE UNIT 18-30 BD

Well Number: 201H

Disturbance type: TRANSMISSION LINE Describe:

Surface Owner: BUREAU OF LAND MANAGEMENT

Other surface owner description:

BIA Local Office:

BOR Local Office:

COE Local Office:

DOD Local Office:

NPS Local Office:

State Local Office:

Military Local Office:

USFWS Local Office: Other Local Office:

USFS Region:

USFS Forest/Grassland:

USFS Ranger District:

Disturbance type: OTHER

Describe: Flowline

Surface Owner: BUREAU OF LAND MANAGEMENT

Other surface owner description:

BIA Local Office:

BOR Local Office:

COE Local Office:

DOD Local Office:

NPS Local Office: State Local Office:

Military Local Office: USFWS Local Office:

Other Local Office:

USFS Region:

USFS Forest/Grassland:

USFS Ranger District:

Well Name: POKER LAKE UNIT 18-30 BD

Well Number: 201H

Section 12 - Other

Right of Way needed? N

Use APD as ROW?

ROW Type(s):

ROW

SUPO Additional Information: SUPO written for all wells in section/project area.


Use a previously conducted onsite? \forall

Previous Onsite information: The XTO Permian Operating, LLC. representatives and BLM NRS were on location for onsite on 2/15/22.

Other SUPO

PLU_18_19__18_30_BD_SUPO_20250312032757.pdf

Page 12 of 12



DRIVING DIRECTIONS TO LOCATION

FROM THE INTERSECTION OF HIGHWAY 285 AND LONGHORN ROAD, GO NORTHEAST ON LONGHORN ROAD FOR APPROX. 4.2 MILES. TURN LEFT (NORTHEAST) ON PIPELINE ROAD NUMBER 1 AND GO APPROX. 7.0 MILES. TURN LEFT (NORTH) ON LEASE ROAD AND GO APPROX. 0.9 MILES. TURN LEFT (WEST) ON LEASE ROAD AND GO APPROX. 0.5 MILES. TURN LEFT (SOUTH) ON LEASE ROAD AND GO APPROX. 0.2 MILES. TURN LEFT (SOUTH) ON LEASE ROAD AND GO APPROX. 0.2 MILES. TURN LET (CAST) ON LEASE ROAD AND GO APPROX. 0.1 MILES ARRIVING AT THE LOCATION TO THE NORTH.

A TOPOGRAPHICAL AND ACCESS ROAD MAP FOR XTO ENERGY, INC. POKER LAKE UNIT 18-30 BD 201H

•

O

CONSULTING

POKER LAKE UNIT 18-30 BD 201H WELL LOCATION

EXISTING WELL PAD DRIVING ROUTE


LEGEND


LOCATED 265 FEET FROM THE NORTH LINE AND 2365 FEET FROM THE EAST LINE OF SECTION


| 18, TOWNSHII | 18, TOWNSHIP 25 SOUTH, RANGE 30 EAST, N.M.P.M. EDDY COUNTY, NEW MEXICO | ST, N.M.P.M. EDDY COUNTY, | NEW MEXICO |
|---------------------|------------------------------------------------------------------------|---------------------------|----------------------------------|
| снескер ву: | DATE: 6/28/2024 | SCALE: 1":5,000' | PROJECT NUMBER: 618.013003.32-10 |
| DRAWN BY: BE | FIELD CREW: | REVISION NUMBER: | SHEET: 3 OE 3 |

| com and Eng) | СНЕСКЕD ВҮ: AI | DATE: 6/28/2024 | SCALE: 1":5,000' | PROJECT NUMBE 618.013 (|
|--------------------|-----------------------|-----------------|-----------------------------------|-----------------------------------|
| VED | DRAWN BY: RE | FIELD CREW: RD | REVISION NUMBER: $oldoynom{0}{0}$ | SHEET: 3 (|
| | | | | |

Poker Lake Unit 18-19/18-30 BD







POKER LAKE UNIT 18-30 BD 201H WELL LOCATION

EXISTING WELL PAD

DRIVING ROUTE

LEGEND


A VICINITY MAP FOR XTO ENERGY, INC. POKER LAKE UNIT 18-30 BD 201H


LOCATED 265 FEET FROM THE NORTH LINE AND 2365 FEET FROM THE EAST LINE OF SECTION

| 18, TOWNSHIP | 18, TOWNSHIP 25 SOUTH, RANGE 30 EAST, N.M.P.M. EDDY COUNTY, NEW MEXICO | ST, N.M.P.M. EDDY COUNTY, | , NEW MEXICO |
|--------------|------------------------------------------------------------------------|---------------------------|------------------|
| CHECKEU BY: | 6/28/2024 | 3CALE: 1":10,000' | 618.013003.32-10 |
| DRAWN BY: | FIELD CREW: | REVISION NUMBER: | SHEET: |


| CONSULTING | 505 Pecan Street, Suite 201, Fort Worth, TX 76102 Ph: 972.972.4550, manhard.com Texas Board of Professional Engineers & Land Surveyors Reg. No. F-10194754 (Surv), F-22053 (Engl |
|------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|

© 2024 MANHARD CONSULTING, ALL RIGHTS RESERVED





I,MARK DILLON HARP, NEW MEXICO PROFESSIONAL SURVEYOR NO. 23766, DO HEREBY CERTIFY THAT THIS SURVEY PLAT AND THE ACTUAL SURVEY ON THE GROUND UPON WHICH IT IS BASED WERE PREFORMED BY ME OR UNDER MY DIRECT SUPERVISION; THAT I AM RESPONSIBLE FOR THIS SURVEY. THAT THIS SURVEY NEW MESTS THE MINIMUM STANDARDS FOR SURVEYING IN NEW MEXICO, AND THAT IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIFF.



PERMITTED PLU 18-30 BD WELL LOCATION PERMITTED PLU 18-19 BD WELL LOCATION **EXISTING WELL PAD** SECTION LINE

TBD WELL LOCATION **EXISTING ROAD**

EXISTING OVERHEAD ELECTRIC

MARK DILLON HARP NEW MEXICO PROFESSIONAL LAND SURVEYOR NO. 23786




505 Pecan Street, Suite 201, Fort Worth, TX 76102 ph:817.865.5344 manhard.com Texas Board of Professional Engineers & Land Surveyors Reg. No. F-10194754 (Surv), F-22053 (Eng) ©2024 MANHARD CONSULTING, ALL RIGHTS RESERVED

A WELL SITE PLAN FOR XTO PERMIAN OPERATING, LLC POKER LAKE UNIT 18-19/18-30 BD EXISTING PAD A

POKER LAKE UNIT 18-30 BD 201H IS LOCATED 265 FEET FROM THE NORTH LINE AND 2,365 FEET FROM THE EAST LINE OF SECTION 18, TOWNSHIP 25 SOUTH, RANGE 30 EAST, N.M.P.M. EDDY COUNTY, NEW MEXICO

| CHECKED BY: | DATE: | SCALE: | PROJECT NO.: |
|-------------|-------------|---------------|------------------|
| DB | 09/06/2024 | 1" = 200 | 618 013003 32-10 |
| DRAWN BY: | FIELD CREW: | REVISION NO.: | SHEET: |
| Ā | as. | 4 | 1 OF 3 |



GENERAL NOTES

200 ft. FEET)

Z 1 inch

200

100

EDDY/DWG/To-Client/PAD A INTERIM REC.dwg

- BEARINGS AND COORDINATES SHOWN HEREON ARE MERCATOR GRID AND CONFORM TO THE NEW MEXICO COORDINATES SYSTEM "NEW MEXICO EAST ZONE" NORTH AMERICAN DATUM 1983.
- LATITUDE AND LONGITUDE VALUES SHOWN HEREON ARE RELATIVE TO THE NORTH AMERICAN DATA (NAD83). ۲,

ROYAVEVOR WEX/00 W07710 PROFESS I.MARK DILLON HARP, NEW MEXICO PROFESSIONAL
SURVEYOR NO. 23786. DO HERBY CERTIFY THAT THIS
SURVEY PLATAND THE ACTUAL SURVEY ON THE
GROUND UPON WHICH IT IS BASED WERE PREFORMED
BY ME OR UNDER MY DIRECT SUPERVISION; THAT I AM
RESPONSIBLE FOR THIS SURVEY, THAT THIS SURVEY
MEETS THE MINIMUM STANDARDS FOR SURVEYING IN
NEW MEXICO, AND THAT IS TRUE AND CORRECT TO THE
BEST OF MY KNOWLEDGE AND #ELIJEF.

P:\618.013 XTO Energy - NM\003 Poker Lake Unit\.32 - PLU 18-19,18-30 BD-

ACREAGE INFORMATION
INITIAL CONSTRUCTED DISTURBED AREA
INTERIM RECLAMATION

= 11.486 ACRES = 1.810 ACRES

TOWNSHIP 25 SOUTH,

RANGE 30 EAST

NMPM

9.676 ACRE OTAL PAD ACREAGE AFTER IR

LEGEND

SECTION LINE

PERMITTED WELL LOCATION PLU 18-30 BD TBD WELL LOCATION **EXISTING ROAD EXISTING PAD**

PERMITTED WELL LOCATION PLU 18-19 BD INTERIM RECLAMATION AREA

AN INTERIM RECLAMATION DIAGRAM FOR

POKER LAKE UNIT 18-19/18-30 BD EXISTING PAD "A" XTO PERMIAN OPERATING, LLC.

PAD CENTER IS LOCATED 290 FEET FROM THE NORTH LINE AND 2,105 FEET FROM THE EAST LINE OF SECTION 18, TOWNSHIP 25 SOUTH, RANGE 30 EAST, N.M.P.M. EDDY COUNTY, NEW MEXICO

505 Pecan Street, Suite 201, Fort Worth, TX 76102 ph:817.865.5344 manhard.com Texas Board of Professional Engineers & Land Surveyors Reg. No. F-10194754 (Surv), F-22053 (Eng)

0

TINS X

MARK DILLON HARP NEW MEXICO PROFESSIONAL LAND SURVEYOR NO. 23786

©2025 MANHARD CONSULTING, ALL RIGHTS RESERVED

| CHECKED BY: | DATE: | SCALE: | PROJECT NO.: |
|-------------|-------------|---------------|--------------|
| DB | 4/14/2025 | 1" = 200' | 618 013003 |
| DRAWN BY: | FIELD CREW: | REVISION NO.: | SHEET: |
| _ | 00 | c | - 10 - |

32

Well Site Locations

The results of the Poker Lake Unit 18-30/18-19 BD Development Program will develop economic quantities of oil and gas in the Poker Lake Unit 18-30/18-19 BD with multiple primary formations targeted. Well locations are determined based on cross-section variations and details. Locations will be selected to minimize the likelihood of encountering faults and/or drilling hazards while still targeting suitably productive zones. If drilling results in an unproductive well, the well will be plugged and abandoned as soon as practical after the conclusion of production testing. Productive wells may be shut-in temporarily for BLM authorization for production activities and facilities

| NAME | N/S FOOTAGE CALL | N/S LINE | E/W FOOTAGE CALL | EW LINE |
|----------------------------------|---------------------|-------------|---------------------|------------|
| POKER LAKE UNIT 18-30 BD 200H | 265 | FNL | 2,395 | FEL |
| POKER LAKE UNIT 18-30 BD 201H | 265 | JNH L | 2,365 | FEL |
| POKER LAKE UNIT 18-30 BD 202H | 265 | FNL | 2,335 | FEL |
| POKER LAKE UNIT 18-30 BD 203H | 265 | FNL | 2,305 | FEL |
| POKER LAKE UNIT 18-19 BD 204H | 265 | FNL | 2,275 | FEL |
| POKER LAKE UNIT 18-19 BD 205H | 265 | FNL | 1,935 | FEL |
| POKER LAKE UNIT 18-19 BD 206H | 265 | FNL | 1,905 | FEL |
| POKER LAKE UNIT 18-19 BD 207H | 265 | FNL | 1,875 | FEL |
| POKER LAKE UNIT 18-19 BD 208H | 265 | FNL | 1,845 | FEL |
| POKER LAKE UNIT 18-19 BD 209H | 265 | A N H | 1,815 | Æ |


Surface Use Plan

.. Existing Roads

- A. FROM THE INTERSECTION OF HIGHWAY 285 AND LONGHORN ROAD, GO NORTHEAST ON LONGHORN ROAD ROAD FOR APPROX. 4.2 MILES. TURN LEFT (NORTHEAST) ON PIPELINE ROAD NUMBER 1 AND GO APPROX. 7.0 MILES. TURN LEFT (NORTH) ON LEASE ROAD AND GO APPROX. 0.9 MILES. TURN LEFT (WEST) ON LEASE ROAD AND GO APPROX. 0.5 MILES. TURN LEFT (SOUTH) ON LEASE ROAD AND GO APPROX. 0.2 MILES. TURN LEFT (EAST) ON LEASE ROAD AND GO APPROX. 0.1 MILES ARRIVING AT THE LOCATION TO THE NORTH.
 - . Transportation maps identifying existing roads that will be used to access the project area are included from Manhard. marked as, 'Topographical and Access Road Map'.
- Transportation Plan identifying existing roads that will be used to access the project area is included from Manhard. marked as, Topographical and Access Road Map. All equipment and vehicles will Manhard. Maintenance of the access roads will continue until abandonment and reclamation of as provided Access Map be confined to the routes shown on the Topographical and the well pads is completed. ä

New or Upgraded Access Roads ۲i

- **New Roads**. There are no new roads necessary to access the Poker Lake Unit 18-30/18-19 BD ocation.
- The well pads selected for development will determine which existing roads will be Well Pads. œ.
- truck. The Central Battery will require one lease operator truck to continually travel to each well site Additional traffic will include one maintenance truck periodically throughout the year for pad upkeep **Anticipated Traffic**. After well completion, travel to each well site will include one lease operator to monitor the working order of the wells and to check well equipment for proper operation. and weed removal. Well service trips will include only the traffic necessary to work on the wells or provide chemical treatments periodically and as needed throughout the year. ن
- Routing. All equipment and vehicles will be confined to the travel routes laid out in the vicinity map by Manhard unless otherwise approved by the BLM and applied for by PERMIAN OPERATING LLC provided ä
- Road Dimensions. The maximum width of the driving surface of new roads will be 14 feet. The roads will be crowned and ditched with a 2% slope from the tip of the crown to the edge of the driving surface. The ditches will be 1 foot deep with 3:1 slope. The driving surface will be made of 8" rolled and compacted caliche. نس



Level Ground Section

- Surface Material. Surface material will be native caliche. The average grade of all roads will be approximately 3%. ٠.
- Fences: No. ェ
- Cattle Guards: No. <u>-</u>:
 - Turnouts: No. ᅶ
 - Culverts: No.
- Cuts and Fills: look at attached plats.
- prior to any further construction activity. The topsoil that was stripped will be spread along the edge Topsoil. Approximately 6 inches of topsoil (root zone) will be stripped from the existing access road of the road and within the ditch. The topsoil will be seeded with the proper seed mix designated by
- and accommodate all-weather traffic. The road will be crowned and ditched with water turnouts **Maintenance**. The access road will be constructed and maintained as necessary to prevent soil erosion installed as necessary to provide for proper drainage along with access road route. ż
- Drainage. The access road and associated drainage structures will be constructed and maintained in accordance with road guidelines contained in the joint BLM/USFS publication: Surface Operating Standards for Oil and Gas Exploration and Development, The Gold Book, Fourth Edition and/or BLM 9113 concerning road construction standards on projects subject to federal Manual Section jurisdiction. o.

Location of Existing Wells m.

See attached 1-mile radius well map.

4. Location of Existing Production Facilities

- Once drilled and completed, the wells will flow to the Poker Lake Unit 18-30/18-19 BD battery. Production Facilities. No New facility is required for the Poker Lake Unit 18-30/18-19 BD wells.
- B. Flowlines. No further flowlines disturbance is requested.
- Gas Pipeline. No Gas Sales line is required for this well. No additional surface disturbance is needed. ن
- **Disposal Facilities**. Produced water will be hauled from location to a commercial or private disposal facility as needed. \Box
- E. Flare. Check in facility plot attached.
- Aboveground Structures. All permanent (on site six months or longer) aboveground structures constructed or installed on location and not subject to safety requirements will be painted earth-tone colors such as BLM Standard Environmental Color Chart (CC-001: June 2008) that reduce the visual mpacts of the built environment. ц
- Containment Berms. Containment berms will be constructed completely around any production acilities designed. The containment berms will be constructed of compacted 24" sufficiently impervious, away from cut or fill areas. G.
- Electrical. No additional electrical is required for this well. No additional surface disturbance is ェ
- Facility Description- Kindly see the facility plot attached.

5. Location and Types of Water Supply

Water composition depends on the mud type needed per formation to protect useable water. Fresh water is The well will be drilled using a combination of water mud systems as outlined in the Drilling Program. trucked to location for use in surface casing drilling and cementing. All other water is either brackish or raw produced water that is all piped from either a pipeline or a pond (32.1483028, -103.922338) to the drilling Anticipated water usage for drilling includes an estimated 50,000 barrels of water to drill a horizontal well in a combination of fresh water and brine as detailed in the mud program in the drilling plans. These volumes are calculated for ~1.5bbls per foot of hole drilled with excess to accommodate any lost circulation or wash out that may occur. Actual water volumes used during operations will depend on the depth of the well, length of horizontal sections, and the losses that may occur during the operation.

approximately 550,000 barrels of water per horizontal well. Actual water volumes used during operations will Temporary water lines will be permitted via a Temporary Water Line Approved Decision letter and/or any necessary Right of Way Grants as needed based on drilling and completion schedules. Well completion is expected to require depend on the depth of the well and length of horizontal sections

6. Construction Activities - NO NEW Construction

Construction, reclamation, and/or routine maintenance will not be conducted during periods when the soil conditions for construction could lead to impacts to the surrounding environment, or when watershed damage is likely to occur because of these activities. Any construction material that may be required for surfacing of the drill pad and access road will be from a contractor having a permitted source of materials within the general area. No construction materials will be removed from federal lands without prior approval from the appropriate surface management agency.

Well Pad. No New construction

Caliche Pit Location: 32.128730, -103.906308

7. Methods for Handling Waste

- Cuttings. The well will be drilled utilizing a closed-loop mud system. Drill cuttings will be held in roll-off style mud boxes and taken to a New Mexico Oil Conservation Division (NMOCD) approved disposal site.
 - **Drilling Fluids**. These will be contained in steel mud pits and then taken to a NMOCD approved commercial disposal facility.
- Produced Fluids. Water produced from the well will be held temporarily in steel tanks and then taken to a NMOCD approved commercial disposal facility. Oil produced during operations will be stored in s until
- Sewage. Portable, self-contained toilets will be provided for human waste disposal. Upon completion of drilling and completion activities, or as required, the toilet holding tanks will be pumped and the contents thereof disposed of in an approved sewage disposal facility. All state and local laws and regulations pertaining to the disposal of human and solid waste will be complied with. This equipment will be properly maintained during the drilling and completion operations and will be removed when all operations are
- and deposited in an approve sanitary landfill. Immediately after drilling all debris and other waste materials on and around the well location not contained in the trash cage will be cleaned up and removed Garbage and Other Waste Materials. All garbage, junk and non-flammable waste materials will be contained in a self-contained, portable dumpster or trash cage, to prevent scattering and will be removed from the location. No potentially adverse materials or substances will be left on the location.
- Debris. Immediately after removal of the drilling rig, all debris and other waste materials not contained in the trash cage will be cleaned and removed from the well location. No potential adverse materials or substances will be left on location. •

Hazardous Materials.

- Response Compensation Liability Act (CERCLA) removed from the location and not reused at All drilling wastes identified as hazardous substances by the Comprehensive Environmental another drilling location will be disposed of at a hazardous waste facility approved by the U.S. Environmental Protection Agency (EPA).
- XTO PERMIAN OPERATING LLC and its contractors will comply with all applicable Federal, State and local laws and regulations, existing or hereafter enacted promulgated, regarding any seq., and its regulation. The definition of hazardous substances under CERLCA includes any 'hazardous waste" as defined in the RCRA of 1976, as amended, 42 U.S.C. 6901 et seq., and its regulations. The term hazardous material also includes any nuclear or nuclear by-product material as defined by the Atomic Energy Act of 1954, as amended, 42 U.C.S. 2011 et seq. The term does not include petroleum, including crude oil or any fraction thereof that is not otherwise specifically listed or designated as a hazardous substance under CERCLA Section 101 (14) U.S.C. 9601 (14) nor hazardous material, as defined in this paragraph, that will be used, produced, transported or "Hazardous material" means any substance, pollutant or contaminant that is listed as hazardous under the CERCLA of 1980, as amended, 42 U.S.C 9601 et stored on the oil and gas lease. does the term include natural gas. ≔
- No hazardous substances or wastes will be stored on the location after completion of the well. i≡
- Chemicals brought to location will be on the Toxic Substance Control Act (TSCA) approved .<u>≥</u>
 - All undesirable events (fires, accidents, blowouts, spills, discharges) as specified in Notice to Lessees (NTL) 3A will be reported to the BLM Carlsbad Field Office. Major events will be reported verbally within 24 hours, followed by a written report within 15 days. "Other than Major Events" will be reported in writing within 15 days. >

8. Ancillary Facilities

Ancillary Facilities. No off-pad ancillary facilities are planned during the exploration phase including, but not limited to campsites, airstrips or staging areas.

9. Well Site Layout

Rig Plat Diagrams: There is 1 multi-well pad in the Poker Lake Unit 18-30/18-19 BD lease. This will allow enough space for cuts and fills, topsoil storage, and storm water control. Interim reclamation of these pads is anticipated after the drilling and completion of all wells on the pad. A well site layout for the pad is attached.

- Pad A is a 26-well pad expected to be 898'x539'
- **Closed-Loop System**: There will be no reserve pit as each well will be drilled utilizing a closed loop mud system. The closed loop system will meet the NMOCD requirements 19.15.17

V-Door Orientation: These pads were staked with multiple v-door orientations. The following list is from West to East in accordance with the staked section and as agreed upon with Zane Kirsch, BLM Natural Resource Specialist, present at on-site inspection.

Pad A has a V-Door Orientation: East

All equipment and vehicles will be confined to the approved disturbed areas of this APD (i.e., access road, well pad and topsoil storage areas

10. Plans for Surface Reclamation:

consecutive with the other wells on the pad. Once activities are completed, XTO Permian Operating, LLC. will activities have been finished on the pads as these are multi-well pads where drilling and completion will be XTO Permian Operating, LLC. requests a variance from interim reclamation until all drilling and completion coordinate interim reclamation with the appropriate BLM personnel or use the following plan:

Non-Commercial Well (Not Productive), Interim & Final Reclamation:

vegetative community will be restored, and it is anticipated the site will not be disturbed for future Definition: Reclamation includes disturbed areas where the original landform and a natural development.

Reclamation Standards:

operations will be reclaimed and seeded as per BLM requirements for interim reclamation. (See The portions of the pad not essential to production facilities or space required for workover Interim Reclamation plats attached). All equipment and trash will be removed, and the surfacing material will be removed from the well pad and road and transported to the original caliche pit or used to maintain other roads. The location will then be ripped and seeded.

pipelines, and utility corridors as close as possible to the original topography. The location will then landform will be restored for all disturbed areas including well pads, production facilities, roads, The original stockpiled topsoil will be spread over the areas being reclaimed and the original be ripped and seeded.

established on the site with a density sufficient to control erosion and invasion by non-native plants and to re-establish wildlife habitat or forage production. At a minimum, the established plant A self-sustaining, vigorous, diverse, native (or otherwise approved) plant community will be

community will consist of species included in the seed mix and/or desirable species occurring in the surrounding natural vegetation.

Erosion features are equal to or less than surrounding area and erosion control is sufficient so that water naturally infiltrates into the soil and gullying, head cutting, slumping, and deep or excessive rills (greater than 3 inches) are not observed.

The site will be free of State or County listed noxious weeds, oil field debris and equipment, and contaminated soil. Invasive and non-native noxious weeds will be controlled.

Seeding:

- Seedbed Preparation: Initial seedbed preparation will consist of recontouring to the appropriate interim or final reclamation standard. All compacted areas to be seeded will be ripped to a minimum depth of 18 inches with a minimum furrow spacing of 2 feet, followed by recontouring the surface and then evenly spreading the stockpiled topsoil. Prior to seeding, the seedbed will be scarified to a depth of no less than 4-6 inches. If the site is to be broadcast seeded, the surface will be left rough enough to trap seed and snow, control erosion, and increase water infiltration.
- If broadcast seeding is to be used and is delayed, final seedbed preparation will consist of contour cultivating to a depth of 4-6 inches within 24 hours prior to seeding, dozer tracking, or other imprinting to break the soil crust and create seed germination micro-sites.
- Seed Application. Seeding will be conducted no more than two weeks following completion of final seedbed preparation. A certified weed-free seed mix designed by the BLM to meet reclamation standards will be used.
- If the site is harrowed or dragged, seed will be covered by no more than 0.25 inch of soil.

11. Surface Ownership

- The Poker Lake Unit 18-30/18-19 BD is 100% of the surface is under the administrative jurisdiction of the Bureau of Land Management.
- The surface is multiple use with the primary uses of the region for grazing and to produce oil and gas.

2. Other Information

Surveying

- Well Sites. Well pad locations have been staked. Surveys of the Existing access roads and well pad surveys with access roads have been completed on State and Federal lands with Zane Kirsch, Bureau locations have been completed by Manhard, a registered professional land surveyor. Center stake of Land Management Natural Resource Specialist in attendance, on February 15, 2022.
- Boone Archaeological Services. A PA payment has been made for the well pad, access road, and overhead Cultural Resources – Archaeology: A Class III Cultural Resources Examination has been completed by
- **Dwellings and Structures.** There are no dwellings or structures within 2 miles of this location.

Soils and Vegetation

- Complex. Simona soils are found on alluvial fans and plans and form in mixed alluvium and/or Aeolian Bippus soils are dominant to the east and the Simona Gravelly Fine Sandy Loams are dominant to the sands. Bippus soils are found on alluvial fans and floodplains and form in mixed alluvium. The Simona Environmental Setting. Soils are classified as Simona Gravelly Fine Sandy Loam and Simona-Bippus West. Dominant vegetation species include mesquite, sumac snakeweed, and various forbs and grasses. Ground cover is minimal, offering 90 percent visibility.
- Traffic. No truck traffic will be operated during periods or in areas of saturated ground when surface rutting could occur. The access road will be constructed and maintained as necessary to prevent soil erosion and accommodate all-weather traffic. The road will be crowned and ditched with water turnouts nstalled as necessary to provide for proper drainage along the access road route.
- Water. There is no permanent or live water in the immediate or within the project area.

13. Bond Coverage

Bond Coverage is Nationwide. Bond Number: COB000050

Onsite- The XTO Permian Operating, LLC. representatives and BLM NRS were on location for onsite on 2/15/22.

Operator's Representatives:

The XTO PERMIAN OPERATING LLC representatives for ensuring compliance of the surface use plan are listed below:

Robert Bartels

Project Execution Planner XTO Energy, Incorporated

6401 Holiday Hill Road Bldg 5

Midland, Texas 79701

Phone: (406) 478-3671

AFMSS

PWD Data Report

U.S. Department of the Interior BUREAU OF LAND MANAGEMENT

APD ID: 10400100853

Operator Name: XTO PERMIAN OPERATING LLC

Well Name: POKER LAKE UNIT 18-30 BD

Well Type: OIL WELL

Submission Date: 09/23/2024

Well Number: 201H

Well Work Type: Drill

- General _ Section Would you like to address long-term produced water disposal? NO

Section 2 - Lined

Would you like to utilize Lined Pit PWD options? N

Produced Water Disposal (PWD) Location:

PWD surface owner:

PWD disturbance (acres):

Other PWD Surface Owner Description:

Lined pit PWD on or off channel:

Lined pit PWD discharge volume (bbl/day):

Lined pit

Pit liner description:

Pit liner manufacturers

Precipitated solids disposal:

Decribe precipitated solids disposal:

Precipitated solids disposal

Lined pit precipitated solids disposal schedule:

Lined pit precipitated solids disposal schedule

Lined pit reclamation description:

Lined pit reclamation

Leak detection system description:

Leak detection system

Well Name: POKER LAKE UNIT 18-30 BD

Well Number: 201H

Lined pit Monitor description:

Lined pit Monitor

Lined pit: do you have a reclamation bond for the pit?

s the reclamation bond a rider under the BLM bond?

Lined pit bond number:

Lined pit bond amount:

Additional bond information

Section 3 - Unlined

Would you like to utilize Unlined Pit PWD options? ${\sf N}$

Produced Water Disposal (PWD) Location:

PWD disturbance (acres): PWD surface owner:

Other PWD Surface Owner Description:

Unlined pit PWD on or off channel:

Unlined pit PWD discharge volume (bbl/day):

Unlined pit

Precipitated solids disposal:

Decribe precipitated solids disposal:

Precipitated solids disposal

Unlined pit precipitated solids disposal schedule:

Unlined pit precipitated solids disposal schedule

Unlined pit reclamation description:

Unlined pit reclamation

Unlined pit Monitor description:

Unlined pit Monitor

Do you propose to put the produced water to beneficial use?

Beneficial use user

Estimated depth of the shallowest aquifer (feet):

Precipitated Solids Permit

Does the produced water have an annual average Total Dissolved Solids (TDS) concentration equal to or less than that of the existing water to be protected?

TDS lab results:

Geologic and hydrologic

Well Name: POKER LAKE UNIT 18-30 BD

Well Number: 201H

State

Unlined Produced Water Pit Estimated

Unlined pit: do you have a reclamation bond for the pit?

Is the reclamation bond a rider under the BLM bond?

Unlined pit bond number:

Unlined pit bond amount:

Additional bond information

Section 4

Would you like to utilize Injection PWD options? N

Produced Water Disposal (PWD) Location:

PWD surface owner:

PWD disturbance (acres):

Other PWD Surface Owner Description:

Injection PWD discharge volume (bbl/day):

Injection well mineral owner:

Injection well type:

Injection well number:

Assigned injection well API number?

Injection well API number:

Injection well name:

Injection well new surface disturbance (acres):

Minerals protection information:

Mineral protection

Underground Injection Control (UIC) Permit?

UIC Permit

Section 5 - Surface

Would you like to utilize Surface Discharge PWD options? N

Produced Water Disposal (PWD) Location:

Other PWD Surface Owner Description:

PWD surface owner:

PWD disturbance (acres):

Surface discharge PWD discharge volume (bbl/day):

Surface Discharge NPDES Permit?

Surface Discharge NPDES Permit attachment:

Surface Discharge site facilities information:

Surface discharge site facilities map:

Well Name: POKER LAKE UNIT 18-30 BD

Well Number: 201H

Section 6 -

Would you like to utilize Other PWD options? N

Produced Water Disposal (PWD) Location:

PWD surface owner:

PWD disturbance (acres):

PWD Surface Owner Description:

Other PWD discharge volume (bbl/day):

Other PWD type description:

Other PWD type

Have other regulatory requirements been met?

Other regulatory requirements

U.S. Department of the Interior BUREAU OF LAND MANAGEMENT

APD ID: 10400100853

Operator Name: XTO PERMIAN OPERATING LLC

Well Name: POKER LAKE UNIT 18-30 BD

Well Type: OIL WELL

Submission Date: 09/23/2024

Highlighted data reflects the most Show Final Text recent changes

Well Number: 201H

Well Work Type: Drill

Bond Info Data 05/19/2025

Bond

Federal/Indian APD: FED

BLM Bond number: COB000050

BIA Bond number:

Do you have a reclamation bond? NO

Is the reclamation bond a rider under the BLM bond?

Is the reclamation bond BLM or Forest Service?

BLM reclamation bond number:

Forest Service reclamation bond number:

Forest Service reclamation bond attachment:

Reclamation bond amount:

Reclamation bond rider amount:

Additional reclamation bond information attachment:



U.S. Department of the Interior BUREAU OF LAND MANAGEMENT

Sundry Print Reports

Well Name: POKER LAKE UNIT 18-30 Well Location: T25S / R30E / SEC 18 / County or Parish/State: EDDY /

NWNE / 32.136718 / -103.919737

Well Number: 201H Type of Well: OIL WELL Allottee or Tribe Name:

Lease Number: NMLC065705B Unit or CA Name: POKER LAKE UNIT Unit or CA Number:

NMNM71016X

US Well Number: Operator: XTO PERMIAN OPERATING

LLC

Notice of Intent

Sundry ID: 2869620

Type of Submission: Notice of Intent

Type of Action: APD Change

Date Sundry Submitted: 08/26/2025 Time Sundry Submitted: 09:39

Date proposed operation will begin: 09/09/2025

Procedure Description: Poker Lake Unit 18-30 BD 201H XTO Permian Operating, LLC. respectfully requests approval to make the following changes to the approved APD. Changes to include SHL, KOP, FTP, LTP, BHL, proposed total depth, and dedicated acreage. APD ID: 10400100853 FROM: TO: SHL: 265'FNL & 2365' FEL OF SECTION 18-T25S-R30E 285' FNL & 2365' FEL OF SECTION 18-T25S-R30E KOP: 265' FNL & 2365' FEL OF SECTION 18-T25S-R30E 1882' FNL & 1853' FWL OF SECTION 18-T25S-R30E FTP: 100' FNL & 2010' FEL OF SECTION 18-T25S-R30E 2559' FSL & 1835' FWL OF SECTION 18-T25S-R30E LTP: 2556' FNL & 2010' FEL OF SECTION 30-T25S-R30E 100' FSL & 1393' FWL OF SECTION 19-T25S-R30E BHL: 2646' FNL & 2010' FEL OF SECTION 30-T25S-R30E 10' FSL & 1393' FWL OF SECTION 19-T25S-R30E The proposed total depth is changing FROM 22955' MD; 10072' TVD TO 18172' MD; 9303' TVD. Dedicated Acreage is changing FROM 400 Acres TO 480 Acres. There is no new surface disturbance.

NOI Attachments

Procedure Description

 $POKER_LAKE_UNIT_18_30_BD_201H_Sundry_Docs_Updated_9.15.25_20250915124308.pdf$

Page 1 of 2

Well Name: POKER LAKE UNIT 18-30

BD

Well Location: T25S / R30E / SEC 18 / NWNE / 32.136718 / -103.919737

County or Parish/State: EDDY of 189

NM

Well Number: 201H

Type of Well: OIL WELL

Allottee or Tribe Name:

Lease Number: NMLC065705B

Unit or CA Name: POKER LAKE UNIT

NMNM71016X

Unit or CA Number:

US Well Number:

Operator: XTO PERMIAN OPERATING

LLC

Conditions of Approval

Additional

253018 Poker Lake Unit 18 30 BD 201H 09 17 2025 SUNDRY ID 2869620 20250917091720.pdf

Operator

I certify that the foregoing is true and correct. Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction. Electronic submission of Sundry Notices through this system satisfies regulations requiring a

Operator Electronic Signature: SAMANTHA WEIS Signed on: SEP 15, 2025 12:45 PM

Name: XTO PERMIAN OPERATING LLC

Title: Permitting Advisor

Street Address: 22777 SPRINGWOODS VILLAGE PARKWAY

City: SPRING State: TX

Phone: (832) 625-7361

Email address: SAMANTHA.R.BARTNIK@EXXONMOBIL.COM

Field

Representative Name:

Street Address:

City:

State:

Zip:

Phone:

Email address:

BLM Point of Contact

BLM POC Name: CHRISTOPHER WALLS

BLM POC Title: Petroleum Engineer

BLM POC Phone: 5752342234 BLM POC Email Address: CWALLS@BLM.GOV

Disposition: Approved **Disposition Date:** 09/18/2025

Signature: Chris Walls

Page 2 of 2

Form 3160-5 (October 2024)

UNITED STATES DEPARTMENT OF THE INTERIOR

| FORM APPROVEI |) |
|------------------------|-----|
| OMB No. 1004-022 | 0 |
| Expires: October 31, 2 | 027 |

| BUR | EAU OF LAND MANAGEMENT | | 5. Lease Serial No. | |
|------------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------|---------------------------------------|-------------------------------------------|
| Do not use this t | IOTICES AND REPORTS ON Vitorm for proposals to drill or t Use Form 3160-3 (APD) for su | o re-enter an | 6. If Indian, Allottee or Tribe N | Vame |
| SUBMIT IN | TRIPLICATE - Other instructions on pag | ge 2 | 7. If Unit of CA/Agreement, N | Iame and/or No. |
| 1. Type of Well Oil Well Gas W | Vell Other | | 8. Well Name and No. | |
| 2. Name of Operator | | | 9. API Well No. | |
| 3a. Address | 3b. Phone No | . (include area code) | 10. Field and Pool or Explorate | ory Area |
| 4. Location of Well (Footage, Sec., T., K | R.,M., or Survey Description) | | 11. Country or Parish, State | |
| 12. CHE | CK THE APPROPRIATE BOX(ES) TO IN | DICATE NATURE | OF NOTICE, REPORT OR OTH | HER DATA |
| TYPE OF SUBMISSION | | TYP | E OF ACTION | |
| Notice of Intent | Acidize Dee | pen raulic Fracturing | Production (Start/Resume) Reclamation | Water Shut-Off Well Integrity |
| Subsequent Report | | Construction | Recomplete | Other |
| Final Abandonment Notice | | g and Abandon g Back | Temporarily Abandon Water Disposal | |
| completion of the involved operation completed. Final Abandonment No is ready for final inspection.) | I be perfonned or provide the Bond No. on one. If the operation results in a multiple contices must be filed only after all requirement times must be filed only after all requirement true and correct. Name (Printed/Timed) | mpletion or recomple | etion in a new interval, a Form 3 | 160-4 must be filed once testing has been |
| 14. I hereby certify that the foregoing is | true and correct. Name (Printed/Typed) | Title | | |
| | | Title | | |
| Signature | | Date | | |
| | THE SPACE FOR FED | ERAL OR STA | ATE OFICE USE | |
| Approved by | | Title | ı | Date |
| | hed. Approval of this notice does not warranguitable title to those rights in the subject laduct operations thereon. | nt or | 1 | |
| Title 18 U.S.C Section 1001 and Title 4 | 3 U.S.C Section 1212, make it a crime for a | ny person knowingl | y and willfully to make to any de | epartment or agency of the United States |

any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Instructions on page 2)

GENERAL INSTRUCTIONS

This form is designed for submitting proposals to perform certain well operations and reports of such operations when completed as indicated on Federal and Indian lands pursuant to applicable Federal law and regulations. Any necessary special instructions concerning the use of this form and the number of copies to be submitted, particularly with regard to local area or regional procedures and practices, are either shown below, will be issued by or may be obtained from the local Federal office.

SPECIFIC INSTRUCTIONS

Item 4 - Locations on Federal or Indian land should be described in accordance with Federal requirements. Consult the local Federal office for specific instructions.

Item 13: Proposals to abandon a well and subsequent reports of abandonment should include such special information as is required by the local Federal office. In addition, such proposals and reports should include reasons for the abandonment; data on any former or present productive zones or other zones with present significant fluid contents not sealed off by cement or otherwise; depths (top and bottom) and method of placement of cement plugs; mud or other material placed below, between and above plugs; amount, size, method of parting of any casing, liner or tubing pulled and the depth to the top of any tubing left in the hole; method of closing top of well and date well site conditioned for final inspection looking for approval of the abandonment. If the proposal will involve **hydraulic fracturing operations**, you must comply with 43 CFR 3162.3-3, including providing information about the protection of usable water. Operators should provide the best available information about all formations containing water and their depths. This information could include data and interpretation of resistivity logs run on nearby wells. Information may also be obtained from state or tribal regulatory agencies and from local BLM offices.

NOTICES

The privacy Act of 1974 and the regulation in 43 CFR 2.48(d) provide that you be furnished the following information in connection with information required by this application.

AUTHORITY: 30 U.S.C. 181 et seq., 351 et seq., 25 U.S.C. 396; 43 CFR 3160.

PRINCIPAL PURPOSE: The information is used to: (1) Evaluate, when appropriate, approve applications, and report completion of subsequent well operations, on a Federal or Indian lease; and (2) document for administrative use, information for the management, disposal and use of National Resource lands and resources, such as: (a) evaluating the equipment and procedures to be used during a proposed subsequent well operation and reviewing the completed well operations for compliance with the approved plan; (b) requesting and granting approval to perform those actions covered by 43 CFR 3162.3-2, 3162.3-3, and 3162.3-4; (c) reporting the beginning or resumption of production, as required by 43 CFR 3162.4-1(c)and (d) analyzing future applications to drill or modify operations in light of data obtained and methods used.

ROUTINE USES: Information from the record and/or the record will be transferred to appropriate Federal, State, local or foreign agencies, when relevant to civil, criminal or regulatory investigations or prosecutions in connection with congressional inquiries or to consumer reporting agencies to facilitate collection of debts owed the Government.

EFFECT OF NOT PROVIDING THE INFORMATION: Filing of this notice and report and disclosure of the information is mandatory for those subsequent well operations specified in 43 CFR 3162.3-2, 3162.3-3, 3162.3-4.

The Paperwork Reduction Act of 1995 requires us to inform you that:

The BLM collects this information to evaluate proposed and/or completed subsequent well operations on Federal or Indian oil and gas leases.

Response to this request is mandatory.

The BLM would like you to know that you do not have to respond to this or any other Federal agency-sponsored information collection unless it displays a currently valid OMB control number.

BURDEN HOURS STATEMENT: Public reporting burden for this form is estimated to average 8 hours per response, including the time for reviewing instructions, gathering and maintaining data, and completing and reviewing the form. Direct comments regarding the burden estimate or any other aspect of this form to U.S. Department of the Interior, Bureau of Land Management (1004-0137), Bureau Information Collection Clearance Officer (WO-630), 1849 C St., N.W., Mail Stop 401 LS, Washington, D.C. 20240

(Form 3160-5, page 2)

Additional Information

Additional Remarks

FTP: 100' FNL & 2010' FEL OF SECTION 18-T25S-R30E 2559' FSL & 1835' FWL OF SECTION 18-T25S-R30E LTP: 2556 FNL & 2010 FEL OF SECTION 30-T25S-R30E 100 FSL & 1393 FWL OF SECTION 19-T25S-R30E BHL: 2646 FNL & 2010 FEL OF SECTION 30-T25S-R30E 10 FSL & 1393 FWL OF SECTION 19-T25S-R30E

The proposed total depth is changing FROM 22955 MD; 10072 TVD TO 18172 MD; 9303 TVD.

Dedicated Acreage is changing FROM 400 Acres TO 480 Acres.

There is no new surface disturbance.

Location of Well

0. SHL: NWNE / 265 FNL / 2365 FEL / TWSP: 25S / RANGE: 30E / SECTION: 18 / LAT: 32.136718 / LONG: -103.919737 (TVD: 0 feet, MD: 0 feet)
PPP: NWNE / 0 FSL / 2011 FEL / TWSP: 25S / RANGE: 30E / SECTION: 19 / LAT: 32.122834 / LONG: -103.918569 (TVD: 10072 feet, MD: 15700 feet)
PPP: NWNE / 100 FNL / 2010 FEL / TWSP: 25S / RANGE: 30E / SECTION: 18 / LAT: 32.137172 / LONG: -103.918591 (TVD: 10072 feet, MD: 10495 feet)
BHL: SWNE / 2646 FNL / 2010 FEL / TWSP: 25S / RANGE: 30E / SECTION: 30 / LAT: 32.100949 / LONG: -103.918534 (TVD: 10072 feet, MD: 22955 feet)

| <u>C-10</u> | 12 | | Eno | nov. N | | New Mexico | Damautus ant | | | Revised July 9, 2024 |
|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------|---------------------|-----------------------------|
| Submit El | Submit Electronically Via OCD Permitting WELL API Number 30-015 -57272 Pool Code 96473 Property Code 333648 Property Name 333648 Property Name 333648 ORGID No. 373075 Operator Name XTO PERMIA UL Section Township Range Lot Ft. fro 18 Section N 19 25 S 30 E Defining Well ABO DEFINING Dedicated Acres 480 DEFINING Defining Well DEFINING Order Numbers. UL Section Township Range Lot Ft. fro 1 Section N 19 Se | | | | | • | | | ☐ Initial Submittal | |
| Energy, Mineral Submit Electronically Via OCD Permitting WELL L API Number 30-015 -57272 | | IL CONSER V | ATION DIVISION | JIN | Submit | ttal | Amended Report | | | |
| | | | | | | | | Type: | | ☐ As Drilled |
| | | | | | | | | | | |
| | | | | • | | N INFORMATION | | | | |
| 30-0 | 15 -572 7 | 7 2 | | | Pool Na PIE | me ERCE CROSSING; BO | NE SPRING, EAST | • | | |
| Propert | y Code 333648 | | Property Name | POKE | ER LAKE UNIT 18-3 |) BD | | | 1 | l Number 11H |
| | | | Operator Name | XTO F | PERMIAN OPERAT | NG, LLC. | | | 1 | und Level Elevation 182' |
| Surface | Owner: | State F | ee ☐ Tribal 🔀 | Federal | | Mineral Owner: | State Fee Trib | al 🛛 Fed | leral | |
| | | _ | | | Surface | Location | | | | |
| | | 1 | . . | Lot | Ft. from N/S 285' FNL | Ft. from E/W 2,365' FEL | Latitude I 32.136663 | ongitude. -103.91 | | County EDDY |
| | | | | | Bottom H | lole Location | | | | |
| | | 1 | . - | Lot | Ft. from N/S 10' FSL | Ft. from E/W 1,393' FWL | Latitude I 32.108239 | ongitude -103.92 | | County EDDY |
| | | | | | 1 | | | | | I |
| | ted Acres | 1 | | Defining | g Well API | Overlapping Spacing U | nit (Y/N) Consolid | ation Cod | е | |
| Order 1 | Numbers. | | | | | Well setbacks are under | r Common Ownership: | ⊠ Yes | □ No |) |
| | | | | | Kick Of | Point (KOP) | | | | |
| UL | Section | Townshi | p Range | Lot | Ft. from N/S | Ft. from E/W | Latitude I | ongitude. | | County |
| F | 18 | 25 S | 30 E | | 1,882' FNL | 1,853' FWL | 32.132273 | -103.92 | 3425 | EDDY |
| TIT | Section | Townshi | n Range | Lot | | Point (FTP) Ft. from E/W | Latitude I | Longitude | | County |
| | | 1 | . - | Lot | 2,559' FSL | 1,853' FWL | 32.129862 | -103.92 | | |
| | | T | | | | Point (LTP) | T | | | |
| | | | . - | Lot | 100' FSL | Ft. from E/W 1,393' FWL | Latitude I 32.108486 | ongitude | | County |
| Unitize | d Area or Are | ea of Unifor | m Interest | Spacing | v Unit Type ▼ Horize | ontal 🗆 Vertical | Ground Floor | Elevation | | |
| | | NMNM10 | 05422429 | Spacing | S cant Type \(\square \square \text{Tionze} | mui Verticai | Ground 1 roof | | 3,18 | 82' |
| | | | | | | | | | | |
| OPE | RATOR C | ERTIFIC | CATIONS | | | SURVEYOR CI | ERTIFICATIONS | 3 | | |
| best of interest location an own agreem | my knowledge or unleased i n or has a rigi er of such a n ent or a comp vell is a horize | e and belief, mineral inte ht to drill th nineral or w pulsory pool | and that this orgonest in the land in is well at this local orking interest, or ing order heretofol further certify the | unization ecluding the tion pursication pursication to a volucione enterect this organization. | either owns a working e proposed bottom hole uant to a contract with ntary pooling d by the division. anization has received | notes of actual surve is true and correct to 1, TIM C. PAPPAS, NEW M 21209, DO HEREBY CERT ACTUAL SURVEY ON THE WERE PERFORMED BY ME THAT I AM RESPONSIBLE MEETS THE MINIMUM STAME MEXICO, AND THAT IS THE MY KNOWLEDGE AND BE | the well location show by s made by me or una the best of my belief. MEXICO PROFESSIONAL SUI TIFY THAT THIS SURVEY PI GROUND UPON WHICH IT E OR UNDER MY DIRECT SE FOR THIS SURVEY, THAT NDARDS FOR SURVEYING I UE AND CORRECT TO THE IEF. | RVEYOR NO. AT AND THI IS BASED SUPERVISION THIS SURVE N NEW | ervisi E | |
| interesi comple division | in each tract ted interval w 1. | (in the targ ill be locate | et pool or formati d or obtained a co | on) in whi ompulsory | ich any part of the well', pooling form the | - . | 9 Sept 2 AL LAND SURVEYOR 10. 21209 | 2025 | PROFT | SS/ONAL SURVEY |
| Sar | nanth | a We | 91 | 15/20 | 25 | - | | | | YUNAL 30 |
| | | | Γ | ate | | Signature and Seal of | Professional Surveyor | | | |
| UL Section Township Range Lot Ft. from N/S 1,882' UL Section Township Range Lot Ft. from N/S 2,559' Late UL Section Township Range Lot Ft. from N/S 19 25 S 30 E Lot Ft. from N/S 100' FS Unitized Area or Area of Uniform Interest NMNM105422429 Spacing Unit Type Section or Area of Uniform Interest NMNM105422429 Spacing Unit Type Interest of my knowledge and belief, and that this organization either owns a winterest or unleased mineral interest in the land including the proposed both location or has a right to drill this well at this location pursuant or a contral an owner of such a mineral or working interest, or to a voluntary pooling agreement or a compulsory pooling order heretofore entered by the division of this well is a horizontal well, I further certify that this organization has reflected interest in each tract (in the target pool or formation) in which any part of the consent of at least one lessee or owner of a working interest or unlease interest in each tract (in the target pool or formation) in which any part of the compeleted interval will be located or obtained a compulsory pooling form to division. Samantha Weis Printed Name samantha.r.bartnik@exxonmobil.com | | | Certificate Number | Date of Su | rvev | | | | | |
| UL Section Township Range Lot Ft. from N/S Firs UL Section Township Range Lot Ft. from N/S K 18 25 S 30 E Las UL Section Township Range Lot Ft. from N/S N 19 25 S 30 E Unitized Area or Area of Uniform Interest NMNM105422429 OPERATOR CERTIFICATIONS I hereby certify that the information contained herein is true and complete to best of my knowledge and belief, and that this organization either owns a we interest or unleased mineral interest in the land including the proposed both location or has a right to drill this well at this location pursuant to a contrat an owner of such a mineral or working interest, or to a voluntary pooling agreement or a compulsory pooling order heretofore entered by the division. If this well is a horizontal well, I further certify that this organization has re the consent of at least one lessee or owner of a working interest or unleased interest in each tract (in the target pool or formation) in which any part of the completed interval will be located or obtained a compulsory pooling form the division. Samantha Weis Printed Name | | 1 | TIM C. PAPPAS 2 | | • | | | | | |
| Dedicated Acres | | | - | | | | | | | |
| | Note: No al | lowable wii | ll be assigned to t | his compi | letion until all interests | have been consolidated o | or a non-standard unit | has been | appro | oved by the division. |



2205 Walnut Street - Columbus, TX 78934
Ph: 817.349.9800 - Fax: 979.732.5271
TBPE Firm 17957 | TBPLS Firm 10000100
www.fscinc.net
© COPYRIGHT 2025 - ALL RIGHTS RESERVED

DATE: DRAWN BY: CHECKED BY: FIELD CREW:


9-9-2025 LM WL IR PROJECT NO: SCALE: SHEET: REVISION:

2025060194 1 OF 2

ACREAGE DEDICATION PLATS

This grid represents a standard section. You may superimpose a non-standard section, or a larger area, over this grid. Operators must outline the dedicated acreage in a red box, clearly show the well surface location and bottom hole location, if it is directionally drilled, with the dimensions from the section lines in the cardinal directions. If this is a horizontal wellbore show on this plat the location of the First Take Point and Last Take Point, and the point within the Completed interval (other than the First Take Point or Last Take Point) that is the closest to any outer boundary of the tract.

Surveyors shall use the latest United States government survey or dependent resurvey. Well locations will be in reference to the New Mexico Principal Meridian. If the land is not surveyed, contact the OCD Engineering Bureau. Independent subdivision surveys will not be acceptable.



| C | ORNER COO | RDI | NATES (N | NAD83 NME) | |
|---------|-----------|-----|----------|------------|---|
| A - Y = | 411,318.8 | Ν | A - X = | 667,717.9 | Е |
| B - Y = | 411,325.0 | Ν | B - X = | 669,062.2 | Е |
| C - Y = | 408,659.4 | Ν | C - X = | 667,733.0 | Е |
| D - Y = | 408,666.5 | Ν | D - X = | 669,077.2 | Е |
| E - Y = | 406,001.2 | Ν | E - X = | 667,747.8 | Е |
| F - Y = | 406,009.2 | Ν | F - X = | 669,089.3 | Е |
| G - Y = | 403,343.1 | N | G - X = | 667,762.3 | Е |
| H - Y = | 403,350.7 | Ν | H - X = | 669,101.5 | Е |
| C | ORNER COO | RDI | NATES (N | NAD27 NME) | |
| A - Y = | 411,260.5 | N | A - X = | 626,533.3 | Е |
| B - Y = | 411,266.7 | N | B - X = | 627,877.5 | Е |
| C - Y = | 408,601.2 | N | C - X = | 626,548.3 | Е |
| D - Y = | 408,608.3 | N | D - X = | 627,892.5 | Е |
| E - Y = | 405,943.0 | N | E - X = | 626,563.0 | Е |
| F - Y = | 405,951.0 | N | F - X = | 627,904.5 | Е |
| G - Y = | 403,285.0 | N | G - X = | 626,577.4 | Е |
| H - Y = | 403,292.6 | Ν | H - X = | 627,916.6 | Е |

| COORDINATE TABLE | | | | | | | |
|-----------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------|------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------|---------------------------|--|--|
| SH | L (NAD 83 NM | IE) | L | TP (NAD 83 NME | <u>.</u>) | | |
| | 413,699.3 | N | Y = | 403,443.4 | N | | |
| X = | 669,357.3 | E | X = | 667,815.4 | Е | | |
| LAT. = | 32.136663 | °N | LAT. = | 32.108486 | °N | | |
| LONG. = | 103.919737 | °W | LONG. = | 103.924844 | °W | | |
| | P (NAD 83 NN | | | HL (NAD 83 NME | | | |
| Y = | 412,098.2 | | Y = | | N | | |
| X = | 668,222.0 | E | X = | 667,816.0 | E | | |
| LAT. = | 32.132273 | °NI | I AT - | 32.108239 | °N | | |
| | | 91/1/ | LAT. = LONG. = | 102.100233 | °W | | |
| LONG. = | 103.923425 | E) | LONG. = | 103.924843 | | | |
| | P (NAD 83 NM | | | P1 (NAD 83 NME) | | | |
| | 411,221.2 | | Υ = | 410,434.3 | N | | |
| X = | 668,227.1 | | X = | 668,231.8 | E | | |
| LAT. = | 32.129862 | °N | LAT. = | | °N | | |
| | 103.923419 | | | 103.923413 | °W | | |
| | 2 (NAD 83 NMI | | | P3 (NAD 83 NME) |) | | |
| | 410,035.9 | | | 409,645.9 | N | | |
| X = | 668,199.7 | E | X = | 668,112.5 | Е | | |
| LAT. = | 32.126604 | °N | LAT. = | 32.125533 | °N | | |
| LONG. = | | | | 103.923809 | °W | | |
| | 4 (NAD 83 NM | | | P5 (NAD 83 NME |) | | |
| Y = | 409,317.3 | N | Y = | 408,986.1 | N | | |
| X - | 667,992.7 | E | X = | 667,880.2 | E | | |
| I AT - | 32.124631 | ∘NI | | 32.123722 | °N | | |
| LAI. = | 102.024000 | °W | | | °W | | |
| | 103.924200 | | | 103.924567 | | | |
| | 6 (NAD 83 NMI | Ε) | | P7 (NAD 83 NME) | | | |
| Y = | 408,594.1 | N | Y = | 408,215.1 | N | | |
| X = | 667,802.2 | E | X = | 667,779.4 | E | | |
| LAT. = | 32.122645 | ٥N | LAT. = | 32.121604 | °N | | |
| LONG. = | 103.924824 | °W | LONG. = | 103.924902 | °W | | |
| SH | L (NAD 27 NM | IE) | L | TP (NAD 27 NME | <u> </u> | | |
| Y = | 413,640.7 | N | Y = | 403,385.1 | N | | |
| X = | 628,172.8 | E | X = | 626,630.6 | Е | | |
| LAT. = | 32.136538 | °N | LAT. = | 32.108361 | °N | | |
| LONG. = | 103.919252 | | LONG. = | | °W | | |
| | P (NAD 27 NN | | | HL (NAD 27 NME | | | |
| | | | | | | | |
| | 412,039.6 | <u>N</u> | | 403,295.1 | N | | |
| X = | 627,037.5 | | X = | 626,631.2 | | | |
| LAT. = | 32.132148 | °N | LAT. = | 32.108114 | °N | | |
| | 103.922940 | | | 103.924359 | °W | | |
| | P (NAD 27 NM | | | P1 (NAD 27 NME) | | | |
| Y = | 411,162.7 | | | 410,375.8 | N | | |
| X = | 627,042.6 | Е | X = | 627,047.2 | Е | | |
| LAT. = | 32.129737 | °N | LAT. = | 32.127574 | °N | | |
| LONG. = | 103.922934 | | LONG. = | 103.922929 | °W | | |
| P2 | 2 (NAD 27 NM | | | P3 (NAD 27 NME |) | | |
| Y = | 400.077.4 | , NI | V | 409,587.4 | N | | |
| | 627,015.1 | F | X = | 626,927.9 | E | | |
| | 32.126479 | ∘NI | ΙΔΤ _ | 32.125408 | °N | | |
| LONC. | 103.923037 | | LONG | | °W | | |
| | 103.923037 | -^ | LUNG. = | 103.923324 | | | |
| P4 | 1 (NAD 27 NMI | E) | | P5 (NAD 27 NME) | | | |
| | 409,258.8 | | | 408,927.6 | N | | |
| X = | 626,808.1 | E | X = | 626,695.6 | E | | |
| LAT. = | 32.124506 | °N | LAT. = | 32.123597 | °N | | |
| LONG. = | 103.923715 | °W | LONG. = | 103.924082 | °W | | |
| Pe | 6 (NAD 27 NM | Ε) | F | P7 (NAD 27 NME) |) | | |
| Y = | 408,535.6 | N | Y = | 408,156.6 | N | | |
| X = | 626,617.6 | Е | X = | 626,594.8 | Е | | |
| LAT. = | 32.122520 | °N | LAT. = | 32.121479 | °N | | |
| LONG. = | 103.924339 | °W | LONG. = | | °W | | |
| LUING. = | | | | P #1 (NAD 27 NN | | | |
| | #1 (NAD 83 N | | | (12 2. 1414 | | | |
| PPP | #1 (NAD 83 N 413.267.8 | | | 413 209 2 | N | | |
| PPP Y = | 413,267.8 | N | Y = | 413,209.2 627.866.8 | N F | | |
| PPP Y = X = | 413,267.8 669,051.3 | N E | Y = X = | 627,866.8 | Е | | |
| PPP Y = X = LAT. = | 413,267.8 669,051.3 32.135480 | N E °N | Y = X = LAT. = | 627,866.8 32.135355 | E °N | | |
| Y = X = LAT. = LONG. = | 413,267.8 669,051.3 32.135480 103.920731 | N E °N °W | Y = X = LAT. = LONG. = | 627,866.8 32.135355 103.920246 | e °N °W | | |
| Y = X = LAT. = LONG. = PPP | 413,267.8 669,051.3 32.135480 103.920731 #2 (NAD 83 N | N E °N °W ME) | Y = X = LAT. = LONG. = PP | 627,866.8 32.135355 103.920246 P #2 (NAD 27 NN | E °N °W IE) | | |
| PPP Y = | 413,267.8 669,051.3 32.135480 103.920731 #2 (NAD 83 N 411,321.2 | N E °N °W ME) | Y = X = LAT. = LONG. = PP | 627,866.8 32.135355 103.920246 P #2 (NAD 27 NN 411,262.6 | E °N °W IE) N | | |
| Y = X = LAT. = LONG. = PPP | 413,267.8 669,051.3 32.135480 103.920731 #2 (NAD 83 N 411,321.2 668,226.5 | N E °N °W ME) | Y = X = LAT. = LONG. = PP | 627,866.8 32.135355 103.920246 P #2 (NAD 27 NN | E °N °W IE) | | |
| PPP Y = | 413,267.8 669,051.3 32.135480 103.920731 #2 (NAD 83 N 411,321.2 | N E °N °W ME) N E | Y = X = LAT. = PP Y = X = LAT. = | 627,866.8 32.135355 103.920246 P #2 (NAD 27 NN 411,262.6 | E | | |
| PPP Y = | 413,267.8 669,051.3 32.135480 103.920731 #2 (NAD 83 N 411,321.2 668,226.5 | N E °N °W ME) N E | Y = X = LAT. = LONG. = PP Y = X = | 627,866.8 32.135355 103.920246 P #2 (NAD 27 NN 411,262.6 627,042.0 | E °N °W IE) N | | |
| PPP Y = | 413,267.8 669,051.3 32.135480 103.920731 #2 (NAD 83 N 411,321.2 668,226.5 32.130137 | N E °N °W ME) N E °N °W | Y = X = LAT. = PP Y = X = LAT. = LONG. = | 627,866.8 32.135355 103.920246 P #2 (NAD 27 NW 411,262.6 627,042.0 32.130012 | E | | |
| PPP Y = | 413,267.8 669,051.3 32.135480 103.920731 #2 (NAD 83 N 411,321.2 668,226.5 32.130137 103.923420 | N E °N °W ME) N E °N °W | Y = X = LONG. = PP | 627,866.8 32.135355 103.920246 P #2 (NAD 27 NW 411,262.6 627,042.0 32.130012 103.922935 | E | | |
| PPP Y = | 413,267.8 669,051.3 32.135480 103.920731 #2 (NAD 83 N 411,321.2 668,226.5 32.130137 103.923420 #3 (NAD 83 N 408,659.9 | N E °N °W ME) N E °N °W ME) N | Y = X = LAT. = LONG. = PP | 627,866.8 32.135355 103.920246 P#2 (NAD 27 NW 411,262.6 627,042.0 32.130012 103.922935 P#3 (NAD 27 NW 408,601.4 | E | | |
| PPP Y = | 413,267.8 669,051.3 32.135480 103.920731 #2 (NAD 83 N 411,321.2 668,226.5 32.130137 103.923420 #3 (NAD 83 N | N E °N °W ME) N E °N °W | Y = X = LONG. = PP | 627,866.8 32.135355 103.920246 P #2 (NAD 27 NN 411,262.6 627,042.0 32.130012 103.922935 P #3 (NAD 27 NN | E | | |

| LINE TABLE | | |
|------------|-------------|-----------|
| LINE | AZIMUTH | LENGTH |
| L1 | 215° 20'21" | 1,962.77' |
| L2 | 179° 39'54" | 877.06' |
| L3 | 179° 39'30" | 786.93' |
| L4 | 184° 36'25" | 399.65' |
| L5 | 192° 36'15" | 399.65' |
| L6 | 200° 02′10" | 349.79' |
| L7 | 198° 45'22" | 349.76' |
| L8 | 191° 15'02" | 399.64' |
| L9 | 183° 27'04" | 379.73' |
| L10 | 179° 34'08" | 4,861.82' |
| | | |



2205 Walnut Street - Columbus, TX 78934
Ph: 817.349.9800 - Fax: 979.732.5271
TBPE Firm 17957 | TBPL5 Firm 10000100
www.fscinc.net
© COPYRIGHT 2025 - ALL RIGHTS RESERVED

 DATE:
 9-9-2025
 PROJECT NO:
 2025060194

 DRAWN BY:
 LM
 SCALE:
 1" = 2,000'

 CHECKED BY:
 WL
 SHEET:
 2 OF 2

 FIELD CREW:
 IR
 REVISION:
 1

DRILLING PLAN: BLM COMPLIANCE (Supplement to BLM 3160-3)

ExxonMobil

Poker Lake Unit 18-30 BD 201H Projected TD: 18172' MD / 9303' TVD SHL: 285' FNL & 2365' FEL , Section 18, T25S, R30E BHL: 10' FSL & 1393' FWL , Section 19, T25S, R30E Eddy County, NM

1. Geologic Name of Surface Formation A. Quaternary

2. Estimated Tops of Geological Markers & Depths of Anticipated Fresh Water, Oil or Gas

| Formation | Well Depth (TVD) | Water/Oil/Gas |
|--------------------------|------------------------|---------------|
| Rustler | 771' | Water |
| Salado | 1045' | Water |
| Base of Salt | 3214' | Water |
| Delaware | 3598' | Water |
| Cherry Canyon | 4486' | Water/Oil/Gas |
| Brushy Canyon | 7100' | Water/Oil/Gas |
| Bone Spring Lm. | 7335' | Water/Oil/Gas |
| Avalon | 7442' | Water/Oil/Gas |
| 1st Bone Spring Sand | 8237' | Water/Oil/Gas |
| 2nd Bone Spring Shale | 8539' | Water/Oil/Gas |
| 2nd Bone Spring Lime | 8708' | Water/Oil/Gas |
| 2nd Bone Spring Sand | 8857' | Water/Oil/Gas |
| 2nd Bone Spring Mid Carb | 9303' | Water/Oil/Gas |
| | | |

| | Summa | |
|--|-------|--|
| | | |

* Deepest Expected Groundwater Depth: 40' (per NM State Engineers Office).

No other formations are expected to give up oil, gas or fresh water in measurable quantities. Surface fresh water sands will be protected by setting 9-5/8" inch casing at 1020' and circulating cement back to surface.

3. Primary Casing Design Primary Design:

| Hole Size (in.) | MD | Casing TVD | OD Csg | Weight | Grade | Collar | New/Used | SF Burst | SF Collapse | SF Tension |
|-----------------|----------------|---------------|--------|--------|----------|-------------------|----------|----------|-------------|------------|
| 12.25" | 0' – 1020' | 1020' | 9-5/8" | 40 | J55 | BTC | New | 12.62 | 11.63 | 5.18 |
| 8.75" | 0' - 4000' | 3846' | 7-5/8" | 29.7 | P110-ICY | Tenaris Wedge 511 | New | 6.04 | 8.84 | 3.49 |
| 8.75" | 4000' - 8804' | 8437' | 7-5/8" | 29.7 | L80-IC | Tenaris Wedge 511 | New | 3.35 | 6.14 | 2.52 |
| 6.75" | 0' - 8704' | 8337' | 5-1/2" | 20 | P110-ICY | Tenaris Wedge 441 | New | 1.18 | 3.41 | 3.00 |
| 6.75" | 8704' – 18172' | 9303' | 5-1/2" | 20 | P110-ICY | Tenaris Wedge 441 | New | 1.18 | 3.05 | 3.00 |
| | | | | | | | | | | |
| | | | | | | | | | | |

Section 3 Summary:

XTO will keep casing fluid filled to meet BLM's collapse requirement.

The planned kick off point is located at: 8954' MD / 8587' TVD.

Wellhead:

A multi-bowl wellhead system will be utilized. The well design chosen is: 3-String Slim Non-Potash

Wellhead will be installed by manufacturer's representatives.

Manufacturer will monitor welding process to ensure appropriate temperature of seal.

4. Cement Program

| | | | Р | rimary Cementi | ng | | | |
|----------------|-----------------------|-----------|---------------|------------------|----------|---------------------------------|------------|---------------------------------------------------|
| Hole Section | Slurry Type | No. Sacks | Density (ppg) | Yield (ft3/sack) | TOC (ft) | Casing Setting Depth (MD) | Excess (%) | Slurry Description |
| Surface 1 | Lead | 214 | 12.4 | 2.11 | 0 | 1,020 | 100% | Surface 1 Class C Lead Cement |
| Surface 1 | Tail | 141 | 14.8 | 1.33 | 720 | 1,020 | 100% | Surface 1 Class C Tail Cement |
| Intermediate 1 | Lead | | | | | | | |
| Intermediate 1 | Tail | 159 | 14.8 | 1.45 | 7100 | 8,804 | 35% | Intermediate 1 Class C Tail Cement |
| Production 1 | Lead | | | | | | | |
| Production 1 | Tail | 686 | 13.2 | 1.44 | 8304 | 18,172 | 25% | Production 1 Class C Tail Cement |
| | | | | | | | | |
| | | | Brea | denhead Ceme | nting | | | |
| Casing | Slurry Type | No. Sacks | Density (ppg) | Yield (ft3/sack) | Cement | ed Interval | Excess (%) | Slurry Description |
| Intermediate 1 | Bradenhead Squeeze | 664 | 14.8 | 1.45 | 0 - | 7100' | 35% | Intermediate Class C Bradenhead Squeeze Cement |
| | | | | | | | | |

Section 4 Summary:

| *Bradenhead Squeeze 2nd Stage Offline |
|---------------------------------------|
| |
| |
| |
| |
| |
| |
| |
| |
| |
| |
| |

5. Pressure Control Equipment

| Section 5 Summary: |
|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| Once the permanent WH is installed on the casing, the blow out preventer equipment (BOP) will consist of a minimum 5M Hydril and a minimum 10M triple Ram BOP. |
| All BOP testing will be done by an independent service company. Operator will Test as per 43CFR-3172. |
| No break testing will be done if intermediate casing point penetrates the Wolfcamp |
| Requested Variances |
| 4A) Offline Cementing Variance XOM requests the option to perform offline cement and bradenhead jobs (if needed) SURFACE, INTERMEDIATE, and PRODUCTION casing strings where batch drilling is approved. XOM will ensure well is static with no pressure on the csg annulus, as with all other casing strings where batch drilling operations occur before moving off the rig. Offline cement operations will then be conducted after the rig is moved off the current well to the next well in the batch sequence. The TA cap will also be installed when applicable per wellhead manufacturer's procedure and pressure inside the casing will be monitored via the valve on the TA cap as per standard batch drilling ops. |
| 5A) Break Test Variance A break testing variance is requested to ONLY test broken pressure seals on the BOP equipment when moving from wellhead to wellhead for the intermediate hole sections which is in compliance with API Standard 53. The maximum anticipated surface pressure is less than 4800psi and the deepest intermediate casing point does not penetrate the Wolfcamp Formation. |
| 5B) Flex Hose Variance A variance is requested to allow use of a flex hose as the choke line from the BOP to the Choke Manifold. If this hose is used, a copy of the manufacturer's certification and pressure test chart will be kept on the rig. Attached is an example of a certification and pressure test chart. The manufacturer does not require anchors. |
| 8A) Open Hole Logging Variance Open hole logging will not be done on this well. |
| 10A) Spudder Rig Variance XOM requests the option to utilize a spudder rig (Atlas Copco RD20 or Equivalent) to set and cement surface casing. |
| 10B) Batch Drilling Variance XOM requests a variance to be able to batch drill this well. In doing so, XOM will set casing and ensure that the well is cemented properly (unless approval is given for offline cementing) and the well is static. XOM will contact the BLM to skid the rig to drill the remaining wells on the pad. Once surface and intermediate strings are all completed, XOM will begin drilling the production hole on each of the wells. |
| |
| |
| |
| |
| |
| |

6. Proposed Mud Circulation System

| INTERVAL | Hole Size | Mud Type | MW (ppq) | Viscosity (sec/qt) | Fluid Loss (cc) | Comments |
|----------------|-----------|---------------------|-------------|-----------------------|--------------------|-------------------------------------------------------------------------------------------------------------------|
| 0' - 1020' | 12.25" | FW/Native | 8.3 - 8.7 | 35-40 | NC | Fresh Water or Native Water |
| 1020' – 8804' | 8.75" | BDE/OBM or FW/Brine | 9.5 - 10 | 30-32 | NC | Fluid type will be based upon on well conditions. A fully saturated system will be used across the salt interval. |
| 8804' – 18172' | 6.75" | ОВМ | 9 - 9.6 | 50-60 | NC - 20 | OBM or Cut Brine depending on Well Conditions |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Section 6 Summary:

The necessary mud products for weight addition and fluid loss control will be on location at all times.

Pump viscous sweeps as needed for hole cleaning. Pump speed will be recorded on a daily drilling report after mudding up. An EDR (Electronic Drilling Recorder) will be used to detect changes in loss or gain of mud volume. A mud test will be performed every 24 hours to determine: density, viscosity, strength, filtration and pH as necessary. Use available solids controls equipment to help keep mud weight down after mud up. Rig up solids control equipment to operate as a closed loop system.

7. Auxiliary Well Control and Monitoring Equipment

Section 7 Summary:

A Kelly cock will be in the drill string at all times.

A full opening drill pipe stabbing valve having appropriate connections will be on the rig floor at all times.

H2S monitors will be on location when drilling below the 9-5/8" casing.

8. Logging, Coring and Testing Program

Section 8 Summary:

Open hole logging will not be done on this well.

9. Abnormal Pressures and Temperatures / Potential Hazards

Section 9 Summary:

The estimated bottom hole temperature of 159F to 179F. No H2S is expected but monitors will be in place to detect any H2S occurrences. Should these circumstances be encountered the operator and drilling contractor are prepared to take all necessary steps to ensure safety of all personnel and environment. Lost circulation is possible throughout the well.

10. Anticipated Starting Date and Duration of Operations

Section 10 Summary:


Anticipated spud date will be after BLM approval. Move in operations and drilling is expected to take 40 days.




Site: Poker Lake Unit 18-30 BD

Well: Poker Lake Unit 18-30 BD 201H

Wellbore: OH Design: Plan 0





| | FORMAT | TION TOP DETAILS |
|-----------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| TVDPath 771.0 1045.1 3214.3 3598.0 4485.8 6001.9 7099.7 7335.2 7441.6 7793.0 8237.0 8538.6 8707.9 8856.6 9303.0 | MDPath 771.0 1045.1 3313.6 3730.5 4694.9 6341.8 7467.1 7702.6 7808.9 8160.3 8604.4 8906.0 9075.8 9230.7 9343.9 | Formation Rustler Salado Base of Salt Delaware Cherry Canyon Brushy Canyon Basal Brushy Canyon Bone Spring Lm. Avalon Lower Avalon 1st Bone Spring Sand 2nd Bone Spring Lime 2nd Bone Spring Sand 2rd Bone Spring Sand |

ROC

Long Lead - PLU 18-30 BD Poker Lake Unit 18-30 BD Poker Lake Unit 18-30 BD 201H

OH

Plan: Plan 0

Standard Planning Report

11 September, 2025

EDM 5000.18 Single User Db Database:

Company: Project:

Site:

Long Lead - PLU 18-30 BD Poker Lake Unit 18-30 BD

Well: Poker Lake Unit 18-30 BD 201H

Wellbore: ОН Plan 0 Design:

Local Co-ordinate Reference:

TVD Reference: MD Reference: North Reference:

Survey Calculation Method:

Well Poker Lake Unit 18-30 BD 201H

RKB @ 3212.0usft RKB @ 3212.0usft

Grid

Minimum Curvature

Project Long Lead - PLU 18-30 BD

Map System: Geo Datum:

US State Plane 1927 (Exact solution) NAD 1927 (NADCON CONUS)

New Mexico East 3001 Map Zone:

System Datum:

Mean Sea Level

Poker Lake Unit 18-30 BD Site

Site Position: From:

Мар

Northing: Easting:

413,640.80 usft Latitude: 628,142.70 usft Longitude:

32° 8' 11.538 N 103° 55' 9.659 W

Position Uncertainty: 0.0 usft Slot Radius: 13-3/16 "

Well Poker Lake Unit 18-30 BD 201H

Well Position +N/-S +E/-W

0.0 usft 0.0 usft 2.0 usft

Northing: Easting:

413,640.70 usft 628,172.80 usft Latitude: Longitude:

32° 8' 11.535 N 103° 55' 9.309 W

Position Uncertainty Wellhead Elevation: usft Ground Level: 3,182.0 usft

0.22 **Grid Convergence:**

ОН Wellbore

| Magnetics | Model Name | Sample Date | Declination | Dip Angle | Field Strength |
|-----------|------------|-------------|-------------|-----------|-----------------|
| | | | (°) | (°) | (nT) |
| | IGRF2020 | 6/4/2025 | 6.23 | 59.64 | 46,995.97394080 |

Plan 0 Design

Audit Notes:

Version:

Phase: Vertical Section: Depth From (TVD) PLAN

Tie On Depth: +N/-S +E/-W

0.0 Direction

(usft) (usft) (usft) (°) 184.13 0.0 0.0 0.0

Plan Survey Tool Program

Date 9/11/2025

Depth From (usft) 0.0 Depth To (usft) 18,171.6

Survey (Wellbore)

Plan 0 (OH)

Tool Name

Remarks

XOMR2_OWSG MWD+IFR1+ OWSG MWD + IFR1 + Multi-St

Database: EDM 5000.18 Single User Db

Company: ROC

 Project:
 Long Lead - PLU 18-30 BD

 Site:
 Poker Lake Unit 18-30 BD

 Well:
 Poker Lake Unit 18-30 BD 201H

Wellbore: OH
Design: Plan 0

Local Co-ordinate Reference:

TVD Reference:
MD Reference:
North Reference:

Survey Calculation Method:

Well Poker Lake Unit 18-30 BD 201H

RKB @ 3212.0usft RKB @ 3212.0usft

Grid

| Plan Sections | | | | | | | | | | |
|-----------------------------|--------------------|----------------|-----------------------------|-----------------|-----------------|-------------------------------|------------------------------|-----------------------------|------------|--------------------|
| Measured Depth (usft) | Inclination (°) | Azimuth (°) | Vertical Depth (usft) | +N/-S (usft) | +E/-W (usft) | Dogleg Rate (°/100usft) | Build Rate (°/100usft) | Turn Rate (°/100usft) | TFO (°) | Target |
| 0.0 | 0.00 | 0.00 | 0.0 | 0.0 | 0.0 | 0.00 | 0.00 | 0.00 | 0.00 | |
| 1,300.0 | 0.00 | 0.00 | 1,300.0 | 0.0 | 0.0 | 0.00 | 0.00 | 0.00 | 0.00 | |
| 2,450.0 | 23.00 | 215.40 | 2,419.4 | -185.6 | -131.9 | 2.00 | 2.00 | 0.00 | 215.40 | |
| 6,300.1 | 23.00 | 215.40 | 5,963.4 | -1,411.9 | -1,003.4 | 0.00 | 0.00 | 0.00 | 0.00 | |
| 7,450.1 | 0.00 | 0.00 | 7,082.8 | -1,597.5 | -1,135.3 | 2.00 | -2.00 | 12.57 | 180.00 | |
| 8,954.1 | 0.00 | 0.00 | 8,586.8 | -1,597.5 | -1,135.3 | 0.00 | 0.00 | 0.00 | 0.00 | |
| 10,079.1 | 90.00 | 179.65 | 9,303.0 | -2,313.7 | -1,130.9 | 8.00 | 8.00 | 0.00 | 179.65 | |
| 10,979.1 | 90.00 | 179.65 | 9,303.0 | -3,213.7 | -1,125.4 | 0.00 | 0.00 | 0.00 | 0.00 | |
| 12,142.9 | 90.00 | 202.93 | 9,303.0 | -4,347.1 | -1,351.7 | 2.00 | 0.00 | 2.00 | 90.00 | |
| 13,310.7 | 90.00 | 179.57 | 9,303.0 | -5,484.5 | -1,577.9 | 2.00 | 0.00 | -2.00 | -90.00 | |
| 18,081.9 | 90.00 | 179.57 | 9,303.0 | -10,255.6 | -1,542.2 | 0.00 | 0.00 | 0.00 | 0.00 l | TP PLU 18-30 BD 2 |
| 18,171.9 | 90.00 | 179.57 | 9,303.0 | -10,345.6 | -1,541.5 | 0.00 | 0.00 | 0.00 | 0.00 E | 3HL PLU 18-30 BD 2 |

Database: EDM 5000.18 Single User Db

Company: ROC

 Project:
 Long Lead - PLU 18-30 BD

 Site:
 Poker Lake Unit 18-30 BD

 Well:
 Poker Lake Unit 18-30 BD 201H

Wellbore: OH
Design: Plan 0

Local Co-ordinate Reference:

TVD Reference:
MD Reference:
North Reference:

Survey Calculation Method:

Well Poker Lake Unit 18-30 BD 201H

RKB @ 3212.0usft RKB @ 3212.0usft

Grid

| lanned Survey | | | | | | | | | |
|-----------------------------|--------------------|------------------|-----------------------------|------------------|------------------|-------------------------------|-------------------------------|------------------------------|-----------------------------|
| Measured Depth (usft) | Inclination (°) | Azimuth (°) | Vertical Depth (usft) | +N/-S (usft) | +E/-W (usft) | Vertical Section (usft) | Dogleg Rate (°/100usft) | Build Rate (°/100usft) | Turn Rate (°/100usft) |
| 0.0 | 0.00 | 0.00 | 0.0 | 0.0 | 0.0 | 0.0 | 0.00 | 0.00 | 0.00 |
| 100.0 | 0.00 | 0.00 | 100.0 | 0.0 | 0.0 | 0.0 | 0.00 | 0.00 | 0.00 |
| 200.0 | 0.00 | 0.00 | 200.0 | 0.0 | 0.0 | 0.0 | 0.00 | 0.00 | 0.00 |
| 300.0 400.0 | 0.00 0.00 | 0.00 0.00 | 300.0 400.0 | 0.0 0.0 | 0.0 0.0 | 0.0 0.0 | 0.00 0.00 | 0.00 0.00 | 0.00 0.00 |
| | | | | | | | | | |
| 500.0 | 0.00 | 0.00 | 500.0 | 0.0 | 0.0 | 0.0 | 0.00 | 0.00 | 0.00 |
| 600.0 | 0.00 | 0.00 | 600.0 | 0.0 | 0.0 | 0.0 | 0.00 | 0.00 | 0.00 |
| 700.0 | 0.00 | 0.00 | 700.0 | 0.0 | 0.0 | 0.0 | 0.00 | 0.00 | 0.00 |
| 800.0 | 0.00 | 0.00 | 800.0 | 0.0 | 0.0 | 0.0 | 0.00 | 0.00 | 0.00 |
| 900.0 | 0.00 | 0.00 | 900.0 | 0.0 | 0.0 | 0.0 | 0.00 | 0.00 | 0.00 |
| 1,000.0 | 0.00 | 0.00 | 1,000.0 | 0.0 | 0.0 | 0.0 | 0.00 | 0.00 | 0.00 |
| 1,100.0 | 0.00 | 0.00 | 1,100.0 | 0.0 | 0.0 | 0.0 | 0.00 | 0.00 | 0.00 |
| 1,200.0 | 0.00 | 0.00 | 1,200.0 | 0.0 | 0.0 | 0.0 | 0.00 | 0.00 | 0.00 |
| 1,300.0 | 0.00 | 0.00 | 1,300.0 | 0.0 | 0.0 | 0.0 | 0.00 | 0.00 | 0.00 |
| 1,400.0 | 2.00 | 215.40 | 1,400.0 | -1.4 | -1.0 | 1.5 | 2.00 | 2.00 | 0.00 |
| 1,500.0 | 4.00 | 215.40 | 1,499.8 | -5.7 | -4.0 | 6.0 | 2.00 | 2.00 | 0.00 |
| 1,600.0 | 6.00 | 215.40 | 1,599.5 | -12.8 | -9.1 | 13.4 | 2.00 | 2.00 | 0.00 |
| 1,700.0 | 8.00 | 215.40 | 1,698.7 | -22.7 | -16.2 | 23.8 | 2.00 | 2.00 | 0.00 |
| 1,800.0 | 10.00 | 215.40 | 1,797.5 | -35.5 | -25.2 | 37.2 | 2.00 | 2.00 | 0.00 |
| 1,900.0 | 12.00 | 215.40 | 1,895.6 | -51.0 | -36.3 | 53.5 | 2.00 | 2.00 | 0.00 |
| 2,000.0 | 14.00 | 215.40 | 1,993.1 | -69.4 | -49.3 | 72.7 | 2.00 | 2.00 | 0.00 |
| 2,100.0 | 16.00 | 215.40 | 2,089.6 | -90.5 | -64.3 | 94.9 | 2.00 | 2.00 | 0.00 |
| 2,200.0 | 18.00 | 215.40 | 2,185.3 | -114.3 | -81.2 | 119.8 | 2.00 | 2.00 | 0.00 |
| 2,300.0 | 20.00 | 215.40 | 2,279.8 | -140.8 | -100.1 | 147.7 | 2.00 | 2.00 | 0.00 |
| 2,400.0 | 22.00 | 215.40 | 2,373.2 | -170.0 | -120.8 | 178.3 | 2.00 | 2.00 | 0.00 |
| 2.450.0 | 22.00 | 215 40 | 2,419.4 | -185.6 | 121.0 | 194.7 | 2.00 | 2.00 | 0.00 |
| 2,450.0 2,500.0 | 23.00 23.00 | 215.40 215.40 | 2,419.4 | -105.0 -201.6 | -131.9 -143.2 | 211.4 | 0.00 | 2.00 0.00 | 0.00 |
| 2,600.0 | 23.00 | 215.40 | 2,557.4 | -233.4 | -165.9 | 244.7 | 0.00 | 0.00 | 0.00 |
| 2,700.0 | 23.00 | 215.40 | 2,649.5 | -265.3 | -188.5 | 278.1 | 0.00 | 0.00 | 0.00 |
| 2,800.0 | 23.00 | 215.40 | 2,741.5 | -297.1 | -211.1 | 311.5 | 0.00 | 0.00 | 0.00 |
| | | | | | | | | | |
| 2,900.0 | 23.00 | 215.40 | 2,833.6 | -329.0 | -233.8 | 344.9 | 0.00 | 0.00 | 0.00 |
| 3,000.0 3,100.0 | 23.00 23.00 | 215.40 215.40 | 2,925.6 3,017.7 | -360.8 -392.7 | -256.4 -279.0 | 378.3 411.7 | 0.00 | 0.00 0.00 | 0.00 0.00 |
| 3,200.0 | 23.00 | 215.40 | 3,109.7 | -392.7 -424.5 | -279.0 -301.7 | 445.1 | 0.00 0.00 | 0.00 | 0.00 |
| 3,300.0 | 23.00 | 215.40 | 3,201.8 | -424.3 -456.4 | -324.3 | 478.5 | 0.00 | 0.00 | 0.00 |
| | | | | | | | | | |
| 3,400.0 | 23.00 | 215.40 | 3,293.8 | -488.2 | -346.9 | 511.9 | 0.00 | 0.00 | 0.00 |
| 3,500.0 | 23.00 | 215.40 | 3,385.9 | -520.1 | -369.6 | 545.3 | 0.00 | 0.00 | 0.00 |
| 3,600.0 | 23.00 | 215.40 | 3,477.9 | -551.9 | -392.2 | 578.7 | 0.00 | 0.00 | 0.00 |
| 3,700.0 | 23.00 | 215.40 | 3,570.0 | -583.8 | -414.9 | 612.1 | 0.00 | 0.00 | 0.00 |
| 3,800.0 | 23.00 | 215.40 | 3,662.0 | -615.6 | -437.5 | 645.5 | 0.00 | 0.00 | 0.00 |
| 3,900.0 | 23.00 | 215.40 | 3,754.1 | -647.5 | -460.1 | 678.9 | 0.00 | 0.00 | 0.00 |
| 4,000.0 | 23.00 | 215.40 | 3,846.1 | -679.3 | -482.8 | 712.3 | 0.00 | 0.00 | 0.00 |
| 4,100.0 | 23.00 | 215.40 | 3,938.2 | -711.2 | -505.4 | 745.7 | 0.00 | 0.00 | 0.00 |
| 4,200.0 | 23.00 | 215.40 | 4,030.2 | -743.0 | -528.0 | 779.1 | 0.00 | 0.00 | 0.00 |
| 4,300.0 | 23.00 | 215.40 | 4,122.3 | -774.9 | -550.7 | 812.5 | 0.00 | 0.00 | 0.00 |
| 4,400.0 | 23.00 | 215.40 | 4,214.3 | -806.7 | -573.3 | 845.9 | 0.00 | 0.00 | 0.00 |
| 4,500.0 | 23.00 | 215.40 | 4,306.4 | -838.6 | -595.9 | 879.3 | 0.00 | 0.00 | 0.00 |
| 4,600.0 | 23.00 | 215.40 | 4,398.4 | -870.4 | -618.6 | 912.7 | 0.00 | 0.00 | 0.00 |
| 4,700.0 | 23.00 | 215.40 | 4,490.5 | -902.3 | -641.2 | 946.1 | 0.00 | 0.00 | 0.00 |
| 4,800.0 | 23.00 | 215.40 | 4,582.5 | -934.1 | -663.8 | 979.5 | 0.00 | 0.00 | 0.00 |
| 4,900.0 | 23.00 | 215.40 | 4,674.6 | -965.9 | -686.5 | 1,012.9 | 0.00 | 0.00 | 0.00 |
| 5,000.0 | 23.00 | 215.40 | 4,766.6 | -997.8 | -709.1 | 1,046.3 | 0.00 | 0.00 | 0.00 |
| 5,100.0 | 23.00 | 215.40 | 4,858.7 | -1,029.6 | -731.7 | 1,079.7 | 0.00 | 0.00 | 0.00 |
| 5,200.0 | 23.00 | 215.40 | 4,950.8 | -1,061.5 | -754.4 | 1,113.1 | 0.00 | 0.00 | 0.00 |

Database: EDM 5000.18 Single User Db

Company: ROC

 Project:
 Long Lead - PLU 18-30 BD

 Site:
 Poker Lake Unit 18-30 BD

 Well:
 Poker Lake Unit 18-30 BD 201H

Wellbore: OH
Design: Plan 0

Local Co-ordinate Reference:

TVD Reference: MD Reference: North Reference:

Survey Calculation Method:

Well Poker Lake Unit 18-30 BD 201H

RKB @ 3212.0usft RKB @ 3212.0usft

Grid

| nned Survey | | | | | | | | | |
|-----------------------------|--------------------|------------------|-----------------------------|----------------------|----------------------|-------------------------------|-------------------------------|------------------------------|-----------------------------|
| Measured Depth (usft) | Inclination (°) | Azimuth (°) | Vertical Depth (usft) | +N/-S (usft) | +E/-W (usft) | Vertical Section (usft) | Dogleg Rate (°/100usft) | Build Rate (°/100usft) | Turn Rate (°/100usft) |
| 5,300.0 | 23.00 | 215.40 | 5,042.8 | -1,093.3 | -777.0 | 1,146.5 | 0.00 | 0.00 | 0.00 |
| 5,400.0 | 23.00 | 215.40 | 5,134.9 | -1,125.2 | -799.6 | 1,179.9 | 0.00 | 0.00 | 0.00 |
| 5,500.0 | 23.00 | 215.40 | 5,226.9 | -1,157.0 | -822.3 | 1,213.3 | 0.00 | 0.00 | 0.00 |
| 5,600.0 | 23.00 | 215.40 | 5,319.0 | -1,188.9 | -844.9 | 1,246.7 | 0.00 | 0.00 | 0.00 |
| 5,700.0 | 23.00 | 215.40 | 5,411.0 | -1,220.7 | -867.5 | 1,280.1 | 0.00 | 0.00 | 0.00 |
| 5,800.0 | 23.00 | 215.40 | 5,503.1 | -1,252.6 | -890.2 | 1,313.5 | 0.00 | 0.00 | 0.00 |
| 5,900.0 | 23.00 | 215.40 | 5,595.1 | -1,284.4 | -912.8 | 1,346.8 | 0.00 | 0.00 | 0.00 |
| 6,000.0 | 23.00 | 215.40 | 5,687.2 | -1,316.3 | -935.4 | 1,380.2 | 0.00 | 0.00 | 0.00 |
| 6,100.0 | 23.00 | 215.40 | 5,779.2 | -1,348.1 | -958.1 | 1,413.6 | 0.00 | 0.00 | 0.00 |
| 6,200.0 | 23.00 | 215.40 | 5,871.3 | -1,380.0 | -980.7 | 1,447.0 | 0.00 | 0.00 | 0.00 |
| 6,300.0 | 23.00 | 215.40 | 5,963.3 | -1,411.8 | -1,003.3 | 1,480.4 | 0.00 | 0.00 | 0.00 |
| 6,300.1 | 23.00 | 215.40 | 5,963.4 | -1,411.9 | -1,003.4 | 1,480.5 | 0.00 | 0.00 | 0.00 |
| 6,400.0 | 21.00 | 215.40 | 6,056.0 | -1,442.4 | -1,025.0 | 1,512.5 | 2.00 | -2.00 | 0.00 |
| 6,500.0 | 19.00 | 215.40 | 6,150.0 | -1,470.3 | -1,044.9 | 1,541.7 | 2.00 | -2.00 | 0.00 |
| 6,600.0 | 17.00 | 215.40 | 6,245.1 | -1,495.5 | -1,062.8 | 1,568.1 | 2.00 | -2.00 | 0.00 |
| 6,700.0 | 15.00 | 215.40 | 6,341.2 | -1,517.9 | -1,078.7 | 1,591.7 | 2.00 | -2.00 | 0.00 |
| 6,800.0 | 13.00 | 215.40 | 6,438.2 | -1,537.6 | -1,092.7 | 1,612.3 | 2.00 | -2.00 | 0.00 |
| 6,900.0 | 11.00 | 215.40 | 6,536.0 | -1,554.6 | -1,104.8 | 1,630.1 | 2.00 | -2.00 | 0.00 |
| 7,000.0 | 9.00 | 215.40 | 6,634.5 | -1,568.7 | -1,114.9 | 1,645.0 | 2.00 | -2.00 | 0.00 |
| 7,100.0 | 7.00 | 215.40 | 6,733.5 | -1,580.1 | -1,122.9 | 1,656.9 | 2.00 | -2.00 | 0.00 |
| 7,200.0 | 5.00 | 215.40 | 6,833.0 | -1,588.6 | -1,129.0 | 1,665.8 | 2.00 | -2.00 | 0.00 |
| 7,300.0 | 3.00 | 215.40 | 6,932.7 | -1,594.3 | -1,133.0 | 1,671.8 | 2.00 | -2.00 | 0.00 |
| 7,400.0 | 1.00 | 215.40 | 7,032.7 | -1,597.2 | -1,135.0 | 1,674.8 | 2.00 | -2.00 | 0.00 |
| 7,450.1 | 0.00 | 0.00 | 7,082.8 | -1,597.5 | -1,135.3 | 1,675.1 | 2.00 | -2.00 | 288.62 |
| 7,500.0 | 0.00 | 0.00 | 7,132.7 | -1,597.5 | -1,135.3 | 1,675.1 | 0.00 | 0.00 | 0.00 |
| 7,600.0 | 0.00 | 0.00 | 7,232.7 | -1,597.5 | -1,135.3 | 1,675.1 | 0.00 | 0.00 | 0.00 |
| 7,700.0 | 0.00 | 0.00 | 7,332.7 | -1,597.5 | -1,135.3 | 1,675.1 | 0.00 | 0.00 | 0.00 |
| 7,800.0 | 0.00 | 0.00 | 7,432.7 | -1,597.5 | -1,135.3 | 1,675.1 | 0.00 | 0.00 | 0.00 |
| 7,900.0 | 0.00 | 0.00 | 7,532.7 | -1,597.5 | -1,135.3 | 1,675.1 | 0.00 | 0.00 | 0.00 |
| 8,000.0 | 0.00 | 0.00 | 7,632.7 | -1,597.5 | -1,135.3 | 1,675.1 | 0.00 | 0.00 | 0.00 |
| 8,100.0 | 0.00 | 0.00 | 7,732.7 | -1,597.5 | -1,135.3 | 1,675.1 | 0.00 | 0.00 | 0.00 |
| 8,200.0 | 0.00 | 0.00 | 7,832.7 | -1,597.5 | -1,135.3 | 1,675.1 | 0.00 | 0.00 | 0.00 |
| 8,300.0 | 0.00 | 0.00 | 7,932.7 | -1,597.5 | -1,135.3 | 1,675.1 | 0.00 | 0.00 | 0.00 |
| 8,400.0 | 0.00 | 0.00 | 8,032.7 | -1,597.5 | -1,135.3 | 1,675.1 | 0.00 | 0.00 | 0.00 |
| 8,500.0 | 0.00 | 0.00 | 8,132.7 | -1,597.5 | -1,135.3 | 1,675.1 | 0.00 | 0.00 | 0.00 |
| 8,600.0 | 0.00 | 0.00 | 8,232.7 | -1,597.5 | -1,135.3 | 1,675.1 | 0.00 | 0.00 | 0.00 |
| 8,700.0 | 0.00 | 0.00 | 8,332.7 | -1,597.5 | -1,135.3 | 1,675.1 | 0.00 | 0.00 | 0.00 |
| 8,800.0 | 0.00 | 0.00 | 8,432.7 | -1,597.5 | -1,135.3 | 1,675.1 | 0.00 | 0.00 | 0.00 |
| 8,900.0 | 0.00 | 0.00 | 8,532.7 | -1,597.5 | -1,135.3 | 1,675.1 | 0.00 | 0.00 | 0.00 |
| 8,954.1 | 0.00 | 0.00 | 8,586.8 | -1,597.5 | -1,135.3 | 1,675.1 | 0.00 | 0.00 | 0.00 |
| 9,000.0 | 3.67 | 179.65 | 8,632.6 | -1,597.5 | -1,135.3 | 1,676.6 | 8.00 | 8.00 | 391.73 |
| 9,000.0 | 3.67 11.67 | 179.65 | 8,731.7 | -1,599.0 -1,612.3 | -1,135.3 -1,135.2 | 1,689.9 | 8.00 | 8.00 | 0.00 |
| 9,200.0 | 19.67 | 179.65 | 8,827.9 | -1,639.3 | -1,135.0 | 1,716.8 | 8.00 | 8.00 | 0.00 |
| 9,300.0 | 27.67 | 179.65 | 8,919.4 | -1,679.4 | -1,133.0 | 1,710.8 | 8.00 | 8.00 | 0.00 |
| 9,300.0 | | | 9,004.4 | -1,679.4 -1,731.9 | | | | | 0.00 |
| | 35.67 | 179.65 | | | -1,134.5 | 1,809.1 | 8.00 | 8.00 | |
| 9,500.0 9,600.0 | 43.67 51.67 | 179.65 179.65 | 9,081.3 9,148.6 | -1,795.6 -1,869.5 | -1,134.1 -1,133.6 | 1,872.7 1,946.3 | 8.00 8.00 | 8.00 8.00 | 0.00 0.00 |
| 9,700.0 | 59.67 | 179.65 | 9,205.0 | -1,952.0 | -1,133.0 | 2,028.6 | 8.00 | 8.00 | 0.00 |
| | | | | | | | | | |
| 9,800.0 | 67.67 | 179.65 | 9,249.3 | -2,041.6 | -1,132.6 | 2,117.8 | 8.00 | 8.00 | 0.00 |
| 9,900.0 | 75.67 | 179.65 | 9,280.7 | -2,136.4 | -1,132.0 | 2,212.4 | 8.00 | 8.00 | 0.00 |
| 10,000.0 10,079.1 | 83.67 90.00 | 179.65 179.65 | 9,298.6 9,303.0 | -2,234.7 -2,313.7 | -1,131.4 -1,130.9 | 2,310.4 2,389.1 | 8.00 8.00 | 8.00 8.00 | 0.00 0.00 |
| 10,100.0 | 90.00 | 179.65 | 9,303.0 | -2,313.7 -2,334.6 | -1,130.9 | 2,409.9 | 0.00 | 0.00 | 0.00 |
| 10,100.0 | 90.00 | 179.65 | 9,303.0 | -2,334.6 -2,434.6 | -1,130.6 | 2,409.9 | 0.00 | 0.00 | 0.00 |

Database: Company:

Project:

Site:

Well:

EDM 5000.18 Single User Db

ROC

Long Lead - PLU 18-30 BD Poker Lake Unit 18-30 BD Poker Lake Unit 18-30 BD 201H

Wellbore: OH
Design: Plan 0

Local Co-ordinate Reference:

TVD Reference:
MD Reference:
North Reference:

Survey Calculation Method:

Well Poker Lake Unit 18-30 BD 201H

RKB @ 3212.0usft RKB @ 3212.0usft

Grid

| esign: | FIAII U | | | | | | | | |
|-----------------------------|--------------------|------------------|-----------------------------|----------------------|----------------------|-------------------------------|-------------------------------|------------------------------|-----------------------------|
| anned Survey | | | | | | | | | |
| Measured Depth (usft) | Inclination (°) | Azimuth (°) | Vertical Depth (usft) | +N/-S (usft) | +E/-W (usft) | Vertical Section (usft) | Dogleg Rate (°/100usft) | Build Rate (°/100usft) | Turn Rate (°/100usft) |
| 10,300.0 | 90.00 | 179.65 | 9,303.0 | -2,534.5 | -1,129.6 | 2,609.3 | 0.00 | 0.00 | 0.00 |
| 10,400.0 | 90.00 | 179.65 | 9,303.0 | -2,634.5 | -1,129.0 | 2,709.0 | 0.00 | 0.00 | 0.00 |
| 10,500.0 | 90.00 | 179.65 | 9,303.0 | -2,734.5 | -1,128.3 | 2,808.7 | 0.00 | 0.00 | 0.00 |
| 10,600.0 10,700.0 | 90.00 90.00 | 179.65 179.65 | 9,303.0 9,303.0 | -2,834.5 -2,934.5 | -1,127.7 -1,127.1 | 2,908.4 3,008.1 | 0.00 0.00 | 0.00 0.00 | 0.00 0.00 |
| 10,800.0 | 90.00 | 179.65 | 9,303.0 | -3,034.5 | -1,126.5 | 3,107.8 | 0.00 | 0.00 | 0.00 |
| 10,900.0 | 90.00 | 179.65 | 9,303.0 | -3,134.5 | -1,125.9 | 3,207.5 | 0.00 | 0.00 | 0.00 |
| 10,979.1 | 90.00 | 179.65 | 9,303.0 | -3,213.7 | -1,125.4 | 3,286.4 | 0.00 | 0.00 | 0.00 |
| 11,000.0 | 90.00 | 180.07 | 9,303.0 | -3,234.5 | -1,125.4 | 3,307.2 | 2.00 | 0.00 | 2.00 |
| 11,100.0 | 90.00 | 182.07 | 9,303.0 | -3,334.5 | -1,127.2 | 3,407.0 | 2.00 | 0.00 | 2.00 |
| 11,200.0 | 90.00 | 184.07 | 9,303.0 | -3,434.4 | -1,132.6 | 3,507.0 | 2.00 | 0.00 | 2.00 |
| 11,300.0 | 90.00 | 186.07 | 9,303.0 | -3,534.0 | -1,141.4 | 3,607.0 | 2.00 | 0.00 | 2.00 |
| 11,400.0 | 90.00 | 188.07 | 9,303.0 | -3,633.2 | -1,153.7 | 3,706.9 | 2.00 | 0.00 | 2.00 |
| 11,500.0 | 90.00 | 190.07 | 9,303.0 | -3,732.0 | -1,169.5 | 3,806.5 | 2.00 | 0.00 | 2.00 |
| 11,600.0 | 90.00 | 192.07 | 9,303.0 | -3,830.1 | -1,188.7 | 3,905.7 | 2.00 | 0.00 | 2.00 |
| 11,700.0 | 90.00 | 194.07 | 9,303.0 | -3,927.5 | -1,211.3 | 4,004.5 | 2.00 | 0.00 | 2.00 |
| 11,800.0 | 90.00 | 196.07 | 9,303.0 | -4,024.0 | -1,237.3 | 4,102.7 | 2.00 | 0.00 | 2.00 |
| 11,900.0 | 90.00 | 198.07 | 9,303.0 | -4,119.6 | -1,266.6 | 4,200.2 | 2.00 | 0.00 | 2.00 |
| 12,000.0 | 90.00 | 200.07 | 9,303.0 | -4,214.1 | -1,299.3 | 4,296.8 | 2.00 | 0.00 | 2.00 |
| 12,100.0 | 90.00 | 202.07 | 9,303.0 | -4,307.5 | -1,335.2 | 4,392.4 | 2.00 | 0.00 | 2.00 |
| 12,142.9 12,200.0 | 90.00 90.00 | 202.93 201.78 | 9,303.0 9,303.0 | -4,347.1 -4,399.9 | -1,351.7 -1,373.4 | 4,433.2 4,487.4 | 2.00 2.00 | 0.00 0.00 | 2.00 -2.00 |
| | | | | • | | , | | | |
| 12,300.0 12,400.0 | 90.00 90.00 | 199.78 197.78 | 9,303.0 9,303.0 | -4,493.4 -4,588.1 | -1,408.8 -1,441.0 | 4,583.2 4,679.9 | 2.00 2.00 | 0.00 0.00 | -2.00 -2.00 |
| 12,500.0 | 90.00 | 195.78 | 9,303.0 | -4,566.1 -4,683.8 | -1,441.0 | 4,079.9 | 2.00 | 0.00 | -2.00 |
| 12,600.0 | 90.00 | 193.78 | 9,303.0 | -4,780.5 | -1,495.4 | 4,875.8 | 2.00 | 0.00 | -2.00 |
| 12,700.0 | 90.00 | 191.78 | 9,303.0 | -4,878.0 | -1,517.6 | 4,974.6 | 2.00 | 0.00 | -2.00 |
| 12,800.0 | 90.00 | 189.78 | 9,303.0 | -4,976.2 | -1,536.3 | 5,073.9 | 2.00 | 0.00 | -2.00 |
| 12,900.0 | 90.00 | 187.78 | 9,303.0 | -5,075.0 | -1,551.5 | 5,173.6 | 2.00 | 0.00 | -2.00 |
| 13,000.0 | 90.00 | 185.78 | 9,303.0 | -5,174.3 | -1,563.4 | 5,273.5 | 2.00 | 0.00 | -2.00 |
| 13,100.0 | 90.00 | 183.78 | 9,303.0 | -5,274.0 | -1,571.7 | 5,373.5 | 2.00 | 0.00 | -2.00 |
| 13,200.0 | 90.00 | 181.78 | 9,303.0 | -5,373.9 | -1,576.6 | 5,473.5 | 2.00 | 0.00 | -2.00 |
| 13,300.0 | 90.00 | 179.78 | 9,303.0 | -5,473.8 | -1,577.9 | 5,573.3 | 2.00 | 0.00 | -2.00 |
| 13,310.7 | 90.00 | 179.57 | 9,303.0 | -5,484.5 | -1,577.9 | 5,583.9 | 2.00 | 0.00 | -2.00 |
| 13,400.0 | 90.00 | 179.57 | 9,303.0 | -5,573.8 | -1,577.2 | 5,673.0 | 0.00 | 0.00 | 0.00 |
| 13,500.0 | 90.00 | 179.57 | 9,303.0 | -5,673.8 | -1,576.5 | 5,772.6 | 0.00 | 0.00 | 0.00 |
| 13,600.0 | 90.00 | 179.57 | 9,303.0 | -5,773.8 | -1,575.7 | 5,872.3 | 0.00 | 0.00 | 0.00 |
| 13,700.0 | 90.00 | 179.57 | 9,303.0 | -5,873.8 | -1,575.0 | 5,972.0 | 0.00 | 0.00 | 0.00 |
| 13,800.0 | 90.00 | 179.57 | 9,303.0 | -5,973.8 | -1,574.2 | 6,071.7 | 0.00 | 0.00 | 0.00 |
| 13,900.0 14,000.0 | 90.00 90.00 | 179.57 | 9,303.0 9,303.0 | -6,073.8 -6,173.8 | -1,573.5 | 6,171.4 6,271.1 | 0.00 | 0.00 | 0.00 |
| 14,000.0 | 90.00 | 179.57 179.57 | 9,303.0 | -6,173.8 -6,273.8 | -1,572.7 -1,572.0 | 6,370.7 | 0.00 0.00 | 0.00 0.00 | 0.00 0.00 |
| | | | | | | | | | 0.00 |
| 14,200.0 14,300.0 | 90.00 90.00 | 179.57 179.57 | 9,303.0 9,303.0 | -6,373.8 -6,473.8 | -1,571.2 -1,570.5 | 6,470.4 6,570.1 | 0.00 0.00 | 0.00 0.00 | 0.00 |
| 14,400.0 | 90.00 | 179.57 | 9,303.0 | -6,573.8 | -1,569.7 | 6,669.8 | 0.00 | 0.00 | 0.00 |
| 14,500.0 | 90.00 | 179.57 | 9,303.0 | -6,673.8 | -1,569.0 | 6,769.5 | 0.00 | 0.00 | 0.00 |
| 14,600.0 | 90.00 | 179.57 | 9,303.0 | -6,773.8 | -1,568.2 | 6,869.2 | 0.00 | 0.00 | 0.00 |
| 14,700.0 | 90.00 | 179.57 | 9,303.0 | -6,873.8 | -1,567.5 | 6,968.8 | 0.00 | 0.00 | 0.00 |
| 14,800.0 | 90.00 | 179.57 | 9,303.0 | -6,973.8 | -1,566.7 | 7,068.5 | 0.00 | 0.00 | 0.00 |
| 14,900.0 | 90.00 | 179.57 | 9,303.0 | -7,073.8 | -1,566.0 | 7,168.2 | 0.00 | 0.00 | 0.00 |
| 15,000.0 | 90.00 | 179.57 | 9,303.0 | -7,173.8 | -1,565.2 | 7,267.9 | 0.00 | 0.00 | 0.00 |
| 15,100.0 | 90.00 | 179.57 | 9,303.0 | -7,273.8 | -1,564.5 | 7,367.6 | 0.00 | 0.00 | 0.00 |
| 15,200.0 | 90.00 | 179.57 | 9,303.0 | -7,373.8 | -1,563.7 | 7,467.3 | 0.00 | 0.00 | 0.00 |
| 15,300.0 | 90.00 | 179.57 | 9,303.0 | -7,473.8 | -1,563.0 | 7,567.0 | 0.00 | 0.00 | 0.00 |

Database: Company:

Site:

Well:

EDM 5000.18 Single User Db

Long Lead - PLU 18-30 BD Project: Poker Lake Unit 18-30 BD Poker Lake Unit 18-30 BD 201H

ОН Wellbore: Design: Plan 0 Local Co-ordinate Reference:

TVD Reference: MD Reference: North Reference:

Survey Calculation Method:

Well Poker Lake Unit 18-30 BD 201H

RKB @ 3212.0usft RKB @ 3212.0usft

Grid

| ed Survey | | | | | | | | | |
|-----------------------------|--------------------|----------------|-----------------------------|-----------------|-----------------|-------------------------------|-------------------------------|------------------------------|-----------------------------|
| Measured Depth (usft) | Inclination (°) | Azimuth (°) | Vertical Depth (usft) | +N/-S (usft) | +E/-W (usft) | Vertical Section (usft) | Dogleg Rate (°/100usft) | Build Rate (°/100usft) | Turn Rate (°/100usft) |
| 15,400.0 | 90.00 | 179.57 | 9,303.0 | -7,573.8 | -1,562.3 | 7,666.6 | 0.00 | 0.00 | 0.00 |
| 15,500.0 | 90.00 | 179.57 | 9,303.0 | -7,673.8 | -1,561.5 | 7,766.3 | 0.00 | 0.00 | 0.00 |
| 15,600.0 | 90.00 | 179.57 | 9,303.0 | -7,773.8 | -1,560.8 | 7,866.0 | 0.00 | 0.00 | 0.00 |
| 15,700.0 | 90.00 | 179.57 | 9,303.0 | -7,873.8 | -1,560.0 | 7,965.7 | 0.00 | 0.00 | 0.00 |
| 15,800.0 | 90.00 | 179.57 | 9,303.0 | -7,973.8 | -1,559.3 | 8,065.4 | 0.00 | 0.00 | 0.00 |
| 15,900.0 | 90.00 | 179.57 | 9,303.0 | -8,073.8 | -1,558.5 | 8,165.1 | 0.00 | 0.00 | 0.00 |
| 16,000.0 | 90.00 | 179.57 | 9,303.0 | -8,173.8 | -1,557.8 | 8,264.7 | 0.00 | 0.00 | 0.00 |
| 16,100.0 | 90.00 | 179.57 | 9,303.0 | -8,273.8 | -1,557.0 | 8,364.4 | 0.00 | 0.00 | 0.00 |
| 16,200.0 | 90.00 | 179.57 | 9,303.0 | -8,373.8 | -1,556.3 | 8,464.1 | 0.00 | 0.00 | 0.00 |
| 16,300.0 | 90.00 | 179.57 | 9,303.0 | -8,473.8 | -1,555.5 | 8,563.8 | 0.00 | 0.00 | 0.00 |
| 16,400.0 | 90.00 | 179.57 | 9,303.0 | -8,573.8 | -1,554.8 | 8,663.5 | 0.00 | 0.00 | 0.00 |
| 16,500.0 | 90.00 | 179.57 | 9,303.0 | -8,673.8 | -1,554.0 | 8,763.2 | 0.00 | 0.00 | 0.00 |
| 16,600.0 | 90.00 | 179.57 | 9,303.0 | -8,773.8 | -1,553.3 | 8,862.8 | 0.00 | 0.00 | 0.00 |
| 16,700.0 | 90.00 | 179.57 | 9,303.0 | -8,873.8 | -1,552.5 | 8,962.5 | 0.00 | 0.00 | 0.00 |
| 16,800.0 | 90.00 | 179.57 | 9,303.0 | -8,973.8 | -1,551.8 | 9,062.2 | 0.00 | 0.00 | 0.00 |
| 16,900.0 | 90.00 | 179.57 | 9,303.0 | -9,073.7 | -1,551.0 | 9,161.9 | 0.00 | 0.00 | 0.00 |
| 17,000.0 | 90.00 | 179.57 | 9,303.0 | -9,173.7 | -1,550.3 | 9,261.6 | 0.00 | 0.00 | 0.00 |
| 17,100.0 | 90.00 | 179.57 | 9,303.0 | -9,273.7 | -1,549.5 | 9,361.3 | 0.00 | 0.00 | 0.00 |
| 17,200.0 | 90.00 | 179.57 | 9,303.0 | -9,373.7 | -1,548.8 | 9,460.9 | 0.00 | 0.00 | 0.00 |
| 17,300.0 | 90.00 | 179.57 | 9,303.0 | -9,473.7 | -1,548.0 | 9,560.6 | 0.00 | 0.00 | 0.00 |
| 17,400.0 | 90.00 | 179.57 | 9,303.0 | -9,573.7 | -1,547.3 | 9,660.3 | 0.00 | 0.00 | 0.00 |
| 17,500.0 | 90.00 | 179.57 | 9,303.0 | -9,673.7 | -1,546.6 | 9,760.0 | 0.00 | 0.00 | 0.00 |
| 17,600.0 | 90.00 | 179.57 | 9,303.0 | -9,773.7 | -1,545.8 | 9,859.7 | 0.00 | 0.00 | 0.00 |
| 17,700.0 | 90.00 | 179.57 | 9,303.0 | -9,873.7 | -1,545.1 | 9,959.4 | 0.00 | 0.00 | 0.00 |
| 17,800.0 | 90.00 | 179.57 | 9,303.0 | -9,973.7 | -1,544.3 | 10,059.0 | 0.00 | 0.00 | 0.00 |
| 17,900.0 | 90.00 | 179.57 | 9,303.0 | -10,073.7 | -1,543.6 | 10,158.7 | 0.00 | 0.00 | 0.00 |
| 18,000.0 | 90.00 | 179.57 | 9,303.0 | -10,173.7 | -1,542.8 | 10,258.4 | 0.00 | 0.00 | 0.00 |
| 18,081.9 | 90.00 | 179.57 | 9,303.0 | -10,255.6 | -1,542.2 | 10,340.0 | 0.00 | 0.00 | 0.00 |
| 18,100.0 | 90.00 | 179.57 | 9,303.0 | -10,273.7 | -1,542.1 | 10,358.1 | 0.00 | 0.00 | 0.00 |
| 18,171.9 | 90.00 | 179.57 | 9,303.0 | -10,345.6 | -1,541.5 | 10,429.8 | 0.00 | 0.00 | 0.00 |

Database: EDM 5000.18 Single User Db

Company: ROC

 Project:
 Long Lead - PLU 18-30 BD

 Site:
 Poker Lake Unit 18-30 BD

 Well:
 Poker Lake Unit 18-30 BD 201H

Wellbore: OH
Design: Plan 0

Local Co-ordinate Reference:

TVD Reference:
MD Reference:
North Reference:

Survey Calculation Method:

Well Poker Lake Unit 18-30 BD 201H

RKB @ 3212.0usft RKB @ 3212.0usft

Grid

| Design Targets | | | | | | | | | |
|-----------------------------------------------------------------------|------------------|------------------------|-------------------------|----------------------------|----------------------------|-----------------------|-------------------|-----------------|-------------------|
| Target Name - hit/miss target - Shape | Dip Angle (°) | Dip Dir. (°) | TVD (usft) | +N/-S (usft) | +E/-W (usft) | Northing (usft) | Easting (usft) | Latitude | Longitude |
| PPP#2 PLU 18-30 BD 2 - plan misses target - Point | | 0.00 3.3usft at 0.0 | 0.0 usft MD (0.0 | -2,378.1 TVD, 0.0 N, | -1,130.8 0.0 E) | 411,262.60 | 627,042.00 | 32° 7' 48.044 N | 103° 55' 22.565 W |
| PPP#3 PLU 18-30 BD 2 - plan misses target - Point | | 0.00 0.0usft at 0.0 | 0.0 usft MD (0.0 | -5,039.3 TVD, 0.0 N, | -1,542.1 0.0 E) | 408,601.40 | 626,630.70 | 32° 7' 21.723 N | 103° 55' 27.466 W |
| SHL PLU 18-30 BD 201 - plan hits target ce - Rectangle (sides \ | nter | 0.00 | 0.0 | 0.0 | 0.0 | 413,640.70 | 628,172.80 | 32° 8' 11.535 N | 103° 55' 9.309 W |
| PPP#1 PLU 18-30 BD 2 - plan misses target - Point | | 0.00 .0usft at 0.0u | 0.0 sft MD (0.0 | -431.5 TVD, 0.0 N, 0 | -306.0 .0 E) | 413,209.20 | 627,866.80 | 32° 8' 7.277 N | 103° 55' 12.887 W |
| P6 PLU 18-30 BD 201H - plan misses target - Point | | 0.00 usft at 12930 | 9,303.0 3usft MD (93 | -5,105.1 303.0 TVD, -5 | -1,555.2 105.1 N, -155 | 408,535.60 5.5 E) | 626,617.60 | 32° 7' 21.073 N | 103° 55' 27.621 W |
| P3 PLU 18-30 BD 201H - plan misses target - Point | | 0.00 usft at 11830. | 9,303.0 2usft MD (93 | -4,053.3 303.0 TVD, -4 | -1,244.9 053.0 N, -124 | 409,587.40 5.8 E) | 626,927.90 | 32° 7' 31.470 N | 103° 55' 23.966 W |
| P2 PLU 18-30 BD 201H - plan misses target - Point | | 0.00 usft at 11430. | 9,303.0 3usft MD (93 | -3,663.3 303.0 TVD, -3 | -1,157.7 663.2 N, -1158 | 409,977.40 3.1 E) | 627,015.10 | 32° 7' 35.326 N | 103° 55' 22.935 W |
| P4 PLU 18-30 BD 201H - plan misses target - Point | | 0.00 usft at 12180 | 9,303.0 1usft MD (93 | -4,381.9 303.0 TVD, -4 | -1,364.7 381.4 N, -136 | 409,258.80 5.9 E) | 626,808.10 | 32° 7' 28.223 N | 103° 55' 25.374 W |
| P1 PLU 18-30 BD 201H - plan hits target cel - Point | | 0.00 | 9,303.0 | -3,264.9 | -1,125.6 | 410,375.80 | 627,047.20 | 32° 7′ 39.268 N | 103° 55' 22.544 W |
| P5 PLU 18-30 BD 201H - plan misses target - Point | | 0.00 usft at 12530 | 9,303.0 2usft MD (93 | -4,713.1 303.0 TVD, -4 | -1,477.2 712.9 N, -147 | 408,927.60 8.0 E) | 626,695.60 | 32° 7′ 24.949 N | 103° 55' 26.697 W |
| P7 PLU 18-30 BD 201H - plan misses target - Point | | 0.00 usft at 13310 | 9,303.0 3usft MD (93 | -5,484.1 303.0 TVD, -5 | -1,578.0 484.1 N, -157 | 408,156.60 7.9 E) | 626,594.80 | 32° 7' 17.323 N | 103° 55' 27.903 W |
| BHL PLU 18-30 BD 201 - plan misses target - Point | | 0.00 usft at 18171. | 9,303.0 9usft MD (93 | -10,345.6 303.0 TVD, -1 | -1,541.6 0345.6 N, -15 | 403,295.10 41.5 E) | 626,631.20 | 32° 6' 29.211 N | 103° 55' 27.694 W |
| LTP PLU 18-30 BD 201 - plan hits target cel - Point | | 0.00 | 9,303.0 | -10,255.6 | -1,542.2 | 403,385.10 | 626,630.60 | 32° 6' 30.101 N | 103° 55' 27.697 W |
| FTP PLU 18-30 BD 201 - plan misses target - Point | | 0.00 usft at 10243 | 9,303.0 4usft MD (93 | -2,478.0 303.0 TVD, -2 | -1,130.2 478.0 N, -112 | 411,162.70 9.9 E) | 627,042.60 | 32° 7' 47.055 N | 103° 55' 22.563 W |

Database: EDM 5000.18 Single User Db

Company: ROO

Project: Long Lead - PLU 18-30 BD
Site: Poker Lake Unit 18-30 BD

 Well:
 Poker Lake Unit 18-30 BD 201H

 Wellbore:
 OH

 Design:
 Plan 0

Local Co-ordinate Reference:

TVD Reference:
MD Reference:
North Reference:


Survey Calculation Method:

Well Poker Lake Unit 18-30 BD 201H

RKB @ 3212.0usft RKB @ 3212.0usft

Grid

| rmations | | | | | | |
|----------|-----------------------------|-----------------------------|------------------------------------|-----------|------------|-------------------------|
| | Measured Depth (usft) | Vertical Depth (usft) | Name | Lithology | Dip (°) | Dip Direction (°) |
| | 771.0 | 771.0 | Rustler | | | |
| | 1,045.1 | 1,045.1 | Salado | | | |
| | 3,313.6 | 3,214.3 | Base of Salt | | | |
| | 3,730.5 | 3,598.0 | Delaware | | | |
| | 4,694.9 | 4,485.8 | Cherry Canyon | | | |
| | 6,341.8 | 6,001.9 | Brushy Canyon | | | |
| | 7,467.1 | 7,099.7 | Basal Brushy Canyon | | | |
| | 7,702.6 | 7,335.2 | Bone Spring Lm. | | | |
| | 7,808.9 | 7,441.6 | Avalon | | | |
| | 8,160.3 | 7,793.0 | Lower Avalon | | | |
| | 8,604.4 | 8,237.0 | 1st Bone Spring Sand | | | |
| | 8,906.0 | 8,538.6 | 2nd Bone Spring Shale | | | |
| | 9,075.8 | 8,707.9 | 2nd Bone Spring Lime | | | |
| | 9,230.7 | 8,856.6 | 2nd Bone Spring Sand | | | |
| | 9,343.9 | 9,303.0 | 2rd Bone Spring Sand Lower Landing | | | |



TenarisHydril Wedge 511



| Coupling | Pipe Body |
|----------------------|----------------------|
| Grade: P110-ICY | Grade: P110-ICY |
| Body: White | 1st Band: White |
| 1st Band: Pale Green | 2nd Band: Pale Green |
| 2nd Band: - | 3rd Band: Pale Green |
| 3rd Band: - | 4th Band: - |
| | 5th Band: - |
| | 6th Band: - |

| Outside Diameter | 7.625 in. | Wall Thickness | 0.375 in. | Grade | P110-ICY |
|----------------------|-----------|-----------------|--------------|-------|----------|
| Min. Wall Thickness | 90.00 % | Pipe Body Drift | API Standard | Туре | Casing |
| Connection OD Option | REGULAR | | | | |

Pipe Body Data

| Geometry | | | |
|----------------|-------------|------------------|-------------|
| Nominal OD | 7.625 in. | Wall Thickness | 0.375 in. |
| Nominal Weight | 29.70 lb/ft | Plain End Weight | 29.06 lb/ft |
| Drift | 6.750 in. | OD Tolerance | API |
| Nominal ID | 6.875 in. | | |

| Performance | |
|------------------------------|---------------|
| Body Yield Strength | 1068 x1000 lb |
| Min. Internal Yield Pressure | 11,070 psi |
| SMYS | 125,000 psi |
| Collapse Pressure | 7360 psi |

Connection Data

| Geometry | |
|----------------------|-----------|
| Connection OD | 7.625 in. |
| Connection ID | 6.787 in. |
| Make-up Loss | 3.704 in. |
| Threads per inch | 3.28 |
| Connection OD Option | Regular |
| Connection OD Option | Regula |

| Performance | |
|----------------------------|----------------|
| Tension Efficiency | 61.10 % |
| Joint Yield Strength | 653 x1000 lb |
| Internal Pressure Capacity | 11,070 psi |
| Compression Efficiency | 73.80 % |
| Compression Strength | 788 x1000 lb |
| Max. Allowable Bending | 45.83 °/100 ft |
| External Pressure Capacity | 7360 psi |

| Make-Up Torques | |
|-------------------------|--------------|
| Minimum | 5900 ft-lb |
| Optimum | 7100 ft-lb |
| Maximum | 10,300 ft-lb |
| Operation Limit Torques | |
| Operating Torque | 55,000 ft-lb |
| Yield Torque | 82,000 ft-lb |
| | |

Notes

For the lastest performance data, always visit our website: www.tenaris.com
For further information on concepts indicated in this datasheet, download the Datasheet Manual from www.tenaris.com

Tenaris has issued this document for general information only, and the information in this document, including, without limitation, any pictures, drawings or designs ("Information") is not intended to constitute professional or any other type of advice or recommendation and is provided on an "as is" basis. No warranty is given. Tenaris has not independently verified any information —if any- provided by the user in connection with, or for the purpose of, the Information contained hereunder. The use of the Information is at user's own risk and Tenaris does not assume any responsibility or liability of any kind for any loss, damage or injury resulting from, or in connection with any Information contained hereunder or any use thereof. The Information in this document is subject to change or modification without notice. Tenaris's products and services are subject to Tenaris's standard terms and conditions or otherwise to the terms resulting from the respective contracts of sale or services, as the case may be, between petitioner and Tenaris. For more complete information please contact a Tenaris's representative or visit our website at www.tenaris.com. ©Tenaris 2025. All rights reserved.



TenarisHydril Wedge 511



| Coupling | Pipe Body |
|-----------------|----------------------|
| Grade: L80-IC | Grade: L80-IC |
| Body: Red | 1st Band: Red |
| 1st Band: Brown | 2nd Band: Brown |
| 2nd Band: - | 3rd Band: Pale Green |
| 3rd Band: - | 4th Band: - |
| | 5th Band: - |
| | 6th Band: - |
| | |

| Outside Diameter | 7.625 in. | Wall Thickness | 0.375 in. | Grade | L80-IC |
|----------------------|-----------|-----------------|--------------|-------|--------|
| Min. Wall Thickness | 87.50 % | Pipe Body Drift | API Standard | Туре | Casing |
| Connection OD Option | REGULAR | | | | |

Pipe Body Data

| Geometry | | | |
|----------------|-------------|------------------|-------------|
| Nominal OD | 7.625 in. | Wall Thickness | 0.375 in. |
| Nominal Weight | 29.70 lb/ft | Plain End Weight | 29.06 lb/ft |
| Drift | 6.750 in. | OD Tolerance | API |
| Nominal ID | 6.875 in. | | |

| Performance | |
|------------------------------|--------------|
| Body Yield Strength | 683 x1000 lb |
| Min. Internal Yield Pressure | 6890 psi |
| SMYS | 80,000 psi |
| Collapse Pressure | 5900 psi |

Connection Data

| Geometry | |
|----------------------|-----------|
| Connection OD | 7.625 in. |
| Connection ID | 6.787 in. |
| Make-up Loss | 3.704 in. |
| Threads per inch | 328 |
| Connection OD Option | Regular |
| | |

| Performance | |
|----------------------------|----------------|
| Tension Efficiency | 61.10 % |
| Joint Yield Strength | 417 x1000 lb |
| Internal Pressure Capacity | 6890 psi |
| Compression Efficiency | 73.80 % |
| Compression Strength | 504 x1000 lb |
| Max. Allowable Bending | 29.33 °/100 ft |
| External Pressure Capacity | 5900 psi |

| Make-Up Torques | |
|-------------------------|--------------|
| Minimum | 5900 ft-lb |
| Optimum | 7100 ft-lb |
| Maximum | 10,300 ft-lb |
| Operation Limit Torques | |
| Operating Torque | 35,000 ft-lb |
| Yield Torque | 52,000 ft-lb |
| | |

Notes

For the lastest performance data, always visit our website: www.tenaris.com
For further information on concepts indicated in this datasheet, download the Datasheet Manual from www.tenaris.com

Tenaris has issued this document for general information only, and the information in this document, including, without limitation, any pictures, drawings or designs ("Information") is not intended to constitute professional or any other type of advice or recommendation and is provided on an "as is" basis. No warranty is given. Tenaris has not independently verified any information —if any- provided by the user in connection with, or for the purpose of, the Information contained hereunder. The use of the Information is at user's own risk and Tenaris does not assume any responsibility or liability of any kind for any loss, damage or injury resulting from, or in connection with any Information contained hereunder or any use thereof. The Information in this document is subject to change or modification without notice. Tenaris's products and services are subject to Tenaris's standard terms and conditions or otherwise to the terms resulting from the respective contracts of sale or services, as the case may be, between petitioner and Tenaris. For more complete information please contact a Tenaris's representative or visit our website at www.tenaris.com. ©Tenaris 2024. All rights reserved.

TenarisHydril Wedge 441®



Coupling Pipe Body Grade: P110-ICY Grade: P110-ICY Body: White 1st Band: White 1st Band: Pale Green 2nd Band: Pale Green 2nd Band: -3rd Band: Pale Green 3rd Band: -4th Band: -5th Band: -6th Band: -

| Outside Diameter | 5.500 in. | Wall Thickness | 0.361 in. | Grade | P110-ICY |
|----------------------|-----------|-----------------|--------------|-------|----------|
| Min. Wall Thickness | 87.50 % | Pipe Body Drift | API Standard | Туре | Casing |
| Connection OD Option | REGULAR | | | | |

Pipe Body Data

| Geometry | | | |
|----------------|-------------|------------------|-------------|
| Nominal OD | 5.500 in. | Wall Thickness | 0.361 in. |
| Nominal Weight | 20.00 lb/ft | Plain End Weight | 19.83 lb/ft |
| Drift | 4.653 in. | OD Tolerance | API |
| Nominal ID | 4.778 in. | | |

| Performance | |
|------------------------------|--------------|
| Body Yield Strength | 729 x1000 lb |
| Min. Internal Yield Pressure | 14,360 psi |
| SMYS | 125,000 psi |
| Collapse Pressure | 12,300 psi |

Make-Up Torques

Connection Data

| Geometry | |
|----------------------|-----------|
| Connection OD | 5.852 in. |
| Coupling Length | 8.714 in. |
| Connection ID | 4.778 in. |
| Make-up Loss | 3.780 in. |
| Threads per inch | 3.40 |
| Connection OD Option | Regular |
| | |

| Performance | |
|----------------------------|----------------|
| Tension Efficiency | 81.50 % |
| Joint Yield Strength | 594 x1000 lb |
| Internal Pressure Capacity | 14,360 psi |
| Compression Efficiency | 81.50 % |
| Compression Strength | 594 x1000 lb |
| Max. Allowable Bending | 84.76 °/100 ft |
| External Pressure Capacity | 12,300 psi |

| Minimum | 15,000 ft-lb |
|-------------------------|--------------|
| Optimum | 16,000 ft-lb |
| Maximum | 19,200 ft-lb |
| Operation Limit Torques | |
| Operating Torque | 36,000 ft-lb |
| Yield Torque | 42,000 ft-lb |
| Buck-On | |
| Minimum | 19,200 ft-lb |
| Maximum | 20,700 ft-lb |
| | |

Notes

This connection is fully interchangeable with: Wedge 441\$ - 5.5 in. - 0.304 (17.00) in. (lb/ft) Wedge 461\$ - 5.5 in. - 0.304 (17.00) / 0.361 (20.00) / 0.415 (23.00) in. (lb/ft) Connections with Dopeless\$ Technology are fully compatible with the same connection in its doped version

For the lastest performance data, always visit our website: www.tenaris.com
For further information on concepts indicated in this datasheet, download the Datasheet Manual from www.tenaris.com

Tenaris has issued this document for general information only, and the information in this document, including, without limitation, any pictures, drawings or designs ("Information") is not intended to constitute professional or any other type of advice or recommendation and is provided on an "as is" basis. No warranty is given. Tenaris has not independently verified any information —if any- provided by the user in connection with, or for the purpose of, the Information contained hereunder. The use of the Information is at user's own risk and Tenaris does not assume any responsibility or liability of any kind for any loss, damage or injury resulting from, or in connection with any Information contained hereunder or any use thereof. The Information in this document is subject to change or modification without notice. Tenaris's products and services are subject to Tenaris's translated terms and conditions or otherwise to the terms resulting from the respective contracts of sale or services, as the case may be, between petitioner and Tenaris. For more complete information please contact a Tenaris's representative or visit our website at www.tenaris.com. ©Tenaris 2025. All rights reserved.

ALL DIMENSIONS APPROXIMA

CACTUS WELLHEAD LLC

20" x 9-5/8" x 7-5/8" x 5-1/2" MBU-T-CFL-R-DBLO Wellhead With 11" 10M x 7-1/16" 15M CTH-DBLHPS Tubing Head And 9-5/8", 7-5/8" & 5-1/2" Pin Bottom Mandrel Casing Hangers

| DELAWARE BASIN | | | |
|----------------|-----|-------|--|
| DRAWN | VJK | 31MAR | |
| APPRV | | | |
| | | | |

ders DRAWING NO. HBE0000479

FORMATION CONTAINED HEREIN IS THE PROPERTY OF CACTUS WELLHEAD, LLC. REPRODUCTION, SCLOSURE, OR USE THEREOF IS PERMISSIBLE ONLY AS PROVIDED BY CONTRACT OR AS EXPRESSLY SUTHORIZED BY CACTUS WELLHEAD, LLC.

XTO Permian Operating, LLC. states that we will not introduce any additives that contain PFAS chemicals in the completion or recompletion of the well and will meet the certification requirement.

XTO respectfully requests approval to utilize a spudder rig to pre-set surface casing.

Description of Operations:

- 1. Spudder rig will move in to drill the surface hole and pre-set surface casing on the well.
 - a. After drilling the surface hole section, the spudder rig will run casing and cement following all of the applicable rules and regulations (OnShore Order 2, all COAs and NMOCD regulations).
 - The spudder rig will utilize fresh water-based mud to drill the surface hole to TD.
 Solids control will be handled entirely on a closed loop basis. No earth pits will be used.
- 2. The wellhead will be installed and tested as soon as the surface casing is cut off and WOC time has been reached.
- 3. A blind flange at the same pressure rating as the wellhead will be installed to seal the wellbore. Pressure will be monitored with needle valves installed on two wing valves.
 - a. A means for intervention will be maintained while the drilling rig is not over the well.
- 4. Spudder rig operations are expected to take 2-3 days per well on the pad.
- 5. The BLM will be contacted and notified 24 hours prior to commencing spudder rig operations.
- 6. Drilling Operations will begin with a larger rig and a BOP stack equal to or greater than the pressure rating that was permitted will be nippled up and tested on the wellhead before drilling operations resume on each well.
 - a. The larger rig will move back onto the location within 90 days from the point at which the wells are secured and the spudder rig is moved off location.
 - b. The BLM will be notified 24 hours before the larger rig moves back on the pre-set locations
- 7. XTO will have supervision on the rig to ensure compliance with all BLM and NMOCD regulations and to oversee operations.
- 8. Once the rig is removed, XTO will secure the wellhead area by placing a guard rail around the cellar area.

Subject: Request for a Variance Allowing break Testing of the Blowout Preventer Equipment (BOPE)

XTO Energy requests a variance to ONLY test broken pressure seals on the BOPE and function test BOP when skidding a drilling rig between multiple wells on a pad.

Background

Onshore Oil and Gas Order CFR Title 43 Part 3170, Drilling Operations, Sections III.A.2.i.iv.B states that the BOP test must be performed whenever any seal subject to test pressure is broken. The current interpretation of the Bureau of Land Management (BLM) requires a complete BOP test and not just a test of the affected component. CFR Title 43 Part 3170 states, "Some situation may exist either on a well-by- well basis or field-wide basis whereby it is commonly accepted practice to vary a particular minimum standard(s) established in this order. This situation can be resolved by requesting a variance...". XTO Energy feels the break testing the BOPE is such a situation. Therefore, as per CFR Title 43 Part 3170, XTO Energy submits this request for the variance.

Supporting Documentation

CFR Title 43 Part 3170 became effective on December 19, 1988 and has remained the standard for regulating BLM onshore drilling operations for over 30 years. During this time there have been significant changes in drilling technology. BLM continues to use the variance request process to allow for the use of modern technology and acceptable engineering practices that have arisen since CFR Title 43 Part 3170 was originally released. The XTO Energy drilling rig fleet has many modern upgrades that allow the intact BOP stack to be moved between well slots on a multi-well pad, as well as, wellhead designs that incorporate quick connects facilitating release of the BOP from the wellhead without breaking any BOP stack components apart. These technologies have been used extensively offshore, and other regulators, API, and many operators around the world have endorsed break testing as safe and reliable.



Figure 1: Winch System attached to BOP Stack



Figure 2: BOP Winch System

American Petroleum Institute (API) standards, specification and recommended practices are considered the industry standard and are consistently utilized and referenced by the industry. CFR Title 43 Part 3170recognizes API recommended Practices (RP) 53 in its original development. API Standard 53, *Well Control Equipment Systems for Drilling Wells* (Fifth Edition, December 2018, Annex C, Table C.4) recognizes break testing as an acceptable practice. Specifically, API Standard 53, Section 5.3.7.1 states "A pressure test of the pressure containing component shall be performed following the disconnection or repair, limited to the affected component." See Table C.4 below for reference.

| Tac | l C.4—Initial Pressure 16 | esting, Surface BOP Stacks | -High Pressure ^{ac} |
|----------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------|
| Component to be Pressure Tested | Pressure Test—Low Pressure ^{ac} psig (MPa) | Change Out of Component, Elastomer, or Ring Gasket | No Change Out of Component, Elastomer, or Ring Gasket |
| Annular preventerb | 250 to 350 (1.72 to 2.41) | RWP of annular preventer | MASP or 70% annular RWP, whichever is lower. |
| Fixed pipe, variable bore, blind, and BSR preventers ^{bd} | 250 to 350 (1.72 to 2.41) | RWP of ram preventer or wellhead system, whichever is lower | ITP |
| Choke and kill line and BOP side outlet valves below ram preventers (both sides) | 250 to 350 (1.72 to 2.41) | RWP of side outlet valve or wellhead system, whichever is lower | ITP |
| Choke manifold—upstream of chokes ^e | 250 to 350 (1.72 to 2.41) | RWP of ram preventers or wellhead system, whichever is lower | ITP |
| Choke manifold—downstream of chokese | 250 to 350 (1.72 to 2.41) | RWP of valve(s), line(s), or MASP for the well program, whichever is lower | |
| Kelly, kelly valves, drill pipe safety valves, IBOPs | 250 to 350 (1.72 to 2.41) | MASP for the well program | |
| Annular(s) and VBR(s) shall be pre For pad drilling operations, moving | during the evaluation period. The p ssure tested on the largest and sm from one wellhead to another withi when the integrity of a pressure se | oressure shall not decrease below the allest OD drill pipe to be used in well n the 21 days, pressure testing is req | program. juired for pressure-containing an |

The Bureau of Safety and Environmental Enforcement (BSEE), Department of Interior, has also utilized the API standards, specification and best practices in the development of its offshore oil and gas regulations and incorporates them by reference within its regulations.

Break testing has been approved by the BLM in the past with other operators based on the detailed information provided in this document.

XTO Energy feels break testing and our current procedures meet the intent of CFR Title 43 Part 317 Oand often exceed it. There has been no evidence that break testing results in more components failing than seen on full BOP tests. XTO Energy's internal standards requires complete BOPE tests more often than that of CFR Title 43 Part 3170 (Every 21 days). In addition to function testing the annular, pipe rams and blind rams after


each BOP nipple up, XTO Energy performs a choke drill with the rig crew prior to drilling out every casing shoe. This is additional training for the rig crew that exceeds the requirements of the CFR Title 43 Part 3170.

Procedures

- XTO Energy will use this document for our break testing plan for New Mexico Delaware basin.
 The summary below will be referenced in the APD or Sundry Notice and receive approval prior
 to implementing this variance.
- 2. XTO Energy will perform BOP break testing on multi-wells pads where multiple intermediate sections can be drilled and cased within the 21-day BOP test window.
 - a. A full BOP test will be conducted on the first well on the pad.
 - b. The first intermediate hole section drilled on the pad will be the deepest. All of the remaining hole sections will be the same depth or shallower.
 - i. Our Lower WC targets set the intermediate casing shoe no deeper than the Wolfcamp B.
 - ii. Our Upper WC targets set the intermediate casing shoe shallower than the Wolfcamp B.
 - c. A Full BOP test will be required if the intermediate hole section being drilled has a MASP over 5M.
 - d. A full BOP test will be required prior to drilling any production hole.
- 3. After performing a complete BOP test on the first well, the intermediate hole section will be drilled and cased, two breaks would be made on the BOP equipment.
 - a. Between the HCV valve and choke line connection
 - b. Between the BOP quick connect and the wellhead
- 4. The BOP is then lifted and removed from the wellhead by a hydraulic system.
- 5. After skidding to the next well, the BOP is moved to the wellhead by the same hydraulic system and installed.
- 6. The connections mentioned in 3a and 3b will then be reconnected.
- 7. Install test plug into the wellhead using test joint or drill pipe.
- 8. A shell test is performed against the upper pipe rams testing the two breaks.
- 9. The shell test will consist of a 250 psi low test and a high test to the value submitted in the APD or Sundry (e.g. 5,000 psi or 10,000psi).
- 10. Function test will be performed on the following components: lower pipe rams, blind rams, and annular.

- 11. For a multi-well pad the same two breaks on the BOP would be made and on the next wells and steps 4 through 10 would be repeated.
- 12. A second break test would only be done if the intermediate hole section being drilled could not be completed within the 21 day BOP test window.

Note: Picture below highlights BOP components that will be tested during batch operations




Summary

A variance is requested to **ONLY** test broken pressure seals on the BOP equipment when moving from wellhead to wellhead which is in compliance with API Standard 53. API Standard 53 states, that for pad drilling operation, moving from one wellhead to another within 21 days, pressure testing is required for pressure-containing and pressure-controlling connections when the integrity of a pressure seal is broken.

The BOP will be secured by a hydraulic carrier or cradle. The BLM will be contacted if a Well Control event occurs prior to the commencement of a BOPE Break Testing operation.

Based on discussions with the BLM on February 27th 2020 and the supporting documentation submitted to the BLM, we will request permission to ONLY retest broken pressure seals if the following conditions are met:

- 1. After a full BOP test is conducted on the first well on the pad.
- 2. The first intermediate hole section drilled on the pad will be the deepest. All of the remaining hole sections will be the same depth or shallower.
- 3. Full BOP test will be required if the intermediate hole section being drilled has a MASP over 5M.
- 4. Full BOP test will be required prior to drilling the production hole.





GATES ENGINEERING & SERVICES NORTH AMERICA

7603 Prairie Oak Dr.

Houston, TX. 77086

PHONE: +1 (281) 602-4100

FAX: +1 (281) 602-4147

EMAIL: gesna.quality@gates.com

WEB: www.gates.com/oilandgas

NEW CHOKE HOSE

INSTAUED 02-10-2024

CERTIFICATE OF CONFORMANCE

This is to verify that the items detailed below meet the requirements of the Customer's Purchase Order referenced herein, and are in Conformance with applicable specifications, and that Records of Required Tests are on file and subject to examination. The following items were inspected and hydrostatically tested at **Gates Engineering & Services North America** facilities in Houston, TX, USA.

| CUSTOMER: | |
|-----------|--|
|-----------|--|

NABORS DRILLING TECHNOLOGIES USA DBA NABORS DRILLING USA

CUSTOMER P.O.#:

15582803 (TAG NABORS PO #15582803 SN 74621 ASSET 66-1531)

CUSTOMER P/N:

IMR RETEST SN 74621 ASSET #66-1531

PART DESCRIPTION:

RETEST OF CUSTOMER 3" X 45 FT 16C CHOKE & KILL HOSE ASSEMBLY C/W 4 1/16" 10K

FLANGES

SALES ORDER #:

529480

QUANTITY:

1


SERIAL #:

74621 H3-012524-1

SIGNATURE: 7. CUSTUS &

TITLE: QUALITY ASSURANCE

DATE: 1/25/2024



1/25/2024 11:48:06 AM



TEST REPORT

CUSTOMER

Company:

Nabors Industries Inc.

TEST OBJECT

Serial number: H3-012524-1

Lot number:

Production description: 74621/66-1531

529480

Description:

74621/66-1531

Sales order #: Customer reference:

FG1213

Hose ID:

Fitting 1:

3" 16C CK

Part number:

TEST INFORMATION

Test procedure:

GTS-04-053

15000.00 psi

3.0 x 4-1/16 10K

Test pressure: Test pressure hold:

3600.00

sec

Part number: Description:

Work pressure: Work pressure hold: 10000.00

psi

Fitting 2:

3.0 x 4-1/16 10K

Length difference:

Length difference:

900.00 0.00 0.00

sec % inch

Part number:

Description:

Visual check:

Pressure test result:

PASS

Length measurement result:

Length:


45

feet

n /n

Test operator:

Travis






H3-15/16

1/25/2024 11:48:06 AM

TEST REPORT

GAUGE TRACEABILITY

| Serial number | Calibration date | Calibration due date |
|---------------|------------------|----------------------|
| 110D3PHO | 2023-06-06 | 2024-06-06 |
| 110IQWDG | 2023-05-16 | 2024-05-16 |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | 110D3PHO | 110D3PHO 2023-06-06 |




Released to Imaging: 9/19/2025 3:18:06 PM









Released to Imaging: 9/19/2025 3:18:06 PM

XTO Permian Operating, LLC Offline Cementing Variance Request

XTO requests the option to cement the surface and intermediate casing strings offline as a prudent batch drilling efficiency of acreage development.

1. Cement Program

No changes to the cement program will take place for offline cementing.

2. Offline Cementing Procedure


The operational sequence will be as follows. If a well control event occurs, the BLM will be contacted for approval prior to conducting offline cementing operations.

- 1. Run casing as per normal operations. While running casing, conduct negative pressure test and confirm integrity of the float equipment (float collar and shoe)
- 2. Land casing with mandrel
- 3. Fill pipe with kill weight fluid, do not circulate through floats and confirm well is static
- 4. Set annular packoff shown below and pressure test to confirm integrity of the seal. Pressure ratings of wellhead components and valves is 5,000 psi.
- 5. After confirmation of both annular barriers and internal barriers, nipple down BOP and install cap flange.
 - a. If any barrier fails to test, the BOP stack will not be nippled down until after the cement job is completed with cement 500ft above the highest formation capable of flow with kill weight mud above or after it has achieved 50-psi compressive strength if kill weight fluid cannot be verified.



Annular packoff with both external and internal seals


XTO Permian Operating, LLC Offline Cementing Variance Request



Wellhead diagram during skidding operations

- 6. Skid rig to next well on pad.
- 7. Confirm well is static before removing cap flange, flange will not be removed and offline cementing operations will not commence until well is under control. If well is not static, casing outlet valves will provide access to both the casing ID and annulus. Rig or third party pump truck will kill well prior to cementing or nippling up for further remediation.
 - a. Well Control Plan
 - i. The Drillers Method will be the primary well control method to regain control of the wellbore prior to cementing, if wellbore conditions do not permit the drillers method other methods of well control may be used
 - ii. Rig pumps or a 3rd party pump will be tied into the upper casing valve to pump down the casing ID
 - iii. A high pressure return line will be rigged up to lower casing valve and run to choke manifold to control annular pressure
 - iv. Once influx is circulated out of the hole, kill weight mud will be circulated
 - v. Well will be confirmed static
 - vi. Once confirmed static, cap flange will be removed to allow for offline cementing operations to commence
- 8. Install offline cement tool
- 9. Rig up cement equipment

XTO Permian Operating, LLC Offline Cementing Variance Request



Wellhead diagram during offline cementing operations

- 10. Circulate bottoms up with cement truck
 - a. If gas is present on bottoms up, well will be shut in and returns rerouted through gas buster to handle entrained gas
 - b. Max anticipated time before circulating with cement truck is 6 hrs
- 11. Perform cement job taking returns from the annulus wellhead valve
- 12. Confirm well is static and floats are holding after cement job
- 13. Remove cement equipment, offline cement tools and install night cap with pressure gauge for monitoring.

Received by OCD: 9/19/2025 11:43:28 AM



Offline Production Cementing

Delaware Basin | 18 March 2025

Energy lives here

Received by OCD: 9/19/2025 11:43:28 AM

Variance Request for Offline Production Cementing

Proposal: allow wells that meet set criteria to perform production casing cement jobs offline, consistent with ExxonMobil's extensive experience safely and effectively cementing production casing strings offline in Texas

Supporting Materials:

- Criteria for offline production cementing
- Proposed procedure
- Process and equipment
- Barrier comparison



Received by OCD: 9/19/2025 11:43:28 AM

Criteria for Offline Cementing

The following conditions must be met to proceed with offline production cementing on Wolfcamp target formations or shallower:

- a) Casing hanger successfully landed in the wellhead
- b) Ability to circulate overbalanced mud weight
- c) Initiate offline cementing operations within 24hr of landing casing
- d) All well control barriers test successfully and BLM notified of intent to perform offline production cementing prior to N/D BOP
- e) No offset frac operations within 1 mile and within the same target horizon
- f) Well Control certified ExxonMobil Operations Supervisor to be present during offline cementing operation to monitor returns
- g) Drill ahead operations will not begin on next well until offline production cement operations have concluded

Trigger to reevaluate plan

Offline Cementing Procedure

- 1. Land production casing hanger If casing hanger cannot be landed, cementing will be performed online
- 2. Flow check and **confirm the well is static on the casing and annulus**. *If flow is observed, cementing will be performed online*
- 3. Lay down landing joint
- 4. Install and test pack-off assembly
 - a) Pressure test the seal assembly per wellhead provider's procedure to confirm integrity to 250 / 10,000psi
- 5. Install back-pressure valve (BPV, rated to 10,000psi) in hanger per wellhead provider's procedure
- 6. Confirm the well is static
 - a) Flow indicates failure of hydrostatic barrier or mechanical barriers and underbalanced well conditions. If flow is observed, cementing will be performed online
 - b) Notify BLM of intent to proceed with nipple down and offline cementing
- 7. With the well secured and BLM notified; **nipple down BOP and skid rig** to next well on pad
 - a) Note, verify offline cementing criteria is met before N/D BOP. If unable to meet criteria, cement job will be performed online
- 8. Install and test gate valve
 - a) Test connection between wellhead adapter seals against hanger neck and ring gasket to 250 / 10,000 psi for 5 minutes
- 9. Remove BPV from casing
- 10. Rig up cement head and cementing lines
- 11. **Perform production cement job** as per procedure
 - a) Confirm flowpath and valve alignment; default routing to take returns from casing upper side outlet valves \rightarrow offline cementing manifold \rightarrow shakers / pits
 - b) If elevated gas or flow trend observed, reroute returns through choke manifold for ability to hold backpressure to maintain well control and route mud returns to MGS
- 12. Confirm well is static and double floats are holding after cement job
 - a) If double floats do not hold, the well can be secured by closing gate valve or cement head or by holding and monitoring pressure at the cement truck while WOC
- 13. Rigdown surface equipment
 - a) Bleed any remaining line pressure and remove cement head
 - b) Install BPV per wellhead providers recommended procedure
 - c) Close upper casing side outlet valves, break and R/D offline cement lines
 - d) Remove 10M gate valve and wellhead adapter
- 14. Secure well
 - a) Install temporary abandonment cap





OFFLINE CEMENTING

MANIFOLD

Process and Equipment


ONLINE CEMENTING

OFFLINE CEMENTING

RETURNS FROM WELLHEAD SIDE OUTLET VALVES

CASING HANGER AND PACKOFF

SEAL ASSEMBLY (10M)





- 1. Rig BOP replaced by gate valve and WH adaptor assembly (10M rated)
- 2. Addition of offline cementing manifold and high pressure iron to direct fluid returns to rig active system and/or choke manifold
- Packoff annulus barrier in place and tested prior to cementing operations (10M rated)
- 4. Cement truck performs cement job displacement (vs rig pumps)



TO SHAKERS / PITS

TO OPEN TOP TANK

TO RIG CHOKE MANIFOLD

Barrier Comparison

| | ONLINE | | OFFLINE (PROPOSED) | | |
|-------------------------|--------------------------------------------------------------|-------------------------------------------------------------|----------------------------------------------------------------------------------|----------------------------------------------------------------------------|--|
| | Casing | Annulus | Casing | Annulus | |
| N/D BOP & Skid Rig | | | Hydrostatic Double float valves BPV | Hydrostatic Packoff | |
| Install Cement Head | Hydrostatic Double float valves | Hydrostatic BOP (annular, VBR) | Hydrostatic Double float valves Gate valve | Hydrostatic Packoff Wellhead Adaptor | |
| Perform Cement Job | Double float valves Cement Head | Hydrostatic BOP (annular, VBR) | Double float valves Cement Head Gate valve | Hydrostatic Packoff Wellhead Adaptor | |
| Remove Cement Head | 1. Double float valves | Hydrostatic BOP (annular, VBR) | Double float valves Gate valve | Hydrostatic Packoff Wellhead Adaptor | |
| N/D & Install TA Cap | Double float valves BPV | Hydrostatic Packoff | Double float valves BPV | Hydrostatic Packoff | |

Well Control Response Plan

The following well control response plan for offline cementing is the same as for online cementing.

- 1. Pre-job design: Cement job designed to define max pump rates to reduce ECD and avoid losses during cement job.
- 2. Identify the influx / re-route return flow: If an influx is observed, the cementing manifold would be re-routed to direct flow to the rig choke manifold (instead of the shakers). If gas was encountered or a kick was detected, continue pumping the job through the rig choke / gas buster while controlling annulus back pressure through the rig choke. Shut the well in once the job is finished (to ensure cement does not set up inside casing). Roles & responsibilities are as follows:
 - Onsite well site representative responsible for monitoring and helping to identify if an influx occurred with support from the rig crews.
 - Rig crew responsible for shutting in the well.
 - Onsite well site representative responsible for operating the rig choke manifold.
- 3. Monitor pressure: If well is shut-in, pressure monitored while cement is building compressive strength.
- 4. Flow check: Once sufficient time is allocated to build compressive strength, perform flow check.
- 5. Shut-in: If annulus pressure / flow is observed, shut-in the well at the casing valves.
- 6. Kill the well: Pump kill weight mud or cement (depending on well conditions) via bradenhead squeeze down the annulus using the rig pumps tied into the cementing manifold or the cement truck.
- 7. Flow check: Flow check the well to confirm static.

ExonMobil

Sante Fe Main Office Phone: (505) 476-3441

General Information Phone: (505) 629-6116

Online Phone Directory https://www.emnrd.nm.gov/ocd/contact-us

State of New Mexico Energy, Minerals and Natural Resources Oil Conservation Division 1220 S. St Francis Dr. Santa Fe, NM 87505

ACKNOWLEDGMENTS

Action 507589

ACKNOWLEDGMENTS

| Operator: | OGRID: |
|----------------------------|-------------------------------------------------------|
| XTO PERMIAN OPERATING LLC. | 373075 |
| 6401 HOLIDAY HILL ROAD | Action Number: |
| MIDLAND, TX 79707 | 507589 |
| | Action Type: |
| | [C-101] BLM - Federal/Indian Land Lease (Form 3160-3) |

ACKNOWLEDGMENTS

I hereby certify that no additives containing PFAS chemicals will be added to the completion or recompletion of this well.

Sante Fe Main Office Phone: (505) 476-3441

General Information Phone: (505) 629-6116

Online Phone Directory https://www.emnrd.nm.gov/ocd/contact-us

State of New Mexico Energy, Minerals and Natural Resources Oil Conservation Division 1220 S. St Francis Dr. Santa Fe, NM 87505

CONDITIONS

Action 507589

CONDITIONS

| Operator: | OGRID: |
|----------------------------|-------------------------------------------------------|
| XTO PERMIAN OPERATING LLC. | 373075 |
| 6401 HOLIDAY HILL ROAD | Action Number: |
| MIDLAND, TX 79707 | 507589 |
| | Action Type: |
| | [C-101] BLM - Federal/Indian Land Lease (Form 3160-3) |

CONDITIONS

| Created By | Condition | Condition Date |
|-------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------|
| mvenkatesh | Cement is required to circulate on both surface and intermediate1 strings of casing. | 9/19/2025 |
| mvenkatesh | If cement does not circulate on any string, a Cement Bond Log (CBL) is required for that string of casing. | 9/19/2025 |
| ward.rikala | Notify the OCD 24 hours prior to casing & cement. | 9/19/2025 |
| ward.rikala | File As Drilled C-102 and a directional Survey with C-104 completion packet. | 9/19/2025 |
| ward.rikala | Once the well is spud, to prevent ground water contamination through whole or partial conduits from the surface, the operator shall drill without interruption through the fresh water zone or zones and shall immediately set in cement the water protection string. | 9/19/2025 |
| ward.rikala | Oil base muds are not to be used until fresh water zones are cased and cemented providing isolation from the oil or diesel. This includes synthetic oils. Oil based mud, drilling fluids and solids must be contained in a steel closed loop system. | 9/19/2025 |