Bureau of Land Management

AFMSS

Application for Permit to Drill

APD Package Report

APD ID: 10400100857

APD Received Date: 09/23/2024 12:49 PM

Operator: XTO PERMIAN OPERATING LLC

Date Printed: 05/19/2025 03:32 PM

Received by OCD: 9/19/2025 11:53:46 AM

Well Name: POKER LAKE UNIT 18-30 BL

Well Status: AAPD

Well Number: 202H

APD Package Report Contents

- Form 3160-3

- Operator Certification Report

- Application Report

- Application Attachments

-- Well Plat: 1 file(s)

- Drilling Plan Report

- Drilling Plan Attachments

-- Blowout Prevention Choke Diagram Attachment: 1 file(s)

-- Blowout Prevention BOP Diagram Attachment: 1 file(s)

Casing Spec Documents: 2 file(s)

Casing Taperd String Specs: 1 file(s)

Casing Design Assumptions and Worksheet(s): 1 file(s)

Hydrogen sulfide drilling operations plan: 1 file(s)

-- Proposed horizontal/directional/multi-lateral plan submission: 2 file(s)

Other Facets: 4 file(s)

-- Other Variances: 4 file(s)

SUPO Report

- SUPO Attachments

-- Existing Road Map: 1 file(s)

-- Attach Well map: 1 file(s)

-- Production Facilities map: 1 file(s)

-- Water source and transportation map: 1 file(s)

-- Well Site Layout Diagram: 2 file(s)

Recontouring attachment: 1 file(s)

-- Other SUPO Attachment: 1 file(s)

- PWD Report

- PWD Attachments

-- None

Released to Imaging: 9/19/2025 3:47:41 PM

Bond ReportBond AttachmentsNone

*(Instructions on page 2)

Form 3160-3 (June 2015) UNITED STATES	FORM APPROVED OMB No. 1004-0137 Expires: January 31, 2018
DEPARTMENT OF THE INTERIOR BUREAU OF LAND MANAGEMENT	5. Lease Serial No. NMLC065705B
APPLICATION FOR PERMIT TO DRILL OR REENTER	6. If Indian, Allotee or Tribe Name
DRILL S ON WELL S ON WELL	7. If Unit or CA Agreement, Name and No. NMNM071016X/POKER LAKE UNIT
1c. Type of Completion: Hydraulic Fracturing Single Zone	8. Lease Name and Well No. POKER LAKE UNIT 18-30 BD
	202H
2. Name of Operator XTO PERMIAN OPERATING LLC	9. API Well No. 30-015-57273
3a. Address S401 HOLIDAY HILL ROAD BLDG 5, MIDLAND, TX 7970 (432) 683-2277	10. Field and Pool, or Exploratory PIERCE CROSSING/BONE SPRING EAS
4. Location of Well (Report location clearly and in accordance with any State requirements.*)	11. Sec., T. R. M. or Blk. and Survey or Area
At surface NWNE / 265 FNL / 2335 FEL / LAT 32.136718 / LONG -103.91964	SEC 18/T25S/R30E/NMP
At proposed prod. zone SWNE / 2646 FNL / 1758 FEL / LAT 32.100951 / LONG -103.91772	
14. Distance in miles and direction from nearest town or post office*	12. County or Parish 13. State EDDY NM
15. Distance from proposed* 265 feet 16. No of acres in lease 17. Space	17. Spacing Unit dedicated to this well
property or lease line, ft. (Also to nearest drig. unit line, if any)	>

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No. 1, and the Hydraulic Fracturing rule per 43 CFR 3162.3-3 (as applicable)

24. Attachments

23. Estimated duration 45 days

22. Approximate date work will start* 10/05/2025

etc.)

21. Elevations (Show whether DF, KDB, RT, GL,

3179 feet

Distance from proposed location* to nearest well, drilling, completed, 30 feet applied for, on this lease, ft.

20, BLM/BIA Bond No. in file

FED: COB000050

9366 feet / 22237 feet

19. Proposed Depth

- 1. Well plat certified by a registered surveyor.
- A Drilling Plan.
 A Surface Use Plan (if the location is on National Forest System Lands, the SUPO must be filed with the appropriate Forest Service Office).
- Bond to cover the operations unless covered by an existing bond on file (see Item 20 above).
- 5. Operator certification. 6. Such other site specific information and/or plans as may be requested by the BLM.

25. Signature		Name (Printed/Typed)	Date
(Electronic Submission)		SAMANTHA WEIS / Ph: (432) 682-8873	09/23/2024
Title			

Permitting Advisor

Approved by (Signature) (Electronic Submission)	Name (<i>Printed/Typed</i>) CODY LAYTON / Ph: (575) 234-5959	Date 05/19/2025
Title	Office	
Assistant Field Manager Lands & Minerals	Carlsbad Field Office	

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Conditions of approval, if any, are attached.

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.



(Continued on page 2)

INSTRUCTIONS

Indian lands and leases for action by appropriate Federal agencies, pursuant to applicable Federal laws and regulations. Any GENERAL: This form is designed for submitting proposals to perform certain well operations, as indicated on Federal and regard to local, area, or regional procedures and practices, either are shown below or will be issued by, or may be obtained necessary special instructions concerning the use of this form and the number of copies to be submitted, particularly with from local Federal offices. ITEM I: If the proposal is to redrill to the same reservoir at a different subsurface location or to a new reservoir, use this form with appropriate notations. Consult applicable Federal regulations concerning subsequent work proposals or reports on the well.

ITEM 4: Locations on Federal or Indian land should be described in accordance with Federal requirements. Consult local Federal offices for specific instructions. ITEM 14: Needed only when location of well cannot readily be found by road from the land or lease description. A plat, or plats, separate or on the reverse side, showing the roads to, and the surveyed location of, the wen, and any other required information, should be furnished when required by Federal agency offices.

ITEMS 15 AND 18: If well is to be, or has been directionany drilled, give distances for subsurface location of hole in any present or objective productive zone.

ITEM 22: Consult applicable Federal regulations, or appropriate officials, concerning approval of the proposal before operations are started ITEM 24: If the proposal will involve hydraulic fracturing operations, you must comply with 43 CFR 3162.3-3, including providing information about the protection of usable water. Operators should provide the best available information about all formations containing water and their depths. This information could include data and interpretation of resistivity logs run on nearby wells. Information may also be obtained from state or tribal regulatory agencies and from local BLM offices.

NOTICES

The Privacy Act of 1974 and regulation in 43 CFR 2,48(d) provide that you be furnished the following information in connection with information required by this application.

AUTHORITY: 30 U.S.C. 181 et seq., 25 U.S.C. 396; 43 CFR 3160

information for the management, disposal and use of National Resource Lands and resources including (a) analyzing your proposal to discover and extract the Federal or Indian resources encountered; (b) reviewing procedures and equipment and the projected impact on the land involved; and (c) evaluating the effects of the proposed operation on the surface and PRINCIPAL PURPOSES: The information will be used to: (1) process and evaluate your application for a permit to drill a new oil, gas, or service wen or to reenter a plugged and abandoned well; and (2) document, for administrative use, subsurface water and other environmental impacts.

local or foreign agencies, when relevant to civil, criminal or regulatory investigations or prosecution, in connection with ROUTINE USE: Information from the record and/or the record win be transferred to appropriate Federal, State, and congressional inquiries and for regulatory responsibilities.

EFFECT OF NOT PROVIDING INFORMATION: Filing of this application and disclosure of the information is mandatory only if you elect to initiate a drilling or reentry operation on an oil and gas lease.

The Paperwork Reduction Act of 1995 requires us to inform you that:

drilling for oil and/or gas on Federal and Indian oil and gas leases. This information will be used to analyze and approve applications. Response to this request is mandatory only if the operator elects to initiate drilling or reentry operations on oil and gas lease. The BLM would like you to know that you do not have to respond to this or any other Federal agency-The BLM conects this information to anow evaluation of the technical, safety, and environmental factors involved with sponsored information collection unless it displays a currently valid OMB control number.

including the time for reviewing instructions, gathering and maintaining data, and completing and reviewing the form. Direct Management (1004-0137), Bureau Information Conection Clearance Officer (WO-630), 1849 C Street, N.W., Mail Stop 401 comments regarding the burden estimate or any other aspect of this form to U.S. Department of the Interior, Bureau of Land BURDEN HOURS STATEMENT: Public reporting burden for this form is estimated to average 8 hours per response, LS, Washington, D.C. 20240. (Form 3160-3, page 2)

Additional Operator Remarks

Location of Well

BHL: SWNE / 2646 FNL / 1758 FEL / TWSP: 25S / RANGE: 30E / SECTION: 30 / LAT: 32.100951 / LONG: -103.91772 (TVD: 9366 feet, MD: 22237 feet) PPP: NWNE / 100 FNL / 1758 FEL / TWSP: 25S / RANGE: 30E / SECTION: 18 / LAT: 32.137172 / LONG: -103.917777 (TVD: 9366 feet, MD: 9777 feet) PPP: NWNE / 0 FSL / 1759 FEL / TWSP: 25S / RANGE: 30E / SECTION: 19 / LAT: 32.122836 / LONG: -103.917755 (TVD: 9366 feet, MD: 15000 feet) 0. SHL; NWNE / 265 FNL / 2335 FEL / TWSP: 25S / RANGE; 30E / SECTION: 18 / LAT; 32.136718 / LONG; -103.91964 (TVD: 0 feet, MD: 0 feet)


BLM Point of Contact

Name: MARIAH HUGHES

Title: Land Law Examiner

Phone: (575) 234-5972

Email: mhughes@blm.gov





Review and Appeal Rights

20 working days of receipt of the Notice with the appropriate State Director (see 43 CFR 3165.3). The Quincy Street, Suite 300, Arlington, VA 22203 (see 43 CFR 3165.4). Contact the above listed Bureau A person contesting a decision shall request a State Director review. This request must be filed within State Director review decision may be appealed to the Interior Board of Land Appeals, 801 North of Land Management office for further information.



PECOS DISTRICT SURFACE USE CONDITIONS OF APPROVAL

LEASE NO.: NMLC 0657

NMLC 065705, NMLC065705B

XTO Permian Operating LLC

OPERATOR'S NAME:

COUNTY:

Eddy County, New Mexico

. 11 - 11 -

Poker Lake Unit 18-19 BD 106H

Poker Lake Unit 18-19 BD 127H

Poker Lake Unit 18-30 BD 200H

Poker Lake Unit 18-30 BD 201H

Poker Lake Unit 18-30 BD 202H

Poker Lake Unit 18-30 BD 203H

Poker Lake Unit 18-30 BD 203H Poker Lake Unit 18-19 BD 204H Poker Lake Unit 18-19 BD 205H Poker Lake Unit 18-19 BD 206H

Poker Lake Unit 18-19 BD 207H

Poker Lake Unit 18-19 BD 209H

Poker Lake Unit 18-19 BD 208H

Page 1 of 24

TABLE OF CONTENTS

<u>†</u>	4.	4.	4.	.5	5.	5.	.5	.5	.5	5.	9.	9.	9.	9.	9.	9.	9.	7 .	٧.	7.	7.	7.	7.
	RICAL SITES																						
	ARCHAEOLOGICAL, PALEONTOLOGY & HISTORICAL SITES																(5)						
	PALEONTOL	RCES			irement		ırmala)										2.1.4. Temporary Use Fresh Water Frac Line(s)			NAGEMENT.		NMENTS	ICATION
GNIOIGIAC	EOLOGICAL,	RANGELAND RESOURCES	rds	quirement	1.2.3. Livestock Watering Requirement.	NOXIOUS WEEDS	1.3.1 African Rue (Peganum harmala)	LIGHT POLLUTION	ng		Color	UIREMENTS.	SHED	ery	rface Line(s)	ine(s)	y Use Fresh W.		2.3.2. Texas Hornshell Mussel	VISUAL RESOURCE MANAGEMENT		CONSTRUCTION REQUIRENMENTS	CONSTRCUTION NOTIFICATION
GENERAL FROVISIONS		RANGE]	1.2.1. Cattleguards.	1.2.2. Fence Requirement	.2.3. Livestock		.3.1 African Ru		1.4.1. Downfacing	1.4.2. Shielding	1.4.3. Lighting Color	SPECIAL REQUIREMENTS	WATERSHED	2.1.1. Tank Battery	2.1.2. Buried/Surface Line(s)	2.1.3. Electric Line(s)	.1.4. Temporar	WILDLIFE	.3.2. Texas Ho		2.5.1 VRM IV.	ONSTRUCTION	CONSTRC
) :	1.1.	1.2.	- i	ij	Τ΄	1.3.	Τ.	1.4.	<u>.</u>	Ţ.	Τ.	2. SI	2.1.	2.	2.	2.	2.	2.3	2.	2.4	2.	3. C	3.1

Page 2 of 24

5.1.1 Placement of Production Facilities 5.1.3. Chemical and Fuel Secondary Containment and Exclosure Screening 5.1.2 Exclosure Netting (Open-top Tanks) SURFACE PIPELINES..... ON LEASE ACESS ROAD..... 4.5.1 Fence Requirement...... RANGLAND MITIGATION FOR PIPELINES 6.2 EROSION CONTROL...... 4.5.3 Livestock Watering Requirement WELL STRUCTURES & FACILITIES...... 5.1.5. Containment Structures 5.1.4. Open-Vent Exhaust Stack Exclosures BURIED PIPELINES..... PRODUCTION (POST DRILLING)..... 6.1 ROAD AND SITE RECLAMATION WELL PAD & SURFACING TOPSOIL Road Width Ditching 3.7.6 3.7.7 3.7.3 3.7.4 3.7.5 Š. 6.

Page 3 of 24

6.4 FINAL ABANDONMENT & RECLAMATION......

6.3 INTERIM RECLAMATION

SOIL SPECIFIC SEED MIXTURE

GENERAL PROVISIONS

location during construction, drilling and reclamation activity. Any request for a variance shall be submitted to the The failure of the operator to comply with these requirements may result in the assessment of liquidated damages or penalties pursuant to 43 CFR 3163.1 or 3163.2. A copy of these conditions of approval shall be present on the Authorized Officer on Form 3160-5, Sundry Notices and Report on Wells.

ARCHAEOLOGICAL, PALEONTOLOGY & HISTORICAL SITES

prevent the loss of significant scientific values. The operator shall be responsible for the cost of evaluation and any Any cultural resource (historic or prehistoric site or object) discovered by the operator, or any person working on Authorized Officer, in conjunction with a BLM Cultural Resource Specialist, to determine appropriate actions to authorization to proceed is issued by the Authorized Officer. An evaluation of the discovery will be made by the the operator's behalf, on the public or federal land shall be immediately reported to the Authorized Officer. The decision as to the proper mitigation measures will be made by the Authorized Officer after consulting with the operator shall suspend all operations in the immediate area (within 100ft) of such discovery until written

approval, the BLM Authorized Officer will notify the operator of the following conditions and the duration traditional, religious, and cultural significance tied to a certain group of individuals. Though there are currently designated TCPs within the project area or within a mile of the project area, but it is possible for a TCP to be designated after the approval of this project. If a TCP is designated in the project area after the project's Traditional Cultural Properties (TCPs) are protected by NHPA as codified in 36 CFR 800 for possessing for which these conditions are required.

- 1. Temporary halting of all construction, drilling, and production activities to lower noise.
- Temporary shut-off of all artificial lights at night.

The operator is hereby obligated to comply with procedures established in the Native American Graves Protection the discovery. The written notification should include the geographic location by county and state, the contents of Officer will be notified immediately. The BLM will then be required to be notified, in writing, within 24 hours of discovery and a conformation that all activity within 100ft of the discovery has ceased and work will not resume remains, associated funerary objects, sacred objects, and objects of cultural patrimony discovered during project until written certification is issued. All work on the entire project must halt for a minimum of 3 days and work the discovery, and the steps taken to protect said discovery. You must also include any potential threats to the work. If any human skeletal remains, funerary objects, sacred objects, or objects of cultural patrimony are discovered at any time during construction, all construction activities shall halt and a BLM-CFO Authorized and Repatriation Act (NAGPRA), specifically NAGPRA Subpart B regarding discoveries, to protect human cannot resume until an Authorized Officer grants permission to do so. Any paleontological resource discovered by the operator, or any person working on the operator's behalf, on public or Federal land shall be immediately reported to the Authorized Officer. The operator shall suspend all operations in the immediate area of such discovery until written authorization to proceed is issued by the Authorized Officer. The operator will be responsible for the cost of evaluation and any decision as to the proper mitigation measures will be made by the Authorized Officer after consulting with the operator.

.2. RANGELAND RESOURCES

1.2.1. Cattleguards

responsible for the condition of the existing cattleguard(s) that are in place and are utilized during lease operations. Where a permanent cattleguard is approved, an appropriately sized cattleguard(s) sufficient to carry out the project shall be installed and maintained at fence crossing(s). Any existing cattleguard(s) on the access road shall be repaired or replaced if they are damaged or have deteriorated beyond practical use. The operator shall be gate shall be constructed on one side of the cattleguard and fastened securely to H-braces.

Page 4 of 24

1.2.2. Fence Requirement

operator shall notify the private surface landowner or the grazing allotment holder prior to crossing any fence(s). Where entry granted across a fence line, the fence must be braced and tied off on both sides of the passageway prior to cutting. Once the work is completed, the fence will be restored to its prior condition, or better. The

1.2.3. Livestock Watering Requirement

234-5972) and the private surface landowner or the grazing allotment holder if any damage occurs to structures that Any damage to structures that provide water to livestock throughout the life of the well, caused by operations from the well site, must be immediately corrected by the operator. The operator must notify the BLM office (575provide water to livestock.

.3. NOXIOUS WEEDS

The operator shall be held responsible if noxious weeds become established within the areas of operations. Weed operator shall consult with the Authorized Officer for acceptable weed control methods, which include following associated pipeline corridor, and adjacent land affected by the establishment of weeds due to this action. The control shall be required on the disturbed land where noxious weeds exist, which includes the roads, pads, EPA, New Mexico Department of Agriculture, and BLM requirements and policies.

1.3.1 African Rue (Peganum harmala)

chemical and decrease chances of developing herbicide resistance. After spraying, the operator or necessary parties connection to any dirt working activities or disturbances to the site being sprayed. Spraying of African Rue shall be (Imazapyr) and 2% Roundup (Glyphosate) along with a nonionic surfactant. Any other chemicals or combinations stages. Spraying shall not be conducted after flowering when plant is fruiting. This will ensure optimal intake of shall be approved by the BLM Noxious Weeds Coordinator prior to treatment. African Rue shall be sprayed in done on immature plants at initial growth through flowering and mature plants between budding and flowering attempt to kill or remove African Rue the proper mix of chemical is needed. The mix consists of 2% Arsenal The spraying of African Rue must be completed by a licensed or certified applicator. In order to complete. The operator may contact the Environmental Protection Department or the BLM Noxious Weed must contact the Carlsbad Field Office to inspect the effectiveness of the application treatment to the plant No ground disturbing activities can take place until the inspection by the authorized officer is Coordinator at (575) 234-5972 or BLM_NM_CFO_NoxiousWeeds@blm.gov.

followed. All equipment should be washed off using a power washer in a designated containment area. The containment area shall be bermed to allow for containment of the seed to prevent it from entering any open areas of feet and just large enough to get equipment inside it to be washed off. This will allow all seeds to be in a centrally the nearby landscape. The containment area shall be excavated near or adjacent to the well pad at a depth of three Management Practices: In addition to spraying for African Rue, good management practices should be ocated area that can be treated at a later date if the need arises.

1.4. LIGHT POLLUTION

1.4.1. Downfacing

All permanent lighting will be pointed straight down at the ground in order to prevent light spill beyond the edge of approved surface disturbance.

1.4.2. Shielding

All permanent lighting will use full cutoff luminaires, which are fully shielded (i.e., not emitting direct or indirect light above an imaginary horizontal plane passing through the lowest part of the light source).

Page 5 of 24

1.4.3. Lighting Color

Lighting shall be 3,500 Kelvin or less (Warm White) except during drilling, completion, and workover operations. No bluish-white lighting shall be used in permanent outdoor lighting.

. SPECIAL REQUIREMENTS

1. WATERSHED

allowed to enter the well pad. The integrity of the berm shall be maintained around the surfaced pad throughout the life of the well and around the downsized pad after interim reclamation has been completed. Any water erosion that Topsoil shall not be used to construct the berm. No water flow from the uphill side(s) of the pad shall be pad. The compacted berm shall be constructed at a minimum of 12 inches with impermeable mineral material (e.g. may occur due to the construction of the well pad during the life of the well will be quickly corrected and proper measures will be taken to prevent future erosion. Stockpiling of topsoil is required. The topsoil shall be stockpiled in an appropriate location to prevent loss of soil due to water or wind erosion and not used for berming or erosion control. If fluid collects within the bermed area, the fluid must be vacuumed into a safe container and disposed of The entire well pad(s) will be bermed to prevent oil, salt, and other chemical contaminants from leaving the well properly at a state approved facility.

2.1.1. Tank Battery

½ times the content of the largest tank or 24-hourproduction, whichever is greater (displaced volume from all tanks backing to prevent tears or punctures. Secondary containment holding capacity must be large enough to contain 1 Tank battery locations will be lined and bermed. A 20-mil permanent liner will be installed with a 4 oz. felt within the berms MUST be subtracted from total volume of containment in calculating holding capacity). Automatic shut off, check valves, or similar systems will be installed for tanks to minimize the effects of catastrophic line failures used in production or drilling.

2.1.2. Buried/Surface Line(s)

When crossing ephemeral drainages, the pipeline(s) will be buried to a minimum depth of 48 inches from the top of and vegetation have stabilized. Water bars must be placed within the corridor to divert and dissipate surface runoff. downstream sides of the pipeline crossing. In addition, curled (weed free) wood/straw fiber wattles/logs and/or silt fences must be placed on the downstream side for sediment control during construction and maintained until soils pipe to ground level. Erosion control methods such as gabions and/or rock aprons must be placed on both up and A pipeline access road is not permitted to cross ephemeral drainages. Traffic must be diverted to a preexisting route. Additional seeding may be required in floodplains and drainages to restore energy dissipating vegetation. Prior to pipeline installation/construction a leak detection plan will be developed. The method(s) could incorporate installing electronic sensors to alarm when a leak is present. The leak detection plan will incorporate an automatic shut off system that will be installed for proposed pipelines to minimize the effects of an undesirable event. gauges to detect pressure drops, situating valves and lines so they can be visually inspected periodically or

2.1.3. Electric Line(s)

Any water erosion that may occur due to the construction of overhead electric line and during the life of the power line will be quickly corrected and proper measures will be taken to prevent future erosion. A power pole must not be placed in drainages, playas, wetlands, riparian areas, or floodplains and must span across the features at distance away that does not promote further erosion.

2.1.4. Temporary Use Fresh Water Frac Line(s)

Once the temporary use exceeds the timeline of 180 days and/or with a 90 day extension status; further analysis will be required if the applicant pursues to turn the temporary pipeline into a permanent pipeline.

Page 6 of 24

2.3 WILDLIFE

2.3.2. Texas Hornshell Mussel

Oil and Gas and Associated Infrastructure Mitigation Measures for Zone D – CCA Boundary Requirements:

- Provide CEHMM with the permit, lease, or other authorization form BLM, if applicable
- Provide CEHMM with plats or other electronic media describing the new surface disturbance for the project.

2.4 VISUAL RESOURCE MANAGEMENT

5.1 VRM IV

Above-ground structures including meter housing that are not subject to safety requirements are painted a flat nonreflective paint color, Shale Green from the BLM Standard Environmental Color Chart (CC-001: June 2008) Above-ground structures including meter housing that are not subject to safety requirements are painted a flat non-reflective paint color, Shale Green from the BLM Standard Environmental Color Chart (CC-001: June 2008).

3. CONSTRUCTION REQUIRENMENTS

.1 CONSTRCUTION NOTIFICATION

Carlsbad Field Office at BLM_NM_CFO_Construction_Reclamation@blm.gov at least 3 working days prior to The BLM shall administer compliance and monitor construction of the access road and well pad. Notify the commencing construction of the access road and/or well pad.

When construction operations are being conducted on this well, the operator shall have the approved APD and COAs on the well site and they shall be made available upon request by the Authorized Officer.

2 TOPSOIL

The operator shall strip the topsoil (the A horizon) from the entire well pad area and stockpile the topsoil along the edge of the well pad as depicted in the APD. No more than the top 6 inches of topsoil shall be removed. All the Topsoil shall not be used for berming the pad or facilities. For final reclamation, the topsoil shall be spread over the entire pad area for seeding stockpiled topsoil will be redistributed over the interim reclamation areas.

Other subsoil (the B horizon and below) stockpiles must be completely segregated from the topsoil stockpile. Large rocks or subsoil clods (not evident in the surrounding terrain) must be buried within the approved area for interim and final reclamation.

3 CLOSED LOOP SYSTEM

Tanks are required for drilling operations: No reserve pits will be used for drill cuttings. The operator shall properly dispose of drilling contents at an authorized disposal site.

3.4 FEDERAL MINERAL PIT

Payment shall be made to the BLM prior to removal of any federal mineral materials. Call the Carlsbad Field Office at (575) 234-5972

3.5 WELL PAD & SURFACING

Any surfacing material used to surface the well pad will be removed at the time of interim and final reclamation.

Page 7 of 24

.6 EXCLOSURE FENCING (CELLARS & PITS)

livestock, and large forms of wildlife before and after drilling operations until the well cellar is free of fluids and the operator initiates backfilling. (For examples of exclosure fencing design, refer to BLM's Oil and Gas Gold The operator will install and maintain exclosure fencing for all open well cellars to prevent access to public, Book, Exclosure Fence Illustrations, Figure 1, Page 18.)

wildlife before and after drilling operations until the well cellar is free of fluids and the operator. Use a maximum The operator will also install and maintain mesh netting for all open well cellars to prevent access to smaller netting mesh size of 1 ½ inches. The netting must not have holes or gaps.

.7 ON LEASE ACESS ROAD

7.1 Road Width

The access road shall have a driving surface that creates the smallest possible surface disturbance and does not exceed fourteen (14) feet in width. The maximum width of surface disturbance, when constructing the access road, shall not exceed twenty-five (25) feet.

7.2 Surfacing

Surfacing material is not required on the new access road driving surface. If the operator elects to surface the new access road or pad, the surfacing material may be required to be removed at the time of reclamation.

Where possible, no improvements will be made on the unsurfaced access road other than to remove vegetation as necessary, road irregularities, safety issues, or to fill low areas that may sustain standing water. The Authorized Officer reserves the right to require surfacing of any portion of the access road at any time deemed necessary. Surfacing may be required in the event the road deteriorates, erodes, road traffic increases, or it is determined to be beneficial for future field development. The surfacing depth and type of material will be determined at the time of notification.

7.3 Crowning

Crowning shall be done on the access road driving surface. The road crown shall have a grade of approximately 2% (i.e., a 1" crown on a 14' wide road). The road shall conform to Figure 1; cross section and plans for typical road construction.

3.7.4 Ditching

Ditching shall be required on both sides of the road.

3.7.5 Turnouts

Vehicle turnouts shall be constructed on the road. Turnouts shall be intervisible with interval spacing distance less than 1000 feet. Turnouts shall conform to Figure 1; cross section and plans for typical road construction.

3.7.6 Drainage

Drainage control systems shall be constructed on the entire length of road (e.g. ditches, sidehill outsloping and insloping, leadoff ditches, culvert installation, and low water crossings). A typical lead-off ditch has a minimum depth of 1 foot below and a berm of 6 inches above natural ground level. The berm shall be on the down-slope side of the lead-off ditch.

Cross Section of a Typical Lead-off Ditch

Page 8 of 24



All lead-off ditches shall be graded to drain water with a 1 percent minimum to 3 percent maximum ditch slope. The spacing interval are variable for lead-off ditches and shall be determined according to the formula for spacing intervals of lead-off ditches, but may be amended depending upon existing soil types and centerline road slope (in

Formula for Spacing Interval of Lead-off Ditches

Example - On a 4% road slope that is 400 feet long, the water flow shall drain water into a lead-off ditch. Spacing interval shall be determined by the following formula:

400' + 100' = 200' lead-off ditch interval 400 foot road with 4% road slope:

Δ

3.7.7 Public Access

Public access on this road shall not be restricted by the operator without specific written approval granted by the Authorized Officer.

Page 9 of 24




Figure 1. Cross-sections and plans for typical road sections representative of BLM resource or FS local and higher-class roads.

Page 10 of 24

4. PIPELINES

- The BLM, Carlsbad Field Office, will be informed immediately if any subsurface drainage channels, passages, or voids are intersected by trenching, and no pipe will be laid in the trench at that point until clearance has been issued by the Authorized Officer.
- and lines so they can be visually inspected periodically or installing electronic sensors to alarm when The method could incorporate gauges to detect pressure drops, situating values A leak detection plan will be submitted to the BLM Carlsbad Field Office for approval prior to leak is present. The leak detection plan will incorporate an automatic shut off system that will be installed for proposed pipelines to minimize the effects of an undesirable event. pipeline installation.
- Regular monitoring is required to quickly identify leaks for their immediate and proper treatment.
- All spills or leaks will be reported to the BLM immediately for their immediate and proper treatment.

4.1 BURIED PIPELINES

survey plat and/or map, will be on location during construction. BLM personnel may request a copy of your permit during construction to ensure compliance with all stipulations. A copy of the application (APD, or Sundry Notice) and attachments, including conditions of approval,

Operator agrees to comply with the following stipulations to the satisfaction of the Authorized Officer:

- The Operator shall indemnify the United States against any liability for damage to life or property arising from the occupancy or use of public lands under this APD. _;
- 761.193.) Additionally, any release of toxic substances (leaks, spills, etc.) in excess of the reportable quantity established by 40 CFR Part 117 shall be reported as required by the Comprehensive required or requested by any Federal agency or State government as a result of a reportable release or used, generated by or stored on the pipeline corridor or on facilities authorized under this APD. (See enacted or promulgated. In any event, the operator shall comply with the Toxic Substances Control Act of 1976 as amended, 15 USC 2601 et seq. (1982) with regards to any toxic substances that are spill of any toxic substances shall be furnished to the authorized officer concurrent with the filing The Operator shall comply with all applicable Federal laws and regulations existing or hereafter Environmental Response, Compensation, and Liability Act, section 102b. A copy of any report 40 CFR Part 702-799 and especially, provisions on polychlorinated biphenyls, 40 CFR 761.1the reports to the involved Federal agency or State government. \ddot{c}
- Resource Conservation and Recovery Act, 42 U.S.C.6901, et seq.) on the Pipeline corridor (unless the The operator agrees to indemnify the United States against any liability arising from the release of any release or threatened release is wholly unrelated to the operator's activity on the pipeline corridor), resulting from the activity of the Operator on the pipeline corridor. This agreement applies without Environmental Response, Compensation and Liability Act of 1980, 42 U.S.C. 9601, et seq. or the hazardous substance or hazardous waste (as these terms are defined in the Comprehensive regard to whether a release is caused by the operator, its agent, or unrelated third parties. \ddot{s}
- or other pollutant is discharged from the pipeline system, impacting Federal lands, the control and total If, during any phase of the construction, operation, maintenance, or termination of the pipeline, any oil responsibility of operator, regardless of fault. Upon failure of operator to control, dispose of, or clean clean up the discharge and restore the area, including where appropriate, the aquatic environment and Federal lands, the Authorized Officer may take such measures as he deems necessary to control and up such discharge on or affecting Federal lands, or to repair all damages resulting therefrom, on the removal, disposal, and cleaning up of such oil or other pollutant, wherever found, shall be the 4.

Page 11 of 24

Such action by the Authorized Officer shall not relieve operator of any responsibility as provided herein. fish and wildlife habitats, at the full expense of the operator.

- All construction and maintenance activity will be confined to the authorized pipeline corridor. 5
- The pipeline will be buried with a minimum cover of 36 inches between the top of the pipe and ground 6.
- The maximum allowable disturbance for construction in this pipeline corridor will be 30 feet: ۲.
- operations will not exceed 20 feet. The trench is included in this area. (Blading is defined as the Blading of vegetation within the pipeline corridor will be allowed: maximum width of blading complete removal of brush and ground vegetation.)
- Clearing of brush species within the pipeline corridor will be allowed: maximum width of clearing operations will not exceed 30 feet. The trench and bladed area are included in this area. (Clearing is defined as the removal of brush while leaving ground vegetation (grasses, weeds, etc.) intact. Clearing is best accomplished by holding the blade 4 to 6 inches above the ground surface.)
- The remaining area of the pipeline corridor (if any) shall only be disturbed by compressing the vegetation. (Compressing can be caused by vehicle tires, placement of equipment, etc.)
- The operator shall stockpile an adequate amount of topsoil where blading is allowed. The topsoil to be inches in depth. The topsoil will be segregated from other spoil stripped is approximately 6 inches in depth. The topsoil will be segregated from other spoi piles from trench construction. The topsoil will be evenly distributed over the bladed area for the preparation of seeding. ∞:
- surrounding landscape. The backfilled soil shall be compacted, and a 6-inch berm will be left over the approved by the Authorized Officer. The entire pipeline corridor shall be recontoured to match the Vegetation, soil, and rocks left as a result of construction or maintenance activity will be randomly scattered on this pipeline corridor and will not be left in rows, piles, or berms, unless otherwise ditch line to allow for settling back to grade. 9.
- and at all road crossings. At a minimum, signs will state the operator's name, BLM serial number, and The pipeline will be identified by signs at the point of origin and completion of the pipeline corridor the product being transported. All signs and information thereon will be posted in a permanent, conspicuous manner, and will be maintained in a legible condition for the life of the pipeline. 10.
- determined necessary by the Authorized Officer in consultation with the operator before maintenance The operator shall not use the pipeline route as a road for purposes other than routine maintenance as used as a roadway. As determined necessary during the life of the pipeline, the Authorized Officer begins. The operator will take whatever steps are necessary to ensure that the pipeline route is not may ask the operator to construct temporary deterrence structures. 11.
- includes associated roads, pipeline corridor and adjacent land affected by the establishment of weeds due to this action. The operator shall consult with the Authorized Officer for acceptable weed control operations. Weed control shall be required on the disturbed land where noxious weeds exist, which The operator shall be held responsible if noxious weeds become established within the areas of methods, which include following EPA and BLM requirements and policies. 12.
- entrapped. At a minimum, the operator will construct and maintain escape ramps, ladders, or other methods of avian and terrestrial wildlife escape in the trenches according to the following criteria: otherwise fenced, screened, or netted to prevent livestock, wildlife, and humans from becoming Escape Ramps - The operator will construct and maintain pipeline/utility trenches [that are not 13.

Page 12 of 24

- before the trench is backfilled, the contractor/operator shall inspect the trench for wildlife, remove Any trench left open for eight (8) hours or less is not required to have escape ramps; however, all trapped wildlife, and release them alive at least 100 yards from the trench. ಡ
- trench is backfilled, the contractor/operator shall inspect the trench for wildlife, remove all trapped wildlife, and release them alive at least 100 yards from the trench. 30-degree slope and spaced no more than 500 feet apart) shall be placed in the trench. Before the For trenches left open for eight (8) hours or more, earthen escape ramps (built at no more than a <u>ب</u>

SURFACE PIPELINES

A copy of the APD and attachments, including stipulations, survey plat(s) and/or map(s), shall be on location during construction. BLM personnel may request to review a copy of your permit during construction to ensure compliance with all stipulations.

Operator agrees to comply with the following stipulations to the satisfaction of the Authorized Officer:

- Operator shall indemnify the United States against any liability for damage to life or property arising from the occupancy or use of public lands under this APD. _;
- promulgated. In any event, Operator shall comply with the Toxic Substances Control Act of 1976 as amended, 15 USC § 2601 et seq. (1982) with regard to any toxic substances that are used, generated by Operator shall comply with all applicable Federal laws and regulations existing or hereafter enacted or or stored on the pipeline corridoror on facilities authorized under this APD (see 40 CFR, Part 702-799 and in particular, provisions on polychlorinated biphenyls, 40 CFR 761.1-761.193). Additionally, any Federal agency or State government as a result of a reportable release or spill of any toxic substances shall be furnished to the Authorized Officer concurrent with the filing of the reports to the involved release of toxic substances (leaks, spills, etc.) in excess of the reportable quantity established by 40 Compensation, and Liability Act, section 102b. A copy of any report required or requested by any CFR, Part 117 shall be reported as required by the Comprehensive Environmental Response, Federal agency or State government. \vec{c}
- Resource Conservation and Recovery Act, 42 U.S.C. 6901, et seq.) on the Pipeline corridor (unless the corridor), or resulting from the activity of the Operator on the pipeline corridor. This provision applies release or threatened release is wholly unrelated to activity of the Operator's activity on the Pipeline Environmental Response, Compensation and Liability Act of 1980, 42 U.S.C. § 9601, et seq. or the Operator agrees to indemnify the United States against any liability arising from the release of any without regard to whether a release is caused by Operator, its agent, or unrelated third parties. hazardous substance or hazardous waste (as these terms are defined in the Comprehensive 3
- Sec. 2883.1-4. Operator shall be held to a standard of strict liability for damage or injury to the United Operator shall be liable for damage or injury to the United States to the extent provided by 43 CFR States resulting from pipe rupture, fire, or spills caused or substantially aggravated by any of the following within the pipeline corridor or permit area: 4.
- Activities of Operator including, but not limited to: construction, operation, maintenance, and termination of the facility; ಚ
- Activities of other parties including, but not limited to: Ъ.
 - (1) Land clearing
- Earth-disturbing and earth-moving work 000
- Vandalism and sabotage
- Acts of God

The maximum limitation for such strict liability damages shall not exceed one million dollars (\$1,000,000)

Page 13 of 24

for any one event, and any liability in excess of such amount shall be determined by the ordinary rules of negligence of the jurisdiction in which the damage or injury occurred. This section shall not impose strict liability for damage or injury resulting primarily from an act of war or from the negligent acts or omissions of the United States.

- If, during any phase of the construction, operation, maintenance, or termination of the pipeline, any oil, control and total removal, disposal, and cleaning up of such oil, salt water, or other pollutant, wherever aquatic environment and fish and wildlife habitats, at the full expense of Operator. Such action by the found, shall be the responsibility of Operator, regardless of fault. Upon failure of Operator to control, dispose of, or clean up such discharge on or affecting Federal lands, or to repair all damages resulting necessary to control and clean up the discharge and restore the area, including, where appropriate, the salt water, or other pollutant is discharged from the pipeline system, impacting Federal lands, the therefrom, on the Federal lands, the Authorized Officer may take such measures as they deem Authorized Officer shall not relieve Operator of any responsibility as provided herein. 5.
- All construction and maintenance activity shall be confined to the authorized pipeline corridor width of 30-feet. If the pipeline route follows an existing road or buried pipeline corridor, the surface pipeline shall be installed no farther than 10 feet from the edge of the road or buried pipeline corridor. If immediately adjacent to the outer surface pipeline. All construction and maintenance activity shall be existing surface pipelines prevent this distance, the proposed surface pipeline shall be installed confined to existing roads or pipeline corridors. 6.
- No blading or clearing of any vegetation shall be allowed unless approved in writing by the Authorized ۲.
- Operator shall install the pipeline on the surface in such a manner that will minimize suspension of the pipeline across low areas in the terrain. In hummocky of duney areas, the pipeline shall be "snaked" around hummocks and dunes rather than suspended across these features. ∞:
- Burial of the pipe will continue for 20 feet on each side of each crossing. The condition of the road, upon completion of construction, shall be returned to at least its former state with no bumps or dips The pipeline shall be buried with a minimum of 6 inches under all roads, "two-tracks," and trails. remaining in the road surface. 6
- improvements prior to disturbing them. When necessary to pass through a fence line, the fence shall be The operator is required to promptly repair improvements to at least their former state. Functional use The operator shall minimize disturbance to existing fences and other improvements on public lands. of these improvements will be maintained at all times. The operator will contact the owner of any braced on both sides of the passageway prior to cutting of the fence. No permanent gates will be allowed unless approved by the Authorized Officer. 10.
- will install such structures as are suitable for the specific soil conditions being encountered and which In those areas where erosion control structures are required to stabilize soil conditions, the operator are in accordance with sound resource management practices. 11:
- simulates "Standard Environmental Colors" Shale Green, Munsell Soil Color No. 5Y 4/2; designated Excluding the pipe, all above-ground structures not subject to safety requirement shall be painted by the operator to blend with the natural color of the landscape. The paint used shall be a color which by the Rocky Mountain Five State Interagency Committee. 12.
- and at all road crossings. At a minimum, signs will state the operator's name, BLM serial number, and The pipeline will be identified by signs at the point of origin and completion of the pipeline corridor the product being transported. Signs will be maintained in a legible condition for the life of the 13.

Page 14 of 24

- The operator shall not use the pipeline route as a road for purposes other than routine maintenance as determined necessary by the Authorized Officer in consultation with the operator. The operator will take whatever steps are necessary to ensure that the pipeline route is not used as a roadway. 4.
- includes the roads, powerline corridor, and adjacent land affected by the establishment of weeds due to operations. Weed control shall be required on the disturbed land where noxious weeds exist, which The operator shall be held responsible if noxious weeds become established within the areas of this action. The operator shall consult with the Authorized Officer for acceptable weed control methods, which include following EPA and BLM requirements and policies. 15.
- Surface pipelines shall be less than or equal to 4 inches and a working pressure below 125 psi. 16.

3 OVERHEAD ELECTRIC LINES

location during construction. BLM personnel may request to you a copy of your permit during A copy of the APD and attachments, including stipulations, survey plat and/or map, will be on construction to ensure compliance with all stipulations. Operator agrees to comply with the following stipulations to the satisfaction of the Authorized Officer:

- The operator shall indemnify the United States against any liability for damage to life or property arising from the occupancy or use of public lands under this APD.
- corridor. (See 40 CFR, Part 702-799 and especially, provisions on polychlorinated biphenyls, 40 CFR any report required or requested by any Federal agency or State government as a result of a reportable used, generated by or stored on the powerline corridor or on facilities authorized under this powerline release or spill of any toxic substances shall be furnished to the authorized officer concurrent with the Comprehensive Environmental Response, Compensation, and Liability Act, section 102b. A copy of enacted or promulgated. In any event, the operator shall comply with the Toxic Substances Control Act of 1976 as amended, 15 USC 2601 et seq. (1982) with regards to any toxic substances that are 761.1-761.193.) Additionally, any release of toxic substances (leaks, spills, etc.) in excess of the The operator shall comply with all applicable Federal laws and regulations existing or hereafter reportable quantity established by 40 CFR, Part 117 shall be reported as required by the filing of the reports to the involved Federal agency or State government. ri
- The operator agrees to indemnify the United States against any liability arising from the release of any Resource Conservation and Recovery Act, 42 U.S.C. 6901, et seq.) on the Powerline corridor(unless corridor), or resulting from the activity of the Operator on the powerline corridor. This agreement Environmental Response, Compensation and Liability Act of 1980, 42 U.S.C. 9601, et seq. or the applies without regard to whether a release is caused by the operator, its agent, or unrelated third the release or threatened release is wholly unrelated to the operator's activity on the powerline hazardous substance or hazardous waste (as these terms are defined in the Comprehensive 3
- There will be no clearing or blading of the powerline corridor unless otherwise agreed to in writing by the Authorized Officer. 4.
- placed on this powerline corridor, should they be necessary to ensure the safety of large perching birds. Practices for Avian Protection on Power lines: The State of the Art in 2006" Edison Electric Institute, Such modifications and/or additions shall be made by the operator without liability or expense to the Officer. The BLM reserves the right to require modification or additions to all powerline structures roosting, and nesting. Such proof shall be provided by a raptor expert approved by the Authorized APLIC, and the California Energy Commission 2006. The operator shall assume the burden and Power lines shall be constructed and designed in accordance to standards outlined in "Suggested expense of proving that pole designs not shown in the above publication deter raptor perching, United States. δ.

Page 15 of 24

- Raptor deterrence will consist of but not limited to the following: triangle perch discouragers shall be placed on each side of the cross arms and a nonconductive perching deterrence shall be placed on all vertical poles that extend past the cross arms. 6.
- The operator is required to promptly repair improvements to at least their former state. Functional use improvements prior to disturbing them. When necessary to pass through a fence line, the fence shall The operator shall minimize disturbance to existing fences and other improvements on public lands. of these improvements will be maintained at all times. The operator will contact the owner of any be braced on both sides of the passageway prior to cutting the fence. No permanent gates will be allowed unless approved by the Authorized Officer. ۲,
- manner where the power line crosses roads and at all serviced facilities. Numbers will be at least two inches high and will be affixed to the pole nearest the road crossing and at the facilities served. The BLM serial number assigned to this authorization shall be posted in a permanent, conspicuous ∞
- Upon cancellation, relinquishment, or expiration of this APD, the operator shall comply with those abandonment procedures as prescribed by the Authorized Officer. 6
- days of abandonment, relinquishment, cancellation, or expiration of this APD, whichever comes first. abandonment, relinquishment, or termination of use of the serviced facility or facilities or within 180 This will not apply where the power line extends service to an active, adjoining facility or facilities. All surface structures (poles, lines, transformers, etc.) shall be removed within 180 days of 10.

11. Special Stipulations:

For reclamation remove poles, lines, transformer, etc. and dispose of properly. Fill in any holes from the poles removed.

4.4 RANGLAND MITIGATION FOR PIPELINES

4.5.1 Fence Requirement

prior condition, or better. The operator shall notify the private surface landowner or the grazing allotment passageway with H-braces prior to cutting. Once the work is completed, the fence will be restored to its Where entry is granted across a fence line, the fence must be braced and tied off on both sides of the operator prior to crossing any fence(s).

4.5.2 Cattleguards

An appropriately sized cattleguard(s) sufficient to carry out the project shall be installed and maintained at are damaged or have deteriorated beyond practical use. The operator shall be responsible for the condition road-fence crossing(s). Any existing cattleguard(s) on the access road shall be repaired or replaced if they of the existing cattleguard(s) that are in place and are utilized during lease operations. A gate shall be constructed on one side of the cattleguard and fastened securely to H-braces.

4.5.3 Livestock Watering Requirement

Structures that provide water to livestock, such as windmills, pipelines, drinking troughs, and earthen reservoirs, will be avoided by moving the proposed action.

operations from the well site, must be immediately corrected by the operator. The operator must notify the BLM office (575-234-5972) and the private surface landowner or the grazing allotment operator if any Any damage to structures that provide water to livestock throughout the life of the well, caused by damage occurs to structures that provide water to livestock.

- Livestock operators will be contacted, and adequate crossing facilities will be provided as needed to ensure livestock are not prevented from reaching water sources because of the open trench.
- Wildlife and livestock trails will remain open and passable by adding soft plugs (areas where the trench is excavated and replaced with minimal compaction) during the construction phase. Soft plugs with ramps on either side will be left at all well-defined livestock and wildlife trails along

Page 16 of 24

the open trench to allow passage across the trench and provide a means of escape for livestock and wildlife that may enter the trench.

cannot be backfilled immediately will have escape ramps (wooden) placed at no more than 2,500 Operator will avoid leaving trenches open overnight to the extent possible and open trenches that Trenches will be backfilled as soon as feasible to minimize the amount of open trench. The feet intervals and sloped no more than 45 degrees.

5. PRODUCTION (POST DRILLING)

5.1 WELL STRUCTURES & FACILITIES

5.1.1 Placement of Production Facilities

Production facilities must be placed on the well pad to allow for maximum interim recontouring and revegetation of the well location.

5.1.2 Exclosure Netting (Open-top Tanks)

maximum netting mesh size of 1 ½ inches. The netting must not be in contact with fluids and must not have prevent wildlife and livestock access, including avian wildlife, to all open-topped tanks that contain or have the potential to contain salinity sufficient to cause harm to wildlife or livestock, hydrocarbons, or Resource Immediately following active drilling or completion operations, the operator will take actions necessary to Conservation and Recovery Act of 1976-exempt hazardous substances. At a minimum, the operator will operator uses netting, the operator will cover and secure the open portion of the tank to prevent wildlife entry. The operator will net, screen, or cover the tanks until the operator removes the tanks from the ocation or the tanks no longer contain substances that could be harmful to wildlife or livestock. Use a net, screen, or cover open-topped tanks to exclude wildlife and livestock and prevent mortality. If the holes or gaps.

5.1.3. Chemical and Fuel Secondary Containment and Exclosure Screening

containment system for any tank or barrel containing hazardous, poisonous, flammable, or toxic substances Environmental Protection Agency livestock water standards in accordance with state law; the operator must The operator will dispose of fluids within the containment system that do not meet applicable state or U. S. contact with soil and water. At a minimum, the operator will install and maintain an impervious secondary operator will install effective wildlife and livestock exclosure systems such as fencing, netting, expanded sufficient to contain the contents of the tank or barrel and any drips, leaks, and anticipated precipitation. not drain the fluids to the soil or ground. The operator will design, construct, and maintain all secondary The operator will prevent all hazardous, poisonous, flammable, and toxic substances from coming into containment systems to prevent wildlife and livestock exposure to harmful substances. At a minimum, metal mesh, lids, and grate covers. Use a maximum netting mesh size of 1 1/2 inches.

5.1.4. Open-Vent Exhaust Stack Exclosures

equipment includes, but may not be limited to, tanks, heater-treaters, separators, dehydrators, flare stacks, (Recommended exclosure structures on open-vent exhaust stacks are in the shape of a cone.) Production equipment to prevent birds and bats from entering, and to discourage perching, roosting, and nesting. The operator will construct, modify, equip, and maintain all open-vent exhaust stacks on production in-line units, and compressor mufflers.

5.1.5. Containment Structures

structure that is constructed to hold the capacity of 1.5 times the largest tank, plus freeboard to account for Proposed production facilities such as storage tanks and other vessels will have a secondary containment precipitation, unless more stringent protective requirements are deemed necessary.

Page 17 of 24

6. RECLAMATION

Stipulations required by the Authorized Officer on specific actions may differ from the following general guidelines

6.1 ROAD AND SITE RECLAMATION

contaminants are indicated then testing will be required for chlorides and applicable contaminate anomalies Federal, State and Local statutes, regulations, and ordinances) and seeded to the specifications in sections for final disposal determination (disposed of in a manner approved by the Authorized Officer within Any roads constructed during the life of the well will have the caliche removed or linear burial. If 6.5 and 6.6.

6.2 EROSION CONTROL

down-slope. The surface must be left rough in order to catch and contain rainfall on-site. Any trenches between windrows must be ripped to a depth of at least 12", unless bedrock is encountered. Any large boulders pulled up during ripping must be deep-buried on location. Ripping must be perpendicular to perpendicular to down-slope drainage; steeper slopes will require greater windrow density. Topsoil Install erosion control berms, windrows, and hummocks. Windrows must be level and constructed resulting from erosion cause by run-off shall be addressed immediately.

6.3 INTERIM RECLAMATION

During the life of the development, all disturbed areas not needed for active support of production operations must undergo interim reclamation in order to minimize the environmental impacts of development on other resources and uses. Within six (6) months of well completion, operators must work with BLM surface protection specialists (BLM_NM_CFO_Construction_Reclamation@blm.gov) to devise the best strategies to reduce the size of the location. Interim reclamation must allow for remedial well operations, as well as safe and efficient removal of oil and gas.

order to operate the well or complete workover operations, it may be necessary to drive, park and operate on During reclamation, the removal of caliche and any other surface material is required. Removed caliche that is free of contaminants may be used for road repairs, fire walls or for building other roads and locations. In restored interim vegetation within the previously disturbed area. Disturbing revegetated areas for production or workover operations will be allowed. If there is significant disturbance and loss of vegetation, the area will need to be revegetated. Communicate with the appropriate BLM office for any exceptions/exemptions All disturbed areas after they have been satisfactorily prepared need to be reseeded with the seed mixture provided in section 6.6. Upon completion of interim reclamation, the operator shall submit a Sundry Notice, Subsequent Report of Reclamation (Form 3160-5)

6.4 FINAL ABANDONMENT & RECLAMATION

Prior to surface abandonment, the operator shall submit a Notice of Intent Sundry Notice and reclamation

At final abandonment, well locations, production facilities, and access roads must undergo "final" reclamation so that the character and productivity of the land are restored.

Page 18 of 24

Earthwork for final reclamation must be completed within six (6) months of well plugging. All pads, pits, facility locations and roads must be reclaimed to a satisfactory revegetated, safe, and stable condition, unless an agreement is made with the landowner or BLM to keep the road and/or pad intact.

by the BLM. After earthwork and seeding is completed, the operator is required to submit a Sundry Notice, mixture provided below. Seeding will be accomplished by drilling on the contour whenever practical or by After all disturbed areas have been satisfactorily prepared, these areas need to be revegetated with the seed other approved methods. Seeding may need to be repeated until revegetation is successful, as determined Subsequent Report of Reclamation.

Operators shall contact a BLM surface protection specialist prior to surface abandonment operations for site specific objectives (BLM_NM_CFO_Construction_Reclamation@blm.gov).

6.5 SEEDING TECHNIQUES

ripped or dragged to aid in covering the seed. The seed mixture shall be evenly and uniformly planted over Seeds shall be hydro-seeded, mechanically drilled, or broadcast, with the broadcast-seeded area raked, the disturbed area.

6.6 SOIL SPECIFIC SEED MIXTURE

Commercial seed will be either certified or registered seed. The seed container will be tagged in accordance shall be planted in the amounts specified in pounds of pure live seed (PLS)* per acre. There shall be no primary or secondary noxious weeds in the seed mixture. Seed will be tested and the viability testing of The lessee/permitee shall seed all disturbed areas with the seed mixture listed below. The seed mixture seed will be done in accordance with State law(s) and within nine (9) months prior to purchase. with State law(s) and available for inspection by the Authorized Officer.

uniformly planted over the disturbed area. Smaller/heavier seeds tend to drop the bottom of the drill and are regulator to ensure proper depth of planting where drilling is possible. The seed mixture will be evenly and planted first; the operator shall take appropriate measures to ensure this does not occur. Where drilling is Seed land application will be accomplished by mechanical planting using a drill equipped with a depth not possible, seed will be broadcast and the area shall be raked or chained to cover the seed. When broadcasting the seed, the pounds per acre are to be doubled. The seeding will be repeated until a satisfactory BLM or Soil Conservation District stand is established as determined by the Authorized Officer. Evaluation of growth will not be made before completion of at least one full growing season after seeding or until several months of precipitation have occurred, enabling a full four months of growth, with one or more seed generations being established.

Page 19 of 24

Seed Mixture 2, for Sandy Site

Species to be planted in pounds of pure live seed* per acre:

l <u>b/acre</u>	1.0	1.0	2.0
Species	Sand dropseed (Sporobolus cryptandrus)	Sand love grass (Eragrostis trichodes)	Plains bristlegrass (Setaria macrostachya)

*Pounds of pure live seed:

Pounds of seed x percent purity x percent germination = pounds pure live seed

Page 20 of 24

Page 21 of 24

LING PLAN: BLM COMPLIANCE (Supplement to BLM 3160-3) DRILLING PLAN:

POKER LAKE UNIT 18-30 BD 202H
Projected TD: 22236.89' MD / 9335' TVD
SHL: 265' FNL & 2335' FEL , Section 18, T25S, R30E
BHL: 2646' FNL & 1758' FEL , Section 30, T25S, R30E XTO Energy Inc. EDDY County, NM

1. Geologic Name of Surface Formation

Quaternary

2. Estimated Tops of Geological Markers & Depths of Anticipated Fresh Water, Oil or Gas

Formation	Well Depth (TVD)	Water/Oil/Gas
Rustler	712'	Water
Top of Salt	1143'	Water
Base of Salt	3315'	Water
Delaware	3534'	Water
Brushy Canyon	2699,	Water/Oil/Gas
Bone Spring	7300'	Water
Avalon	7467	Water/Oil/Gas
1st Bone Spring	,0908	Water/Oil/Gas
2nd Bone Spring	8208	Water/Oil/Gas
Target/Land Curve	9335'	Water/Oil/Gas

No other formations are expected to yield oil, gas or fresh water in measurable volumes. The surface fresh water sands will be protected by setting 9.625 inch casing @ 812' (331' above the salt) and circulating cement back to surface. The intermediate will isolate from the top of salt down to the next casing seat by setting 7.625 inch casing at 8452.1' and cemented to surface. A 6.75 inch curve and 6.75 inch lateral hole will be drilled to 22236.89 MD/TD and 5.5 inch production casing will be set at TD and cemented back up in the intermediate shoe (estimated TOC 8152.1 feet).

3. Casing Design

SF Tension	19.40	2.22	3.07	700	2.27
SF SF Burst Collapse	7.75	2.86	2.71	0 04	2.51
SF Burst	1.88	4.00	2.91	40.4	1.05
New/Used	wəN	wəN	weN	Tro N	New
Collar	втс	Flush Joint	Flush Joint	Semi-premium/ Freedom HTQ	Semi-flush/ Talon HTQ
Grade	J-55	RY P-110	HC L-80	RY P-110	RY P-110
OD Csg Weight	40	29.7	7:67	20	20
OD Csg	9.625	7.625	7.625	5.5	5.5
Depth	0' – 812'	0, – 4000,	4000' – 8452.1'	0' - 8352.1'	8352.1' - 22236.89'
Hole Size	12.25	8.75	8.75	6.75	6.75

[·] XTO requests the option to utilize a spudder rig (Atlas Copco RD20 or Equivalent) to set and cement

^{***} Hydrocarbons @ Brushy Canyon
*** Groundwater depth 40' (per NM State Engineers Office).

Wellhead:

XTO will utilize a 3 string Multi-bowl system.

4. Cement Program

XTO requests the option to offline cement and remediate (if needed) surface and intermediate casing strings where batch drilling is approved and if unplanned remediation is needed. XTO will ensure well is static with no pressure on the csg annulus, as with all other casing strings where batch drilling operations occur before moving off the rig. The TA cap will also be installed when applicable per Cactus procedure and pressure inside the casing will be monitored via the valve on the TA cap as per standard batch drilling ops. Offline cement operations will then be conducted after the rig is moved off the current well to the next well in the batch sequence.

Surface Casing: 9.625, 40 New BTC, J-55 casing to be set at +/- 815

Lead: 170 sxs EconoCem-HLTRRC (mixed at 10.5 ppg, 1.87 ft3/sx, 10.13 gal/sx water)

Tail: 130 sxs Class C + 2% CaCl (mixed at 14.8 ppg, 1.35 ft3/sx, 6.39 gal/sx water)

Surface Top of Cement:

900 psi 12-hr =

Intermediate Casing: 7.625, 29.7 New casing to be set at +/- 8452.1'

1st Stage

Optional Lead: 310 sxs Class C (mixed at 10.5 ppg, 2.77 ft3/sx, 15.59 gal/sx water)

: Surface

Tail: 250 sxs Class C (mixed at 14.8 ppg, 1.35 ft3/sx, 6.39 gal/sx water)

TOC: Brushy Canyon @ 5699 Compressives

24 hr = 1150 psi900 psi

Lead: 0 sxs Class C (mixed at 12.9 ppg, 2.16 ft3/sx, 9.61 gal/sx water)

Tail: 640 sxs Class C (mixed at 14.8 ppg, 1.33 ft3/sx, 6.39 gal/sx water)

Top of Cement:

24 hr = 1150 psi 900 psi

being pumped conventionally with the calculated top of cement at the Brush Canyon (5699') and the second 1% PreMag-M + 6% Bentonite Gel (2.30 yld, 12.91 ppg) will be executed as a contingency. If cement is still cement is not visually confirmed to circulate to surface, the final cement top after the second stage job will be verified by Echo-meter. If necessary, a top out consisting of 1,500 sack of Class C cement + 3% Salt + XTO requests to pump a two stage cement job on the 7-5/8" intermediate casing string with the first stage stage performed as a bradenhead squeeze with planned cement from the Brushy Canyon to surface. If unable to circulate to surface, another Echo-meter run will be performed for cement top verification.

XTO will report to the BLM the volume of fluid (limited to 5 bbls) used to flush intermediate casing valves following backside cementing procedures, XTO requests to pump an Optional Lead if well conditions dictate in an attempt to bring cement inside the first intermediate casing. If cement reaches the desired height, the BLM will be notified and the second stage bradenhead squeeze and subsequent TOC verification will be negated.

approval from BLM when unplanned remediation is needed and batch drilling is approved. In the event the and pressure inside the casing will be monitored via the valve on the TA cap as per standard batch drilling XTO requests the option to conduct the bradenhead squeeze and TOC verification offline as per standard static with floats holding and no pressure on the csg annulus as with all other casing strings where batch drilling operations occur before moving off the rig. The TA cap will also be installed per Cactus procedure bradenhead is conducted, we will ensure the first stage cement job is cemented properly and the well is

Production Casing: 5.5, 20 New Semi-Flush, RY P-110 casing to be set at +/- 22236.89

Lead: 20 sxs NeoCem (mixed at 11.5 ppg, 2.69 ft3/sx, 15.00 gal/sx water) Top of Cement: Tail: 970 sxs VersaCem (mixed at 13.2 ppg, 1.51 ft3/sx, 8.38 gal/sx water) Top of Cement: Compressives: 12-hr = 800 psi

8152.1 feet 8652.1 feet

5. Pressure Control Equipment

Once the permanent WH is installed on the casing, the blow out preventer equipment (BOP) will consist of a 5M Hydril Annular and a 10M Triple Ram BOP.

All BOP testing will be done by an independent service company. Operator will test as per 43 CFR3172

A variance is requested to allow use of a flex hose as the choke line from the BOP to the Choke Manifold.

XTO requests a variance to be able to batch drill this well if necessary. In doing so, XTO will set casing a ensure that the well is cemented properly (unless approval is given for offline cementing) and the well is static. With floats holding, no pressure on the csg annulus, and the installation of a 10K TA cap as per Cactus recommendations, XTO will contact the BLM to skid the rig to drill the remaining wells on the pad. Once surface and both intermediate strings are all completed, XTO will begin drilling the production

A variance is requested to **ONLY** test broken pressure seals on the BOP equipment when moving from wellhead to wellhead which is in compliance with API Standard 53.

XTO requests a variance to utilize a spudder rig.

6. Proposed Mud Circulation System

I WAS DEFINE	8-13 STST	FFIN	MW	Viscosity	Fluid Loss	Additional
INIERVAL		Mud 1 ype	(bdd)	(sec/qt)	(cc)	Comments
0'-812'	12.25	FW/Native 8.4-8.9	8.4-8.9	35-40	NC	Fresh water or native water
812' - 8452.1'	8.75	Saturated brine for salt interval / Direct Emulsion	9-9.5	30-32	NC	Fully saturated salt across salado / salt
8452.1' - 22236.89'	6.75	OBM	9.1-9.6	50-60	NC - 20	N/A

The necessary mud products for weight addition and fluid loss control will be on location at all times.

recorded on a daily drilling report after mudding up. A Pason or Totco will be used to detect changes in loss or gain of mud volume. A mud test will be performed every 24 hours to determine: density, viscosity, strength, filtration and pH as necessary. Use available solids controls equipment to help keep mud weight down after mud up. Rig up solids control equipment to operate as a closed loop system. Spud with fresh water/native mud. Drill out from under surface casing with Saturated Salt. A saturated salt brine mud will be used while drilling through the salt formation. Use fibrous materials as needed to control seepage and lost circulation. Pump viscous sweeps as needed for hole cleaning. Pump speed will be

7. Auxiliary Well Control and Monitoring Equipment

- A Kelly cock will be in the drill string at all times.

 A full opening drill pipe stabbing valve having appropriate connections will be on the rig floor at all times.

 H2S monitors will be on location when drilling below the 9.625 casing. A B O

8. Logging, Coring and Testing Program

Open hole logging will not be done on this well.

detect any H2S occurrences. Should these circumstances be encountered the operator and drilling contractor are prepared to take all necessary steps to ensure safety of all personnel and environment. Lost circulation could occur but is not expected to be a serious problem in this area and hole seepage will be compensated for by additions of small amounts of LCM in the drilling fluid. Abnormal Pressures and Temperatures / Potential Hazards
 None Anticipated. BHT of 160 to 180 F is anticipated. No H2S is expected but monitors will be in place to

10. Anticipated Starting Date and Duration of Operations Anticipated spud date will be after BLM approval. Move in operations and drilling is expected to take 40

DRILLING CONDITIONS OF APPROVAL PECOS DISTRICT

OPERATOR'S NAME:XTO Permian Operating LLCWELL NAME & NO.:Poker Lake Unit 18-30 BD 202HLOCATION:Section 18, T.25S., R.30E.

COA

Eddy County

COUNTY:

H2S	• Yes	o No	
Potash	None	© Secretary	C R-111-P
Cave/Karst Potential © Low	© Low	© Medium	C High
Cave/Karst Potential	© Critical		
Variance	© None	© Flex Hose	© Other
Wellhead	© Conventional	• Multibowl	C Both
Wellhead Variance	© Diverter		
Other	■4 String	Capitan Reef	ddIM
Other	Fluid Filled	Pilot Hole	Open Annulus
Cementing	Contingency	EchoMeter	Primary Cement
	Cement Squeeze		Squeeze
Special Requirements Mater Disposal	Water Disposal	MO2	🔽 Unit
Special Requirements Batch Sundry	☐ Batch Sundry		
Special Requirements	Break Testing	Offline	Casing
Variance		Cementing	Clearance

A. HYDROGEN SULFIDE

the Hydrogen Sulfide area must meet 43 CFR part 3170 requirements, which includes A Hydrogen Sulfide (H2S) Drilling Plan shall be activated AT SPUD. As a result, If Hydrogen Sulfide is encountered, please provide measured values and formations to the BLM. equipment and personnel/public protection items.

Possibility of water flows in the Salado

Abnormal pressures may be encountered within the 3rd Bone Spring and Wolfcamp Possibility of lost circulation in the Red Beds, Rustler, and Delaware. Formations.

B. CASING

- The 9-5/8 inch surface casing shall be set at approximately 812 feet (a minimum of 70 feet (Eddy County) into the Rustler Anhydrite, above the salt, and below usable fresh water) and cemented to the surface. The surface hole shall be 12-1/4 inch in diameter.
- to verify the top of the cement. Temperature survey will be run a minimum of survey with surface log readout will be used or a cement bond log shall be run be notified and a temperature survey utilizing an electronic type temperature If cement does not circulate to the surface, the appropriate BLM office shall six hours after pumping cement and ideally between 8-10 hours after completing the cement job. ಕ
 - Wait on cement (WOC) time for a primary cement job will be a minimum of hours or 500 pounds compressive strength, whichever is greater. (This is to include the lead cement) Ъ.
- Wait on cement (WOC) time for a remedial job will be a minimum of 4 hours after bringing cement to surface or 500 pounds compressive strength, whichever is greater. ပ
- If cement falls back, remedial cementing will be done prior to drilling out that ġ
- The minimum required fill of cement behind the 7-5/8 inch intermediate casing is: 7
- Cement to surface. If cement does not circulate see B.1.a, c-d above.

in the annulus Or operator shall run a CBL from TD of the 7-5/8" casing to surface cementing stage. Operator must run Echo-meter to verify Cement Slurry/Fluid top Operator has proposed to pump down 9-5/8" X 7-5/8" annulus after primary after the second stage BH to verify TOC.

top of the cement slurry between second stage BH and top out. Operator must run Submit results to the BLM. No displacement fluid/wash out shall be utilized at the one CBL per Well Pad.

If cement does not reach surface, the next casing string must come to surface.

Operator must use a limited flush fluid volume of 1 bbl following backside cementing procedures.

- The minimum required fill of cement behind the 5-1/2 inch production casing is: 3
- Cement should tie-back at least 200 feet into previous casing string. Operator shall provide method of verification.

S. PRESSURE CONTROL

- specification to be readily available. No external damage to flex line. Flex line to be Variance approved to use flex line from BOP to choke manifold. Manufacturer's installed as straight as possible (no hard bends).
- tested when installed on the 9-5/8 inch surface casing. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the Operator has proposed a multi-bowl wellhead assembly. This assembly will only be surface casing shoe shall be 5000 (5IM) psi. $\vec{\alpha}$
- Wellhead shall be installed by manufacturer's representatives, submit documentation with subsequent sundry.
- If the welding is performed by a third party, the manufacturer's representative shall monitor the temperature to verify that it does not exceed the maximum temperature of the seal. ب
- Manufacturer representative shall install the test plug for the initial BOP test. ပ
 - possible with a standard wellhead, the well head shall be cut off, cementing If the cement does not circulate and one inch operations would have been operations performed and another wellhead installed. ġ
 - Whenever any seal subject to test pressure is broken, all the tests in 43 CFR **3172** i must be followed. \mathbf{o}

). SPECIAL REQUIREMENT (S)

Unit Wells

designation, but will replace the unit number with the participating area number when the The well sign for a unit well shall include the unit number in addition to the surface and bottom hole lease numbers. This also applies to participating area numbers. If a participating area has not been established, the operator can use the general unit sign is replaced.

Commercial Well Determination

A commercial well determination shall be submitted after production has been established for at least six months.

SPECIAL REQUIREMENT (S) E.

BOPE Break Testing Variance

- BOPE Break Testing is ONLY permitted for 5M BOPE or less. (Annular preventer must be tested to a minimum of 70% of BOPE working pressure and shall be higher than the MASP)
 - BOPE Break Testing is NOT permitted to drilling the production hole section.
- Variance only pertains to the intermediate hole-sections and no deeper than the Bone Springs formation.
 - While in transfer between wells, the BOPE shall be secured by the hydraulic carrier or cradle.
- Engineer (575-706-2779) prior to the commencement of any BOPE Break Testing Any well control event while drilling require notification to the BLM Petroleum operations.
- A full BOPE test is required prior to drilling the first deep intermediate hole section. If any subsequent hole interval is deeper than the first, a full BOPE test will be required. (200' TVD tolerance between intermediate shoes is allowable)
- The BLM is to be contacted (575-361-2822 Eddy County) 4 hours prior to BOPE
- As a minimum, a full BOPE test shall be performed at 21-day intervals.
- In the event any repairs or replacement of the BOPE is required, the BOPE shall test as per **43** CFR 3172.
- If in the event break testing is not utilized, then a full BOPE test would be conducted

Offline Cementing

Contact the BLM prior to the commencement of any offline cementing procedure.

GENERAL REOUIREMENTS

The BLM is to be notified in advance for a representative to witness:

- Spudding well (minimum of 24 hours)
- Setting and/or Cementing of all casing strings (minimum of 4 hours) BOPE tests (minimum of 4 hours) Ъ.
- X Eddy County

EMAIL or call the Carlsbad Field Office, 620 East Greene St., Carlsbad, NM 88220,

NM_CFO_DrillingNotifications@BLM.GOV BLM_NM_CF((575) 361-2822

Call the Hobbs Field Station, 414 West Taylor, Hobbs NM 88240, (575) 689-5981

Page 4 of 9

- properly plugged, the drilling rig shall not be removed from over the hole without Unless the production casing has been run and cemented or the well has been prior approval _;
- pressure rating to the wellhead and a pressure gauge that can be monitored after installing and testing the wellhead, by installing a blind flange of like skid/walking rig. Operator shall secure the wellbore on the current well, In the event the operator has proposed to drill multiple wells utilizing a while drilling is performed on the other well(s).
- When the operator proposes to set surface casing with Spudder Rig Ъ.
- Notify the BLM when moving in and removing the Spudder Rig.
- Notify the BLM when moving in the 2nd Rig. Rig to be moved in within 90 days of notification that Spudder Rig has left the location.
- BOP/BOPE test to be conducted per 43 CFR 3172 as soon as 2nd Rig is rigged up on well. Ξ.
- at all times during drilling and/or completion activities. Rig floor is defined as the the rig floor, unobstructed, readily accessible to the driller and will be operational Floor controls are required for 3M or Greater systems. These controls will be on substructure on which the draw works are located, this does not include the dog area immediately around the rotary table; the area immediately above the house or stairway area. 7
- spacer and drilling mud. The results should be documented in the driller's log and verified with a visual check and density or pH check to differentiate cement from For intervals in which cement to surface is required, cement to surface should be daily reports. ω.

A. CASING

API. The Operator can exchange the components of the proposal with that of superior strength (i.e. changing from J-55 to N-80, or from 36# to 40#). substantial (i.e. Multistage tool, ECP, etc.). The initial wellhead installed Changes to the approved APD casing program need prior approval if the items substituted are of lesser grade or different casing size or are Nonaltered cement plan has less volume or strength or if the changes are Changes to the approved cement program need prior approval if the on the well will remain on the well with spools used as needed.

- reaches a minimum compressive strength of 500 psi for all cement blends pressure until both of the following conditions have been met: 1) cement of both lead and tail cement, 2) until cement has been in place at least $\frac{8}{8}$ Wait on cement (WOC) for Potash Areas: After cementing but before integrity test can be done (prior to the cement setting up) immediately commencing any tests, the casing string shall stand cemented under hours. WOC time will be recorded in the driller's log. The casing after bumping the plug. \ddot{c}
- cement slurry requirements. The casing integrity test can be done (prior to pressure until both of the following conditions have been met: 1) cement cement has been in place at least 8 hours. WOC time will be recorded in reaches a minimum compressive strength of 500 psi at the shoe, 2) until the driller's log. See individual casing strings for details regarding lead Wait on cement (WOC) for Water Basin: After cementing but before commencing any tests, the casing string shall stand cemented under the cement setting up) immediately after bumping the plug. 3
- pounds compressive strength prior to cementing each casing string. Have well specific cement details onsite prior to pumping the cement for each Provide compressive strengths including hours to reach required 500 casing string. 4.
 - No pea gravel permitted for remedial or fall back remedial without prior authorization from the BLM engineer. S.
- anticipated to control the formation pressure to the next casing depth or at On that portion of any well approved for a 5M BOPE system or greater, a pressure integrity test of each casing shoe shall be performed. Formation total depth of the well. This test shall be performed before drilling more at the shoe shall be tested to a minimum of the mud weight equivalent than 20 feet of new hole. 6.
- If hardband drill pipe is rotated inside casing, returns will be monitored for metal. If metal is found in samples, drill pipe will be pulled and rubber protectors which have a larger diameter than the tool joints of the drill pipe will be installed prior to continuing drilling operations. 7.
 - Whenever a casing string is cemented in the R-111-Q potash area, the NMOCD requirements shall be followed. ∞

B. PRESSURE CONTROL

All blowout preventer (BOP) and related equipment (BOPE) shall comply with well control requirements as described in 43 CFR 3172

Page 6 of 9

Approval Date: 05/19/2025

- from BOP to choke manifold, replace if exterior is damaged or if line fails Anchor requirements, specification sheet and hydrostatic pressure These documents shall be posted in the company man's trailer and on the must meet the requirements of API 16C. Check condition of flexible line If a variance is approved for a flexible hose to be installed from the BOP can be exchanged with a hose of equal size and equal or greater pressure to the choke manifold, the following requirements apply: The flex line anchored according to Manufacturer's requirements. The flexible hose test. Line to be as straight as possible with no hard bends and is to be test certification matching the hose in service, to be onsite for review. \ddot{c}
- to match. The remote kill line is to be installed prior to testing the system 5M or higher system requires an HCR valve, remote kill line and annular and tested to stack pressure.
- If the operator has proposed a multi-bowl wellhead assembly in the APD. The following requirements must be met: 4.
- Wellhead shall be installed by manufacturer's representatives, submit documentation with subsequent sundry.
- representative shall monitor the temperature to verify that it does If the welding is performed by a third party, the manufacturer's not exceed the maximum temperature of the seal. :≓
- Manufacturer representative shall install the test plug for the initial BOP test. Ξ.
- Whenever any seal subject to test pressure is broken, all the tests in 43 CFR 3172.6(b)(9) must be followed. .<u>`</u>
- have been possible with a standard wellhead, the well head shall be If the cement does not circulate and one inch operations would cut off, cementing operations performed and another wellhead installed. >
- The appropriate BLM office shall be notified a minimum of 4 hours in advance for a representative to witness the tests. 5
- In a water basin, for all casing strings utilizing slips, these are to be which will be approximately six hours after bumping the plug. For can begin after cut-off or once cement reaches 500 psi compressive those casing strings not using slips, the minimum wait time before cut-off is eight hours after bumping the plug. BOP/BOPE testing strength (including lead cement), whichever is greater. However, set as soon as the crew and rig are ready and any fallback cement installation can be initiated four hours after installing the slips, remediation has been done. The casing cut-off and BOP

- if the float does not hold, cut-off cannot be initiated until cement reaches 500 psi compressive strength (including lead when specified)
- and BOP installation can be initiated at twelve hours after bumping the cement plug. The BOPE test can be initiated after bumping the In potash areas, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. For all casing strings, casing cut-off cement plug with the casing valve open. (only applies to single stage cement jobs, prior to the cement setting up.) :=;
 - immediately with the casing valve open. The operator also has the against the casing) pursuant to 43 CFR 3172 with the pressure not option of utilizing an independent tester to test without a plug (i.e. to exceed 70% of the burst rating for the casing. Any test against compressive strength, whichever is greater, prior to initiating the the casing must meet the WOC time for 8 hours or 500 pounds test (see casing segment as lead cement may be critical item). utilizing a test plug not a cup or J-packer and can be initiated The tests shall be done by an independent service company Ξ.
- If a twelve hour or twenty-four hour chart is used, tester shall make The test shall be run on a 5000 psi chart for a 2-3M BOP/BOP, on a 10000 psi chart for a 5M BOP/BOPE and on a 15000 psi chart for a 10M BOP/BOPE. If a linear chart is used, it shall be a one hour chart. A circular chart shall have a maximum 2 hour clock. a notation that it is run with a two hour clock. . .
- The results of the test shall be reported to the appropriate BLM $\dot{>}$
- All tests are required to be recorded on a calibrated test chart. A service company test will be submitted to the appropriate BLM copy of the BOP/BOPE test chart and a copy of independent ۲.
- 300 psi. The test will be held for a minimum of 10 minutes if test The BOP/BOPE test shall include a low pressure test from 250 to is done with a test plug and 30 minutes without a test plug. This test shall be performed prior to the test at full stack pressure. ΥΠ.
- depth exceeds 20 days. This test does not exclude the test prior to within 500 feet of the top of the Wolfcamp formation if the time between the setting of the intermediate casing and reaching this BOP/BOPE must be tested by an independent service company drilling out the casing shoe as per 43 CFR 3172. VIII.

C. DRILLING MUD

audio alarms, shall be operating before drilling into the Wolfcamp formation, and Mud system monitoring equipment, with derrick floor indicators and visual and shall be used until production casing is run and cemented.

D. WASTE MATERIAL AND FLUIDS

contained and disposed of properly at a waste disposal facility. No waste material created as a result of drilling operations and completion operations shall be safely or fluid shall be disposed of on the well location or surrounding area. Porto-johns and trash containers will be on-location during fracturing operations or any other All waste (i.e. drilling fluids, trash, salts, chemicals, sewage, gray water, etc.) crew-intensive operations.

JS 4/28/2025

Page 9 of 9

Approval Date: 05/19/2025



Operator Certification Data Report

U.S. Department of the Interior BUREAU OF LAND MANAGEMENT

Operator

knowledge, true and correct; and that the work associated with the operations proposed herein will be performed in conformity with this APD package and the terms and conditions under which it is approved. I also certify that I, or the company I represent, am responsible for the operations conducted under this application. These statements are subject to the provisions of 18 U.S.C. 1001 for the filing of false statements. proposed herein; that I am familiar with the conditions which currently exist; that I have full knowledge of state and Federal laws applicable to this operation; that the statements made in this APD package are, to the best of my I hereby certify that I, or someone under my direct supervision, have inspected the drill site and access route

Signed on: 09/23/2024 **NAME:** SIVAPRAKASH SELVAM

Title: Regulatory Clerk

Street Address: 22777 SPRINGWOODS VILLAGE PARKWAY

City: SPRING State: TX

Zip: 77389

Phone: (720)539-1673

Email address: SIVAPRAKASH.SELVAM1@EXXONMOBIL.COM

Field

Representative Name:

Street Address:

City: State:

Zip:

Phone:

Email address:

AFMSS

U.S. Department of the Interior BUREAU OF LAND MANAGEMENT

APD ID: 10400100857

Submission Date: 09/23/2024

Operator Name: XTO PERMIAN OPERATING LLC

Well Name: POKER LAKE UNIT 18-30 BD

Well Type: OIL WELL

Well Work Type: Drill Well Number: 202H

Highlighted data reflects the most recent changes Show Final Text

Application Data 05/19/2025

Section 1 - General

Tie to previous NOS? N 10400100857 APD ID:

Title: Regulatory Clerk **User: SIVAPRAKASH SELVAM BLM Office:** Carlsbad

Is the first lease penetrated for production Federal or Indian? FED

Submission Date: 09/23/2024

Lease Acres:

Lease number: NMLC065705B

Federal/Indian APD: FED

Reservation:

Federal or Indian agreement: FEDERAL

Allotted? Surface access agreement in place?

Agreement number: NMNM71016X

Agreement in place? YES

Agreement name: POKER LAKE UNIT

Keep application confidential? Y

Permitting Agent? NO

APD Operator: XTO PERMIAN OPERATING LLC

Operator letter of

Operator Info

Operator Organization Name: XTO PERMIAN OPERATING LLC

Operator Address: 6401 HOLIDAY HILL ROAD BLDG 5

Zip: 79707

Operator PO Box:

State: TX **Operator City: MIDLAND**

Operator Phone: (432)683-2277

Operator Internet Address:

Section 2 - Well Information

Master Development Plan name: Well in Master Development Plan? NO

Well in Master SUPO? NO

Well in Master Drilling Plan? NO

Well Number: 202H Well Name: POKER LAKE UNIT 18-30 BD

Field/Pool or Exploratory? Field and Pool

Pool Name: BONE SPRING EAST Field Name: PIERCE CROSSING

Master Drilling Plan name:

Master SUPO name:

Well API Number:

Operator Name: XTO PERMIAN OPERATING LLC

Well Name: POKER LAKE UNIT 18-30 BD

Well Number: 202H

is the proposed well in an area containing other mineral resources? USEABLE WATER, NATURAL GAS, OIL

New surface disturbance? N Use Existing Well Pad? Y Is the proposed well in a Helium production area? N

Type of Well Pad: MULTIPLE WELL

Multiple Well Pad Name:
POKER LAKE UNIT 18-19 18-30
BD

BD Number of Legs: 1

Well Work Type: Drill

Well Class: DUAL-COMPLETION

Well Type: OIL WELL

Describe Well Type:

Well sub-Type: INFILL

Describe sub-type:

Distance to lease line: 265 FT Distance to nearest well: 30 FT Distance to town:

Reservoir well spacing assigned acres Measurement: 400 Acres

XTO_POKER_LAKE_UNIT_18_30_BD_202H_C_102_FINAL_09_12_2024_20250312113847.pdf Well plat:

Duration: 45 DAYS

Well work start Date: 10/05/2025

Section 3 - Well Location Table

Survey Type: RECTANGULAR

Describe Survey Type:

Datum: NAD83

Survey number:

Reference Datum: GROUND LEVEL

Vertical Datum: NAVD88

	Will this well produce from this	>	\
	αντ		865 0
	MD		865 2
	Elevation	317 9	- 547 1
	Lease Number	NMLC0 317 65705B 9	NMLC0 - 65705B 547
	Гезге Туре	ட	Ь
	Meridian	NEW MEXI CO	NEW MEXI CO
	State	NEW MEXI CO	NEW MEXI CO
	County	EDD Y	EDD Y
	Pongitude	- 103.9196 Y 4	- 103.9196 Y 4
	Latitude	32.13671 8	32.13671 8
	Aliquot/Lot/Tract	Aliquot NWNE	Aliquot NWNE
4	Section	18	18
	Кsnge	30E	30E
	dswT	25S	25S
	EW Indicator	FEL	FEL
	EW-Foot	233	233 5
	NS Indicator	FNL 233	FNL
	Joo-Foot	265	265
	Wellbore	SHL Leg #1	KOP Leg #1

Page 2 of 3


Operator Name: XTO PERMIAN OPERATING LLC

Well Name: POKER LAKE UNIT 18-30 BD

Well Number: 202H

Will this well produce from this	>	>	>	>
ΠVT	936 6	936 6	936 6	936 6
MD	977 7	150	221 47	222 37
Elevation	- 618 7	- 618 7	- 618 7	- 618 7
Fesse Mumber	NMLC0 - 65705B 618	NMLC0 70341	NMLC0 70125	NMLC0 70125
Гезге Туре	ட	L	ш	ш 🧀
Meridian	NEW MEXI CO	NEW F	NEW MEXI CO	NEW MEXI CO
State	NEW MEXI CO	NEW MEXI CO	NEW MEXI CO	NEW MEXI CO
County	EDD	EDD	EDD	EDD
Pongitude	- 103.9177 Y 77	- 103.9177 Y 55	- 103.9177 Y 21	- 103.9177 Y 2
-butitude	32.13717 2	Aliquot 32.12283 NWNE ⁶	32.10119 8	Aliquot 32.10095 SWNE 1
Aliquot/Lot/Tract	Aliquot 32 NWNE 2	Aliquot 32 NWNE 6		
Section	9	19	30	30
Кзиде	30E	30E	30E	30E
dswT	25S	25S	25S	25S
EW Indicator	FEL	FEL	FEL	FEL
foo4-W∃	175 8	175 9	175 8	175 8
NS Indicator	N N	FSL	Z Z	N N
foo-Foot	100	0	255 6	264 6
Wellbore	PPP Leg #1-1	PPP Leg #1-2	EXIT Leg #1	BHL Leg #1

								Initial Submittal	uittal
							Submital Tvpe:	Amended Report	eport
								☐ As Drilled	
				WELL LOCATI	WELL LOCATION INFORMATION				
API Number 30-015-		Pool Code [96473]	73]	Pc	Pool Name PIERCE	PIERCE CROSSING,		BONE SPRING, EAST	AST
Property Code		Property Name	ne	POKER I AK	POKEBIAKE IINIT 18-30 BD			Well Number	т 202H
OGRID No.		Operator Name						Ground Level Elevation	Elevation
373075	<u> </u>	Tribol & Eodom		XTO PERMIAN OPERATING	OPERATING, LLC.		T. Indian	S Supposed	3,179
Surface Owner.	2	Inidai Narede	<u>a</u>			2	TIDGE I	ederai	
				Surface F	Surface Hole Location				
UL Section 1 B 18	Township 25S	Range 30E	Lot	Ft. from N/S 265 FNL	Ft. from E/W 2,335 FEL	Latitude 32.136718		Longitude -103.919640	County
				Bottom F	Bottom Hole Location				
UL Section 1 G 30	Township 25S	Range 30E	Lot	Ft. from N/S 2,646 FNL	Ft. from E/W 1,758 FEL	Latitude 32.100951		Longitude -103.917720	County
					,				
Dedicated Acres 1	Infill or Defining Well	ng Well	Defining Well API 200H	Vell API 200H	Overlapping Spacing Unit (Y/N) No		Consolidation Code	n Code	
Order Numbers.					Well Setbacks are under Common Ownership:	r Common Ow	nership:	N Ves □No	
				Kick Off	Kick Off Paint (KOP)				
UL Section 1	Township	Range	Lot	Ft. from N/S	Ft. from E/W	Latitude	Ic	Longitude	County
B 18	25S	30E		265 FNL	2,335 FEL	32.136718		-103.919640	EDDY
				First Tak	First Take Point (FTP)			-	
Section	Township	Range	Lot	Ft. from N/S	Ft. from E/W	Latitude		Longitude	County
2 2	222	30E		100 FNL	1,738 FEL	32.13/1/2		-103.91///	EDDY
-				Last Tak	Last Take Point (LTP)				
Section	Township	Range	Lot	Ft. from N/S	Ft. from E/W	Latitude		Longitude	County
30	25S	30E		2,556 FNL	1,758 FEL	32.101198		-103.917721	EDDY
Unitized Area of Area of Interest	fInterest					Ground	Ground Elevation		
NMNM-071016X	V	•	Spacing Unit Type:	t Type: MHorizontal	ntal 🛮 Vertical			3,179'	
OPERATOR CERTIFICATIONS	ATIONS				SURVEYOR CERTIFICATIONS	SNOIL			
hereby certify that the	information c	ontained herei	n is true and		I hereby certify that the w	ell location shov	vn on this p	lat was plotted fi	om field notes of
est of my knowledge an nat this organization eit	d belief, and, ther owns a w	if the well is working interest	ertical or dii or unleasec		actual surveys made by me or under my supervision, and that the same is true and correct to the best of my belief	e or under my su elief	tpervision, o	and that the sam	is true and
in the cards netted for proposed order or a region of as a region of an in the and netted for the proposed order of an information pursuant to a contract with an owner of a working interest or unleased mineral interest, or a voluntary pooling agreement or a compulsory.	proposea bor to a contract t, or a volunt	tom note tocat with an owner try pooling ag	ion or nas a · of a workir reement or α	right to arill this ig interest or compulsory			\	W DILLOW A	(2
ooling order of heretof	ore entered by	the division.		,			M	NEX/G	ARP
If this well is a horizontal well, I further certify that this organization has received the consent of at least one lessee or owner of a working interest or unlessed mineral threats it need trace (in the target pool or information) in this known one of the scall; coundard instead of the bound or obtained in	il well, I furth it least one le: it in each trac	er certify that a see or owner of t (in the target	this organizate working pool or info	ation has interest or rmation) in			PF	23786	FC.
men any part of the we ompulsory pooling ord	u s comptetee er from the di	i mtervat wilt t vision.	oe tocated o	· obtained a		\ \ \	OFF		EVE
Par Dal		9/23	9/23/2024				£3/	ONAL ONAL	tens.
Signature		Date			Signature and Seal of Professional Surveyor	essional Survey	or		
Adrian BaKEK					MARK DILLON HARP 23786	ı		9/12/2024	
Printed Name					Certificate Number	Date of Survey	urvey		
adrian.baker@exxonmobil.com	xonmobil.	COM							
man Address					ā			7 00 00000	,



Page 1 of 6

AFMSS

BUREAU OF LAND MANAGEMENT U.S. Department of the Interior

APD ID: 10400100857

Operator Name: XTO PERMIAN OPERATING LLC

Well Name: POKER LAKE UNIT 18-30 BD

Well Type: OIL WELL

Submission Date: 09/23/2024

Highlighted data reflects the most ecent changes

Show Final Text

Well Work Type: Drill Well Number: 202H

Drilling Plan Data Report 05/19/2025

Geologic Formations - Section

Producing	rormatio	Z	z	Z	z	z	z	>	>	>	>
Mineral Resources Producing	ISEABLE WATED	USEABLE WATER	USEABLE WATER	NONE	NONE	NATURAL GAS, OIL, OTHER : Produced water					
	Lithologies	ALLOVION	ANHYDRITE, SANDSTONE	SALT	SALT	LIMESTONE, SANDSTONE	SANDSTONE	LIMESTONE, SANDSTONE	LIMESTONE, SANDSTONE	LIMESTONE, SANDSTONE	LIMESTONE, SANDSTONE
Measured	Deptin	0	712	1143	3315	3534	2699	7300	8060	8208	9230
True Vertical Measured	c	O	712	1143	3315	3534	5699	7300	8060	8508	9230
;;;;;;;;;;;;;;;;;;;;;;;;;;;;;;;;;;;;;;	Elevation 3179	31/9	2467	2036	-136	-355	-2520	-4121	-4881	-5329	-6051
	Pormation Name	QUATERNARY	RUSTLER	SALADO	BASE OF SALT	DELAWARE	BRUSHY CANYON	BONE SPRING	BONE SPRING 1ST	BONE SPRING 2ND	BONE SPRING 2ND
Formation	15678113	13648113	15648114	15648115	15648116	15648117	15648118	15648119	15648120	15648121	15648123

- Blowout Prevention Section 2

Pressure Rating (PSI): 5M

Rating Depth: 9366

Equipment: Once the permanent WH is installed on the surface casing, the BOP equipment will have a 5M Hydril Annular & a 10M Triple Ram BOP. XTO will use a Multi-Bowl System which is attached.

Requesting Variance? YES

Variance request: A variance is requested to allow use of a flex hose. See attached. XTO requests a variance to be able to batch drill this well if necessary. XTO requests a break test variance. See attached. XTO requests a variance to utilize a spudder rig. See attached.

Testing Procedure: All BOP testing will be done by an independent service company. Operator will test as per 43 CFR

Choke Diagram Attachment:

18_30_BD__10MCM_20250307054052.pdf POKER_LAKE_UNIT_18_19

Page 2 of 6

Operator Name: XTO PERMIAN OPERATING LLC

Well Name: POKER LAKE UNIT 18-30 BD

Well Number: 202H

_10MCM_20250307054052.pdf 18_30_BD_ POKER_LAKE_UNIT_18_19_

BOP Diagram Attachment:

18_30_BD__5M10M_BOP_20250307054417.pdf POKER_LAKE_UNIT_18_19_

Section 3 - Casing

Body SF	19.4	3.07	2.27
Body SF Type	DRY	DRY	DRY
48 Iniol	19.4	3.07	2.27
9dyT 3S tnioU	DRY	DRY	DRY
Burst SF	1.88	2.91	1.05
Collapse SF	7.75	2.71	2.51
Joint Type	BUTT	FJ	OTHER - TPN/Wedge 441
tdgiə₩	40	29.7	20
Grade	J-55 ⁴	L-80 29.7	P- ;
Calculated casing length MD	812	8452	
Bottom Set MSL	2367	-5265	-6187 22237
Top Set MSL	3179	3179	3179
Bottom Set TVD	812	8444	9366
QVT fe2 qoT	0	0	0 2
Bottom Set MD	812	8452	22237
Top Set MD	0	0	0
Tapered String	z	>	>
Standard	API	API	NON API
noiilibno	NEW	NEW	NEW
esiS geJ	9.625	7.625	5.5
əzi2 əloH	12.2 5	8.75	6.75
9dyT gning	SURFACE 12.2 9.625	INTERMED 8.75 IATE	PRODUCTI ON
Ol gnissO	-	7	က

Casing Attachments

SURFACE String Casing ID:

Inspection Document:

Spec Document:

Tapered String Spec:

Casing Design Assumptions and Worksheet(s):

Operator Name: XTO PERMIAN OPERATING LLC

Well Name: POKER LAKE UNIT 18-30 BD

Well Number: 202H

Casing Attachments

Casing ID: 2 String INTERMEDIATE

Inspection Document:

Spec Document:

Tapered String Spec:

Casing Design Assumptions and Worksheet(s):

Casing ID: 3 String

Inspection Document:

PRODUCTION

Spec Document:

TPN_5.500_20.00_0.361_P110_ICY_20250307062246.pdf

Wedge_441__5.500__20.00_0.361_P110_ICY_20250307062246.pdf

Tapered String Spec:

POKER_LAKE_UNIT_18_30_BD_202H_CSG_20250307062439.pdf

Casing Design Assumptions and Worksheet(s):

POKER_LAKE_UNIT_18_30_BD_202H_CSG_20250307062507.pdf

Section 4 - Cement

səvifibbA	NA	2% CaCl	NA	NA
Cement type	EconoCem- HLTRRC	100 Class C	100 Class C	100 Class C
Excess%	100	100	100	100
Cu Ft	10.5 317.9	14.8 175.5	14.8 337.5	14.8 851.2
Density	10.5	14.8	14.8	14.8
bləiY	1.87	1.35	1.35	1.33
Quantity(sx)	170	130	250	640
GM mottoB	812	812	5699	8452
□M qoT	0	0	0	5699
Stage Tool Depth				
lisT\bsəL	Lead	Tail	Lead	Tail
String Type	SURFACE	SURFACE	INTERMEDIATE	INTERMEDIATE

Operator Name: XTO PERMIAN OPERATING LLC

Well Name: POKER LAKE UNIT 18-30 BD

Well Number: 202H

səvitibbA	NA	٧N
Cement type	NeoCem	VersaCem
Excess%	30	30
Cu Ft	53.8	1464. 7
Density	11.5	1.51 13.2 1464. 7
bləiY	2.69	1.51
Quantity(sx)	20	026
GM mottoB	8652	2223 7
dM qoΤ	8152	8652
Stage Tool Depth		
lisT\bsəJ	Lead	Tail
String Type	PRODUCTION	PRODUCTION

Section 5 - Circulating Medium

Mud System Type: Closed

Will an air or gas system be Used? NO

Description of the equipment for the circulating system in accordance with 43 CFR 3172:

Diagram of the equipment for the circulating system in accordance with 43 CFR 3172:

Describe what will be on location to control well or mitigate other conditions: The necessary mud products for weight addition and fluid loss control will be on location at all times.

volume. A mud test will be performed every 24 hours to determine: density, viscosity, strength, filtration and pH as necessary. Use available solids controls equipment to help keep mud weight down after mud up. Rig up solids control equipment to Describe the mud monitoring system utilized: Spud with fresh water/native mud. Drill out from under surface casing with needed to control seepage and lost circulation. Pump viscous sweeps as needed for hole cleaning. Pump speed will be recorded on a daily drilling report after mudding up. A Pason or Totco will be used to detect changes in loss or gain of mud Saturated Salt solution. Saturated Salt mud will be used while drilling through the salt formation. Use fibrous materials as operate as a closed loop system.

Circulating Medium Table

8.9	9.5	9.6
8.4	6	9.1
WATER-BASED MUD	OTHER: Saturated Salt for Salt Interval/Direct Emulsion	OIL-BASED MUD
812	8452	8452 2223
0	812	8452
	812 WATER-BASED 8.4 MUD	8452 WATER-BASED 8.4 MUD 8452 OTHER: 9 for Salt for Salt Interval/Direct Emulsion

Page 5 of 6

Operator Name: XTO PERMIAN OPERATING LLC

Well Name: POKER LAKE UNIT 18-30 BD

Well Number: 202H

Section 6 - Test, Logging, Coring

List of production tests including testing procedures, equipment and safety measures:

Open hole logging will not be done on this well.

List of open and cased hole logs run in the well:

GAMMA RAY LOG,CEMENT BOND LOG,DIRECTIONAL SURVEY,MEASUREMENT WHILE DRILLING,MUD LOG/GEOLOGICAL LITHOLOGY LOG,

Coring operation description for the well:

No Coring is planned for the well.

Section 7 - Pressure

Anticipated Bottom Hole Pressure: 4676

Anticipated Bottom Hole Temperature(F): 180

Anticipated Surface Pressure: 2615

Anticipated abnormal pressures, temperatures, or potential geologic hazards? N ${\sf O}$

Describe:

Contingency Plans geoharzards description:

Contingency Plans geohazards

Hydrogen Sulfide drilling operations plan required? YES

Hydrogen sulfide drilling operations

XTO_Energy_H2S_Plan_Updated_20240827051401.pdf

Section 8 - Other Information

Proposed horizontal/directional/multi-lateral plan submission:

POKER_LAKE_UNIT_18_30_BD_202H_DD_20240905125422.pdf

20250310141154.pdf Section_and_Plan_View_1 Poker_Lake_Unit_18_30_BD_202H_Formation_

Other proposed operations facets description:

proposed operations facets attachment: Other

_18_30_BD_MBS_9.625_x_7.625_3String_20240827064007.pdf POKER_LAKE_UNIT_18_19_

_18_30_BD_20250307090455.pdf POKER_LAKE_UNIT_18_30_BD_202H_CMT_20240905125352.pdf H2S_Diagram_POKER_LAKE_UNIT_18_19_

_18_30_BD_NGMP_Form_20250311142753.pdf POKER_LAKE_UNIT_18_19_

Other Variance request(s)?:

Other Variance attachment:

_18_30_BD__OLCV_20240905101924.pdf POKER_LAKE_UNIT_18_19_

BOP_Break_Test_Variance_20240827064431.pdf


Page 6 of 6


Spudder_Rig_Request_20240827064424.pdf Updated_Flex_Hose_20240827064426.pdf

Well Name: POKER LAKE UNIT 18-30 BD Well

Operator Name: XTO PERMIAN OPERATING LLC

Well Number: 202H





14/ -



Coupling	Pipe Body
Grade: P110-ICY	Grade: P110-ICY
Body: White	1st Band: White
1st Band: Pale Green	2nd Band: Pale Green
2nd Band: -	3rd Band: Pale Green
3rd Band: -	4th Band: -
	5th Band: -

Printed on: 01-08-2025

	7		Glade.	Glade: FIIO-101	Glade, P. I. O-I C.	
icilalistiyalli wedge	3	1	Body: White	Mite	1st Band: White	
441®			1st Ban	ার Band: Pale Green	2nd Band: Pale Green	
			2nd Band: -	- :pu	3rd Band: Pale Green	
			3rd Band: -	-: pi	4th Band: -	
					5th Band: -	
					6th Band: -	
Outside Diameter 5.	5.500 in.	Wall Thickness	0.361 in.	Grade	P110-ICY	≿
Min, Wall Thickness	87.50 %	87.50 % Pipe Body Drift AP	API Standard Type	Type	Casing	Dí.
Connection OD Option	REGULAR					

Pipe Body Data

Performance	Body Yield Strength	Min. Internal Yield Pressure	SMYS	Collapse Pressure	
	0.361 in.	19.83 lb/ft	API		
	5.500 in. Wall Thickness	20.00 lb/ft Plain End Weight	4.653 in. OD Tolerance		
	5.500 in.	20.00 lb/ft	4.653 in.	4.778 in.	
Geometry	Nominal OD	Nominal Weight	Drift	Nominal ID	

12,300 psi

729 x1000 lb 14,360 psi 125,000 psi

	12,300 psi	External Pressure Capacity
Tield Tollybe	10 300 noi	External Drassura Canadia
Viold Torgin	04:70	wax. Allowable benuing
operaung rordue	# 001/0 9Z NO	May Allowable Dending
Operating Torgin	2100014 +60	Compression on engin
	594 ×1000 lb	Compression Strenoth
T jimi I moiterano	81.50 %	Compression Efficiency
Maximum	14,360 psi	Internal Pressure Capacity
Optimum	594 x1000 lb	Joint Yield Strength
Minimum	81.50 %	Tension Efficiency
Make-Up Torques		Performance

3.40

Regular

Connection OD Option

Threads per inch

Connection Data

Geometry

5.852 in.

8.714 in. 4.778 in. 3.780 in.

Coupling Length Connection OD

Connection ID Make-up Loss

Make-Up Torques	
Minimum	15,000 ft-lb
Optimum	16,000 ft-lb
Maximum	19,200 ft-lb
Operation Limit Torques	
Operating Torque	36,000 ft-lb
Yield Torque	42,000 ft-lb
Buck-On	
Minimum	19,200 ft-lb
Maximum	20,700 ft-lb

Notes

This connection is fully interchangeable with:

Wedge 44(18-5.5in. - 0.394 (17.00)) in. (Ib/R)

Wedge 44(18-5.5in. - 0.394 (17.00)) / 0.381 (20.00) / 0.415 (23.00) in. (Ib/R)

Connections with Dopeless® Technology are fully compatible with the same connection in its doped version

For the lastest performance data, always, visit our website; www.tenaris.com For further information on concepts indicated in this datasheet, download the Datasheet Manual from www.tenaris.com

Tenaris has issued this document for general information only, and the information in this document, including, without limitation, any pictures, drawings or designs ("Information") is not intended to constitute professional or any other type of advice or recommendation and is provided on an "as is" basis. No warranty is given. I chansis has not independently verified any information —if any provided by the user in connection with, or for the purpose of, the Information contained hereunder. The use of the Information is at user's own risk and Tenaris does not assume any responsibility of largificial for any finds, and any information contained hereunder or any use thereof. The Information in this document is subject to change or modification without notice. Infants is products and services are subject to Tenaris's standard terms and conditions or document in the respective contracts of sale or services, as the case maybe, between petitioner and Tenaris. For more complete information please contact a Tenaris's representative or visit our website at www.tenaris.com. ©lenaris 2025. All rights reserved.

TPN Tenaris



Coupling	Pipe Body
Grade: P1104CY	Grade: P1104CY
Body: White	1st Band: White
1st Band: Pale Green	2nd Band: Pale Green
2nd Band: -	3rd Band: Pale Green
3rd Band: -	4th Band: -
	5th Band: -
	6th Band: -

Printed on: 04/23/2024

Customer	XTO ENERGY INC. Wall Thickness		0.361 in. Grade	Grade	P110-ICY
Outside Diameter	5.500 in.	Pipe Body Driff	API Standard Type	Туре	Casing
Min. Wall Thickness	87.50 %				
Connection OD Option	REGULAR				

Data
Body
Pipe

	Performance	Body Yield Strength	Min. Internal Yield Pressure	SMYS	Collapse Pressure	
		ness 0.361 in.	Veight 19.83 lb/ft	ce API		
		5.500 in. Wall Thickness	20.00 lb/ft Plain End Weight	4.653 in. OD Tolerance	4.778 in.	
San Carried	Geometry	Nominal OD	Nominal Weight	Drift	Nominal ID	

14,360 psi 125,000 psi

12,300 psi

729 x1000 lb

Connection Data

	Performance	Tension Efficiency	Joint Yield Strength	Internal Pressure Capacity	Compression Efficiency	Compression Strength	Max. Allowable Bending	External Pressure Canacity
		6.300 in.	8.408 in.	4.778 in.	4.204 in.	5	Regular	
Connection Data	Geometry	Connection OD	Coupling Length	Connection ID	Make-up Loss	Threads per inch	Connection OD Option	

Make-Up Torques	100 % Minimum 21,100 ft-lb	000 lb Optimum 22,600 ft-lb	960 psi Maximum 24,100 ft-lb	100%	Operation Limit Torques	Operation Torons	chei amig ici que	32 500 #B	enh o	2000
	100 %	729 x1000 lb	14,360 psi	100 %	729 Y 000 Ib	200170	104 °/100 #	1001	12 300 nei	27,000,7

Notes

For the lastest performance data, always visit our website: www.tenaris.com For further information on concepts indicated in this datasheet, download the Datasheet Manual from www.tenaris.com

Tenaris has issued this document for general information only, and the information in this document, including, without limitation, any pictures, drawings or designs ("Information") is not intended to constitute professional or any other type of advice or recommendation and is provided on an "as is" basis. No warranty is given. Tenaris has not independently verified any information —if any provided by the user in connection with, or for the purpose of, the Information contained hereunder. The use of the Information is at user's own risk and Tenaris does not assume any responsibility or flability of any kind for any loss, damage or injury resulting from, or in commedion with any Information contained hereunder or any use thereof. The Information in this document is subject to change or modification without notice. Flantaris is products and services are subject to Tenaris's standard terms and conditions or document in the respective contracts of sale or services, as the case maybe, between petitioner and Tenaris. For more complete information please contact a Tenaris's representative or visit our website at www.tenaris.com. ©Tenaris 2024. All rights reserved.

PI-0/CII-3

Casing Assumptions

Casing Design

-12	ed in				
SF Tension	19.40	2.22	3.07	2.27	2.27
SF Collapse	7.75	2.86	2.71	2.81	2.51
SF Burst	1.88	4.00	2.91	1.05	1.05
New/Used	New	New	New	New	New
Collar	BTC	Flush Joint	Flush Joint	Semi-Premium/ TPN	Semi-Flush/ Wedge 441
Grade	J-55	RY P-110	HC L-80	RY P-100 ICY	RY P-100 ICY
Weight	40	29.7	29.7	20	20
OD Csg	9.625	7.625	7.625	5.5	5.5
Depth	0' – 812'	0' - 4000'	4000' - 8452.1'	0' - 8352.1'	8352.1' - 22236.89'
Hole Size	12.25	8.75	8.75	6.75	6.75

Casing Assumptions

Casing Design

19.40	2.22	3.07	2.27	2.27
7.75	2.86	2.71	2.81	2.51
1.88	4.00	2.91	1.05	1.05
New	New	New	New	New
BTC	Flush Joint	Flush Joint	Semi-Premium/ TPN	Semi-Flush/ Wedge 441
J-55	RY P-110	HC L-80	RY P-100 ICY	RY P-100 ICY
40	29.7	29.7	20	20
9.625	7.625	7.625	5.5	5.5
0' – 812'	0' - 4000'	4000' - 8452.1'	0' - 8352.1'	8352.1' - 22236.89'
12.25	8.75	8.75	6.75	6.75
	0'-812' 9.625 40 J-55 BTC New 1.88 7.75	0'-812' 9.625 40 J-55 BTC New 1.88 7.75 0'-4000' 7.625 29.7 RY P-110 Flush Joint New 4.00 2.86	0'-812' 9.625 40 J-55 BTC New 1.88 7.75 0'-4000' 7.625 29.7 RY P-110 Flush Joint New 4.00 2.86 4000'-8452.1' 7.625 29.7 HC L-80 Flush Joint New 2.91 2.71	0'-812' 9.625 40 J-55 BTC New 1.88 7.75 0'-4000' 7.625 29.7 RY P-110 Flush Joint New 4.00 2.86 4000'-8452.1' 7.625 29.7 HC L-80 Flush Joint New 2.91 2.71 0'-8352.1' 5.5 20 RY P-100 ICY Semi-Premium/ TPN New 1.05 2.81



HYDROGEN SULFIDE (H2S) CONTINGENCY PLAN

Assumed 100 ppm ROE = 3000

100 ppm H2S concentration shall trigger activation of this plan.

Emergency Procedures

In the event of a release of gas containing H₂S, the first responder(s) must

- Isolate the area and prevent entry by other persons into the 100 ppm ROE.
- Evacuate any public places encompassed by the 100 ppm ROE. Be equipped with H_2S monitors and air packs in order to control the release. Use the "buddy system" to ensure no injuries occur during the response
- Take precautions to avoid personal injury during this operation. Contact operator and/or local officials to aid in operation. See list of phone numbers
- Have received training in the o Detection of H₂S, and
- Measures for protection against the gas, 0
- Equipment used for protection and emergency response.

<u>Ignition of Gas source</u>

NMOCD and local officials. Additionally, the NM State Police may become involved. NM State Police shall be the Incident Command on scene of any major release. Take care to protect against exposure to Sulfur Dioxide (SO₂). Intentional ignition must be coordinated with the Should control of the well be considered lost and ignition considered, take care to protect downwind whenever this is an ignition of the gas.

Characteristics of H₂S and SO₂

Lethal Concentration	mdd 009	1000 ppm
Hazardous Limit	100 ppm/hr 6	N/A
Threshold Limit Hazardous Limit	10 ppm	2 ppm
fic Gravity	1.189 Air = I	2.21 Air = I
Chemical Specifical Formula	H ₂ S	SO ₂
Common Name	Hydrogen Sulfide	Sulfur Dioxide

Contacting Authorities

prepared for use during a release. (Operator Name)'s response must be in coordination with the State of New Mexico's "Hazardous Materials Emergency Response Plan" (HMER). possible but no later than 4 hours. Agencies will ask for information such as type and volume of including directions to site. The following call list of essential and potential responders has been response to a major release. Additionally, the OCD must be notified of the release as soon as release, wind direction, location of release, etc. Be prepared with all information available personnel must liaison with local and state agencies to ensure a proper All XTO location

CARLSBAD OFFICE - EDDY & LEA COUNTIES

3104 E. Greene St., Carlsbad, NM 88220 Carlsbad, NM	575-887-7329
Will Dacus, Drilling Manager Brian Dunn, Drilling Supervisor Robert Bartels, Construction Execution Planner Andy Owens, EH & S Manager Frank Fuentes, Production Foreman	832-948-5021 832-653-0490 406-478-3617 903-245-2602 575-689-3363
SHERIFF DEPARTMENTS: Eddy County Lea County	575-887-7551 575-396-3611
NEW MEXICO STATE POLICE:	575-392-5588
FIRE DEPARTMENTS: Carlsbad Eunice Hobbs Jal Lovington	911 575-885-2111 575-394-2111 575-397-9308 575-395-2221 575-396-2359
HOSPITALS: Carlsbad Medical Emergency Eunice Medical Emergency Hobbs Medical Emergency Jal Medical Emergency Lovington Medical Emergency	911 575-885-2111 575-394-2112 575-397-9308 575-395-2221 575-396-2359
AGENT NOTIFICATIONS: For Lea County: Bureau of Land Management – Hobbs New Mexico Oil Conservation Division – Hobbs	575-393-3612 575-393-6161
For Eddy County: Bureau of Land Management - Carlsbad New Mexico Oil Conservation Division - Arresia	575-234-5972

Bone Spring 2 Sand

Well Plan Report - Poker Lake Unit 18-30 BD 202H

Measured Depth: 22236.00 ft Site:

TVD RKB: 9366.00 ft Slot: Poker Lake Unit 18-30 BD 202H

Location

Cartographic New Mexico East -Reference System: NAD 27 Northing: 413661.03 ft Easting: 628202.88 ft RKB: 3211.00 ft **Ground Level:** 3180.00 ft North Reference: Grid **Convergence Angle:** 0.22 Deg

Plan Sections Poker Lake Unit 18-30 BD 202H

Measured			TVD			Build	Turn	Dogleg
Depth	Inclination	Azimuth	RKB	Y Offset	X Offset	Rate	Rate	Rate
(ft)	(Deg)	(Deg)	(ft)	(ft)	(ft)	(Deg/100ft)	(Deg/100ft)	(Deg/100ft) Target
0.00	0.00	0.00	0.00	-0.00	-0.00	0.00	0.00	0.00
1100.00	0.00	0.00	1100.00	-0.00	-0.00	0.00	0.00	0.00
1424.38	6.49	73.82	1423.69	5.11	17.62	2.00	0.00	2.00
6408.92	6.49	73.82	6376.31	162.06	558.50	0.00	0.00	0.00
6733.30	0.00	0.00	6700.00	167.17	576.12	-2.00	0.00	2.00
8652.10	0.00	0.00	8618.80	167.17	576.12	0.00	0.00	0.00
9777.10	90.00	179.71	9335.00	-549.01	579.79	8.00	0.00	8.00
9777.12	90.00	179.71	9335.00	-549.03	579.80	0.00	0.00	0.00
22146.88	90.00	179.71	9335.00	-12918.63	643.32	0.00	0.00	0.00 LTP 13
22236.89	90.00	179.71	9335.00	-13008.64	643.78	0.00	0.00	0.00 BHL3

Position Uncertainty Poker Lake Unit 18-30 BD 202H

Measured			TVD	Highside		Lateral		Vertical		Magnitude	Semi- major	Semi- minor	Semi- minor	Tool
Depth	Inclination	Azimuth	RKB	Error	Bias	Error	Bias	Error	Bias	of Bias	Error	Error	Azimuth	Used
(ft)	(°)	(°)	(ft)	(ft)	(ft)	(ft)	(ft)	(ft)	(ft)	(ft)	(ft)	(ft)	(°)	
0.000	0.000	0.000	31.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	XOMR2_OWSG MWD+IFR1+MS
100.000	0.000	0.000	131.000	0.358	0.000	0.179	0.000	2.300	0.000	0.000	0.358	0.179	90.000	XOMR2_OWSG MWD+IFR1+MS
200.000	0.000	0.000	231.000	0.717	0.000	0.538	0.000	2.309	0.000	0.000	0.717	0.538	90.000	XOMR2_OWSG MWD+IFR1+MS
300.000	0.000	0.000	331.000	1.075	0.000	0.896	0.000	2.325	0.000	0.000	1.075	0.896	90.000	XOMR2_OWSG MWD+IFR1+MS
400.000	0.000	0.000	431.000	1.434	0.000	1.255	0.000	2.346	0.000	0.000	1.434	1.255	90.000	XOMR2_OWSG MWD+IFR1+MS
500.000	0.000	0.000	531.000	1.792	0.000	1.613	0.000	2.373	0.000	0.000	1.792	1.613	90.000	XOMR2_OWSG MWD+IFR1+MS
600.000	0.000	0.000	631.000	2.151	0.000	1.972	0.000	2.405	0.000	0.000	2.151	1.972	90.000	XOMR2_OWSG MWD+IFR1+MS
700.000	0.000	0.000	731.000	2.509	0.000	2.330	0.000	2.441	0.000	0.000	2.509	2.330	90.000	XOMR2_OWSG MWD+IFR1+MS
800.000	0.000	0.000	831.000	2.868	0.000	2.688	0.000	2.483	0.000	0.000	2.868	2.688	90.000	XOMR2_OWSG MWD+IFR1+MS
900.000	0.000	0.000	931.000	3.225	0.000	3.047	0.000	2.528	0.000	0.000	3.225	3.047	90.000	XOMR2_OWSG MWD+IFR1+MS
1000.000	0.000	0.000	1031.000	3.585	0.000	3.404	0.000	2.577	0.000	0.000	3.585	3.404	90.000	XOMR2_OWSG MWD+IFR1+MS
1100.000	0.000	0.000	1131.000	3.942	0.000	3.763	0.000	2.630	0.000	0.000	3.942	3.763	90.000	XOMR2_OWSG MWD+IFR1+MS
1200.000	1.999	73.810	1230.980	4.085	0.000	4.282	0.000	2.686	0.000	0.000	4.295	4.116	90.094	XOMR2_OWSG MWD+IFR1+MS
1300.000	4.000	73.810	1330.838	4.375	0.000	4.629	0.000	2.742	0.000	0.000	4.643	4.464	90.386	XOMR2_OWSG MWD+IFR1+MS
1400.000	6.000	73.810	1430.452	4.654	0.000	4.979	0.000	2.800	0.000	0.000	4.994	4.813	90.739	XOMR2_OWSG MWD+IFR1+MS
1424.300	6.487	73.810	1454.687	4.721	0.000	5.065	0.000	2.812	0.000	0.000	5.080	4.901	90.973	XOMR2_OWSG MWD+IFR1+MS
1500.000	6.487	73.810	1529.823	4.978	0.000	5.331	0.000	2.861	0.000	0.000	5.347	5.164	91.041	XOMR2_OWSG MWD+IFR1+MS
1600.000	6.487	73.810	1629.183	5.319	0.000	5.685	0.000	2.930	0.000	0.000	5.701	5.514	91.115	XOMR2_OWSG MWD+IFR1+MS

1700.000	6.487	73.810 1728.542	5.662 0.000	6.040 0.000	3.001 0.000	0.000	6.056	5.866	91.228 XOMR2_OWSG MWD+IFR1+MS
1800.000	6.487	73.810 1827.902	6.006 0.000	6.395 0.000	3.075 0.000	0.000	6.413	6.218	91.376 XOMR2_OWSG MWD+IFR1+MS
1900.000	6.487	73.810 1927.262	6.351 0.000	6.753 0.000	3.151 0.000	0.000	6.771	6.573	91.545 XOMR2_OWSG MWD+IFR1+MS
2000.000	6.487	73.810 2026.621	6.698 0.000	7.110 0.000	3.230 0.000	0.000	7.129	6.928	91.742 XOMR2_OWSG MWD+IFR1+MS
2100.000	6.487	73.810 2125.981	7.045 0.000	7.469 0.000	3.311 0.000	0.000	7.488	7.284	91.950 XOMR2_OWSG MWD+IFR1+MS
2200.000	6.487	73.810 2225.340	7.393 0.000	7.828 0.000	3.393 0.000	0.000	7.848	7.641	92.171 XOMR2_OWSG MWD+IFR1+MS
2300.000	6.487	73.810 2324.700	7.742 0.000	8.188 0.000	3.477 0.000	0.000	8.209	7.998	92.399 XOMR2_OWSG MWD+IFR1+MS
2400.000	6.487	73.810 2424.060	8.092 0.000	8.548 0.000	3.564 0.000	0.000	8.570	8.357	92.642 XOMR2_OWSG MWD+IFR1+MS
2500.000	6.487	73.810 2523.419	8.442 0.000	8.908 0.000	3.651 0.000	0.000	8.931	8.716	92.894 XOMR2_OWSG MWD+IFR1+MS
2600.000	6.487	73.810 2622.779	8.792 0.000	9.269 0.000	3.742 0.000	0.000	9.293	9.075	93.144 XOMR2_OWSG MWD+IFR1+MS
2700.000	6.487	73.810 2722.139	9.143 0.000	9.630 0.000	3.833 0.000	0.000	9.654	9.434	93.401 XOMR2_OWSG MWD+IFR1+MS
2800.000	6.487	73.810 2821.498	9.494 0.000	9.990 0.000	3.926 0.000	0.000	10.016	9.793	93.669 XOMR2_OWSG MWD+IFR1+MS
2900.000	6.487	73.810 2920.858	9.844 0.000	10.352 0.000	4.020 0.000	0.000	10.379	10.153	93.909 XOMR2_OWSG MWD+IFR1+MS
3000.000	6.487	73.810 3020.218	10.194 0.000	10.712 0.000	4.116 0.000	0.000	10.739	10.511	94.175 XOMR2_OWSG MWD+IFR1+MS
3100.000	6.487	73.810 3119.577	10.545 0.000	11.073 0.000	4.213 0.000	0.000	11.101	10.871	94.446 XOMR2_OWSG MWD+IFR1+MS
3200.000	6.487	73.810 3218.937	10.898 0.000	11.435 0.000	4.313 0.000	0.000	11.465	11.232	94.718 XOMR2_OWSG MWD+IFR1+MS
3300.000	6.487	73.810 3318.296	11.253 0.000	11.799 0.000	4.412 0.000	0.000	11.830	11.596	94.991 XOMR2_OWSG MWD+IFR1+MS
3400.000	6.487	73.810 3417.656	11.605 0.000	12.161 0.000	4.514 0.000	0.000	12.192	11.956	95.267 XOMR2_OWSG MWD+IFR1+MS
3500.000	6.487	73.810 3517.016	11.958 0.000	12.524 0.000	4.618 0.000	0.000	12.556	12.318	95.544 XOMR2_OWSG MWD+IFR1+MS
3600.000	6.487	73.810 3616.375	12.310 0.000	12.888 0.000	4.723 0.000	0.000	12.921	12.678	95.728 XOMR2_OWSG MWD+IFR1+MS

3700.000	6.487	73.810 3715.735	12.662 0.000	13.250	0.000	4.829 0.000	0.000	13.284	13.040	96.006 XOMR2_OWSG MWD+IFR1+MS
3800.000	6.487	73.810 3815.095	13.016 0.000	13.613	0.000	4.938 0.000	0.000	13.648	13.402	96.284 XOMR2_OWSG MWD+IFR1+MS
3900.000	6.487	73.810 3914.454	13.368 0.000	13.977	0.000	5.047 0.000	0.000	14.014	13.763	96.469 XOMR2_OWSG MWD+IFR1+MS
4000.000	6.487	73.810 4013.814	13.721 0.000	14.339	0.000	5.158 0.000	0.000	14.377	14.124	96.747 XOMR2_OWSG MWD+IFR1+MS
4100.000	6.487	73.810 4113.174	14.076 0.000	14.702	0.000	5.271 0.000	0.000	14.741	14.488	97.025 XOMR2_OWSG MWD+IFR1+MS
4200.000	6.487	73.810 4212.533	14.428 0.000	15.067	0.000	5.385 0.000	0.000	15.107	14.849	97.210 XOMR2_OWSG MWD+IFR1+MS
4300.000	6.487	73.810 4311.893	14.785 0.000	15.429	0.000	5.501 0.000	0.000	15.471	15.214	97.576 XOMR2_OWSG MWD+IFR1+MS
4400.000	6.487	73.810 4411.252	15.137 0.000	15.792	0.000	5.619 0.000	0.000	15.835	15.574	97.761 XOMR2_OWSG MWD+IFR1+MS
4500.000	6.487	73.810 4510.612	15.492 0.000	16.157	0.000	5.738 0.000	0.000	16.201	15.938	98.037 XOMR2_OWSG MWD+IFR1+MS
4600.000	6.487	73.810 4609.972	15.846 0.000	16.522	0.000	5.858 0.000	0.000	16.567	16.301	98.218 XOMR2_OWSG MWD+IFR1+MS
4700.000	6.487	73.810 4709.331	16.198 0.000	16.885	0.000	5.982 0.000	0.000	16.932	16.662	98.404 XOMR2_OWSG MWD+IFR1+MS
4800.000	6.487	73.810 4808.691	16.554 0.000	17.247	0.000	6.106 0.000	0.000	17.295	17.026	98.772 XOMR2_OWSG MWD+IFR1+MS
4900.000	6.487	73.810 4908.051	16.909 0.000	17.613	0.000	6.232 0.000	0.000	17.662	17.389	98.952 XOMR2_OWSG MWD+IFR1+MS
5000.000	6.487	73.810 5007.410	17.261 0.000	17.976	0.000	6.360 0.000	0.000	18.026	17.750	99.137 XOMR2_OWSG MWD+IFR1+MS
5100.000	6.487	73.810 5106.770	17.615 0.000	18.340	0.000	6.490 0.000	0.000	18.392	18.112	99.315 XOMR2_OWSG MWD+IFR1+MS
5200.000	6.487	73.810 5206.130	17.969 0.000	18.703	0.000	6.622 0.000	0.000	18.756	18.475	99.586 XOMR2_OWSG MWD+IFR1+MS
5300.000	6.487	73.810 5305.489	18.324 0.000	19.067	0.000	6.756 0.000	0.000	19.121	18.838	99.859 XOMR2_OWSG MWD+IFR1+MS
5400.000	6.487	73.810 5404.849	18.678 0.000	19.431	0.000	6.891 0.000	0.000	19.487	19.201	100.041 XOMR2_OWSG MWD+IFR1+MS
5500.000	6.487	73.810 5504.208	19.033 0.000	19.796	0.000	7.029 0.000	0.000	19.853	19.564	100.220 XOMR2_OWSG MWD+IFR1+MS
5600.000	6.487	73.810 5603.568	19.388 0.000	20.160	0.000	7.169 0.000	0.000	20.218	19.928	100.486 XOMR2_OWSG MWD+IFR1+MS

5700.000	6.487	73.810 5702.928	19.742 0.000	20.525	0.000	7.311 0.000	0.000	20.584	20.290	100.666 XOMR2_OWSG MWD+IFR1+MS
5800.000	6.487	73.810 5802.287	20.097 0.000	20.888	0.000	7.455 0.000	0.000	20.949	20.653	100.931 XOMR2_OWSG MWD+IFR1+MS
5900.000	6.487	73.810 5901.647	20.450 0.000	21.253	0.000	7.601 0.000	0.000	21.316	21.015	101.022 XOMR2_OWSG MWD+IFR1+MS
6000.000	6.487	73.810 6001.007	20.806 0.000	21.616	0.000	7.749 0.000	0.000	21.680	21.380	101.371 XOMR2_OWSG MWD+IFR1+MS
6100.000	6.487	73.810 6100.366	21.161 0.000	21.981	0.000	7.899 0.000	0.000	22.046	21.743	101.547 XOMR2_OWSG MWD+IFR1+MS
6200.000	6.487	73.810 6199.726	21.515 0.000	22.345	0.000	8.052 0.000	0.000	22.411	22.105	101.721 XOMR2_OWSG MWD+IFR1+MS
6300.000	6.487	73.810 6299.085	21.869 0.000	22.709	0.000	8.206 0.000	0.000	22.777	22.468	101.897 XOMR2_OWSG MWD+IFR1+MS
6408.900	6.487	73.810 6407.313	22.256 0.000	23.106	0.000	8.377 0.000	0.000	23.176	22.864	102.112 XOMR2_OWSG MWD+IFR1+MS
6500.000	4.666	73.810 6497.953	22.797 0.000	23.436	0.000	8.522 0.000	0.000	23.507	23.193	102.294 XOMR2_OWSG MWD+IFR1+MS
6600.000	2.666	73.810 6597.743	23.370 0.000	23.794	0.000	8.682 0.000	0.000	23.866	23.552	102.446 XOMR2_OWSG MWD+IFR1+MS
6700.000	0.666	73.810 6697.696	23.919 0.000	24.150	0.000	8.840 0.000	0.000	24.222	23.906	102.444 XOMR2_OWSG MWD+IFR1+MS
6733.300	0.000	0.000 6731.000	24.323 0.000	24.037	0.000	8.893 0.000	0.000	24.337	24.023	102.464 XOMR2_OWSG MWD+IFR1+MS
6800.000	0.000	0.000 6797.695	24.554 0.000	24.265	0.000	8.998 0.000	0.000	24.568	24.251	102.193 XOMR2_OWSG MWD+IFR1+MS
6900.000	0.000	0.000 6897.695	24.900 0.000	24.609	0.000	9.158 0.000	0.000	24.913	24.595	101.915 XOMR2_OWSG MWD+IFR1+MS
7000.000	0.000	0.000 6997.695	25.247 0.000	24.952	0.000	9.320 0.000	0.000	25.260	24.939	101.575 XOMR2_OWSG MWD+IFR1+MS
7100.000	0.000	0.000 7097.695	25.593 0.000	25.296	0.000	9.485 0.000	0.000	25.605	25.284	101.314 XOMR2_OWSG MWD+IFR1+MS
7200.000	0.000	0.000 7197.695	25.940 0.000	25.640	0.000	9.653 0.000	0.000	25.952	25.628	100.999 XOMR2_OWSG MWD+IFR1+MS
7300.000	0.000	0.000 7297.695	26.287 0.000	25.985	0.000	9.823 0.000	0.000	26.298	25.973	100.760 XOMR2_OWSG MWD+IFR1+MS
7400.000	0.000	0.000 7397.695	26.635 0.000	26.331	0.000	9.997 0.000	0.000	26.645	26.320	100.524 XOMR2_OWSG MWD+IFR1+MS
7500.000	0.000	0.000 7497.695	26.981 0.000	26.676	0.000	10.169 0.000	0.000	26.992	26.665	100.299 XOMR2_OWSG MWD+IFR1+MS

7600.000	0.000	0.000	7597.695	27.329 0	.000	27.022	0.000	10.349	0.000	0.000	27.339	27.012	100.078	XOMR2_OWSG MWD+IFR1+MS
7700.000	0.000	0.000	7697.695	27.679 0	.000	27.368	0.000	10.531	0.000	0.000	27.688	27.358	99.813	XOMR2_OWSG MWD+IFR1+MS
7800.000	0.000	0.000	7797.695	28.027 0	.000	27.715	0.000	10.714	0.000	0.000	28.036	27.705	99.610	XOMR2_OWSG MWD+IFR1+MS
7900.000	0.000	0.000	7897.695	28.376 0	.000	28.061	0.000	10.904	0.000	0.000	28.385	28.052	99.360	XOMR2_OWSG MWD+IFR1+MS
8000.000	0.000	0.000	7997.695	28.725 0	.000	28.408	0.000	11.091	0.000	0.000	28.733	28.399	99.170	XOMR2_OWSG MWD+IFR1+MS
8100.000	0.000	0.000	8097.695	29.074 0	.000	28.756	0.000	11.283	0.000	0.000	29.082	28.748	98.985	XOMR2_OWSG MWD+IFR1+MS
8200.000	0.000	0.000	8197.695	29.423 0	.000	29.103	0.000	11.480	0.000	0.000	29.431	29.095	98.803	XOMR2_OWSG MWD+IFR1+MS
8300.000	0.000	0.000	8297.695	29.772 0	.000	29.450	0.000	11.679	0.000	0.000	29.780	29.442	98.586	XOMR2_OWSG MWD+IFR1+MS
8400.000	0.000	0.000	8397.695	30.123 0	.000	29.799	0.000	11.879	0.000	0.000	30.130	29.792	98.417	XOMR2_OWSG MWD+IFR1+MS
8500.000	0.000	0.000	8497.695	30.473 0	.000	30.148	0.000	12.083	0.000	0.000	30.480	30.141	98.251	XOMR2_OWSG MWD+IFR1+MS
8600.000	0.000	0.000	8597.695	30.822 0	.000	30.496	0.000	12.292	0.000	0.000	30.829	30.489	98.091	XOMR2_OWSG MWD+IFR1+MS
8652.100	0.000	0.000	8649.800	31.005 0	.000	30.677	0.000	12.402	0.000	0.000	31.011	30.671	97.992	XOMR2_OWSG MWD+IFR1+MS
8700.000	3.831	179.700	8697.660	33.125 0	.000	30.840	-0.000	12.502	0.000	0.000	31.174	30.833	97.897	XOMR2_OWSG MWD+IFR1+MS
8800.000	11.830	179.700	8796.646	36.801 0	.000	31.161	-0.000	12.704	0.000	0.000	31.491	31.155	97.598	XOMR2_OWSG MWD+IFR1+MS
8900.000	19.830	179.700	8892.775	39.468 0	.000	31.471	-0.000	12.900	0.000	0.000	31.786	31.465	97.407	XOMR2_OWSG MWD+IFR1+MS
9000.000	27.830	179.700	8984.174	41.093 0	.000	31.765	-0.000	13.077	0.000	0.000	32.052	31.760	97.584	XOMR2_OWSG MWD+IFR1+MS
9100.000	35.830	179.700	9069.066	41.666 0	.000	32.032	-0.000	13.248	0.000	0.000	32.301	32.026	97.846	XOMR2_OWSG MWD+IFR1+MS
9200.000	43.830	179.700	9145.796	41.124 0	.000	32.280	-0.000	13.409	0.000	0.000	32.503	32.273	99.939	XOMR2_OWSG MWD+IFR1+MS
9300.000	51.830	179.700	9212.873	39.476 0	.000	32.527	-0.000	13.565	0.000	0.000	32.679	32.513	106.708	XOMR2_OWSG MWD+IFR1+MS
9400.000	59.830	179.700	9268.990	36.700 0	.000	32.727	-0.000	13.733	0.000	0.000	32.822	32.691	121.086	XOMR2_OWSG MWD+IFR1+MS

9500.000	67.830	179.700	9313.055	32.798 0.000	32.910 -0.000	13.914 0.000	0.000	32.972	32.815	-39.414	XOMR2_OWSG MWD+IFR1+MS
9600.000	75.830	179.700	9344.211	27.707 0.000	33.077 -0.000	14.121 0.000	0.000	33.131	32.883	-28.314	XOMR2_OWSG MWD+IFR1+MS
9700.000	83.830	179.700	9361.851	21.174 0.000	33.213 -0.000	14.353 0.000	0.000	33.271	32.894	-23.484	XOMR2_OWSG MWD+IFR1+MS
9777.100	90.000	179.700	9365.997	14.550 0.000	33.288 -0.000	14.550 0.000	0.000	33.359	32.896	-23.398	XOMR2_OWSG MWD+IFR1+MS
9777.100	90.000	179.700	9365.997	14.550 0.000	33.288 -0.000	14.550 0.000	0.000	33.359	32.896	-23.398	XOMR2_OWSG MWD+IFR1+MS
9800.000	90.000	179.700	9365.997	14.612 0.000	33.319 -0.000	14.612 0.000	0.000	33.392	32.894	-22.917	XOMR2_OWSG MWD+IFR1+MS
9900.000	90.000	179.700	9365.997	14.903 0.000	33.424 -0.000	14.903 0.000	0.000	33.514	32.891	- 22.716	XOMR2_OWSG MWD+IFR1+MS
10000.000	90.000	179.700	9365.997	15.232 0.000	33.544 -0.000	15.232 0.000	0.000	33.646	32.878	-21.794	XOMR2_OWSG MWD+IFR1+MS
10100.000	90.000	179.700	9365.997	15.592 0.000	33.693 -0.000	15.592 0.000	0.000	33.804	32.868	-20.550	XOMR2_OWSG MWD+IFR1+MS
10200.000	90.000	179.700	9365.997	15.984 0.000	33.856 -0.000	15.984 0.000	0.000	33.976	32.873	-19.694	XOMR2_OWSG MWD+IFR1+MS
10300.000	90.000	179.700	9365.997	16.401 0.000	34.033 -0.000	16.401 0.000	0.000	34.161	32.879	-18.862	XOMR2_OWSG MWD+IFR1+MS
10400.000	90.000	179.700	9365.997	16.846 0.000	34.224 -0.000	16.846 0.000	0.000	34.357	32.872	-17.900	XOMR2_OWSG MWD+IFR1+MS
10500.000	90.000	179.700	9365.997	17.318 0.000	34.429 -0.000	17.318 0.000	0.000	34.568	32.880	- 17.179	XOMR2_OWSG MWD+IFR1+MS
10600.000	90.000	179.700	9365.997	17.807 0.000	34.661 -0.000	17.807 0.000	0.000	34.803	32.875	-16.254	XOMR2_OWSG MWD+IFR1+MS
10700.000	90.000	179.700	9365.997	18.319 0.000	34.891 -0.000	18.319 0.000	0.000	35.038	32.884	-15.643	XOMR2_OWSG MWD+IFR1+MS
10800.000	90.000	179.700	9365.997	18.852 0.000	35.149 -0.000	18.852 0.000	0.000	35.298	32.895	-14.975	XOMR2_OWSG MWD+IFR1+MS
10900.000	90.000	179.700	9365.997	19.398 0.000	35.418 -0.000	19.398 0.000	0.000	35.570	32.905		XOMR2_OWSG MWD+IFR1+MS
11000.000	90.000	179.700	9365.997	19.962 0.000	35.700 -0.000	19.962 0.000	0.000	35.854	32.917	-13.803	XOMR2_OWSG MWD+IFR1+MS
11100.000	90.000	179.700	9365.997	20.543 0.000	35.993 -0.000	20.543 0.000	0.000	36.149	32.928	-13.283	XOMR2_OWSG MWD+IFR1+MS
11200.000	90.000	179.700	9365.997	21.133 0.000	36.312 -0.000	21.133 0.000	0.000	36.467	32.926	-12.699	XOMR2_OWSG MWD+IFR1+MS

11300.000	90.000	179.700	9365.997	21.737 0.00	00 36	.641 -0.00	00 21.7	737 0.00	0.000	36.797	32.939	-12.218	XOMR2_OWSG MWD+IFR1+MS
11400.000	90.000	179.700	9365.997	22.352 0.00	00 36	.968 -0.0	00 22.3	352 0.00	0.000	37.126	32.965	-11.855	XOMR2_OWSG MWD+IFR1+MS
11500.000	90.000	179.700	9365.997	22.978 0.00	00 37	.318 -0.0	00 22.9	78 0.00	0.000	37.476	32.978	-11.440	XOMR2_OWSG MWD+IFR1+MS
11600.000	90.000	179.700	9365.997	23.614 0.00	00 37	.692 - 0.0	00 23.6	314 0.00	0.000	37.849	32.991	-11.023	XOMR2_OWSG MWD+IFR1+MS
11700.000	90.000	179.700	9365.997	24.257 0.00	00 38	.062 -0.00	00 24.2	257 0.00	0.000	38.219	33.004	-10.667	XOMR2_OWSG MWD+IFR1+MS
11800.000	90.000	179.700	9365.997	24.908 0.00	00 38	.454 -0.00	00 24.9	0.00	0.000	38.611	33.018	-10.311	XOMR2_OWSG MWD+IFR1+MS
11900.000	90.000	179.700	9365.997	25.568 0.00	00 38	.843 - 0.00	00 25.5	568 0.00	0.000	39.000	33.031	-10.005	XOMR2_OWSG MWD+IFR1+MS
12000.000	90.000	179.700	9365.997	26.234 0.00	00 39	.253 -0.00	00 26.2	234 0.00	0.000	39.410	33.059	-9.717	XOMR2_OWSG MWD+IFR1+MS
12100.000	90.000	179.700	9365.997	26.907 0.00	00 39	.671 -0.00	00 26.9	0.00	0.000	39.827	33.072	-9.428	XOMR2_OWSG MWD+IFR1+MS
12200.000	90.000	179.700	9365.997	27.586 0.00	00 40	.098 -0.0	00 27.5	586 0.00	0.000	40.253	33.086	-9.157	XOMR2_OWSG MWD+IFR1+MS
12300.000	90.000	179.700	9365.997	28.270 0.00	00 40	.545 -0.00	00 28.2	270 0.00	0.000	40.699	33.115	-8.905	XOMR2_OWSG MWD+IFR1+MS
12400.000	90.000	179.700	9365.997	28.959 0.00	00 40	.987 - 0.0	00 28.9	959 0.00	0.000	41.140	33.128	-8.666	XOMR2_OWSG MWD+IFR1+MS
12500.000	90.000	179.700	9365.997	29.653 0.00	00 41	.448 -0.00	00 29.6	353 0.00	0.000	41.601	33.157	-8.442	XOMR2_OWSG MWD+IFR1+MS
12600.000	90.000	179.700	9365.997	30.351 0.00	00 41	.916 -0.0	00 30.3	351 0.00	0.000	42.068	33.171	-8.218	XOMR2_OWSG MWD+IFR1+MS
12700.000	90.000	179.700	9365.997	31.053 0.00	00 42	.391 -0.0	00 31.0	0.00	0.000	42.541	33.200	-8.019	XOMR2_OWSG MWD+IFR1+MS
12800.000	90.000	179.700	9365.997	31.749 0.00	00 42	.872 -0.00	00 31.7	'49 0.00	0.000	43.021	33.214	-7.814	XOMR2_OWSG MWD+IFR1+MS
12900.000	90.000	179.700	9365.997	32.465 0.00	00 43	.371 -0.00	00 32.4	165 0.00	0.000	43.519	33.243	-7.629	XOMR2_OWSG MWD+IFR1+MS
13000.000	90.000	179.700	9365.997	33.181 0.00	00 43	.865 -0.0	00 33.′	181 0.00	0.000	44.011	33.272	-7.463	XOMR2_OWSG MWD+IFR1+MS
13100.000	90.000	179.700	9365.997	33.897 0.00	00 44	.375 -0.0	00 33.8	397 0.00	0.000	44.520	33.301	-7.290	XOMR2_OWSG MWD+IFR1+MS
13200.000	90.000	179.700	9365.997	34.612 0.00	00 44	.891 -0.0	00 34.6	812 0.00	0.000	45.035	33.315	-7.124	XOMR2_OWSG MWD+IFR1+MS

13300.000	90.000	179.700	9365.997	35.341 0.0	000	45.411 -0.0	000 35	5.341	0.000	0.000	45.554	33.344	-6.973	XOMR2_OWSG MWD+IFR1+MS
13400.000	90.000	179.700	9365.997	36.056 0.0	000	45.937 -0.0	000 36	5.056	0.000	0.000	46.079	33.373	-6.830	XOMR2_OWSG MWD+IFR1+MS
13500.000	90.000	179.700	9365.997	36.783 0.0	000	46.479 -0.0	000 36	5.783	0.000	0.000	46.619	33.402	-6.686	XOMR2_OWSG MWD+IFR1+MS
13600.000	90.000	179.700	9365.997	37.523 0.0	000	47.014 -0.0	000 37	7.523	0.000	0.000	47.153	33.431	-6.549	XOMR2_OWSG MWD+IFR1+MS
13700.000	90.000	179.700	9365.997	38.249 0.0	000	47.564 -0.0	000 38	3.249	0.000	0.000	47.702	33.460	-6.418	XOMR2_OWSG MWD+IFR1+MS
13800.000	90.000	179.700	9365.997	38.987 0.0	000	48.118 -0.0	000 38	3.987	0.000	0.000	48.255	33.488	-6.297	XOMR2_OWSG MWD+IFR1+MS
13900.000	90.000	179.700	9365.997	39.724 0.0	000	48.676 -0.0	000 39).724	0.000	0.000	48.812	33.517	-6.177	XOMR2_OWSG MWD+IFR1+MS
14000.000	90.000	179.700	9365.997	40.460 0.0	000	49.238 -0.0	000 40	.460	0.000	0.000	49.372	33.546	-6.062	XOMR2_OWSG MWD+IFR1+MS
14100.000	90.000	179.700	9365.997	41.195 0.0	000	49.814 -0.0	000 41	.195	0.000	0.000	49.947	33.576	-5.947	XOMR2_OWSG MWD+IFR1+MS
14200.000	90.000	179.700	9365.997	41.940 0.0	000	50.383 -0.0	000 41	.940	0.000	0.000	50.515	33.619	- 5.845	XOMR2_OWSG MWD+IFR1+MS
14300.000	90.000	179.700	9365.997	42.685 0.0	000	50.966 -0.0	000 42	2.685	0.000	0.000	51.096	33.648	-5.742	XOMR2_OWSG MWD+IFR1+MS
14400.000	90.000	179.700	9365.997	43.428 0.0	000	51.551 -0.0	000 43	3.428	0.000	0.000	51.680	33.677	-5.640	XOMR2_OWSG MWD+IFR1+MS
14500.000	90.000	179.700	9365.997	44.170 0.0	000	52.140 -0.0	000 44	.170	0.000	0.000	52.268	33.721	-5.549	XOMR2_OWSG MWD+IFR1+MS
14600.000	90.000	179.700	9365.997	44.911 0.0	000	52.741 -0.0	000 44	1.911	0.000	0.000	52.867	33.750	-5.451	XOMR2_OWSG MWD+IFR1+MS
14700.000	90.000	179.700	9365.997	45.662 0.0	000	53.335 -0.0	000 45	5.662	0.000	0.000	53.460	33.779	-5.364	XOMR2_OWSG MWD+IFR1+MS
14800.000	90.000	179.700	9365.997	46.411 0.0	000	53.941 -0.0	000 46	6.411	0.000	0.000	54.065	33.822	-5.276	XOMR2_OWSG MWD+IFR1+MS
14900.000	90.000	179.700	9365.997	47.159 0.0	000	54.550 -0.0	000 47	'.159	0.000	0.000	54.673	33.851	- 5.192	XOMR2_OWSG MWD+IFR1+MS
15000.000	90.000	179.700	9365.997	47.917 0.0	000	55.161 -0.0	000 47	'.917	0.000	0.000	55.282	33.895	- 5.113	XOMR2_OWSG MWD+IFR1+MS
15100.000	90.000	179.700	9365.997	48.672 0.0	000	55.774 -0.0	000 48	3.672	0.000	0.000	55.895	33.938	-5.037	XOMR2_OWSG MWD+IFR1+MS
15200.000	90.000	179.700	9365.997	49.427 0.0	000	56.390 -0.0	000 49	.427	0.000	0.000	56.509	33.967	-4.961	XOMR2_OWSG MWD+IFR1+MS

15300.000	90.000 1	79.700	9365.997	50.180 0.000	57.016 - 0.	.000 50).180 (0.000	0.000	57.134	34.010	-4.887	XOMR2_OWSG MWD+IFR1+MS
15400.000	90.000 1	79.700	9365.997	50.931 0.000	57.635 - 0.	.000 50).931 (0.000	0.000	57.752	34.054	- 4.818	XOMR2_OWSG MWD+IFR1+MS
15500.000	90.000 1	79.700	9365.997	51.691 0.000	58.266 -0.	.000 51	.691 (0.000	0.000	58.381	34.082	- 4.747	XOMR2_OWSG MWD+IFR1+MS
15600.000	90.000 1	79.700	9365.997	52.450 0.000	58.897 -0.	.000 52	2.450 (0.000	0.000	59.012	34.126	- 4.680	XOMR2_OWSG MWD+IFR1+MS
15700.000	90.000 1	79.700	9365.997	53.207 0.000	59.531 -0.	.000 53	3.207 (0.000	0.000	59.645	34.169	-4.616	XOMR2_OWSG MWD+IFR1+MS
15800.000	90.000 1	79.700	9365.997	53.963 0.000	60.175 -0.	.000 53	3.963 (0.000	0.000	60.287	34.212	-4.551	XOMR2_OWSG MWD+IFR1+MS
15900.000	90.000 1	79.700	9365.997	54.727 0.000	60.811 -0.	.000 54	1.727 (0.000	0.000	60.923	34.256	-4.490	XOMR2_OWSG MWD+IFR1+MS
16000.000	90.000 1	79.700	9365.997	55.480 0.000	61.458 - 0.	.000 55	5.480 (0.000	0.000	61.568	34.299	-4.432	XOMR2_OWSG MWD+IFR1+MS
16100.000	90.000 1	79.700	9365.997	56.241 0.000	62.105 - 0.	.000 56	6.241 (0.000	0.000	62.215	34.342	- 4.373	XOMR2_OWSG MWD+IFR1+MS
16200.000	90.000 1	79.700	9365.997	57.009 0.000	62.754 - 0.	.000 57	.009 (0.000	0.000	62.863	34.385	- 4.318	XOMR2_OWSG MWD+IFR1+MS
16300.000	90.000 1	79.700	9365.997	57.767 0.000	63.405 - 0.	.000 57	7.767 (0.000	0.000	63.512	34.428	- 4.262	XOMR2_OWSG MWD+IFR1+MS
16400.000	90.000 1	79.700	9365.997	58.532 0.000	64.056 -0.	.000 58	3.532 (0.000	0.000	64.162	34.471	- 4.210	XOMR2_OWSG MWD+IFR1+MS
16500.000	90.000 1	79.700	9365.997	59.296 0.000	64.716 - 0.	.000 59	.296 (0.000	0.000	64.821	34.514	-4.156	XOMR2_OWSG MWD+IFR1+MS
16600.000	90.000 1	79.700	9365.997	60.058 0.000	65.378 -0.	.000 60	0.058	0.000	0.000	65.482	34.571	-4.106	XOMR2_OWSG MWD+IFR1+MS
16700.000	90.000 1	79.700	9365.997	60.819 0.000	66.040 -0.	.000 60).819(0.000	0.000	66.143	34.614	- 4.057	XOMR2_OWSG MWD+IFR1+MS
16800.000	90.000 1	79.700	9365.997	61.587 0.000	66.703 -0.	.000 61	.587 (0.000	0.000	66.805	34.656	-4.009	XOMR2_OWSG MWD+IFR1+MS
16900.000	90.000 1	79.700	9365.997	62.354 0.000	67.367 -0.	.000 62	2.354 (0.000	0.000	67.468	34.713	-3.962	XOMR2_OWSG MWD+IFR1+MS
17000.000	90.000 1	79.700	9365.997	63.119 0.000	68.032 -0.	.000 63	3.119(0.000	0.000	68.132	34.756	-3.916	XOMR2_OWSG MWD+IFR1+MS
17100.000	90.000 1	79.700	9365.997	63.883 0.000	68.705 -0.	.000 63	3.883 (0.000	0.000	68.805	34.813	-3.872	XOMR2_OWSG MWD+IFR1+MS
17200.000	90.000 1	79.700	9365.997	64.653 0.000	69.379 -0.	.000 64	1.653 (0.000	0.000	69.477	34.855	-3.828	XOMR2_OWSG MWD+IFR1+MS


17300.000	90.000	179.700	9365.997	65.422 0.0	000	70.046 -0.	.000 6	65.422	0.000	0.000	70.144	34.912	-3.787	XOMR2_OWSG MWD+IFR1+MS
17400.000	90.000	179.700	9365.997	66.189 0.0	000	70.728 -0.	.000 6	66.189	0.000	0.000	70.825	34.954	- 3.745	XOMR2_OWSG MWD+IFR1+MS
17500.000	90.000	179.700	9365.997	66.955 0.0	000	71.404 -0.	.000 6	66.955	0.000	0.000	71.500	35.011	-3.705	XOMR2_OWSG MWD+IFR1+MS
17600.000	90.000	179.700	9365.997	67.720 0.0	000	72.080 -0.	.000 6	67.720	0.000	0.000	72.175	35.053	-3.665	XOMR2_OWSG MWD+IFR1+MS
17700.000	90.000	179.700	9365.997	68.491 0.0	000	72.764 -0.	.000 6	68.491	0.000	0.000	72.858	35.110	-3.625	XOMR2_OWSG MWD+IFR1+MS
17800.000	90.000	179.700	9365.997	69.260 0.0	000	73.448 -0.	.000 6	69.260	0.000	0.000	73.541	35.166	-3.589	XOMR2_OWSG MWD+IFR1+MS
17900.000	90.000	179.700	9365.997	70.029 0.0	000	74.133 -0.	.000 7	70.029	0.000	0.000	74.225	35.222	-3.551	XOMR2_OWSG MWD+IFR1+MS
18000.000	90.000	179.700	9365.997	70.803 0.0	000	74.818 -0.	.000 7	70.803	0.000	0.000	74.909	35.279	-3.516	XOMR2_OWSG MWD+IFR1+MS
18100.000	90.000	179.700	9365.997	71.568 0.0	000	75.503 -0.	.000 7	71.568	0.000	0.000	75.594	35.321	-3.479	XOMR2_OWSG MWD+IFR1+MS
18200.000	90.000	179.700	9365.997	72.339 0.0	000	76.189 -0.	.000 7	72.339	0.000	0.000	76.279	35.377	- 3.446	XOMR2_OWSG MWD+IFR1+MS
18300.000	90.000	179.700	9365.997	73.110 0.0	000	76.882 -0.	.000	73.110	0.000	0.000	76.971	35.432	-3.412	XOMR2_OWSG MWD+IFR1+MS
18400.000	90.000	179.700	9365.997	73.885 0.0	000	77.575 -0.	.000 7	73.885	0.000	0.000	77.663	35.488	-3.378	XOMR2_OWSG MWD+IFR1+MS
18500.000	90.000	179.700	9365.997	74.653 0.0	000	78.268 -0.	.000 7	74.653	0.000	0.000	78.356	35.544	-3.346	XOMR2_OWSG MWD+IFR1+MS
18600.000	90.000	179.700	9365.997	75.425 0.0	000	78.961 -0.	.000 7	75.425	0.000	0.000	79.048	35.614	-3.315	XOMR2_OWSG MWD+IFR1+MS
18700.000	90.000	179.700	9365.997	76.197 0.0	000	79.655 -0.	.000 7	76.197	0.000	0.000	79.741	35.669	-3.284	XOMR2_OWSG MWD+IFR1+MS
18800.000	90.000	179.700	9365.997	76.968 0.0	000	80.355 -0.	.000 7	76.968	0.000	0.000	80.441	35.725	-3.253	XOMR2_OWSG MWD+IFR1+MS
18900.000	90.000	179.700	9365.997	77.743 0.0	000	81.049 -0.	.000 7	77.743	0.000	0.000	81.134	35.780	-3.224	XOMR2_OWSG MWD+IFR1+MS
19000.000	90.000	179.700	9365.997	78.518 0.0	000	81.750 -0.	.000 7	78.518	0.000	0.000	81.834	35.836	-3.194	XOMR2_OWSG MWD+IFR1+MS
19100.000	90.000	179.700	9365.997	79.291 0.0	000	82.450 -0.	.000 7	79.291	0.000	0.000	82.534	35.905	-3.166	XOMR2_OWSG MWD+IFR1+MS
19200.000	90.000	179.700	9365.997	80.062 0.0	000	83.151 -0.	.000	30.062	0.000	0.000	83.234	35.960	-3.137	XOMR2_OWSG MWD+IFR1+MS


19300.000	90.000	179.700	9365.997	80.833 0.000	83.858 -0.00	00 80.833	0.000	0.000	83.940	36.015	-3.110	XOMR2_OWSG MWD+IFR1+MS
19400.000	90.000	179.700	9365.997	81.609 0.000	84.558 -0.00	00 81.609	0.000	0.000	84.640	36.084	-3.083	XOMR2_OWSG MWD+IFR1+MS
19500.000	90.000	179.700	9365.997	82.383 0.000	85.265 -0.00	00 82.383	0.000	0.000	85.346	36.139	-3.056	XOMR2_OWSG MWD+IFR1+MS
19600.000	90.000	179.700	9365.997	83.156 0.000	85.972 -0.00	00 83.156	0.000	0.000	86.052	36.207	-3.030	XOMR2_OWSG MWD+IFR1+MS
19700.000	90.000	179.700	9365.997	83.929 0.000	86.679 -0.00	00 83.929	0.000	0.000	86.759	36.262	-3.004	XOMR2_OWSG MWD+IFR1+MS
19800.000	90.000	179.700	9365.997	84.705 0.000	87.386 -0.00	00 84.705	0.000	0.000	87.465	36.330	-2.980	XOMR2_OWSG MWD+IFR1+MS
19900.000	90.000	179.700	9365.997	85.481 0.000	88.093 -0.00	00 85.481	0.000	0.000	88.171	36.399	-2.955	XOMR2_OWSG MWD+IFR1+MS
20000.000	90.000	179.700	9365.997	86.255 0.000	88.805 -0.00	00 86.255	0.000	0.000	88.883	36.453	- 2.930	XOMR2_OWSG MWD+IFR1+MS
20100.000	90.000	179.700	9365.997	87.029 0.000	89.517 -0.00	00 87.029	0.000	0.000	89.595	36.521	-2.907	XOMR2_OWSG MWD+IFR1+MS
20200.000	90.000	179.700	9365.997	87.807 0.000	90.230 -0.00	0 87.807	0.000	0.000	90.306	36.589	-2.883	XOMR2_OWSG MWD+IFR1+MS
20300.000	90.000	179.700	9365.997	88.578 0.000	90.942 -0.00	00 88.578	0.000	0.000	91.018	36.657	-2.860	XOMR2_OWSG MWD+IFR1+MS
20400.000	90.000	179.700	9365.997	89.353 0.000	91.654 -0.00	00 89.353	0.000	0.000	91.730	36.711	-2.838	XOMR2_OWSG MWD+IFR1+MS
20500.000	90.000	179.700	9365.997	90.133 0.000	92.366 -0.00	00 90.133	0.000	0.000	92.441	36.778	-2.816	XOMR2_OWSG MWD+IFR1+MS
20600.000	90.000	179.700	9365.997	90.907 0.000	93.083 -0.00	00 90.907	0.000	0.000	93.158	36.846	-2.794	XOMR2_OWSG MWD+IFR1+MS
20700.000	90.000	179.700	9365.997	91.684 0.000	93.801 -0.00	00 91.684	0.000	0.000	93.875	36.913	- 2.772	XOMR2_OWSG MWD+IFR1+MS
20800.000	90.000	179.700	9365.997	92.461 0.000	94.512 -0.00	00 92.461	0.000	0.000	94.586	36.980	-2.751	XOMR2_OWSG MWD+IFR1+MS
20900.000	90.000	179.700	9365.997	93.236 0.000	95.235 -0.00	00 93.236	0.000	0.000	95.307	37.047	-2.730	XOMR2_OWSG MWD+IFR1+MS
21000.000	90.000	179.700	9365.997	94.011 0.000	95.951 -0.00	00 94.011	0.000	0.000	96.024	37.128	-2.711	XOMR2_OWSG MWD+IFR1+MS
21100.000	90.000	179.700	9365.997	94.789 0.000	96.668 -0.00	00 94.789	0.000	0.000	96.740	37.194	- 2.691	XOMR2_OWSG MWD+IFR1+MS
21200.000	90.000	179.700	9365.997	95.567 0.000	97.390 -0.00	00 95.567	0.000	0.000	97.461	37.261	- 2.671	XOMR2_OWSG MWD+IFR1+MS

21300.000	90.000	179.700	9365.997	96.343	0.000	98.111	-0.000	96.343	0.000	0.000	98.182	37.328	-2.652 XOMR2_OWSG MWD+IFR1+MS
21400.000	90.000	179.700	9365.997	97.118	0.000	98.827	-0.000	97.118	0.000	0.000	98.897	37.394	-2.633 XOMR2_OWSG MWD+IFR1+MS
21500.000	90.000	179.700	9365.997	97.893	0.000	99.553	-0.000	97.893	0.000	0.000	99.623	37.474	-2.614 XOMR2_OWSG MWD+IFR1+MS
21600.000	90.000	179.700	9365.997	98.671	0.000	100.269	-0.000	98.671	0.000	0.000	100.338	37.540	-2.596 XOMR2_OWSG MWD+IFR1+MS
21700.000	90.000	179.700	9365.997	99.448	0.000	100.965	-0.000	99.448	0.000	0.000	101.034	37.606	-2.579 XOMR2_OWSG MWD+IFR1+MS
21800.000	90.000	179.700	9365.997	100.200	0.000	101.705	-0.000	100.200	0.000	0.000	101.773	37.685	-2.561 XOMR2_OWSG MWD+IFR1+MS
21900.000	90.000	179.700	9365.997	100.995	0.000	102.440	-0.000	100.995	0.000	0.000	102.508	37.751	-2.542 XOMR2_OWSG MWD+IFR1+MS
22000.000	90.000	179.700	9365.997	101.784	0.000	103.170	-0.000	101.784	0.000	0.000	103.237	37.830	-2.524 XOMR2_OWSG MWD+IFR1+MS
22100.000	90.000	179.700	9365.997	102.518	0.000	103.894	-0.000	102.518	0.000	0.000	103.961	37.909	-2.508 XOMR2_OWSG MWD+IFR1+MS
22146.000	90.000	179.700	9366.000	102.908	0.000	104.231	-0.000	102.908	0.000	0.000	104.297	37.935	-2.500 XOMR2_OWSG MWD+IFR1+MS
22200.000	90.000	179.700	9366.000	103.296	0.000	104.614	-0.000	103.296	0.000	0.000	104.680	37.974	-2.491 XOMR2_OWSG MWD+IFR1+MS
22236.000	90.000	179.700	9366.000	103.586	0.000	104.853	-0.000	103.586	0.000	0.000	104.919	38.000	-2.486 XOMR2_OWSG MWD+IFR1+MS


Plan Targets	Poker Lake Unit 18-30 BD 202H			
	Measured Depth	Grid Northing	Grid Easting	TVD MSL Target Shape
Target Name	(ft)	(ft)	(ft)	(ft)
FTP 3	9474.97	413828.20	628779.00	6124.00 CIRCLE
LTP 13	22177.00	400742.40	628846.20	6124.00 CIRCLE
BHL 3	22267.00	400652.40	628846.80	6124.00 CIRCLE

Poker Lake Unit 18-30 BD 202H





Formation	TVDSS (feet)	TVD (feet)
Rustler	2,499'	712'
Salado	2,068"	1,143"
Base of Salt	-104"	3,315
Delaware	-323"	3,534"
Cherry Canyon	-1,231'	4,442"
Brushy Canyon	-2,488'	5,699"
Basal Brushy Canyon	-3,871	7,082"
Bone Spring Lm.	-4,089'	7,300°
Avalon Shale	-4,256'	7,467
Lower Avalon Shale	-4,673	7,884*
1st Bone Spring Lime	-4,849'	8,060"
1st Bone Spring Sand	-5,059"	8,270°
2nd Bone Spring Shale	-5,297	8,508"
2nd Bone Spring Lime	-5,390"	8,601"
2nd Bone Spring Sand	-5,859"	9,070"
2nd Bone Spring T/B Carb	-6,019"	9,230"
2nd Bone Spring C Sand (Landing)	-6,124	9,335"
3rd Bone Spring Lime	-6,174"	9,385°



		ALL DIMENSIO	NS APPROX I MATE
CACTUS WELLHEAD LLC		XTO ENERGY IN DELAWARE BAS	_
20" x 9-5/8" x 7-5/8" x 5-1/2" MBU-T-CFL-R-DBLO Wellhead	DRAWN	VJK	31MAR22
	APPRV		
With 11" 10M x 7-1/16" 15M CTH-DBLHPS Tubing Head And 9-5/8", 7-5/8" & 5-1/2" Pin Bottom Mandrel Casing Hangers	DRAWING N	o. HBE000	0479

INFORMATION CONTAINED HEREIN IS THE PROPERTY OF CACTUS WELLHEAD, LLC. REPRODUCTION, DISCLOSURE, OR USE THEREOF IS PERMISSIBLE ONLY AS PROVIDED BY CONTRACT OR AS EXPRESSLY AUTHORIZED BY CACTUS WELLHEAD, LLC.

Cement Variance Request

Intermediate Casing:


+ 3% Salt + 1% PreMag-M + 6% Bentonite Gel (2.30 yld, 12.91 ppg) will be executed as a contingency. If cement is still unable to circulate to surface, another Echo-meter run will be performed for cement top XTO requests to pump a two stage cement job on the 7-5/8" intermediate casing string with the first stage being pumped conventionally with the calculated top of cement at the Brush Canyon (5699') and the second stage performed as a bradenhead squeeze with planned cement from the Brushy Canyon to surface. If cement is not visually confirmed to circulate to surface, the final cement top after the second stage job will be verified by Echo-meter. If necessary, a top out consisting of 1,500 sack of Class C cement verification.

XTO will report to the BLM the volume of fluid (limited to 5 bbls) used to flush intermediate casing valves following backside cementing procedures.

first intermediate casing. If cement reaches the desired height, the BLM will be notified and the second XTO requests to pump an Optional Lead if well conditions dictate in an attempt to bring cement inside the stage bradenhead squeeze and subsequent TOC verification will be negated. XTO requests the option to conduct the bradenhead squeeze and TOC verification offline as per standard approval from BLM when unplanned remediation is needed and batch drilling is approved. In the event the bradenhead is conducted, we will ensure the first stage cement job is cemented properly and the well is static with floats holding and no pressure on the csg annulus as with all other casing strings where batch drilling operations occur before moving off the rig. The TA cap will also be installed per Cactus procedure and pressure inside the casing will be monitored via the valve on the TA cap as per standard batch drilling

Production Casing:

strings where batch drilling is approved and if unplanned remediation is needed. XTO will ensure well is static with no pressure on the csg annulus, as with all other casing strings where batch drilling operations XTO requests the option to offline cement and remediate (if needed) surface and intermediate casing occur before moving off the rig. The TA cap will also be installed when applicable per Cactus procedure and pressure inside the casing will be monitored via the valve on the TA cap as per standard batch drilling ops. Offline cement operations will then be conducted after the rig is moved off the current well to the next well in the batch sequence.



State of New Mexico Energy, Minerals and Natural Resources Department

Submit Electronically Via E-permitting

> Oil Conservation Division 1220 South St. Francis Dr. Santa Fe, NM 87505

NATURAL GAS MANAGEMENT PLAN

This Natural Gas Management Plan must be submitted with each Application for Permit to Drill (APD) for a new or recompleted well.

Section 1 – Plan Description Effective May 25, 2021

RID: 373075 Date:		TI 10 15 27 9 D/67/h) NMAC II Orher
XTO PERMIAN OPERATING, LLC. OG		Original Amendment due to 1915 279 D(6/s) NMAC 1915 279 D(6/k) NMAC Orl
I. Operator:	_07_/_29_/_2024_	II Tyne 🛭 Origina

III. Well(s): Provide the following information for each new or recompleted well or set of wells proposed to be drilled or proposed to be recompleted from a single well pad or connected to a central delivery point.

If Other, please describe:

3 yr Anticipated decline Water BBL/D	400	700	400	006	400	006	400	006	1,100
Anticipated Produced Water BBL/D	1,250	3,750	1,250	4,250	1,500	4,250	1,500	4,250	4,750
3 yr Anticipated decline Gas MCF/D	006	006	006	1,200	1,000	1,200	1,000	1,200	1,400
Anticipa ted Gas MCF/D	1,500	2,750	1,500	3,000	1,750	3,000	1,750	3,000	3,500
3 yr Anticipated decline Oil BBL/D	125	125	125	175	150	175	150	175	200
Anticip ated Oil BBL/D	200	1,100	500	1,200	009	1,200	009	1,200	1,300
Footages	1434 FSL; 1904 FWL	1433 FSL; 1934 FWL	1432 FSL; 1964 FWL	1431 FSL; 1994 FWL	1430 FSL; 2024 FWL	1813 FSL; 1604 FEL	1813 FSL; 1574 FEL	1813 FSL; 1544 FEL	1813 FSL; 1514 FEL
ULSTR	20 T25S R30E	20 T25S R30E	20 T25S R30E	20 T25S R30E	20 T25S R30E	20 T25S R30E	20 T25S R30E	20 T25S R30E	20 T25S R30E
API	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD
Well Name	Poker Lake Unit 20-17 BD 201	Poker Lake Unit 20-17 BD 202	Poker Lake Unit 20-17 BD 203	Poker Lake Unit 20-17 BD 204	Poker Lake Unit 20-8 BD 205	Poker Lake Unit 20-8 BD 206	Poker Lake Unit 20-8 BD 207	Poker Lake Unit 20-8 BD 208	Poker Lake Unit 20-8 BD 209

Page 1 of 6

006	006	400	006	400	700	400	700	400	700	009
4,750	4,250	1,500	4,250	1,500	3,750	1,250	3,750	1,250	3,750	4,000
2,700	1,200	1,000	1,200	1,000	006	006	006	006	006	1,700
7,250	3,000	1,750	3,000	1,750	2,750	1,500	2,750	1,500	2,750	5,500
75	175	150	175	150	125	125	125	125	125	50
009	1,200	009	1,200	009	1,100	500	1,100	500	1,100	500
1813 FSL; 1484 FEL	265 FNL; 2395 FEL	265 FNL; 2365 FEL	265 FNL; 2335 FEL	265 FNL; 2305 FEL	265 FNL; 2275 FEL	265 FNL; 1935 FEL	265 FNL; 1905 FEL	265 FNL; 1875 FEL	265 FNL; 1845 FEL	265 FNL; 1815 FEL
20 T25S R30E	18 T25S R30E									
TBD	ТВD	TBD	ТВD							
Poker Lake Unit 20-8 BD 210	Poker Lake Unit 18-30 BD 200H	Poker Lake Unit 18-30 BD 201H	Poker Lake Unit 18-30 BD 202H	Poker Lake Unit 18-30 BD 203H	Poker Lake Unit 18-19 BD 204H	Poker Lake Unit 18-19 BD 205H	Poker Lake Unit 18-19 BD 206H	Poker Lake Unit 18-19 BD 207H	Poker Lake Unit 18-19 BD 208H	Poker Lake Unit 18-19 BD 209H

PLU Brushy Draw 18 (PLU 18-30/18-19) and PLU Brushy Draw 20 (PLU 20-17/20-8) IV. Central Delivery Point Name:_ [See 19.15.27.9(D)(1) NMAC]

V. Anticipated Schedule: Provide the following information for each new or recompleted well or set of wells proposed to be drilled or proposed to be recompleted from a single well pad or connected to a central delivery point.

	API	Spud Date	TD Reached	Completion	Initial Flow	First Production
		,	Date	Commencement Date	Back Date	Date
Poker Lake Unit 20-17 BD 201	TRD	Anonet 2025	TRD	TBD	TRD	TRD
Poker Lake Unit 20-17	201	CZOZ lengur	AG.	777	O. C.	aar
	TBD	August 2025	TBD	TBD	TBD	TBD
Poker Lake Unit 20-17						
BD 203	TBD	August 2025	TBD	TBD	TBD	TBD
Poker Lake Unit 20-17						
† 00 00 00 00 00 00 00 00 00 00 00 00 00	TBD	August 2025	TBD	TBD	TBD	TBD
Poker Lake Unit 20-8						
202	TBD	August 2025	TBD	TBD	TBD	TBD
Poker Lake Unit 20-8 BD 206						
	TBD	August 2025	TBD	TBD	TBD	TBD
Poker Lake Unit 20-8 BD 207						
	TBD	August 2025	TBD	TBD	TBD	TBD

Page 2 of 6

Poker Lake Unit 20-8 BD 208	TBD	August 2025	TBD	TBD	TBD	TBD
Poker Lake Unit 20-8 BD 209	TBD	August 2025	TBD	ΠBD	TBD	TBD
Poker Lake Unit 20-8 BD 210	TBD	August 2025	TBD	CEL	TBD	TBD
Poker Lake Unit 18-30 BD 200H	TBD	October 2025	TBD	TBD	TBD	TBD
Poker Lake Unit 18-30 BD 201H	TBD	October 2025	TBD	CEL	ΠBD	TBD
Poker Lake Unit 18-30 BD 202H	TBD	October 2025	TBD	ΠBD	ΠBD	TBD
Poker Lake Unit 18-30 BD 203H	TBD	October 2025	TBD	CEL	ΠBD	TBD
Poker Lake Unit 18-19 BD 204H	TBD	October 2025	TBD	CEL	ΠBD	TBD
Poker Lake Unit 18-19 BD 205H	TBD	October 2025	TBD	ΠBD	ПВП	TBD
Poker Lake Unit 18-19 BD 206H	TBD	October 2025	TBD	TBD	TBD	TBD
Poker Lake Unit 18-19 BD 207H	TBD	October 2025	TBD	ΠBD	ΠBD	TBD
Poker Lake Unit 18-19 BD 208H	TBD	October 2025	TBD	TBD	ПВП	TBD
Poker Lake Unit 18-19 BD 209H	TBD	October 2025	TBD	ТВД	TBD	TBD

VI. Separation Equipment: 🗵 Attach a complete description of how Operator will size separation equipment to optimize gas capture.

VII. Operational Practices: A Attach a complete description of the actions Operator will take to comply with the requirements of Subsection A through F of 19.15.27.8 NMAC.

VIII. Best Management Practices:

Attach a complete description of Operator's best management practices to minimize venting during active and planned maintenance.

Section 2 – Enhanced Plan EFFECTIVE APRIL 1,2022

Beginning April 1, 2022, an operator that is not in compliance with its statewide natural gas capture requirement for the applicable reporting area must complete this section. ■ Operator certifies that it is not required to complete this section because Operator is in compliance with its statewide natural gas.

IX. Anticipated Natural Gas Production:

capture requirement for the applicable reporting area.

Page 3 of 6

Anticipated Volume of Natural Gas for the First Year MCF	
Anticipated Average Natural Gas Rate MCF/D	
API	
Well	

X. Natural Gas Gathering System (NGGS):

	 _
Available Maximum Daily Capacity of System Segment Tie-in	
Anticipated Gathering Start Date	
ULSTR of Tie-in	
System	
Operator	

XI. Map. \square Attach an accurate and legible map depicting the location of the well(s), the anticipated pipeline route(s) connecting the production operations to the existing or planned interconnect of the natural gas gathering system (s), and the maximum daily capacity of the segment or portion of the natural gas gathering system(s) to which the well(s) will be connected

XII. Line Capacity. The natural gas gathering system \square will \square will not have capacity to gather 100% of the anticipated natural gas production volume from the well prior to the date of first production. XIII. Line Pressure. Operator 🗆 does 🗆 does not anticipate that its existing well(s) connected to the same segment, or portion, of the natural gas gathering system(s) described above will continue to meet anticipated increases in line pressure caused by the new well(s).

☐ Attach Operator's plan to manage production in response to the increased line pressure.

☐ Operator asserts confidentiality pursuant to Section 71-2-8 NMSA 1978 for the information provided in Section 2 as provided in Paragraph (2) of Subsection D of 19.15.27.9 NMAC, and attaches a full description of the specific information for which confidentiality is asserted and the basis for such assertion. XIV. Confidentiality:

Section 3 - Certifications Effective May 25, 202

Operator certifies that, after reasonable inquiry and based on the available information at the time of submittal:

hundred percent of the anticipated volume of natural gas produced from the well(s) commencing on the date of first production, taking taking into account the current and anticipated volumes of produced natural gas from other wells connected to the pipeline ga thering Solution Solutio one hundred percent of the anticipated volume of natural gas produced from the well(s) commencing on the date of first production, Operator will not be able to connect to a natural gas gathering system in the general area with sufficient capacity to transport one into account the current and anticipated volumes of produced natural gas from other wells connected to the pipeline gathering system.

Well Shut-In. \square Operator will shut-in and not produce the well until it submits the certification required by Paragraph (4) of Subsection D of 19.15.27.9 NMAC; or

If Operator checks this box, Operator will select one of the following:

Venting and Flaring Plan.

Operator has attached a venting and flaring plan that evaluates and selects one or more of the potential

alternative beneficial uses for the natural gas until a natural gas gathering system is available, including:

(a) power generation on lease;


- power generation for grid;
 - compression on lease;
- reinjection for underground storage;
- reinjection for temporary storage;
- reinjection for enhanced oil recovery;
- other alternative beneficial uses approved by the division. fuel cell production; and £ 5 5 6 5 6 5 6 5 6

Section 4

- 1. If, at any time after Operator submits this Natural Gas Management Plan and before the well is spud:
- Operator becomes aware that the natural gas gathering system it planned to connect the well(s) to has become unavailable or will not have capacity to transport one hundred percent of the production from the well(s), no later than 20 days after becoming aware of such information, Operator shall submit for OCD's approval a new or revised venting and flaring plan containing the information specified in Paragraph (5) of Subsection D of 19.15.27.9 NMAC; or
- Operator becomes aware that it has, cumulatively for the year, become out of compliance with its baseline natural gas for OCD's approvala new or revised Natural Gas Management Plan for each well it plans to spud during the next 90 days containing the information specified in Paragraph (2) of Subsection D of 19.15.27.9 NMAC, and shall file an update for each Natural Gas capture rate or natural gas capture requirement, no later than 20 days after becoming aware of such information, Operator shall submit Management Plan until Operator is back in compliance with its baseline natural gas capture rate or natural gas capture requirement.
- flaring plan which includes alternative beneficial uses for the anticipated volume of natural gas produced, or if OCD determines that 2. OCD may deny or conditionally approve an APD if Operator does not make a certification, fails to submit an adequate venting and Operator will not have a dequate natural gas ta kea way capacity at the time a well will be spud.

Page 6 of 6

I certify that, after reasonable inquiry, the statements in and attached to this Natural Gas Management Plan are true and correct to the best of my knowledge and acknowledge that a false statement may be subject to civil and criminal penalties under the Oil (Only applicable when submitted as a standalone form) OIL CONSERVATION DIVISION **Environmental and Regulatory Advisor** nicj100@gmail.com 432-2363808 Adrian Baker 9/9/2024 Conditions of Approval: E-mail Address: and Gas Act. Approval Date: Printed Name: Approved By: Signature: Phone: Title: Date: Title:



VI. Separation Equipment:

XTO Permian Operating LLC. utilizes a "stage separation" process in which oil and gas separation is separation process is to attain maximum recovery of liquid hydrocarbons from the fluids and allow Hydrocarbon liquids are produced into a high-pressure inlet separator, then carried through one or Compression units to capture gas off the staged separation and send it to the sales pipeline. This maximum capture of produced gas into the sales pipeline. XTO utilizes a series of Low-Pressure more lower pressure separation vessels before entering the storage tanks. The purpose of this process minimizes the amount of flash gas that enters the end-stage storage tanks that is carried out through a series of separators operating at successively reduced pressures. subsequently vented or flared.

VII. Operational Practices

XTO Permian Operating LLC will employ best management practices and control technologies to maximize the recovery and minimize waste of natural gas through venting and flaring.

- technically feasible. If flaring is deemed technically in-feasible, XTO will employ best management During drilling operations, XTO will utilize flares to capture and control natural gas, where practices to minimize or reduce venting to the extent possible.
- During completions operations, XTO will utilize Green Completion methods to capture gas produced during well completions that is otherwise vented or flared. If capture is technically inflowback. Upon indication of first measurable hydrocarbon volumes, XTO Permian Operating feasible, flares will be used to control flow back fluids entering into frac tanks during initial LLCwill turn operations to onsite separation vessels and flow to the gathering pipeline.
- During production operations, XTO Permian Operating LLC will take every practical effort to minimize waste of natural gas through venting and flaring by:
- Designing and constructing facilities in a manner consistent to achieve maximum capture and control of hydrocarbon liquids & produced gas
- Utilizing a closed-loop capture system to collect, and route produced gas to sales line via low pressure compression, or to a flare/combustor
- Flaring in lieu of venting, where technically feasible
- Utilizing auto-ignitors or continuous pilots, with thermocouples connected to Scada, to quickly detect and resolve issues related to malfunctioning flares/combustors
- Employ the use of automatic tank gauging to minimize storage tank venting during loading
- Installing air-driven or electric-driven pneumatics & combustion engines, where technically feasible to minimize venting to the atmosphere
 - Confirm equipment is properly maintained and repaired through a preventative maintenance and repair program to ensure equipment meets all manufacturer specifications

Conduct and document AVO inspections on the frequency set forth in Part 27 to detect and repair any onsite leaks as quickly and efficiently as is feasible. •

VIII. Best Management Practices during Maintenance

venting to the atmosphere. XTO will work with third-party operators during scheduled maintenance facilities permitted under NOI permits have no provisions to allow high pressure flaring and highof downstream pipeline or processing plants to address those events ahead of time to minimize pressure flaring is only allowed in disruption scenarios so long as the duration is less than eight hours. When technically feasible, flaring during maintenance activities will be utilized in lieu of XTO Permian Operating LLC. will utilize best management practices to minimize venting during venting. Actions considered include identifying alternative capture approaches or planning to active and planned maintenance activities. XTO is operating under guidance that production temporarily reduce production or shut in the well to address these circumstances.

XTO Permian Operating, LLC Offline Cementing Variance Request

a XTO requests the option to cement the surface and intermediate casing strings offline as prudent batch drilling efficiency of acreage development.


1. Cement Program

No changes to the cement program will take place for offline cementing.

2. Offline Cementing Procedure


The operational sequence will be as follows. If a well control event occurs, the BLM will be contacted for approval prior to conducting offline cementing operations.

- Run casing as per normal operations. While running casing, conduct negative pressure test and confirm integrity of the float equipment (float collar and shoe)
- Land casing with mandrel
- Fill pipe with kill weight fluid, do not circulate through floats and confirm well is static 5 6 4 4 4 4 H
 - Set annular packoff shown below and pressure test to confirm integrity of the seal Pressure ratings of wellhead components and valves is 5,000 psi.
- After confirmation of both annular barriers and internal barriers, nipple down BOP δ.
- If any barrier fails to test, the BOP stack will not be nippled down until after the cement job is completed with cement 500ft above the highest formation capable of flow with kill weight mud above or after it has achieved 50-psi compressive strength if kill weight fluid cannot be verified. and install cap flange.



Annular packoff with both external and internal seals


XTO Permian Operating, LLC Offline Cementing Variance Request



Wellhead diagram during skidding operations

- Skid rig to next well on pad.
- Confirm well is static before removing cap flange, flange will not be removed and offline cementing operations will not commence until well is under control. If well is not static, party pump truck will kill well prior to cementing or nippling up for further remediation. casing outlet valves will provide access to both the casing ID and annulus. Rig or third 6.
 - Well Control Plan
- control of the wellbore prior to cementing, if wellbore conditions do not The Drillers Method will be the primary well control method to regain permit the drillers method other methods of well control may be used
- Rig pumps or a 3rd party pump will be tied into the upper casing valve to pump down the casing ID :=
- A high pressure return line will be rigged up to lower casing valve and run Once influx is circulated out of the hole, kill weight mud will be to choke manifold to control annular pressure :≓ . ĭ.
- Well will be confirmed static circulated
- Once confirmed static, cap flange will be removed to allow for offline cementing operations to commence ۲.
 - Install offline cement tool ∞. *e*.
- Rig up cement equipment

XTO Permian Operating, LLC Offline Cementing Variance Request



Wellhead diagram during offline cementing operations

- 10. Circulate bottoms up with cement truck
- a. If gas is present on bottoms up, well will be shut in and returns rerouted through gas buster to handle entrained gas
 - Max anticipated time before circulating with cement truck is 6 hrs
 - 11. Perform cement job taking returns from the annulus wellhead valve
 - 12. Confirm well is static and floats are holding after cement job
- 13. Remove cement equipment, offline cement tools and install night cap with pressure gauge for monitoring.

Subject: Request for a Variance Allowing break Testing of the Blowout Preventer Equipment (BOPE)

XTO Energy requests a variance to ONLY test broken pressure seals on the BOPE and function test BOP when skidding a drilling rig between multiple wells on a pad.

Background

test of the affected component. CFR Title 43 Part 3170 states, "Some situation may exist either on a wellby- well basis or field-wide basis whereby it is commonly accepted practice to vary a particular minimum Energy feels the break testing the BOPE is such a situation. Therefore, as per CFR Title 43 Part 3170, XTO Onshore Oil and Gas Order CFR Title 43 Part 3170, Drilling Operations, Sections III.A.2.i.iv.B states that interpretation of the Bureau of Land Management (BLM) requires a complete BOP test and not just a standard(s) established in this order. This situation can be resolved by requesting a variance...". XTO the BOP test must be performed whenever any seal subject to test pressure is broken. The current Energy submits this request for the variance.

Supporting Documentation

regulating BLM onshore drilling operations for over 30 years. During this time there have been significant was originally released. The XTO Energy drilling rig fleet has many modern upgrades that allow the intact changes in drilling technology. BLM continues to use the variance request process to allow for the use of stack components apart. These technologies have been used extensively offshore, and other regulators, incorporate quick connects facilitating release of the BOP from the wellhead without breaking any BOP modern technology and acceptable engineering practices that have arisen since CFR Title 43 Part 3170 CFR Title 43 Part 3170 became effective on December 19, 1988 and has remained the standard for BOP stack to be moved between well slots on a multi-well pad, as well as, wellhead designs that API, and many operators around the world have endorsed break testing as safe and reliable.



Figure 1: Winch System attached to BOP Stack



Figure 2: BOP Winch System

American Petroleum Institute (API) standards, specification and recommended practices are considered "A pressure test of the pressure containing component shall be performed following the disconnection 3170recognizes API recommended Practices (RP) 53 in its original development. API Standard 53, Well recognizes break testing as an acceptable practice. Specifically, API Standard 53, Section 5.3.7.1 states the industry standard and are consistently utilized and referenced by the industry. CFR Title 43 Part Control Equipment Systems for Drilling Wells (Fifth Edition, December 2018, Annex C, Table C.4) or repair, limited to the affected component." See Table C.4 below for reference.

Tab	le C.4—Initial Pressure Te	Table C.4—Initial Pressure Testing, Surface BOP Stacks	
	mo I toot cancerde	Pressure Test-	Pressure Test—High Pressure
Component to be Pressure Tested	Pressure 1630 Pressure 36 psig (MPa)	Change Out of Component, Elastomer, or Ring Gasket	No Change Out of Component, Elastomer, or Ring Gasket
Annular preventer ⁶	250 to 350 (1.72 to 2.41)	RWP of annular preventer	MASP or 70% annular RWP, whichever is lower.
Fixed pipe, variable bore, blind, and BSR preventers ^{bd}	250 to 350 (1.72 to 2.41)	RWP of ram preventer or wellhead system, whichever is lower	Œ
Choke and kill line and BOP side outlet valves below ram preventers (both sides)	250 to 350 (1.72 to 2.41)	RWP of side outlet valve or wellhead system, whichever is lower	Ш
Choke manifold—upstream of chokes*	250 to 350 (1.72 to 2.41)	RWP of ram preventers or wellhead system, whichever is lower	Щ
Choke manifold—downstream of chokes*	250 to 350 (1.72 to 2.41)	RWP of valve(s), line(s), or MASP for the well program, whichever is lower	AASP for the well program
Kelly, kelly valves, drill pipe safety valves, IBOPs	250 to 350 (1.72 to 2.41)	MASP for the well program	
³ Pressure test evaluation periods shall be a minimum of five minutes. No visible leaks. The pressure shall remain stable during the evaluation period. The pressure shall not decrease below the intended a Amnulari(s) and VBR(s) shall be pressure tested on the largest and smallest OD drill pipe to be used in well program.	half be a minimum of five minutes. during the evaluation period. The pressure tested on the largest and sma	ressure test evaluation periods shall be a minimum of five minutes. No visible leaks. The pressure shall remain stable during the evaluation period. The pressure shall not decrease below the intended test pressure. The pressure shall remain stable during the evaluation period. The pressure shall remain stable program: mulants) and VBR(s) shall be pressure tested on the largest and smallest OD drill pipe to be used in well program.	intended test pressure.
For pad drilling operations, moving from one wellhead to another within the 21 days, pressure testing is required for pressure-containing and pressure-containing connections when the integrity of a pressure seal is broken.	or pad drilling operations, moving from one wellhead to another within the 21 day pressure-controlling connections when the integrity of a pressure seal is broken.	the 21 days, pressure testing is req is broken.	luired for pressure-containing
⁴ For surface offshore operations, the ram BOPs shall be pressure tested with the ram locks engaged and the closing and locking pressure verted during in initial test. For fand operations, the ram BOPs shall be pressure tested with the ram locks engaged and the closing and locking necessure verted at commissioning and annually.	e ram BOPs shall be pressure tests and operations, the ram BOPs shall ssioning and annually.	or surface offshore operations, the ram BOPs shall be pressure tested with the ram locks engaged and the closing and locking pressure wented during the Intial test. For fand operations, the card and the closing and locking the intial test for fand operations, the aim and BOPs shall be pressure tested with the ram locks engaged and the closing and locking card arounds and annual law.	the closing and locking press

The Bureau of Safety and Environmental Enforcement (BSEE), Department of Interior, has also utilized the API standards, specification and best practices in the development of its offshore oil and gas regulations and incorporates them by reference within its regulations.

Break testing has been approved by the BLM in the past with other operators based on the detailed information provided in this document. XTO Energy feels break testing and our current procedures meet the intent of CFR Title 43 Part 317 Oand that of CFR Title 43 Part 3170 (Every 21 days). In addition to function testing the annular, pipe rams and often exceed it. There has been no evidence that break testing results in more components failing than seen on full BOP tests. XTO Energy's internal standards requires complete BOPE tests more often than blind rams after each BOP nipple up, XTO Energy performs a choke drill with the rig crew prior to drilling out every casing shoe. This is additional training for the rig crew that exceeds the requirements of the CFR Title 43 Part

Procedures

- The summary below will be referenced in the APD or Sundry Notice and receive approval prior XTO Energy will use this document for our break testing plan for New Mexico Delaware basin. to implementing this variance ۲i
- XTO Energy will perform BOP break testing on multi-wells pads where multiple intermediate sections can be drilled and cased within the 21-day BOP test window. 7
- A full BOP test will be conducted on the first well on the pad.
- The first intermediate hole section drilled on the pad will be the deepest. All of the remaining hole sections will be the same depth or shallower.
- Our Lower WC targets set the intermediate casing shoe no deeper than the Wolfcamp B.
- Our Upper WC targets set the intermediate casing shoe shallower than the Wolfcamp B.

A Full BOP test will be required if the intermediate hole section being drilled has a MASP


A full BOP test will be required prior to drilling any production hole.

over 5M.

- After performing a complete BOP test on the first well, the intermediate hole section will be drilled and cased, two breaks would be made on the BOP equipment. 'n
- Between the HCV valve and choke line connection
 -). Between the BOP quick connect and the wellhead
- The BOP is then lifted and removed from the wellhead by a hydraulic system. 4.
- After skidding to the next well, the BOP is moved to the wellhead by the same hydraulic system and installed. 5.
- The connections mentioned in 3a and 3b will then be reconnected. 6.
 - 7. Install test plug into the wellhead using test joint or drill pipe.
- A shell test is performed against the upper pipe rams testing the two breaks. œ.
- The shell test will consist of a 250 psi low test and a high test to the value submitted in the APD or Sundry (e.g. 5,000 psi or 10,000psi). 9
- Function test will be performed on the following components: lower pipe rams, blind rams, and annular. 10.

- 11. For a multi-well pad the same two breaks on the BOP would be made and on the next wells and steps 4 through 10 would be repeated.
 - A second break test would only be done if the intermediate hole section being drilled could not be completed within the 21 day BOP test window. 12.

Note: Picture below highlights BOP components that will be tested during batch operations




Summary

drilling operation, moving from one wellhead to another within 21 days, pressure testing is required for wellhead to wellhead which is in compliance with API Standard 53. API Standard 53 states, that for pad A variance is requested to **ONLY** test broken pressure seals on the BOP equipment when moving from pressure-containing and pressure-controlling connections when the integrity of a pressure seal is broken.

The BOP will be secured by a hydraulic carrier or cradle. The BLM will be contacted if a Well Control event occurs prior to the commencement of a BOPE Break Testing operation. Based on discussions with the BLM on February 27th 2020 and the supporting documentation submitted to the BLM, we will request permission to ONLY retest broken pressure seals if the following conditions are met:

- After a full BOP test is conducted on the first well on the pad.
- 2. The first intermediate hole section drilled on the pad will be the deepest. All of the remaining hole sections will be the same depth or shallower.
- 3. Full BOP test will be required if the intermediate hole section being drilled has a MASP over 5M.
- 4. Full BOP test will be required prior to drilling the production hole.



XTO respectfully requests approval to utilize a spudder rig to pre-set surface casing.

Description of Operations:

- Spudder rig will move in to drill the surface hole and pre-set surface casing on the well.
- following all of the applicable rules and regulations (OnShore Order 2, all COAs and After drilling the surface hole section, the spudder rig will run casing and cement NMOCD regulations).
- Solids control will be handled entirely on a closed loop basis. No earth pits will be The spudder rig will utilize fresh water-based mud to drill the surface hole to TD. used. Þ.
- The wellhead will be installed and tested as soon as the surface casing is cut off and WOC time has been reached. $\ddot{\circ}$
- A blind flange at the same pressure rating as the wellhead will be installed to seal the wellbore. Pressure will be monitored with needle valves installed on two wing valves. က
- A means for intervention will be maintained while the drilling rig is not over the well.
- Spudder rig operations are expected to take 2-3 days per well on the pad. 4
- The BLM will be contacted and notified 24 hours prior to commencing spudder rig operations. 5
- Drilling Operations will begin with a larger rig and a BOP stack equal to or greater than the pressure rating that was permitted will be nippled up and tested on the wellhead before drilling operations resume on each well. 6
- The larger rig will move back onto the location within 90 days from the point at which the wells are secured and the spudder rig is moved off location.
- The BLM will be notified 24 hours before the larger rig moves back on the pre-set locations Þ.
- XTO will have supervision on the rig to ensure compliance with all BLM and NMOCD regulations and to oversee operations. ζ.
- Once the rig is removed, XTO will secure the wellhead area by placing a guard rail around the cellar area. œί



BLACK GOLD®

GATES ENGINEERING & SERVICES NORTH AMERICA

7603 Prairie Oak Dr. Houston, TX. 77086

PHONE: +1 (281) 602-4100

EMAIL: gesna.quality@gates.com +1 (281) 602-4147

www.gates.com/oilandgas WEB:

HOSE

02-10-2024 CHOKE INSTAMED MBN

OF CONFORMANCE CERTIFICATE

Order referenced herein, and are in Conformance with applicable specifications, and that Records of hydrostatically tested at Gates Engineering & Services North America facilities in Houston, TX, This is to verify that the items detailed below meet the requirements of the Customer's Purchase Required Tests are on file and subject to examination. The following items were inspected and

NABORS DRILLING TECHNOLOGIES USA DBA NABORS DRILLING USA 15582803 (TAG NABORS PO #15582803 SN 74621 ASSET 66-1531) IMR RETEST SN 74621 ASSET #66-1531 CUSTOMER P.O.#: CUSTOMER P/N: CUSTOMER:

RETEST OF CUSTOMER 3" X 45 FT 16C CHOKE & KILL HOSE ASSEMBLY C/W 4 1/16" 10K FLANGES PART DESCRIPTION:

529480 SALES ORDER #: QUANTITY: 74621 H3-012524-1

SERIAL #:

SIGNATURE:

QUALITY ASSURANCE

DATE:

TITLE:

1/25/2024

H3-15/16

1/25/2024 11:48:06 AM

TEST REPORT

		TEST OBJECT
	Nabors industries inc.	Lot number:
Production description:	74621/66-1531	Description:
	529480	
Customer reference:	FG1213	Hose ID:
		Dark primbor

74621/66-1531

3" 16C CK

H3-012524-1

			Part number:	
TEST INFORMATION				
Test procedure:	GTS-04-053		Fitting 1:	3.0 × 4-1/16 10K
Test pressure:	15000.00	psi	Part number;	
Test pressure hold:	3600.00	sec	Description:	
Work pressure:	10000.00	psi		
Work pressure hold:	900.00	sec	Fitting 2:	3.0 × 4-1/16 10K
Length difference:	0.00	%	Part number:	
Length difference:	0.00	inch	Description:	

feet

45


Length:

PASS

Length measurement result:

Pressure test result:

Visual check:




Released to Imaging: 9/19/2025 3:47:41 PM

H3-15/16 1/25/2024 11:48:06 AM


S-25-A-W 110D3PHO 2023-06-06 2024-06-06 S-25-A-W 110IQWDG 2023-05-16 2024-05-16 Comment		Serial number	Calibration date	Calibration due date
110lQWDG 2023-05-16	S-25-A-W	110D3PHO	2023-06-06	2024-06-06
Comment	S-25-A-W	110IQWDG	2023-05-16	2024-05-16
	Comment			
				r

Released to Imaging: 9/19/2025 3:47:41 PM

GAUGE TRACEABILITY




Released to Imaging: 9/19/2025 3:47:41 PM









Released to Imaging: 9/19/2025 3:47:41 PM

U.S. Department of the Interior BUREAU OF LAND MANAGEMENT

APD ID: 10400100857

Operator Name: XTO PERMIAN OPERATING LLC

Well Name: POKER LAKE UNIT 18-30 BD

Well Type: OIL WELL

Well Work Type: Drill Well Number: 202H

Highlighted data reflects the most recent changes

Submission Date: 09/23/2024

SUPO Data Report

Show Final Text

- Existing Roads Section 1

Will existing roads be used? YES

Existing Road Map:

POKER_LAKE_UNIT_18_30_BD_202H_EXISTING_ROAD_MAP_20250307090632.pdf

Existing Road Purpose: ACCESS

Row(s) Exist? NO

ROW ID(s)

≘

Do the existing roads need to be improved? NO

Existing Road Improvement Description:

Existing Road Improvement Attachment:

Section 2 - New or Reconstructed Access Roads

Will new roads be needed? NO

Section 3 - Location of Existing Wells

Existing Wells Map? YES

Existing Well map Attachment:

Operator Name: XTO PERMIAN OPERATING LLC

Well Name: POKER LAKE UNIT 18-30 BD

Well Number: 202H

18 30 BD_1Mile Radius_Map_20240905080544.pdf POKER_LAKE_UNIT_18_19

Location of Existing and/or Proposed Production Facilities Section 4

Submit or defer a Proposed Production Facilities plan? SUBMIT

facilities designed. The containment berms will be constructed of compacted 24 caliche, be sufficiently impervious, away from disturbance is needed. D. Disposal Facilities. Produced water will be hauled from location to a commercial or private disposal facility as needed. E. Flare. - Check in facility plot attached. F. Aboveground Structures. All permanent (on site six months or longer) aboveground structures constructed or installed on location and not subject to safety requirements will be painted earth-tone colors such as BLM Standard Environmental Color Chart (CC-001: June 2008) that reduce the visual impacts of **Production Facilities description:** A. Production Facilities. No New facility is required for the Poker Lake Unit 18-30/18-19 BD wells. Once drilled and completed, the wells will flow to the Poker Lake Unit 18-30/18-19 BD battery. B. Flowlines. No further flowlines disturbance is requested. C. Gas Pipeline. No Gas Sales line is required for this well. No additional surface cut or fill areas. H. Electrical. No additional electrical is required for this well. No additional surface disturbance is needed. I. the built environment. G. Containment Berms. Containment berms will be constructed completely around any production Facility Description-Kindly see the facility plot attached

Production Facilities map:

618.013003.03_XTO_PLU_18_BD_EXISTING_CVB_FINAL_10_04_2024_20250311091302.pdf

Section 5 - Location and Types of Water Supply

ater Source Table

Water source type: OTHER

Describe type: Raw produced water

Water source use type: INTERMEDIATE/PRODUCTION

CASING

Source latitude:

Source longitude:

Source datum:

City:

Water source permit type: PRIVATE CONTRACT

Water source transport method: PIPELINE

Source land ownership: COMMERCIAL

Source transportation land ownership: FEDERAL

Source volume (acre-feet): 70.89120298 Water source volume (barrels): 550000

Source volume (gal): 23100000

Operator Name: XTO PERMIAN OPERATING LLC

Well Name: POKER LAKE UNIT 18-30 BD

Well Number: 202H

Water source type: OTHER

Describe type: Fresh Water

Water source use type: DUST CONTROL

SURFACE CASING

STIMULATION

Source longitude: Source latitude:

Source datum:

city:

Water source permit type: PRIVATE CONTRACT

Water source transport method: TRUCKING

Source land ownership: COMMERCIAL

Source transportation land ownership: FEDERAL

Source volume (acre-feet): 70.89120298 Water source volume (barrels): 550000

Source volume (gal): 23100000

Water source type: RECYCLED

Water source use type: INTERMEDIATE/PRODUCTION

CASING

Source latitude:

Source longitude:

Source datum:

City:

Water source permit type: PRIVATE CONTRACT

Water source transport method: PIPELINE

Source land ownership: COMMERCIAL

Source transportation land ownership: FEDERAL

Source volume (acre-feet): 70.89120298 Water source volume (barrels): 550000

Water source and transportation

POKER_LAKE_UNIT_18_30_BD_202H_VICINITY_MAP_20250307090837.pdf

Program. Water composition depends on the mud type needed per formation to protect useable water. Fresh water is trucked to location for use in surface casing drilling and cementing. All other water is either brackish or raw produced water that is all piped from either a pipeline or a pond (32.1483028, -103.922338) to the drilling location. Anticipated water usage for drilling includes an estimated 50,000 barrels of water to drill a horizontal well in a combination of fresh water and brine as detailed in Page 3 of 12 Water source comments: The well will be drilled using a combination of water mud systems as outlined in the Drilling the mud program in

Page 4 of 12

Operator Name: XTO PERMIAN OPERATING LLC

Well Name: POKER LAKE UNIT 18-30 BD

Well Number: 202H

and completion schedules. Well completion is expected to require approximately 550,000 barrels of water per horizontal well. length of horizontal sections, and the losses that may occur during the operation. Temporary water lines will be permitted via a Temporary Water Line Approved Decision letter and/or any necessary Right of Way Grants as needed based on drilling circulation or wash out that may occur. Actual water volumes used during operations will depend on the depth of the well, the drilling plans. These volumes are calculated for ∼1.5bbls per foot of hole drilled with excess to accommodate any lost Actual water volumes used during operations will depend on the depth of the well and length of horizontal sections

New water well? N

New Water Well Info

Well datum: Well Longitude: Well latitude:

Well target aquifer:

Est thickness of aquifer: Est. depth to top of aquifer(ft):

Aquifer comments:

Aquifer documentation:

Well casing type: Well depth (ft):

Well casing inside diameter (in.): Well casing outside diameter (in.):

Used casing source:

New water well casing?

Drilling method:

Grout material:

Drill material:

Grout depth:

Completion Method:

Casing top depth (ft.):

Water well additional information:

Well Production type:

Casing length (ft.):

State appropriation permit:

Additional information attachment:

Section 6 - Construction Materials

Using any construction materials: NO

Construction Materials description:

Construction Materials source location

Section 7 - Methods for Handling

Waste type: GARBAGE

portable dumpster or trash cage, to prevent scattering and will be removed and deposited in an approve sanitary landfill. Immediately after drilling all debris and other waste materials on and around the well location not contained in the trash cage will be cleaned up and removed from the location. No potentially adverse materials or substances will be left on the location. Waste content description: All garbage, junk and non-flammable waste materials will be contained in a self-contained

Amount of waste: 250 pounds

Waste disposal frequency : Weekly

Well Name: POKER LAKE UNIT 18-30 BD

Well Number: 202H

Immediately after drilling all debris and other waste materials on and around the well location not contained in the trash cage will be cleaned up and removed from the location. No potentially adverse materials or substances will be left on the location. **Safe containment description:** All garbage, junk and non-flammable waste materials will be contained in a self-contained, portable dumpster or trash cage, to prevent scattering and will be removed and deposited in an approve sanitary landfill.

Safe containmant attachment:

Disposal location ownership: COMMERCIAL Waste disposal type: HAUL TO COMMERCIAL

Disposal type description:

Disposal location description: A licensed 3rd party contractor will be used to haul and dispose of garbage.

Waste type: SEWAGE

in an approved sewage disposal facility. All state and local laws and regulations pertaining to the disposal of human and solid drilling and completion activities, or as required, the toilet holding tanks will be pumped and the contents there of disposed of waste will be complied with. This equipment will be properly maintained during the drilling and completion operations and will Waste content description: Portable, self-contained toilets will be provided for human waste disposal. Upon completion of be removed when all operations are complete.

gallons Amount of waste: 250

Waste disposal frequency : Weekly

Safe containment description: Portable, self-contained toilets will be provided for human waste disposal. Upon completion of drilling and completion activities, or as required, the toilet holding tanks will be pumped and the contents there of disposed of in an approved sewage disposal facility. All state and local laws and regulations pertaining to the disposal of human and solid waste will be complied with. This equipment will be properly maintained during the drilling and completion operations and will be removed when all operations are complete.

Safe containmant attachment:

Disposal location ownership: COMMERCIAL Waste disposal type: HAUL TO COMMERCIAL

Disposal type description:

Disposal location description: A licensed 3rd party contractor to haul and dispose of human waste.

Waste type: DRILLING

Waste content description: FLUID

: One Time Only Waste disposal frequency

barrels

Amount of waste: 500

Safe containment description: Steel mud boxes

Safe containmant attachment

Disposal location ownership: COMMERCIAL Waste disposal type: HAUL TO COMMERCIAL

Disposal type description:

Disposal location description: R360 Environmental Solutions 4507 W Carlsbad Hwy, Hobbs, NM 88240

Well Name: POKER LAKE UNIT 18-30 BD

Well Number: 202H

Waste type: DRILLING

Waste content description: CUTTINGS

Amount of waste: 2100 pounds

Waste disposal frequency : One Time Only

Safe containment description: The well will be drilled utilizing a closed-loop mud system. Drill cuttings will be held in roll-off style mud boxes and taken to a New Mexico Oil Conservation Division (NMOCD) approved disposal site.

Safe containmant attachment:

Disposal location ownership: COMMERCIAL Waste disposal type: HAUL TO COMMERCIAL

ACILITY .

Disposal type description:

Disposal location description: R360 Environmental Solutions 4507 W Carlsbad Hwy, Hobbs, NM 88240

Reserve Pit

Reserve Pit being used? NO

Temporary disposal of produced water into reserve pit? NO

Reserve pit length (ft.) Reserve pit width (ft.)

Reserve pit volume (cu. yd.) Reserve pit depth (ft.)

Is at least 50% of the reserve pit in cut?

Reserve pit liner

Reserve pit liner specifications and installation description

Cuttings Area

Cuttings Area being used? NO

Are you storing cuttings on location? imes

Drilling Fluids. These will be contained in steel mud pits and then taken to a NMOCD approved commercial disposal facility. Produced Fluids. Water produced from the well will be held temporarily in steel tanks and then taken to a NMOCD approved Description of cuttings location Cuttings. The well will be drilled utilizing a closed-loop mud system. Drill cuttings will be held in roll-off style mud boxes and taken to a New Mexico Oil Conservation Division (NMOCD) approved disposal site. commercial disposal facility. Oil produced during operations will be stored in s until sold.

Cuttings area length (ft.)

Cuttings area depth (ft.)

Cuttings area volume (cu. yd.)

Cuttings area width (ft.)

Is at least 50% of the cuttings area in cut?

Cuttings area liner

Cuttings area liner specifications and installation description

Page 6 of 12

Well Name: POKER LAKE UNIT 18-30 BD

Well Number: 202H

- Ancillary Section 8

Are you requesting any Ancillary Facilities?: N

Ancillary Facilities

Comments:

- Well Site တ Section

Well Site Layout Diagram:

POKER_LAKE_UNIT_18_30_BD_202H_RL_20250307091355.pdf

202H WELL SITE PLAT 20250307090938.pdf POKER_LAKE_UNIT_18_30_BD_

Comments: Multi-well Pad.

Plans for Surface Section 10

Multiple Well Pad Name: POKER LAKE UNIT 18-19 18-30 BD Type of disturbance: No New Surface Disturbance

Multiple Well Pad Number: A

Recontouring

18_30_BD_PAD_A_INTERIM_RECLAMATION_FINAL_UPDATED_20250417124040.pdf 18_19 Drainage/Erosion control construction: Initial seedbed preparation will consist of recontouring to the appropriate interim or final reclamation standard. All compacted areas to be seeded will be ripped to a minimum depth of 18 inches with a minimum furrow spacing of 2 feet, followed by recontouring the surface and then evenly spreading the stockpiled topsoil. Prior to seeding, the seedbed will be scarified to a depth of no less than 4-6 inches

Drainage/Erosion control reclamation: Erosion features are equal to or less than surrounding area and erosion control is sufficient so that water naturally infiltrates into the soil and gullying, head cutting, slumping, and deep or excessive rills (greater than 3 inches) are not observed.

Well pad proposed disturbance

Road long term disturbance (acres): 0 Road interim reclamation (acres): 0 Road proposed disturbance (acres):

Powerline long term disturbance

Pipeline long term disturbance (acres): 0 Powerline interim reclamation (acres): Pipeline interim reclamation (acres): 0 0 Powerline proposed disturbance Pipeline proposed disturbance

Other long term disturbance (acres): 0 (acres): 0 Other interim reclamation (acres): 0 Other proposed disturbance (acres): acres):

Total long term disturbance: 0 Total interim reclamation: 0 Total proposed disturbance: 0

Disturbance Comments:

landform will be restored for all disturbed areas including well pads, production facilities, roads, pipelines, and utility corridors Reconstruction method: The original stock piled topsoil will be spread over the areas being reclaimed and the original as close as possible to the original topography. The location will then be ripped and seeded.

Page 8 of 12

Operator Name: XTO PERMIAN OPERATING LLC

Well Name: POKER LAKE UNIT 18-30 BD

Well Number: 202H

landform will be restored for all disturbed areas including well pads, production facilities, roads, pipelines, and utility corridors **Fopsoil redistribution:** The original stock piled topsoil will be spread over the areas being reclaimed and the original as close as possible to the original topography. The location will then be ripped and seeded.

Soil treatment: A self-sustaining, vigorous, diverse, native (or otherwise approved) plant community will be established on the site with a density sufficient to control erosion and invasion by non-native plants and to re-establish wildlife habitat or forage production. At a minimum, the established plant community will consist of species included in the seed mix and/or desirable species occurring in the surrounding natural vegetation.

are found on alluvial fans and floodplains and form in mixed alluvium. The Simona Bippus soils are dominant to the east and Vegetation at the well pad: Soils are classified as Simona Gravelly Fine Sandy Loam and Simona-Bippus Simona soils are found on alluvial fans and plans and form in mixed alluvium and/or Aeolian sands. Bippus soils the Simona Gravelly Fine Sandy Loams are dominant to the West. Dominant vegetation species include mesquite, sumac snakeweed, and various forbs and grasses. Ground cover is minimal, offering 90 percent visibility. Existing Vegetation at the well pad: Soils are classified as Simona Gravelly

Existing Vegetation at the well pad

Existing Vegetation Community at the road: Soils are classified as Simona Gravelly Fine Sandy Loam and Simona-Bippus are found on alluvial fans and floodplains and form in mixed alluvium. The Simona Bippus soils are dominant to the east and Simona soils are found on alluvial fans and plans and form in mixed alluvium and/or Aeolian sands. Bippus soils the Simona Gravelly Fine Sandy Loams are dominant to the West. Dominant vegetation species include mesquite, sumac snakeweed, and various forbs and grasses. Ground cover is minimal, offering 90 percent visibility. Complex.

Existing Vegetation Community at the road

Bippus Complex. Simona soils are found on alluvial fans and plans and form in mixed alluvium and/or Aeolian sands. Bippus soils are found on alluvial fans and floodplains and form in mixed alluvium. The Simona Bippus soils are dominant to the east **Existing Vegetation Community at the pipeline**: Soils are classified as Simona Gravelly Fine Sandy Loam and Simonaand the Simona Gravelly Fine Sandy Loams are dominant to the West. Dominant vegetation species include mesquite, sumac snakeweed, and various forbs and grasses. Ground cover is minimal, offering 90 percent visibility.

Existing Vegetation Community at the pipeline

Simona-Bippus Complex. Simona soils are found on alluvial fans and plans and form in mixed alluvium and/or Aeolian sands. Bippus soils are found on alluvial fans and floodplains and form in mixed alluvium. The Simona Bippus soils are dominant to Existing Vegetation Community at other disturbances: Soils are classified as Simona Gravelly Fine Sandy Loam and the east and the Simona Gravelly Fine Sandy Loams are dominant to the West. Dominant vegetation species include mesquite, sumac snakeweed, and various forbs and grasses. Ground cover is minimal, offering 90 percent visibility.

Existing Vegetation Community at other disturbances

Non native seed used? N

Non native seed description:

Seedling transplant description:

Will seedlings be transplanted for this project? N

Seedling transplant description attachment:

Will seed be harvested for use in site reclamation? N

Seed harvest description:

Seed harvest description attachment:

Page 9 of 12

Operator Name: XTO PERMIAN OPERATING LLC

Well Name: POKER LAKE UNIT 18-30 BD

Well Number: 202H

Seed

Seed Table

Seed Summary

Total pounds/Acre:

Pounds/Acre

Seed Type

Seed reclamation

Operator Contact/Responsible Official

Email: bobby.hankins@exxonmobil.com Last Name: Hankins Phone: (970)629-5213 First Name: Bobby

standard. All compacted areas to be seeded will be ripped to a minimum depth of 18 inches with a minimum furrow spacing of 2 feet, followed by recontouring the surface and then evenly spreading the stockpiled topsoil. Prior to seeding, the seedbed will be scarified to a depth of no less than 4-6 inches. If the site is to be broadcast seeded, the surface will be left Seedbed prep: Initial seedbed preparation will consist of recontouring to the appropriate interim or final reclamation rough enough to trap seed and snow, control erosion, and increase water infiltration.

Seed BMP: If broadcast seeding is to be used and is delayed, final seedbed preparation will consist of contour cultivating to a depth of 4-6 inches within 24 hours prior to seeding, dozer tracking, or other imprinting to break the soil crust and create seed germination micro-sites.

Seed method: Seeding will be conducted no more than two weeks following completion of final seedbed preparation. A certified weed-free seed mix designed by the BLM to meet reclamation standards will be used.

Existing invasive species? N

Existing invasive species treatment description:

Existing invasive species treatment

Weed treatment plan description: Weed control for all phases will be through the use of approved pesticides and herbicides according to applicable State, Federal and local laws

Weed treatment plan

additional methods are required to monitor invasive and noxious weeds, appropriate BLM authorities will be contacted with Monitoring plan description: Monitoring of invasive and noxious weeds will be visual and as-needed. If it is determined a plan of action for approval prior to implementation. Weed treatment plan

Monitoring plan

Success standards: 100% compliance with applicable regulations.

Pit closure description: There will be no reserve pit as each well will be drilled utilizing a closed loop mud system. The closed loop system will meet the NMOCD requirements 19.15.17.
Pit closure attachment:

- Surface Section

Well Name: POKER LAKE UNIT 18-30 BD

Well Number: 202H

Disturbance type: EXISTING ACCESS ROAD

Describe:

Surface Owner: BUREAU OF LAND MANAGEMENT

Other surface owner description:

BIA Local Office:

BOR Local Office:

COE Local Office:

DOD Local Office: NPS Local Office: State Local Office:

Military Local Office:

USFWS Local Office: Other Local Office:

USFS Region:

USFS Forest/Grassland:

USFS Ranger District:

Disturbance type: WELL PAD

Describe:

Surface Owner: BUREAU OF LAND MANAGEMENT

Other surface owner description:

BIA Local Office:

BOR Local Office:

COE Local Office:

DOD Local Office:

NPS Local Office:

Military Local Office: State Local Office:

Other Local Office:

USFWS Local Office:

USFS Region:

USFS Forest/Grassland:

USFS Ranger District:

Page 11 of 12

Operator Name: XTO PERMIAN OPERATING LLC

Well Name: POKER LAKE UNIT 18-30 BD

Well Number: 202H

Disturbance type: TRANSMISSION LINE

Describe:

Surface Owner: BUREAU OF LAND MANAGEMENT

Other surface owner description:

BIA Local Office:

BOR Local Office:

COE Local Office:

DOD Local Office: NPS Local Office: State Local Office:

Military Local Office:

Other Local Office:

USFWS Local Office:

USFS Region:

USFS Forest/Grassland:

USFS Ranger District:

Disturbance type: OTHER

Describe: Flowline

Surface Owner: BUREAU OF LAND MANAGEMENT

Other surface owner description:

BIA Local Office:

BOR Local Office:

COE Local Office:

DOD Local Office:

NPS Local Office:

State Local Office:

Military Local Office:

USFWS Local Office: Other Local Office:

USFS Region:

USFS Forest/Grassland:

USFS Ranger District:

Well Name: POKER LAKE UNIT 18-30 BD

Well Number: 202H

Section 12 - Other

Right of Way needed? N

Use APD as ROW?

ROW Type(s):

ROW

SUPO Additional Information: SUPO written for all wells in section/project area.


Use a previously conducted onsite? \forall

Previous Onsite information: The XTO Permian Operating, LLC. representatives and BLM NRS were on location for onsite on 2/15/22.

Other SUPO

PLU_18_19__18_30_BD_SUPO_20250312033046.pdf

Page 12 of 12




DRIVING DIRECTIONS TO LOCATION

FROM THE INTERSECTION OF HIGHWAY 285 AND LONGHORN ROAD, GO NORTHEAST ON LONGHORN ROAD ROAD FOR APPROX. 4.2 MILES. TURN LEFT (NORTHEAST) ON PIPELINE ROAD NUMBER 1 AND GO APPROX. 7.0 MILES. TURN LEFT (WEST) ON LEASE ROAD AND GO APPROX. 0.9 MILES. TURN LEFT (WEST) ON LEASE ROAD AND GO APPROX. 0.5 MILES. TURN LEFT (SOUTH) ON LEASE ROAD AND GO APPROX. 0.2 MILES. TURN LEFT (SOUTH) ON LEASE ROAD AND GO APPROX. 0.2 MILES. TURN LET (CAST) ON LEASE ROAD AND GO APPROX. 0.1 MILES ARRIVING AT THE LOCATION TO THE NORTH.



5,000

2,500



A TOPOGRAPHICAL AND ACCESS ROAD MAP FOR XTO ENERGY, INC. POKER LAKE UNIT 18-30 BD 202H

.

ō


CONSULTING


LOCATED 265 FEET FROM THE NORTH LINE AND 2335 FEET FROM THE EAST LINE OF SECTION

2	18, TOWNSHIF	18, TOWNSHIP 25 SOUTH, RANGE 30 EAST, N.M.P.M. EDDY COUNTY, NEW MEXICO	ST, N.M.P.M. EDDY COUNTY	, NEW MEXICO
= D ^	СНЕСКЕD ВУ: AI	DATE: 6/28/2024	SCALE: 1":5,000'	PROJECT NUMBER: 618.013003.32-11
_	DRAWN BY:	FIELD CREW:	REVISION NUMBER:	SHEET:

505 Pecan Street, Suite 201, Fort Worth, TX 76102 Ph: 972.972.4550 Texas Board of Professional Engineers & Land Surveyors Reg. No. F-10194754 (Survi), F-22053 (Eng) © 2024 MANHARD CONSULTING, ALL RIGHTS RESERVED

Poker Lake Unit 18-19/18-30 BD





FROM THE INTERSECTION OF HIGHWAY 285 AND LONGHORN ROAD, GO NORTHEAST ON LONGHORN ROAD FOR APPROX. 4.2 MILES. TURN LEFT (NORTHEAST) ON PIPELINE ROAD NUMBER 1 AND GO APPROX. 7.0 MILES. TURN LEFT (NORTH) ON LEASE ROAD AND GO APPROX. 0.9 MILES. TURN LEFT (WEST) ON LEASE ROAD AND GO APPROX. 0.5 MILES. TURN LEFT (SOUTH) ON LEASE ROAD AND GO APPROX. 0.2 MILES. TURN LEFT (SOUTH) ON LEASE ROAD AND GO APPROX. 0.2 MILES. TURN LET (CAST) ON LEASE ROAD AND GO APPROX. 0.1 MILES ARRIVING AT THE LOCATION TO THE NORTH.

A VICINITY MAP FOR XTO ENERGY, INC.

POKER LAKE UNIT 18-30 BD 202H WELL LOCATION

EXISTING WELL PAD

DRIVING ROUTE


LEGEND


FROM THE EAST LINE OF SECTION

18, TOWNSHIF	18, TOWNSHIP 25 SOUTH, RANGE 30 EAST, N.M.P.M. EDDY COUNTY, NEW MEXICO	ST, N.M.P.M. EDDY COUNTY,	NEW MEXICO
снескер ву:	DATE: 6/28/2024	SCALE: 1":10,000'	PROJECT NUMBER: 618.013003. 3
DRAWN BY:	FIELD CREW:	REVISION NUMBER:	SHEET:

32-11

POKER LAKE UNIT 18-30 BD THE NORTH LINE AND 2335 FEET F PITH DANGE 30 EAST AN M DAM EI	OU EAST, IN.IVI.F.IVI. EI	SCALE: 1":10.	REVISION NUMBER
POKER LAKE UNIT 18-30 BD LOCATED 265 FEET FROM THE NORTH LINE AND 2335 FEET F	23 SOUTH, PAINGE	DATE: 6/28/2024	FIELD CREW: BD
LOCATED 265 FEET I	IO, IOWINSHIP	СНЕСКЕД ВУ:	DRAWN BY: RF
	t, Suite 201, Fort Wo	Ph. 972.972.4250 Texas Board of Professional Engineers & Land Strowners Boar No. = 10104754 (Stry) = 23063 (Engl	© 2024 MANHARD CONSULTING, ALL RIGHTS RESERVED





regived by OCD . 0/10/2025 11.52.46

FROM THE INTERSECTION OF LONGHORN ROAD AND PIPELINE ROAD NUMBER 1, HEAD NORTHEAST ON PIPELINE ROAD NUMBER ONE AND GO APPROX. 7.0 MILES. TURN LEFT (NORTHWEST) ONTO LEASE ROAD AND GO APPROX. 0.9 MILES. TURN LEFT (WEST) ONTO LEASE ROAD AND GO APPROX. 0.5 MILES. TURN LEFT (SOUTH) ONTO LEASE ROAD AND GO APPROX. 0.1 MILES. TURN LEFT (EAST) ONTO LEASE ROAD AND GO APPROX. 0.1 MILES AND THE LOCATION IS TO THE NORTH.

EDDX/MGII2/-11 -

GENERAL NOTES

200 SCALE

100

GRAPHIC

200 ft.

1 inch


(IN FEET)

EGEND

- BEARINGS AND COORDINATES SHOWN
 HEREON ARE MERCATOR GRID AND
 CONFORM TO THE NEW MEXICO
 COORDINATES SYSTEM "NEW MEXICO EAST
 ZONE" NORTH AMERICAN DATUM 1983.
- LATITUDE AND LONGITUDE VALUES SHOWN HEREON ARE RELATIVE TO THE NORTH AMERICAN DATA (NAD83). Ö
- REFER TO TOPOGRAPHICAL AND ACCESS ROAD MAP FOR PROPOSED ROAD LOCATION.

I,MARK DILLON HARP, NEW MEXICO PROFESSIONAL SURVEYOR NO. 23786, DO HEREBY CERTIFY THAT THIS SURVEYOR LOY THE GROUND UPON WHICH IT IS BASED WERE PREFORMED BY ME OR UNDER MY DIRECT SUPERVISION; THAT I AM RESPONSIBLE FOR THIS SURYEY. THAT THIS SURYEY NEW MEXICO, AND THAT IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIFF.

P:\618.013 XTO Energy - \M\003 Poker Lake Unit\.32 - PLU 18-19,18-30 BD-



SECTION LINE

PERMITTED PLU 18-30 BD WELL LOCATION PERMITTED PLU 18-19 BD WELL LOCATION TBD WELL LOCATION **EXISTING WELL PAD**

EXISTING ROAD

EXISTING OVERHEAD ELECTRIC

MARK DILLON HARP NEW MEXICO PROFESSIONAL LAND SURVEYOR NO. 23786



505 Pecan Street, Suite 201, Fort Worth, TX 76102 ph:817.865.5344 manhard.com Texas Board of Professional Engineers & Land Surveyors Reg. No. F-10194754 (Surv), F-22053 (Eng) ©2024 MANHARD CONSULTING, ALL RIGHTS RESERVED

POKER LAKE UNIT 18-30 BD 202H IS LOCATED 285 FEET FROM THE NORTH LINE AND 2,335 FEET FROM THE EAST LINE OF SECTION 18, TOWNSHIP 25 SOUTH, RANGE 30 EAST, N.M.P.M. EDDY COUNTY, NEW MEXICO A WELL SITE PLAN FOR XTO PERMIAN OPERATING, LLC POKER LAKE UNIT 18-19/18-30 BD EXISTING PAD A

CHECKED BY:	DATE:	SCALE:	PROJECT NO.:
DB	09/06/2024	1" = 200'	618.013003.32-11
DRAWN BY:	FIELD CREW:	REVISION NO.:	SHEET:
ΙĀ	SB	4	1 OF 3

paginal by OCD 0/10/2025 11.52.46

Released to imaging. 3/19/2023 3.47.41 PM

GENERAL NOTES

200 ft. FEET)

Z 1 inch

200

100

EDDY/DWG/To-Client/PAD A INTERIM REC.dwg

= 11.486 ACRES = 1.810 ACRES 9.676 ACRE

TOWNSHIP 25 SOUTH,

RANGE 30 EAST

NMPM

- BEARINGS AND COORDINATES SHOWN HEREON ARE MERCATOR GRID AND CONFORM TO THE NEW MEXICO COORDINATES SYSTEM "NEW MEXICO EAST ZONE" NORTH AMERICAN DATUM 1983.
- LATITUDE AND LONGITUDE VALUES SHOWN HEREON ARE RELATIVE TO THE NORTH AMERICAN DATA (NAD83). ۲,

WEX/00 W07710 I.MARK DILLON HARP, NEW MEXICO PROFESSIONAL
SURVEYOR NO. 23786. DO HERBY CERTIFY THAT THIS
SURVEY PLATAND THE ACTUAL SURVEY ON THE
GROUND UPON WHICH IT IS BASED WERE PREFORMED
BY ME OR UNDER MY DIRECT SUPERVISION; THAT I AM
RESPONSIBLE FOR THIS SURVEY, THAT THIS SURVEY
MEETS THE MINIMUM STANDARDS FOR SURVEYING IN
NEW MEXICO, AND THAT IS TRUE AND CORRECT TO THE
BEST OF MY KNOWLEDGE AND #ELIJEF.

P:\618.013 XTO Energy - NM\003 Poker Lake Unit\.32 - PLU 18-19,18-30 BD-

PERMITTED WELL LOCATION PLU 18-19 BD PERMITTED WELL LOCATION PLU 18-30 BD

TBD WELL LOCATION

EXISTING ROAD EXISTING PAD SECTION LINE

LEGEND

INTERIM RECLAMATION AREA

OTAL PAD ACREAGE AFTER IR ACREAGE INFORMATION
INITIAL CONSTRUCTED DISTURBED AREA
INTERIM RECLAMATION

ROYAVEVOR PROFESS

AN INTERIM RECLAMATION DIAGRAM FOR:

POKER LAKE UNIT 18-19/18-30 BD EXISTING PAD "A" XTO PERMIAN OPERATING, LLC.

1 OF 1	~	<u>ي</u>	
SHEET:	REVISION NO.:	FIELD CREW:	DRAWN BY:
PROJECT NO.: 618.01300 3	SCALE: 1" = 200'	DATE: 4/14/2025	СНЕСКЕD ВУ: DB
OM THE EAST LINE	PAD CENTER IS LOCATED 290 FEET FROM THE NORTH LINE AND 2,105 FEET FROM THE EAST LINE OF SECTION 18, TOWNSHIP 25 SOUTH, RANGE 30 EAST, N.M.P.M. EDDY COUNTY, NEW MEXICO	SATED 290 FEET FROM THE NO OWNSHIP 25 SOUTH, RANGE 3	PAD CENTER IS LOC OF SECTION 18, T

505 Pecan Street, Suite 201, Fort Worth, TX 76102 ph:817.865.5344 manhard.com Texas Board of Professional Engineers & Land Surveyors Reg. No. F-10194754 (Surv), F-22053 (Eng)

J

TIPS X

MARK DILLON HARP NEW MEXICO PROFESSIONAL LAND SURVEYOR NO. 23786

©2025 MANHARD CONSULTING, ALL RIGHTS RESERVED

1 OF 1	2	SR	A
SHEET:	REVISION NO.:	FIELD CREW:	DRAWN BY:
618,013003,32	1" = 200'	4/14/2025	DB
PROJECT NO.:	SCALE:	DATE:	CHECKED BY:

Well Site Locations

The results of the Poker Lake Unit 18-30/18-19 BD Development Program will develop economic quantities of oil and gas in the Poker Lake Unit 18-30/18-19 BD with multiple primary formations targeted. Well locations are determined based on cross-section variations and details. Locations will be selected to minimize the likelihood of encountering faults and/or drilling hazards while still targeting suitably productive zones. If drilling results in an unproductive well, the well will be plugged and abandoned as soon as practical after the conclusion of production testing. Productive wells may be shut-in temporarily for BLM authorization for production activities and facilities

L	N/S FOOTAGE	S/N	E/W FOOTAGE	E/W
NAME	CALL	LINE	CALL	LINE
POKER LAKE UNIT 18-30 BD 200H	265	JNH	2,395	Æ
POKER LAKE UNIT 18-30 BD 201H	265	JNH NH	2,365	FEL
POKER LAKE UNIT 18-30 BD 202H	265	HNL NL	2,335	FEL
POKER LAKE UNIT 18-30 BD 203H	265	FNL	2,305	FEL
POKER LAKE UNIT 18-19 BD 204H	265	FNL	2,275	FEL
POKER LAKE UNIT 18-19 BD 205H	265	FNL	1,935	FEL
POKER LAKE UNIT 18-19 BD 206H	265	FNL	1,905	FEL
POKER LAKE UNIT 18-19 BD 207H	265	FNL	1,875	Æ
POKER LAKE UNIT 18-19 BD 208H	265	FNL	1,845	FEL
POKER LAKE UNIT 18-19 BD 209H	265	FNL	1,815	FEL


Surface Use Plan

Existing Roads

- A. FROM THE INTERSECTION OF HIGHWAY 285 AND LONGHORN ROAD, GO NORTHEAST ON LONGHORN ROAD ROAD FOR APPROX. 4.2 MILES. TURN LEFT (NORTHEAST) ON PIPELINE ROAD NUMBER 1 AND GO APPROX. 7.0 MILES. TURN LEFT (NORTH) ON LEASE ROAD AND GO APPROX. 0.9 MILES. TURN LEFT (WEST) ON LEASE ROAD AND GO APPROX. 0.5 MILES. TURN LEFT (SOUTH) ON LEASE ROAD AND GO APPROX. 0.2 MILES. TURN LEFT (EAST) ON LEASE ROAD AND GO APPROX. 0.1 MILES ARRIVING AT THE LOCATION TO THE NORTH.
 - . Transportation maps identifying existing roads that will be used to access the project area are included from Manhard. marked as, 'Topographical and Access Road Map'.
- Transportation Plan identifying existing roads that will be used to access the project area is included from Manhard. marked as, Topographical and Access Road Map. All equipment and vehicles will Manhard. Maintenance of the access roads will continue until abandonment and reclamation of as provided Access Map be confined to the routes shown on the Topographical and the well pads is completed. ä

New or Upgraded Access Roads 'n

- **New Roads**. There are no new roads necessary to access the Poker Lake Unit 18-30/18-19 BD ocation.
- The well pads selected for development will determine which existing roads will be Well Pads. œ.
- truck. The Central Battery will require one lease operator truck to continually travel to each well site Additional traffic will include one maintenance truck periodically throughout the year for pad upkeep **Anticipated Traffic**. After well completion, travel to each well site will include one lease operator to monitor the working order of the wells and to check well equipment for proper operation. and weed removal. Well service trips will include only the traffic necessary to work on the wells or provide chemical treatments periodically and as needed throughout the year. ن
- Routing. All equipment and vehicles will be confined to the travel routes laid out in the vicinity map by Manhard unless otherwise approved by the BLM and applied for by PERMIAN OPERATING LLC provided ä
- Road Dimensions. The maximum width of the driving surface of new roads will be 14 feet. The roads will be crowned and ditched with a 2% slope from the tip of the crown to the edge of the driving surface. The ditches will be 1 foot deep with 3:1 slope. The driving surface will be made of 8" rolled and compacted caliche. نس



Level Ground Section

- Surface Material. Surface material will be native caliche. The average grade of all roads will be approximately 3%. ٠.
 - Fence Cuts: No. G.
 - Fences: No. ェ
- Cattle Guards: No. <u>-</u>:
 - Turnouts: No. ᅶ **∹**
 - Culverts: No.
- Cuts and Fills: look at attached plats.
- prior to any further construction activity. The topsoil that was stripped will be spread along the edge Topsoil. Approximately 6 inches of topsoil (root zone) will be stripped from the existing access road of the road and within the ditch. The topsoil will be seeded with the proper seed mix designated by
- and accommodate all-weather traffic. The road will be crowned and ditched with water turnouts **Maintenance**. The access road will be constructed and maintained as necessary to prevent soil erosion installed as necessary to provide for proper drainage along with access road route. ż
- Drainage. The access road and associated drainage structures will be constructed and maintained in accordance with road guidelines contained in the joint BLM/USFS publication: Surface Operating Standards for Oil and Gas Exploration and Development, The Gold Book, Fourth Edition and/or BLM 9113 concerning road construction standards on projects subject to federal Manual Section jurisdiction. ö

Location of Existing Wells m.

See attached 1-mile radius well map.

4. Location of Existing Production Facilities

- Once drilled and completed, the wells will flow to the Poker Lake Unit 18-30/18-19 BD battery. Production Facilities. No New facility is required for the Poker Lake Unit 18-30/18-19 BD wells.
- B. Flowlines. No further flowlines disturbance is requested.
- Gas Pipeline. No Gas Sales line is required for this well. No additional surface disturbance is needed. ن
- **Disposal Facilities**. Produced water will be hauled from location to a commercial or private disposal facility as needed. \Box
- E. Flare. Check in facility plot attached.
- Aboveground Structures. All permanent (on site six months or longer) aboveground structures constructed or installed on location and not subject to safety requirements will be painted earth-tone colors such as BLM Standard Environmental Color Chart (CC-001: June 2008) that reduce the visual mpacts of the built environment. ц
- Containment Berms. Containment berms will be constructed completely around any production acilities designed. The containment berms will be constructed of compacted 24" sufficiently impervious, away from cut or fill areas. G.
- Electrical. No additional electrical is required for this well. No additional surface disturbance is ェ
- Facility Description- Kindly see the facility plot attached.

5. Location and Types of Water Supply

Water composition depends on the mud type needed per formation to protect useable water. Fresh water is The well will be drilled using a combination of water mud systems as outlined in the Drilling Program. trucked to location for use in surface casing drilling and cementing. All other water is either brackish or raw produced water that is all piped from either a pipeline or a pond (32.1483028, -103.922338) to the drilling Anticipated water usage for drilling includes an estimated 50,000 barrels of water to drill a horizontal well in a combination of fresh water and brine as detailed in the mud program in the drilling plans. These volumes are calculated for ~1.5bbls per foot of hole drilled with excess to accommodate any lost circulation or wash out that may occur. Actual water volumes used during operations will depend on the depth of the well, length of horizontal sections, and the losses that may occur during the operation.

approximately 550,000 barrels of water per horizontal well. Actual water volumes used during operations will Temporary water lines will be permitted via a Temporary Water Line Approved Decision letter and/or any necessary Right of Way Grants as needed based on drilling and completion schedules. Well completion is expected to require depend on the depth of the well and length of horizontal sections

6. Construction Activities - NO NEW Construction

Construction, reclamation, and/or routine maintenance will not be conducted during periods when the soil conditions for construction could lead to impacts to the surrounding environment, or when watershed damage is likely to occur because of these activities. Any construction material that may be required for surfacing of the drill pad and access road will be from a contractor having a permitted source of materials within the general area. No construction materials will be removed from federal lands without prior approval from the appropriate surface management agency.

Well Pad. No New construction

Caliche Pit Location: 32.128730, -103.906308

7. Methods for Handling Waste

- Cuttings. The well will be drilled utilizing a closed-loop mud system. Drill cuttings will be held in roll-off style mud boxes and taken to a New Mexico Oil Conservation Division (NMOCD) approved disposal site.
 - **Drilling Fluids**. These will be contained in steel mud pits and then taken to a NMOCD approved commercial disposal facility.
- Produced Fluids. Water produced from the well will be held temporarily in steel tanks and then taken to a NMOCD approved commercial disposal facility. Oil produced during operations will be stored in s until
- Sewage. Portable, self-contained toilets will be provided for human waste disposal. Upon completion of drilling and completion activities, or as required, the toilet holding tanks will be pumped and the contents thereof disposed of in an approved sewage disposal facility. All state and local laws and regulations pertaining to the disposal of human and solid waste will be complied with. This equipment will be properly maintained during the drilling and completion operations and will be removed when all operations are
- Garbage and Other Waste Materials. All garbage, junk and non-flammable waste materials will be and deposited in an approve sanitary landfill. Immediately after drilling all debris and other waste materials on and around the well location not contained in the trash cage will be cleaned up and removed contained in a self-contained, portable dumpster or trash cage, to prevent scattering and will be removed from the location. No potentially adverse materials or substances will be left on the location.
- Debris. Immediately after removal of the drilling rig, all debris and other waste materials not contained in the trash cage will be cleaned and removed from the well location. No potential adverse materials or substances will be left on location. •

Hazardous Materials.

- Response Compensation Liability Act (CERCLA) removed from the location and not reused at All drilling wastes identified as hazardous substances by the Comprehensive Environmental another drilling location will be disposed of at a hazardous waste facility approved by the U.S. Environmental Protection Agency (EPA).
- XTO PERMIAN OPERATING LLC and its contractors will comply with all applicable Federal, State and local laws and regulations, existing or hereafter enacted promulgated, regarding any seq., and its regulation. The definition of hazardous substances under CERLCA includes any 'hazardous waste" as defined in the RCRA of 1976, as amended, 42 U.S.C. 6901 et seq., and its regulations. The term hazardous material also includes any nuclear or nuclear by-product material as defined by the Atomic Energy Act of 1954, as amended, 42 U.C.S. 2011 et seq. The term does not include petroleum, including crude oil or any fraction thereof that is not otherwise specifically listed or designated as a hazardous substance under CERCLA Section 101 (14) U.S.C. 9601 (14) nor hazardous material, as defined in this paragraph, that will be used, produced, transported or "Hazardous material" means any substance, pollutant or contaminant that is listed as hazardous under the CERCLA of 1980, as amended, 42 U.S.C 9601 et stored on the oil and gas lease. does the term include natural gas. ≔
- No hazardous substances or wastes will be stored on the location after completion of the well. i≡
- Chemicals brought to location will be on the Toxic Substance Control Act (TSCA) approved .<u>≥</u>
 - All undesirable events (fires, accidents, blowouts, spills, discharges) as specified in Notice to Lessees (NTL) 3A will be reported to the BLM Carlsbad Field Office. Major events will be reported verbally within 24 hours, followed by a written report within 15 days. "Other than Major Events" will be reported in writing within 15 days. >

8. Ancillary Facilities

Ancillary Facilities. No off-pad ancillary facilities are planned during the exploration phase including, but not limited to campsites, airstrips or staging areas.

9. Well Site Layout

Rig Plat Diagrams: There is 1 multi-well pad in the Poker Lake Unit 18-30/18-19 BD lease. This will allow enough space for cuts and fills, topsoil storage, and storm water control. Interim reclamation of these pads is anticipated after the drilling and completion of all wells on the pad. A well site layout for the pad is attached.

Pad A is a 26-well pad expected to be 898'x539'

Closed-Loop System: There will be no reserve pit as each well will be drilled utilizing a closed loop mud system. The closed loop system will meet the NMOCD requirements 19.15.17

V-Door Orientation: These pads were staked with multiple v-door orientations. The following list is from West to East in accordance with the staked section and as agreed upon with Zane Kirsch, BLM Natural Resource Specialist, present at on-site inspection.

Pad A has a V-Door Orientation: East

All equipment and vehicles will be confined to the approved disturbed areas of this APD (i.e., access road, well pad and topsoil storage areas

10. Plans for Surface Reclamation:

consecutive with the other wells on the pad. Once activities are completed, XTO Permian Operating, LLC. will activities have been finished on the pads as these are multi-well pads where drilling and completion will be XTO Permian Operating, LLC. requests a variance from interim reclamation until all drilling and completion coordinate interim reclamation with the appropriate BLM personnel or use the following plan:

Non-Commercial Well (Not Productive), Interim & Final Reclamation:

vegetative community will be restored, and it is anticipated the site will not be disturbed for future Definition: Reclamation includes disturbed areas where the original landform and a natural development.

Reclamation Standards:

operations will be reclaimed and seeded as per BLM requirements for interim reclamation. (See The portions of the pad not essential to production facilities or space required for workover Interim Reclamation plats attached). All equipment and trash will be removed, and the surfacing material will be removed from the well pad and road and transported to the original caliche pit or used to maintain other roads. The location will then be ripped and seeded.

pipelines, and utility corridors as close as possible to the original topography. The location will then landform will be restored for all disturbed areas including well pads, production facilities, roads, The original stockpiled topsoil will be spread over the areas being reclaimed and the original be ripped and seeded.

established on the site with a density sufficient to control erosion and invasion by non-native plants and to re-establish wildlife habitat or forage production. At a minimum, the established plant A self-sustaining, vigorous, diverse, native (or otherwise approved) plant community will be

community will consist of species included in the seed mix and/or desirable species occurring in the surrounding natural vegetation.

Erosion features are equal to or less than surrounding area and erosion control is sufficient so that water naturally infiltrates into the soil and gullying, head cutting, slumping, and deep or excessive rills (greater than 3 inches) are not observed.

The site will be free of State or County listed noxious weeds, oil field debris and equipment, and contaminated soil. Invasive and non-native noxious weeds will be controlled.

Seeding:

- Seedbed Preparation: Initial seedbed preparation will consist of recontouring to the appropriate interim or final reclamation standard. All compacted areas to be seeded will be ripped to a minimum depth of 18 inches with a minimum furrow spacing of 2 feet, followed by recontouring the surface and then evenly spreading the stockpiled topsoil. Prior to seeding, the seedbed will be scarified to a depth of no less than 4-6 inches. If the site is to be broadcast seeded, the surface will be left rough enough to trap seed and snow, control erosion, and increase water infiltration.
- If broadcast seeding is to be used and is delayed, final seedbed preparation will consist of contour cultivating to a depth of 4-6 inches within 24 hours prior to seeding, dozer tracking, or other imprinting to break the soil crust and create seed germination micro-sites.
- Seed Application. Seeding will be conducted no more than two weeks following completion of final seedbed preparation. A certified weed-free seed mix designed by the BLM to meet reclamation standards will be used.
- If the site is harrowed or dragged, seed will be covered by no more than 0.25 inch of soil.

11. Surface Ownership

- The Poker Lake Unit 18-30/18-19 BD is 100% of the surface is under the administrative jurisdiction of the Bureau of Land Management.
- The surface is multiple use with the primary uses of the region for grazing and to produce oil and gas.

2. Other Information

Surveying

- Well Sites. Well pad locations have been staked. Surveys of the Existing access roads and well pad surveys with access roads have been completed on State and Federal lands with Zane Kirsch, Bureau locations have been completed by Manhard, a registered professional land surveyor. Center stake of Land Management Natural Resource Specialist in attendance, on February 15, 2022.
- Cultural Resources Archaeology: A Class III Cultural Resources Examination has been completed by Boone Archaeological Services. A PA payment has been made for the well pad, access road, and overhead
- **Dwellings and Structures.** There are no dwellings or structures within 2 miles of this location.

Soils and Vegetation

- Complex. Simona soils are found on alluvial fans and plans and form in mixed alluvium and/or Aeolian Bippus soils are dominant to the east and the Simona Gravelly Fine Sandy Loams are dominant to the sands. Bippus soils are found on alluvial fans and floodplains and form in mixed alluvium. The Simona Environmental Setting. Soils are classified as Simona Gravelly Fine Sandy Loam and Simona-Bippus West. Dominant vegetation species include mesquite, sumac snakeweed, and various forbs and grasses. Ground cover is minimal, offering 90 percent visibility.
- Traffic. No truck traffic will be operated during periods or in areas of saturated ground when surface rutting could occur. The access road will be constructed and maintained as necessary to prevent soil erosion and accommodate all-weather traffic. The road will be crowned and ditched with water turnouts nstalled as necessary to provide for proper drainage along the access road route.
- Water. There is no permanent or live water in the immediate or within the project area.

13. Bond Coverage

Bond Coverage is Nationwide. Bond Number: COB000050

Onsite- The XTO Permian Operating, LLC. representatives and BLM NRS were on location for onsite on 2/15/22.

Operator's Representatives:

The XTO PERMIAN OPERATING LLC representatives for ensuring compliance of the surface use plan are listed below:

6401 Holiday Hill Road Bldg 5 Project Execution Planner XTO Energy, Incorporated Phone: (406) 478-3671 Midland, Texas 79701 **Robert Bartels**

U.S. Department of the Interior BUREAU OF LAND MANAGEMENT AFMSS

PWD Data Report

APD ID: 10400100857

Operator Name: XTO PERMIAN OPERATING LLC

Well Name: POKER LAKE UNIT 18-30 BD

Well Type: OIL WELL

Submission Date: 09/23/2024

Well Number: 202H

Well Work Type: Drill

- General $\overline{}$ Section

Would you like to address long-term produced water disposal? NO

Section 2 - Lined

Would you like to utilize Lined Pit PWD options? N

Produced Water Disposal (PWD) Location:

PWD surface owner:

PWD disturbance (acres):

Lined pit PWD on or off channel:

Other PWD Surface Owner Description:

Lined pit PWD discharge volume (bbl/day):

Lined pit

Pit liner description:

Precipitated solids disposal: Pit liner manufacturers

Decribe precipitated solids disposal:

Precipitated solids disposal

Lined pit precipitated solids disposal schedule:

Lined pit precipitated solids disposal schedule

Lined pit reclamation description:

Lined pit reclamation

Leak detection system description:

Leak detection system

Well Name: POKER LAKE UNIT 18-30 BD

Well Number: 202H

Lined pit Monitor description:

Lined pit Monitor

Lined pit: do you have a reclamation bond for the pit?

s the reclamation bond a rider under the BLM bond?

Lined pit bond number:

Lined pit bond amount:

Additional bond information

Section 3 - Unlined

Would you like to utilize Unlined Pit PWD options? ${\sf N}$

Produced Water Disposal (PWD) Location:

PWD disturbance (acres): PWD surface owner:

Other PWD Surface Owner Description:

Unlined pit PWD on or off channel:

Unlined pit PWD discharge volume (bbl/day):

Unlined pit

Precipitated solids disposal:

Decribe precipitated solids disposal:

Precipitated solids disposal

Unlined pit precipitated solids disposal schedule:

Unlined pit precipitated solids disposal schedule

Unlined pit reclamation description:

Unlined pit reclamation

Unlined pit Monitor description:

Unlined pit Monitor

Do you propose to put the produced water to beneficial use?

Beneficial use user

Estimated depth of the shallowest aquifer (feet):

Precipitated Solids Permit

Does the produced water have an annual average Total Dissolved Solids (TDS) concentration equal to or less than that of the existing water to be protected?

TDS lab results:

Geologic and hydrologic

Well Name: POKER LAKE UNIT 18-30 BD

Well Number: 202H

State

Unlined Produced Water Pit Estimated

Unlined pit: do you have a reclamation bond for the pit?

Is the reclamation bond a rider under the BLM bond?

Unlined pit bond number:

Unlined pit bond amount:

Additional bond information

Section 4

Would you like to utilize Injection PWD options? N

Produced Water Disposal (PWD) Location:

PWD surface owner:

PWD disturbance (acres):

Other PWD Surface Owner Description:

Injection PWD discharge volume (bbl/day):

Injection well mineral owner:

Injection well type:

Injection well number:

Assigned injection well API number?

Injection well API number:

Injection well name:

Injection well new surface disturbance (acres):

Minerals protection information:

Mineral protection

Underground Injection Control (UIC) Permit?

UIC Permit

Section 5 - Surface

Would you like to utilize Surface Discharge PWD options? N

Produced Water Disposal (PWD) Location:

PWD disturbance (acres):

Other PWD Surface Owner Description:

PWD surface owner:

Surface discharge PWD discharge volume (bbl/day):

Surface Discharge NPDES Permit?

Surface Discharge NPDES Permit attachment:

Surface Discharge site facilities information:

Surface discharge site facilities map:

Well Name: POKER LAKE UNIT 18-30 BD

Well Number: 202H

Section 6 -

Would you like to utilize Other PWD options? N

Produced Water Disposal (PWD) Location:

PWD surface owner:

PWD disturbance (acres):

Other PWD discharge volume (bbl/day): PWD Surface Owner Description:

Other PWD type description:

Other PWD type

Have other regulatory requirements been met?

Other regulatory requirements

U.S. Department of the Interior BUREAU OF LAND MANAGEMENT

APD ID: 10400100857

Operator Name: XTO PERMIAN OPERATING LLC

Well Name: POKER LAKE UNIT 18-30 BD

Well Type: OIL WELL

Well Work Type: Drill Well Number: 202H

Highlighted data reflects the most Show Final Text recent changes

Submission Date: 09/23/2024

Bond Info Data 05/19/2025

Bond

Federal/Indian APD: FED

BLM Bond number: COB000050

BIA Bond number:

Do you have a reclamation bond? NO

Is the reclamation bond a rider under the BLM bond?

Is the reclamation bond BLM or Forest Service?

BLM reclamation bond number:

Forest Service reclamation bond number:

Forest Service reclamation bond attachment:

Reclamation bond amount:

Reclamation bond rider amount:

Additional reclamation bond information attachment:

Sundry Print Report

U.S. Department of the Interior BUREAU OF LAND MANAGEMENT

Well Name: POKER LAKE UNIT 18-30 Well Location: T25S / R30E / SEC 18 / County or Parish/State: EDDY /

NWNE / 32.136718 / -103.91964

Well Number: 202H Type of Well: OIL WELL Allottee or Tribe Name:

Lease Number: NMLC065705B Unit or CA Name: POKER LAKE UNIT Unit or CA Number:

NMNM71016X

US Well Number: Operator: XTO PERMIAN OPERATING

LLC

Notice of Intent

Sundry ID: 2869627

Type of Submission: Notice of Intent

Type of Action: APD Change

Date Sundry Submitted: 08/26/2025 Time Sundry Submitted: 09:43

Date proposed operation will begin: 09/09/2025

Procedure Description: Poker Lake Unit 18-30 BD 202H XTO Permian Operating, LLC. respectfully requests approval to make the following changes to the approved APD. Changes to include SHL, KOP, FTP, LTP, BHL, proposed total depth, and dedicated acreage. APD ID: 10400100857 FROM: TO: SHL: 265' FNL & 2335' FEL OF SECTION 18-T25S-R30E 285' FNL & 2335' FEL OF SECTION 18-T25S-R30E KOP: 265' FNL & 2335' FEL OF SECTION 18-T25S-R30E 2552' FNL & 2274' FWL OF SECTION 18-T25S-R30E FTP: 100' FNL & 1758' FEL OF SECTION 18-T25S-R30E 2559' FSL & 2273' FWL OF SECTION 18-T25S-R30E LTP: 2556' FNL & 1758' FEL OF SECTION 30-T25S-R30E 100' FSL & 2449' FWL OF SECTION 19-T25S-R30E BHL: 2646' FNL & 1758' FEL OF SECTION 30-T25S-R30E 10' FSL & 2449' FWL OF SECTION 19-T25S-R30E The proposed total depth is changing FROM 22237' MD; 9366' TVD TO 17513' MD; 9263' TVD. Dedicated Acreage is changing FROM 400 Acres TO 480 Acres. There is no new surface disturbance.

NOI Attachments

Procedure Description

POKER_LAKE_UNIT_18_30_BD_202H_Sundry_Docs_updated_9.15.25_20250915124752.pdf

Page 1 of 2

Convert by OCD: 8/18/2025 11:53:44 18:30

BD

Well Location: T25S / R30E / SEC 18 /

NWNE / 32.136718 / -103.91964

County or Parish/State: EDDY of 185

NM

Well Number: 202H

Type of Well: OIL WELL

Allottee or Tribe Name:

Lease Number: NMLC065705B

Unit or CA Name: POKER LAKE UNIT

NMNM71016X

Unit or CA Number:

US Well Number:

Operator: XTO PERMIAN OPERATING

LLC

Conditions of Approval

Additional

253018 Poker Lake Unit 18 30 BD 202H 09 17 2025 SUNDRY ID 2869627 20250917090256.pdf

Operator

I certify that the foregoing is true and correct. Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction. Electronic submission of Sundry Notices through this system satisfies regulations requiring a

Operator Electronic Signature: SAMANTHA WEIS Signed on: SEP 15, 2025 12:50 PM

Name: XTO PERMIAN OPERATING LLC

Title: Permitting Advisor

Street Address: 22777 SPRINGWOODS VILLAGE PARKWAY

City: SPRING State: TX

Phone: (832) 625-7361

Email address: SAMANTHA.R.BARTNIK@EXXONMOBIL.COM

Field

Representative Name:

Street Address:

City:

State:

Zip:

Phone:

Email address:

BLM Point of Contact

BLM POC Name: CHRISTOPHER WALLS

BLM POC Title: Petroleum Engineer

BLM POC Phone: 5752342234 BLM POC Email Address: CWALLS@BLM.GOV

Disposition: Approved **Disposition Date:** 09/18/2025

Signature: Chris Walls

Page 2 of 2

C-102 State of Nev Energy, Minerals & Natura							w Mexico				Revised July 9, 2024
Submit El	ectronically		Ene	-			•	ment		Ť	Initial Submittal
	Permitting			O.	IL CONSERV	ATION DIVISION	JN		Submit	ttal -	✓ Amended Report
									Type:	-	As Drilled
				,	WELL LOCATION	INFORMATION					e
API Nu 30-0	mber 15 <u>-5727</u>	3	Pool Code 96473		Pool Na	^{ne} ERCE CROSSING; BO	ONE SP	RING. EAST			
Propert		0	Property Name	POKE	ER LAKE UNIT 18-30			<u> </u>		Well 202	Number 2H
ORGID 3730			Operator Name	XTO F	PERMIAN OPERATI	NG, LLC.				Grou	nd Level Elevation 82'
Surface	Owner:	State F	ee 🗌 Tribal 🛛	Federal		Mineral Owner:	State	Fee Triba	l 🛛 Fed	leral	
:			337		Surface	Location					ï-
UL B	Section 18	Township 25 S	. -	Lot	Ft. from N/S 285' FNL	Ft. from E/W 2,335' FEL	Latitud 32.13		ongitude -103.91	9640	County EDDY
	ř	î.		!	T .	ole Location	1				7
UL N	Section 19	Township 25 S	P Range 30 E	Lot	Ft. from N/S 10'FSL	Ft. from E/W 2,449' FWL	Latitud		ongitude -103.92	1433	County EDDY
	13	200			10 1 02	2,449 1 000	J 02.10		100.02		
Dedicated Acres Infill or Defining Well Defining Well API INFILL Order Numbers					Overlapping Spacing U	nit (Y/N)	Consolida	tion Cod	e		
Order Numbers.					Well setbacks are under	r Commo	n Ownership:	⊠ Yes	☐ No		
Kick Off					Point (KOP)						
UL Section Township Range Lot Ft. from N/S					Ft. from E/W	t. from E/W Latitude Longitude Coun 2,274' FWL 32.130431 -103.922061 EDD		County			
F 18 25 S 30 E 2,552' FNL					· ·	32.13	0431	-103.92	2061	EDDY	
First Take UL Section Township Range Lot Ft. from N/S					Ft. from E/W	Latitud	le Lo	ongitude		County	
UL Section Township Range Lot Ft. from N/S K 18 25 S 30 E 2,559' FSL					2,273' FWL	32.12	9863	-103.92	2062	EDDY	
Last Take					Point (LTP) Et from E/W Latitude Longitude County				-		
UL Section N Township 19 Range 30 E Lot 100' FSL					Ft. from E/W 2,449' FWL	Ft. from E/W Latitude Longitude County 2,449' FWL 32.108492 -103.921434 EDDY					
							C 1 El	714:			
Unitized Area or Area of Uniform Interest NMNM105422429 Spacing Unit Type ☐ Horizon					ntal Vertical		Ground Floor I	Elevation	[:] 3,18	2'	
_											
OPEI	RATOR C	ERTIFIC	CATIONS			SURVEYOR CERTIFICATIONS					
OPERATOR CERTIFICATIONS I hereby certify that the information contained herein is true and complete to the best of my knowledge and belief, and that this organization either owns a working interest or unleased mineral interest in the land including the proposed bottom hole location or has a right to drill this well at this location pursuant to a contract with an owner of such a mineral or working interest, or to a voluntary pooling agreement or a compulsory pooling order heretofore entered by the division.					I hereby certify that the well location shown on this plat was plotted from field notes of actual surveys made by me or under my supervision, and that the same is true and correct to the best of my belief. I, TIM C. PAPPAS, NEW MEXICO PROFESSIONAL SURVEYOR NO. 21209, DO HEREBY CERTIFY THAT THIS SURVEY PLAT AND THE ACTUAL SURVEY ON THE GROUND UPON WHICH IT IS BASED WERE PERFORMED BY ME OR UNDER MY DIRECT SUPERVISION; THAT I AM RESPONSIBLE FOR THIS SURVEY, THAT THIS SURVEY MEETS THIS MINIMUM STANDARDS FOR SURVEYING IN, NEW						
agreement or a compulsory pooling order heretofore entered by the division. If this well is a horizontal well, I further certify that this organization has received the consent of at least one lessee or owner of a working interest or unleased mineral interest in each tract (in the target pool or formation) in which any part of the well's completed interval will be located or obtained a compulsory pooling form the division.					MEETS THE MINIMUM STANDARDS FOR SURVEYING IN NEW MEXICO, AND THAT IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.						
San	nantho	e We	is	9/15/2	2025	STATE OF NEW MEXICO N	TIM C. PAPPAS REGISTERED PROFESSIONAL LAND SURVEYOR STATE OF NEW MEXICO NO. 21209				
Signatu	re		I	Date		Signature and Seal of	Profession	onal Surveyor			
Sam	antha Wo	eis				+(1			
Printed	Name					Certificate Number		Date of Surv	vey		
sama Email A		rtnik@	exxonmob	il.com		TIM C. PAPPAS 2	21209	09/09/2	2025		
	Note: No al	lowable wil	l be assigned to	his compl	letion until all interests	have been consolidated o	or a non-	standard unit l	has been	appro	ved by the division.



2205 Walnut Street - Columbus, TX 78934
Ph: 817.349.9800 - Fax: 979.732.5271
TBPE Firm 17957 | TBPLS Firm 10000100
www.fscinc.net
© COPYRIGHT 2025 - ALL RIGHTS RESERVED

DATE: DRAWN BY: CHECKED BY: FIELD CREW:

9-9-2025 LM WL IR PROJECT NO: SCALE: SHEET:

REVISION:


2025060195

1 OF 2

ACREAGE DEDICATION PLATS

This grid represents a standard section. You may superimpose a non-standard section, or a larger area, over this grid. Operators must outline the dedicated acreage in a red box, clearly show the well surface location and bottom hole location, if it is directionally drilled, with the dimensions from the section lines in the cardinal directions. If this is a horizontal wellbore show on this plat the location of the First Take Point and Last Take Point, and the point within the Completed interval (other than the First Take Point or Last Take Point) that is the closest to any outer boundary of the tract.

Surveyors shall use the latest United States government survey or dependent resurvey. Well locations will be in reference to the New Mexico Principal Meridian. If the land is not surveyed, contact the OCD Engineering Bureau. Independent subdivision surveys will not be acceptable.



-	<u></u>	OOKDII	ORDINATE TABLE) LTP (NAD 83 NN			
	IL (NAD 83 NN	IE)				
Y =	413,699.5	N	Y =	403,449.4	N	
X =	669,387.3		X =	668,871.4	E	
LAT. =	32.136663		LAT. =	32.108492	°N	
LONG. =	103.919640	°W	LONG. =	103.921434	°W	
КС	P (NAD 83 NN	IE)	В	HL (NAD 83 NME)	
	411,429.5		Y =	403,359.4	N	
X =	668,646.7	Е	X =	668,871.9	Е	
IAT =	32.130431	°N	IAT =	32.108244	°N	
	103.922061			103.921433	°W	
	P (NAD 83 NM			P1 (NAD 83 NME)	**	
Y =	411,223.1	N	Y =	410,213.4	N	
X =	668,647.1			668,654.1	E	
					°N	
LAT. =	32.129863		LAT. =	32.127087		
	103.922062	°W	LONG. =	103.922052	°W	
	2 (NAD 83 NMI	Ε)	F	P3 (NAD 83 NME)		
Y =	409,872.1	N	Y =	409,528.4	N	
X =	668,676.7	Е		668,741.6	Е	
LAT. =	32.126149	°N	LAT. =	32.125204	°N	
LONG. =	103.921983	°W	LONG. =	103.921778	°W	
P	4 (NAD 83 NMI	Ε)	F	P5 (NAD 83 NME)		
	409,184.9		Y =	408,833.1	N	
X =	668,807.8	Е	X =	668,831.6	Е	
LAT. =	32.124259	°N	LAT. =	32.123291	°N	
LONG. =			LONG. =	103.921496	°W	
	IL (NAD 27 NN			TP (NAD 27 NME		
			Y =	403,391.1		
Y =	413,640.9				N	
X =	628,202.8		X =	627,686.6	E	
LAT. =	32.136538		LAT. =	32.108367	°N	
LONG. =	103.919155			103.920950	°W	
	P (NAD 83 NN		В	HL (NAD 27 NME		
Y =	411,370.9	Ν	Y =	403,301.1	N	
X =	627,462.2	E	X =	627,687.1	Е	
LAT. =	32.130306	°N	LAT. =	32.108119	°N	
LONG. =	103.921576	°W	LONG. =	103.920949	°W	
FT	P (NAD 27 NM	E)	F	P1 (NAD 27 NME)		
Y =	411,164.6			410,154.9	N	
X =	627,462.6	Е	X =	627,469.5	Е	
LAT. =	32.129738		LAT. =		°N	
	103.921577			103.921567	°W	
D'	2 (NAD 27 NMI			P3 (NAD 27 NME)	• • •	
V F	400 913 G		V	400 460 0		
Υ =	409,813.6	N	Υ =	409,469.9 627,557.0	N	
X =	627,492.1	Е	X =	627,557.0	Е	
LAI.=	32.126024	°N	LAT. =		°N	
LONG. =	103.921499	°W	LONG. =		°W	
P	4 (NAD 27 NMI	Ε)	F	P5 (NAD 27 NME)		
Y =	409,126.4	N		408,774.6	N	
X =	627,623.2	Е	X =	627,647.0	Е	
LAT. =	32.124134	°N	LAT. =		°N	
LONG. =	103.921084	°W	LONG. =	103.921011	°W	
	#1 (NAD 83 N	ME)		P #1 (NAD 27 NM	E)	
Y =	412,679.7	N N	Y =	412,621.1	_, N	
X =	669,054.6	Е	X =	627,870.1	Е	
LAT. =	32.133863	°N	LAT. =	32.133738	°N	
LONG. =	103.920728	°W	LONG. =	103.920243	°W	
	#2 (NAD 83 N			P #2 (NAD 27 NM		
Y=	411,323.1	N N	Y=	411,264.5	N N	
X =	668,646.9	E	X =	627,462.4	E	
LAT. =	32.130138	°N	LAT. =	32.130013	°N	
LONG. =	103.922062	°W	LONG. =	103.921577	°W	
PPP	#3 (NAD 83 N	ME)		P #3 (NAD 27 NM	E)	
	408,665.2	Ν	Y =	408,606.7	N	
Y =						
	668,832.0	Е	X =	627,647.4	E	
Y =		e °N	X = LAT. =	627,647.4 32.122705	°N	

C	ORNER COO	RDII	NATES (N	NAD83 NME)	
A - Y =	411,318.8	Ν	A - X =	667,717.9	Е
B - Y =	411,325.0	N	B - X =	669,062.2	Е
C - Y =	408,659.4	N	C - X =	667,733.0	Е
D - Y =	408,666.5	Ν	D - X =	669,077.2	Е
E - Y =	406,001.2	Ν	E - X =	667,747.8	Е
F - Y =	406,009.2	N	F - X =	669,089.3	Е
G - Y =	403,343.1	Ν	G - X =	667,762.3	Е
H - Y =	403,350.7	Ν	H - X =	669,101.5	Е
C	ORNER COO	RDI	NATES (1	NAD27 NME)	
A - Y =	411,260.5	N	A - X =	626,533.3	Е
B - Y =	411,266.7	Ν	B - X =	627,877.5	Е
C - Y =	408,601.2	N	C - X =	626,548.3	Е
D - Y =	408,608.3	Ν	D - X =	627,892.5	Е
E - Y =	405,943.0	N	E - X =	626,563.0	Е
F-Y=	405,951.0	N	F - X =	627,904.5	Е
G - Y =	403,285.0	Ν	G - X =	626,577.4	Е
H - Y =	403,292.6	N	H - X =	627,916.6	Е

	LINE TABL	<u>E</u>
LINE	AZIMUTH	LENGTH
L1	198° 04'11"	2,387.73'
L2	179° 52'44"	206.37'
L3	179° 36'06"	1,009.78'
L4	176° 13'30"	342.05'
L5	169° 18'05"	349.77'
L6	169 05'52"	349.77'
L7	176° 07'17"	352.61'
L8	179° 34'40"	5,473.86'



2205 Walnut Street - Columbus, TX 78934
Ph: 817.349.9800 - Fax: 979.732.5271
TBPE Firm 17957 | TBPL5 Firm 10000100
www.fscinc.net
© COPYRIGHT 2025 - ALL BROHTS RESERVED

 DATE:
 9-9-2025
 PROJECT NO:
 2025060195

 DRAWN BY:
 LM
 SCALE:
 1" = 2,000'

 CHECKED BY:
 WL
 SHEET:
 2 OF 2

 FIELD CREW:
 IR
 REVISION:
 1

DRILLING PLAN: BLM COMPLIANCE (Supplement to BLM 3160-3)

ExxonMobil Poker Lake Unit 18-30 BD 202H

Projected TD: 17513' MD / 9263' TVD SHL: 285' FNL & 2335' FEL , Section 18, T25S, R30E BHL: 10' FSL & 2449' FWL , Section 19, T25S, R30E Eddy County, NM

1. Geologic Name of Surface Formation A. Quaternary

2. Estimated Tops of Geological Markers & Depths of Anticipated Fresh Water, Oil or Gas

Well Depth (TVD)	Water/Oil/Gas
767'	Water
1044'	Water
3235'	Water
3610'	Water
4503'	Water/Oil/Gas
7092'	Water/Oil/Gas
7334'	Water/Oil/Gas
7436'	Water/Oil/Gas
8243'	Water/Oil/Gas
8581'	Water/Oil/Gas
8722'	Water/Oil/Gas
8862'	Water/Oil/Gas
9262'	Water/Oil/Gas
	Depth (TVD) 767' 1044' 3235' 3610' 4503' 7092' 7334' 7436' 8243' 8581' 8722' 8862'

	Summ	

* Deepest Expected Groundwater Depth: 40' (per NM State Engineers Office).

No other formations are expected to give up oil, gas or fresh water in measurable quantities. Surface fresh water sands will be protected by setting 9-5/8" inch casing at 1019' and circulating cement back to surface.

3. Primary Casing Design Primary Design:

Hole Size (in.)	MD	Casing TVD	OD Csg	Weight	Grade	Collar	New/Used	SF Burst	SF Collapse	SF Tension
12.25"	0' – 1019'	1019'	9-5/8"	40	J55	BTC	New	12.64	11.65	5.18
8.75"	0' - 4000'	3844'	7-5/8"	29.7	P110-ICY	Tenaris Wedge 511	New	6.04	8.84	3.50
8.75"	4000' - 8868'	8395'	7-5/8"	29.7	L80-IC	Tenaris Wedge 511	New	3.35	6.20	2.53
6.75"	0' – 8768'	8296'	5-1/2"	20	P110-ICY	Tenaris Wedge 441	New	1.18	3.42	3.03
6.75"	8768' – 17513'	9263'	5-1/2"	20	P110-ICY	Tenaris Wedge 441	New	1.18	3.07	3.03

Section 3 Summary:

XTO will keep casing fluid filled to meet BLM's collapse requirement.

The planned kick off point is located at: 9018' MD / 8547' TVD.

Wellhead:
A multi-bowl wellhead system will be utilized. The well design chosen is: 3-String Slim Non-Potash

Wellhead will be installed by manufacturer's representatives.

Manufacturer will monitor welding process to ensure appropriate temperature of seal.

4. Cement Program

Primary Cementing								
Hole Section	Slurry Type	No. Sacks	Density (ppg)	Yield (ft3/sack)	TOC (ft)	Casing Setting Depth (MD)	Excess (%)	Slurry Description
Surface 1	Lead	213	12.4	2.11	0	1,019	100%	Surface 1 Class C Lead Cement
Surface 1	Tail	141	14.8	1.33	719	1,019	100%	Surface 1 Class C Tail Cement
ntermediate 1	Lead							
Intermediate 1	Tail	166	14.8	1.45	7092	8,868	35%	Intermediate 1 Class C Tail Cement
Production 1	Lead							
Production 1	Tail	634	13.2	1.44	8368	17,513	25%	Production 1 Class C Tail Cement
			Brea	denhead Ceme	nting			
Casing	Slurry Type	No. Sacks	Density (ppg)	Yield (ft3/sack)	Cement	ted Interval	Excess (%)	Slurry Description
ntermediate 1	Bradenhead Squeeze	663	14.8	1.45	0 -	- 7092'	35%	Intermediate Class C Bradenhead Squeeze Cement

Section 4 Summary:

*Bradenhead Squeeze 2nd Stage Offline

5. Pressure Control Equipment

Section	5	Summarv:

Section 5 Summary:
Once the permanent WH is installed on the casing, the blow out preventer equipment (BOP) will consist of a minimum 5M Hydril and a minimum 10M triple Ram BOP.
All BOP testing will be done by an independent service company. Operator will Test as per 43CFR-3172.
No break testing will be done if intermediate casing point penetrates the Wolfcamp
Requested Variances
4A) Offline Cementing Variance XOM requests the option to perform offline cement and bradenhead jobs (if needed) SURFACE, INTERMEDIATE, and PRODUCTION casing strings where batch drillin is approved. XOM will ensure well is static with no pressure on the csg annulus, as with all other casing strings where batch drilling operations occur before moving of the rig. Offline cement operations will then be conducted after the rig is moved off the current well to the next well in the batch sequence. The TA cap will also be installed when applicable per wellhead manufacturer's procedure and pressure inside the casing will be monitored via the valve on the TA cap as per standard batch drilling ops.
5A) Break Test Variance A break testing variance is requested to ONLY test broken pressure seals on the BOP equipment when moving from wellhead to wellhead for the intermediate hole sections which is in compliance with API Standard 53. The maximum anticipated surface pressure is less than 4800psi and the deepest intermediate casing point does not penetrate the Wolfcamp Formation.
5B) Flex Hose Variance A variance is requested to allow use of a flex hose as the choke line from the BOP to the Choke Manifold. If this hose is used, a copy of the manufacturer's certification and pressure test chart will be kept on the rig. Attached is an example of a certification and pressure test chart. The manufacturer does not require anchors.
8A) Open Hole Logging Variance Open hole logging will not be done on this well.
10A) Spudder Rig Variance XOM requests the option to utilize a spudder rig (Atlas Copco RD20 or Equivalent) to set and cement surface casing.
10B) Batch Drilling Variance XOM requests a variance to be able to batch drill this well. In doing so, XOM will set casing and ensure that the well is cemented properly (unless approval is given for offline cementing) and the well is static. XOM will contact the BLM to skid the rig to drill the remaining wells on the pad. Once surface and intermediate strings are all completed, XOM will begin drilling the production hole on each of the wells.

6. Proposed Mud Circulation System

INTERVAL	Hole Size	Mud Type	MW Viscosity Fluid Loss (ppq) (sec/qt) (cc)			Comments		
0' – 1019'	12.25"	FW/Native	8.3 - 8.7	35-40	NC	Fresh Water or Native Water		
1019' – 8868'	8.75"	BDE/OBM or FW/Brine	9.5 - 10	30-32	NC	Fluid type will be based upon on well conditions. A fully saturated system will be used across the salt interval.		
8868' – 17513'	6.75"	ОВМ	9 - 9.6	50-60	NC - 20	OBM or Cut Brine depending on Well Conditions		

Section 6 Summary:

The necessary mud products for weight addition and fluid loss control will be on location at all times.

Pump viscous sweeps as needed for hole cleaning. Pump speed will be recorded on a daily drilling report after mudding up. An EDR (Electronic Drilling Recorder) will be used to detect changes in loss or gain of mud volume. A mud test will be performed every 24 hours to determine: density, viscosity, strength, filtration and pH as necessary. Use available solids controls equipment to help keep mud weight down after mud up. Rig up solids control equipment to operate as a closed loop system.

7. Auxiliary Well Control and Monitoring Equipment

Section 7 Summary:

A Kelly cock will be in the drill string at all times.

A full opening drill pipe stabbing valve having appropriate connections will be on the rig floor at all times.

H2S monitors will be on location when drilling below the 9-5/8" casing.

8. Logging, Coring and Testing Program

Section 8 Summary:

Open hole logging will not be done on this well.

9. Abnormal Pressures and Temperatures / Potential Hazards

Section 9 Summary:

The estimated bottom hole temperature of 158F to 178F. No H2S is expected but monitors will be in place to detect any H2S occurrences. Should these circumstances be encountered the operator and drilling contractor are prepared to take all necessary steps to ensure safety of all personnel and environment. Lost circulation is possible throughout the well.

10. Anticipated Starting Date and Duration of Operations

Section 10 Summary:


Anticipated spud date will be after BLM approval. Move in operations and drilling is expected to take 40 days.




Site: Poker Lake Unit 18-30 BD

Well: Poker Lake Unit 18-30 BD 202H

Wellbore: OH Design: Plan 0





TVDPath MDPath Formation 768.5 768.5 Rustler 1044.8 1044.8 Salado 3236.4 3334.7 Base of Salt 3611.0 3744.8 Delaware 4504.0 4722.3 Cherry Canyon 6004.6 6364.9 Brushy Canyon 7093.1 7550.0 Basal Brushy Canyon 7334.5 7800.6 Bone Spring Lm. 7436.9 7905.2 Avalon 7812.0 8283.5 Lower Avalon 8243.8 8715.4 1st Bone Spring Sand 8581.8 9053.4 2nd Bone Spring Shale 8722.8 9196.2 2nd Bone Spring Lime 8862.6 9345.5 2nd Bone Spring Sand 9263.0 10143.4 2rd Bone Spring Sand Lower Landing

ROC

Long Lead - PLU 18-30 BD Poker Lake Unit 18-30 BD Poker Lake Unit 18-30 BD 202H

OH

Plan: Plan 0

Standard Planning Report

11 September, 2025

EDM 5000.18 Single User Db Database:

Company: Project:

Site:

Design:

Long Lead - PLU 18-30 BD Poker Lake Unit 18-30 BD

Well: Wellbore: ОН

Poker Lake Unit 18-30 BD 202H

Plan 0

Local Co-ordinate Reference:

TVD Reference: MD Reference: North Reference:

Survey Calculation Method:

Well Poker Lake Unit 18-30 BD 202H

RKB30' @ 3212.0usft RKB30' @ 3212.0usft

Grid

Minimum Curvature

Project Long Lead - PLU 18-30 BD

Map System: Geo Datum:

Map Zone:

US State Plane 1927 (Exact solution) NAD 1927 (NADCON CONUS)

New Mexico East 3001

System Datum:

Mean Sea Level

Poker Lake Unit 18-30 BD Site

Site Position: From:

Мар

Northing: Easting:

413,640.80 usft 628,142.70 usft Latitude: Longitude:

32° 8' 11.538 N 103° 55' 9.659 W

Position Uncertainty: 0.0 usft Slot Radius: 13-3/16 "

Well Poker Lake Unit 18-30 BD 202H

Well Position +N/-S +E/-W

Position Uncertainty

0.0 usft 0.0 usft 2.0 usft

Northing: Easting:

413,640.90 usft 628,202.80 usft Wellhead Elevation: usft Latitude: Longitude: Ground Level:

32° 8' 11.536 N 103° 55' 8.960 W

3,182.0 usft

0.22 **Grid Convergence:**

ОН Wellbore

Magnetics	Model Name	Sample Date	Declination (°)	Dip Angle (°)	Field Strength (nT)
	IGRF2020	6/4/2025	6.23	59.64	46,995.98371296

Plan 0 Design

Audit Notes:

Version:

Vertical Section:

Phase: Depth From (TVD)

(usft)

0.0

PLAN +N/-S

(usft)

0.0

Tie On Depth: +E/-W (usft)

0.0

0.0 Direction

(°) 179.70

Plan Survey Tool Program

Date 9/11/2025

Depth From (usft) 0.0 Depth To (usft) 17,513.4

Survey (Wellbore)

Plan 0 (OH)

Tool Name

Remarks

XOMR2_OWSG MWD+IFR1+ OWSG MWD + IFR1 + Multi-St

Database: EDM 5000.18 Single User Db

Company: ROC

 Project:
 Long Lead - PLU 18-30 BD

 Site:
 Poker Lake Unit 18-30 BD

 Well:
 Poker Lake Unit 18-30 BD 202H

Wellbore: OH
Design: Plan 0

Local Co-ordinate Reference:

TVD Reference: MD Reference: North Reference:

Survey Calculation Method:

Well Poker Lake Unit 18-30 BD 202H

RKB30' @ 3212.0usft RKB30' @ 3212.0usft

Grid

Plan Sections										
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)	TFO (°)	Target
0.0	0.00	0.00	0.0	0.0	0.0	0.00	0.00	0.00	0.00	
1,400.0	0.00	0.00	1,400.0	0.0	0.0	0.00	0.00	0.00	0.00	
2,600.0	24.00	198.10	2,565.2	-235.4	-76.9	2.00	2.00	0.00	198.10	
7,250.0	24.00	198.10	6,813.2	-2,033.2	-664.5	0.00	0.00	0.00	0.00	
8,450.0	0.00	0.00	7,978.4	-2,268.6	-741.5	2.00	-2.00	0.00	180.00	
9,018.4	0.00	0.00	8,546.8	-2,268.6	-741.5	0.00	0.00	0.00	0.00	
10,143.4	90.00	179.65	9,263.0	-2,984.8	-737.1	8.00	8.00	0.00	179.65	
10,643.4	90.00	179.65	9,263.0	-3,484.7	-734.1	0.00	0.00	0.00	0.00	
11,340.9	90.00	165.70	9,263.0	-4,174.8	-645.3	2.00	0.00	-2.00	-90.00	
12,034.4	90.00	179.57	9,263.0	-4,860.9	-556.7	2.00	0.00	2.00	90.00	
17,423.4	90.00	179.57	9,263.0	-10,249.8	-516.2	0.00	0.00	0.00	0.00	LTP PLU 18-30 BD 20
17,513.4	90.00	179.57	9,263.0	-10,339.8	-515.5	0.00	0.00	0.00	0.00	BHL PLU 18-30 BD 2

Database: EDM 5000.18 Single User Db

Company: ROC

 Project:
 Long Lead - PLU 18-30 BD

 Site:
 Poker Lake Unit 18-30 BD

 Well:
 Poker Lake Unit 18-30 BD 202H

Wellbore: OH
Design: Plan 0

Local Co-ordinate Reference:

TVD Reference: MD Reference: North Reference:

Survey Calculation Method:

Well Poker Lake Unit 18-30 BD 202H

RKB30' @ 3212.0usft RKB30' @ 3212.0usft

Grid

lanned Survey									
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
0.0	0.00	0.00	0.0	0.0	0.0	0.0	0.00	0.00	0.00
100.0	0.00	0.00	100.0	0.0	0.0	0.0	0.00	0.00	0.00
200.0	0.00	0.00	200.0	0.0	0.0	0.0	0.00	0.00	0.00
300.0 400.0	0.00	0.00	300.0	0.0	0.0	0.0	0.00	0.00	0.00
	0.00	0.00	400.0	0.0	0.0	0.0	0.00	0.00	0.00
500.0	0.00	0.00	500.0	0.0	0.0	0.0	0.00	0.00	0.00
600.0	0.00	0.00	600.0	0.0	0.0	0.0	0.00	0.00	0.00
700.0	0.00	0.00	700.0	0.0	0.0	0.0	0.00	0.00	0.00
800.0	0.00	0.00	800.0	0.0	0.0	0.0	0.00	0.00	0.00
900.0	0.00	0.00	900.0	0.0	0.0	0.0	0.00	0.00	0.00
1,000.0	0.00	0.00	1,000.0	0.0	0.0	0.0	0.00	0.00	0.00
1,100.0	0.00	0.00	1,100.0	0.0	0.0	0.0	0.00	0.00	0.00
1,200.0	0.00	0.00	1,200.0	0.0	0.0	0.0	0.00	0.00	0.00
1,300.0	0.00	0.00	1,300.0	0.0	0.0	0.0	0.00	0.00	0.00
1,400.0	0.00	0.00	1,400.0	0.0	0.0	0.0	0.00	0.00	0.00
1,500.0	2.00	198.10	1,500.0	-1.7	-0.5	1.7	2.00	2.00	0.00
1,600.0	4.00	198.10	1,599.8	-6.6	-2.2	6.6	2.00	2.00	0.00
1,700.0	6.00	198.10	1,699.5	-14.9	-4.9	14.9	2.00	2.00	0.00
1,800.0	8.00	198.10	1,798.7	-26.5	-8.7	26.5	2.00	2.00	0.00
1,900.0	10.00	198.10	1,897.5	-41.4	-13.5	41.3	2.00	2.00	0.00
2,000.0	12.00	198.10	1,995.6	-59.5	-19.4	59.4	2.00	2.00	0.00
2,100.0	14.00	198.10	2,093.1	-80.9	-26.4	80.7	2.00	2.00	0.00
2,200.0	16.00	198.10	2,189.6	-105.5	-34.5	105.3	2.00	2.00	0.00
2,300.0	18.00	198.10	2,285.3	-133.3	-43.6	133.0	2.00	2.00	0.00
2,400.0	20.00	198.10	2,379.8	-164.2	-53.7	163.9	2.00	2.00	0.00
2,500.0 2,600.0	22.00 24.00	198.10 198.10	2,473.2 2,565.2	-198.3 -235.4	-64.8 -76.9	197.9 235.0	2.00 2.00	2.00 2.00	0.00 0.00
2,700.0	24.00	198.10	2,565.2	-235.4 -274.1	-76.9 -89.6	235.0 273.6	0.00	0.00	0.00
2,800.0	24.00	198.10	2,747.9	-312.7	-102.2	312.2	0.00	0.00	0.00
2,900.0	24.00	198.10	2,839.3	-351.4	-114.9	350.8	0.00	0.00	0.00
3,000.0	24.00	198.10	2,930.6	-390.1	-127.5	389.4	0.00	0.00	0.00
3,100.0	24.00	198.10	3,022.0	-428.7	-140.1	428.0	0.00	0.00	0.00
3,200.0	24.00	198.10	3,113.3	-467.4	-152.8	466.6	0.00	0.00	0.00
3,300.0	24.00	198.10	3,204.7	-506.0	-165.4	505.2	0.00	0.00	0.00
3,400.0	24.00	198.10	3,296.1	-544.7	-178.0	543.8	0.00	0.00	0.00
3,500.0	24.00	198.10	3,387.4	-583.4	-190.7	582.4	0.00	0.00	0.00
3,600.0	24.00	198.10	3,478.8	-622.0	-203.3	621.0	0.00	0.00	0.00
3,700.0	24.00	198.10	3,570.1	-660.7	-215.9	659.5	0.00	0.00	0.00
3,800.0	24.00	198.10	3,661.5	-699.3	-228.6	698.1	0.00	0.00	0.00
3,900.0	24.00	198.10	3,752.8	-738.0	-241.2	736.7	0.00	0.00	0.00
4,000.0	24.00	198.10	3,844.2	-776.7	-253.9	775.3	0.00	0.00	0.00
4,100.0	24.00	198.10	3,935.5	-815.3	-266.5	813.9	0.00	0.00	0.00
4,200.0	24.00	198.10	4,026.9	-854.0	-279.1	852.5	0.00	0.00	0.00
4,300.0	24.00	198.10	4,118.2	-892.7	-291.8	891.1	0.00	0.00	0.00
4,400.0	24.00	198.10	4,209.6	-931.3	-304.4	929.7	0.00	0.00	0.00
4,500.0	24.00	198.10	4,301.0	-970.0	-317.0	968.3	0.00	0.00	0.00
4,600.0	24.00	198.10	4,392.3	-1,008.6	-329.7	1,006.9	0.00	0.00	0.00
4,700.0	24.00	198.10	4,483.7	-1,047.3	-342.3	1,045.5	0.00	0.00	0.00
4,800.0	24.00	198.10	4,575.0	-1,086.0	-354.9	1,084.1	0.00	0.00	0.00
4,900.0	24.00	198.10	4,666.4	-1,124.6	-367.6	1,122.7	0.00	0.00	0.00
5,000.0	24.00				-380.2	1,161.3	0.00	0.00	0.00
5,000.0 5,100.0	24.00 24.00	198.10 198.10	4,757.7 4,849.1	-1,163.3 -1,201.9	-380.2 -392.9	1,161.3	0.00	0.00	0.00
5,100.0	24.00	198.10	4,049.1 4,940.4	-1,201.9 -1,240.6	-392.9 -405.5	1,199.9	0.00	0.00	0.00
5,200.0	24.00	198.10	5,031.8	-1,240.0	-403.3 -418.1	1,230.3	0.00	0.00	0.00

Database: Company: EDM 5000.18 Single User Db

ROC

Project: Long Lead - PLU 18-30 BD
Site: Poker Lake Unit 18-30 BD
Well: Poker Lake Unit 18-30 BD 202H

Wellbore: OH
Design: Plan 0

Local Co-ordinate Reference:

TVD Reference: MD Reference: North Reference:

Survey Calculation Method:

Well Poker Lake Unit 18-30 BD 202H

RKB30' @ 3212.0usft RKB30' @ 3212.0usft

Grid

Planned Survey									
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
5,400.0	24.00	198.10	5,123.1	-1,317.9	-430.8	1,315.7	0.00	0.00	0.00
5,500.0	24.00	198.10	5,214.5	-1,356.6	-443.4	1,354.2	0.00	0.00	0.00
5,600.0	24.00	198.10	5,305.9	-1,395.2	-456.0	1,392.8	0.00	0.00	0.00
5,700.0	24.00	198.10	5,397.2	-1,433.9	-468.7	1,431.4	0.00	0.00	0.00
5,800.0	24.00	198.10	5,488.6	-1,472.6	-481.3	1,470.0	0.00	0.00	0.00
5,900.0	24.00	198.10	5,579.9	-1,511.2	-493.9	1,508.6	0.00	0.00	0.00
6,000.0	24.00	198.10	5,671.3	-1,549.9	-506.6	1,547.2	0.00	0.00	0.00
6,100.0	24.00	198.10	5,762.6	-1,588.6	-519.2	1,585.8	0.00	0.00	0.00
6,200.0	24.00	198.10	5,854.0	-1,627.2	-531.9	1,624.4	0.00	0.00	0.00
6,300.0	24.00	198.10	5,945.3	-1,665.9	-544.5	1,663.0	0.00	0.00	0.00
6,400.0	24.00	198.10	6,036.7	-1,704.5	-557.1	1,701.6	0.00	0.00	0.00
6,500.0	24.00	198.10	6,128.0	-1,743.2	-569.8	1,740.2	0.00	0.00	0.00
6,600.0	24.00	198.10	6,219.4	-1,781.9	-582.4	1,778.8	0.00	0.00	0.00
6,700.0	24.00	198.10	6,310.8	-1,820.5	-595.0	1,817.4	0.00	0.00	0.00
6,800.0	24.00	198.10	6,402.1	-1,859.2	-607.7	1,856.0	0.00	0.00	0.00
6,900.0	24.00	198.10	6,493.5	-1,897.8	-620.3	1,894.6	0.00	0.00	0.00
7,000.0	24.00	198.10	6,584.8	-1,936.5	-632.9	1,933.2	0.00	0.00	0.00
7,100.0	24.00	198.10	6,676.2	-1,975.2	-645.6	1,971.8	0.00	0.00	0.00
7,200.0	24.00	198.10	6,767.5	-2,013.8	-658.2	2,010.3	0.00	0.00	0.00
7,250.0	24.00	198.10	6,813.2	-2,033.2	-664.5	2,029.6	0.00	0.00	0.00
7,300.0	23.00	198.10	6,859.1	-2,052.1	-670.7	2,048.6	2.00	-2.00	0.00
7,400.0	21.00	198.10	6,951.8	-2,087.7	-682.4	2,084.1	2.00	-2.00	0.00
7,500.0	19.00	198.10	7,045.7	-2,120.2	-693.0	2,116.6	2.00	-2.00	0.00
7,600.0	17.00	198.10	7,140.8	-2,149.6	-702.6	2,145.9	2.00	-2.00	0.00
7,700.0	15.00	198.10	7,237.0	-2,175.8	-711.2	2,172.0	2.00	-2.00	0.00
7,800.0	13.00	198.10	7,334.0	-2,198.8	-718.7	2,195.0	2.00	-2.00	0.00
7,900.0	11.00	198.10	7,431.8	-2,218.5	-725.1	2,214.7	2.00	-2.00	0.00
8,000.0	9.00	198.10	7,530.3	-2,235.0	-730.5	2,231.2	2.00	-2.00	0.00
8,100.0	7.00	198.10	7,629.3	-2,248.3	-734.8	2,244.4	2.00	-2.00	0.00
8,200.0	5.00	198.10	7,728.7	-2,258.2	-738.1	2,254.3	2.00	-2.00	0.00
8,300.0	3.00	198.10	7,828.5	-2,264.8	-740.3	2,260.9	2.00	-2.00	0.00
8,400.0	1.00	198.10	7,928.4	-2,268.2	-741.3	2,264.2	2.00	-2.00	0.00
8,450.0	0.00	0.00	7,978.4	-2,268.6	-741.5	2,264.7	2.00	-2.00	0.00
8,500.0	0.00	0.00	8,028.4	-2,268.6	-741.5	2,264.7	0.00	0.00	0.00
8,600.0	0.00	0.00	8,128.4	-2,268.6	-741.5	2,264.7	0.00	0.00	0.00
8,700.0	0.00	0.00	8,228.4	-2,268.6	-741.5	2,264.7	0.00	0.00	0.00
8,800.0	0.00	0.00	8,328.4	-2,268.6	-741.5	2,264.7	0.00	0.00	0.00
8,900.0	0.00	0.00	8,428.4	-2,268.6	-741.5	2,264.7	0.00	0.00	0.00
9,000.0	0.00	0.00	8,528.4	-2,268.6	-741.5	2,264.7	0.00	0.00	0.00
9,018.4	0.00	0.00	8,546.8	-2,268.6	-741.5	2,264.7	0.00	0.00	0.00
9,100.0	6.53	179.65	8,628.2	-2,273.2	-741.5	2,269.3	8.00	8.00	0.00
9,200.0	14.53	179.65	8,726.5	-2,291.5	-741.3	2,287.6	8.00	8.00	0.00
9,300.0	22.53	179.65	8,821.2	-2,323.2	-741.1	2,319.3	8.00	8.00	0.00
9,400.0	30.53	179.65	8,910.6	-2,367.9	-740.9	2,363.9	8.00	8.00	0.00
9,500.0	38.53	179.65	8,992.9	-2,424.5	-740.5	2,420.6	8.00	8.00	0.00
9,600.0	46.53	179.65	9,066.6	-2,492.0	-740.1	2,488.1	8.00	8.00	0.00
9,700.0	54.53	179.65	9,130.1	-2,569.2	-739.6	2,565.3	8.00	8.00	0.00
9,800.0	62.53	179.65	9,182.2	-2,654.4	-739.1	2,650.5	8.00	8.00	0.00
9,900.0	70.53	179.65	9,222.0	-2,746.0	-738.6	2,742.1	8.00	8.00	0.00
10,000.0	78.53	179.65	9,248.7	-2,842.3	-738.0	2,838.4	8.00	8.00	0.00
10,100.0	86.53	179.65	9,261.7	-2,941.4	-737.4	2,937.5	8.00	8.00	0.00
10,143.4	90.00	179.65	9,263.0	-2,984.8	-737.1	2,980.9	8.00	8.00	0.00
10,200.0	90.00	179.65	9,263.0	-3,041.4	-736.8	3,037.5	0.00	0.00	0.00
10,300.0	90.00	179.65	9,263.0	-3,141.4	-736.2	3,137.5	0.00	0.00	0.00

Database: Company: EDM 5000.18 Single User Db

ROC

Project: Long Lead - PLU 18-30 BD
Site: Poker Lake Unit 18-30 BD
Well: Poker Lake Unit 18-30 BD 202H

Wellbore: OH
Design: Plan 0

Local Co-ordinate Reference:

TVD Reference:
MD Reference:
North Reference:

Survey Calculation Method:

Well Poker Lake Unit 18-30 BD 202H

RKB30' @ 3212.0usft RKB30' @ 3212.0usft

Grid

200.g									
Planned Survey									
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
10,400.0 10,500.0	90.00 90.00	179.65 179.65	9,263.0 9,263.0	-3,241.4 -3,341.4	-735.5 -734.9	3,237.5 3,337.5	0.00 0.00	0.00 0.00	0.00 0.00
10,600.0	90.00	179.65	9,263.0	-3,441.4	-734.3	3,437.5	0.00	0.00	0.00
10,643.4	90.00	179.65	9,263.0	-3,484.7	-734.1	3,480.9	0.00	0.00	0.00
10,700.0 10,800.0	90.00 90.00	178.52 176.52	9,263.0 9,263.0	-3,541.4 -3,641.3	-733.1 -728.8	3,537.5 3,637.4	2.00 2.00	0.00 0.00	-2.00 -2.00
10,900.0	90.00	174.52	9,263.0	-3,740.9	-721.0	3,737.1	2.00	0.00	-2.00
11,000.0	90.00	172.52	9,263.0	-3,840.3	-709.7	3,836.5	2.00	0.00	-2.00
11,100.0	90.00	170.52	9,263.0	-3,939.2	-695.0	3,935.5	2.00	0.00	-2.00
11,200.0	90.00	168.52	9,263.0	-4,037.5	-676.8	4,033.9	2.00	0.00	-2.00
11,300.0	90.00	166.52	9,263.0	-4,135.2	-655.2	4,131.7	2.00	0.00	-2.00
11,340.9	90.00	165.70	9,263.0	-4,174.8	-645.3	4,171.4	2.00	0.00	-2.00
11,400.0	90.00	166.88	9,263.0	-4,232.3	-631.3	4,228.9	2.00	0.00	2.00
11,500.0	90.00	168.88	9,263.0	-4,330.0	-610.3	4,326.8	2.00	0.00	2.00
11,600.0	90.00	170.88	9,263.0	-4,428.5	-592.8	4,425.3	2.00	0.00	2.00
11,700.0 11,800.0	90.00 90.00	172.88 174.88	9,263.0 9,263.0	-4,527.5 -4,626.9	-578.7 -568.0	4,524.4 4,623.9	2.00 2.00	0.00 0.00	2.00 2.00
11,900.0	90.00	176.88	9,263.0	-4,726.6	-560.8	4,723.6	2.00	0.00	2.00
12,000.0	90.00	178.88	9,263.0	-4,826.6	-557.1	4,823.6	2.00	0.00	2.00
12,034.4	90.00	179.57	9,263.0	-4,860.9	-556.7	4,858.0	2.00	0.00	2.00
12,100.0	90.00	179.57	9,263.0	-4,926.6	-556.2	4,923.6	0.00	0.00	0.00
12,200.0	90.00	179.57	9,263.0	-5,026.6	-555.4	5,023.6	0.00	0.00	0.00
12,300.0	90.00	179.57	9,263.0	-5,126.6	-554.7	5,123.6	0.00	0.00	0.00
12,400.0	90.00	179.57	9,263.0	-5,226.6	-553.9	5,223.6	0.00	0.00	0.00
12,500.0	90.00	179.57	9,263.0	-5,326.5	-553.2	5,323.6	0.00	0.00	0.00
12,600.0	90.00	179.57	9,263.0	-5,426.5	-552.4	5,423.6	0.00	0.00	0.00
12,700.0	90.00	179.57	9,263.0	-5,526.5	-551.7	5,523.6	0.00	0.00	0.00
12,800.0	90.00	179.57	9,263.0	-5,626.5	-550.9	5,623.6	0.00	0.00	0.00
12,900.0	90.00	179.57	9,263.0	-5,726.5	-550.2	5,723.6	0.00	0.00	0.00
13,000.0	90.00	179.57 179.57	9,263.0	-5,826.5	-549.4	5,823.6	0.00	0.00	0.00
13,100.0 13,200.0	90.00 90.00	179.57	9,263.0 9,263.0	-5,926.5 -6,026.5	-548.7 -547.9	5,923.6 6,023.6	0.00 0.00	0.00 0.00	0.00 0.00
13,300.0	90.00	179.57	9,263.0	-6,126.5	-547.2	6,123.6	0.00	0.00	0.00
13,400.0	90.00	179.57	9,263.0	-6,226.5	-546.4	6,223.6	0.00	0.00	0.00
13,500.0	90.00	179.57	9,263.0	-6,326.5	-545.7	6,323.6	0.00	0.00	0.00
13,600.0	90.00	179.57	9,263.0	-6,426.5	-544.9	6,423.6	0.00	0.00	0.00
13,700.0	90.00	179.57	9,263.0	-6,526.5	-544.2	6,523.6	0.00	0.00	0.00
13,800.0	90.00	179.57	9,263.0	-6,626.5	-543.4	6,623.6	0.00	0.00	0.00
13,900.0	90.00	179.57	9,263.0	-6,726.5	-542.7	6,723.6	0.00	0.00	0.00
14,000.0	90.00	179.57	9,263.0	-6,826.5	-541.9	6,823.6	0.00	0.00	0.00
14,100.0	90.00	179.57	9,263.0	-6,926.5	-541.2	6,923.6	0.00	0.00	0.00
14,200.0	90.00	179.57	9,263.0	-7,026.5	-540.4	7,023.6	0.00	0.00	0.00
14,300.0	90.00	179.57	9,263.0	-7,126.5	-539.7	7,123.6	0.00	0.00	0.00
14,400.0	90.00	179.57	9,263.0	-7,226.5	-538.9	7,223.6	0.00	0.00	0.00
14,500.0	90.00	179.57	9,263.0	-7,326.5	-538.1	7,323.6	0.00	0.00	0.00
14,600.0 14,700.0	90.00 90.00	179.57 179.57	9,263.0 9,263.0	-7,426.5 -7,526.5	-537.4 -536.6	7,423.6 7,523.6	0.00 0.00	0.00 0.00	0.00 0.00
14,800.0	90.00	179.57	9.263.0	-7,626.5	-535.9	7,623.6	0.00	0.00	0.00
14,900.0	90.00	179.57	9,263.0	-7,726.5	-535.1	7,723.6	0.00	0.00	0.00
15,000.0	90.00	179.57	9,263.0	-7,826.5	-534.4	7,823.6	0.00	0.00	0.00
15,100.0	90.00	179.57	9,263.0	-7,926.5	-533.6	7,923.6	0.00	0.00	0.00
15,200.0	90.00	179.57	9,263.0	-8,026.5	-532.9	8,023.6	0.00	0.00	0.00
15,300.0	90.00	179.57	9,263.0	-8,126.5	-532.1	8,123.6	0.00	0.00	0.00
15,400.0	90.00	179.57	9,263.0	-8,226.5	-531.4	8,223.6	0.00	0.00	0.00

Database: Company:

Project:

Site:

Well:

EDM 5000.18 Single User Db

ROC

Long Lead - PLU 18-30 BD Poker Lake Unit 18-30 BD

Poker Lake Unit 18-30 BD 202H

Wellbore: OH
Design: Plan 0

Local Co-ordinate Reference:

TVD Reference: MD Reference: North Reference:

Survey Calculation Method:

Well Poker Lake Unit 18-30 BD 202H

RKB30' @ 3212.0usft RKB30' @ 3212.0usft

Grid

Planned Survey									
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
15,500.0	90.00	179.57	9,263.0	-8,326.5	-530.6	8,323.6	0.00	0.00	0.00
15,600.0	90.00	179.57	9,263.0	-8,426.5	-529.9	8,423.6	0.00	0.00	0.00
15,700.0	90.00	179.57	9,263.0	-8,526.5	-529.1	8,523.6	0.00	0.00	0.00
15,800.0	90.00	179.57	9,263.0	-8,626.5	-528.4	8,623.6	0.00	0.00	0.00
15,900.0	90.00	179.57	9,263.0	-8,726.5	-527.6	8,723.6	0.00	0.00	0.00
16,000.0	90.00	179.57	9,263.0	-8,826.4	-526.9	8,823.6	0.00	0.00	0.00
16,100.0	90.00	179.57	9,263.0	-8,926.4	-526.1	8,923.6	0.00	0.00	0.00
16,200.0	90.00	179.57	9,263.0	-9,026.4	-525.4	9,023.6	0.00	0.00	0.00
16,300.0	90.00	179.57	9,263.0	-9,126.4	-524.6	9,123.6	0.00	0.00	0.00
16,400.0	90.00	179.57	9,263.0	-9,226.4	-523.9	9,223.6	0.00	0.00	0.00
16,500.0	90.00	179.57	9,263.0	-9,326.4	-523.1	9,323.6	0.00	0.00	0.00
16,600.0	90.00	179.57	9,263.0	-9,426.4	-522.4	9,423.6	0.00	0.00	0.00
16,700.0	90.00	179.57	9,263.0	-9,526.4	-521.6	9,523.6	0.00	0.00	0.00
16,800.0	90.00	179.57	9,263.0	-9,626.4	-520.9	9,623.6	0.00	0.00	0.00
16,900.0	90.00	179.57	9,263.0	-9,726.4	-520.1	9,723.6	0.00	0.00	0.00
17,000.0	90.00	179.57	9,263.0	-9,826.4	-519.4	9,823.6	0.00	0.00	0.00
17,100.0	90.00	179.57	9,263.0	-9,926.4	-518.6	9,923.6	0.00	0.00	0.00
17,200.0	90.00	179.57	9,263.0	-10,026.4	-517.9	10,023.6	0.00	0.00	0.00
17,300.0	90.00	179.57	9,263.0	-10,126.4	-517.1	10,123.6	0.00	0.00	0.00
17,400.0	90.00	179.57	9,263.0	-10,226.4	-516.4	10,223.6	0.00	0.00	0.00
17,423.4	90.00	179.57	9,263.0	-10,249.8	-516.2	10,247.0	0.00	0.00	0.00
17,500.0	90.00	179.57	9,263.0	-10,326.4	-515.6	10,323.6	0.00	0.00	0.00
17,513.4	90.00	179.57	9,263.0	-10,339.8	-515.5	10,337.0	0.00	0.00	0.00

Database: EDM 5000.18 Single User Db

Company: ROC

 Project:
 Long Lead - PLU 18-30 BD

 Site:
 Poker Lake Unit 18-30 BD

 Well:
 Poker Lake Unit 18-30 BD 202H

Wellbore: OH
Design: Plan 0

Local Co-ordinate Reference:

TVD Reference:
MD Reference:
North Reference:

Survey Calculation Method:

Well Poker Lake Unit 18-30 BD 202H

RKB30' @ 3212.0usft RKB30' @ 3212.0usft

Grid

Design Targets									
Target Name - hit/miss target - Shape	Dip Angle (°)	Dip Dir. (°)	TVD (usft)	+N/-S (usft)	+E/-W (usft)	Northing (usft)	Easting (usft)	Latitude	Longitude
P2 PLU 18-30 BD 202H - plan misses targe - Point		0.00 2.7usft at 0.0	0.0 Ousft MD (0.0	-3,827.3 O TVD, 0.0 N,	-710.7 0.0 E)	409,813.60	627,492.10	32° 7′ 33.687 N	103° 55' 17.395 W
P5 PLU 18-30 BD 202H - plan misses targe - Point		0.00 7.9usft at 0.0	0.0 Ousft MD (0.0	-4,866.3 O TVD, 0.0 N,	-555.8 0.0 E)	408,774.60	627,647.00	32° 7′ 23.399 N	103° 55' 15.640 W
SHL PLU 18-30 BD 202 - plan hits target ce - Rectangle (sides \)	nter	0.00	0.0	0.0	0.0	413,640.90	628,202.80	32° 8' 11.536 N	103° 55′ 8.960 W
P4 PLU 18-30 BD 202H - plan misses targe - Point		0.00 1.6usft at 0.0	0.0 Ousft MD (0.0	-4,514.5 O TVD, 0.0 N,	-579.6 0.0 E)	409,126.40	627,623.20	32° 7' 26.882 N	103° 55' 15.901 W
P1 PLU 18-30 BD 202H - plan misses targe - Point		0.00 2.3usft at 0.0	0.0 Ousft MD (0.0	-3,486.0 O TVD, 0.0 N,	-733.3 0.0 E)	410,154.90	627,469.50	32° 7' 37.066 N	103° 55' 17.643 W
P3 PLU 18-30 BD 202H - plan misses targe - Point		0.00 0.7usft at 0.0	0.0 Ousft MD (0.0	-4,171.0 0 TVD, 0.0 N,	-645.8 0.0 E)	409,469.90	627,557.00	32° 7′ 30.283 N	103° 55' 16.656 W
PPP#3 PLU 18-30 BD 2 - plan hits target ce - Point		0.00	9,263.0	-5,034.2	-555.4	408,606.70	627,647.40	32° 7' 21.738 N	103° 55' 15.643 W
LTP PLU 18-30 BD 202 - plan hits target ce - Point		0.00	9,263.0	-10,249.8	-516.2	403,391.10	627,686.60	32° 6' 30.121 N	103° 55' 15.419 W
PPP#1 PLU 18-30 BD 2 - plan misses targe - Point		0.00 5.6usft at 93	9,263.0 00.0usft MD	-1,019.8 (8821.2 TVD	-332.7 , -2323.2 N, -7	412,621.10 41.1 E)	627,870.10	32° 8' 1.457 N	103° 55' 12.875 W
FTP PLU 18-30 BD 202 - plan misses targe - Point		0.00 .1usft at 970	9,263.0 0.0usft MD (-2,476.3 9130.1 TVD,	-740.2 -2569.2 N, -73	411,164.60 9.6 E)	627,462.60	32° 7' 47.058 N	103° 55' 17.678 W
BHL PLU 18-30 BD 202 - plan misses targe - Point		0.00 usft at 17513	9,263.0 .4usft MD (9	-10,339.8 263.0 TVD, -1	-515.7 0339.8 N, -51	403,301.10 5.5 E)	627,687.10	32° 6' 29.230 N	103° 55' 15.418 W
PPP#2 PLU 18-30 BD 2 - plan misses targe - Point		0.00 5.5usft at 963	9,263.0 5.6usft MD (-2,376.4 9090.4 TVD,	-740.4 -2518.5 N, -74	411,264.50 0.0 E)	627,462.40	32° 7′ 48.047 N	103° 55' 17.676 W

Database: EDM 5000.18 Single User Db

Company: ROC

 Project:
 Long Lead - PLU 18-30 BD

 Site:
 Poker Lake Unit 18-30 BD

 Well:
 Poker Lake Unit 18-30 BD 202H

Wellbore: OH
Design: Plan 0

Local Co-ordinate Reference:

TVD Reference: MD Reference: North Reference:


Survey Calculation Method:

Well Poker Lake Unit 18-30 BD 202H

RKB30' @ 3212.0usft RKB30' @ 3212.0usft

Grid

rmations						
	Measured Depth (usft)	Vertical Depth (usft)	Name	Lithology	Dip (°)	Dip Direction (°)
	768.5	768.5	Rustler			
	1,044.8	1,044.8	Salado			
	3,334.7	3,236.4	Base of Salt			
	3,744.8	3,611.0	Delaware			
	4,722.3	4,504.0	Cherry Canyon			
	6,364.9	6,004.6	Brushy Canyon			
	7,550.0	7,093.1	Basal Brushy Canyon			
	7,800.6	7,334.5	Bone Spring Lm.			
	7,905.2	7,436.9	Avalon			
	8,283.5	7,812.0	Lower Avalon			
	8,715.4	8,243.8	1st Bone Spring Sand			
	9,053.4	8,581.8	2nd Bone Spring Shale			
	9,196.2	8,722.8	2nd Bone Spring Lime			
	9,345.5	8,862.6	2nd Bone Spring Sand			
	10,143.4	9,263.0	2rd Bone Spring Sand Lower Landing			



TenarisHydril Wedge 511



Coupling	Pipe Body
Grade: P110-ICY	Grade: P110-ICY
Body: White	1st Band: White
1st Band: Pale Green	2nd Band: Pale Green
2nd Band: -	3rd Band: Pale Green
3rd Band: -	4th Band: -
	5th Band: -
	6th Band: -

Outside Diameter	7.625 in.	Wall Thickness	0.375 in.	Grade	P110-ICY
Min. Wall Thickness	90.00 %	Pipe Body Drift	API Standard	Туре	Casing
Connection OD Option	REGULAR				

Pipe Body Data

Geometry			
Nominal OD	7.625 in.	Wall Thickness	0.375 in.
Nominal Weight	29.70 lb/ft	Plain End Weight	29.06 lb/ft
Drift	6.750 in.	OD Tolerance	API
Nominal ID	6.875 in.		

Performance	
Body Yield Strength	1068 x1000 lb
Min. Internal Yield Pressure	11,070 psi
SMYS	125,000 psi
Collapse Pressure	7360 psi

Connection Data

Geometry	
Connection OD	7.625 in.
Connection ID	6.787 in.
Make-up Loss	3.704 in.
Threads per inch	3.28
Connection OD Option	Regular
Connection OD Option	Regula

Performance	
Tension Efficiency	61.10 %
Joint Yield Strength	653 x1000 lb
Internal Pressure Capacity	11,070 psi
Compression Efficiency	73.80 %
Compression Strength	788 x1000 lb
Max. Allowable Bending	45.83 °/100 ft
External Pressure Capacity	7360 psi

Make-Up Torques	
Minimum	5900 ft-lb
Optimum	7100 ft-lb
Maximum	10,300 ft-lb
Operation Limit Torques	
Operating Torque	55,000 ft-lb
Yield Torque	82,000 ft-lb

Notes

For the lastest performance data, always visit our website: www.tenaris.com
For further information on concepts indicated in this datasheet, download the Datasheet Manual from www.tenaris.com

Tenaris has issued this document for general information only, and the information in this document, including, without limitation, any pictures, drawings or designs ("Information") is not intended to constitute professional or any other type of advice or recommendation and is provided on an "as is" basis. No warranty is given. Tenaris has not independently verified any information —if any-provided by the user in connection with, or for the purpose of, the Information contained hereunder. The use of the Information is at user's own risk and Tenaris does not assume any responsibility or liability of any kind for any loss, damage or injury resulting from, or in connection with any Information contained hereunder or any use thereof. The Information in this document is subject to change or modification without notice. Tenaris's products and services are subject to Tenaris's standard terms and conditions or otherwise to the terms resulting from the respective contracts of sale or services, as the case may be, between petitioner and Tenaris. For more complete information please contact a Tenaris's representative or visit our website at www.tenaris.com. ©Tenaris 2025. All rights reserved.



TenarisHydril Wedge 511



Coupling	Pipe Body
Grade: L80-IC	Grade: L80-IC
Body: Red	1st Band: Red
1st Band: Brown	2nd Band: Brown
2nd Band: -	3rd Band: Pale Green
3rd Band: -	4th Band: -
	5th Band: -
	6th Band: -

Outside Diameter	7.625 in.	Wall Thickness	0.375 in.	Grade	L80-IC
Min. Wall Thickness	87.50 %	Pipe Body Drift	API Standard	Туре	Casing
Connection OD Option	REGULAR				

Pipe Body Data

Geometry			
Nominal OD	7.625 in.	Wall Thickness	0.375 in.
Nominal Weight	29.70 lb/ft	Plain End Weight	29.06 lb/ft
Drift	6.750 in.	OD Tolerance	API
Nominal ID	6.875 in.		

Performance	
Body Yield Strength	683 x1000 lb
Min. Internal Yield Pressure	6890 psi
SMYS	80,000 psi
Collapse Pressure	5900 psi

Connection Data

Geometry	
Connection OD	7.625 in.
Connection ID	6.787 in.
Make-up Loss	3.704 in.
Threads per inch	328
Connection OD Option	Regular

61.10 %
417 x1000 lb
6890 psi
73.80 %
504 x1000 lb
29.33 °/100 ft
5900 psi

Make-Up Torques	
Minimum	5900 ft-lb
Optimum	7100 ft-lb
Maximum	10,300 ft-lb
Operation Limit Torques	
Operating Torque	35,000 ft-lb
Yield Torque	52,000 ft-lb

Notes

For the lastest performance data, always visit our website: www.tenaris.com
For further information on concepts indicated in this datasheet, download the Datasheet Manual from www.tenaris.com

Tenaris has issued this document for general information only, and the information in this document, including, without limitation, any pictures, drawings or designs ("Information") is not intended to constitute professional or any other type of advice or recommendation and is provided on an "as is" basis. No warranty is given. Tenaris has not independently verified any information —if any- provided by the user in connection with, or for the purpose of, the Information contained hereunder. The use of the Information is at user's own risk and Tenaris does not assume any responsibility or liability of any kind for any loss, damage or injury resulting from, or in connection with any Information contained hereunder or any use thereof. The Information in this document is subject to change or modification without notice. Tenaris's products and services are subject to Tenaris's standard terms and conditions or otherwise to the terms resulting from the respective contracts of sale or services, as the case may be, between petitioner and Tenaris. For more complete information please contact a Tenaris's representative or visit our website at www.tenaris.com. ©Tenaris 2024. All rights reserved.



TenarisHydril Wedge 441®



Coupling Pipe Body Grade: P110-ICY Grade: P110-ICY Body: White 1st Band: White 1st Band: Pale Green 2nd Band: Pale Green 2nd Band: -3rd Band: Pale Green 3rd Band: -4th Band: -5th Band: -

6th Band: -

Outside Diameter	5.500 in.	Wall Thickness	0.361 in.	Grade	P110-ICY
Min. Wall Thickness	87.50 %	Pipe Body Drift	API Standard	Туре	Casing
Connection OD Option	REGULAR				

Pipe Body Data

Geometry			
Nominal OD	5.500 in.	Wall Thickness	0.361 in.
Nominal Weight	20.00 lb/ft	Plain End Weight	19.83 lb/ft
Drift	4.653 in.	OD Tolerance	API
Nominal ID	4.778 in.		

Performance	
Body Yield Strength	729 x1000 lb
Min. Internal Yield Pressure	14,360 psi
SMYS	125,000 psi
Collapse Pressure	12,300 psi

Connection Data

Geometry	
Connection OD	5.852 in.
Coupling Length	8.714 in.
Connection ID	4.778 in.
Make-up Loss	3.780 in.
Threads per inch	3.40
Connection OD Option	Regular

Performance	
Tension Efficiency	81.50 %
Joint Yield Strength	594 x1000 lb
Internal Pressure Capacity	14,360 psi
Compression Efficiency	81.50 %
Compression Strength	594 x1000 lb
Max. Allowable Bending	84.76 °/100 ft
External Pressure Capacity	12,300 psi

Make-Up Torques	
Minimum	15,000 ft-lb
Optimum	16,000 ft-lb
Maximum	19,200 ft-lb
Operation Limit Torques	
Operating Torque	36,000 ft-lb
Yield Torque	42,000 ft-lb
Yield Torque Buck-On	42,000 ft-lb
	42,000 ft-lb

Notes

This connection is fully interchangeable with: Wedge 441\$ - 5.5 in. - 0.304 (17.00) in. (lb/ft) Wedge 461\$ - 5.5 in. - 0.304 (17.00) / 0.361 (20.00) / 0.415 (23.00) in. (lb/ft) Connections with Dopeless\$ Technology are fully compatible with the same connection in its doped version

For the lastest performance data, always visit our website: www.tenaris.com
For further information on concepts indicated in this datasheet, download the Datasheet Manual from www.tenaris.com

Tenaris has issued this document for general information only, and the information in this document, including, without limitation, any pictures, drawings or designs ("Information") is not intended to constitute professional or any other type of advice or recommendation and is provided on an "as is" basis. No warranty is given. Tenaris has not independently verified any information —if any-provided by the user in connection with, or for the purpose of, the Information contained hereunder. The use of the Information is at user's own risk and Tenaris does not assume any responsibility or liability of any kind for any loss, damage or injury resulting from, or in connection with any Information contained hereunder or any use thereof. The Information in this document is subject to change or modification without notice. Tenaris's products and services are subject to Tenaris's translated terms and conditions or otherwise to the terms resulting from the respective contracts of sale or services, as the case may be, between petitioner and Tenaris. For more complete information please contact a Tenaris's representative or visit our website at www.tenaris.com. ©Tenaris 2025. All rights reserved.

CACTUS WELLHEAD LLC

20" x 9-5/8" x 7-5/8" x 5-1/2" MBU-T-CFL-R-DBLO Wellhead With 11" 10M x 7-1/16" 15M CTH-DBLHPS Tubing Head And 9-5/8", 7-5/8" & 5-1/2" Pin Bottom Mandrel Casing Hangers

	XTO ENERGY IN DELAWARE BASI	
DRAWN	VJK	31MAR2
APPRV		
DRAWING NO	D. HBE000	0479

FORMATION CONTAINED HEREIN IS THE PROPERTY OF CACTUS WELLHEAD, LLC. REPRODUCTION, SCLOSURE, OR USE THEREOF IS PERMISSIBLE ONLY AS PROVIDED BY CONTRACT OR AS EXPRESSLY SUTHORIZED BY CACTUS WELLHEAD, LLC.

XTO Permian Operating, LLC. states that we will not introduce any additives that contain PFAS chemicals in the completion or recompletion of the well and will meet the certification requirement.

XTO respectfully requests approval to utilize a spudder rig to pre-set surface casing.

Description of Operations:

- Spudder rig will move in to drill the surface hole and pre-set surface casing on the well.
 - a. After drilling the surface hole section, the spudder rig will run casing and cement following all of the applicable rules and regulations (OnShore Order 2, all COAs and NMOCD regulations).
 - b. The spudder rig will utilize fresh water-based mud to drill the surface hole to TD. Solids control will be handled entirely on a closed loop basis. No earth pits will be used.
- 2. The wellhead will be installed and tested as soon as the surface casing is cut off and WOC time has been reached.
- 3. A blind flange at the same pressure rating as the wellhead will be installed to seal the wellbore. Pressure will be monitored with needle valves installed on two wing valves.
 - a. A means for intervention will be maintained while the drilling rig is not over the well.
- 4. Spudder rig operations are expected to take 2-3 days per well on the pad.
- 5. The BLM will be contacted and notified 24 hours prior to commencing spudder rig operations.
- 6. Drilling Operations will begin with a larger rig and a BOP stack equal to or greater than the pressure rating that was permitted will be nippled up and tested on the wellhead before drilling operations resume on each well.
 - a. The larger rig will move back onto the location within 90 days from the point at which the wells are secured and the spudder rig is moved off location.
 - b. The BLM will be notified 24 hours before the larger rig moves back on the pre-set locations
- 7. XTO will have supervision on the rig to ensure compliance with all BLM and NMOCD regulations and to oversee operations.
- 8. Once the rig is removed, XTO will secure the wellhead area by placing a guard rail around the cellar area.

Subject: Request for a Variance Allowing break Testing of the Blowout Preventer Equipment (BOPE)

XTO Energy requests a variance to ONLY test broken pressure seals on the BOPE and function test BOP when skidding a drilling rig between multiple wells on a pad.

Background

Onshore Oil and Gas Order CFR Title 43 Part 3170, Drilling Operations, Sections III.A.2.i.iv.B states that the BOP test must be performed whenever any seal subject to test pressure is broken. The current interpretation of the Bureau of Land Management (BLM) requires a complete BOP test and not just a test of the affected component. CFR Title 43 Part 3170 states, "Some situation may exist either on a well-by-well basis or field-wide basis whereby it is commonly accepted practice to vary a particular minimum standard(s) established in this order. This situation can be resolved by requesting a variance...". XTO Energy feels the break testing the BOPE is such a situation. Therefore, as per CFR Title 43 Part 3170, XTO Energy submits this request for the variance.

Supporting Documentation

CFR Title 43 Part 3170 became effective on December 19, 1988 and has remained the standard for regulating BLM onshore drilling operations for over 30 years. During this time there have been significant changes in drilling technology. BLM continues to use the variance request process to allow for the use of modern technology and acceptable engineering practices that have arisen since CFR Title 43 Part 3170 was originally released. The XTO Energy drilling rig fleet has many modern upgrades that allow the intact BOP stack to be moved between well slots on a multi-well pad, as well as, wellhead designs that incorporate quick connects facilitating release of the BOP from the wellhead without breaking any BOP stack components apart. These technologies have been used extensively offshore, and other regulators, API, and many operators around the world have endorsed break testing as safe and reliable.



Figure 1: Winch System attached to BOP Stack



Figure 2: BOP Winch System

American Petroleum Institute (API) standards, specification and recommended practices are considered the industry standard and are consistently utilized and referenced by the industry. CFR Title 43 Part 3170recognizes API recommended Practices (RP) 53 in its original development. API Standard 53, *Well Control Equipment Systems for Drilling Wells* (Fifth Edition, December 2018, Annex C, Table C.4) recognizes break testing as an acceptable practice. Specifically, API Standard 53, Section 5.3.7.1 states "A pressure test of the pressure containing component shall be performed following the disconnection or repair, limited to the affected component." See Table C.4 below for reference.

		Pressure Test—High Pressureac		
Component to be Pressure Tested	Pressure Test—Low Pressure <mark>ac</mark> psig (MPa)	Change Out of Component, Elastomer, or Ring Gasket	No Change Out of Component, Elastomer, or Ring Gasket	
Annular preventer ^b	250 to 350 (1.72 to 2.41)	RWP of annular preventer	MASP or 70% annular RWP, whichever is lower.	
Fixed pipe, variable bore, blind, and BSR preventers ^{bd}	250 to 350 (1.72 to 2.41)	RWP of ram preventer or wellhead system, whichever is lower	ITP	
Choke and kill line and BOP side outlet valves below ram preventers (both sides)	250 to 350 (1.72 to 2.41)	RWP of side outlet valve or wellhead system, whichever is lower	ITP	
Choke manifold—upstream of chokes ^e	250 to 350 (1.72 to 2.41)	RWP of ram preventers or wellhead system, whichever is lower	ITP	
Choke manifold—downstream of chokese	250 to 350 (1.72 to 2.41)	RWP of valve(s), line(s), or MASP for the well program, whichever is lower		
Kelly, kelly valves, drill pipe safety valves, IBOPs	250 to 350 (1.72 to 2.41)	50 to 350 (1.72 to 2.41) MASP for the well program		
 Annular(s) and VBR(s) shall be pre For pad drilling operations, moving pressure-controlling connections For surface offshore operations, the 	during the evaluation period. The j essure tested on the largest and sm from one wellhead to another with when the integrity of a pressure se er am BOPs shall be pressure tes land operations, the ram BOPs sh	pressure shall not decrease below the allest OD drill pipe to be used in well in the 21 days, pressure testing is req	program. puired for pressure-containing and the closing and locking pressure	

The Bureau of Safety and Environmental Enforcement (BSEE), Department of Interior, has also utilized the API standards, specification and best practices in the development of its offshore oil and gas regulations and incorporates them by reference within its regulations.

Break testing has been approved by the BLM in the past with other operators based on the detailed information provided in this document.

XTO Energy feels break testing and our current procedures meet the intent of CFR Title 43 Part 317 Oand often exceed it. There has been no evidence that break testing results in more components failing than seen on full BOP tests. XTO Energy's internal standards requires complete BOPE tests more often than that of CFR Title 43 Part 3170 (Every 21 days). In addition to function testing the annular, pipe rams and blind rams after


each BOP nipple up, XTO Energy performs a choke drill with the rig crew prior to drilling out every casing shoe. This is additional training for the rig crew that exceeds the requirements of the CFR Title 43 Part 3170.

Procedures

- XTO Energy will use this document for our break testing plan for New Mexico Delaware basin.
 The summary below will be referenced in the APD or Sundry Notice and receive approval prior
 to implementing this variance.
- 2. XTO Energy will perform BOP break testing on multi-wells pads where multiple intermediate sections can be drilled and cased within the 21-day BOP test window.
 - a. A full BOP test will be conducted on the first well on the pad.
 - b. The first intermediate hole section drilled on the pad will be the deepest. All of the remaining hole sections will be the same depth or shallower.
 - i. Our Lower WC targets set the intermediate casing shoe no deeper than the Wolfcamp B.
 - ii. Our Upper WC targets set the intermediate casing shoe shallower than the Wolfcamp B.
 - c. A Full BOP test will be required if the intermediate hole section being drilled has a MASP over 5M.
 - d. A full BOP test will be required prior to drilling any production hole.
- 3. After performing a complete BOP test on the first well, the intermediate hole section will be drilled and cased, two breaks would be made on the BOP equipment.
 - a. Between the HCV valve and choke line connection
 - b. Between the BOP quick connect and the wellhead
- 4. The BOP is then lifted and removed from the wellhead by a hydraulic system.
- 5. After skidding to the next well, the BOP is moved to the wellhead by the same hydraulic system and installed.
- 6. The connections mentioned in 3a and 3b will then be reconnected.
- 7. Install test plug into the wellhead using test joint or drill pipe.
- 8. A shell test is performed against the upper pipe rams testing the two breaks.
- 9. The shell test will consist of a 250 psi low test and a high test to the value submitted in the APD or Sundry (e.g. 5,000 psi or 10,000psi).
- 10. Function test will be performed on the following components: lower pipe rams, blind rams, and annular.

- 11. For a multi-well pad the same two breaks on the BOP would be made and on the next wells and steps 4 through 10 would be repeated.
- 12. A second break test would only be done if the intermediate hole section being drilled could not be completed within the 21 day BOP test window.

Note: Picture below highlights BOP components that will be tested during batch operations




Summary

A variance is requested to **ONLY** test broken pressure seals on the BOP equipment when moving from wellhead to wellhead which is in compliance with API Standard 53. API Standard 53 states, that for pad drilling operation, moving from one wellhead to another within 21 days, pressure testing is required for pressure-containing and pressure-controlling connections when the integrity of a pressure seal is broken.

The BOP will be secured by a hydraulic carrier or cradle. The BLM will be contacted if a Well Control event occurs prior to the commencement of a BOPE Break Testing operation.

Based on discussions with the BLM on February 27th 2020 and the supporting documentation submitted to the BLM, we will request permission to ONLY retest broken pressure seals if the following conditions are met:

- 1. After a full BOP test is conducted on the first well on the pad.
- 2. The first intermediate hole section drilled on the pad will be the deepest. All of the remaining hole sections will be the same depth or shallower.
- 3. Full BOP test will be required if the intermediate hole section being drilled has a MASP over 5M.
- 4. Full BOP test will be required prior to drilling the production hole.





GATES ENGINEERING & SERVICES NORTH AMERICA

7603 Prairie Oak Dr.

Houston, TX. 77086

PHONE: +1 (281) 602-4100

FAX: +1 (281) 602-4147

EMAIL: gesna.quality@gates.com

WEB: www.gates.com/oilandgas

NEW CHOKE HOSE

INSTAUED 02-10-2024

CERTIFICATE OF CONFORMANCE

This is to verify that the items detailed below meet the requirements of the Customer's Purchase Order referenced herein, and are in Conformance with applicable specifications, and that Records of Required Tests are on file and subject to examination. The following items were inspected and hydrostatically tested at **Gates Engineering & Services North America** facilities in Houston, TX, USA.

CI	CT	OM	ED.	
CU	31	CIAI	ER.	

NABORS DRILLING TECHNOLOGIES USA DBA NABORS DRILLING USA

CUSTOMER P.O.#:

15582803 (TAG NABORS PO #15582803 SN 74621 ASSET 66-1531)

CUSTOMER P/N:

IMR RETEST SN 74621 ASSET #66-1531

PART DESCRIPTION:

RETEST OF CUSTOMER 3" X 45 FT 16C CHOKE & KILL HOSE ASSEMBLY C/W 4 1/16" 10K

FLANGES

SALES ORDER #:

529480

QUANTITY:

1

SERIAL #:


74621 H3-012524-1

SIGNATURE: F. CUSTUSE

TITLE: QUALITY ASSURANCE

DATE: 1/25/2024

H3-15/16





TEST REPORT

CUSTOMER

Company:

Nabors Industries Inc.

TEST OBJECT

Serial number: H3-012524-1

Lot number:

Production description:

529480

74621/66-1531

Description:

74621/66-1531

Sales order #: Customer reference: FG1213

Hose ID:

3" 16C CK

Part number:

TEST INFORMATION

Test procedure:

GTS-04-053

psi

Fitting 1:

3.0 x 4-1/16 10K

Test pressure: Test pressure hold: 15000.00 3600.00

sec

Part number: Description:

45

Work pressure: Work pressure hold: 10000.00

psi

Fitting 2:

3.0 x 4-1/16 10K

Length difference:

900.00 0.00 0.00

sec % inch

Part number:

Length:

Description:

feet

n /n

Visual check: Pressure test result:


Length difference:

PASS

Length measurement result:

Test operator:

Travis





H3-15/16

1/25/2024 11:48:06 AM

TEST REPORT

GAUGE TRACEABILITY

Description	Serial number	Calibration date	Calibration due date
S-25-A-W	110D3PHO	2023-06-06	2024-06-06
S-25-A-W	110IQWDG	2023-05-16	2024-05-16
Comment			




Released to Imaging: 9/19/2025 3:47:41 PM









Released to Imaging: 9/19/2025 3:47:41 PM

XTO Permian Operating, LLC Offline Cementing Variance Request

XTO requests the option to cement the surface and intermediate casing strings offline as a prudent batch drilling efficiency of acreage development.

1. Cement Program

No changes to the cement program will take place for offline cementing.

2. Offline Cementing Procedure


The operational sequence will be as follows. If a well control event occurs, the BLM will be contacted for approval prior to conducting offline cementing operations.

- 1. Run casing as per normal operations. While running casing, conduct negative pressure test and confirm integrity of the float equipment (float collar and shoe)
- 2. Land casing with mandrel
- 3. Fill pipe with kill weight fluid, do not circulate through floats and confirm well is static
- 4. Set annular packoff shown below and pressure test to confirm integrity of the seal. Pressure ratings of wellhead components and valves is 5,000 psi.
- 5. After confirmation of both annular barriers and internal barriers, nipple down BOP and install cap flange.
 - a. If any barrier fails to test, the BOP stack will not be nippled down until after the cement job is completed with cement 500ft above the highest formation capable of flow with kill weight mud above or after it has achieved 50-psi compressive strength if kill weight fluid cannot be verified.



Annular packoff with both external and internal seals


XTO Permian Operating, LLC Offline Cementing Variance Request



Wellhead diagram during skidding operations

- 6. Skid rig to next well on pad.
- 7. Confirm well is static before removing cap flange, flange will not be removed and offline cementing operations will not commence until well is under control. If well is not static, casing outlet valves will provide access to both the casing ID and annulus. Rig or third party pump truck will kill well prior to cementing or nippling up for further remediation.
 - a. Well Control Plan
 - i. The Drillers Method will be the primary well control method to regain control of the wellbore prior to cementing, if wellbore conditions do not permit the drillers method other methods of well control may be used
 - ii. Rig pumps or a 3rd party pump will be tied into the upper casing valve to pump down the casing ID
 - iii. A high pressure return line will be rigged up to lower casing valve and run to choke manifold to control annular pressure
 - iv. Once influx is circulated out of the hole, kill weight mud will be circulated
 - v. Well will be confirmed static
 - vi. Once confirmed static, cap flange will be removed to allow for offline cementing operations to commence
- 8. Install offline cement tool
- 9. Rig up cement equipment

XTO Permian Operating, LLC Offline Cementing Variance Request



Wellhead diagram during offline cementing operations

- 10. Circulate bottoms up with cement truck
 - a. If gas is present on bottoms up, well will be shut in and returns rerouted through gas buster to handle entrained gas
 - b. Max anticipated time before circulating with cement truck is 6 hrs
- 11. Perform cement job taking returns from the annulus wellhead valve
- 12. Confirm well is static and floats are holding after cement job
- 13. Remove cement equipment, offline cement tools and install night cap with pressure gauge for monitoring.

Received by OCD: 9/19/2025 11:53:46 AM



Offline Production Cementing

Delaware Basin | 18 March 2025

Energy lives here

Received by OCD: 9/19/2025 11:53:46 AM

Variance Request for Offline Production Cementing

Proposal: allow wells that meet set criteria to perform production casing cement jobs offline, consistent with ExxonMobil's extensive experience safely and effectively cementing production casing strings offline in Texas

Supporting Materials:

- Criteria for offline production cementing
- Proposed procedure
- Process and equipment
- Barrier comparison



Criteria for Offline Cementing

The following conditions must be met to proceed with offline production cementing on Wolfcamp target formations or shallower:

- a) Casing hanger successfully landed in the wellhead
- b) Ability to circulate overbalanced mud weight
- c) Initiate offline cementing operations within 24hr of landing casing
- d) All well control barriers test successfully and BLM notified of intent to perform offline production cementing prior to N/D BOP
- e) No offset frac operations within 1 mile and within the same target horizon
- f) Well Control certified ExxonMobil Operations Supervisor to be present during offline cementing operation to monitor returns
- g) Drill ahead operations will not begin on next well until offline production cement operations have concluded

Trigger to reevaluate plan


Offline Cementing Procedure


- 1. Land production casing hanger If casing hanger cannot be landed, cementing will be performed online
- 2. Flow check and **confirm the well is static on the casing and annulus**. *If flow is observed, cementing will be performed online*
- 3. Lay down landing joint
- 4. Install and test pack-off assembly
 - a) Pressure test the seal assembly per wellhead provider's procedure to confirm integrity to 250 / 10,000psi
- 5. Install back-pressure valve (BPV, rated to 10,000psi) in hanger per wellhead provider's procedure
- 6. Confirm the well is static
 - a) Flow indicates failure of hydrostatic barrier or mechanical barriers and underbalanced well conditions. If flow is observed, cementing will be performed online
 - b) Notify BLM of intent to proceed with nipple down and offline cementing
- 7. With the well secured and BLM notified; **nipple down BOP and skid rig** to next well on pad
 - a) Note, verify offline cementing criteria is met before N/D BOP. If unable to meet criteria, cement job will be performed online
- 8. Install and test gate valve
 - a) Test connection between wellhead adapter seals against hanger neck and ring gasket to 250 / 10,000 psi for 5 minutes
- Remove BPV from casing
- 10. Rig up cement head and cementing lines
- 11. **Perform production cement job** as per procedure
 - a) Confirm flowpath and valve alignment; default routing to take returns from casing upper side outlet valves \rightarrow offline cementing manifold \rightarrow shakers / pits
 - b) If elevated gas or flow trend observed, reroute returns through choke manifold for ability to hold backpressure to maintain well control and route mud returns to MGS
- 12. Confirm well is static and double floats are holding after cement job
 - a) If double floats do not hold, the well can be secured by closing gate valve or cement head or by holding and monitoring pressure at the cement truck while WOC
- 13. Rigdown surface equipment
 - a) Bleed any remaining line pressure and remove cement head
 - b) Install BPV per wellhead providers recommended procedure
 - c) Close upper casing side outlet valves, break and R/D offline cement lines
 - d) Remove 10M gate valve and wellhead adapter
- 14. Secure well
 - a) Install temporary abandonment cap



Process and Equipment

ONLINE CEMENTING OFFLINE CEMENTING





KEY DIFFERENCES

- 1. Rig BOP replaced by gate valve and WH adaptor assembly (10M rated)
- 2. Addition of offline cementing manifold and high pressure iron to direct fluid returns to rig active system and/or choke manifold
- Packoff annulus barrier in place and tested prior to cementing operations (10M rated)
- 4. Cement truck performs cement job displacement (vs rig pumps)



Barrier Comparison

	ONI	LINE	OFFLINE (PROPOSED)	
	Casing	Annulus	Casing	Annulus
N/D BOP & Skid Rig			 Hydrostatic Double float valves BPV 	 Hydrostatic Packoff
Install Cement Head	 Hydrostatic Double float valves 	 Hydrostatic BOP (annular, VBR) 	 Hydrostatic Double float valves Gate valve 	 Hydrostatic Packoff Wellhead Adaptor
Perform Cement Job	 Double float valves Cement Head 	 Hydrostatic BOP (annular, VBR) 	 Double float valves Cement Head Gate valve 	 Hydrostatic Packoff Wellhead Adaptor
Remove Cement Head	1. Double float valves	 Hydrostatic BOP (annular, VBR) 	 Double float valves Gate valve 	 Hydrostatic Packoff Wellhead Adaptor
N/D & Install TA Cap	 Double float valves BPV 	 Hydrostatic Packoff 	 Double float valves BPV 	 Hydrostatic Packoff

Well Control Response Plan

The following well control response plan for offline cementing is the same as for online cementing.

- 1. Pre-job design: Cement job designed to define max pump rates to reduce ECD and avoid losses during cement job.
- 2. Identify the influx / re-route return flow: If an influx is observed, the cementing manifold would be re-routed to direct flow to the rig choke manifold (instead of the shakers). If gas was encountered or a kick was detected, continue pumping the job through the rig choke / gas buster while controlling annulus back pressure through the rig choke. Shut the well in once the job is finished (to ensure cement does not set up inside casing). Roles & responsibilities are as follows:
 - Onsite well site representative responsible for monitoring and helping to identify if an influx occurred with support from the rig crews.
 - Rig crew responsible for shutting in the well.
 - Onsite well site representative responsible for operating the rig choke manifold.
- 3. Monitor pressure: If well is shut-in, pressure monitored while cement is building compressive strength.
- 4. Flow check: Once sufficient time is allocated to build compressive strength, perform flow check.
- 5. Shut-in: If annulus pressure / flow is observed, shut-in the well at the casing valves.
- 6. Kill the well: Pump kill weight mud or cement (depending on well conditions) via bradenhead squeeze down the annulus using the rig pumps tied into the cementing manifold or the cement truck.
- 7. Flow check: Flow check the well to confirm static.

ExonMobil

Sante Fe Main Office Phone: (505) 476-3441

General Information Phone: (505) 629-6116

Online Phone Directory https://www.emnrd.nm.gov/ocd/contact-us State of New Mexico
Energy, Minerals and Natural Resources
Oil Conservation Division
1220 S. St Francis Dr.
Santa Fe, NM 87505

ACKNOWLEDGMENTS

Action 507591

ACKNOWLEDGMENTS

Operator:	OGRID:
XTO PERMIAN OPERATING LLC.	373075
6401 HOLIDAY HILL ROAD	Action Number:
MIDLAND, TX 79707	507591
	Action Type:
	[C-101] BLM - Federal/Indian Land Lease (Form 3160-3)

ACKNOWLEDGMENTS

I hereby certify that no additives containing PFAS chemicals will be added to the completion or recompletion of this well.

Sante Fe Main Office Phone: (505) 476-3441

General Information Phone: (505) 629-6116

Online Phone Directory https://www.emnrd.nm.gov/ocd/contact-us

State of New Mexico Energy, Minerals and Natural Resources Oil Conservation Division 1220 S. St Francis Dr. Santa Fe, NM 87505

CONDITIONS

Action 507591

CONDITIONS

Operator:	OGRID:
XTO PERMIAN OPERATING LLC.	373075
6401 HOLIDAY HILL ROAD	Action Number:
MIDLAND, TX 79707	507591
	Action Type:
	[C-101] BLM - Federal/Indian Land Lease (Form 3160-3)

CONDITIONS

Created By	Condition	Condition Date
mvenkatesh	Cement is required to circulate on both surface and intermediate1 strings of casing.	9/19/2025
mvenkatesh	If cement does not circulate on any string, a Cement Bond Log (CBL) is required for that string of casing.	9/19/2025
ward.rikala	Notify the OCD 24 hours prior to casing & cement.	9/19/2025
ward.rikala	File As Drilled C-102 and a directional Survey with C-104 completion packet.	9/19/2025
ward.rikala	Once the well is spud, to prevent ground water contamination through whole or partial conduits from the surface, the operator shall drill without interruption through the fresh water zone or zones and shall immediately set in cement the water protection string.	9/19/2025
ward.rikala	Oil base muds are not to be used until fresh water zones are cased and cemented providing isolation from the oil or diesel. This includes synthetic oils. Oil based mud, drilling fluids and solids must be contained in a steel closed loop system.	9/19/2025