Phone: (505) 476-3441 General Information Phone: (505) 629-6116

Online Phone Directory

https://www.emnrd.nm.gov/ocd/contact-us

# State of New Mexico Energy, Minerals and Natural Resources Oil Conservation Division 1220 S. St Francis Dr. Santa Fe, NM 87505

Form C-101 August 1, 2011

Permit 402129

		APPLICA	ATION FOF	R PERMIT	TO DRILL, RE-	ENTER, DEEPE	N, PLUGBAC	CK, OR ADD	AZO	NE		
Per	me and Address mian Resources		:							RID Number 372165		
	N. Marienfeld St land. TX 79701	Ste 1000							3. API	Number 30-015-574	14	
4. Property Cod	de		5. Property Na	ame					6. Well	No.		
337	843		AL	PINE 7 11 S	TATE					124H		
					7. Sur	face Location						
UL - Lot	Section	Township	Range		Lot Idn	Feet From	N/S Line	Feet From		E/W Line	County	
- 1	7	198		28E		1646	S	7	64	E	Eddy	
					8. Proposed E	Bottom Hole Location	on					
UL - Lot	Section	Township	Rang		Lot Idn	Feet From	N/S Line	Feet From		E/W Line	County	
M	11	19	9S	27E	M	990	S	1	00	W	Eddy	
					9. Pod	I Information						
WINCHESTE	R; BONE SPRIN	G, WEST								9756	9	
					Additional	Well Information						
11. Work Type		12. Well Type		13. Cable/F		14. Lease	Туре	15. Gro	15. Ground Level Elevation			
Nev	v Well	OIL			•		State			3532		
16. Multiple		17. Proposed D		18. Format		19. Contra	19. Contractor 20. Spud Da			ate /2/2026		
N N		2266	50		2nd Bone Spring		,,,,			'=		
Depth to Groun	id water			Distance from nearest fresh water well					Distance to nearest surface water			
☑ We will be u	using a closed-lo	op system in li	eu of lined pi	ts					ļ			
				2	21. Proposed Cas	ing and Cement Pr	ogram					
Туре	Hole Size	Casing	g Size		sing Weight/ft	Setting D		Sacks of	Cement		Estimated TOC	
Surf	17.5	13.3	375		54.5	295		24	0		0	
Int1	12.25	9.6			36	3505		900			0	
Prod	8.75	5.			17	7452		55			3005	
Prod         8.5         5.5         17         22660							266	2660 6702				
				Cas	sing/Cement Prog	ıram: Additional Co	mments					
Variances wi	II be added to the	forms										
				2	22. Proposed Blov	wout Prevention Pr	ogram					
	Туре			Working Pressure				Test Pressure			Manufacturer	
	Double Ram			5000			5000	)				
23. I hereby o		ormation given a	bove is true a	and complete	e to the best of my	′		OIL CONSERV	ATION [	DIVISION		

Jeffrey Harrison

11/6/2025

Conditions of Approval Attached

Petroleum Specialist III

Expiration Date: 11/6/2027

Approved By:

Approved Date:

Title:

or recompletion of this well.

⋈, if applicable.
Signature:

Printed Name:

Email Address:

Title:

Date:

I hereby certify that no additives containing PFAS chemicals will be added to the completion

I further certify I have complied with 19.15.14.9 (A) NMAC and/or 19.15.14.9 (B) NMAC

Phone: 432-260-4388

Electronically filed by Stephanie Rabadue

stephanie.rabadue@permianres.com

Regulatory Manager

11/2/2025

<u> C-1</u>	<u>02</u>				State of No	Revised July 9, 2024							
			En		inerals & Natu								
	it Electronical CD Permitting			OIL	CONSERVA	TIC	ON DIVISION			☑ Initial Submit	tal		
	8								Submitt Type:	tal	ort		
									rype.	☐ As Drilled			
			-		WELL LOCA	ATIO	ON INFORMATION						
	Tumber -015-574	144	Pool Code <b>97569</b>	46370	_	Poo	ol Name WINC	HESTER	; BON	NE SPRING, V	WEST		
Proper	rty Code <b>7843</b>		Property N		ļ	NE 7	7-11 STATE			Well Number			
OGRI			Operator N	lame						Ground Level El			
	372165	5		P	PERMIAN RESO	URC	CES OPERATING, I			3,53	2.2'		
Surfac	ce Owner: 🛚	State ☐ Fee ☐	Tribal 🗆 Fee	deral			Mineral Owner: 🖾	State   Fee [	☐ Tribal	☐ Federal			
					Sur	rface	Location						
UL	Section	Range	Lot	Ft. from N/S		Ft. from E/W	Latitude (N.	AD 83)	Longitude (NAD 83)	County			
I	7	19S	28E		1,646 SOUT	Ή	764 EAST	32.6721	30°	-104.208814°	EDDY		
					Botto	m Ho	lole Location						
UL	Section	Township	Range	Lot	Ft. from N/S		Ft. from E/W			Longitude (NAD 83)	County		
M <del>P</del>	11	19S	27E		990 SOUTH	-I	100 WEST	32.6708	02°	-104.257832°	EDDY		
Dedic	ated Acres	Infill or Defi	ining Well	Definin	g Well API		Overlapping Spacin	g Unit (Y/N)	Consolie	dation Code			
483	483.25 Infill			1231	Н		N						
Order	Numbers.			•		Well setbacks are under Common Ownership: ☑Yes ☐No							
					Kick	Off I	Point (KOP)						
UL	Section	Township	Range	Lot	Ft. from N/S	OII I	Ft. from E/W	Latitude (N.	AD 83)	Longitude (NAD 83)	County		
I	7	198	28E		1,646 SOUT	Ή	764 EAST	32.6721		-104.208814°	EDDY		
					First 7	Take	Point (FTP)						
UL	Section	Township	Range	Lot	Ft. from N/S	Tunc	Ft. from E/W	Latitude (N.	AD 83)	Longitude (NAD 83)	County		
P	7	19S	28E		990 SOUTH	I	100 EAST	32.6703	56°	-104.206666°	EDDY		
					Last T	l Γake	Point (LTP)						
UL	Section	Township	Range	Lot	Ft. from N/S		Ft. from E/W	Latitude (N.	AD 83)	Longitude (NAD 83)	County		
M <del>P</del>	11	19S	27E		990 SOUTH	I	100 WEST	32.6708	02°	-104.257832°	EDDY		
Linitia	rad Arran arr Ar	rea of Uniform	Intovast	Chaoina	Unit Type 🛛 Hor	ni z o na	tal D Vartical	Crown	d Floor I	Elevation: TBD			
Ollitiz	ed Alea of Al	tea of Childrin	NA	Spacing	Cint Type Minor	12011	tai 🔲 Verticai	Groun	iu Floor L	nevation. TBD			
OPER	ATOR CERT	TIFICATIONS				S	SURVEYOR CERTIF	CATIONS					
I h au ah	a contife that th	a information con	tained honoin is	tune and som	unlate to the heat of	,	houshy coutify that the sur	II location abou	on this al	at was plotted from the fiel	ld notes of setual		
my kno	wledge and bel	e injormation con ief , and, if the we ns a working inte	ll is a vertical o	r directional		Si	nereby certify that the we urveys made by me or und ny belief.	der my supervisio	n, and that	the same is true and corr	ect to the best of		
includi	ng the proposed	l bottom hole loca	tion or has a rig	ght to drill th	is well at this	"	ну бенеј.			Q PO MEX			
					or unleased mineral ng order heretofore					SEN CO			
enterea	l by the division								100	23/18/2			
					n has received the used mineral interest				Va	al Duch	LØ1		
					e well's completed				\\\	09-18-25	<b>"</b>		

11/1/25 23782 November 20, 2023

Printed Name

Signature

Cassie Evans


Email Address cassie.evans@permianres.com

Certificate Number Date of Survey

Signature and Seal of Professional Surveyor


Note: No allowable will be assigned to this completion until all interest have been consolidated or a non-standard unit has been approved by the division.

Property NameWell NumberDrawn ByRevised ByREV. 2 D.J.S. 09-18-25ALPINE 7-11 STATE124HD.J.S. 11-22-23(UPDATE WELL, WELL NAME & WELLBORE)



SECTION — LINE TABLE								
LINE	DIRECTION	LENGTH						
L1	N00°23'36"E	2630.82						
L2	N00°31'50"E	2639.46						
L3	N00°37'57"E	2655.96						
L4	N02°12'41"E	2654.87'						

WELLBORE - LINE TABLE								
LINE	DIRECTION	LENGTH						
L5	AZ = 134.48°	924.04'						
L6	AZ = 270.78°	15749.18'						



- = SURFACE HOLE LOCATION/
  KICK OFF POINT
- ♦ = FIRST TAKE POINT
- O = LAST TAKE POINT/ BOTTOM HOLE LOCATION
- $\triangle$  = SECTION CORNER LOCATED
- = 330' BUFFER FROM WELLBORE

#### NOTE:

- Distances referenced on plat to section lines are perpendicular.
- Basis of Bearings is a Transverse Mercator Projection with a Central Meridian of W103°53'00" (NAD 83)

NAD 83 (SHL/KOP)	FOOTAGES
LATITUDE = 32°40'19.67" (32.672130°)	1,646' FSL
LONGITUDE = -104°12'31.73" (-104.208814°)	764' FEL
NAD 27 (SHL/KOP)	
LATITUDE = 32°40'19.25" (32.672013°)	1
LONGITUDE = -104°12'29.89" (-104.208304°)	
STATE PLANE NAD 83 (N.M. EAST)	1
N: 608274.36' E: 579652.79'	1
STATE PLANE NAD 27 (N.M. EAST)	
N: 608212.27' E: 538473.11'	

NAD 83 (FIRST TAKE POINT)	FOOTAGES
LATITUDE = 32°40'13.28" (32.670356°)	990' FSL
	100' FEL
NAD 27 (FIRST TAKE POINT)	
LATITUDE = 32°40'12.86" (32.670240°)	
LONGITUDE = -104°12'22.16" (-104.206156°)	
STATE PLANE NAD 83 (N.M. EAST)	
N: 607629.86' E: 580314.65'	
STATE PLANE NAD 27 (N.M. EAST)	
N: 607567.78' E: 539134.97'	

NAD 83 (LTP/BHL)	FOOTAGES
LATITUDE = 32°40'14.89" (32.670802°)	990' FSL
LONGITUDE = -104°15'28.20" (-104.257832°)	100' FWL
NAD 27 (LTP/BHL)	
LATITUDE = 32°40'14.47" (32.670686°)	
LONGITUDE = -104°15'26.36" (-104.257321°)	
STATE PLANE NAD 83 (N.M. EAST)	
N: 607776.95' E: 564569.87'	
STATE PLANE NAD 27 (N.M. EAST)	
N: 607714.98' E: 523390.22'	

Sante Fe Main Office Phone: (505) 476-3441 General Information

Phone: (505) 629-6116
Online Phone Directory
https://www.emnrd.nm.gov/ocd/contact-us

# State of New Mexico Energy, Minerals and Natural Resources Oil Conservation Division 1220 S. St Francis Dr. Santa Fe, NM 87505

Form APD Conditions

Permit 402129

#### PERMIT CONDITIONS OF APPROVAL

Operator Name and Address:	API Number:
Permian Resources Operating, LLC [372165]	30-015-57444
300 N. Marienfeld St Ste 1000	Well:
Midland, TX 79701	ALPINE 7 11 STATE #124H

OCD Reviewer	Condition
jeffrey.harrison	No additives containing PFAS chemicals will be added to the drilling fluids or completion fluids used during drilling, completions, or recompletions operations.
jeffrey.harrison	All logs run on the well must be submitted to NMOCD.
jeffrey.harrison	Cement is required to circulate on both surface and intermediate1 strings of casing.
jeffrey.harrison	If cement does not circulate on any string, a Cement Bond Log (CBL) is required for that string of casing.
jeffrey.harrison	A [C-103] Sub. Drilling (C-103N) is required within (10) days of spud.
jeffrey.harrison	Notify the OCD 24 hours prior to casing & cement.
jeffrey.harrison	File As Drilled C-102 and a directional Survey with C-104 completion packet.
	Once the well is spud, to prevent ground water contamination through whole or partial conduits from the surface, the operator shall drill without interruption through the fresh water zone or zones and shall immediately set in cement the water protection string.
jeffrey.harrison	Oil base muds are not to be used until fresh water zones are cased and cemented providing isolation from the oil or diesel. This includes synthetic oils. Oil based mud, drilling fluids and solids must be contained in a steel closed loop system.

# Permian Resources - Alpine 7-11 State 124H

# 1. Geologic Formations

Formation	Elevation	TVD	Lithology	Target
Rustler	-3452	110	Sandstone	No
Top of Salt	-3292	270	Salt	No
Tansill	-3107	455	Anhydrite/Shale	No
Yates	-2992	570	Anhydrite/Shale	No
Seven Rivers	-2612	950	Limestone	No
Queen	-2052	1510	Limestone	No
Grayburg	-1692	1870	Limestone	No
San Andres	-1225	2337	Limestone	No
Cherry Canyon	-107	3455	Sandstone	No
Brushy Canyon	NP	NP	Sandstone	No
Bone Spring Lime	8	3570	Limestone/Shale	No
1st Bone Spring Sand	1763	5325	Sandstone/Limestone/Shale	No
2nd Bone Spring Sand	3278	6840	Sandstone/Limestone/Shale	Yes
3rd Bone Spring Sand	4688	8250	Sandstone/Limestone/Shale	No
Wolfcamp	5108	8670	Shale	No

# 2. Blowout Prevention

BOP installed and tested before drilling which hole?	Size?	Min. Required WP	Туре		x	Tested to:			
			Ann	ular	Х	2500 psi			
			Blind Ram		Х				
12.25	13-5/8"	5M	Pipe Ram		Х	5000 psi			
			Double Ram			3000 psi			
			Other*						
			Ann	ular	Х	2500 psi			
			Blind Ram		Х				
8.75	13-5/8"	5M	Pipe Ram		Pipe Ram x Double Ram		Х	5000 noi	
			Double Ram					5000 psi	
			Other*						

**Equipment**: BOPE will meet all requirements for above listed system per 43 CFR 3172. BOPE with working pressure ratings in excess of anticipated maximum surface pressure will be utilized for well control from drill out of surface casing to TMD. The system may be upgraded to a higher pressure but still tested to the working pressure listed in the table above. If the system is upgraded all of the components installed will be functional, tested, and will meet all requirements per 43 CFR 3172. The wellhead will be a multibowl speed head allowing for hangoff of intermediate casing of the surface x intermedicate annulus without breaking the connection between the BOP & wellhead. A variance is requested to utilize a flexible choke line (flexhose) from the BOP to choke manifold.

#### **Requesting Variance?** YES

Variance request: Multibowl Wellhead, Flexhose, Breaktesting, Offline Cementing Variances. Attachments in Section 8.

**Testing Procedure:** Operator requests to ONLY test broken pressure seals per API Standard 53 and the attachments in Section 8. The BOP test shall be performed before drilling out of the surface casing shoe and will occur at a minimum: a. when initially installed, b. whenever any seal subject to test pressure is broken, c. following related repairs, d. at 21-day intervals. Testing of the ram type preventer(s) and annual type preventer(s) shall be tested per 43 CFR 3172. The BOPE configuration, choke manifold layout, and accumulator system will be in compliance with 43 CFR 3172. Bleed lines will discharge 100' from wellhead in non-H2S scenarios and 150' from wellhead in H2S scenarios.

Choke Diagram Attachemnt: 5 M Choke Manifold BOP Diagram Attachment: BOP Schematic

#### 3. Casing

String	Hole Size	Casing Size	Тор	Bottom	Тор ТVD	Bottom TVD	Length	Grade	Weight	Connection	Collapse SF	Burst SF	Joint SF Type	Joint SF	Body SF Type	Body SF
Surface	17.5	13.375	0	295	0	295	295	J55	54.5	BTC	7.75	2.46	Dry	7.83	Dry	7.35
Intermediate	12.25	9.625	0	3505	0	3505	3505	J55	36	BTC	3.23	1.74	Dry	2.83	Dry	2.49
Production	8.75	5.5	0	7452	0	7077	7452	P110RY	17	Bushmaste	2.03	2.12	Dry	2.48	Dry	2.48
Production	8.5	5.5	7452	22660	7077	7077	15208	P110RY	17	Bushmaste	2.03	2.12	Dry	2.48	Dry	2.48
								BLM M	lin Saf	ety Factor	1.125	1		1.6		1.6

Non API casing spec sheets and casing design assumptions attached.

#### 4. Cement

String	Lead/Tail	Top MD	Bottom MD	Quanity (sx)	Yield	Density	Cu Ft	Excess %	Cement Type	Additives
Surface	Tail	0	295	240	1.34	14.8	310	50%	Class C	Accelerator
Intermediate	Lead	0	2800	650	2.08	12.7	1340	50%	Class C	Salt, Extender, and LCM
Intermediate	Tail	2800	3505	260	1.34	14.8	340	50%	Class C	Accelerator
Production	Lead	3005	6702	550	2.41	11.5	1320	40%	Class H	POZ, Extender, Fluid Loss, Dispersant, Retarder
Production	Tail	6702	22660	2660	1.73	12.5	4600	25%	Class H	POZ, Extender, Fluid Loss, Dispersant, Retarder

#### 5. Circulating Medium

Mud System Type: Closed

Will an air or gas system be used: No

Describe what will be on location to control well or mitigate oter conditions: Sufficient quantities of mud materials will be on the well site at all times for the purpose of assuring well control and maintaining wellbore integrity. Surface interval will employ fresh water mud. The intermediate hole will utilize a saturated brine fluid to inhibit salt washout. The production hole will employ brine based and oil base fluid to inhibit formation reactivity and of the appropriate density to maintain well control.

**Describe the mud monitoring system utilized:** Centrifuge separation system. Open tank monitoring with EDR will be used for drilling fluids and return volumes. Open tank monitoring will be used for cement and cuttings return volumes. Mud properties will be monitored at least every 24 hours using industry accepted mud check practices.

Cuttings Volume: 10770 Cu Ft

### **Circulating Medium Table**

Top Depth	Bottom Depth	Mud Type	Min Weight	Max Weight
0	295	Spud Mud	8.6	9.5
295	3505	Salt Saturated	10	10
3505	19038	Oil Based Mud	9	10

# 6. Test, Logging, Coring

List of production tests including testing procedures, equipment and safety measures:

Will utilize MWD/LWD from intermediate hole to TD of the well.

List of open and cased hole logs run in the well:

DIRECTIONAL SURVEY

Coring operation description for the well:

# 7. Pressure

Anticipated Bottom Hole Pressure	3690	psi
Anticipated Surface Pressure	2123.1	psi
Anticipated Bottom Hole Temperature	129	°F
Anticipated Abnormal pressure, temp, or geo hazards	No	



# **NEW MEXICO**

(SP) LEA ALPINE 7-11 ALPINE 7-11 STATE 124H

**OWB** 

Plan: PWP0

# **Standard Planning Report - Geographic**

27 October, 2025



 Database:
 Compass\_17

 Company:
 NEW MEXICO

 Project:
 (SP) LEA

 Site:
 ALPINE 7-11

Well: ALPINE 7-11 STATE 124H

Wellbore: OWB
Design: PWP0

Local Co-ordinate Reference:

TVD Reference: MD Reference: North Reference:

**Survey Calculation Method:** 

Well ALPINE 7-11 STATE 124H

KB @ 3562.2usft KB @ 3562.2usft

Grid

Minimum Curvature

Project (SP) LEA

Map System:US State Plane 1983Geo Datum:North American Datum 1983Map Zone:New Mexico Eastern Zone

System Datum:

Mean Sea Level

Site ALPINE 7-11

**Position Uncertainty** 

 Site Position:
 Northing:
 610,748.22 usft
 Latitude:
 32° 40′ 44.141 N

 From:
 Map
 Easting:
 580,182.66 usft
 Longitude:
 104° 12′ 25.497 W

 Position Uncertainty:
 0.0 usft
 Slot Radius:
 13-3/16 "

·

Well Position +N/-S 0.0 usft Northing:

 +N/-S
 0.0 usft
 Northing:
 608,274.36 usft
 Latitude:
 32° 40' 19.667 N

 +E/-W
 0.0 usft
 Easting:
 579,652.79 usft
 Longitude:
 104° 12' 31.730 W

 0.0 usft
 Wellhead Elevation:
 usft
 Ground Level:
 3,532.2 usft

Grid Convergence: 0.07 °

OWB Wellbore Declination Field Strength Magnetics **Model Name** Sample Date **Dip Angle** (°) (°) (nT) IGRF200510 12/31/2009 8.07 60.54 48.990.57506071

PWP0 Design **Audit Notes:** Version: Phase: **PROTOTYPE** Tie On Depth: 0.0 Vertical Section: Depth From (TVD) +N/-S +E/-W Direction (usft) (usft) (usft) (°) 0.0 0.0 0.0 268.11

 Plan Survey Tool Program
 Date 10/27/2025

 Depth From (usft)
 Depth To (usft)
 Tool Name
 Remarks

 1
 0.0
 22,659.9 PWP0 (OWB)
 MWD OWSG Rev2 MWD - Standar



Database: Compass\_17
Company: NEW MEXICO
Project: (SP) LEA

ALPINE 7-11 STATE 124H

RESOURCES

Project: (SP) LEA
Site: ALPINE 7-11

Wellbore: OWB
Design: PWP0

Well:

Local Co-ordinate Reference:

TVD Reference:
MD Reference:
North Reference:

**Survey Calculation Method:** 

Well ALPINE 7-11 STATE 124H

KB @ 3562.2usft KB @ 3562.2usft

Grid

Plan Sections										
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)	TFO (°)	Target
0.0	0.00	0.00	0.0	0.0	0.0	0.00	0.00	0.00	0.00	
1,200.0	0.00	0.00	1,200.0	0.0	0.0	0.00	0.00	0.00	0.00	
1,400.0	4.00	200.00	1,399.8	-6.6	-2.4	2.00	2.00	0.00	200.00	
2,200.0	4.00	200.00	2,197.9	-59.0	-21.5	0.00	0.00	0.00	0.00	
2,400.0	0.00	0.00	2,397.7	-65.6	-23.9	2.00	-2.00	0.00	180.00	
2,500.0	0.00	0.00	2,497.7	-65.6	-23.9	0.00	0.00	0.00	0.00	
3,220.5	14.41	132.77	3,210.6	-126.8	42.3	2.00	2.00	0.00	132.77	
5,921.9	14.41	132.77	5,827.1	-583.3	535.7	0.00	0.00	0.00	0.00	
6,642.4	0.00	0.00	6,540.0	-644.5	601.9	2.00	-2.00	0.00	180.00	
6,701.9	0.00	0.00	6,599.5	-644.5	601.9	0.00	0.00	0.00	0.00	
7,451.9	90.00	270.54	7,077.0	-640.0	124.5	12.00	12.00	-11.93	270.54	
22,659.9	90.00	270.54	7,077.0	-497.4	-15,082.9	0.00	0.00	0.00	0.00	LTP/BHL - ALPINE 7-



RESOURCES

 Database:
 Compass\_17

 Company:
 NEW MEXICO

 Project:
 (SP) LEA

 Site:
 ALPINE 7-11

Well: ALPINE 7-11 STATE 124H

Wellbore: OWB
Design: PWP0

Local Co-ordinate Reference:

TVD Reference: MD Reference: North Reference:

**Survey Calculation Method:** 

Well ALPINE 7-11 STATE 124H

KB @ 3562.2usft KB @ 3562.2usft

Grid

PI	anned Survey									
	Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Map Northing (usft)	Map Easting (usft)	Latitude	Longitude
	0.0	0.00	0.00	0.0	0.0	0.0	608,274.36	579,652.79	32° 40' 19.667 N	104° 12' 31.730 W
	100.0	0.00	0.00	100.0	0.0	0.0	608,274.36	579,652.79	32° 40' 19.667 N	104° 12' 31.730 W
	200.0	0.00	0.00	200.0	0.0	0.0	608,274.36	579,652.79	32° 40' 19.667 N	104° 12' 31.730 W
	300.0	0.00	0.00	300.0	0.0	0.0	608,274.36	579,652.79	32° 40' 19.667 N	104° 12' 31.730 W
	400.0	0.00	0.00	400.0	0.0	0.0	608,274.36	579,652.79	32° 40' 19.667 N	104° 12' 31.730 W
	500.0	0.00	0.00	500.0	0.0	0.0	608,274.36	579,652.79	32° 40' 19.667 N	104° 12' 31.730 W
	600.0	0.00	0.00	600.0	0.0	0.0	608,274.36	579,652.79	32° 40' 19.667 N	104° 12' 31.730 W
	700.0	0.00	0.00	700.0	0.0	0.0	608,274.36	579,652.79	32° 40′ 19.667 N	104° 12' 31.730 W
	800.0	0.00	0.00	800.0	0.0	0.0	608,274.36	579,652.79	32° 40' 19.667 N	104° 12' 31.730 W
	900.0	0.00	0.00	900.0	0.0	0.0	608,274.36	579,652.79	32° 40' 19.667 N	104° 12' 31.730 W
	1,000.0	0.00	0.00	1,000.0	0.0	0.0	608,274.36	579,652.79	32° 40' 19.667 N	104° 12' 31.730 W
	1,100.0	0.00	0.00	1,100.0	0.0	0.0	608,274.36	579,652.79	32° 40' 19.667 N	104° 12' 31.730 W
	1,200.0	0.00	0.00	1,200.0	0.0	0.0	608,274.36	579,652.79	32° 40' 19.667 N	104° 12' 31.730 W
	Start Bui	ild 2.00								
	1,300.0	2.00	200.00	1,300.0	-1.6	-0.6	608,272.72	579,652.20	32° 40' 19.651 N	104° 12' 31.737 W
	1,400.0	4.00	200.00	1,399.8	-6.6	-2.4	608,267.81	579,650.41	32° 40' 19.602 N	104° 12' 31.758 W
	Start 800	0.0 hold at 140	00.0 MD							
	1,500.0	4.00	200.00	1,499.6	-13.1	-4.8	608,261.25	579,648.02	32° 40' 19.537 N	104° 12' 31.786 W
	1,600.0	4.00	200.00	1,599.4	-19.7	-7.2	608,254.70	579,645.63	32° 40' 19.473 N	104° 12' 31.814 W
	1,700.0	4.00	200.00	1,699.1	-26.2	-9.5	608,248.14	579,643.25	32° 40' 19.408 N	104° 12' 31.842 W
	1,800.0	4.00	200.00	1,798.9	-32.8	-11.9	608,241.59	579,640.86	32° 40' 19.343 N	104° 12' 31.870 W
	1,900.0	4.00	200.00	1,898.6	-39.3	-14.3	608,235.03	579,638.48	32° 40' 19.278 N	104° 12' 31.898 W
	2,000.0	4.00	200.00	1,998.4	-45.9	-16.7	608,228.48	579,636.09	32° 40' 19.213 N	104° 12' 31.926 W
	2,100.0	4.00	200.00	2,098.1	-52.4	-19.1	608,221.92	579,633.71	32° 40' 19.148 N	104° 12' 31.954 W
	2,200.0	4.00	200.00	2,197.9	-59.0	-21.5	608,215.37	579,631.32	32° 40' 19.084 N	104° 12' 31.982 W
	Start Dro	op -2.00								
	2,300.0	2.00	200.00	2,297.7	-63.9	-23.3	608,210.45	579,629.53	32° 40' 19.035 N	104° 12' 32.003 W
	2,400.0	0.00	0.00	2,397.7	-65.6	-23.9	608,208.81	579,628.93	32° 40' 19.019 N	104° 12' 32.010 W
		0.0 hold at 240								
	2,500.0	0.00	0.00	2,497.7	-65.6	-23.9	608,208.81	579,628.93	32° 40' 19.019 N	104° 12' 32.010 W
	Start Bui	ild 2.00								
	2,600.0	2.00	132.77	2,597.7	-66.7	-22.6	608,207.62	579,630.21	32° 40' 19.007 N	104° 12' 31.995 W
	2,700.0	4.00	132.77	2,697.6	-70.3	-18.7	608,204.07	579,634.06	32° 40' 18.972 N	104° 12' 31.951 W
	2,800.0	6.00	132.77	2,797.2	-76.2	-12.3	608,198.15	579,640.45	32° 40' 18.913 N	104° 12' 31.876 W
	2,900.0	8.00	132.77	2,896.4	-84.5	-3.4	608,189.87	579,649.40	32° 40' 18.831 N	104° 12' 31.771 W
	3,000.0	10.00	132.77	2,995.2	-95.1	8.1	608,179.25	579,660.88	32° 40' 18.726 N	104° 12' 31.637 W
	3,100.0	12.00	132.77	3,093.3	-108.1	22.1	608,166.29	579,674.89	32° 40' 18.597 N	104° 12' 31.473 W
	3,200.0	14.00	132.77	3,190.8	-123.3	38.6	608,151.02	579,691.40	32° 40' 18.446 N	104° 12' 31.280 W
	3,220.5	14.41	132.77	3,210.6	-126.8	42.3	608,147.61	579,695.08	32° 40' 18.412 N	104° 12' 31.237 W
	Start 270	1.4 hold at 32	220.5 MD							
	3,300.0	14.41	132.77	3,287.7	-140.2	56.8	608,134.17	579,709.61	32° 40' 18.279 N	104° 12' 31.068 W
	3,400.0	14.41	132.77	3,384.5	-157.1	75.1	608,117.27	579,727.88	32° 40' 18.112 N	104° 12' 30.854 W
	3,500.0	14.41	132.77	3,481.4	-174.0	93.4	608,100.37	579,746.14	32° 40' 17.944 N	104° 12' 30.641 W
	3,600.0	14.41	132.77	3,578.2	-190.9	111.6	608,083.47	579,764.41	32° 40' 17.777 N	104° 12' 30.427 W
	3,700.0	14.41	132.77	3,675.1	-207.8	129.9	608,066.57	579,782.68	32° 40' 17.609 N	104° 12' 30.214 W
	3,800.0	14.41	132.77	3,771.9	-224.7	148.1	608,049.67	579,800.94	32° 40' 17.442 N	104° 12' 30.000 W
	3,900.0	14.41	132.77	3,868.8	-241.6	166.4	608,032.77	579,819.21	32° 40′ 17.274 N	104° 12' 29.787 W
	4,000.0	14.41	132.77	3,965.6	-258.5	184.7	608,015.87	579,837.48	32° 40' 17.107 N	104° 12' 29.573 W
	4,100.0	14.41	132.77	4,062.5	-275.4	202.9	607,998.97	579,855.74	32° 40′ 16.940 N	104° 12' 29.360 W
	4,200.0	14.41	132.77	4,159.3	-292.3	221.2	607,982.07	579,874.01	32° 40′ 16.772 N	104° 12' 29.146 W
	4,300.0	14.41	132.77	4,256.2	-309.2	239.5	607,965.17	579,892.27	32° 40' 16.605 N	104° 12' 28.933 W
	4,400.0	14.41	132.77	4,353.0	-326.1	257.7	607,948.27	579,910.54	32° 40′ 16.437 N	104° 12' 28.719 W
	4,500.0	14.41	132.77	4,449.9	-343.0	276.0	607,931.37	579,928.81	32° 40′ 16.270 N	104° 12' 28.506 W
L	4,600.0	14.41	132.77	4,546.8	-359.9	294.3	607,914.47	579,947.07	32° 40′ 16.102 N	104° 12' 28.292 W
=										



RESOURCES

 Database:
 Compass\_17

 Company:
 NEW MEXICO

 Project:
 (SP) LEA

 Site:
 ALPINE 7-11

Well: ALPINE 7-11 STATE 124H

Wellbore: OWB
Design: PWP0

Local Co-ordinate Reference:

TVD Reference: MD Reference: North Reference:

Survey Calculation Method:

Well ALPINE 7-11 STATE 124H

KB @ 3562.2usft KB @ 3562.2usft

Grid

4,700.0 14.41 132.77 4,643.6 -376.8 312.5 607,897.57 579,965.34 32° 40′ 15.935 N 10 4,800.0 14.41 132.77 4,740.5 -393.7 330.8 607,880.67 579,983.61 32° 40′ 15.767 N 10 4,900.0 14.41 132.77 4,837.3 -410.6 349.1 607,863.77 580,001.87 32° 40′ 15.600 N 10 5,000.0 14.41 132.77 4,934.2 -427.5 367.3 607,846.87 580,020.14 32° 40′ 15.600 N 10 5,000.0 14.41 132.77 5,031.0 444.4 385.6 607,829.97 580,038.41 32° 40′ 15.265 N 10 5,200.0 14.41 132.77 5,127.9 -461.3 403.9 607,813.07 580,056.67 32° 40′ 15.098 N 10 5,300.0 14.41 132.77 5,224.7 478.2 422.1 607,786.17 580,074.94 32° 40′ 14.763 N 10 5,400.0 14.41 132.77 5,216 -495.1 440.4 607,779.27 580,093.21 32° 40′ 14.763 N 10 5,600.0 14.41 132.77 5,418.4 -512.0 458.7 607,762.37 580,111.47 32° 40′ 14.763 N 10 5,600.0 14.41 132.77 5,615.3 -528.9 476.9 607,745.47 580,129.74 32° 40′ 14.280 N 10 5,800.0 14.41 132.77 5,615.2 -545.8 495.2 607,728.57 580,148.00 32° 40′ 14.280 N 10 5,900.0 14.41 132.77 5,615.2 -545.8 495.2 607,728.57 580,148.00 32° 40′ 14.280 N 10 5,900.0 14.41 132.77 5,805.9 -579.6 531.7 607,694.77 580,184.54 32° 40′ 14.000 N 10 5,900.0 14.41 132.77 5,805.9 -579.6 531.7 607,694.77 580,184.54 32° 40′ 14.000 N 10 5,921.9 14.41 132.77 5,805.9 -579.6 531.7 607,691.07 580,184.54 32° 40′ 13.889 N 10 5,900.0 14.41 132.77 5,805.9 -579.6 531.7 607,691.07 580,184.54 32° 40′ 13.889 N 10 5 500.0 14.41 132.77 5,805.9 -579.6 531.7 607,691.07 580,184.54 32° 40′ 13.889 N 10 5 500.0 14.41 132.77 5,805.9 -579.6 531.7 607,691.07 580,184.54 32° 40′ 13.889 N 10 5 500.0 14.41 132.77 5,805.9 -579.6 531.7 607,691.07 580,184.54 32° 40′ 13.889 N 10 5 500.0 14.41 132.77 6,909.4 -621.3 576.9 607,683.02 580,229.67 32° 40′ 13.889 N 10 5 500.0 14.41 132.77 6,909.4 -621.3 576.9 607,683.02 580,229.67 32° 40′ 13.889 N 10 5 500.0 12.85 132.77 6,909.4 -621.3 576.9 607,633.02 580,229.67 32° 40′ 13.389 N 10 6,000.0 8.85 132.77 6,999.4 -621.3 576.9 607,633.02 580,229.67 32° 40′ 13.282 N 10 6,000.0 8.85 132.77 6,999.4 -621.3 576.9 607,633.02 580,229.67 32° 40′ 13.385 N 10 6,600.0 0.85 132.77 6,999.4 -621.3 5	Longitude  04° 12' 28.079 W  04° 12' 27.865 W  04° 12' 27.439 W  04° 12' 27.225 W  04° 12' 27.012 W  04° 12' 26.798 W  04° 12' 26.585 W  04° 12' 26.371 W  04° 12' 26.158 W  04° 12' 25.944 W  04° 12' 25.731 W  04° 12' 25.517 W  04° 12' 25.471 W
4,800.0 14.41 132.77 4,740.5 -393.7 330.8 607,880.67 579,983.61 32° 40′ 15.767 N 10 4,900.0 14.41 132.77 4,837.3 -410.6 349.1 607,863.77 580,001.87 32° 40′ 15.600 N 10 5,000.0 14.41 132.77 4,934.2 -427.5 367.3 607,846.87 580,020.14 32° 40′ 15.433 N 10 5,000.0 14.41 132.77 5,031.0 -444.4 385.6 607,829.97 580,038.41 32° 40′ 15.265 N 10 5,200.0 14.41 132.77 5,127.9 -461.3 403.9 607,813.07 580,056.67 32° 40′ 15.098 N 10 5,300.0 14.41 132.77 5,224.7 478.2 422.1 607,796.17 580,074.94 32° 40′ 14.930 N 10 5,400.0 14.41 132.77 5,321.6 495.1 440.4 607,779.27 580,093.21 32° 40′ 14.763 N 10 5,500.0 14.41 132.77 5,418.4 -512.0 458.7 607,762.37 580,111.47 32° 40′ 14.595 N 10 5,500.0 14.41 132.77 5,515.3 -528.9 476.9 607,745.47 580,129.74 32° 40′ 14.260 N 10 5,700.0 14.41 132.77 5,612.2 -545.8 495.2 607,728.57 580,148.00 32° 40′ 14.260 N 10 5,800.0 14.41 132.77 5,605.9 -579.6 531.7 607,694.77 580,184.54 32° 40′ 14.260 N 10 5,900.0 14.41 132.77 5,827.1 -583.3 535.7 607,694.77 580,184.54 32° 40′ 13.289 N 10 5,900.0 14.41 132.77 5,827.1 -583.3 535.7 607,694.77 580,184.54 32° 40′ 13.289 N 10 5,900.0 14.41 132.77 5,827.1 -583.3 535.7 607,694.77 580,185.54 32° 40′ 13.280 N 10 6,000.0 10.85 132.77 6,000.8 -609.7 564.3 607,664.63 580,221.12 32° 40′ 13.520 N 10 6,200.0 8.85 132.77 6,009.4 -621.3 576.9 607,693.02 580,229.67 32° 40′ 13.520 N 10 6,300.0 6.85 132.77 6,198.4 -630.6 586.9 607,638.2 580,221.1 32° 40′ 13.220 N 10 6,400.0 4.85 132.77 6,198.4 -630.6 586.9 607,638.2 580,221.17 32° 40′ 13.320 N 10 6,600.0 0.85 132.77 6,198.4 -630.6 586.9 607,638.2 580,221.17 32° 40′ 13.320 N 10 6,600.0 0.85 132.77 6,198.4 -630.6 586.9 607,632.27 580,229.67 32° 40′ 13.320 N 10 6,600.0 0.85 132.77 6,497.6 -644.3 601.7 607,630.08 580,254.69 32° 40′ 13.282 N 10 6,600.0 0.85 132.77 6,497.6 -644.3 601.7 607,630.08 580,254.69 32° 40′ 13.282 N 10 6,600.0 0.85 132.77 6,497.6 -644.3 601.7 607,630.08 580,254.69 32° 40′ 13.282 N 10 6,600.0 0.85 132.77 6,497.6 -644.3 601.7 607,630.08 580,254.69 32° 40′ 13.282 N 10 6,600.0 0.85 132.77 6,497.6 -644.5 601.9 607,	04° 12' 27.865 W 04° 12' 27.652 W 04° 12' 27.439 W 04° 12' 27.225 W 04° 12' 27.012 W 04° 12' 26.798 W 04° 12' 26.585 W 04° 12' 26.371 W 04° 12' 26.158 W 04° 12' 25.731 W 04° 12' 25.731 W 04° 12' 25.517 W
4,800.0 14.41 132.77 4,740.5 -393.7 330.8 607,880.67 579,983.61 32° 40′ 15.767 N 10 4,900.0 14.41 132.77 4,837.3 -410.6 349.1 607,863.77 580,001.87 32° 40′ 15.600 N 10 5,000.0 14.41 132.77 4,934.2 -427.5 367.3 607,846.87 580,020.14 32° 40′ 15.433 N 10 5,000.0 14.41 132.77 5,031.0 -444.4 385.6 607,829.97 580,038.41 32° 40′ 15.265 N 10 5,200.0 14.41 132.77 5,127.9 -461.3 403.9 607,813.07 580,056.67 32° 40′ 15.098 N 10 5,300.0 14.41 132.77 5,224.7 478.2 422.1 607,796.17 580,074.94 32° 40′ 14.930 N 10 5,400.0 14.41 132.77 5,321.6 495.1 440.4 607,779.27 580,093.21 32° 40′ 14.763 N 10 5,500.0 14.41 132.77 5,418.4 -512.0 458.7 607,762.37 580,111.47 32° 40′ 14.595 N 10 5,500.0 14.41 132.77 5,515.3 -528.9 476.9 607,745.47 580,129.74 32° 40′ 14.260 N 10 5,800.0 14.41 132.77 5,612.2 -545.8 495.2 607,728.57 580,148.00 32° 40′ 14.260 N 10 5,800.0 14.41 132.77 5,612.2 -545.8 495.2 607,728.57 580,148.00 32° 40′ 14.260 N 10 5,800.0 14.41 132.77 5,827.1 -583.3 535.7 607,691.07 580,148.54 32° 40′ 13.926 N 10 5,900.0 14.41 132.77 5,827.1 -583.3 535.7 607,691.07 580,148.54 32° 40′ 13.289 N 10 5,900.0 14.41 132.77 5,827.1 -583.3 535.7 607,691.07 580,148.54 32° 40′ 13.280 N 10 5,900.0 14.41 132.77 5,827.1 -583.3 535.7 607,691.07 580,148.54 32° 40′ 13.280 N 10 5,900.0 14.41 132.77 6,909.4 -621.3 576.9 607,694.77 580,188.54 32° 40′ 13.280 N 10 6,000.0 12.85 132.77 6,009.8 -609.7 564.3 607,664.63 580,220.5 32° 40′ 13.657 N 10 6,300.0 6.85 132.77 6,009.4 -621.3 576.9 607,653.02 580,229.67 32° 40′ 13.512 N 10 6,300.0 6.85 132.77 6,198.4 -630.6 586.9 607,633.27 580,229.67 32° 40′ 13.351 N 10 6,600.0 0.85 132.77 6,499.9 -637.5 594.4 607,636.82 580,247.17 32° 40′ 13.320 N 10 6,600.0 0.85 132.77 6,499.9 -637.5 594.4 607,630.8 580,247.17 32° 40′ 13.320 N 10 6,600.0 0.85 132.77 6,499.9 -637.5 594.4 607,630.8 580,254.69 32° 40′ 13.320 N 10 6,600.0 0.85 132.77 6,499.6 -644.3 601.7 607,630.08 580,254.69 32° 40′ 13.282 N 10 6,600.0 0.85 132.77 6,497.6 -644.3 601.7 607,630.8 580,254.69 32° 40′ 13.282 N 10 6,600.0 0.85 132.77 6,497.6 -644.5 601.9 60	04° 12' 27.865 W 04° 12' 27.652 W 04° 12' 27.439 W 04° 12' 27.225 W 04° 12' 27.012 W 04° 12' 26.798 W 04° 12' 26.585 W 04° 12' 26.371 W 04° 12' 26.158 W 04° 12' 25.731 W 04° 12' 25.731 W 04° 12' 25.517 W
4,900.0 14.41 132.77 4,837.3 -410.6 349.1 607,863.77 580,001.87 32° 40′ 15.600 N 10 5,000.0 14.41 132.77 4,934.2 -427.5 367.3 607,846.87 580,020.14 32° 40′ 15.433 N 10 5,100.0 14.41 132.77 5,031.0 -444.4 385.6 607,829.97 580,038.41 32° 40′ 15.265 N 10 5,200.0 14.41 132.77 5,127.9 -461.3 403.9 607,829.97 580,038.41 32° 40′ 15.098 N 10 5,300.0 14.41 132.77 5,224.7 -478.2 422.1 607,796.17 580,074.94 32° 40′ 14.930 N 10 5,400.0 14.41 132.77 5,321.6 -495.1 440.4 607,7792.7 580,093.21 32° 40′ 14.763 N 10 5,500.0 14.41 132.77 5,418.4 -512.0 458.7 607,762.37 580,111.47 32° 40′ 14.763 N 10 5,500.0 14.41 132.77 5,515.3 -528.9 476.9 607,745.47 580,129.74 32° 40′ 14.260 N 10 5,700.0 14.41 132.77 5,612.2 -545.8 495.2 607,728.57 580,148.00 32° 40′ 14.260 N 10 5,800.0 14.41 132.77 5,612.2 -545.8 495.2 607,728.57 580,148.00 32° 40′ 14.260 N 10 5,800.0 14.41 132.77 5,709.0 -562.7 513.5 607,711.67 580,166.27 32° 40′ 14.093 N 10 5,900.0 14.41 132.77 5,805.9 -579.6 531.7 607,694.77 580,184.54 32° 40′ 13.889 N 10 5,900.0 14.41 132.77 5,805.9 -579.6 531.7 607,694.77 580,184.54 32° 40′ 13.926 N 10 5,901.0 14.41 132.77 5,805.9 -579.6 531.7 607,694.77 580,184.54 32° 40′ 13.889 N 10 5,901.0 14.41 132.77 6,909.4 -621.3 576.9 607,694.77 580,202.05 32° 40′ 13.627 N 10 6,000.0 12.85 132.77 6,099.4 -621.3 576.9 607,664.63 580,217.12 32° 40′ 13.627 N 10 6,200.0 8.85 132.77 6,099.4 -621.3 576.9 607,664.63 580,217.12 32° 40′ 13.627 N 10 6,400.0 4.85 132.77 6,999.4 -621.3 576.9 607,664.63 580,229.67 32° 40′ 13.351 N 10 6,400.0 4.85 132.77 6,999.9 -637.5 594.4 607,636.82 580,229.67 32° 40′ 13.326 N 10 6,400.0 0.85 132.77 6,997.9 -637.5 594.4 607,636.82 580,254.69 32° 40′ 13.328 N 10 6,600.0 0.85 132.77 6,497.6 -644.3 601.7 607,630.8 580,254.69 32° 40′ 13.282 N 10 6,600.0 0.85 132.77 6,497.6 -644.3 601.7 607,630.8 580,254.69 32° 40′ 13.282 N 10 6,600.0 0.85 132.77 6,497.6 -644.3 601.7 607,630.8 580,254.69 32° 40′ 13.282 N 10 6,600.0 0.85 132.77 6,497.6 -644.5 601.9 607,629.86 580,254.69 32° 40′ 13.282 N 10 6,600.0 0.65 132.77 6,497.6 -644.5 601.9	04° 12' 27.439 W 04° 12' 27.225 W 04° 12' 27.012 W 04° 12' 26.798 W 04° 12' 26.585 W 04° 12' 26.371 W 04° 12' 26.158 W 04° 12' 25.944 W 04° 12' 25.731 W 04° 12' 25.517 W
5,100.0         14.41         132.77         5,031.0         -444.4         385.6         607,829.97         580,038.41         32° 40' 15.265 N         10           5,200.0         14.41         132.77         5,127.9         -461.3         403.9         607,813.07         580,056.67         32° 40' 15.098 N         10           5,300.0         14.41         132.77         5,224.7         -478.2         422.1         607,796.17         580,074.94         32° 40' 14.930 N         10           5,500.0         14.41         132.77         5,216.6         -495.1         440.4         607,792.7         580,093.21         32° 40' 14.763 N         10           5,600.0         14.41         132.77         5,418.4         -512.0         458.7         607,762.37         580,111.47         32° 40' 14.763 N         10           5,600.0         14.41         132.77         5,515.3         -528.9         476.9         607,745.47         580,129.74         32° 40' 14.260 N         10           5,700.0         14.41         132.77         5,612.2         -545.8         495.2         607,728.57         580,148.00         32° 40' 14.260 N         10           5,800.0         14.41         132.77         5,709.0         -562.7	04° 12' 27.225 W 04° 12' 27.012 W 04° 12' 26.798 W 04° 12' 26.585 W 04° 12' 26.371 W 04° 12' 26.158 W 04° 12' 25.944 W 04° 12' 25.731 W 04° 12' 25.517 W
5,200.0         14.41         132.77         5,127.9         -461.3         403.9         607,813.07         580,056.67         32° 40' 15.098 N         10           5,300.0         14.41         132.77         5,224.7         -478.2         422.1         607,796.17         580,074.94         32° 40' 14.930 N         10           5,400.0         14.41         132.77         5,321.6         -495.1         440.4         607,792.7         580,093.21         32° 40' 14.763 N         10           5,500.0         14.41         132.77         5,418.4         -512.0         458.7         607,762.37         580,111.47         32° 40' 14.269 N         10           5,600.0         14.41         132.77         5,515.3         -528.9         476.9         607,745.47         580,129.74         32° 40' 14.260 N         10           5,700.0         14.41         132.77         5,612.2         -548.8         495.2         607,728.57         580,148.00         32° 40' 14.260 N         10           5,800.0         14.41         132.77         5,709.0         -562.7         513.5         607,711.67         580,184.54         32° 40' 14.260 N         10           5,921.9         14.41         132.77         5,805.9         -579.6	04° 12' 27.012 W 04° 12' 26.798 W 04° 12' 26.585 W 04° 12' 26.371 W 04° 12' 26.158 W 04° 12' 25.944 W 04° 12' 25.731 W 04° 12' 25.517 W
5,300.0       14.41       132.77       5,224.7       -478.2       422.1       607,796.17       580,074.94       32° 40' 14.930 N       10         5,400.0       14.41       132.77       5,321.6       -495.1       440.4       607,779.27       580,093.21       32° 40' 14.763 N       10         5,500.0       14.41       132.77       5,418.4       -512.0       458.7       607,745.47       580,111.47       32° 40' 14.595 N       10         5,600.0       14.41       132.77       5,515.3       -528.9       476.9       607,745.47       580,129.74       32° 40' 14.28 N       10         5,700.0       14.41       132.77       5,612.2       -545.8       495.2       607,728.57       580,148.00       32° 40' 14.093 N       10         5,800.0       14.41       132.77       5,709.0       -562.7       513.5       607,711.67       580,166.27       32° 40' 14.093 N       10         5,901.0       14.41       132.77       5,805.9       -579.6       531.7       607,694.77       580,184.54       32° 40' 13.926 N       10         5,921.9       14.41       132.77       5,805.9       -579.6       531.7       607,691.07       580,188.54       32° 40' 13.889 N       10	04° 12' 26.798 W 04° 12' 26.585 W 04° 12' 26.371 W 04° 12' 26.158 W 04° 12' 25.944 W 04° 12' 25.731 W 04° 12' 25.517 W
5,400.0       14.41       132.77       5,321.6       -495.1       440.4       607,779.27       580,093.21       32° 40' 14.763 N       10         5,500.0       14.41       132.77       5,418.4       -512.0       458.7       607,762.37       580,111.47       32° 40' 14.595 N       10         5,600.0       14.41       132.77       5,515.3       -528.9       476.9       607,745.47       580,129.74       32° 40' 14.428 N       10         5,700.0       14.41       132.77       5,612.2       -545.8       495.2       607,728.57       580,148.00       32° 40' 14.260 N       10         5,800.0       14.41       132.77       5,605.9       -562.7       513.5       607,711.67       580,166.27       32° 40' 14.093 N       10         5,900.0       14.41       132.77       5,805.9       -579.6       531.7       607,694.77       580,184.54       32° 40' 13.926 N       10         5,921.9       14.41       132.77       5,827.1       -583.3       535.7       607,691.07       580,188.54       32° 40' 13.889 N       10         Start Drop -2.00         6,000.0       12.85       132.77       5,903.0       -595.8       549.3       607,678.57       580,202.05       <	04° 12' 26.585 W 04° 12' 26.371 W 04° 12' 26.158 W 04° 12' 25.944 W 04° 12' 25.731 W 04° 12' 25.517 W
5,500.0 14.41 132.77 5,418.4 -512.0 458.7 607,762.37 580,111.47 32° 40′ 14.595 N 10 5,600.0 14.41 132.77 5,515.3 -528.9 476.9 607,745.47 580,129.74 32° 40′ 14.428 N 10 5,700.0 14.41 132.77 5,612.2 -545.8 495.2 607,728.57 580,148.00 32° 40′ 14.260 N 10 5,800.0 14.41 132.77 5,709.0 -562.7 513.5 607,711.67 580,166.27 32° 40′ 14.093 N 10 5,900.0 14.41 132.77 5,805.9 -579.6 531.7 607,694.77 580,184.54 32° 40′ 13.926 N 10 5,921.9 14.41 132.77 5,827.1 -583.3 535.7 607,691.07 580,188.54 32° 40′ 13.889 N 10 54 10 10 10 10 10 10 10 10 10 10 10 10 10	04° 12' 26.371 W 04° 12' 26.158 W 04° 12' 25.944 W 04° 12' 25.731 W 04° 12' 25.517 W
5,600.0       14.41       132.77       5,515.3       -528.9       476.9       607,745.47       580,129.74       32° 40′ 14.428 N       10         5,700.0       14.41       132.77       5,612.2       -545.8       495.2       607,728.57       580,148.00       32° 40′ 14.260 N       10         5,800.0       14.41       132.77       5,709.0       -562.7       513.5       607,711.67       580,166.27       32° 40′ 13.926 N       10         5,900.0       14.41       132.77       5,805.9       -579.6       531.7       607,694.77       580,184.54       32° 40′ 13.926 N       10         5,921.9       14.41       132.77       5,805.9       -579.6       531.7       607,691.07       580,184.54       32° 40′ 13.926 N       10         Start Drop -2.00         Start Drop -2.00         6,000.0       12.85       132.77       5,903.0       -595.8       549.3       607,678.57       580,202.05       32° 40′ 13.765 N       10         6,100.0       10.85       132.77       6,000.8       -609.7       564.3       607,678.57       580,202.05       32° 40′ 13.762 N       10         6,200.0       8.85       132.77       6,009.4       -621.3       576.9 <td>04° 12' 26.158 W 04° 12' 25.944 W 04° 12' 25.731 W 04° 12' 25.517 W</td>	04° 12' 26.158 W 04° 12' 25.944 W 04° 12' 25.731 W 04° 12' 25.517 W
5,700.0       14.41       132.77       5,612.2       -545.8       495.2       607,728.57       580,148.00       32° 40' 14.260 N       10         5,800.0       14.41       132.77       5,709.0       -562.7       513.5       607,711.67       580,166.27       32° 40' 14.093 N       10         5,900.0       14.41       132.77       5,805.9       -579.6       531.7       607,694.77       580,184.54       32° 40' 13.926 N       10         5,921.9       14.41       132.77       5,827.1       -583.3       535.7       607,691.07       580,184.54       32° 40' 13.889 N       10         Start Drop -2.00         6,000.0       12.85       132.77       5,903.0       -595.8       549.3       607,678.57       580,202.05       32° 40' 13.765 N       10         6,100.0       10.85       132.77       6,000.8       -609.7       564.3       607,678.57       580,202.05       32° 40' 13.627 N       10         6,200.0       8.85       132.77       6,099.4       -621.3       576.9       607,653.02       580,229.67       32° 40' 13.512 N       10         6,300.0       6.85       132.77       6,198.4       -630.6       586.9       607,643.74       580,239.69 <td< td=""><td>04° 12' 25.944 W 04° 12' 25.731 W 04° 12' 25.517 W</td></td<>	04° 12' 25.944 W 04° 12' 25.731 W 04° 12' 25.517 W
5,800.0       14.41       132.77       5,709.0       -562.7       513.5       607,711.67       580,166.27       32° 40' 14.093 N       10         5,900.0       14.41       132.77       5,805.9       -579.6       531.7       607,694.77       580,184.54       32° 40' 13.926 N       10         5,921.9       14.41       132.77       5,827.1       -583.3       535.7       607,691.07       580,188.54       32° 40' 13.889 N       10         Start Drop -2.00         6,000.0       12.85       132.77       5,903.0       -595.8       549.3       607,678.57       580,202.05       32° 40' 13.765 N       10         6,100.0       10.85       132.77       6,000.8       -609.7       564.3       607,664.63       580,217.12       32° 40' 13.627 N       10         6,200.0       8.85       132.77       6,099.4       -621.3       576.9       607,653.02       580,229.67       32° 40' 13.512 N       10         6,300.0       6.85       132.77       6,198.4       -630.6       586.9       607,643.74       580,239.69       32° 40' 13.351 N       10         6,500.0       2.85       132.77       6,297.9       -637.5       594.4       607,636.82       580,254.46	04° 12' 25.731 W 04° 12' 25.517 W
5,900.0       14.41       132.77       5,805.9       -579.6       531.7       607,694.77       580,184.54       32° 40' 13.926 N       10         5,921.9       14.41       132.77       5,827.1       -583.3       535.7       607,691.07       580,188.54       32° 40' 13.889 N       10         Start Drop -2.00         6,000.0       12.85       132.77       5,903.0       -595.8       549.3       607,678.57       580,202.05       32° 40' 13.765 N       10         6,100.0       10.85       132.77       6,000.8       -609.7       564.3       607,664.63       580,217.12       32° 40' 13.627 N       10         6,200.0       8.85       132.77       6,099.4       -621.3       576.9       607,653.02       580,229.67       32° 40' 13.512 N       10         6,300.0       6.85       132.77       6,198.4       -630.6       586.9       607,643.74       580,239.69       32° 40' 13.420 N       10         6,400.0       4.85       132.77       6,297.9       -637.5       594.4       607,636.82       580,247.17       32° 40' 13.351 N       10         6,500.0       2.85       132.77       6,497.6       -642.1       599.3       607,632.27       580,254.46       3	04° 12' 25.517 W
5,921.9       14.41       132.77       5,827.1       -583.3       535.7       607,691.07       580,188.54       32° 40' 13.889 N       10         Start Drop -2.00         6,000.0       12.85       132.77       5,903.0       -595.8       549.3       607,678.57       580,202.05       32° 40' 13.765 N       10         6,100.0       10.85       132.77       6,000.8       -609.7       564.3       607,664.63       580,217.12       32° 40' 13.627 N       10         6,200.0       8.85       132.77       6,099.4       -621.3       576.9       607,653.02       580,229.67       32° 40' 13.512 N       10         6,300.0       6.85       132.77       6,198.4       -630.6       586.9       607,643.74       580,239.69       32° 40' 13.420 N       10         6,400.0       4.85       132.77       6,297.9       -637.5       594.4       607,636.82       580,247.17       32° 40' 13.351 N       10         6,500.0       2.85       132.77       6,397.7       -642.1       599.3       607,632.27       580,252.10       32° 40' 13.285 N       10         6,600.0       0.85       132.77       6,497.6       -644.3       601.7       607,630.08       580,254.69       32	
Start Drop -2.00           6,000.0         12.85         132.77         5,903.0         -595.8         549.3         607,678.57         580,202.05         32° 40' 13.765 N         10           6,100.0         10.85         132.77         6,000.8         -609.7         564.3         607,664.63         580,217.12         32° 40' 13.627 N         10           6,200.0         8.85         132.77         6,099.4         -621.3         576.9         607,653.02         580,229.67         32° 40' 13.512 N         10           6,300.0         6.85         132.77         6,198.4         -630.6         586.9         607,643.74         580,239.69         32° 40' 13.420 N         10           6,400.0         4.85         132.77         6,297.9         -637.5         594.4         607,636.82         580,247.17         32° 40' 13.351 N         10           6,500.0         2.85         132.77         6,397.7         -642.1         599.3         607,632.27         580,252.10         32° 40' 13.306 N         10           6,600.0         0.85         132.77         6,497.6         -644.3         601.7         607,630.08         580,254.46         32° 40' 13.285 N         10           6,642.4         0.00         0.00<	)4° 12' 25.471 W
6,000.0 12.85 132.77 5,903.0 -595.8 549.3 607,678.57 580,202.05 32° 40' 13.765 N 10 6,100.0 10.85 132.77 6,000.8 -609.7 564.3 607,664.63 580,217.12 32° 40' 13.627 N 10 6,200.0 8.85 132.77 6,099.4 -621.3 576.9 607,653.02 580,229.67 32° 40' 13.512 N 10 6,300.0 6.85 132.77 6,198.4 -630.6 586.9 607,643.74 580,239.69 32° 40' 13.420 N 10 6,400.0 4.85 132.77 6,297.9 -637.5 594.4 607,636.82 580,247.17 32° 40' 13.351 N 10 6,500.0 2.85 132.77 6,397.7 -642.1 599.3 607,632.27 580,252.10 32° 40' 13.306 N 10 6,600.0 0.85 132.77 6,497.6 -644.3 601.7 607,630.08 580,254.46 32° 40' 13.285 N 10 6,642.4 0.00 0.00 6,540.0 -644.5 601.9 607,629.86 580,254.69 32° 40' 13.282 N 10 Start 59.5 hold at 6642.4 MD	
6,100.0 10.85 132.77 6,000.8 -609.7 564.3 607,664.63 580,217.12 32° 40' 13.627 N 10 6,200.0 8.85 132.77 6,099.4 -621.3 576.9 607,653.02 580,229.67 32° 40' 13.512 N 10 6,300.0 6.85 132.77 6,198.4 -630.6 586.9 607,643.74 580,239.69 32° 40' 13.420 N 10 6,400.0 4.85 132.77 6,297.9 -637.5 594.4 607,636.82 580,247.17 32° 40' 13.351 N 10 6,500.0 2.85 132.77 6,397.7 -642.1 599.3 607,632.27 580,252.10 32° 40' 13.306 N 10 6,600.0 0.85 132.77 6,497.6 -644.3 601.7 607,630.08 580,254.46 32° 40' 13.285 N 10 6,642.4 0.00 0.00 6,540.0 -644.5 601.9 607,629.86 580,254.69 32° 40' 13.282 N 10 5tart 59.5 hold at 6642.4 MD 6,701.9 0.00 0.00 6,599.5 -644.5 601.9 607,629.86 580,254.69 32° 40' 13.282 N 10	
6,200.0 8.85 132.77 6,099.4 -621.3 576.9 607,653.02 580,229.67 32° 40' 13.512 N 10 6,300.0 6.85 132.77 6,198.4 -630.6 586.9 607,643.74 580,239.69 32° 40' 13.420 N 10 6,400.0 4.85 132.77 6,297.9 -637.5 594.4 607,636.82 580,247.17 32° 40' 13.351 N 10 6,500.0 2.85 132.77 6,397.7 -642.1 599.3 607,632.27 580,252.10 32° 40' 13.306 N 10 6,600.0 0.85 132.77 6,497.6 -644.3 601.7 607,630.08 580,254.46 32° 40' 13.285 N 10 6,642.4 0.00 0.00 6,540.0 -644.5 601.9 607,629.86 580,254.69 32° 40' 13.282 N 10 5tart 59.5 hold at 6642.4 MD 6,701.9 0.00 0.00 6,599.5 -644.5 601.9 607,629.86 580,254.69 32° 40' 13.282 N 10	04° 12' 25.313 W
6,300.0 6.85 132.77 6,198.4 -630.6 586.9 607,643.74 580,239.69 32° 40' 13.420 N 10 6,400.0 4.85 132.77 6,297.9 -637.5 594.4 607,636.82 580,247.17 32° 40' 13.351 N 10 6,500.0 2.85 132.77 6,397.7 -642.1 599.3 607,632.27 580,252.10 32° 40' 13.306 N 10 6,600.0 0.85 132.77 6,497.6 -644.3 601.7 607,630.08 580,254.46 32° 40' 13.285 N 10 6,642.4 0.00 0.00 6,540.0 -644.5 601.9 607,629.86 580,254.69 32° 40' 13.282 N 10 Start 59.5 hold at 6642.4 MD 6,701.9 0.00 0.00 6,599.5 -644.5 601.9 607,629.86 580,254.69 32° 40' 13.282 N 10	04° 12' 25.137 W
6,400.0 4.85 132.77 6,297.9 -637.5 594.4 607,636.82 580,247.17 32° 40' 13.351 N 10 6,500.0 2.85 132.77 6,397.7 -642.1 599.3 607,632.27 580,252.10 32° 40' 13.306 N 10 6,600.0 0.85 132.77 6,497.6 -644.3 601.7 607,630.08 580,254.46 32° 40' 13.285 N 10 6,642.4 0.00 0.00 6,540.0 -644.5 601.9 607,629.86 580,254.69 32° 40' 13.282 N 10 Start 59.5 hold at 6642.4 MD 6,701.9 0.00 0.00 6,599.5 -644.5 601.9 607,629.86 580,254.69 32° 40' 13.282 N 10	04° 12' 24.990 W
6,500.0 2.85 132.77 6,397.7 -642.1 599.3 607,632.27 580,252.10 32° 40' 13.306 N 10 6,600.0 0.85 132.77 6,497.6 -644.3 601.7 607,630.08 580,254.46 32° 40' 13.285 N 10 6,642.4 0.00 0.00 6,540.0 -644.5 601.9 607,629.86 580,254.69 32° 40' 13.282 N 10 Start 59.5 hold at 6642.4 MD 6,701.9 0.00 0.00 6,599.5 -644.5 601.9 607,629.86 580,254.69 32° 40' 13.282 N 10	04° 12' 24.873 W
6,600.0 0.85 132.77 6,497.6 -644.3 601.7 607,630.08 580,254.46 32° 40' 13.285 N 10 6,642.4 0.00 0.00 6,540.0 -644.5 601.9 607,629.86 580,254.69 32° 40' 13.282 N 10   Start 59.5 hold at 6642.4 MD 6,701.9 0.00 0.00 6,599.5 -644.5 601.9 607,629.86 580,254.69 32° 40' 13.282 N 10	04° 12' 24.785 W
6,642.4 0.00 0.00 6,540.0 -644.5 601.9 607,629.86 580,254.69 32° 40' 13.282 N 10  Start 59.5 hold at 6642.4 MD  6,701.9 0.00 0.00 6,599.5 -644.5 601.9 607,629.86 580,254.69 32° 40' 13.282 N 10	04° 12' 24.728 W
Start 59.5 hold at 6642.4 MD         6,701.9       0.00       0.00       6,599.5       -644.5       601.9       607,629.86       580,254.69       32° 40' 13.282 N       10	04° 12' 24.700 W
6,701.9 0.00 0.00 6,599.5 -644.5 601.9 607,629.86 580,254.69 32° 40' 13.282 N 10	04° 12' 24.697 W
	04° 12' 24.697 W
Start DLS 12.00 TFO 270.54	
	04° 12' 24.704 W
	04° 12' 24.726 W
	04° 12' 24.763 W
	04° 12' 24.815 W
	)4° 12' 24.882 W )4° 12' 24.964 W
	04° 12' 25.061 W
	04° 12' 25.061 W
	04° 12' 25.296 W
	04° 12' 25.435 W
	04° 12' 25.587 W
	04° 12' 25.751 W
	04° 12' 25.928 W
	04° 12' 26.117 W
FTP - ALPINE 7-11 ST 124H	, 12 20
	04° 12' 26.318 W
· · · · · · · · · · · · · · · · · · ·	04° 12' 26.529 W
	04° 12' 26.751 W
	04° 12' 26.982 W
	04° 12' 27.222 W
	04° 12' 27.471 W
	04° 12' 27.728 W
	04° 12' 27.991 W
	04° 12' 28.261 W
	04° 12' 28.536 W
	04° 12' 28.816 W
	04° 12' 29.100 W
7,375.0 80.77 270.54 7,070.8 -640.7 201.0 607,633.62 579,853.81 32° 40' 13.324 N 10	77 12 23.100 W



RESOURCES

 Database:
 Compass\_17

 Company:
 NEW MEXICO

 Project:
 (SP) LEA

 Site:
 ALPINE 7-11

Well: ALPINE 7-11 STATE 124H

Wellbore: OWB
Design: PWP0

Local Co-ordinate Reference:

TVD Reference: MD Reference: North Reference:

**Survey Calculation Method:** 

Well ALPINE 7-11 STATE 124H

KB @ 3562.2usft KB @ 3562.2usft

Grid

Design.	FVVF								
Planned Survey									
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Map Northing (usft)	Map Easting (usft)	Latitude	Longitude
7 400 0			7.074.4			007 000 00	570 000 04	32° 40′ 13.327 N	
7,400.0 7,425.0	83.77 86.77	270.54 270.54	7,074.1 7,076.2	-640.5 -640.3	176.2 151.3	607,633.86 607,634.09	579,829.04 579,804.13	32° 40′ 13.330 N	104° 12' 29.677 W 104° 12' 29.969 W
7,423.0	90.00	270.54	7,076.2	-640.0	124.5	607,634.34	579,777.25	32° 40′ 13.332 N	104° 12' 30.283 W
	208.0 hold at 7		7,077.0	-040.0	124.0	007,004.04	519,111.25	32 40 13.332 N	104 12 30.203 W
7,500.0	90.00	270.54	7,077.0	-639.6	76.4	607.634.79	579,729.15	32° 40' 13.337 N	104° 12' 30.846 W
7,600.0	90.00	270.54	7,077.0	-638.6	-23.6	607,635.73	579,629.15	32° 40' 13.348 N	104° 12' 32.016 W
7,700.0	90.00	270.54	7,077.0	-637.7	-123.6	607,636.67	579,529.16	32° 40' 13.358 N	104° 12' 33.186 W
7,800.0	90.00	270.54	7,077.0	-636.8	-223.6	607,637.61	579,429.16	32° 40' 13.369 N	104° 12' 34.355 W
7,900.0	90.00	270.54	7,077.0	-635.8	-323.6	607,638.54	579,329.17	32° 40' 13.379 N	104° 12' 35.525 W
8,000.0	90.00	270.54	7,077.0	-634.9	-423.6	607,639.48	579,229.17	32° 40' 13.390 N	104° 12' 36.695 W
8,100.0	90.00	270.54	7,077.0	-633.9	-523.6	607,640.42	579,129.18	32° 40′ 13.400 N	104° 12' 37.865 W
8,200.0	90.00	270.54	7,077.0	-633.0	-623.6	607,641.36	579,029.18	32° 40′ 13.410 N	104° 12' 39.035 W
8,300.0	90.00	270.54	7,077.0	-632.1	-723.6	607,642.29	578,929.18	32° 40′ 13.421 N	104° 12' 40.205 W
8,400.0	90.00	270.54	7,077.0	-631.1	-823.6	607,643.23	578,829.19	32° 40' 13.431 N	104° 12' 41.375 W
8,500.0	90.00	270.54	7,077.0	-630.2	-923.6	607,644.17	578,729.19	32° 40' 13.442 N	104° 12' 42.544 W
8,600.0	90.00	270.54	7,077.0	-629.3	-1,023.6	607,645.11	578,629.20	32° 40' 13.452 N	104° 12' 43.714 W
8,700.0	90.00	270.54	7,077.0	-628.3	-1,123.6	607,646.04	578,529.20	32° 40' 13.462 N	104° 12' 44.884 W
8,800.0	90.00	270.54	7,077.0	-627.4	-1,223.6	607,646.98	578,429.21	32° 40' 13.473 N	104° 12' 46.054 W
8,900.0	90.00	270.54	7,077.0	-626.4	-1,323.6	607,647.92	578,329.21	32° 40' 13.483 N	104° 12' 47.224 W
9,000.0 9,100.0	90.00 90.00	270.54 270.54	7,077.0 7,077.0	-625.5 -624.6	-1,423.6 -1,523.6	607,648.86 607,649.80	578,229.21 578,129.22	32° 40' 13.494 N 32° 40' 13.504 N	104° 12' 48.394 W 104° 12' 49.564 W
9,100.0	90.00	270.54	7,077.0	-624.6 -623.6	-1,523.6 -1,623.6	607,650.73	578,029.22	32° 40′ 13.514 N	104 12 49.564 W 104° 12' 50.733 W
9,300.0	90.00	270.54	7,077.0	-623.0 -622.7	-1,023.6 -1,723.6	607,651.67	577,929.23	32° 40′ 13.514 N	104° 12' 51.903 W
9,400.0	90.00	270.54	7,077.0	-621.8	-1,823.6	607,652.61	577,829.23	32° 40' 13.535 N	104° 12' 53.073 W
9,500.0	90.00	270.54	7,077.0	-620.8	-1,923.6	607,653.55	577,729.24	32° 40' 13.546 N	104° 12' 54.243 W
9,600.0	90.00	270.54	7,077.0	-619.9	-2,023.6	607,654.48	577,629.24	32° 40' 13.556 N	104° 12' 55.413 W
9,700.0	90.00	270.54	7,077.0	-618.9	-2,123.5	607,655.42	577,529.25	32° 40' 13.566 N	104° 12' 56.583 W
9,800.0	90.00	270.54	7,077.0	-618.0	-2,223.5	607,656.36	577,429.25	32° 40' 13.577 N	104° 12' 57.753 W
9,900.0	90.00	270.54	7,077.0	-617.1	-2,323.5	607,657.30	577,329.25	32° 40' 13.587 N	104° 12' 58.923 W
10,000.0	90.00	270.54	7,077.0	-616.1	-2,423.5	607,658.24	577,229.26	32° 40' 13.598 N	104° 13' 0.092 W
10,100.0	90.00	270.54	7,077.0	-615.2	-2,523.5	607,659.17	577,129.26	32° 40′ 13.608 N	104° 13' 1.262 W
10,200.0	90.00	270.54	7,077.0	-614.3	-2,623.5	607,660.11	577,029.27	32° 40′ 13.618 N	104° 13' 2.432 W
10,300.0	90.00	270.54	7,077.0	-613.3	-2,723.5	607,661.05	576,929.27	32° 40′ 13.629 N	104° 13' 3.602 W
10,400.0	90.00	270.54	7,077.0	-612.4	-2,823.5	607,661.99	576,829.28	32° 40' 13.639 N	104° 13' 4.772 W
10,500.0	90.00	270.54	7,077.0	-611.4	-2,923.5	607,662.92	576,729.28	32° 40' 13.649 N	104° 13' 5.942 W
10,600.0	90.00	270.54	7,077.0	-610.5	-3,023.5	607,663.86	576,629.29	32° 40' 13.660 N	104° 13' 7.112 W
10,700.0	90.00	270.54	7,077.0 7,077.0	-609.6	-3,123.5	607,664.80	576,529.29 576,429.29	32° 40' 13.670 N	104° 13' 8.281 W
10,800.0 10,900.0	90.00 90.00	270.54 270.54	7,077.0 7,077.0	-608.6 -607.7	-3,223.5 -3,323.5	607,665.74 607,666.68	576,429.29 576,329.30	32° 40' 13.680 N 32° 40' 13.691 N	104° 13' 9.451 W 104° 13' 10.621 W
11,000.0	90.00	270.54	7,077.0	-607.7 -606.8	-3,323.5 -3,423.5	607,667.61	576,329.30	32° 40′ 13.701 N	104° 13' 11.791 W
11,100.0	90.00	270.54	7,077.0	-605.8	-3,423.5 -3,523.5	607,668.55	576,129.31	32° 40′ 13.711 N	104° 13' 12.961 W
11,100.0	90.00	270.54	7,077.0	-604.9	-3,623.5	607,669.49	576,029.31	32° 40' 13.722 N	104° 13' 14.131 W
11,300.0	90.00	270.54	7,077.0	-603.9	-3,723.5	607,670.43	575,929.32	32° 40' 13.732 N	104° 13' 15.301 W
11,400.0	90.00	270.54	7,077.0	-603.0	-3,823.5	607,671.36	575,829.32	32° 40' 13.742 N	104° 13' 16.470 W
11,500.0	90.00	270.54	7,077.0	-602.1	-3,923.5	607,672.30	575,729.32	32° 40' 13.753 N	104° 13' 17.640 W
11,600.0	90.00	270.54	7,077.0	-601.1	-4,023.5	607,673.24	575,629.33	32° 40' 13.763 N	104° 13' 18.810 W
11,700.0	90.00	270.54	7,077.0	-600.2	-4,123.5	607,674.18	575,529.33	32° 40' 13.773 N	104° 13' 19.980 W
11,800.0	90.00	270.54	7,077.0	-599.2	-4,223.5	607,675.12	575,429.34	32° 40' 13.784 N	104° 13' 21.150 W
11,900.0	90.00	270.54	7,077.0	-598.3	-4,323.5	607,676.05	575,329.34	32° 40′ 13.794 N	104° 13' 22.320 W
12,000.0	90.00	270.54	7,077.0	-597.4	-4,423.4	607,676.99	575,229.35	32° 40′ 13.804 N	104° 13' 23.490 W
12,100.0	90.00	270.54	7,077.0	-596.4	-4,523.4	607,677.93	575,129.35	32° 40' 13.815 N	104° 13' 24.660 W
12,200.0	90.00	270.54	7,077.0	-595.5	-4,623.4	607,678.87	575,029.36	32° 40' 13.825 N	104° 13' 25.829 W
12,300.0	90.00	270.54	7,077.0	-594.6	-4,723.4	607,679.80	574,929.36	32° 40' 13.835 N	104° 13' 26.999 W
12,400.0	90.00	270.54	7,077.0	-593.6	-4,823.4	607,680.74	574,829.36	32° 40' 13.845 N	104° 13' 28.169 W



RESOURCES

 Database:
 Compass\_17

 Company:
 NEW MEXICO

 Project:
 (SP) LEA

 Site:
 ALPINE 7-11

Well: ALPINE 7-11 STATE 124H

Wellbore: OWB
Design: PWP0

Local Co-ordinate Reference:

TVD Reference:
MD Reference:
North Reference:

**Survey Calculation Method:** 

Well ALPINE 7-11 STATE 124H

KB @ 3562.2usft KB @ 3562.2usft

Grid

Design:	FVVF								
Planned Survey									
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Map Northing (usft)	Map Easting (usft)	Latitude	Longitude
12,500.0	90.00	270.54	7,077.0	-592.7	-4,923.4	607,681.68	574,729.37	32° 40′ 13.856 N	104° 13' 29.339 W
12,600.0	90.00	270.54	7,077.0	-591.7	-5,023.4	607,682.62	574,629.37	32° 40' 13.866 N	104° 13' 30.509 W
12,700.0	90.00	270.54	7,077.0	-590.8	-5,123.4	607,683.55	574,529.38	32° 40' 13.876 N	104° 13' 31.679 W
12,800.0	90.00	270.54	7,077.0	-589.9	-5,223.4	607,684.49	574,429.38	32° 40′ 13.887 N	104° 13' 32.849 W
12,900.0	90.00	270.54	7,077.0	-588.9	-5,323.4	607,685.43	574,329.39	32° 40' 13.897 N	104° 13' 34.018 W
13,000.0	90.00	270.54	7,077.0	-588.0	-5,423.4	607,686.37	574,229.39	32° 40' 13.907 N	104° 13' 35.188 W
13,100.0	90.00	270.54	7,077.0	-587.1	-5,523.4	607,687.31	574,129.40	32° 40' 13.917 N	104° 13' 36.358 W
13,200.0	90.00	270.54	7,077.0	-586.1	-5,623.4	607,688.24	574,029.40	32° 40′ 13.928 N	104° 13' 37.528 W
13,300.0	90.00	270.54	7,077.0	-585.2	-5,723.4	607,689.18	573,929.40	32° 40′ 13.938 N	104° 13' 38.698 W
13,400.0	90.00	270.54	7,077.0	-584.2	-5,823.4	607,690.12	573,829.41	32° 40' 13.948 N	104° 13' 39.868 W
13,500.0	90.00	270.54	7,077.0	-583.3	-5,923.4	607,691.06	573,729.41	32° 40' 13.958 N	104° 13' 41.038 W
13,600.0	90.00	270.54	7,077.0	-582.4	-6,023.4	607,691.99	573,629.42	32° 40' 13.969 N	104° 13' 42.207 W
13,700.0	90.00	270.54	7,077.0	-581.4	-6,123.4	607,692.93	573,529.42	32° 40' 13.979 N	104° 13' 43.377 W
13,800.0	90.00	270.54	7,077.0	-580.5	-6,223.4	607,693.87	573,429.43	32° 40' 13.989 N	104° 13' 44.547 W
13,900.0	90.00	270.54	7,077.0	-579.6	-6,323.4	607,694.81	573,329.43	32° 40' 13.999 N	104° 13' 45.717 W
14,000.0	90.00	270.54	7,077.0	-578.6	-6,423.4	607,695.75	573,229.43	32° 40′ 14.010 N	104° 13' 46.887 W
14,100.0	90.00	270.54	7,077.0	-577.7	-6,523.4	607,696.68	573,129.44	32° 40' 14.020 N	104° 13' 48.057 W
14,200.0	90.00	270.54	7,077.0	-576.7	-6,623.3	607,697.62	573,029.44	32° 40' 14.030 N	104° 13' 49.227 W
14,300.0 14,400.0	90.00	270.54 270.54	7,077.0 7,077.0	-575.8 -574.9	-6,723.3	607,698.56 607,699.50	572,929.45 572,829.45	32° 40' 14.040 N 32° 40' 14.051 N	104° 13' 50.397 W 104° 13' 51.566 W
14,500.0	90.00 90.00	270.54	7,077.0	-574.9 -573.9	-6,823.3 -6,923.3	607,700.43	572,729.46	32° 40′ 14.061 N	104° 13′ 52.736 W
14,600.0	90.00	270.54	7,077.0	-573.9 -573.0	-0,923.3 -7,023.3	607,700.43	572,629.46	32° 40′ 14.071 N	104° 13' 53.906 W
14,700.0	90.00	270.54	7,077.0	-573.0 -572.1	-7,023.3 -7,123.3	607,702.31	572,529.47	32° 40' 14.081 N	104° 13' 55.076 W
14,800.0	90.00	270.54	7,077.0	-571.1	-7,123.3	607,703.25	572,429.47	32° 40' 14.092 N	104° 13' 56.246 W
14,900.0	90.00	270.54	7,077.0	-570.2	-7,323.3	607,704.19	572,329.47	32° 40' 14.102 N	104° 13' 57.416 W
15,000.0	90.00	270.54	7,077.0	-569.2	-7,423.3	607,705.12	572,229.48	32° 40' 14.112 N	104° 13' 58.586 W
15,100.0	90.00	270.54	7,077.0	-568.3	-7,523.3	607,706.06	572,129.48	32° 40' 14.122 N	104° 13' 59.755 W
15,200.0	90.00	270.54	7,077.0	-567.4	-7,623.3	607,707.00	572,029.49	32° 40' 14.132 N	104° 14' 0.925 W
15,300.0	90.00	270.54	7,077.0	-566.4	-7,723.3	607,707.94	571,929.49	32° 40' 14.143 N	104° 14' 2.095 W
15,400.0	90.00	270.54	7,077.0	-565.5	-7,823.3	607,708.87	571,829.50	32° 40' 14.153 N	104° 14' 3.265 W
15,500.0	90.00	270.54	7,077.0	-564.6	-7,923.3	607,709.81	571,729.50	32° 40' 14.163 N	104° 14' 4.435 W
15,600.0	90.00	270.54	7,077.0	-563.6	-8,023.3	607,710.75	571,629.51	32° 40' 14.173 N	104° 14' 5.605 W
15,700.0	90.00	270.54	7,077.0	-562.7	-8,123.3	607,711.69	571,529.51	32° 40' 14.183 N	104° 14' 6.775 W
15,800.0	90.00	270.54	7,077.0	-561.7	-8,223.3	607,712.62	571,429.51	32° 40' 14.194 N	104° 14' 7.945 W
15,900.0	90.00	270.54	7,077.0	-560.8	-8,323.3	607,713.56	571,329.52	32° 40' 14.204 N	104° 14' 9.114 W
16,000.0	90.00	270.54	7,077.0	-559.9	-8,423.3	607,714.50	571,229.52	32° 40' 14.214 N	104° 14' 10.284 W
16,100.0	90.00	270.54	7,077.0	-558.9	-8,523.3	607,715.44	571,129.53	32° 40' 14.224 N	104° 14' 11.454 W
16,200.0	90.00	270.54	7,077.0	-558.0	-8,623.3	607,716.38	571,029.53	32° 40' 14.234 N	104° 14' 12.624 W
16,300.0	90.00	270.54	7,077.0	-557.1	-8,723.3	607,717.31	570,929.54	32° 40' 14.245 N	104° 14' 13.794 W
16,400.0	90.00	270.54	7,077.0	-556.1	-8,823.3	607,718.25	570,829.54	32° 40' 14.255 N	104° 14' 14.964 W
16,500.0	90.00	270.54	7,077.0	-555.2	-8,923.2	607,719.19	570,729.54	32° 40' 14.265 N	104° 14' 16.134 W
16,600.0	90.00	270.54	7,077.0	-554.2	-9,023.2	607,720.13	570,629.55	32° 40' 14.275 N	104° 14' 17.303 W
16,700.0	90.00	270.54	7,077.0	-553.3	-9,123.2	607,721.06	570,529.55	32° 40' 14.285 N	104° 14' 18.473 W
16,800.0	90.00	270.54	7,077.0	-552.4	-9,223.2	607,722.00	570,429.56	32° 40' 14.295 N	104° 14' 19.643 W
16,900.0	90.00	270.54	7,077.0 7,077.0	-551.4	-9,323.2	607,722.94	570,329.56	32° 40′ 14.306 N	104° 14' 20.813 W
17,000.0	90.00	270.54	7,077.0 7,077.0	-550.5	-9,423.2	607,723.88	570,229.57	32° 40′ 14.316 N	104° 14' 21.983 W
17,100.0 17,200.0	90.00 90.00	270.54 270.54	7,077.0 7,077.0	-549.5 -548.6	-9,523.2 -9,623.2	607,724.82 607,725.75	570,129.57 570,029.58	32° 40' 14.326 N 32° 40' 14.336 N	104° 14' 23.153 W 104° 14' 24.323 W
17,200.0	90.00	270.54 270.54	7,077.0 7,077.0	-548.6 -547.7	-9,623.2 -9,723.2	607,726.69	569,929.58	32° 40′ 14.336 N	104 14 24.323 W 104° 14' 25.493 W
17,300.0	90.00	270.54	7,077.0	-547.7 -546.7	-9,723.2 -9,823.2	607,726.69	569,829.58	32° 40′ 14.356 N	104 14 25.493 W
17,500.0	90.00	270.54	7,077.0	-545.8	-9,923.2 -9,923.2	607,728.57	569,729.59	32° 40′ 14.366 N	104° 14' 27.832 W
17,600.0	90.00	270.54	7,077.0	-544.9	-10,023.2	607,729.50	569,629.59	32° 40′ 14.377 N	104° 14' 29.002 W
17,700.0	90.00	270.54	7,077.0	-543.9	-10,023.2	607,730.44	569,529.60	32° 40' 14.387 N	104° 14' 30.172 W
17,800.0	90.00	270.54	7,077.0	-543.0	-10,123.2	607,731.38	569,429.60	32° 40' 14.397 N	104° 14' 31.342 W
17,900.0	90.00	270.54	7,077.0	-542.0	-10,323.2	607,732.32	569,329.61	32° 40' 14.407 N	104° 14' 32.512 W
11,000.0	00.00	_, 0.0 +	.,011.0	312.0	. 0,520.2	33.,102.02	000,020.01	32 .3 11.101.14	



RESOURCES

 Database:
 Compass\_17

 Company:
 NEW MEXICO

 Project:
 (SP) LEA

 Site:
 ALPINE 7-11

Well: ALPINE 7-11 STATE 124H

Wellbore: OWB
Design: PWP0

Local Co-ordinate Reference:

TVD Reference:
MD Reference:
North Reference:

**Survey Calculation Method:** 

Well ALPINE 7-11 STATE 124H

KB @ 3562.2usft KB @ 3562.2usft

Grid

Planned Survey	,								
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Map Northing (usft)	Map Easting (usft)	Latitude	Longitude
18,000.0	90.00	270.54	7,077.0	-541.1	-10,423.2	607,733.26	569,229.61	32° 40' 14.417 N	104° 14' 33.682 W
18,100.0	90.00	270.54	7,077.0	-540.2	-10,523.2	607,734.19	569,129.61	32° 40' 14.427 N	104° 14' 34.851 W
18,200.0	90.00	270.54	7,077.0	-539.2	-10,623.2	607,735.13	569,029.62	32° 40' 14.437 N	104° 14' 36.021 W
18,300.0	90.00	270.54	7,077.0	-538.3	-10,723.2	607,736.07	568,929.62	32° 40' 14.448 N	104° 14' 37.191 W
18,400.0	90.00	270.54	7,077.0	-537.4	-10,823.2	607,737.01	568,829.63	32° 40' 14.458 N	104° 14' 38.361 W
18,500.0	90.00	270.54	7,077.0	-536.4	-10,923.2	607,737.94	568,729.63	32° 40' 14.468 N	104° 14' 39.531 W
18,600.0	90.00	270.54	7,077.0	-535.5	-11,023.2	607,738.88	568,629.64	32° 40' 14.478 N	104° 14' 40.701 W
18,700.0	90.00	270.54	7,077.0	-534.5	-11,123.2	607,739.82	568,529.64	32° 40' 14.488 N	104° 14' 41.871 W
18,800.0	90.00	270.54	7,077.0	-533.6	-11,223.1	607,740.76	568,429.65	32° 40' 14.498 N	104° 14' 43.041 W
18,900.0	90.00	270.54	7,077.0	-532.7	-11,323.1	607,741.69	568,329.65	32° 40' 14.508 N	104° 14' 44.210 W
19,000.0	90.00	270.54	7,077.0	-531.7	-11,423.1	607,742.63	568,229.65	32° 40' 14.518 N	104° 14' 45.380 W
19,100.0	90.00	270.54	7,077.0	-530.8	-11,523.1	607,743.57	568,129.66	32° 40' 14.528 N	104° 14' 46.550 W
19,200.0	90.00	270.54	7,077.0	-529.9	-11,623.1	607,744.51	568,029.66	32° 40' 14.538 N	104° 14' 47.720 W
19,300.0	90.00	270.54	7,077.0	-528.9	-11,723.1	607,745.45	567,929.67	32° 40' 14.549 N	104° 14' 48.890 W
19,400.0	90.00	270.54	7,077.0	-528.0	-11,823.1	607,746.38	567,829.67	32° 40' 14.559 N	104° 14' 50.060 W
19,500.0	90.00	270.54	7,077.0	-527.0	-11,923.1	607,747.32	567,729.68	32° 40' 14.569 N	104° 14' 51.230 W
19,600.0	90.00	270.54	7,077.0	-526.1	-12,023.1	607,748.26	567,629.68	32° 40' 14.579 N	104° 14' 52.400 W
19,700.0	90.00	270.54	7,077.0	-525.2	-12,123.1	607,749.20	567,529.69	32° 40' 14.589 N	104° 14' 53.569 W
19,800.0	90.00	270.54	7,077.0	-524.2	-12,223.1	607,750.13	567,429.69	32° 40' 14.599 N	104° 14' 54.739 W
19,900.0	90.00	270.54	7,077.0	-523.3	-12,323.1	607,751.07	567,329.69	32° 40' 14.609 N	104° 14' 55.909 W
20,000.0	90.00	270.54	7,077.0	-522.4	-12,423.1	607,752.01	567,229.70	32° 40' 14.619 N	104° 14' 57.079 W
20,100.0	90.00	270.54	7,077.0	-521.4	-12,523.1	607,752.95	567,129.70	32° 40' 14.629 N	104° 14' 58.249 W
20,200.0	90.00	270.54	7,077.0	-520.5	-12,623.1	607,753.89	567,029.71	32° 40' 14.639 N	104° 14' 59.419 W
20,300.0	90.00	270.54	7,077.0	-519.5	-12,723.1	607,754.82	566,929.71	32° 40' 14.649 N	104° 15' 0.589 W
20,400.0	90.00	270.54	7,077.0	-518.6	-12,823.1	607,755.76	566,829.72	32° 40' 14.659 N	104° 15' 1.758 W
20,500.0	90.00	270.54	7,077.0	-517.7	-12,923.1	607,756.70	566,729.72	32° 40' 14.669 N	104° 15' 2.928 W
20,600.0	90.00	270.54	7,077.0	-516.7	-13,023.1	607,757.64	566,629.72	32° 40' 14.679 N	104° 15' 4.098 W
20,700.0	90.00	270.54	7,077.0	-515.8	-13,123.1	607,758.57	566,529.73	32° 40' 14.689 N	104° 15' 5.268 W
20,800.0	90.00	270.54	7,077.0	-514.9	-13,223.1	607,759.51	566,429.73	32° 40' 14.699 N	104° 15' 6.438 W
20,900.0	90.00	270.54	7,077.0	-513.9	-13,323.1	607,760.45	566,329.74	32° 40' 14.709 N	104° 15' 7.608 W
21,000.0	90.00	270.54	7,077.0	-513.0	-13,423.1	607,761.39	566,229.74	32° 40' 14.720 N	104° 15' 8.778 W
21,100.0	90.00	270.54	7,077.0	-512.0	-13,523.0	607,762.33	566,129.75	32° 40' 14.730 N	104° 15' 9.948 W
21,200.0	90.00	270.54	7,077.0	-511.1	-13,623.0	607,763.26	566,029.75	32° 40' 14.740 N	104° 15' 11.117 W
21,300.0	90.00	270.54	7,077.0	-510.2	-13,723.0	607,764.20	565,929.76	32° 40' 14.750 N	104° 15' 12.287 W
21,400.0	90.00	270.54	7,077.0	-509.2	-13,823.0	607,765.14	565,829.76	32° 40' 14.760 N	104° 15' 13.457 W
21,500.0	90.00	270.54	7,077.0	-508.3	-13,923.0	607,766.08	565,729.76	32° 40' 14.770 N	104° 15' 14.627 W
21,600.0	90.00	270.54	7,077.0	-507.3	-14,023.0	607,767.01	565,629.77	32° 40' 14.780 N	104° 15' 15.797 W
21,700.0	90.00	270.54	7,077.0	-506.4	-14,123.0	607,767.95	565,529.77	32° 40' 14.790 N	104° 15' 16.967 W
21,800.0	90.00	270.54	7,077.0	-505.5	-14,223.0	607,768.89	565,429.78	32° 40' 14.800 N	104° 15' 18.137 W
21,900.0	90.00	270.54	7,077.0	-504.5	-14,323.0	607,769.83	565,329.78	32° 40' 14.810 N	104° 15' 19.307 W
22,000.0	90.00	270.54	7,077.0	-503.6	-14,423.0	607,770.77	565,229.79	32° 40' 14.820 N	104° 15' 20.476 W
22,100.0	90.00	270.54	7,077.0	-502.7	-14,523.0	607,771.70	565,129.79	32° 40' 14.830 N	104° 15' 21.646 W
22,200.0	90.00	270.54	7,077.0	-501.7	-14,623.0	607,772.64	565,029.80	32° 40' 14.840 N	104° 15' 22.816 W
22,300.0	90.00	270.54	7,077.0	-500.8	-14,723.0	607,773.58	564,929.80	32° 40' 14.850 N	104° 15' 23.986 W
22,400.0	90.00	270.54	7,077.0	-499.8	-14,823.0	607,774.52	564,829.80	32° 40' 14.860 N	104° 15' 25.156 W
22,500.0	90.00	270.54	7,077.0	-498.9	-14,923.0	607,775.45	564,729.81	32° 40' 14.870 N	104° 15' 26.326 W
22,600.0	90.00	270.54	7,077.0	-498.0	-15,023.0	607,776.39	564,629.81	32° 40' 14.880 N	104° 15' 27.496 W
22,659.9	90.00	270.54	7,077.0	-497.4	-15,082.9	607,776.95	564,569.87	32° 40' 14.886 N	104° 15' 28.197 W
	659.9 - LTP/BI				. 2,302.0	,	,000.0.		
1 D at 22	009.9 - LIF/DI	IL - ALFINE	7-11-01-12411						



Database: Compass\_17

Company: NEW MEXICO
Project: (SP) LEA
Site: ALPINE 7-11

Well: ALPINE 7-11 STATE 124H

Wellbore: OWB
Design: PWP0

Local Co-ordinate Reference:

TVD Reference: MD Reference: North Reference:

**Survey Calculation Method:** 

Well ALPINE 7-11 STATE 124H

KB @ 3562.2usft KB @ 3562.2usft

Grid

Design Targets									
Target Name - hit/miss target - Shape	Dip Angle (°)	Dip Dir. (°)	TVD (usft)	+N/-S (usft)	+E/-W (usft)	Northing (usft)	Easting (usft)	Latitude	Longitude
LTP/BHL - ALPINE 7-11 - plan hits target cent - Point	0.00 er	0.01	7,077.0	-497.4	-15,082.9	607,776.95	564,569.87	32° 40' 14.886 N	104° 15' 28.197 W
FTP - ALPINE 7-11 ST 1 - plan misses target c - Point	0.00 enter by 241.	0.00 .4usft at 7050	7,077.0 0.0usft MD (6	-644.5 6917.6 TVD, -	661.9 643.4 N, 480.	607,629.86 5 E)	580,314.65	32° 40' 13.282 N	104° 12' 23.996 W


Plan Annotations				
Measu Dept (usf	th Depth	+N/-S	Coordinates +E/-W (usft)	Comment
1,2	200.0 1,20	0.0	0	.0 Start Build 2.00
1,4	400.0 1,39	99.8 -6.6	-2	.4 Start 800.0 hold at 1400.0 MD
2,2	200.0 2,19	97.9 -59.0	-21	.5 Start Drop -2.00
2,4	400.0 2,39	97.7 -65.6	-23	.9 Start 100.0 hold at 2400.0 MD
2,5	500.0 2,49	97.7 -65.6	-23	.9 Start Build 2.00
3,2	220.5 3,21	10.6 -126.8	42	.3 Start 2701.4 hold at 3220.5 MD
5,9	921.9 5,82	27.1 -583.3	535	.7 Start Drop -2.00
6,6	6,54	10.0 -644.5	601	.9 Start 59.5 hold at 6642.4 MD
6,7	701.9 6,59	99.5 -644.5	601	.9 Start DLS 12.00 TFO 270.54
7,4	451.9 7,07	77.0 -640.0	124	.5 Start 15208.0 hold at 7451.9 MD
22,6	559.9 7,07	77.0 -497.4	-15,082	.9 TD at 22659.9



County: (SP) LEA Site: ALPINE 7-11

Well: ALPINE 7-11 STATE 124H

GE: 3532.2 Plan: PWP0





9.625" 36# .352" J-55

# **Dimensions (Nominal)**

Outside Diameter	9.625	in.
Wall	0.352	in.
Inside Diameter	8.921	in.
Drift	8.765	in.
Weight, T&C	36.000	lbs/ft
Weight, PE	34.890	lbs/ft

# **Performance Properties (Minimum)**

Collapse, PE	2020	psi
Internal Yield Pressure		
PE	3520	psi
STC	3520	psi
LTC	3520	psi
BTC	3520	psi
Yield Strength, Pipe Body	564	1000 lbs
Joint Strength		
STC	394	1000 lbs
LTC	453	1000 lbs
втс	639	1000 lbs



# **Connection Data Sheet**

Issued on: May. 09, 2025

# 5.500" 17.00# P-110 RY (SeAH) Bushmaster® SP SC6.050

Pipe Body Data			
Nominal OD	5.500 in.		
Wall Thickness	0.304 in.		
Weight	17.00 lb/ft		
PE Weight	16.89 lb/ft		
Nominal ID	4.892 in.		
Drift	4.767 in.		
Minimum Yield Strength	110,000 psi		
Minimum Tensile Strength	125,000 psi		
Remaining Body Wall (RBW)	95.0% Rating		

Connection Data				
Connection OD	6.050 in.			
Connection ID	4.892 in.			
Make-Up Loss	4.209 in.			
Tension Efficiency	100.0% Rating			
Compression Efficiency	100.0% Rating			
Yield Strength in Tension	546,000 lbs			
Yield Strength in Compression	546,000 lbs			
MIYP (Burst)	11,550 psi			
Collapse	7,480 psi			
Uniaxial Bending	91.7 °/100ft.			

Ma	ke-up Torc	<b>Jue</b>
Max. Operating Torque	-	37,300 ft. lbs
Maximum Make-up	-	17,900 ft. lbs
Optimum Make-Up	-	16,300 ft. lbs
Minimum Make-Up	-	14,700 ft. lbs

	Buck-on Torque	
Maximum Make-Up	-	19,900 ft. lbs
Optimum Make-Up	-	18,100 ft. lbs
Minimum Make-Up	-	16,300 ft. lbs



For technical support please email support@fermata-tech.com or call (281) 941-5257.

This document is for general information only. It is not intended to be used or relied upon as a recommendation or profession all advice for any specific application and is subject to change without notice. Anyone who uses this material does so at their own right and assumes any and all liability resulting from such use.

Connection performance values pertain to structural capacity.

# Permian Resources Multi-Well Pad Batch Drilling Procedure

<u>Surface Casing</u> - PR intends to Batch set all surface casing to a depth approved in the APD. Surface Holes will be batch drilled by a rig. Appropriate notifications will be made prior to spudding the well, running and cementing casing and prior to skidding to the rig to the next well on pad.

- 1. Drill Surface hole to Approved Depth with Rig and perform wellbore cleanup cycles. Trip out and rack back drilling BHA.
- 2. Run and land planned surface casing see Illustration 1-1 Below to depth approved in APD.
- 3. Set packoff and test to 5k psi
- 4. Offline Cement
- 5. Install wellhead with pressure gauge and nightcap. Nightcap is shown on final wellhead Stack up Illustration #2-2.
- 6. Skid Rig to adjacent well to drill Surface hole.
- 7. Surface casing test will be performed by the rig in order to allow ample time for Cement to develop 500psi compressive strength. Casing test to 0.22 psi/ft or 1500 psi whichever is greater not to exceed 70% casing burst.




Illustration 1-1

<u>Intermediate Casing</u> – PR intends to Batch set all intermediate casing strings to a depth approved in the APD. Intermediate Holes will be batch drilled by the rig. Appropriate notifications will be made prior to testing BOPE, and prior to running/cementing all casing strings.

- 1. Rig will remove the nightcap and install and test BOPE.
- 2. Test Surface casing per COA WOC timing (.22 psi/ft or 1500 psi whichever is greater) not to exceed 70% casing burst. Cement must have achieved 500psi compressive strength prior to test.
- 3. Install wear bushing then drill out surface casing shoe-track plus 20' and conduct FIT to minimum of the MW equivalent anticipated to control the formation pressure to the next casing point.
- 4. Drill Intermediate hole to approved casing point. Trip out of hole with BHA to run Casing.
- 5. Remove wear bushing then run and land Intermediate Casing with mandrel hanger in wellhead.
- 6. Cement casing to surface with floats holding.
- 7. Washout stack then run wash tool in wellhead and wash hanger and pack-off setting area.
- 8. Install pack-off and test void to 5,000 psi for 15 minutes. Nightcap shown on final wellhead stack up illustration 2-2 on page 3.
- 9. Test casing per COA WOC timing (.22 psi/ft or 1500 psi whichever is greater) not to exceed 70% casing burst. Cement must have achieved 500psi compressive strength prior to test.
- 10. Install nightcap skid rig to adjacent well to drill Intermediate hole.




Illustration 2-2

<u>Production Casing</u> – PR intends to Batch set all Production casings with Rig. Appropriate notifications will be made prior Testing BOPE, and prior to running/cementing all casing strings.

- 1. Drilling Rig will remove the nightcap and install and test BOPE.
- 2. Install wear bushing then drill Intermediate shoe-track plus 20' and conduct FIT to minimum MW equivalent to control the formation pressure to TD of well.
- 3. Drill Vertical hole to KOP Trip out for Curve BHA.
- 4. Drill Curve, landing in production interval Trip for Lateral BHA.
- 5. Drill Lateral / Production hole to Permitted BHL, perform cleanup cycles and trip out to run Production Casing.
- 6. Remove wear bushing then run Production casing to TD landing casing mandrel in wellhead.
- 7. Cement Production string with floats holding.
- 8. Run in with wash tool and wash wellhead area install pack-off and test void to 5,000psi for 15 minutes.
- 9. Install BPV in Production mandrel hanger Nipple down BOPE and install nightcap.
- 10. Test nightcap void to 5,000 psi for 30 minutes per illustration 2-2
- 11. Skid rig to adjacent well on pad to drill production hole.

# Permian Resources BOP Break Testing Variance Procedure

Subject: Request for a Variance Allowing break Testing of the Blowout Preventer Equipment (BOPE). Permian Resources requests a variance to ONLY test broken pressure seals on the BOPE and function test BOP when skidding a drilling rig between multiple wells on a pad.

#### Background

Title 43 CFR 3172, Drilling Operations, Sections 6.b.9.iv states that the BOP test must be performed whenever any seal subject to test pressure is broken. The current interpretation of the Bureau of Land Management (BLM) requires a complete BOP test and not just a test of the affected component. 43 CFR 3172.13, Variances from minimum standards states, "An operator may request the authorized officer to approve a variance from any of the minimum standards prescribed in §§ 3172.6 through 3172.12. All such requests shall be submitted in writing to the appropriate authorized officer and provide information as to the circumstances which warrant approval of the variance(s) requested and the proposed alternative methods by which the related minimum standard(s) are to be satisfied. The authorized officer, after considering all relevant factors, if appropriate, may approve the requested variance(s) if it is determined that the proposed alternative(s) meet or exceed the objectives of the applicable minimum standard(s).". Permian Resources feels the break testing the BOPE is such a situation. Therefore, as per 43 CFR 3172.13, Permian Resources submits this request for the variance.

# <u>Supporting Documentation</u>

The language used in 43 CFR 3172 became effective on December 19, 1988 and has remained the standard for regulating BLM onshore drilling operations for over 30 years. During this time, there have been significant changes in drilling technology. The BLM continues to use the variance request process to allow for the use of modern technology and acceptable engineering practices that have arisen since 43 CFR 3172 was originally released. The Permian Resources drilling rig fleet has many modern upgrades that allow the intact BOP stack to be moved between well slots on a multi-well pad, as well as, wellhead designs that incorporate quick connects facilitating release of the BOP from the wellhead without breaking any BOP stack components apart. These technologies have been used extensively offshore, and other regulators, API, and many operators around the world have endorsed break testing as safe and reliable.

Figure 1: Winch System attached to BOP Stack



Figure 2: BOP Winch System



American Petroleum Institute (API) standards, specification and recommended practices are considered the industry standard and are consistently utilized and referenced by the industry. 43 CFR 3172 recognizes API recommended Practices (RP) 53 in its original development. API Standard 53, Well Control Equipment Systems for Drilling Wells (Fifth Edition, December 2018, Annex C, Table C.4) recognizes break testing as an acceptable practice. Specifically, API Standard 53, Section 5.3.7.1 states "A pressure test of the pressure containing component shall be performed following the disconnection or repair, limited to the affected component." See Table C.4 below for reference.

2	API STANDARD	53		
Та	ble C.4—Initial Pressure Te	sting, Surface BOP Stacks		
	Pressure Test—Low	Pressure Test—High Pressure**		
Component to be Pressure Tested	Pressure** psig (MPa)	Change Out of Component, Elastomer, or Ring Gasket	No Change Out of Component, Elastomer, or Ring Gasket	
Annular preventer	250 to 350 (1.72 to 2.41)	RWP of annular preventer	MASP or 70% annular RWP, whichever is lower.	
Fixed pipe, variable bore, blind, and BSR preventers∞	250 to 350 (1.72 to 2.41)	RWP of ram preventer or wellhead system, whichever is lower	ІТР	
Choke and kill line and BOP side outlet valves below ram preventers (both sides)	250 to 350 (1.72 to 2 41)	RWP of side outlet valve or wellhead system, whichever is lower	ITP	
Choke manifold—upstream of chokes*	250 to 350 (1.72 to 2.41)	RWP of ram preventers or wellhead system, whichever is lower		
Choke manifold—downstream of chokes*	250 to 350 (1.72 to 2.41)	RWP of valve(s), line(s), or N whichever is lower	MASP for the well program,	
Kelly, kelly valves, drill pipe safety valves, IBOPs	250 to 350 (1.72 to 2.41)	MASP for the well program		
	during the evaluation period. The p	ressure shall not decrease below the allest OD drill pipe to be used in well p		
	from one wellhead to another within when the integrity of a pressure sea	the 21 days, pressure testing is required is broken.	uired for pressure-containing and	
	land operations, the ram BOPs sha	ed with the ram locks engaged and If be pressure tested with the ram loc		

The Bureau of Safety and Environmental Enforcement (BSEE), Department of Interior, has also utilized the API standards, specification and best practices in the development of its offshore oil and gas regulations and incorporates them by reference within its regulations.


Break testing has been approved by the BLM in the past with other operators based on the detailed information provided in this document.

Permian Resources feels break testing and our current procedures meet the intent of 43 CFR 3172 and often exceed it. There has been no evidence that break testing results in more components failing than seen on full BOP tests. Permian Resources internal standards require complete BOPE tests more often than that of 43 CFR 3172 (every 21 days). In addition to function testing the annular, pipe rams and blind rams after each BOP nipple up, Permian Resources performs a choke drill with the rig crew prior to drilling out every casing shoe. This is additional training for the rig crew that exceeds the requirements of 43 CFR 3172.

#### Procedures

- 1) Permian Resources will use this document for our break testing plan for New Mexico Delaware Basin. The summary below will be referenced in the APD or Sundry Notice and receive approval prior to implementing this variance.
- 2) Permian Resources will perform BOP break testing on multi-wells pads where multiple intermediate sections can be drilled and cased within the 21-day BOP test window.
  - a)A full BOP test will be conducted on the first well on the pad.
- b)The first intermediate hole section drilled on the pad will be the deepest. All the remaining hole sections will be the same formation depth or shallower.
- c) A full BOP test will be required if the intermediate hole section being drilled has a MASP over 5M.
  - d) A full BOP test will be required prior to drilling any production hole.
- 3) After performing a complete BOP test on the first well, the intermediate hole section will be drilled and cased, two breaks would be made on the BOP equipment.
  - a) Between the HCV valve and choke line connection
  - b)Between the BOP quick connect and the wellhead
- 4) The BOP is then lifted and removed from the wellhead by a hydraulic system.
- 5) After skidding to the next well, the BOP is moved to the wellhead by the same hydraulic system and installed.
- 6) The connections mentioned in 3a and 3b will then be reconnected.
- 7) Install test plug into the wellhead using test joint or drill pipe.
- 8) A shell test is performed against the upper pipe rams testing the two breaks.
- 9) The shell test will consist of a 250 psi low test and a high test to the value submitted in the APD or Sundry (e.g. 5,000 psi or 10,000psi).
- 10) Function tests will be performed on the following components: lower pipe rams, blind rams, and annular.
- 11) For a multi-well pad the same two breaks on the BOP would be made and on the next wells and steps 4 through 10 would be repeated.
- 12) A second break test would only be done if the intermediate hole section being drilled could not be completed within the 21 day BOP test window.

Note: Picture below highlights BOP components that will be tested during batch operations



# **Summary**


A variance is requested to ONLY test broken pressure seals on the BOP equipment when moving from wellhead to wellhead which is in compliance with API Standard 53. API Standard 53 states, that for pad drilling operations, moving from one wellhead to another within 21 days, pressure testing is required for pressure-containing and pressure-controlling connections when the integrity of a pressure seal is broken.

The BOP will be secured by a hydraulic carrier or cradle. The BLM will be contacted if a Well Control

event occurs prior to the commencement of a BOPE Break Testing operation.

Based on public data and the supporting documentation submitted herein to the BLM, we will request permission to ONLY retest broken pressure seals if the following conditions are met:

- 1) After a full BOP test is conducted on the first well on the pad.
- 2) The first intermediate hole section drilled on the pad will be the deepest. All the remaining hole sections will be the same depth or shallower.
- 3) A full BOP test will be required if the intermediate hole section being drilled has a MASP over 5M.
- 4) A full BOP test will be required prior to drilling the production hole.




# Permian Resources Offline Cementing Procedure Surface & Intermediate Casing


- 1. Drill hole to Total Depth with Rig and perform wellbore cleanup cycles.
- 2. Run and casing to Depth.
- 3. Land casing with mandrel.
- 4. Circulate 1.5 csg capacity.
- 5. Flow test Confirm well is static and floats are holding.
- 6. Set Annular packoff and pressure test. Test to 5k.
- 7. Nipple down BOP and install cap flange.
- 8. Skid rig to next well on pad
- 9. Remove cap flange (confirm well is static before removal)
  - a) If well is not static use the casing outlet valves to kill well
  - b) Drillers method will be used in well control event
  - c) High pressure return line will be rigged up to lower casing valve and run to choke manifold to control annular pressure
  - d) Kill mud will be circulated once influx is circulated out of hole
  - e) Confirm well is static and remove cap flange to start offline cement operations
- 10. Install offline cement tool.
- 11. Rig up cementers.
- 12. Circulate bottoms up with cement truck
- 13. Commence planned cement job, take returns through the annulus wellhead valve
- 14. After plug is bumped confirm floats hold and well is static
- 15. Rig down cementers and equipment
- 16. Install night cap with pressure gauge to monitor.

#### 13 3/8" Surface


# **CFL Off-Line Cementing Tool**




# Intermediate




Run 7 5/8" Casing Land Casing on 7 5/8" Mandrel Hanger Cement 7 5/8" Casing Retrieve Running Tool



Run 9 5/8" Packoff
Test Upper and Lower Seals
Engage Lockring
Retrieve Running Tool





# @ntinental<u>⅓</u>

## ContiTech Fluid Technology

ContiTech	Oil & Marine Corp. # 11535 Brittmoore Park Dr., Houston, TX	Packing list / Delivery note
77041-69		Document No. 71461553
		Document Date 28.01.2022
CONSI	GNEE / Ship-to address:	Customer Number 11697
ATTN: 210 MA	ERICH & PAYNE INT'L DRILLING CO FLEX RIG WHSE - B-BAY AGNOLIA DRIVE NA PARK TX 77547	Customer VAT No. Supplier Number Purchase Order No. 740362040 Purchase Order Date 18.01.2022
Buyer:		Sales Order Number 1388153 Sales Order Date 18.01.2022
HELME	ERICH & PAYNE INT'L DRILLING CO COUTH BOULDER TULSA	Unloading Point RAN-No.
Conditi	ions	
30. Iuiti		Page 1 of 2
Incoter	EXW Houston Ex Works	Weights (Gross / Net) Total Gross Weight 2,507.000 LB Total Net Weight 2,507.000 LB
Item	Material/Description	Quantity Net Weight Gross Weigh
	Buyer: Jack Peebles E-mail: Jackie.Peebles@hpinc.com Tel: 832-782-6000	
20	Rig/Whse: HOW 00RECERTIFY	1 PC 2,507.000 LB 2,507.000 L
	Recert of HP Hoses Serial# 67094 Commodity Code:	
	3" X 35 FT 10K Choke & Kill Hoses API 16C	
	End 1: 4 - 1/16" 10Kpsi API Spec 6A Type 6BX Flange End 2: 4 - 1/16" 10Kpsi API Spec 6A Type 6BX Flange c/w BX Standard: API Spec 16C - Monogrammed	
	Working Pressure: 10,000psi	U()_
	Test Pressure: 15,000psi	000240-
	Inspection & Certification includes:	
	External inspection of the hose & couplings	ons (limited cation
	Internal boroscopic inspection of hose liner	0-
	Hydrostatic pressure test of hose assembly	one (limited
	Repair of any external damage to hose body and end connecti- to minor repairs).	ons (mined
	Clean & protect end connections Inspection Report	1.
	Disposal of hose assembly if hose fails inspection and recertifi	cation
	process.	\ a'
	Please Flush Hoses before sending them to our Facility.	$\sim$

ContiTech Rubber Industrial Kft Contriech Rubber Indoorsial N.I. H-6728 Szeged Budapesti út 10. P. O. Box 152 Szeged H-6701 Phone:(62)566-700, Fax:(62)566-713 Tax Number: 11087209-2-06 EU Community VAT: HU11087209 Registration No.: Cg. 0609-002502 Registry Court: Csongråd Megyei Cégbíróság

Please Flush Hoses before sending them to our Facility

COMMERZBANK ZRT (HUF) H-1054 Budapest, Széchenyi rakpart 8. H-1245 Budapest P.O. Box 1070 Account No.: 14220108-26830003 IBAN: HU83 1422 0108 2683 0003 0000 0000 SWIFT: COBA HU HXXXX

COMMERZBANK AG Hannover (EUR) 30159 Hannover, Theaterstr. 11-12. Account No.: 3 066 156 00 Sort Code: 250 400 66 BIC: COBADEFF250 IBAN: DE41250400660306615600

# 

# **Hydrostatic Test Certificate**



ContiTech

Certificate Number H100122	COM Order Reference 1388153	Customer Name & Address HELMERICH & PAYNE DRILLING CO
Customer Purchase Order No:	740362040	1434 SOUTH BOULDER AVE TULSA, OK 74119
Project:		USA
Test Center Address	Accepted by COM Inspection	Accepted by Client Inspection
ContiTech Oil & Marine Corp. 11535 Brittmoore Park Drive Houston, TX 77041 USA	Signed: Gerson Mejia-Lazo  Date: 02/09/22	

We certify that the goods detailed hereon have been inspected as described below by our Quality Management System, and to the best of our knowledge are found to conform the requirements of the above referenced purchase order as issued to ContiTech Oil & Marine Corporation.

Item	Part No.	Description	Qnt	y Serial Number	Work. Press. (psi)	Test Press. (psi)	Test Time (minutes)

20 RECERTIFICATION

3" ID 10K Choke and Kill Hose x 35ft OAL

67094


10,000

15,000

60

Record Information		
Start Time	1/27/2022 13:21:21	
End Time	1/27/2022 14:38:28	
Interval	00:01:00	
Number	78	
MaxValue	15849	
MinValue	-3	
AvgValue	14240	
RecordName	67094-sh	
RecordNumber	199	

Gauge Information		
Model	ADT680	
SN	21817380014	
Range	(0-40000)psi	
Unit	psi	



# PERMIAN RESOURCES

# H<sub>2</sub>S CONTINGENCY PLAN

**FOR** 

Permian Resources Corporation
Alpine 7-11 State Com 123H, 124H, 133H, 134H
Eddy County, New Mexico

10-17-2025
This plan is subject to updating

Permian Resources Corporation H₂S Contingency Plan
Alpine South Pad

Eddy County, New Mexico

# **Table of Contents**

Section	1.0 – Introduction 3
1.	Purpose
II.	Scope & Applicability
Section	2.0 - Plan Implementation3
I.	Activation Requirements
II.	Emergency Evacuation
III.	Emergency Response Activities
Section	a 3.0 - Potential Hazardous Conditions4
Section	n 4.0 - Notification of H2S Release Event6
I.	Local & State Law Enforcement
II.	General Public
III.	New Mexico Oil Conservation Division
IV.	New Mexico Environment Department
٧.	Bureau of Land Management
Section	n 5.0 - Emergency Contact List7
I.	Permian Resources Management Personnel
II.	Eddy County Sheriff
III.	New Mexico State Highway Patrol
IV.	Fire / EMS
٧.	Carlsbad Memorial Hospital
VI.	Emergency Response Contractors
VII.	New Mexico Oil Conservation Division
VIII.	New Mexico Environment Department
IX.	Bureau of Land Management
Χ.	Other Agencies
Section	n 6.0 — Drilling Location Information9-12
I.	Site Safety Information
II.	Directions to Location
III.	Plat of Location including GPS Coordinates
IV.	Routes of Ingress & Egress (MAP)
٧.	ROE Map
VI.	Residences in ROE
VII.	Public Roads in ROE
Section	13-15 – Hazard Communication13-15
I.	Physical Characteristics of Hydrogen Sulfide Gas
II.	Human Health Hazards / Toxicological Information
III.	Environmental Hazards
Section	n 8.0 - Regulatory Information15-17
I.	OSHA Information
II.	New Mexico Oil Conservation Division & Bureau of Land Management
	n 9.0 - Training Requirements17
	10.0 - Personal Protective Equipment18
Append	
l.	Appendix A – H <sub>2</sub> S SDS
II.	Appendix B − SO <sub>2</sub> SDS

Permian Resources Corporation	H₂S Contingency Plan	Eddy County, New Mexico
	Alpine South Pad	

### Section 1.0 - Introduction

### I. Purpose

The purpose of this contingency plan (Plan) is to provide Permian Resources Corporation. (Permian Resources) with an organized plan of action for alerting and protecting Permian Resources employees, the general public, and any potential first responders prior to any intentional release or immediately following the accidental / unintentional release of a potentially hazardous volume / concentration of Hydrogen Sulfide Gas (H2S).

### II. Scope & Applicability

This Plan applies to all planned, unplanned, uncontrolled and/or unauthorized releases of hazardous concentrations of  $H_2S$  or any associated hazardous byproducts of combustion, occurring at any Permian Resources owned or operated facilities including but not limited to: wells, flowlines, pipelines, tank batteries, production facilities, SWD facilities, compressor stations, gas processing plants, drilling / completions / workover operations, and any other applicable company owned property.

### Section 2.0 - Plan Implementation

### I. Activation Requirements

In accordance with the requirements of Bureau of Land Management Onshore Order #6 and NMAC 19.15.11, this Plan shall be activated in advance of any authorized, planned, unplanned, uncontrolled, or unauthorized release of a hazardous volume / concentration of  $H_2S$  gas, or  $SO^2$ , which could potentially adversely impact the workers, general public or the environment.

### II. Emergency Evacuation

In the event of an unplanned, uncontrolled, or unauthorized release of a hazardous volume / concentration of  $H_2S$  gas, the first priority is to ensure the safety of the workers and general public. Upon discovery and subsequent determination of an applicable release, which cannot be quickly mitigated, immediately by using 911, notify local authorities to begin the process of alerting the general public, evacuate any residents within the Radius of Exposure (ROE), and limit any general public or employee access to any areas within the ROE of the affected facility.

### III. Emergency Response Activities

The purpose of emergency response actions is to take steps to quickly mitigate / stop the ongoing release of the hazardous source of  $H_2S$ . Upon discovery of any hazardous release, immediately notify Permian Resources management to activate the Emergency Response Team (ERT). Once Permian Resources supervision arrives and assesses the situation, a work plan identifying the proper procedures shall be developed to stop the release.

### Section 3.0 - Potential Hazardous Conditions & Response Actions

During a planned or unplanned release of  $H_2S$ , there are several hazardous conditions that are presented both to employees, the general public, and emergency responders. These specific hazardous conditions are identified in the tables below.

H2S OPERATING CONDITIONS – RESPONSE ACTIONS TO CONSIDER	✓
H <sub>2</sub> S CONDITION 1: POTENTIAL DANGER TO LIFE AND HEALTH -> WARNING SIGREEN	IGN
H <sub>2</sub> S concentration <10 ppm detected by location monitors	
General Actions During Condition 1	
Notify Site Supervisor / Permian Resources Person-in-Charge (PIC) of any observed increase in ambient H <sub>2</sub> S concentrations	
All personnel check safety equipment is in adequate working order & store in accessible location	
Sensitize crews with safety meetings.	
Limit visitors and non-essential personnel on location	
Continuously monitor H <sub>2</sub> S concentrations and check calibration of sensors	
Ensure H <sub>2</sub> S scavenger is on location.	
H <sub>2</sub> S CONDITION 2: MODERATE DANGER TO LIFE AND HEALTH → WARNING SIGN YELLOW	
H <sub>2</sub> S concentration >10 ppm and < 30 ppm in atmosphere detected by location monitors:	
General Actions During Condition 2	
Sound H <sub>2</sub> S alarm and/or display yellow flag.	
Account for on-site personnel	
Upon sounding of an area or personal H <sub>2</sub> S monitor alarm when 10 ppm is reached, proceed to a safe briefing area upwind of the location immediately (see <b>MA-4</b> , <b>Figure 5-1</b> ).	
Don proper respiratory protection.	
Alert other affected personnel	
<u>If trained and safe to do so</u> undertake measures to control source H2S discharge and eliminate possible ignition sources. Initiate Emergency Shutdown procedures as deemed necessary to correct or control the specific situation.	
Account for on-site personnel at safe briefing area.	
Stay in safe briefing area if not working to correct the situation.	
Keep Site Supervisor / Permian Resources PIC informed. Notify applicable government agencies ( <b>Appendix A</b> ) If off-site impact; notify any neighbors within Radius of Exposure ( <b>ROE</b> ), <b>Fig 5.11</b>	
Continuously monitor H <sub>2</sub> S until readings below 10 ppm.	
Evacuated area shall not be re-entered except by trained and authorized personnel utilizing appropriate respiratory protection; or until "all clear" sounded by Permian Resources PIC / Site Supervisor.	
HIS CONDITION 2: EVEDENG DANCED TO LIFE AND LIFATEL A WARNING SIGN RED	
H <sub>2</sub> S CONDITION 3: EXTREME DANGER TO LIFE AND HEALTH → WARNING SIGN RED	
> 30 ppm H <sub>2</sub> S concentration in air detected by location monitors: Extreme danger to life  General Actions During Condition 3	
Sound H-S alarm and/or display rad flag	
Sound H <sub>2</sub> S alarm and/or display red flag.	
Account for on-site personnel	J

Permian Resources Corporation	H₂S Contingency Plan	Eddy County, New Mexico
	Alpine South Pad	

Move away from H <sub>2</sub> S source and get out of the affected area.	
Proceed to designated safe briefing area; alert other affected personnel.	
Account for personnel at safe briefing area.	
If trained and safe to do so undertake measures to control source H2S discharge and eliminate possible ignition sources. Initiate Emergency Shutdown procedures as deemed necessary to correct or control the specific situation.	
Notify vehicles or situation and divert all traffic away from location.	
Permian Resources Peron-in-Charge will make appropriate community notifications.	
Red warning flag must be on display until the situation has been corrected and the Permian Resources Person-in-Charge determines it is safe to resume operations under <b>Condition</b> 1.	
Notify management of the condition and action taken. If H <sub>2</sub> S concentration is increasing and steps to correct the situation are not successful – or at any time if well control is questionable – alert all responsible parties for possible activation of the H <sub>2</sub> S Contingency Plan. If well control at the surface is lost, determine if situation warrants igniting the well.	
If uncontrolled flow at the surface occurs, the Permian Resources PIC, with approval, if possible, from those coordinating the emergency (as specified in the site-specific H <sub>2</sub> S Contingency Plan) are responsible for determining if the situation warrants igniting the flow of the uncontrolled well. This decision should be made only as a last resort and in a situation where it is obvious that human life is in danger and there is no hope of controlling the flow under prevailing conditions.	
If the flow is ignited, burning H <sub>2</sub> S will be converted to sulfur dioxide (SO <sub>2</sub> ), which is also highly toxic. Do not assume that area is safe after the flow is ignited. If the well is ignited, evacuation of the area is mandatory, because SO <sub>2</sub> will remain in low-lying places under no-wind conditions.	
Keep Site Supervisor / Permian Resources PIC informed.  Notify applicable government agencies and local law enforcement (Appendix A)  If off-site impact; notify any neighbors within the Radius of Exposure (ROE), see example in Figure 5-11.	
Continuously monitor H <sub>2</sub> S until readings fall below 10 ppm.	
Evacuated area shall not be re-entered except by trained and authorized personnel utilizing appropriate respiratory protection; or until "all clear" sounded by Permian Resources PIC / Site Supervisor.	
IF ABOVE ACTIONS CANNOT BE ACCOMPLISHED IN TIME TO PREVENT EXPOSURE TO THE PUBLIC	
Alert public (directly or through appropriate government agencies) who may be subject to potentially harmful exposure levels.	
Make recommendations to public officials regarding blocking unauthorized access to the unsafe area and assist as appropriate.	
Make recommendations to public officials regarding evacuating the public and assist as appropriate.	
Monitor ambient air in the area of exposure (after following abatement measures) to determine when it is safe for re-entry.	

Permian Resources Corporation	H₂S Contingency Plan Alpine South Pad	Eddy County, New Mexico
-------------------------------	--	-------------------------

# 

### Section 4.0 - Notification of H₂S Release Event

### I. Local & State Law Enforcement

Prior to the planned / controlled release of a hazardous concentration of  $H_2S$  gas or any associated byproducts of the combustion of  $H_2S$  gas, notify local law enforcement agencies regarding the contents of this plan.

In the event of the discovery of an unplanned/uncontrolled release of a hazardous concentration of  $H_2S$  gas or any associated byproducts of combustion, immediately notify local and/or state law enforcement agencies of the situation and ask for their assistance.

### II. General Public

In the event of a planned or unplanned release of a hazardous concentration of  $H_2S$  gas or any associated byproducts of combustion, notify local law enforcement agencies and ask for their assistance in alerting the general public and limiting access to any public roads that may be impacted by such a release.

### III. New Mexico Oil Conservation Division

The Permian Resources HSE Department will make any applicable notification to the New Mexico OCD regarding any release of a hazardous concentration of H₂S Gas or any associated byproducts of combustion.

### IV. New Mexico Environment Department

The Permian Resources HSE Department will make any applicable notifications to the NMED regarding any release of a hazardous concentration of H₂S gas or any associated byproducts of combustion.

### V. Bureau of Land Management

The Permian Resources Regulatory Department will make any applicable notifications to the BLM regarding any release of a hazardous concentration of H<sub>2</sub>S gas or any associated byproducts of combustion.

Section 5.0 - Emergency Contact List

EMERGENCY CONTACT LIST				
PERMIAN RESOURCES CORPORATION.				
POSITION	NAME	OFFICE	CELL	ALT PHONE
	Opera	ations		
Operations Superintendent	Rick Lawson		432.530.3188	
TX Operations Superintendent	Josh Graham	432.940.3191	432.940.3191	
NM Operations Superintendent	Manual Mata	432.664.0278	575.408.0216	
Drilling Manager	Jason Fitzgerald	432.315.0146	318.347.3916	
Drilling Engineer	Parker Simmons	432.400.1038	281.536.9813	
Production Manager	Levi Harris	432.219.8568	720.261.4633	
SVP Development Ops	Clayton Smith	720.499.1416	361.215.2494	
SVP Production Ops	Casey McCain	432.695.4239	432.664.6140	
	HSE & Re	gulatory		
H&S Manager	Adam Hicks		903.426.4556	
Regulatory Manager	Stephanie Rabadue		432.260.4388	
Environmental Manager	Montgomery Floyd	432-315-0123	432-425-8321	
HSE Consultant	Blake Wisdom		918-323-2343	
Local, State, & Federal Agencies				
Eddy County Sheriff		575-887-7551		911
New Mexico State Highway Patrol		505-757-2297		911
Carlsbad Fire / EMS		575-885-3125		911
Carlsbad Memorial Hospital		575-887-4100		
Secorp – Safety Contractor	Ricky Stephens		(325)-262-0707	
New Mexico Oil Conservation Division  – District 1 Office – Hobbs, NM.		575-393-6161		
New Mexico Environment Department – District III Office – Hobbs, NM		575-397-6910		
New Mexico Oil Conservation Division  – Hobbs, NM	24 Hour Emergency	575-393-6161		
Bureau of Land Management – Carlsbad, NM		575-706-2779		
Eddy County PET Inspector		575-361-2822		
U.S. Fish & Wildlife		502-248-6911		

### Section 6.0 - Drilling Location Information

### I. Site Safety Information

### 1. Safe Briefing Area

a. There shall be two areas that will be designated as "SAFE BRIEFING AREAs". If  $H_2S$  is detected in concentrations equal to or in excess of 10 ppm all personnel not assigned emergency duties are to assemble in the designated Safe Briefing area for instructions. These two areas shall be positioned in accessible locations to facilitate the availability of self-contained breathing air devices. The briefing areas shall be positioned no less than 250' from the wellhead and in such locations that at least one briefing area will be upwind from the well at all times.

Permian Resources Corporation	H₂S Contingency Plan	Eddy County, New Mexico
	Alpine South Pad	

### 2. Wind Indicators

a. 4 Windsocks will be installed at strategic points on the facility.

### 3. Danger Signs

a. A warning sign indicating the possible well conditions will be displayed at the location entrance.

# DANGER POISONOUS GAS HYDROGEN SULFIDE DO NOT APPROACH IF AMBER LIGHTS ARE FLASHING

### 4. H<sub>2</sub>S Detectors and Alarms

a. Continuous monitoring type  $H_2S$  detectors, capable of sensing a minimum of 5ppm  $H_2S$  in air will be located centrally located at the tanks, heater treater, and combustor. Continuous monitoring type  $SO_2$  detector will also be located at the combustor. The automatic  $H_2S$  alarm/flashing light will be located at the site entrance and in front of tank battery.

### 5. <u>Safety Trailer</u>

a. A safety trailer equipped with an emergency cascade breathing air system with 2 ea. Work/escape packs, a stretcher, 2 OSHA approved full body harnesses, and a 20# Class ABC fire extinguisher shall be available at the site in close proximity to the safe briefing area. The cascade system shall be able to be deployed to the drill floor when needed to provide safe breathing air to the workers as needed.

### 6. Well Control Equipment

- a. The location shall have a flare line to a remote automatic ignitor and back up flare gun, placed 150' from the wellhead.
- b. The location shall be equipped with a remotely operated choke system and a mud gas separator.

### 7. Mud Program

a. Company shall have a mud program that contains sufficient weight and additives to control  $H_2S$ .

### 8. Metallurgy

a. All drill strings, casing, tubing, wellhead, BOP, spools, kill lines, choke manifold and lines, and valves shall be suitable for anticipated H<sub>2</sub>S volume and pressure.

### 9. Communication

a. The location shall be equipped with a means of effective communication such as a cell phones, intercoms, satellite phones or landlines.


Permian Resources Corporation	H₂S Contingency Plan	Eddy County, New Mexico
	Alpine South Pad	

### II. Directions to Location

BEGINNING AT THE INTERSECTION OF U.S. HIGHWAY 285 AND U.S.
HIGHWAY 82 IN ARTESIA, NEW MEXICO, PROCEED IN AN EASTERLY
DIRECTION ALONG U.S. HIGHWAY 82 APPROXIMATELY 12.3 MILES TO THE
JUNCTION OF THIS ROAD AND ILLINOIS CAMP ROAD TO THE SOUTH; TURN
RIGHT AND PROCEED IN A SOUTHERLY DIRECTION APPROXIMATELY 8.1
MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE
EAST; TURN LEFT AND PROCEED IN AN EASTERLY DIRECTION
APPROXIMATELY 0.3 MILES TO THE JUNCTION OF THIS ROAD AND AN
EXISTING ROAD TO THE SOUTH; TURN RIGHT AND PROCEED IN A
SOUTHERLY DIRECTION APPROXIMATELY 0.6 MILES TO THE BEGINNING OF
THE PROPOSED ACCESS ROAD TO THE WEST; FOLLOW ROAD FLAGS IN A
WESTERLY DIRECTION APPROXIMATELY 22' TO THE PROPOSED LOCATION.


TOTAL DISTANCE FROM ARTESIA, NEW MEXICO TO THE PROPOSED WELL LOCATION IS APPROXIMATELY 21.3 MILES.

### Plat of Location



Permian Resources Corporation	H₂S Contingency Plan	Eddy County, New Mexico
	Alpine South Pad	


1. Routes of Ingress & Egress (MAP)



2. Residences in proximity to the 3000' Radius of Exposure (ROE) (MAP)

There are no residences or public gathering places with the 100 PPM, 300 PPM, or 500 PPM ROE.

### Map of 3000' ROE Perimeter



### 100 PPM, 300 PPM, & 500 PPM Max ROE under worst case scenario

Enter H₂S in PPM	1500	
Enter Gas flow in mcf/day (maximum worst case conditions)	2500	
500 ppm radius of exposure (public road)	<u>105</u>	feet
<b>300</b> ppm radius of exposure	<u>146</u>	feet
100 ppm radius of exposure (public area)	<u>230</u>	feet

- Location NAD 83 GPS Coordinates Lat: 32.672203, Long: -104.208876
- 3. Public Roads in proximity of the Radius of Exposure (ROE)

There are no public roads that would be within the 500 PPM ROE. The closest public road is Illinois Camp Rd, which is approx. 3,240' from the location.

Permian Resources Corporation	H₂S Contingency Plan	Eddy County, New Mexico
	Alpine South Pad	

### Section 7.0 - Hazard Communication

### I. Physical Characteristics of Hydrogen Sulfide Gas

Hydrogen sulfide ( $H_2S$ ) is a colorless, poisonous gas that is soluble in water. It can be present in crude oils, condensates, natural gas and wastewater streams.

 $H_2S$  is heavier than air with a vapor density of 1.189 (air = 1.0); however,  $H_2S$  is most often mixed with other gases. These mixtures of  $H_2S$  and other gases can be heavier or lighter than air. If the  $H_2S$ -containing mixture is heavier, it can collect in low areas such as ditches, ravines, firewalls, and pits; in storage tanks; and in areas of poor ventilation. Please see physical properties in **Table 7.0.** 

With H₂S the sense of smell is rapidly lost allowing lethal concentrations to be accumulated without warning. The toxicity of hydrogen sulfide at varying concentrations is indicated in the **Table 7.1.** 

**Warning:** Do not use the mouth-to-mouth method if a victim ingested or inhaled hydrogen sulfide. Give artificial respiration with the aid of a pocket mask equipped with a one-way valve or other proper respiratory medical device.

Table 7.0. Physical Properties of H₂S

Properties of H2S	Description	
Vapor Density > 1 = 1.189 Air = 1	<ul> <li>H2S gas is slightly heavier than air, which can cause it to settle in low places and build in concentration.</li> <li>Produced as a mixture with other gases associated with oil and gas production.</li> </ul>	
Flammable Range 4.3%-46% 43000 ppm – 460000 ppm	<ul> <li>H2S can be extremely flammable / explosive when these concentrations are reached by volume in air.</li> </ul>	

Although  $H_2S$  is primarily a respiratory hazard, it is also flammable and forms an explosive mixture at concentrations of 4.3%–46.0% (40,000ppm – 460,000 ppm) by volume in air.

### H<sub>2</sub>S can be encountered when:

- Venting and draining equipment.
- Opening equipment (separators, pumps, and tanks).
- Opening piping connections ("line breaking").
- Gauging and sampling storage tanks.
- Entering confined spaces.
- Working around wastewater pits, skimmers, and treatment facilities.
- II. Human Health Hazards Toxicological Information

Table 7.1. Hazards & Toxicity

Concentration	Symptoms/Effects
(ppm)	
0.00011-0.00033 ppm	Typical background concentrations
0.01-1.5 ppm	Odor threshold (when rotten egg smell is first noticeable to some). Odor becomes
	more offensive at 3-5 ppm. Above 30 ppm, odor described as sweet or sickeningly
	sweet.
2-5 ppm	Prolonged exposure may cause nausea, tearing of the eyes, headaches or loss of
	sleep. Airway problems (bronchial constriction) in some asthma patients.
20 ppm	Possible fatigue, loss of appetite, headache, irritability, poor memory, dizziness.
50-100 ppm	Slight conjunctivitis ("gas eye") and respiratory tract irritation after 1 hour. May
	cause digestive upset and loss of appetite.
100 ppm	Coughing, eye irritation, loss of smell after 2-15 minutes (olfactory fatigue). Altered
	breathing, drowsiness after 15-30 minutes. Throat irritation after 1 hour. Gradual
	increase in severity of symptoms over several hours. Death may occur after 48 hours.
100-150 ppm	Loss of smell (olfactory fatigue or paralysis).
200-300 ppm	Marked conjunctivitis and respiratory tract irritation after 1 hour. Pulmonary edema
	may occur from prolonged exposure.
500-700 ppm	Staggering, collapse in 5 minutes. Serious damage to the eyes in 30 minutes. Death
	after 30-60 minutes.
700-1000 ppm	Rapid unconsciousness, "knockdown" or immediate collapse within 1 to 2 breaths,
	breathing stops, death within minutes.
1000-2000 ppm	Nearly instant death

### III. Environmental Hazards

 $H_2S$  and its associated byproducts from combustion presents a serious environmental hazard. Sulphur Dioxide  $SO_2$  is produced as a constituent of flaring  $H_2S$  Gas and can present hazards associated, which are similar to  $H_2S$ . Although  $SO_2$  is heavier than air, it will be picked up by a breeze and carried downwind at

Permian Resources Corporation	H₂S Contingency Plan	Eddy County, New Mexico
	Alpine South Pad	

elevated temperatures. Since Sulfur Dioxide is extremely irritating to the eyes and mucous membranes of the upper respiratory tract, it has exceptionally good warning powers in this respect. The following table indicates the toxic nature of the gas. Please see the attached SDS in Appendix B for reference.

SULFUR DIOXIDE TOXICITY		
Concentration		Effects
%SO <sub>2</sub>	PPM	
0.0005	3 to 5	Pungent odor-normally a person can detect SO <sub>2</sub> in this range.
0.0012	12	Throat irritation, coughing, and constriction of the chest tearing and smarting of eyes.
0.15	150	So irritating that it can only be endured for a few minutes.
0.05	500	Causes a sense of suffocation, even with first breath.

### Section 8.0 - Regulatory Information

I. OSHA & NIOSH Information

### II. Table 8.0. OSHA & NIOSH H<sub>2</sub>S Information

Tuble clot cont a most ne		
PEL, IDLH, TLV	Description	
NIOSH PEL 10 PPM	■ PEL is the Permissible Exposure Limit that an employee may be exposed up to 8 hr / day.	
OSHA General Industry Ceiling PEL – 20 PPM	The maximum exposure limit, which cannot be exceeded for any length of time.	
IDLH 100 PPM	■ Immediately Dangerous to Life and Health	
Permian Resources PEL 10 PPM	<ul> <li>Permian Resources Policy Regarding H2S for employee safety</li> </ul>	

### III. New Mexico OCD & BLM – H<sub>2</sub>S Concentration Threshold Requirements

New Mexico NMAC 19.15.11 and Onshore Order #6 identify two Radii of Exposure (ROE) that identify potential danger to the public and require additional compliance measures. Permian Resources is required to install safety devices, establish safety procedures and develop a written  $H_2S$  contingency plan for sites where the  $H_2S$  concentrations are as follows.

Table 8.1. Calculating H<sub>2</sub>S Radius of Exposure

H₂S Radius of Exposure	Description	Control and Equipment Requirements
100 ppm	Distance from a release to where the H <sub>2</sub> S concentration in the air will dilute below 100ppm	ROE > 50-ft and includes any part of a "public area" (residence, school, business, etc., or any area that can be expected to be populated).  ROE > 3,000-ft

Permian Resources Corporation	H₂S Contingency Plan	Eddy County, New Mexico
	Alpine South Pad	

Distance from a release to where the H <sub>2</sub> S concentration in the air will dilute below 500ppm	ROE > 50-ft and includes any part of a public road (public roads are tax supported roads or any road used for public access or use)
---	---

### Calculating H<sub>2</sub>S Radius of Exposure

The ROE of an  $H_2S$  release is calculated to determine if a potentially hazardous volume of  $H_2S$  gas at 100 or 500 parts per million (ppm) is within a regulated distance requiring further action. If information about the concentration of  $H_2S$  and the potential gas release volume is known, the location of the Muster Areas will be set, and safety measures will be implemented based on the calculated radius of exposure (ROE). NMAC 19.15.11 – Hydrogen Sulfide Safety defines the ROE as the radius constructed with the gas's point of escape as its center and its length calculated by the following Pasquill-Gifford equations:

To determine the extent of the 100 ppm ROE:

 $x = [(1.589) \text{ (mole fraction } H_2S)(Q)]^{(.6258)}.$ 

To determine the extent of the **500 ppm ROE**:

 $x = [(0.4546) \text{ (mole fraction H}_2S)(Q)]^{(.6258)}$ .

Table 8.2. Calculating H2S Radius of Exposure

ROE Variable	Description
X =	ROE in feet
Q =	Max volume of gas released determined to be released in cubic feet per day (ft³/d) normalized to standard temperature and pressure, 60°F and 14.65 psia
Mole fraction H₂S =	Mole fraction of H <sub>2</sub> S in the gaseous mixture released.

The volume used as the escape rate in determining the ROE is specified in the rule as follows:

- The maximum daily volume rate of gas containing H<sub>2</sub>S handled by that system element for which the ROE is calculated.
- For existing gas wells, the current adjusted open-flow rate, or the operator's estimate of the well's capacity to flow against zero back-pressure at the wellhead.

# New Mexico Oil Conservation Division & BLM Site Requirements under NMAC 19.15.11 & Onshore Order #6

- Two cleared areas will be designated as Safe Briefing Areas. During an emergency, personnel will assemble in one of these areas for instructions from the Permian Resources Person-in-Charge. Prevailing wind direction should be considered in locating the briefing areas 200' or more on either side of the well head. One area should offset the other at an angle of 45° to 90° with respect to prevailing wind direction to allow for wind shifts during the work period.
- In the event of either an intentional or accidental releases of hydrogen sulfide, safeguards to protect the general public from the harmful effects of hydrogen sulfide must be in place for operations. A summary of the provisions in each of three H₂S ROE cases is included in **Table 8.3**.
  - o **CASE 1** -100 ppm ROE < 50'
  - CASE 2 100 ppm ROE is 50' or greater, but < 3000' and does not penetrate public area.</li>

Permian Resources Corporation	H₂S Contingency Plan	Eddy County, New Mexico
	Alpine South Pad	

O CASE 3 -100 ppm ROE is 50' or greater and penetrates a public area or 500 ppm ROE includes a public road. Also if 100 ppm ROE > 3000' regardless of public area.

Table 8.3. NMAC 19.15.11 Compliance Requirements Drilling & Production

NMAC 19.15.11 & BLM COMPLIANCE REQUIREMENTS - DRILLING & PRODUCTION			DUCTION
PROVISION	CASE 1	CASE 2	CASE 3
H <sub>2</sub> S Concentration Test	X	X	X
H-9	X	X	X
Training	X	X	X
District Office Notification	X	X	X
Drill Stem Tests Restricted	X*	X*	X
BOP Test	X*	X*	X
Materials		X	X
Warning and Marker		X	X
Security		X	X
Contingency Plan			X
Control and Equipment Safety			X
Monitors		X**	X**
Mud (ph Control or Scavenger)			X*
Wind Indicators		X**	X
Protective Breathing Equipment		X**	X
Choke Manifold, Secondary Remote Control, and Mud-Gas Separator			X
Flare Stacks			X*

### Section 9.0 - Training Requirements

### **Training**

The following elements are considered a minimum level of training for personnel assigned to operations who may encounter  $H_2S$  as part of routine or maintenance work.

- The hazards, characteristics, and properties of hydrogen sulfide (H<sub>2</sub>S) and (SO<sub>2</sub>).
- Sources of H<sub>2</sub>S and SO<sub>2</sub>.
- Proper use of H<sub>2</sub>S and SO<sub>2</sub> detection methods used at the workplace.
- Recognition of, and proper response to, the warning signals initiated by H<sub>2</sub>S and SO<sub>2</sub> detection systems in use at the workplace.
- Symptoms of H<sub>2</sub>S exposure; symptoms of SO<sub>2</sub> exposure
- Rescue techniques and first aid to victims of H<sub>2</sub>S and SO<sub>2</sub> exposure.
- Proper use and maintenance of breathing equipment for working in H₂S and SO₂ atmospheres, as appropriate theory and hands-on practice, with demonstrated proficiency (29 CFR Part 1910.134).
- Workplace practices and relevant maintenance procedures that have been established to protect personnel from the hazards of H<sub>2</sub>S and SO<sub>2</sub>.
- Wind direction awareness and routes of egress.
- Confined space and enclosed facility entry procedures (if applicable).

Permian Resources Corporation	H₂S Contingency Plan	Eddy County, New Mexico
	Alpine South Pad	

- Emergency response procedures that have been developed for the facility or operations.
- Locations and use of safety equipment.
- Locations of safe briefing areas.

### Refresher training will be conducted annually.

### Section 10.0 - Personal Protective Equipment

### I. Personal H<sub>2</sub>S Monitors

All personnel engaged in planned or unplanned work activity to mitigate the release of a hazardous concentration of H<sub>2</sub>S shall have on their person a personal H2S monitor.

### II. Fixed H<sub>2</sub>S Detection and Alarms

- 4 channel H<sub>2</sub>S monitor
- 4 wireless H<sub>2</sub>S monitors
- H<sub>2</sub>S alarm system (Audible/Red strobe)
- Personal gas monitor for each person on location
- Gas sample tubes

### III. Flame Resistant Clothing

All personnel engaged in planned or unplanned work activity associated with this Plan shall have on the appropriate level of FRC clothing.

### IV. Respiratory Protection

The following respiratory protection equipment shall be available at each drilling location.

- Working cascade system available on rig floor and pit system & 750' of air line hose
- Four (4) breathing air manifolds
- Four (4) 30-minute rescue packs
- Five (5) work/Escape units
- Five (5) escape units
- One (1) filler hose for the work/escape/rescue units

Supplied air (airline or SCBA) respiratory protection against hydrogen sulfide exposure is required in the following situations:

- When routine or maintenance work tasks involve exposure to H₂S concentrations of 10 ppm or greater.
- When a fixed location area monitor alarms, and re-entry to the work area is required to complete a job.
- When confined spaces are to be entered without knowledge of H₂S levels present, or if initial measurements are to be taken of H₂S levels.
- During rescue of employees suspected of H<sub>2</sub>S overexposure.
- For specific tasks identified with significant exposure potential and outlined in local program guidelines.
- All respiratory equipment for hydrogen sulfide must be of the supplied-air type, equipped with pressure-demand regulators and operated in the pressure-demand mode only. This is the only type of respiratory protection recommended for hydrogen sulfide application. Equipment should be approved by NIOSH/MSHA or other recognized national authority as required. If airline units are used, a five-minute egress bottle should also be carried.
- Gas masks or other air-purifying respirators MUST NEVER BE USED FOR HYDROGEN SULFIDE due to the poor warning properties of the gas.

Permian Resources Corporation	H₂S Contingency Plan	Eddy County, New Mexico
	Alpine South Pad	

 Use of respiratory protection should be accompanied by a written respiratory protection program.

### Appendix A H<sub>2</sub>S SDS



### Hydrogen sulfide

Safety Data Sheet E-4611

according to the Hazardous Products Regulation (February 11, 2015)

Date of issue: 10-15-1979 Revision date: 08-10-2016 Supersedes: 10-15-2013

### **SECTION 1: Identification**

**Product identifier** 

Product form : Substance : Hydrogen sulfide Name CAS No : 7783-06-4 Formula : H2S : Hydrogen sulfide Other means of identification : Core Products Product group

1.2. Recommended use and restrictions on use

Recommended uses and restrictions Industrial use

Use as directed

1.3. Supplier

Praxair Canada inc. 1200 – 1 City Centre Drive Mississauga - Canada L5B 1M2 T 1-905-803-1600 - F 1-905-803-1682 www.praxair.ca

#### 1.4. Emergency telephone number

Emergency number

1-800-363-0042

Call emergency number 24 hours a day only for spills, leaks, fire, exposure, or accidents involving this product.

For routine information, contact your supplier or Praxair sales representative.

### **SECTION 2: Hazard identification**

### Classification of the substance or mixture

### GHS-CA classification

Flam. Gas 1 H220 Liquefied gas
Acute Tox. 2 (Inhalation: gas)
STOT SE 3 H280 H330 H335

### GHS Label elements, including precautionary statements

### GHS-CA labelling

Precautionary statements

Hazard pictograms









Signal word : DANGER

Hazard statements

: EXTREMELY FLAMMABLE GAS
CONTAINS GAS UNDER PRESSURE; MAY EXPLODE IF HEATED FATAL IF INHALED

MAY CAUSE RESPIRATORY IRRITATION
MAY FORM EXPLOSIVE MIXTURES WITH AIR
SYMPTOMS MAY BE DELAYED

EXTENDED EXPOSURE TO GAS REDUCES THE ABILITY TO SMELL SULFIDES

Do not handle until all safety precautions have been read and understood Keep away from heat, hot surfaces, sparks, open flames and other ignition sources. No

smokina

This document is only controlled while on the Praxair Canada Inc. website and a copy of this controlled version is available for download. Praxair cannot assure the integrity or accuracy of any version of this document after it has been downloaded or removed from our website. EN (English) SDS ID : E-4611

1/9

Permian Resources Corporation

H<sub>2</sub>S Contingency Plan

Alpine South Pad

Eddy County, New Mexico



### Hydrogen sulfide

Safety Data Sheet E-4611

according to the Hazardous Products Regulation (February 11, 2015)

Date of issue: 10-15-1979 Revision date: 08-10-2016 Supersedes: 10-15-2013

Do not breathe gas

Use and store only outdoors or in a well-ventilated area

Avoid release to the environment

Wear protective gloves, protective clothing, eye protection, respiratory protection, and/or face

rotection

Leaking gas fire: Do not extinguish, unless leak can be stopped safely

In case of leakage, eliminate all ignition sources

Store locked up

Dispose of contents/container in accordance with container Supplier/owner instructions

Protect from sunlight when ambient temperature exceeds 52°C (125°F)

Close valve after each use and when empty

Do not open valve until connected to equipment prepared for use When returning cylinder, install leak tight valve outlet cap or plug

Do not depend on odour to detect the presence of gas

### 2.3. Other hazards

Other hazards not contributing to the classification

: Contact with liquid may cause cold burns/frostbite.

2.4. Unknown acute toxicity (GHS-CA)

No data available

### SECTION 3: Composition/information on ingredients

### 3.1. Substances

Name	CAS No.	% (Vol.)	Common Name (synonyms)
Hydrogen sulfide (Main constituent)	(CAS No) 7783-06-4		Hydrogen sulfide (H2S) / Hydrogen sulphide / Sulfur hydride / Sulfureted hydrogen / Dihydrogen sulphide / Hydrogensulfide

### 3.2. Mixtures

Not applicable

### **SECTION 4: First-aid measures**

### 4.1. Description of first aid measures

First-aid measures after inhalation : Ren

: Remove to fresh air and keep at rest in a position comfortable for breathing. If not breathing, give artificial respiration. If breathing is difficult, trained personnel should give oxygen. Call a physician.

First-aid measures after skin contact

: The liquid may cause frostbite. For exposure to liquid, immediately warm frostbite area with warm water not to exceed 105°F (41°C). Water temperature should be tolerable to normal skin. Maintain skin warming for at least 15 minutes or until normal coloring and sensation have returned to the affected area. In case of massive exposure, remove clothing while showering with warm water. Seek medical evaluation and treatment as soon as possible.

First-aid measures after eye contact

Immediately flush eyes thoroughly with water for at least 15 minutes. Hold the eyelids open and away from the eyeballs to ensure that all surfaces are flushed thoroughly. Contact an ophthalmologist immediately.

First-aid measures after ingestion

: Ingestion is not considered a potential route of exposure.

### 4.2. Most important symptoms and effects (acute and delayed)

No additional information available

### 4.3. Immediate medical attention and special treatment, if necessary

Other medical advice or treatment

: Obtain medical assistance. Treat with corticosteroid spray as soon as possible after inhalation.

### SECTION 5: Fire-fighting measures

### 5.1. Suitable extinguishing media

Suitable extinguishing media

: Carbon dioxide, Dry chemical, Water spray or fog. Use extinguishing media appropriate for surrounding fire.

### 5.2. Unsuitable extinguishing media

No additional information available

This document is only controlled while on the Praxair Canada Inc. website and a copy of this controlled version is available for download. Praxair cannot assure the integrity or accuracy of any version of this document after it has been downloaded or removed from our website.

EN (English) SDS ID : E-4611 2/9



### Hydrogen sulfide

Safety Data Sheet E-4611

according to the Hazardous Products Regulation (February 11, 2015)

Date of issue: 10-15-1979 Revision date: 08-10-2016 Supersedes: 10-15-2013

### 5.3. Specific hazards arising from the hazardous product

Fire hazard

: EXTREMELY FLAMMABLE GAS. If venting or leaking gas catches fire, do not extinguish flames. Flammable vapors may spread from leak, creating an explosive reignition hazard. Vapors can be ignited by pilot lights, other flames, smoking, sparks, heaters, electrical equipment, static discharge, or other ignition sources at locations distant from product handling point. Explosive atmospheres may linger. Before entering an area, especially a confined area, check the atmosphere with an appropriate device.

Explosion hazard : EXTREMELY FLAMMABLE GAS. Forms explosive mixtures with air and oxidizing agents.

Reactivity : No reactivity hazard other than the effects described in sub-sections below.

Reactivity in case of fire : No reactivity hazard other than the effects described in sub-sections below.

### 5.4. Special protective equipment and precautions for fire-fighters

Firefighting instructions

: DANGER! Toxic, flammable liquefied gas

Evacuate all personnel from the danger area. Use self-contained breathing apparatus (SCBA) and protective clothing. Immediately cool containers with water from maximum distance. Stop flow of gas if safe to do so, while continuing cooling water spray. Remove ignition sources if safe to do so. Remove containers from area of fire if safe to do so. On-site fire brigades must comply with their provincial and local fire code regulations.

Special protective equipment for fire fighters

Standard protective clothing and equipment (Self Contained Breathing Apparatus) for fire

fighters.

Other information

: Containers are equipped with a pressure relief device. (Exceptions may exist where authorized by TC.)

### SECTION 6: Accidental release measures

### 6.1. Personal precautions, protective equipment and emergency procedures

General measures

: DANGER! Toxic, flammable liquefied gas. Forms explosive mixtures with air and oxidizing agents. Immediately evacuate all personnel from danger area. Use self-contained breathing apparatus where needed. Remove all sources of ignition if safe to do so. Reduce vapors with fog or fine water spray, taking care not to spread liquid with water. Shut off flow if safe to do so. Ventilate area or move container to a well-ventilated area. Flammable vapors may spread from leak and could explode if reignited by sparks or flames. Explosive atmospheres way linger. Before entering area, especially confined areas, check atmosphere with an appropriate device.

### 6.2. Methods and materials for containment and cleaning up

Methods for cleaning up

: Try to stop release. Reduce vapour with fog or fine water spray. Prevent waste from contaminating the surrounding environment. Prevent soil and water pollution. Dispose of contents/container in accordance with local/regional/national/international regulations. Contact supplier for any special requirements.

### 6.3. Reference to other sections

For further information refer to section 8: Exposure controls/personal protection

### **SECTION 7: Handling and storage**

### 7.1. Precautions for safe handling

Precautions for safe handling

: Leak-check system with soapy water; never use a flame

All piped systems and associated equipment must be grounded

Keep away from heat, hot surfaces, sparks, open flames and other ignition sources. No smoking. Use only non-sparking tools. Use only explosion-proof equipment

Wear leather safety gloves and safety shoes when handling cylinders. Protect cylinders from physical damage; do not drag, roll, slide or drop. While moving cylinder, always keep in place removable valve cover. Never attempt to lift a cylinder by its cap; the cap is intended solely to protect the valve. When moving cylinders, even for short distances, use a cart (trolley, hand truck, etc.) designed to transport cylinders. Never insert an object (e.g., wrench, screwdriver, pry bar) into cap openings; doing so may damage the valve and cause a leak. Use an adjustable strap wrench to remove over-tight or rusted caps. Slowly open the valve. If the valve is hard to open, discontinue use and contact your supplier. Close the container valve after each use; keep closed even when empty. Never apply flame or localized heat directly to any part of the container. High temperatures may damage the container and could cause the pressure relief device to fail prematurely, venting the container contents. For other precautions in using this product, see section 16.

This document is only controlled while on the Praxair Canada Inc. website and a copy of this controlled version is available for download. Praxair cannot assure the integrity or accuracy of any version of this document after it has been downloaded or removed from our website.

EN (English) SDS ID : E-4611 3/9



# Hydrogen sulfide

Safety Data Sheet E-4611

according to the Hazardous Products Regulation (February 11, 2015)

Date of issue: 10-15-1979 Revision date: 08-10-2016 Supersedes: 10-15-2013

### 7.2. Conditions for safe storage, including any incompatibilities

Storage conditions

: Store only where temperature will not exceed 125°F (52°C). Post "No Smoking/No Open Flames" signs in storage and use areas. There must be no sources of ignition. Separate packages and protect against potential fire and/or explosion damage following appropriate codes and requirements (e.g., NFPA 30, NFPA 55, NFPA 70, and/or NFPA 221 in the U.S.) or according to requirements determined by the Authority Having Jurisdiction (AHJ). Always secure containers upright to keep them from falling or being knocked over. Install valve protection cap, if provided, firmly in place by hand when the container is not in use. Store full and empty containers separately. Use a first-in, first-out inventory system to prevent storing full containers for long periods. For other precautions in using this product, see section 16

OTHER PRECAUTIONS FOR HANDLING, STORAGE, AND USE: When handling product under pressure, use piping and equipment adequately designed to withstand the pressures to be encountered. Never work on a pressurized system. Use a back flow preventive device in the piping. Gases can cause rapid suffocation because of oxygen deficiency; store and use with adequate ventilation. If a leak occurs, close the container valve and blow down the system in a safe and environmentally correct manner in compliance with all international, federal/national, state/provincial, and local laws; then repair the leak. Never place a container where it may become part of an electrical circuit.

SECTION 8: Exposure controls/personal protection		
3.1. Control parameters		
Hydrogen sulfide (7783-06-4)		
USA - ACGIH	ACGIH TLV-TWA (ppm)	1 ppm
USA - ACGIH	ACGIH TLV-STEL (ppm)	5 ppm
USA - OSHA	OSHA PEL (Ceiling) (ppm)	20 ppm
Canada (Quebec)	VECD (mg/m³)	21 mg/m³
Canada (Quebec)	VECD (ppm)	15 ppm
Canada (Quebec)	VEMP (mg/m³)	14 mg/m³
Canada (Quebec)	VEMP (ppm)	10 ppm
Alberta	OEL Ceiling (mg/m³)	21 mg/m³
Alberta	OEL Ceiling (ppm)	15 ppm
Alberta	OEL TWA (mg/m³)	14 mg/m³
Alberta	OEL TWA (ppm)	10 ppm
British Columbia	OEL Ceiling (ppm)	10 ppm
Manitoba	OEL STEL (ppm)	5 ppm
Manitoba	OEL TWA (ppm)	1 ppm
New Brunswick	OEL STEL (mg/m³)	21 mg/m³
New Brunswick	OEL STEL (ppm)	15 ppm
New Brunswick	OEL TWA (mg/m³)	14 mg/m³
New Brunswick	OEL TWA (ppm)	10 ppm
New Foundland & Labrador	OEL STEL (ppm)	5 ppm
New Foundland & Labrador	OEL TWA (ppm)	1 ppm
Nova Scotia	OEL STEL (ppm)	5 ppm
Nova Scotia	OEL TWA (ppm)	1 ppm
Nunavut	OEL Ceiling (mg/m³)	28 mg/m³
Nunavut	OEL Ceiling (ppm)	20 ppm
Nunavut	OEL STEL (mg/m³)	21 mg/m³
Nunavut	OEL STEL (ppm)	15 ppm
Nunavut	OEL TWA (mg/m³)	14 mg/m³
Nunavut	OEL TWA (ppm)	10 ppm
Northwest Territories	OEL STEL (ppm)	15 ppm

This document is only controlled while on the Praxair Canada Inc. website and a copy of this controlled version is available for download. Praxair cannot assure the integrity or accuracy of any version of this document after it has been downloaded or removed from our website.

EN (English) SDS ID : E-4611 4/9

Permian Resources Corporation	H₂S Contingency Plan	Eddy County, New Mexico
	Alpine South Pad	



### Hydrogen sulfide

Safety Data Sheet E-4611

according to the Hazardous Products Regulation (February 11, 2015)

Date of issue: 10-15-1979 Revision date: 08-10-2016 Supersedes: 10-15-2013

Hydrogen sulfide (7783-06-4)		
Northwest Territories	OEL TWA (ppm)	10 ppm
Ontario	OEL STEL (ppm)	15 ppm
Ontario	OEL TWA (ppm)	10 ppm
Prince Edward Island	OEL STEL (ppm)	5 ppm
Prince Edward Island	OEL TWA (ppm)	1 ppm
Québec	VECD (mg/m³)	21 mg/m³
Québec	VECD (ppm)	15 ppm
Québec	VEMP (mg/m³)	14 mg/m³
Québec	VEMP (ppm)	10 ppm
Saskatchewan	OEL STEL (ppm)	15 ppm
Saskatchewan	OEL TWA (ppm)	10 ppm
Yukon	OEL STEL (mg/m³)	27 mg/m³
Yukon	OEL STEL (ppm)	15 ppm
Yukon	OEL TWA (mg/m³)	15 mg/m³
Yukon	OEL TWA (ppm)	10 ppm

### 8.2. Appropriate engineering controls

Appropriate engineering controls

: Use corrosion-resistant equipment. Use an explosion-proof local exhaust system. Local exhaust and general ventilation must be adequate to meet exposure standards. MECHANICAL (GENERAL): Inadequate - Use only in a closed system. Use explosion proof equipment and lighting.

### 8.3. Individual protection measures/Personal protective equipment

Personal protective equipment

: Safety glasses. Face shield. Gloves.







Hand protection

: Wear work gloves when handling containers. Wear heavy rubber gloves where contact with product may occur.

Eye protection

: Wear goggles and a face shield when transfilling or breaking transfer connections. Select in accordance with the current CSA standard Z94.3, "Industrial Eye and Face Protection", and any provincial regulations, local by

Respiratory protection

: Respiratory protection: Use respirable fume respirator or air supplied respirator when working in confined space or where local exhaust or ventilation does not keep exposure below TLV. Select in accordance with provincial regulations, local bylaws or guidelines. Selection should be based on the current CSA standard Z94.4, "Selection, Care, and Use of Respirators." Respirators should also be approved by NIOSH and MSHA. For emergencies or instances with unknown exposure levels, use a self-contained breathing apparatus (SCBA).

Thermal hazard protection

: Wear cold insulating gloves when transfilling or breaking transfer connections. Standard EN 511 - Cold insulating gloves.

Other information

Other protection: Safety shoes for general handling at customer sites. Metatarsal shoes and cuffless trousers for cylinder handling at packaging and filling plants. Select in accordance with the current CSA standard Z195, "Protective Foot Wear", and any provincial regulations, local bylaws or guidelines. For working with flammable and oxidizing materials, consider the use of flame resistant anti-static safety clothing.

### SECTION 9: Physical and chemical properties

### 9.1. Information on basic physical and chemical properties

Physical state

: Gas

Appearance : Colorless gas. Colorless liquid at low temperature or under high pressure.

Molecular mass : 34 g/mol
Colour : Colourless.
Odour : Odour can

Odour : Odour can persist. Poor warning properties at low concentrations. Rotten eggs.
Odour threshold : Odour threshold is subjective and inadequate to warn of overexposure.

SDS ID : E-4611

This document is only controlled while on the Praxair Canada Inc. website and a copy of this controlled version is available for download. Praxair cannot assure the integrity or accuracy of any version of this document after it has been downloaded or removed from our website.

5/9

EN (English)



### Hydrogen sulfide

Safety Data Sheet E-4611

according to the Hazardous Products Regulation (February 11, 2015)

Date of issue: 10-15-1979 Revision date: 08-10-2016 Supersedes: 10-15-2013

: Not applicable. рΗ pH solution : No data available Relative evaporation rate (butylacetate=1) : No data available Relative evaporation rate (ether=1) : Not applicable. Melting point : -86 °C : -82.9 °C Freezing point Boiling point : -60.3 °C Flash point : Not applicable. Critical temperature : 100.4 °C : 260 °C Auto-ignition temperature Decomposition temperature : No data available : 1880 kPa

Vapour pressure Vapour pressure at 50 °C : No data available Critical pressure : 8940 kPa : >=

Relative vapour density at 20 °C Relative density : No data available

Relative density of saturated gas/air mixture : No data available Density : No data available

Relative gas density : 1.2

Solubility : Water: 3980 mg/l Log Pow : Not applicable. : Not applicable. Log Kow Viscosity, kinematic : Not applicable. : Not applicable. Viscosity, dynamic Viscosity, kinematic (calculated value) (40 °C) : No data available Explosive properties : Not applicable. Oxidizing properties : None. Flammability (solid, gas)

4.3 - 46 vol %

#### 9.2. Other information

: Liquefied gas Gas group

Additional information Gas/vapour heavier than air. May accumulate in confined spaces, particularly at or below

ground level

### **SECTION 10: Stability and reactivity**

Reactivity : No reactivity hazard other than the effects described in sub-sections below.

Chemical stability : Stable under normal conditions

Possibility of hazardous reactions : May react violently with oxidants. Can form explosive mixture with air.

Conditions to avoid : Avoid moisture in installation systems. Keep away from heat/sparks/open flames/hot surfaces.

: Ammonia. Bases. Bromine pentafluoride. Chlorine trifluoride. chromium trioxide. (and heat). Incompatible materials Copper (powdered), Fluorine, Lead, Lead oxide, Mercury, Nitric acid, Nitrogen trifluoride, nitrogen sulfide, Organic compounds, Oxidizing agents, Oxygen difluoride, Rubber, Sodium.

(and moisture). Water.

Hazardous decomposition products : Thermal decomposition may produce : Sulfur. Hydrogen.

### **SECTION 11: Toxicological information**

### Information on toxicological effects

Acute toxicity (oral) : Not classified Acute toxicity (dermal) : Not classified

This document is only controlled while on the Praxair Canada Inc. website and a copy of this controlled version is available for download. Praxair cannot assure the integrity or accuracy of any version of this document after it has been downloaded or removed from our website.

EN (English) SDS ID : E-4611 6/9

Permian Resources Corporation	H₂S Contingency Plan	Eddy County, New Mexico
	Alpine South Pad	



### Hydrogen sulfide

Safety Data Sheet E-4611

according to the Hazardous Products Regulation (February 11, 2015)

Date of issue: 10-15-1979 Revision date: 08-10-2016 Supersedes: 10-15-2013

Acute toxicity (inhalation) : Inhalation:gas: FATAL IF INHALED.

Hydrogen sulfide ( \f )7783-06-4	
LC50 inhalation rat (mg/l)	0.99 mg/l (Exposure time: 1 h)
LC50 inhalation rat (ppm)	356 ppm/4h
ATE CA (gases)	356.00000000 ppmv/4h
ATE CA (vapours)	0.99000000 mg/l/4h
ATE CA (dust,mist)	0.99000000 mg/l/4h

Skin corrosion/irritation : Not classified pH: Not applicable.

Serious eye damage/irritation : Not classified pH: Not applicable.

Respiratory or skin sensitization : Not classified
Germ cell mutagenicity : Not classified
Carcinogenicity : Not classified

Reproductive toxicity : Not classified

Specific target organ toxicity (single exposure) : MAY CAUSE RESPIRATORY IRRITATION.

Specific target organ toxicity (repeated : Not classified

exposure)

Aspiration hazard : Not classified

SECTION 12: Eco	logical	information
	iogica.	IIIIOIIIIGGIOII

### 12.1. Toxicity

Ecology - general : VERY TOXIC TO AQUATIC LIFE.

Hydrogen sulfide (7783-06-4)	
LC50 fish 1	0.0448 mg/l (Exposure time: 96 h - Species: Lepomis macrochirus [flow-through])
LC50 fish 2	0.016 mg/l (Exposure time: 96 h - Species: Pimephales promelas [flow-through])

### 12.2. Persistence and degradability

Hydrogen sulfide (7783-06-4)	
Persistence and degradability	Not applicable for inorganic gases.

### 12.3. Bioaccumulative potential

Hydrogen sulfide (7783-06-4)	
BCF fish 1	(no bioaccumulation expected)
Log Pow	Not applicable.
Log Kow	Not applicable.
Bioaccumulative potential	No data available.

### 12.4. Mobility in soil

Hydrogen sulfide (7783-06-4)	
Mobility in soil	No data available.
Log Pow	Not applicable.
Log Kow	Not applicable.
Ecology - soil	Because of its high volatility, the product is unlikely to cause ground or water pollution.

### 12.5. Other adverse effects

Other adverse effects : May cause pH changes in aqueous ecological systems.

Effect on the ozone layer : None

Effect on global warming : No known effects from this product

This document is only controlled while on the Praxair Canada Inc. website and a copy of this controlled version is available for download. Praxair cannot assure the integrity or accuracy of any version of this document after it has been downloaded or removed from our website.

EN (English) SDS ID : E-4611 7/9



# Hydrogen sulfide

Safety Data Sheet E-4611

according to the Hazardous Products Regulation (February 11, 2015)

Date of issue: 10-15-1979 Revision date: 08-10-2016 Supersedes: 10-15-2013

### **SECTION 13: Disposal considerations**

### 13.1. Disposal methods

Waste disposal recommendations : Do not attempt to dispose of residual or unused quantities. Return container to supplier.

### SECTION 14: Transport information

### 14.1. Basic shipping description

In accordance with TDG

TDG

UN-No. (TDG) : UN1053

TDG Primary Hazard Classes : 2.3 - Class 2.3 - Toxic Gas.

TDG Subsidiary Classes : 2.1

Proper shipping name : HYDROGEN SULPHIDE

**ERAP Index** : 500 Explosive Limit and Limited Quantity Index : 0 Passenger Carrying Ship Index : Forbidden Passenger Carrying Road Vehicle or Passenger : Forbidden

Carrying Railway Vehicle Index

#### 14.3. Air and sea transport

UN-No. (IMDG) : 1053

Proper Shipping Name (IMDG) : HYDROGEN SULPHIDE

Class (IMDG) : 2 - Gases MFAG-No : 117

: 1053 UN-No. (IATA)

Proper Shipping Name (IATA) : Hydrogen sulphide

Class (IATA) : 2

### **SECTION 15: Regulatory information**

### 15.1. National regulations

### Hydrogen sulfide (7783-06-4)

Listed on the Canadian DSL (Domestic Substances List)

### 15.2. International regulations

### Hydrogen sulfide (7783-06-4)

Listed on the AICS (Australian Inventory of Chemical Substances)

Listed on IECSC (Inventory of Existing Chemical Substances Produced or Imported in China)

Listed on the EEC inventory EINECS (European Inventory of Existing Commercial Chemical Substances) Listed on the Japanese ENCS (Existing & New Chemical Substances) inventory

Listed on the Korean ECL (Existing Chemicals List)

Listed on NZIoC (New Zealand Inventory of Chemicals)

Listed on PICCS (Philippines Inventory of Chemicals and Chemical Substances) Listed on the United States TSCA (Toxic Substances Control Act) inventory

Listed on INSQ (Mexican national Inventory of Chemical Substances)

### **SECTION 16: Other information**

Date of issue : 15/10/1979 Revision date : 10/08/2016 : 15/10/2013 Supersedes

Indication of changes:

Training advice : Users of breathing apparatus must be trained. Ensure operators understand the toxicity hazard.

Ensure operators understand the flammability hazard.

This document is only controlled while on the Praxair Canada Inc. website and a copy of this controlled version is available for download. Praxair cannot assure the integrity or accuracy of any version of this document after it has been downloaded or removed from our website.

EN (English) SDS ID : E-4611 8/9



### Hydrogen sulfide

Safety Data Sheet E-4611

according to the Hazardous Products Regulation (February 11, 2015)

Date of issue: 10-15-1979 Revision date: 08-10-2016 Supersedes: 10-15-2013

Other information

: When you mix two or more chemicals, you can create additional, unexpected hazards. Obtain and evaluate the safety information for each component before you produce the mixture. Consult an industrial hygienist or other trained person when you evaluate the end product. Before using any plastics, confirm their compatibility with this product

Praxair asks users of this product to study this SDS and become aware of the product hazards and safety information. To promote safe use of this product, a user should (1) notify employees, agents, and contractors of the information in this SDS and of any other known product hazards and safety information, (2) furnish this information to each purchaser of the product, and (3) ask each purchaser to notify its employees and customers of the product hazards and safety information

The opinions expressed herein are those of qualified experts within Praxair Canada Inc. We believe that the information contained herein is current as of the date of this Safety Data Sheet. Since the use of this information and the conditions of use are not within the control of Praxair Canada Inc, it is the user's obligation to determine the conditions of safe use of the product. Praxair Canada Inc, SDSs are furnished on sale or delivery by Praxair Canada Inc, or the independent distributors and suppliers who package and sell our products. To obtain current SDSs for these products, contact your Praxair sales representative, local distributor, or supplier, or download from www.praxair.ca. If you have questions regarding Praxair SDSs, would like the document number and date of the latest SDS, or would like the names of the Praxair suppliers in your area, phone or write Praxair Canada Inc, (Phone: 1-888-257-5149; Address: Praxair Canada Inc, L5B 1M2).

PRAXAIR and the Flowing Airstream design are trademarks or registered trademarks of Praxair Technology, Inc. in the United States and/or other countries.

NFPA health hazard

: 4 - Very short exposure could cause death or serious residual injury even though prompt medical attention was

NFPA fire hazard

: 4 - Will rapidly or completely vaporize at normal pressure and temperature, or is readily dispersed in air and will burn readily.

rea

NFPA reactivity

 0 - Normally stable, even under fire exposure conditions, and are not reactive with water.



HMIS III Rating

Health

Flammability

Flammability

Physical

: 2 Moderate Hazard - Temporary or minor injury may occur

: 4 Severe Hazard - Flammable gases, or very volatile flammable liquids with flash points below 73 F, and boiling points below 100 F. Materials may ignite spontaneously with air. (Class IA)

: 2 Moderate Hazard - Materials that are unstable and may undergo violent chemical changes at normal temperature and pressure with low risk for explosion. Materials may react violently with water or form peroxides upon exposure to air.

SDS Canada (GHS) - Praxair

This information is based on our current knowledge and is intended to describe the product for the purposes of health, safety and environmental requirements only. It should not therefore be construed as guaranteeing any specific property of the product.

This document is only controlled while on the Praxair Canada Inc. website and a copy of this controlled version is available for download. Praxair cannot assure the integrity or accuracy of any version of this document after it has been downloaded or removed from our website.

EN (English) SDS ID : E-4611 9/9

SO<sub>2</sub>SDS



### Safety Data Sheet

Material Name: SULFUR DIOXIDE **SDS ID: MAT22290** 

### Section 1 - PRODUCT AND COMPANY IDENTIFICATION

### Material Name

SULFUR DIOXIDE

#### Synonyms

MTG MSDS 80; SULFUROUS ACID ANHYDRIDE; SULFUROUS OXIDE; SULPHUR DIOXIDE; SULFUROUS ANHYDRIDE; FERMENTICIDE LIQUID; SULFUR DIOXIDE(SO2); SULFUR OXIDE; SULFUR OXIDE(SO2)

### Chemical Family

inorganic, gas

### Product Description

Classification determined in accordance with Compressed Gas Association standards.

Industrial and Specialty Gas Applications.

### Restrictions on Use

None known.

### Details of the supplier of the safety data sheet

MATHESON TRI-GAS, INC.

3 Mountainview Road

Warren, NJ 07059

General Information: 1-800-416-2505

Emergency #: 1-800-424-9300 (CHEMTREC)

Outside the US: 703-527-3887 (Call collect)

### Section 2 - HAZARDS IDENTIFICATION

### Classification in accordance with paragraph (d) of 29 CFR 1910.1200.

Gases Under Pressure - Liquefied gas

Acute Toxicity - Inhalation - Gas - Category 3

Skin Corrosion/Irritation - Category 1B

Serious Eye Damage/Eye Irritation - Category 1

Simple Asphyxiant

### **GHS Label Elements**

Symbol(s)



### Signal Word

Danger

### Hazard Statement(s)

Contains gas under pressure; may explode if heated.

Toxic if inhaled.

Causes severe skin burns and eye damage.

May displace oxygen and cause rapid suffocation.

### Precautionary Statement(s)

Prevention

Use only outdoors or in a well-ventilated area.

Wear protective gloves/protective clothing/eye protection/face protection.

Page 1 of 9 Issue date: 2021-01-30 Revision 8.0 Print date: 2021-01-30

SDS ID: MAT22290

Permian Resources Corporation	H₂S Contingency Plan	Eddy County, New Mexico
	Alpine South Pad	



### Safety Data Sheet

### Material Name: SULFUR DIOXIDE

Wash thoroughly after handling. Do not breathe dusts or mists.

Response

IF INHALED: Remove person to fresh air and keep comfortable for breathing.

IF IN EYES: Rinse cautiously with water for several minutes. Remove contact lenses, if present and easy to do.

IF ON SKIN (or hair): Remove/take off immediately all contaminated clothing. Rinse skin with water/shower.

Wash contaminated clothing before reuse.

IF SWALLOWED: Rinse mouth. Do NOT induce vomiting.

Immediately call a POISON CENTER or doctor.

Specific treatment (see label).

Storage

Store in a well-ventilated place. Keep container tightly closed.

Store locked up.

Protect from sunlight.

Disposal

Dispose of contents/container in accordance with local/regional/national/international regulations.

Other Hazards

Contact with liquified gas may cause frostbite.

Section 3 - COMPOSITION / INFORMATION ON INGREDIENTS		
CAS	Component Name	Percent
7446-09-5	Sulfur dioxide	100.0
Casting A FIRST AID MEASURES		

### Section 4 - FIRST AID MEASURES

### Inhalation

IF INHALED: Remove person to fresh air and keep at rest in a position comfortable for breathing. Get immediate medical attention.

IF ON SKIN (or hair): Remove/take off immediately all contaminated clothing. Rinse skin with water/shower. Wash contaminated clothing before reuse. If frostbite or freezing occur, immediately flush with plenty of lukewarm water (105-115°F; 41-46°C). If warm water is not available, gently wrap affected parts in blankets. DO NOT induce vomiting. Get immediate medical attention.

### Eves

IF IN EYES: Rinse cautiously with water for several minutes. Remove contact lenses, if present and easy to do. Continue rinsing. Get immediate medical attention.

### Ingestion

IF SWALLOWED: Rinse mouth. Do NOT induce vomiting. Get immediate medical attention.

### Most Important Symptoms/Effects

### Acute

Toxic if inhaled, frostbite, suffocation, respiratory tract burns, skin burns, eye burns

### Delayed

No information on significant adverse effects.

Indication of any immediate medical attention and special treatment needed

Treat symptomatically and supportively.

### Note to Physicians

For inhalation, consider oxygen.

Page 2 of 9 Issue date: 2021-01-30 Revision 8.0 Print date: 2021-01-30

Permian Resources Corporation	H₂S Contingency Plan	Eddy County, New Mexico
	Alpine South Pad	



### Safety Data Sheet

Material Name: SULFUR DIOXIDE SDS ID: MAT22290

### Section 5 - FIRE FIGHTING MEASURES

### **Extinguishing Media**

### Suitable Extinguishing Media

carbon dioxide, regular dry chemical, Large fires: Use regular foam or flood with fine water spray.

### Unsuitable Extinguishing Media

None known.

### Special Hazards Arising from the Chemical

Negligible fire hazard.

### **Hazardous Combustion Products**

sulfur oxides

### Fire Fighting Measures

Move container from fire area if it can be done without risk. Cool containers with water spray until well after the fire is out. Stay away from the ends of tanks. Keep unnecessary people away, isolate hazard area and deny entry.

### Special Protective Equipment and Precautions for Firefighters

Wear full protective fire fighting gear including self contained breathing apparatus (SCBA) for protection against possible exposure.

### Section 6 - ACCIDENTAL RELEASE MEASURES

### Personal Precautions, Protective Equipment and Emergency Procedures

Wear personal protective clothing and equipment, see Section 8.

### Methods and Materials for Containment and Cleaning Up

Keep unnecessary people away, isolate hazard area and deny entry. Stay upwind and keep out of low areas.

Ventilate closed spaces before entering. Evacuation radius: 150 feet. Stop leak if possible without personal risk.

Reduce vapors with water spray. Do not get water directly on material.

### **Environmental Precautions**

Avoid release to the environment.

### Section 7 - HANDLING AND STORAGE

### Precautions for Safe Handling

Do not get in eyes, on skin, or on clothing. Do not breathe gas, fumes, vapor, or spray. Wash hands thoroughly after handling. Use only outdoors or in a well-ventilated area. Wear protective gloves/protective clothing/eye protection/face protection. Contaminated work clothing should not be allowed out of the workplace. Do not eat, drink or smoke when using this product. Keep only in original container. Avoid release to the environment.

### Conditions for Safe Storage, Including any Incompatibilities

Store in a well-ventilated place. Keep container tightly closed.

Store locked up.

Protect from sunlight.

Store and handle in accordance with all current regulations and standards. Protect from physical damage. Store outside or in a detached building. Keep separated from incompatible substances.

### Incompatible Materials

bases, combustible materials, halogens, metal carbide, metal oxides, metals, oxidizing materials, peroxides, reducing agents

### Section 8 - EXPOSURE CONTROLS / PERSONAL PROTECTION

Component Exposure Limits	
Sulfur dioxide	7446-09-5
ACGIH:	0.25 ppm STEL

Page 3 of 9 Issue date: 2021-01-30 Revision 8.0 Print date: 2021-01-30

SDS ID: MAT22290

Permian Resources Corporation	H₂S Contingency Plan	Eddy County, New Mexico
	Alpine South Pad	



### Safety Data Sheet

Material Name: SULFUR DIOXIDE

NIOSH:	2 ppm TWA; 5 mg/m3 TWA
	5 ppm STEL; 13 mg/m3 STEL
	100 ppm IDLH
OSHA (US):	5 ppm TWA; 13 mg/m3 TWA
Mexico:	0.25 ppm STEL [PPT-CT]

ACGIH - Threshold Limit Values - Biological Exposure Indices (BEI)

There are no biological limit values for any of this product's components.

Engineering Controls

Provide local exhaust or process enclosure ventilation system. Ensure compliance with applicable exposure limits.

Individual Protection Measures, such as Personal Protective Equipment

Eye/face protection

Wear splash resistant safety goggles with a faceshield. Contact lenses should not be worn. Provide an emergency eye wash fountain and quick drench shower in the immediate work area.

Skin Protection

Wear appropriate chemical resistant clothing. Wear chemical resistant clothing to prevent skin contact.

Respiratory Protection

Any self-contained breathing apparatus that has a full facepiece and is operated in a pressure-demand or other positive-pressure mode.

Glove Recommendations

Wear appropriate chemical resistant gloves.

Section 9 - PHYSICAL AND CHEMICAL PROPERTIES			
Appearance	colorless gas	Physical State	gas
Odor	irritating odor	Color	colorless
Odor Threshold	3 - 5 ppm	рН	(Acidic in solution)
Melting Point	-73 °C (-99 °F )	Boiling Point	-10 °C (14 °F )
<b>Boiling Point Range</b>	Not available	Freezing point	Not available
Evaporation Rate	>1 (Butyl acetate = 1 )	Flammability (solid, gas)	Not available
Autoignition Temperature	Not available	Flash Point	(Not flammable )
Lower Explosive Limit	Not available	Decomposition temperature	Not available
Upper Explosive Limit	Not available	Vapor Pressure	2432 mmHg @ 20 °C
Vapor Density (air=1)	2.26	Specific Gravity (water=1)	1.462 at -10 °C

Page 4 of 9 Issue date: 2021-01-30 Revision 8.0 Print date: 2021-01-30

Permian Resources Corporation	H₂S Contingency Plan	Eddy County, New Mexico
	Alpine South Pad	



### Safety Data Sheet

Material Name: SULFUR DIOXIDE SDS ID: MAT22290

Water Solubility	22.8 % (@ 0 °C )	Partition coefficient: n- octanol/water	Not available
Viscosity	Not available	Kinematic viscosity	Not available
Solubility (Other)	Not available	Density	Not available
Physical Form	liquified gas	Molecular Formula	S-O2
Molecular Weight	64.06		

### Solvent Solubility

Soluble

alcohol, acetic acid, sulfuric acid, ether, chloroform, Benzene, sulfuryl chloride, nitrobenzenes, Toluene, acetone

### Section 10 - STABILITY AND REACTIVITY

Reactivity

No reactivity hazard is expected.

Chemical Stability

Stable at normal temperatures and pressure.

Possibility of Hazardous Reactions

Will not polymerize.

Conditions to Avoid

Minimize contact with material. Containers may rupture or explode if exposed to heat.

Incompatible Materials

bases, combustible materials, halogens, metal carbide, metal oxides, metals, oxidizing materials, peroxides, reducing

Hazardous decomposition products

oxides of sulfur

### Section 11 - TOXICOLOGICAL INFORMATION

### Information on Likely Routes of Exposure

Inhalatio

Toxic if inhaled. Causes damage to respiratory system, burns, difficulty breathing

Skin Contact

skin burns

Eye Contact

eye burns

Ingestion

burns, nausea, vomiting, diarrhea, stomach pain

Acute and Chronic Toxicity

Component Analysis - LD50/LC50

The components of this material have been reviewed in various sources and the following selected endpoints are published:

Sulfur dioxide (7446-09-5)

Inhalation LC50 Rat 965 - 1168 ppm 4 h

Product Toxicity Data Acute Toxicity Estimate

No data available. Immediate Effects

Page 5 of 9 Issue date: 2021-01-30 Revision 8.0 Print date: 2021-01-30

**SDS ID: MAT22290** 

Permian Resources Corporation	H₂S Contingency Plan	Eddy County, New Mexico
	Alpine South Pad	



### Safety Data Sheet

Material Name: SULFUR DIOXIDE

Toxic if inhaled, frostbite, suffocation, respiratory tract burns, skin burns, eye burns

**Delayed Effects** 

No information on significant adverse effects.

Irritation/Corrosivity Data

respiratory tract burns, skin burns, eye burns

Respiratory Sensitization

No data available.

Dermal Sensitization

No data available.

Component Carcinogenicity

Sulfur dioxide	7446-09-5
ACGIH:	A4 - Not Classifiable as a Human Carcinogen
IARC:	Monograph 54 [1992] (Group 3 (not classifiable))

### Germ Cell Mutagenicity

No data available.

Tumorigenic Data

No data available Reproductive Toxicity

No data available.

Specific Target Organ Toxicity - Single Exposure

No target organs identified.

Specific Target Organ Toxicity - Repeated Exposure

No target organs identified.

Aspiration hazard

Not applicable.

Medical Conditions Aggravated by Exposure

respiratory disorders

### Section 12 - ECOLOGICAL INFORMATION

Component Analysis - Aquatic Toxicity

No LOLI ecotoxicity data are available for this product's components.

Persistence and Degradability

No data available.

Bioaccumulative Potential

No data available.

Mobility

No data available.

### Section 13 - DISPOSAL CONSIDERATIONS

Disposal Methods

Dispose of contents/container in accordance with local/regional/national/international regulations.

Component Waste Numbers

The U.S. EPA has not published waste numbers for this product's components.

### Section 14 - TRANSPORT INFORMATION

US DOT Information:

Shipping Name: SULFUR DIOXIDE

Page 6 of 9 Issue date: 2021-01-30 Revision 8.0 Print date: 2021-01-30

SDS ID: MAT22290

Permian Resources Corporation	H₂S Contingency Plan	Eddy County, New Mexico
	Alpine South Pad	



### Safety Data Sheet

Material Name: SULFUR DIOXIDE

Hazard Class: 2.3 UN/NA #: UN1079 Required Label(s): 2.3

IMDG Information:

Shipping Name: SULPHUR DIOXIDE

Hazard Class: 2.3 UN#: UN1079 Required Label(s): 2.3

TDG Information:

Shipping Name: SULFUR DIOXIDE

Hazard Class: 2.3 UN#: UN1079 Required Label(s): 2.3

International Bulk Chemical Code

This material does not contain any chemicals required by the IBC Code to be identified as dangerous chemicals in bulk.

### Section 15 - REGULATORY INFORMATION

### U.S. Federal Regulations

This material contains one or more of the following chemicals required to be identified under SARA Section 302 (40 CFR 355 Appendix A), SARA Section 313 (40 CFR 372.65), CERCLA (40 CFR 302.4), TSCA 12(b), and/or require an OSHA process safety plan.

Sulfur dioxide	7446-09-5			
SARA 302:	500 lb TPQ			
OSHA (safety):	1000 lb TQ (Liquid )			
SARA 304:	500 lb EPCRA RQ			

### SARA Section 311/312 (40 CFR 370 Subparts B and C) reporting categories

Gas Under Pressure; Acute toxicity; Skin Corrosion/Irritation; Serious Eye Damage/Eye Irritation; Simple Asphyxiant

### U.S. State Regulations

The following components appear on one or more of the following state hazardous substances lists:

Component	CAS	CA	MA	MN	NJ	PA
Sulfur dioxide	7446-09-5	Yes	Yes	Yes	Yes	Yes

California Safe Drinking Water and Toxic Enforcement Act (Proposition 65)



WARNING

This product can expose you to chemicals including Sulfur dioxide, which is known to the State of California to cause birth defects or other reproductive harm. For more information go to www.P65Warnings.ca.gov.

Page 7 of 9 Issue date: 2021-01-30 Revision 8.0 Print date: 2021-01-30

Permian Resources Corporation	H₂S Contingency Plan	Eddy County, New Mexico
	Alpine South Pad	



### Safety Data Sheet

Material Name: SULFUR DIOXIDE

SDS ID: MAT22290	
------------------	--

Sulfur dioxide	7446-09-5
Repro/Dev. Tox	developmental toxicity, 7/29/2011

### Component Analysis - Inventory Sulfur dioxide (7446-09-5)

US	CA	AU	CN	EU	JP - ENCS	JP - ISHL	KR KECI - Annex 1	KR KECI - Annex 2
Yes	DSL	Yes	Yes	EIN	Yes	Yes	Yes	No

KR - REACH CCA	MX	NZ	PH	TH-TECI	TW, CN	VN (Draft)
No	Yes	Yes	Yes	Yes	Yes	Yes

### Section 16 - OTHER INFORMATION

### NFPA Ratings

Health: 3 Fire: 0 Instability: 0

Hazard Scale: 0 = Minimal 1 = Slight 2 = Moderate 3 = Serious 4 = Severe

Summary of Changes SDS update: 02/10/2016

### Key / Legend

ACGIH - American Conference of Governmental Industrial Hygienists; ADR - European Road Transport; AU -Australia; BOD - Biochemical Oxygen Demand; C - Celsius; CA - Canada; CA/MA/MN/NJ/PA -California/Massachusetts/Minnesota/New Jersey/Pennsylvania\*; CAS - Chemical Abstracts Service; CERCLA -Comprehensive Environmental Response, Compensation, and Liability Act; CFR - Code of Federal Regulations (US); CLP - Classification, Labelling, and Packaging; CN - China; CPR - Controlled Products Regulations; DFG -Deutsche Forschungsgemeinschaft; DOT - Department of Transportation; DSD - Dangerous Substance Directive; DSL - Domestic Substances List; EC - European Commission; EEC - European Economic Community; EIN -European Inventory of (Existing Commercial Chemical Substances); EINECS - European Inventory of Existing Commercial Chemical Substances; ENCS - Japan Existing and New Chemical Substance Inventory; EPA -Environmental Protection Agency; EU - European Union; F - Fahrenheit; F - Background (for Venezuela Biological Exposure Indices); IARC - International Agency for Research on Cancer; IATA - International Air Transport Association; ICAO - International Civil Aviation Organization; IDL - Ingredient Disclosure List; IDLH -Immediately Dangerous to Life and Health; IMDG - International Maritime Dangerous Goods; ISHL - Japan Industrial Safety and Health Law; IUCLID - International Uniform Chemical Information Database; JP - Japan; Kow - Octanol/water partition coefficient; KR KECI Annex 1 - Korea Existing Chemicals Inventory (KECI) / Korea Existing Chemicals List (KECL); KR KECI Annex 2 - Korea Existing Chemicals Inventory (KECI) / Korea Existing Chemicals List (KECL), KR - Korea; LD50/LC50 - Lethal Dose/ Lethal Concentration; KR REACH CCA Korea Registration and Evaluation of Chemical Substances Chemical Control Act; LEL - Lower Explosive Limit; LLV - Level Limit Value; LOLI - List Of LIsts™ - ChemADVISOR's Regulatory Database; MAK - Maximum Concentration Value in the Workplace; MEL - Maximum Exposure Limits; MX - Mexico; Ne- Non-specific; NFPA - National Fire Protection Agency; NIOSH - National Institute for Occupational Safety and Health; NJTSR - New Jersey Trade Secret Registry; Nq - Non-quantitative; NSL - Non-Domestic Substance List (Canada); NTP -National Toxicology Program; NZ - New Zealand; OSHA - Occupational Safety and Health Administration; PEL-Permissible Exposure Limit; PH - Philippines; RCRA - Resource Conservation and Recovery Act; REACH-Registration, Evaluation, Authorisation, and restriction of Chemicals; RID - European Rail Transport; SARA -Superfund Amendments and Reauthorization Act; Sc - Semi-quantitative; STEL - Short-term Exposure Limit;

Page 8 of 9 Issue date: 2021-01-30 Revision 8.0 Print date: 2021-01-30

### State of New Mexico Energy, Minerals and Natural Resources Department

Submit Electronically Via E-permitting

Oil Conservation Division 1220 South St. Francis Dr. Santa Fe, NM 87505

### NATURAL GAS MANAGEMENT PLAN

This Natural Gas Management Plan must be submitted with each Application for Permit to Drill (APD) for a new or recompleted well.

# Section 1 – Plan Description

Effective May 25, 2021

I. Operator: Permian Resources Operating, LLC	OGRID: <u>372165</u>	<b>Date:</b> <u>10/16/25</u>
II. Type: ⊠ Original □ Amendment due to □ 19.15.27.9.Do	(6)(a) NMAC □ 19.15.27.9.D(6)(1	b) NMAC  Other.
If Other, please describe:		
III. Well(s): Provide the following information for each new be recompleted from a single well pad or connected to a central		s proposed to be drilled or proposed to

Well Name	API	ULSTR	Footages	Anticipated Oil BBL/D	Anticipated Gas MCF/D	Anticipated Produced Water
						BBL/D
Alpine 7-11 State 123H	TBD	I-7-19S-28E	1673' FSL, 783' FEL	544	1859	1870
Alpine 7-11 State 124H	TBD	I-7-19S-28E	1646' FSL, 764' FEL	544	1859	1870
Alpine 7-11 State 133H	TBD	I-7-19S-28E	1605' FSL, 734' FEL	544	1859	1870
Alpine 7-11 State 134H	TBD	I-7-19S-28E	1578' FSL, 715' FEL	544	1859	1870
Alpine 7-11 State 131H	TBD	A-7-19S-28E	1150' FNL, 241' FEL	544	1859	1870
Alpine 7-11 State 202H	TBD	A-7-19S-28E	1183' FNL, 241' FEL	544	1859	1870
Alpine 7-11 State 121H	TBD	A-7-19S-28E	1233' FNL, 241' FEL	544	1859	1870
Alpine 7-11 State 122H	TBD	A-7-19S-28E	1266' FNL, 241' FEL	544	1859	1870

IV. Central Delivery Point Name: Alpine [See 19.15.27.9(D)(1) NMAC]

V. Anticipated Schedule: Provide the following information for each new or recompleted well or set of wells proposed to be drilled or proposed to be recompleted from a single well pad or connected to a central delivery point.

Well Name	API	Spud Date	TD Reached Date	Completion Commencement Date	Initial Flow Back Date	First Production Date
Alpine 7-11 State 123H	TBD	1/8/2026	<u>TBD</u>	TBD	<u>TBD</u>	<u>TBD</u>
Alpine 7-11 State 124H	TBD	1/8/2026	<b>TBD</b>	<u>TBD</u>	<b>TBD</b>	<u>TBD</u>
Alpine 7-11 State 133H	TBD	<u>1/8/2026</u>	<u>TBD</u>	<u>TBD</u>	<u>TBD</u>	TBD
Alpine 7-11 State 134H	TBD	<u>1/8/2026</u>	<u>TBD</u>	<u>TBD</u>	<u>TBD</u>	TBD
Alpine 7-11 State 131H	TBD	<u>1/8/2026</u>	<b>TBD</b>	<u>TBD</u>	<b>TBD</b>	<u>TBD</u>
Alpine 7-11 State 202H	TBD	<u>1/8/2026</u>	<b>TBD</b>	<u>TBD</u>	<b>TBD</b>	<u>TBD</u>
Alpine 7-11 State 121H	TBD	<u>1/8/2026</u>	<b>TBD</b>	<u>TBD</u>	<b>TBD</b>	<u>TBD</u>
Alpine 7-11 State 122H	TBD	<u>1/8/2026</u>	<u>TBD</u>	<u>TBD</u>	<u>TBD</u>	TBD
				·		

VI. Separation Equipment: Attach a complete description of how Operator will size separation equipment to optimize gas capture.

VII. Operational Practices: Attach a complete description of the actions Operator will take to comply with the requirements of Subsection A through F of 19.15.27.8 NMAC.

VIII. Best Management Practices: Attach a complete description of Operator's best management practices to minimize venting during active and planned maintenance.

# **Section 2 – Enhanced Plan**

# **EFFECTIVE APRIL 1, 2022**

Beginning April 1, 2022, an operator that is not in compliance with its statewide natural gas capture requirement for the applicable reporting area must complete this section.

☑ Operator certifies that it is not required to complete this section because Operator is in compliance with its statewide natural gas capture requirement for the applicable reporting area.

Well		API	Anticipated Average Natural Gas Rate MCF/D	Anticipated Volume of Natural Gas for the First Year MCF
Natural Gas Ga	thering System (NO	GGS):		
Operator	System	ULSTR of Tie-in	Anticipated Gathering Start Date	Available Maximum Daily Capacity of System Segment Tie-in
oduction operation	ns to the existing or	planned interconnect of t		ticipated pipeline route(s) connecting to m(s), and the maximum daily capacity sected.

natural gas gathering system(s) described above will continue to meet anticipated increases in line pressure caused by the new well(s).

☐ Attach Operator's plan to manage production in response to the increased line pressure.

**XIV. Confidentiality:** 

Operator asserts confidentiality pursuant to Section 71-2-8 NMSA 1978 for the information provided in Section 2 as provided in Paragraph (2) of Subsection D of 19.15.27.9 NMAC, and attaches a full description of the specific information for which confidentiality is asserted and the basis for such assertion.

XIII. Line Pressure. Operator \( \square\) does \( \square\) does not anticipate that its existing well(s) connected to the same segment, or portion, of the

# Section 3 - Certifications Effective May 25, 2021

<b>Effective May 25, 2021</b>
Operator certifies that, after reasonable inquiry and based on the available information at the time of submittal:
$\boxtimes$ Operator will be able to connect the well(s) to a natural gas gathering system in the general area with sufficient capacity to transport one hundred percent of the anticipated volume of natural gas produced from the well(s) commencing on the date of first production, taking into account the current and anticipated volumes of produced natural gas from other wells connected to the pipeline gathering system; or
Operator will not be able to connect to a natural gas gathering system in the general area with sufficient capacity to transport one hundred percent of the anticipated volume of natural gas produced from the well(s) commencing on the date of first production, taking into account the current and anticipated volumes of produced natural gas from other wells connected to the pipeline gathering system. <i>If Operator checks this box, Operator will select one of the following:</i>
<b>Well Shut-In.</b> □ Operator will shut-in and not produce the well until it submits the certification required by Paragraph (4) of Subsection D of 19.15.27.9 NMAC; or
Venting and Flaring Plan. □ Operator has attached a venting and flaring plan that evaluates and selects one or more of the potential alternative beneficial uses for the natural gas until a natural gas gathering system is available, including:  (a) power generation on lease; (b) power generation for grid; (c) compression on lease; (d) liquids removal on lease; (e) reinjection for underground storage; (f) reinjection for temporary storage; (g) reinjection for enhanced oil recovery; (h) fuel cell production; and (i) other alternative beneficial uses approved by the division.

# **Section 4 - Notices**

- 1. If, at any time after Operator submits this Natural Gas Management Plan and before the well is spud:
- (a) Operator becomes aware that the natural gas gathering system it planned to connect the well(s) to has become unavailable or will not have capacity to transport one hundred percent of the production from the well(s), no later than 20 days after becoming aware of such information, Operator shall submit for OCD's approval a new or revised venting and flaring plan containing the information specified in Paragraph (5) of Subsection D of 19.15.27.9 NMAC; or
- (b) Operator becomes aware that it has, cumulatively for the year, become out of compliance with its baseline natural gas capture rate or natural gas capture requirement, no later than 20 days after becoming aware of such information, Operator shall submit for OCD's approval a new or revised Natural Gas Management Plan for each well it plans to spud during the next 90 days containing the information specified in Paragraph (2) of Subsection D of 19.15.27.9 NMAC, and shall file an update for each Natural Gas Management Plan until Operator is back in compliance with its baseline natural gas capture rate or natural gas capture requirement.
- 2. OCD may deny or conditionally approve an APD if Operator does not make a certification, fails to submit an adequate venting and flaring plan which includes alternative beneficial uses for the anticipated volume of natural gas produced, or if OCD determines that Operator will not have adequate natural gas takeaway capacity at the time a well will be spud.

I certify that, after reasonable inquiry, the statements in and attached to this Natural Gas Management Plan are true and correct to the best of my knowledge and acknowledge that a false statement may be subject to civil and criminal penalties under the Oil and Gas Act.

Signature: Casoù Evan-
Printed Name: Cassie Evans
Title: Regulatory Specialist
E-mail Address: Cassie.Evans@permianres.com
Date: 11/2/2025
Phone: 432-313-1732
OIL CONSERVATION DIVISION
(Only applicable when submitted as a standalone form)
Approved By:
Title:
Approval Date:
Conditions of Approval:

## **Natural Gas Management Plan Descriptions**

# **VI. Separation Equipment:**

Permian utilizes a production forecast from our Reservoir Engineering team to appropriately size each permanent, 3-phase separator and heater treater utilized for production operations. Our goal is to maintain 5 minutes of retention time in the test vessel and 20 minutes in the heater treater at peak production rates. The gas produced is routed from the separator to the gas sales line.

## **VII. Operational Practices:**

# Drilling

During Permian's drilling operations it is uncommon for venting or flaring to occur. If flaring is needed due to safety concerns, gas will be routed to a flare and volumes will be estimated.

#### **Flowback**

During completion/recompletion flowback operations, after separation flowback begins and as soon as it is technically feasible, Permian routes gas though a permanent separator and the controlled facility where the gas is either sold or flared through a high-pressure flare if needed.

#### Production

Per 19.15.27.8.D, Permian's facilities are designed to minimize waste. Our produced gas will only be vented or flared in an emergency or malfunction situation, except as allowed for normal operations noted in 19.15.27.8.D(2) & (4). All gas that is flared is metered. All gas that may be vented will be estimated.

## Performance Standards

Permian utilizes a production forecast from our Reservoir Engineering team to appropriately size each permanent, 3-phase separator and heater treater utilized for production operations.

All of Permian's permanent storage tanks associated with production operations which are routed to a flare or control device are equipped with an automatic gauging system.

All of Permian's flare stacks, both currently installed and for future installation, are:

- 1) Appropriately sized and designed to ensure proper combustion efficiency.
- 2) Equipped with an automatic ignitor or continuous pilot.
- 3) Anchored and located at least 100 feet from the well and storage tanks.

Permian's field operations and HSE teams have implemented an AVO inspection schedule that adheres to the requirements of 19.15.27.8.E(5).

All of our operations and facilities are designed to minimize waste. We routinely employ the following methods and practices:

- Closed-loop systems
- Enclosed and properly sized tanks

- Vapor recovery units to maximize recovery of low-pressure gas streams and potential unauthorized emissions
- Low-emitting or electric engines whenever practical
- Combustors and flare stacks in the event of a malfunction or emergency
- Routine facility inspections to identify leaking components, functioning control devices, such as flares and combustors, and repair / replacement of malfunctioning components where applicable

#### Measurement or estimation

Permian measures or estimates the volumes of natural gas vented, flared and/or beneficially used for all of our drilling, completing and producing wells. We utilize accepted industry standards and methodology which can be independently verified. Annual GOR testing is completed on our wells and will be submitted as required by the OCD. None of our equipment is designed to allow diversion around metering elements except during inspection, maintenance and repair operations.

# **VIII. Best Management Practices:**

Permian utilizes the following BMPs to minimize venting during active and planned maintenance activities:

- Use a closed-loop process wherever possible during planned maintenance activities, such as blowdowns, liquid removal, and work over operations.
- Employ low-emitting or electric engines for equipment, such as compressors
- Adhere to a strict preventative maintenance program which includes routine facility inspections, identification of component malfunctions, and repairing or replacing components such as hatches, seals, valves, etc. where applicable
- Utilize vapor recovery units (VRU's) to maximize recovery of volumes of low-pressure gas streams and potential unauthorized emissions
- Route low pressure gas and emissions streams to a combustion device to prevent venting where necessary

#### **Natural Gas Management Plan Descriptions**

## **VI. Separation Equipment:**

Permian utilizes a production forecast from our Reservoir Engineering team to appropriately size each permanent, 3-phase separator and heater treater utilized for production operations. Our goal is to maintain 5 minutes of retention time in the test vessel and 20 minutes in the heater treater at peak production rates. The gas produced is routed from the separator to the gas sales line.

## **VII. Operational Practices:**

# Drilling

During Permian's drilling operations it is uncommon for venting or flaring to occur. If flaring is needed due to safety concerns, gas will be routed to a flare and volumes will be estimated.

#### **Flowback**

During completion/recompletion flowback operations, after separation flowback begins and as soon as it is technically feasible, Permian routes gas though a permanent separator and the controlled facility where the gas is either sold or flared through a high-pressure flare if needed.

#### Production

Per 19.15.27.8.D, Permian's facilities are designed to minimize waste. Our produced gas will only be vented or flared in an emergency or malfunction situation, except as allowed for normal operations noted in 19.15.27.8.D(2) & (4). All gas that is flared is metered. All gas that may be vented will be estimated.

## Performance Standards

Permian utilizes a production forecast from our Reservoir Engineering team to appropriately size each permanent, 3-phase separator and heater treater utilized for production operations.

All of Permian's permanent storage tanks associated with production operations which are routed to a flare or control device are equipped with an automatic gauging system.

All of Permian's flare stacks, both currently installed and for future installation, are:

- 1) Appropriately sized and designed to ensure proper combustion efficiency.
- 2) Equipped with an automatic ignitor or continuous pilot.
- 3) Anchored and located at least 100 feet from the well and storage tanks.

Permian's field operations and HSE teams have implemented an AVO inspection schedule that adheres to the requirements of 19.15.27.8.E(5).

All of our operations and facilities are designed to minimize waste. We routinely employ the following methods and practices:

- Closed-loop systems
- Enclosed and properly sized tanks

- Vapor recovery units to maximize recovery of low-pressure gas streams and potential unauthorized emissions
- Low-emitting or electric engines whenever practical
- Combustors and flare stacks in the event of a malfunction or emergency
- Routine facility inspections to identify leaking components, functioning control devices, such as flares and combustors, and repair / replacement of malfunctioning components where applicable


#### Measurement or estimation

Permian measures or estimates the volumes of natural gas vented, flared and/or beneficially used for all of our drilling, completing and producing wells. We utilize accepted industry standards and methodology which can be independently verified. Annual GOR testing is completed on our wells and will be submitted as required by the OCD. None of our equipment is designed to allow diversion around metering elements except during inspection, maintenance and repair operations.


# **VIII. Best Management Practices:**

Permian utilizes the following BMPs to minimize venting during active and planned maintenance activities:

- Use a closed-loop process wherever possible during planned maintenance activities, such as blowdowns, liquid removal, and work over operations.
- Employ low-emitting or electric engines for equipment, such as compressors
- Adhere to a strict preventative maintenance program which includes routine facility inspections, identification of component malfunctions, and repairing or replacing components such as hatches, seals, valves, etc. where applicable
- Utilize vapor recovery units (VRU's) to maximize recovery of volumes of low-pressure gas streams and potential unauthorized emissions
- Route low pressure gas and emissions streams to a combustion device to prevent venting where necessary



- 1. Represented curve is generic based on 3-Years available information for the Bone Spring formation and may not be representative of forecasted production or actual volumes.
- 2. Decline curves are based on an average 10,000ft lateral length. Multiple factors may influence production and decline curves, including but not limited to: lateral length and completion type.



- 1. Represented curve is generic based on 3-Years available information for the Bone Spring formation and may not be representative of forecasted production or actual volumes.
- 2. Decline curves are based on an average 10,000ft lateral length. Multiple factors may influence production and decline curves, including but not limited to: lateral length and completion type.

#### **Natural Gas Management Plan Descriptions**

# **VI. Separation Equipment:**

Permian utilizes a production forecast from our Reservoir Engineering team to appropriately size each permanent, 3-phase separator and heater treater utilized for production operations. Our goal is to maintain 5 minutes of retention time in the test vessel and 20 minutes in the heater treater at peak production rates. The gas produced is routed from the separator to the gas sales line.

## **VII. Operational Practices:**

# Drilling

During Permian's drilling operations it is uncommon for venting or flaring to occur. If flaring is needed due to safety concerns, gas will be routed to a flare and volumes will be estimated.

#### **Flowback**

During completion/recompletion flowback operations, after separation flowback begins and as soon as it is technically feasible, Permian routes gas though a permanent separator and the controlled facility where the gas is either sold or flared through a high-pressure flare if needed.

#### Production

Per 19.15.27.8.D, Permian's facilities are designed to minimize waste. Our produced gas will only be vented or flared in an emergency or malfunction situation, except as allowed for normal operations noted in 19.15.27.8.D(2) & (4). All gas that is flared is metered. All gas that may be vented will be estimated.

#### Performance Standards

Permian utilizes a production forecast from our Reservoir Engineering team to appropriately size each permanent, 3-phase separator and heater treater utilized for production operations.

All of Permian's permanent storage tanks associated with production operations which are routed to a flare or control device are equipped with an automatic gauging system.

All of Permian's flare stacks, both currently installed and for future installation, are:

- 1) Appropriately sized and designed to ensure proper combustion efficiency.
- 2) Equipped with an automatic ignitor or continuous pilot.
- 3) Anchored and located at least 100 feet from the well and storage tanks.

Permian's field operations and HSE teams have implemented an AVO inspection schedule that adheres to the requirements of 19.15.27.8.E(5).

All of our operations and facilities are designed to minimize waste. We routinely employ the following methods and practices:

- Closed-loop systems
- Enclosed and properly sized tanks

- Vapor recovery units to maximize recovery of low-pressure gas streams and potential unauthorized emissions
- Low-emitting or electric engines whenever practical
- Combustors and flare stacks in the event of a malfunction or emergency
- Routine facility inspections to identify leaking components, functioning control devices, such as flares and combustors, and repair / replacement of malfunctioning components where applicable


#### Measurement or estimation

Permian measures or estimates the volumes of natural gas vented, flared and/or beneficially used for all of our drilling, completing and producing wells. We utilize accepted industry standards and methodology which can be independently verified. Annual GOR testing is completed on our wells and will be submitted as required by the OCD. None of our equipment is designed to allow diversion around metering elements except during inspection, maintenance and repair operations.


# **VIII. Best Management Practices:**

Permian utilizes the following BMPs to minimize venting during active and planned maintenance activities:

- Use a closed-loop process wherever possible during planned maintenance activities, such as blowdowns, liquid removal, and work over operations.
- Employ low-emitting or electric engines for equipment, such as compressors
- Adhere to a strict preventative maintenance program which includes routine facility inspections, identification of component malfunctions, and repairing or replacing components such as hatches, seals, valves, etc. where applicable
- Utilize vapor recovery units (VRU's) to maximize recovery of volumes of low-pressure gas streams and potential unauthorized emissions
- Route low pressure gas and emissions streams to a combustion device to prevent venting where necessary



- 1. Represented curve is generic based on 3-Years available information for the Bone Spring formation and may not be representative of forecasted production or actual volumes.
- 2. Decline curves are based on an average 10,000ft lateral length. Multiple factors may influence production and decline curves, including but not limited to: lateral length and completion type.



- 1. Represented curve is generic based on 3-Years available information for the Bone Spring formation and may not be representative of forecasted production or actual volumes.
- 2. Decline curves are based on an average 10,000ft lateral length. Multiple factors may influence production and decline curves, including but not limited to: lateral length and completion type.