

District I
1625 N. French Dr., Hobbs, NM 88240
District II
811 S. First St., Artesia, NM 88210
District III
1000 Rio Brazos Rd., Aztec, NM 87410
District IV
1220 S. St. Francis Dr., Santa Fe, NM 87505

State of New Mexico
Energy, Minerals & Natural
Resources

Form C-104
Revised August 1, 2011

Submit one copy to appropriate District Office

Oil Conservation Division
1220 South St. Francis Dr.

AMENDED REPORT

I. REQUEST FOR ALLOWABLE MINERAL AUTHORIZATION TO TRANSPORT

¹ Operator name and Address EOG RESOURCES INC PO BOX 2267 MIDLAND, TEXAS 79702		² OGRID Number 7377
		³ Reason for Filing Code/ Effective Date NW 09/07/2022
⁴ API Number 30 - 025-48852	⁵ Pool Name WC025 G08 S253216D; UPPER WOLFCAMP	⁶ Pool Code 98270
⁷ Property Code 330803	⁸ Property Name JEFE 29 FEDERAL COM	⁹ Well Number 710H

II. ¹⁰ Surface Location

Ul or lot no.	Section	Township	Range	Lot Idn	Feet from the	North/South Line	Feet from the	East/West line	County
L	29	25S	32E		2187'	SOUTH	754'	WEST	LEA

¹¹ Bottom Hole Location

UL or lot no.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County
M	32	25S	32E		110'	SOUTH	975'	WEST	LEA
¹² Lse Code	¹³ Producing Method Code FLOWING	¹⁴ Gas Connection Date	¹⁵ C-129 Permit Number	¹⁶ C-129 Effective Date	¹⁷ C-129 Expiration Date				

III. Oil and Gas Transporters

¹⁸ Transporter OGRID	¹⁹ Transporter Name and Address	²⁰ O/G/W
372812	EOGRM	OIL
151618	ENTERPRISE FIELD SERVICES	GAS
298751	REGENCY FIELD SERVICES	GAS
36785	DCP MIDSTREAM	GAS

IV. Well Completion Data

²¹ Spud Date	²² Ready Date	²³ TD	²⁴ PBDT	²⁵ Perforations	²⁶ DHC, MC
04/18/2022	09/07/2022	19,618'	19,587'	12,027 - 19,587'	
²⁷ Hole Size	²⁸ Casing & Tubing Size	²⁹ Depth Set	³⁰ Sacks Cement		
13 1/2"	10 3/4"	1209'	545 SXS CL C/CIRC		
9 7/8"	8 3/4"	11,339'	1475 SXS CL C&H/CIRC		
7 7/8"	6"	19,596'	1255 SXS CL H TOC 7176' CBL		

V. Well Test Data

³¹ Date New Oil	³² Gas Delivery Date	³³ Test Date	³⁴ Test Length	³⁵ Tbg. Pressure	³⁶ Csg. Pressure
09/07/2022	09/07/2022	09/15/2022	24 HRS		2340
³⁷ Choke Size	³⁸ Oil	³⁹ Water	⁴⁰ Gas	⁴¹ Test Method	
	2477	8728	4619		

⁴² I hereby certify that the rules of the Oil Conservation Division have been complied with and that the information given above is true and complete to the best of my knowledge and belief.

Signature: Kay Maddox
Printed name: Kay Maddox
Title: SENIOR REGULATORY SPECIALIST
E-mail Address: kay_maddox@eogresources.com
Date: 09/22/2022 Phone: 432-638-8475

OIL CONSERVATION DIVISION
Approved by:
Title:
Approval Date:

District I
1625 N. French Dr., Hobbs, NM 88240
Phone: (575) 393-6161 Fax: (575) 393-0720
District II
811 S. First St., Artesia, NM 88210
Phone: (575) 748-1283 Fax: (575) 748-9720
District III
1000 Rio Brazos Road, Aztec, NM 87410
Phone: (505) 334-6178 Fax: (505) 334-6170
District IV
1220 S. St. Francis Dr., Santa Fe, NM 87505
Phone: (505) 476-3460 Fax: (505) 476-3462

State of New Mexico
Energy, Minerals & Natural Resources
Department
OIL CONSERVATION DIVISION
1220 South St. Francis Dr.
Santa Fe, NM 87505

FORM C-102

Revised August 1, 2011

Submit one copy to appropriate
District Office

AMENDED REPORT

AS-DRILLED PLAT

¹ API Number 30-025-48852		² Pool Code 98270		³ Pool Name WC025 G08 S253216D; UPPER WOLFCAMP	
⁴ Property Code 330803		⁵ Property Name JEFE 29 FED COM			⁶ Well Number 710H
⁷ OGRID No. 7377		⁸ Operator Name EOG RESOURCES, INC.			⁹ Elevation 3360'

¹⁰Surface Location

UL or lot no.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County
L	29	25-S	32-E	-	2187'	SOUTH	754'	WEST	LEA

¹¹Bottom Hole Location If Different From Surface

UL or lot no.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County
M	32	25-S	32-E	-	110'	SOUTH	975'	WEST	LEA

¹² Dedicated Acres 480.00	¹³ Joint or Infill	¹⁴ Consolidation Code	¹⁵ Order No.
--	-------------------------------	----------------------------------	-------------------------

No allowable will be assigned to this completion until all interests have been consolidated or a non-standard unit has been approved by the division.

SURFACE HOLE LOCATION
NEW MEXICO EAST
NAD 1983
X=736389
Y=400721
LAT.: N 32.1000958
LONG.: W 103.7034307

KICK OFF POINT
NEW MEXICO EAST
NAD 1983
X=736559
Y=401140
LAT.: N 32.1012439
LONG.: W 103.7028731
MD = 11460'

FIRST TAKE POINT
NEW MEXICO EAST
NAD 1983
X=736609
Y=400944
LAT.: N 32.1007051
LONG.: W 103.7027173
MD = 12027'

LAST TAKE POINT
NEW MEXICO EAST
NAD 1983
X=736649
Y=393400
LAT.: N 32.0799660
LONG.: W 103.7027300
MD = 19587'

BOTTOM HOLE LOCATION
NEW MEXICO EAST
NAD 1983
X=736650
Y=393371
LAT.: N 32.0798885
LONG.: W 103.7027286
MD = 19618'

POINT	UTM ZONE 13 COORDINATES	
SHL	X=2041791.359	Y=11654393.661
KOP	X=2041958.627	Y=11654813.420
FTP	X=2042009.830	Y=11654617.765
LTP	X=2042096.457	Y=11647075.424
BHL	X=2042097.134	Y=11647046.869

17 OPERATOR CERTIFICATION
I hereby certify that the information contained herein is true and complete to the best of my knowledge and belief, and that this organization either owns a working interest or unleased mineral interest in the land including the proposed bottom hole location or has a right to drill this well at this location pursuant to a contract with an owner of such a mineral or working interest, or to a voluntary pooling agreement or a compulsory pooling order heretofore entered by the division.

Kay Maddox 09/21/2022
Signature Date

KAY MADDOX
Printed Name


KAY_MADDOX@EOGRESOURCES.COM
E-mail Address

18 SURVEYOR CERTIFICATION
I hereby certify that the well location shown on this plat was plotted from field notes of actual surveys made by me or under my supervision, and that the same is true to the best of my belief.

04/13/2022
Date of Survey

Ramon A. Dominguez
Signature and Seal of Professional Surveyor

24508
Certificate Number



SURFACE HOLE LOCATION
 NEW MEXICO EAST
 NAD 1983
 X=736389
 Y=400721
 LAT.: N 32.1000958
 LONG.: W 103.7034307

KICK OFF POINT
 NEW MEXICO EAST
 NAD 1983
 X=736559
 Y=401140
 LAT.: N 32.1012439
 LONG.: W 103.7028731
 MD = 11460'

FIRST TAKE POINT
 NEW MEXICO EAST
 NAD 1983
 X=736609
 Y=400944
 LAT.: N 32.1007051
 LONG.: W 103.7027173
 MD = 12027'

LAST TAKE POINT
 NEW MEXICO EAST
 NAD 1983
 X=736649
 Y=393400
 LAT.: N 32.0799660
 LONG.: W 103.7027300
 MD = 19587'

BOTTOM HOLE LOCATION
 NEW MEXICO EAST
 NAD 1983
 X=736650
 Y=393371
 LAT.: N 32.0798885
 LONG.: W 103.7027286
 MD = 19618'

POINT	UTM ZONE 13 COORDINATES	
SHL	X=2041791.359	Y=11654393.661
KOP	X=2041958.627	Y=11654813.420
FTP	X=2042009.830	Y=11654617.765
LTP	X=2042096.457	Y=11647075.424
BHL	X=2042097.134	Y=11647046.869

LEASE NAME & WELL NO.: JEFE 29 FED COM 710H
 SECTION 29 TWP 25-S RGE 32-E SURVEY N.M.P.M.
 COUNTY LEA STATE NM ELEVATION 3360'
 DESCRIPTION 2187' FSL & 754' FWL



TOPOGRAPHIC
 LOYALTY INNOVATION LEGACY
 1400 EVERMAN PARKWAY, Ste. 146 • FT. WORTH, TEXAS 76140
 TELEPHONE: (817) 744-7512 • FAX (817) 744-7554
 TEXAS FIRM REGISTRATION NO. 10042504
 WWW.TOPOGRAPHIC.COM

Ramon A. Dominguez, P.S. No. 24508
 August 25, 2022

JEFE 29 FED COM 710H AS-DRILLED	REVISION:	NOTES: 1. ORIGINAL DOCUMENT SIZE: 8.5" X 11" 2. ALL BEARINGS, DISTANCES, AND COORDINATE VALUES CONTAINED HEREIN ARE GRID BASED UPON THE NEW MEXICO COORDINATE SYSTEM OF 1983, EAST ZONE, U.S. SURVEY FEET. 3. THIS WELL LOCATION SHOWN HEREON HAS BEEN SURVEYED ON THE GROUND UNDER MY SUPERVISION AND PREPARED ACCORDING TO THE EVIDENCE FOUND AT THE TIME OF SURVEY, AND DATA PROVIDED BY EOG RESOURCES, INC. THIS CERTIFICATION IS MADE AND LIMITED TO THOSE PERSONS OR ENTITIES SHOWN ON THE FACE OF THIS PLAT AND IS NON-TRANSFERABLE. THIS SURVEY IS CERTIFIED FOR THIS TRANSACTION ONLY. 4. ADJOINER INFORMATION SHOWN FOR INFORMATIONAL PURPOSES ONLY.
	DATE: 08/25/22	
FILE:AD_JEFE_29_FED_COM_710H		
DRAWN BY: GJU		
SHEET: 2 OF 2		



Midland

Lea County, NM (NAD 83 NME)

Jefe 29 Fed Com

#710H

OH

Design: OH

Final PVA

09 July, 2022



Company:	Midland	Local Co-ordinate Reference:	Well #710H
Project:	Lea County, NM (NAD 83 NME)	TVD Reference:	KB = 26' @ 3386.0usft
Site:	Jefe 29 Fed Com	MD Reference:	KB = 26' @ 3386.0usft
Well:	#710H	North Reference:	Grid
Wellbore:	OH	Survey Calculation Method:	Minimum Curvature
Design:	OH	Database:	PEDM

Project	Lea County, NM (NAD 83 NME)		
Map System:	US State Plane 1983	System Datum:	Mean Sea Level
Geo Datum:	North American Datum 1983		
Map Zone:	New Mexico Eastern Zone		

Site	Jefe 29 Fed Com		
Site Position:		Northing:	400,660.00 usft
From:	Map	Easting:	736,197.00 usft
Position Uncertainty:	0.0 usft	Slot Radius:	13-3/16 "
		Latitude:	32° 5' 59.750 N
		Longitude:	103° 42' 14.588 W
		Grid Convergence:	0.33 °

Well	#710H					
Well Position	+N/-S	0.0 usft	Northing:	400,721.00 usft	Latitude:	32° 6' 0.342 N
	+E/-W	0.0 usft	Easting:	736,389.00 usft	Longitude:	103° 42' 12.352 W
Position Uncertainty		0.0 usft	Wellhead Elevation:	usft	Ground Level:	3,360.0 usft

Wellbore	OH					
Magnetics	Model Name	Sample Date	Declination (°)	Dip Angle (°)	Field Strength (nT)	
	IGRF2020	6/24/2022	6.48	59.73	47,300.98685056	

Design	OH				
Audit Notes:					
Version:	1.0	Phase:	ACTUAL	Tie On Depth:	0.0
Vertical Section:		Depth From (TVD) (usft)	+N/-S (usft)	+E/-W (usft)	Direction (°)
		0.0	0.0	0.0	177.86

Survey Program	Date	7/9/2022			
From (usft)	To (usft)	Survey (Wellbore)	Tool Name	Description	
176.0	19,618.0	Gordon MWD (OH)	EOG MWD+IFR1	MWD + IFR1	

Company:	Midland	Local Co-ordinate Reference:	Well #710H
Project:	Lea County, NM (NAD 83 NME)	TVD Reference:	KB = 26' @ 3386.0usft
Site:	Jefe 29 Fed Com	MD Reference:	KB = 26' @ 3386.0usft
Well:	#710H	North Reference:	Grid
Wellbore:	OH	Survey Calculation Method:	Minimum Curvature
Design:	OH	Database:	PEDM

Survey											
MD (usft)	Inc (°)	Azi (azimuth) (°)	TVD (usft)	N/S (usft)	E/W (usft)	DLeg (°/100usft)	Build (°/100usft)	Turn (°/100usft)	High to Plan (usft)	Right to Plan (usft)	
0.0	0.00	0.00	0.0	0.0	0.0	0.00	0.00	0.00	0.0	0.0	0.0
176.0	0.80	123.93	176.0	-0.7	1.0	0.45	0.45	0.00	-1.2	0.0	
290.0	0.81	137.10	290.0	-1.7	2.2	0.16	0.01	11.55	-2.8	0.5	
463.0	0.92	168.74	463.0	-4.0	3.3	0.28	0.06	18.29	-4.6	2.5	
647.0	1.25	228.64	646.9	-6.8	2.1	0.61	0.18	32.55	-2.9	6.5	
835.0	2.25	242.42	834.8	-9.8	-2.7	0.57	0.53	7.33	-6.9	7.5	
1,024.0	2.11	239.32	1,023.7	-13.3	-9.0	0.10	-0.07	-1.64	-14.5	6.9	
1,157.0	1.82	215.75	1,156.6	-16.3	-12.3	0.64	-0.22	-17.72	-20.4	-0.5	
1,336.0	1.15	208.92	1,335.6	-20.2	-14.8	0.39	-0.37	-3.82	-25.0	-3.2	
1,524.0	1.84	67.67	1,523.5	-20.7	-13.0	1.51	0.37	-75.13	26.3	-19.9	
1,713.0	4.51	60.29	1,712.2	-15.8	-3.7	1.43	1.41	-3.90	33.6	-27.3	
1,901.0	7.20	48.90	1,899.2	-4.4	11.6	1.55	1.43	-6.06	37.4	-29.4	
2,089.0	8.20	39.77	2,085.6	13.6	29.1	0.84	0.53	-4.86	35.5	-29.8	
2,277.0	8.91	24.63	2,271.5	37.2	43.7	1.25	0.38	-8.05	34.1	-22.7	
2,465.0	9.87	23.26	2,457.0	65.2	56.1	0.52	0.51	-0.73	23.5	-21.4	
2,654.0	10.35	23.17	2,643.0	95.7	69.2	0.25	0.25	-0.05	9.9	-20.6	
2,843.0	9.09	17.07	2,829.3	125.6	80.3	0.86	-0.67	-3.23	-0.3	-18.2	
3,032.0	8.63	16.27	3,016.1	153.5	88.6	0.25	-0.24	-0.42	-9.8	-15.2	
3,220.0	8.00	19.73	3,202.1	179.3	97.0	0.43	-0.34	1.84	-18.3	-11.8	
3,409.0	7.38	23.65	3,389.4	202.8	106.3	0.43	-0.33	2.07	-24.6	-8.9	
3,598.0	6.16	26.05	3,577.1	223.1	115.6	0.66	-0.65	1.27	-27.5	-7.5	
3,786.0	4.87	34.92	3,764.2	238.7	124.6	0.82	-0.69	4.72	-26.9	-4.8	
3,975.0	4.10	56.22	3,952.6	249.0	134.8	0.96	-0.41	11.27	-24.0	-1.9	
4,163.0	5.68	68.12	4,139.9	256.2	149.1	0.99	0.84	6.33	-25.2	-8.7	
4,353.0	6.72	69.71	4,328.8	263.6	168.2	0.55	0.55	0.84	-31.7	-21.6	
4,542.0	6.12	43.98	4,516.7	274.7	185.6	1.54	-0.32	-13.61	-20.5	-44.2	
4,731.0	7.20	28.39	4,704.4	292.3	198.2	1.11	0.57	-8.25	-9.8	-51.7	

Company:	Midland	Local Co-ordinate Reference:	Well #710H
Project:	Lea County, NM (NAD 83 NME)	TVD Reference:	KB = 26' @ 3386.0usft
Site:	Jefe 29 Fed Com	MD Reference:	KB = 26' @ 3386.0usft
Well:	#710H	North Reference:	Grid
Wellbore:	OH	Survey Calculation Method:	Minimum Curvature
Design:	OH	Database:	PEDM

Survey											
MD (usft)	Inc (°)	Azi (azimuth) (°)	TVD (usft)	N/S (usft)	E/W (usft)	DLeg (°/100usft)	Build (°/100usft)	Turn (°/100usft)	High to Plan (usft)	Right to Plan (usft)	
4,919.0	7.69	21.13	4,890.8	314.4	208.3	0.56	0.26	-3.86	-7.9	-52.5	
5,108.0	6.96	13.69	5,078.3	337.3	215.6	0.63	-0.39	-3.94	-5.8	-50.6	
5,297.0	7.66	8.93	5,265.8	360.9	220.3	0.49	0.37	-2.52	-6.7	-46.2	
5,485.0	6.40	8.55	5,452.3	383.7	223.8	0.67	-0.67	-0.20	-10.6	-40.5	
5,674.0	4.54	358.52	5,640.5	401.6	225.2	1.10	-0.98	-5.31	-4.6	-35.1	
5,863.0	3.53	353.50	5,829.0	414.8	224.3	0.57	-0.53	-2.66	-7.5	-31.5	
6,051.0	1.54	354.67	6,016.8	423.1	223.4	1.06	-1.06	0.62	-16.3	-31.1	
6,240.0	0.84	357.80	6,205.8	427.0	223.1	0.37	-0.37	1.66	-21.9	-30.0	
6,429.0	1.10	340.69	6,394.7	430.1	222.5	0.20	0.14	-9.05	-15.2	-35.5	
6,617.0	0.95	346.12	6,582.7	433.3	221.5	0.09	-0.08	2.89	-21.8	-33.7	
6,806.0	0.79	350.76	6,771.7	436.1	220.9	0.09	-0.08	2.46	-27.4	-31.7	
6,995.0	0.41	339.37	6,960.7	438.0	220.5	0.21	-0.20	-6.03	-22.5	-36.8	
7,183.0	0.70	307.61	7,148.7	439.4	219.3	0.22	0.15	-16.89	-1.5	-43.5	
7,372.0	0.98	278.26	7,337.7	440.3	216.8	0.27	0.15	-15.53	17.4	-39.2	
7,561.0	1.20	269.78	7,526.6	440.5	213.2	0.14	0.12	-4.49	19.4	-36.4	
7,749.0	1.09	260.66	7,714.6	440.2	209.5	0.11	-0.06	-4.85	21.2	-33.2	
7,938.0	1.02	236.66	7,903.6	439.0	206.3	0.23	-0.04	-12.70	29.5	-22.5	
8,126.0	1.05	237.77	8,091.5	437.2	203.5	0.02	0.02	0.59	25.7	-23.0	
8,315.0	1.40	232.46	8,280.5	434.8	200.2	0.19	0.19	-2.81	23.7	-20.7	
8,504.0	1.47	234.49	8,469.4	432.0	196.4	0.05	0.04	1.07	18.2	-21.4	
8,692.0	1.51	242.71	8,657.4	429.5	192.2	0.12	0.02	4.37	10.1	-23.5	
8,882.0	1.96	263.81	8,847.3	428.0	186.7	0.41	0.24	11.11	-4.6	-24.6	
9,070.0	3.13	295.04	9,035.1	429.8	178.9	0.94	0.62	16.61	-24.6	-17.0	
9,165.0	2.77	297.34	9,130.0	432.0	174.5	0.40	-0.38	2.42	-30.2	-15.9	
9,354.0	2.53	273.93	9,318.8	434.4	166.3	0.58	-0.13	-12.39	-29.7	-28.4	
9,448.0	1.24	112.76	9,412.7	434.1	165.2	3.96	-1.37	-171.46	38.2	16.6	
9,636.0	2.02	156.46	9,600.7	430.3	168.4	0.75	0.41	23.24	34.3	-13.0	

Company:	Midland	Local Co-ordinate Reference:	Well #710H
Project:	Lea County, NM (NAD 83 NME)	TVD Reference:	KB = 26' @ 3386.0usft
Site:	Jefe 29 Fed Com	MD Reference:	KB = 26' @ 3386.0usft
Well:	#710H	North Reference:	Grid
Wellbore:	OH	Survey Calculation Method:	Minimum Curvature
Design:	OH	Database:	PEDM

Survey												
MD (usft)	Inc (°)	Azi (azimuth) (°)	TVD (usft)	N/S (usft)	E/W (usft)	DLeg (°/100usft)	Build (°/100usft)	Turn (°/100usft)	High to Plan (usft)	Right to Plan (usft)		
9,825.0	1.86	166.98	9,789.6	424.2	170.4	0.21	-0.08	5.57	25.0	-18.5		
10,014.0	1.35	178.14	9,978.5	419.0	171.1	0.32	-0.27	5.90	15.7	-22.4		
10,202.0	1.07	135.14	10,166.5	415.6	172.4	0.49	-0.15	-22.87	23.4	-7.1		
10,391.0	0.11	62.11	10,355.4	414.4	173.9	0.55	-0.51	-38.64	12.9	18.6		
10,580.0	1.81	235.21	10,544.4	412.8	171.6	1.02	0.90	91.59	-13.4	-20.0		
10,768.0	2.50	255.78	10,732.3	410.1	165.1	0.55	0.37	10.94	-26.5	-13.0		
10,863.0	1.05	327.16	10,827.2	410.3	162.7	2.51	-1.53	75.14	-22.3	23.0		
11,051.0	1.78	37.74	11,015.2	414.1	163.5	0.93	0.39	37.54	14.2	34.8		
11,240.0	0.63	48.87	11,204.2	417.1	166.1	0.62	-0.61	5.89	21.7	36.3		
11,391.0	1.33	51.44	11,355.1	418.7	168.1	0.46	0.46	1.70	24.9	38.6		
11,460.0	2.63	108.35	11,424.1	418.7	170.2	3.20	1.89	82.48	46.2	0.2		
KOP, MD:11460.0', TVD:11424.1',N/S:418.7', E/W:170.2', INC:2.63												
11,486.0	3.38	115.49	11,450.1	418.2	171.5	3.20	2.87	27.47	45.3	-5.9		
11,580.0	6.35	163.14	11,543.7	412.0	175.5	5.08	3.16	50.69	28.6	-36.0		
11,675.0	10.92	181.20	11,637.7	398.0	176.8	5.54	4.81	19.01	27.5	-45.3		
11,768.0	23.09	169.35	11,726.4	371.1	180.0	13.54	13.09	-12.74	49.1	-36.8		
11,812.2	24.57	166.55	11,766.9	353.7	183.8	4.22	3.35	-6.34	56.5	-31.4		
FTP Crossing, MD:11812.2', TVD:11766.9',N/S:353.7', E/W:183.8', INC:24.57												
11,863.0	26.33	163.70	11,812.7	332.6	189.4	4.22	3.46	-5.61	66.8	-23.4		
11,956.0	45.40	163.19	11,887.8	280.6	204.9	20.51	20.51	-0.55	77.7	-9.1		
12,051.0	65.03	167.60	11,941.7	205.4	224.1	21.00	20.66	4.64	71.9	1.3		
12,145.0	80.39	171.00	11,969.6	117.5	240.6	16.70	16.34	3.62	53.4	11.2		
12,239.0	90.94	177.91	11,976.7	24.4	249.6	13.40	11.22	7.35	29.3	15.8		
12,333.0	91.44	178.84	11,974.7	-69.6	252.3	1.12	0.53	0.99	11.3	16.8		
12,427.0	89.48	176.81	11,974.0	-163.5	255.9	3.00	-2.09	-2.16	8.6	19.8		
12,522.0	91.11	176.83	11,973.5	-258.3	261.1	1.72	1.72	0.02	8.3	24.5		
12,616.0	93.49	181.06	11,969.7	-352.2	262.9	5.16	2.53	4.50	4.6	25.7		

Company:	Midland	Local Co-ordinate Reference:	Well #710H
Project:	Lea County, NM (NAD 83 NME)	TVD Reference:	KB = 26' @ 3386.0usft
Site:	Jefe 29 Fed Com	MD Reference:	KB = 26' @ 3386.0usft
Well:	#710H	North Reference:	Grid
Wellbore:	OH	Survey Calculation Method:	Minimum Curvature
Design:	OH	Database:	PEDM

Survey												
MD (usft)	Inc (°)	Azi (azimuth) (°)	TVD (usft)	N/S (usft)	E/W (usft)	DLeg (°/100usft)	Build (°/100usft)	Turn (°/100usft)	High to Plan (usft)	Right to Plan (usft)		
12,711.0	90.35	180.93	11,966.5	-447.1	261.2	3.31	-3.31	-0.14	1.6	23.6		
12,805.0	90.52	180.48	11,965.8	-541.1	260.1	0.51	0.18	-0.48	1.1	21.9		
12,899.0	88.92	179.90	11,966.3	-635.1	259.7	1.81	-1.70	-0.62	1.7	21.1		
12,994.0	88.58	179.66	11,968.3	-730.1	260.1	0.44	-0.36	-0.25	3.9	20.9		
13,088.0	88.11	178.88	11,971.1	-824.0	261.3	0.97	-0.50	-0.83	6.8	21.6		
13,182.0	89.82	179.41	11,972.8	-918.0	262.7	1.90	1.82	0.56	8.6	22.5		
13,277.0	89.71	179.08	11,973.1	-1,013.0	264.0	0.37	-0.12	-0.35	9.2	23.2		
13,371.0	90.57	180.24	11,972.9	-1,107.0	264.5	1.54	0.91	1.23	9.1	23.3		
13,466.0	90.29	179.89	11,972.2	-1,202.0	264.4	0.47	-0.29	-0.37	8.5	22.6		
13,560.0	89.37	179.39	11,972.5	-1,296.0	265.0	1.11	-0.98	-0.53	9.0	22.7		
13,655.0	88.92	179.26	11,973.9	-1,391.0	266.1	0.49	-0.47	-0.14	10.5	23.3		
13,749.0	87.41	177.76	11,976.9	-1,484.9	268.6	2.26	-1.61	-1.60	13.7	25.2		
13,843.0	91.56	181.48	11,977.8	-1,578.8	269.2	5.93	4.41	3.96	14.7	25.3		
13,937.0	89.20	182.59	11,977.1	-1,672.8	265.8	2.77	-2.51	1.18	14.3	21.5		
14,031.0	88.89	182.23	11,978.7	-1,766.7	261.9	0.51	-0.33	-0.38	16.0	17.0		
14,125.0	89.06	182.38	11,980.4	-1,860.6	258.1	0.24	0.18	0.16	17.8	12.7		
14,220.0	89.68	182.41	11,981.4	-1,955.5	254.1	0.65	0.65	0.03	19.0	8.2		
14,314.0	88.25	182.72	11,983.1	-2,049.4	249.9	1.56	-1.52	0.33	20.8	3.5		
14,408.0	87.07	181.76	11,987.0	-2,143.2	246.3	1.62	-1.26	-1.02	24.8	-0.7		
14,503.0	89.09	180.27	11,990.1	-2,238.2	244.6	2.64	2.13	-1.57	28.2	-2.9		
14,597.0	91.33	182.04	11,989.8	-2,332.1	242.7	3.04	2.38	1.88	28.0	-5.3		
14,692.0	90.32	181.39	11,988.4	-2,427.1	239.8	1.26	-1.06	-0.68	26.8	-8.6		
14,787.0	88.56	180.79	11,989.4	-2,522.0	238.0	1.96	-1.85	-0.63	27.9	-11.0		
14,881.0	90.74	181.37	11,989.9	-2,616.0	236.3	2.40	2.32	0.62	28.6	-13.3		
14,960.0	90.46	180.99	11,989.1	-2,695.0	234.6	0.60	-0.35	-0.48	27.9	-15.3		
15,070.0	88.44	179.83	11,990.2	-2,805.0	233.9	2.12	-1.84	-1.05	29.1	-16.7		
15,164.0	90.18	180.93	11,991.3	-2,899.0	233.2	2.19	1.85	1.17	30.4	-17.8		

Company:	Midland	Local Co-ordinate Reference:	Well #710H
Project:	Lea County, NM (NAD 83 NME)	TVD Reference:	KB = 26' @ 3386.0usft
Site:	Jefe 29 Fed Com	MD Reference:	KB = 26' @ 3386.0usft
Well:	#710H	North Reference:	Grid
Wellbore:	OH	Survey Calculation Method:	Minimum Curvature
Design:	OH	Database:	PEDM

Survey												
MD (usft)	Inc (°)	Azi (azimuth) (°)	TVD (usft)	N/S (usft)	E/W (usft)	DLeg (°/100usft)	Build (°/100usft)	Turn (°/100usft)	High to Plan (usft)	Right to Plan (usft)		
15,259.0	91.67	179.55	11,989.8	-2,994.0	232.8	2.14	1.57	-1.45	29.0	-18.8		
15,353.0	91.27	178.70	11,987.4	-3,087.9	234.3	1.00	-0.43	-0.90	26.8	-17.9		
15,447.0	89.71	176.95	11,986.5	-3,181.8	237.8	2.49	-1.66	-1.86	26.1	-14.8		
15,541.0	91.36	175.55	11,985.7	-3,275.6	244.0	2.30	1.76	-1.49	25.4	-9.2		
15,596.0	92.71	176.30	11,983.7	-3,330.4	247.9	2.81	2.45	1.36	23.5	-5.6		
15,635.0	91.72	175.77	11,982.2	-3,369.3	250.6	2.88	-2.54	-1.36	22.1	-3.1		
15,730.0	93.52	177.52	11,977.9	-3,464.1	256.1	2.64	1.89	1.84	17.9	2.0		
15,824.0	94.02	179.40	11,971.7	-3,557.8	258.7	2.07	0.53	2.00	11.9	4.0		
15,919.0	91.61	180.06	11,967.0	-3,652.7	259.1	2.63	-2.54	0.69	7.4	3.9		
16,014.0	91.08	179.55	11,964.8	-3,747.7	259.4	0.77	-0.56	-0.54	5.3	3.7		
16,108.0	89.29	180.51	11,964.5	-3,841.7	259.4	2.16	-1.90	1.02	5.1	3.1		
16,203.0	88.98	180.32	11,965.9	-3,936.6	258.7	0.38	-0.33	-0.20	6.7	1.9		
16,297.0	88.05	180.01	11,968.4	-4,030.6	258.4	1.04	-0.99	-0.33	9.3	1.1		
16,391.0	90.74	178.65	11,969.4	-4,124.6	259.5	3.21	2.86	-1.45	10.4	1.7		
16,485.0	90.71	178.59	11,968.2	-4,218.5	261.8	0.07	-0.03	-0.06	9.2	3.5		
16,579.0	92.20	178.91	11,965.8	-4,312.5	263.8	1.62	1.59	0.34	6.8	5.0		
16,674.0	87.66	177.16	11,965.9	-4,407.4	267.1	5.12	-4.78	-1.84	6.9	7.8		
16,768.0	87.63	176.75	11,969.8	-4,501.2	272.1	0.44	-0.03	-0.44	10.7	12.3		
16,862.0	86.59	179.10	11,974.5	-4,595.0	275.5	2.73	-1.11	2.50	15.5	15.2		
16,956.0	89.23	180.36	11,977.9	-4,688.9	275.9	3.11	2.81	1.34	18.9	15.1		
16,980.0	90.43	181.45	11,978.0	-4,712.9	275.5	6.75	5.00	4.54	19.0	14.6		
17,051.0	89.68	180.60	11,977.9	-4,783.9	274.3	1.60	-1.06	-1.20	18.9	13.0		
17,145.0	88.95	180.08	11,979.0	-4,877.9	273.7	0.95	-0.78	-0.55	20.0	11.9		
17,240.0	89.73	179.16	11,980.1	-4,972.9	274.3	1.27	0.82	-0.97	21.1	12.0		
17,334.0	91.16	178.92	11,979.4	-5,066.9	275.9	1.54	1.52	-0.26	20.4	13.1		
17,429.0	91.00	177.99	11,977.6	-5,161.8	278.5	0.99	-0.17	-0.98	18.6	15.2		
17,523.0	90.24	178.00	11,976.6	-5,255.8	281.8	0.81	-0.81	0.01	17.6	17.9		

Company: Midland
Project: Lea County, NM (NAD 83 NME)
Site: Jefe 29 Fed Com
Well: #710H
Wellbore: OH
Design: OH

Local Co-ordinate Reference: Well #710H
TVD Reference: KB = 26' @ 3386.0usft
MD Reference: KB = 26' @ 3386.0usft
North Reference: Grid
Survey Calculation Method: Minimum Curvature
Database: PEDM

Survey												
MD (usft)	Inc (°)	Azi (azimuth) (°)	TVD (usft)	N/S (usft)	E/W (usft)	DLeg (°/100usft)	Build (°/100usft)	Turn (°/100usft)	High to Plan (usft)	Right to Plan (usft)		
17,617.0	92.95	181.24	11,974.0	-5,349.7	282.4	4.49	2.88	3.45	15.0	18.1		
17,712.0	93.10	181.04	11,969.0	-5,444.6	280.5	0.26	0.16	-0.21	10.0	15.7		
17,806.0	90.41	180.30	11,966.1	-5,538.5	279.4	2.97	-2.86	-0.79	7.1	14.1		
17,900.0	89.90	179.91	11,965.8	-5,632.5	279.2	0.68	-0.54	-0.41	6.8	13.4		
17,994.0	90.18	180.70	11,965.8	-5,726.5	278.7	0.89	0.30	0.84	6.8	12.4		
18,089.0	88.72	180.76	11,966.7	-5,821.5	277.5	1.54	-1.54	0.06	7.7	10.7		
18,146.0	90.91	182.95	11,966.9	-5,878.4	275.7	5.43	3.84	3.84	7.9	8.5		
18,183.0	89.99	182.58	11,966.6	-5,915.4	273.9	2.68	-2.49	-1.00	7.6	6.5		
18,277.0	90.41	182.42	11,966.3	-6,009.3	269.8	0.48	0.45	-0.17	7.3	1.9		
18,372.0	91.86	182.19	11,964.4	-6,104.2	266.0	1.55	1.53	-0.24	5.4	-2.4		
18,467.0	91.53	181.97	11,961.6	-6,199.1	262.5	0.42	-0.35	-0.23	2.6	-6.3		
18,561.0	90.18	181.87	11,960.2	-6,293.0	259.4	1.44	-1.44	-0.11	1.2	-10.0		
18,655.0	89.85	182.05	11,960.1	-6,387.0	256.2	0.40	-0.35	0.19	1.1	-13.7		
18,749.0	91.14	181.06	11,959.3	-6,480.9	253.6	1.73	1.37	-1.05	0.3	-16.7		
18,844.0	90.69	180.69	11,957.8	-6,575.9	252.2	0.61	-0.47	-0.39	-1.2	-18.7		
18,880.0	91.58	179.92	11,957.1	-6,611.9	252.0	3.27	2.47	-2.14	-1.9	-19.1		
18,938.0	91.25	179.81	11,955.7	-6,669.9	252.1	0.60	-0.57	-0.19	-3.3	-19.3		
19,033.0	89.96	179.25	11,954.7	-6,764.9	252.9	1.48	-1.36	-0.59	-4.3	-19.0		
19,127.0	89.45	179.85	11,955.1	-6,858.9	253.6	0.84	-0.54	0.64	-3.9	-18.8		
19,221.0	91.72	179.86	11,954.2	-6,952.9	253.9	2.41	2.41	0.01	-4.8	-19.0		
19,316.0	90.32	179.40	11,952.5	-7,047.8	254.5	1.55	-1.47	-0.48	-6.5	-18.9		
19,410.0	89.85	178.77	11,952.3	-7,141.8	256.0	0.84	-0.50	-0.67	-6.7	-17.9		
19,430.0	89.90	178.78	11,952.4	-7,161.8	256.4	0.25	0.25	0.05	-6.6	-17.6		
Last MWD Survey (MD=19430.0')												
19,618.0	89.90	178.78	11,952.7	-7,349.8	260.4	0.00	0.00	0.00	-6.3	-14.6		
Projection to Bit (MD=19618.0')												

Company: Midland
Project: Lea County, NM (NAD 83 NME)
Site: Jefe 29 Fed Com
Well: #710H
Wellbore: OH
Design: OH

Local Co-ordinate Reference: Well #710H
TVD Reference: KB = 26' @ 3386.0usft
MD Reference: KB = 26' @ 3386.0usft
North Reference: Grid
Survey Calculation Method: Minimum Curvature
Database: PEDM

Design Annotations				
Measured Depth (usft)	Vertical Depth (usft)	Local Coordinates		Comment
		+N/-S (usft)	+E/-W (usft)	
11,460.0	11,424.1	418.7	170.2	KOP, MD:11460.0', TVD:11424.1',N/S:418.7', E/W:170.2', INC:2.63
11,812.2	11,766.9	353.7	183.8	FTP Crossing, MD:11812.2', TVD:11766.9',N/S:353.7', E/W:183.8', INC:24.57
19,430.0	11,952.4	-7,161.8	256.4	Last MWD Survey (MD=19430.0')
19,618.0	11,952.7	-7,349.8	260.4	Projection to Bit (MD=19618.0')

Checked By: _____ Approved By: _____ Date: _____

I CERTIFY THIS SURVEY TO BE TRUE AND CORRECT TO THE BEST OF MY BELIEF AND KNOWLEDGE
 KAY MADDOX 09/21/2022



Lea County, NM (NAD 83 NME)

Jefe 29 Fed Com #710H

Plan #1

PROJECT DETAILS: Lea County, NM (NAD 83 NME)

Geodetic System: US State Plane 1983
 Datum: North American Datum 1983
 Ellipsoid: GRS 1980
 Zone: New Mexico Eastern Zone
 System Datum: Mean Sea Level

WELL DETAILS: #710H

KB = 26' @ 3386.0usft
 Northing 400721.00 Easting 736389.00 Latitude 32° 6' 0.342 N Longitude 103° 42' 12.352 W



Azimuths to Grid North
 True North: -0.33°
 Magnetic North: 6.14°
 Magnetic Field
 Strength: 47301.0nT
 Dip Angle: 59.73°
 Date: 6/24/2022
 Model: IGRF2020








To convert a Magnetic Direction to a Grid Direction, Add 6.14°
 To convert a Magnetic Direction to a True Direction, Add 6.48° East
 To convert a True Direction to a Grid Direction, Subtract 0.33°

SECTION DETAILS

Sec	MD	Inc	Azi	TVD	+N-S	+E-W	Dleg	TFace	Vsect	Target
1	0.0	0.00	0.00	0.0	0.0	0.0	0.00	0.00	0.0	
2	1300.0	0.00	0.00	1300.0	0.0	0.0	0.00	0.00	0.0	
3	1599.9	6.00	25.65	1599.4	14.1	6.8	2.00	25.65	-13.9	
4	5588.0	6.00	25.65	5565.6	389.9	187.2	0.00	0.00	-382.6	
5	5887.9	0.00	0.00	5865.0	404.0	194.0	2.00	180.00	-396.5	
6	10822.9	0.00	0.00	10800.0	404.0	194.0	0.00	0.00	-396.5	
7	10922.9	2.00	90.00	10900.0	404.0	194.0	2.00	90.00	-396.4	
8	11468.3	2.00	90.00	11445.0	404.0	215.8	0.00	0.00	-395.7	
9	12287.2	90.09	179.69	11965.5	-117.6	235.8	11.00	89.68	126.4	
10	16222.4	90.09	179.69	11959.0	-4052.7	257.4	0.00	0.00	4059.5	TGT#1(JEFE 29 FED COM #710H)
11	16227.1	90.09	179.69	11959.0	-4057.4	257.4	2.00	175.00	4064.2	
12	19519.7	90.00	179.69	11959.0	-7350.0	275.0	0.00	0.00	7355.1	PBHL(Jefe 29 Fed Com #722H)

WELLBORE TARGET DETAILS (MAP CO-ORDINATES)

Name	TVD	+N-S	+E-W	Northing	Easting
Brushy Top(Jefe 29 Fed Com #722H)	6857.0	404.0	194.0	401125.00	736583.00
PBHL(Jefe 29 Fed Com #722H)	11959.0	-7350.0	275.0	393371.00	736664.00
TGT#1(JEFE 29 FED COM #710H)	11959.0	-4052.7	257.4	396668.30	736646.40
FTP(Jefe 29 Fed Com #722H)	11967.0	354.0	234.0	401075.00	736623.00



Intent As Drilled

API #									
Operator Name:					Property Name:				Well Number

Kick Off Point (KOP)

UL	Section	Township	Range	Lot	Feet	From N/S	Feet	From E/W	County
Latitude					Longitude				NAD

First Take Point (FTP)

UL	Section	Township	Range	Lot	Feet	From N/S	Feet	From E/W	County
Latitude					Longitude				NAD

Last Take Point (LTP)

UL	Section	Township	Range	Lot	Feet	From N/S	Feet	From E/W	County
Latitude					Longitude				NAD

Is this well the defining well for the Horizontal Spacing Unit?

Is this well an infill well?

If infill is yes please provide API if available, Operator Name and well number for Defining well for Horizontal Spacing Unit.

API #									
Operator Name:					Property Name:				Well Number

KZ 06/29/2018

Submit To Appropriate District Office Two Copies District I 1625 N. French Dr., Hobbs, NM 88240 District II 811 S. First St., Artesia, NM 88210 District III 1000 Rio Brazos Rd., Aztec, NM 87410 District IV 1220 S. St. Francis Dr., Santa Fe, NM 87505	State of New Mexico Energy, Minerals and Natural Resources Oil Conservation Division 1220 South St. Francis Dr. Santa Fe, NM 87505	Form C-105 Revised August 1, 2011 1. WELL API NO. <div style="text-align: right; font-size: 1.2em;">30-025-48852</div> 2. Type of Lease <input type="checkbox"/> STATE <input type="checkbox"/> FEE <input checked="" type="checkbox"/> FED/INDIAN 3. State Oil & Gas Lease No.
--	--	---

WELL COMPLETION OR RECOMPLETION REPORT AND LOG

4. Reason for filing: <input checked="" type="checkbox"/> COMPLETION REPORT (Fill in boxes #1 through #31 for State and Fee wells only) <input type="checkbox"/> C-144 CLOSURE ATTACHMENT (Fill in boxes #1 through #9, #15 Date Rig Released and #32 and/or #33; attach this and the plat to the C-144 closure report in accordance with 19.15.17.13.K NMAC)	5. Lease Name or Unit Agreement Name <div style="text-align: center; font-weight: bold;">JEFE 29 FEDERAL COM</div> 6. Well Number: <div style="text-align: center; font-size: 1.2em;">710H</div>
---	---

7. Type of Completion:
 NEW WELL WORKOVER DEEPENING PLUGBACK DIFFERENT RESERVOIR OTHER _____

8. Name of Operator <div style="text-align: center;">EOG RESOURCES INC</div>	9. OGRID <div style="text-align: center; font-size: 1.2em;">7377</div>
--	--

10. Address of Operator <div style="text-align: center;">PO BOX 2267 MIDLAND, TEXAS 79702</div>	11. Pool name or Wildcat WC025 G08 S253216D; UPPER WOLFCAMP
---	---

12. Location	Unit Ltr	Section	Township	Range	Lot	Feet from the	N/S Line	Feet from the	E/W Line	County
Surface:	L	29	25S	32E		2187	SOUTH	754	WEST	LEA
BH:	M	32	25S	32E		110	SOUTH	975	WEST	LEA

13. Date Spudded 04/18/2022	14. Date T.D. Reached 07/06/2022	15. Date Rig Released 07/08/2022	16. Date Completed (Ready to Produce) 09/07/2022	17. Elevations (DF and RKB, RT, GR, etc.) 3360' GL
18. Total Measured Depth of Well MD 19,618' TVD 11,952'		19. Plug Back Measured Depth MD 19,587' TVD 11,952'		20. Was Directional Survey Made? YES
22. Producing Interval(s), of this completion - Top, Bottom, Name WOLFCAMP 12,027 - 19,587'				21. Type Electric and Other Logs Run None

22. Producing Interval(s), of this completion - Top, Bottom, Name
WOLFCAMP 12,027 - 19,587'

23. CASING RECORD (Report all strings set in well)

CASING SIZE	WEIGHT LB./FT.	DEPTH SET	HOLE SIZE	CEMENTING RECORD	AMOUNT PULLED
10 3/4"	40.5# J-55	1,209'	13 1/2"	545 CL C/CIRC	
8 3/4"	38.5# HCL 80	11,339'	9 7/8"	1475 CL C & H/CIRC	
6"	24.5# ECP 110	19,596'	7 7/8"	1255 CL H TOC 7176' CB	

24. LINER RECORD				25. TUBING RECORD			
SIZE	TOP	BOTTOM	SACKS CEMENT	SCREEN	SIZE	DEPTH SET	PACKER SET

26. Perforation record (interval, size, and number) <div style="text-align: center; font-size: 1.2em;">12,027 - 19,587' 3 1/8", 1500 holes</div>	27. ACID, SHOT, FRACTURE, CEMENT, SQUEEZE, ETC. <table border="1" style="width:100%; border-collapse: collapse; text-align: center;"> <tr> <th>DEPTH INTERVAL</th> <th>AMOUNT AND KIND MATERIAL USED</th> </tr> <tr> <td>12,027 - 19,587'</td> <td>FRAC W/17,978,016 lbs proppant, 274,400 bbls load fld</td> </tr> </table>	DEPTH INTERVAL	AMOUNT AND KIND MATERIAL USED	12,027 - 19,587'	FRAC W/17,978,016 lbs proppant, 274,400 bbls load fld
DEPTH INTERVAL	AMOUNT AND KIND MATERIAL USED				
12,027 - 19,587'	FRAC W/17,978,016 lbs proppant, 274,400 bbls load fld				

28. PRODUCTION

Date First Production 09/07/2022	Production Method (<i>Flowing, gas lift, pumping - Size and type pump</i>) <div style="text-align: center;">Flowing</div>	Well Status (<i>Prod. or Shut-in</i>) <div style="text-align: center;">Producing</div>					
Date of Test 09/15/2022	Hours Tested 24	Choke Size	Prod'n For Test Period	Oil - Bbl 2477	Gas - MCF 4619	Water - Bbl. 8728	Gas - Oil Ratio 1865
Flow Tubing Press.	Casing Pressure 2340	Calculated 24-Hour Rate	Oil - Bbl.	Gas - MCF	Water - Bbl.	Oil Gravity - API - (<i>Corr.</i>) <div style="text-align: center;">47</div>	

29. Disposition of Gas (<i>Sold, used for fuel, vented, etc.</i>) <div style="text-align: center; font-size: 1.2em;">SOLD</div>	30. Test Witnessed By
---	-----------------------

31. List Attachments

C-102, C-104, Directional Survey, H spacing

32. If a temporary pit was used at the well, attach a plat with the location of the temporary pit.

33. If an on-site burial was used at the well, report the exact location of the on-site burial:

Latitude _____ Longitude _____ NAD 1927 1983

I hereby certify that the information shown on both sides of this form is true and complete to the best of my knowledge and belief

Printed

Signature Kay Maddox	Name Kay Maddox	Title Senior Regulatory Specialist	Date 09/22/2022
-----------------------------	------------------------	---	------------------------

E-mail Address **kay_maddox@eogresources.com**

INSTRUCTIONS

This form is to be filed with the appropriate District Office of the Division not later than 20 days after the completion of any newly-drilled or deepened well and not later than 60 days after completion of closure. When submitted as a completion report, this shall be accompanied by one copy of all electrical and radio-activity logs run on the well and a summary of all special tests conducted, including drill stem tests. All depths reported shall be measured depths. In the case of directionally drilled wells, true vertical depths shall also be reported. For multiple completions, items 11, 12 and 26-31 shall be reported for each zone.

INDICATE FORMATION TOPS IN CONFORMANCE WITH GEOGRAPHICAL SECTION OF STATE

Southeastern New Mexico		Northwestern New Mexico	
T. Anhy <u>Rustler 1040'</u>	T. Canyon <u>Brushy 6895'</u>	T. Ojo Alamo _____	T. Penn A" _____
T. Salt <u>1385'</u>	T. Strawn _____	T. Kirtland _____	T. Penn. "B" _____
B. Salt <u>4270'</u>	T. Atoka _____	T. Fruitland _____	T. Penn. "C" _____
T. Yates _____	T. Miss _____	T. Pictured Cliffs _____	T. Penn. "D" _____
T. 7 Rivers _____	T. Devonian _____	T. Cliff House _____	T. Leadville _____
T. Queen _____	T. Silurian _____	T. Menefee _____	T. Madison _____
T. Grayburg _____	T. Montoya _____	T. Point Lookout _____	T. Elbert _____
T. San Andres _____	T. Simpson _____	T. Mancos _____	T. McCracken _____
T. Glorieta _____	T. McKee _____	T. Gallup _____	T. Ignacio Otzte _____
T. Paddock _____	T. Ellenburger _____	Base Greenhorn _____	T. Granite _____
T. Blinebry _____	T. Gr. Wash _____	T. Dakota _____	
T. Tubb _____	T. Delaware Sand _____	T. Morrison _____	
T. Drinkard _____	T. Bone Springs _____	T. Todilto _____	
T. Abo _____	T. <u>1st BS Sand 9554'</u>	T. Entrada _____	
T. Wolfcamp <u>11,823'</u>	T. <u>2nd BS Sand 10,117'</u>	T. Wingate _____	
T. Penn _____	T. <u>3rd BS Sand 11,408'</u>	T. Chinle _____	
T. Cisco (Bough C) _____	T. _____	T. Permian _____	

OIL OR GAS SANDS OR ZONES

No. 1, from.....to.....
 No. 2, from.....to.....
 No. 3, from.....to.....
 No. 4, from.....to.....

IMPORTANT WATER SANDS

Include data on rate of water inflow and elevation to which water rose in hole.

No. 1, from.....to.....feet.....
 No. 2, from.....to.....feet.....
 No. 3, from.....to.....feet.....

LITHOLOGY RECORD (Attach additional sheet if necessary)

From	To	Thickness In Feet	Lithology	From	To	Thickness In Feet	Lithology

Sante Fe Main Office
Phone: (505) 476-3441

General Information
Phone: (505) 629-6116

Online Phone Directory
<https://www.emnrd.nm.gov/ocd/contact-us>

State of New Mexico
Energy, Minerals and Natural Resources
Oil Conservation Division
1220 S. St Francis Dr.
Santa Fe, NM 87505

ACKNOWLEDGMENTS

Action 145642

ACKNOWLEDGMENTS

Operator: EOG RESOURCES INC 5509 Champions Drive Midland, TX 79706	OGRID: 7377
	Action Number: 145642
	Action Type: [C-104] Completion Packet (C-104C)

ACKNOWLEDGMENTS

<input checked="" type="checkbox"/>	I hereby certify that the required Water Use Report has been, or will be, submitted for this wells completion.
<input checked="" type="checkbox"/>	I hereby certify that the required FracFocus disclosure has been, or will be, submitted for this wells completion.

Sante Fe Main Office
Phone: (505) 476-3441

General Information
Phone: (505) 629-6116

Online Phone Directory
<https://www.emnrd.nm.gov/oecd/contact-us>

State of New Mexico
Energy, Minerals and Natural Resources
Oil Conservation Division
1220 S. St Francis Dr.
Santa Fe, NM 87505

CONDITIONS

Action 145642

CONDITIONS

Operator: EOG RESOURCES INC 5509 Champions Drive Midland, TX 79706	OGRID: 7377
	Action Number: 145642
	Action Type: [C-104] Completion Packet (C-104C)

CONDITIONS

Created By	Condition	Condition Date
plmartinez	File 3160-4 Completion Report within 10 days of BLM approval.	1/20/2026