

Form 3160-3
(October 2024)

FORM APPROVED
OMB No. 1004-0137
Expires: October 31, 2027

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT
APPLICATION FOR PERMIT TO DRILL OR REENTER

1a. Type of work: <input checked="" type="checkbox"/> DRILL <input type="checkbox"/> REENTER		5. Lease Serial No. NMLC063993
1b. Type of Well: <input checked="" type="checkbox"/> Oil Well <input type="checkbox"/> Gas Well <input type="checkbox"/> Other		6. If Indian, Allottee or Tribe Name
1c. Type of Completion: <input type="checkbox"/> Hydraulic Fracturing <input type="checkbox"/> Single Zone <input checked="" type="checkbox"/> Multiple Zone		7. If Unit or CA Agreement, Name and No. NMMN068292H/BELL LAKE-INT. BONE :
2. Name of Operator KAISER FRANCIS OIL COMPANY		8. Lease Name and Well No. BELL LAKE UNIT SOUTH BELL LAKE SOUTH UNIT 702H
3a. Address 6733 S. Yale Ave., Tulsa, OK 74121	3b. Phone No. (include area code) (918) 491-0000	9. API Well No. 30-025-56005
4. Location of Well (Report location clearly and in accordance with any State requirements. *) At surface SENW / 2508 FNL / 2137 FWL / LAT 32.2469597 / LONG -103.5277029 At proposed prod. zone SESW / 25 FSL / 1486 FWL / LAT 32.2249138 / LONG -103.5297976		10. Field and Pool, or Exploratory BELL LAKE/BONE SPRING, SOUTH
11. Sec., T. R. M. or Blk. and Survey or Area SEC 1/T24S/R33E/NMP		
14. Distance in miles and direction from nearest town or post office* 19 miles	12. County or Parish LEA	13. State NM
15. Distance from proposed* location to nearest property or lease line, ft. (Also to nearest drig. unit line, if any) 2137 feet	16. No of acres in lease 480.0	17. Spacing Unit dedicated to this well 480.0
18. Distance from proposed location* to nearest well, drilling, completed, applied for, on this lease, ft. 30 feet	19. Proposed Depth 9825 feet / 18514 feet	20. BLM/BIA Bond No. in file FED: NMB105674934
21. Elevations (Show whether DF, KDB, RT, GL, etc.) 3628 feet	22. Approximate date work will start* 01/04/2027	23. Estimated duration 15 days
24. Attachments		

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No. 1, and the Hydraulic Fracturing rule per 43 CFR 3162.3-3 (as applicable)

- | | |
|--|---|
| 1. Well plat certified by a registered surveyor. | 4. Bond to cover the operations unless covered by an existing bond on file (see Item 20 above). |
| 2. A Drilling Plan. | 5. Operator certification. |
| 3. A Surface Use Plan (if the location is on National Forest System Lands, the SUPO must be filed with the appropriate Forest Service Office). | 6. Such other site specific information and/or plans as may be requested by the BLM. |

25. Signature (Electronic Submission)	Name (Printed/Typed) CHRISTINA OPFER / Ph: (918) 491-0000	Date 08/13/2025
Title Regulatory Manager		
Approved by (Signature) (Electronic Submission)	Name (Printed/Typed) CODY LAYTON / Ph: (575) 234-5959	Date 10/07/2025
Title Assistant Field Manager Lands & Minerals Carlsbad Field Office		

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.
Conditions of approval, if any, are attached.

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.



(Continued on page 2)

*(Instructions on page 2)

INSTRUCTIONS

GENERAL: This form is designed for submitting proposals to perform certain well operations, as indicated on Federal and Indian lands and leases for action by appropriate Federal agencies, pursuant to applicable Federal laws and regulations. Any necessary special instructions concerning the use of this form and the number of copies to be submitted, particularly with regard to local, area, or regional procedures and practices, either are shown below or will be issued by, or may be obtained from local Federal offices.

ITEM I: If the proposal is to redrill to the same reservoir at a different subsurface location or to a new reservoir, use this form with appropriate notations. Consult applicable Federal regulations concerning subsequent work proposals or reports on the well.

ITEM 4: Locations on Federal or Indian land should be described in accordance with Federal requirements. Consult local Federal offices for specific instructions.

ITEM 14: Needed only when location of well cannot readily be found by road from the land or lease description. A plat, or plats, separate or on the reverse side, showing the roads to, and the surveyed location of, the well, and any other required information, should be furnished when required by Federal agency offices.

ITEMS 15 AND 18: If well is to be, or has been directionally drilled, give distances for subsurface location of hole in any present or objective productive zone.

ITEM 22: Consult applicable Federal regulations, or appropriate officials, concerning approval of the proposal before operations are started.

ITEM 24: If the proposal will involve hydraulic fracturing operations, you must comply with 43 CFR 3162.3-3, including providing information about the protection of usable water. Operators should provide the best available information about all formations containing water and their depths. This information could include data and interpretation of resistivity logs run on nearby wells. Information may also be obtained from state or tribal regulatory agencies and from local BLM offices.

NOTICES

The Privacy Act of 1974 and regulation in 43 CFR 2.48(d) provide that you be furnished the following information in connection with information required by this application.

AUTHORITY: 30 U.S.C. 181 et seq., 25 U.S.C. 396; 43 CFR 3160

PRINCIPAL PURPOSES: The information will be used to: (1) process and evaluate your application for a permit to drill a new oil, gas, or service well or to reenter a plugged and abandoned well; and (2) document, for administrative use, information for the management, disposal and use of National Resource Lands and resources including (a) analyzing your proposal to discover and extract the Federal or Indian resources encountered; (b) reviewing procedures and equipment and the projected impact on the land involved; and (c) evaluating the effects of the proposed operation on the surface and subsurface water and other environmental impacts.

ROUTINE USE: Information from the record and/or the record will be transferred to appropriate Federal, State, and local or foreign agencies, when relevant to civil, criminal or regulatory investigations or prosecution, in connection with congressional inquiries and for regulatory responsibilities.

EFFECT OF NOT PROVIDING INFORMATION: Filing of this application and disclosure of the information is mandatory only if you elect to initiate a drilling or reentry operation on an oil and gas lease.

The Paperwork Reduction Act of 1995 requires us to inform you that:

The BLM connects this information to a new evaluation of the technical, safety, and environmental factors involved with drilling for oil and/or gas on Federal and Indian oil and gas leases. This information will be used to analyze and approve applications. Response to this request is mandatory only if the operator elects to initiate drilling or reentry operations on an oil and gas lease. The BLM would like you to know that you do not have to respond to this or any other Federal agency-sponsored information collection unless it displays a currently valid OMB control number.

BURDEN HOURS STATEMENT: Public reporting burden for this form is estimated to average 8 hours per response, including the time for reviewing instructions, gathering and maintaining data, and completing and reviewing the form. Direct comments regarding the burden estimate or any other aspect of this form to U.S. Department of the Interior, Bureau of Land Management (1004-0137), Bureau Information Connection Clearance Officer (WO-630), 1849 C Street, N.W., Mail Stop 401 LS, Washington, D.C. 20240.

Additional Operator Remarks

Location of Well

0. SHL: SENW / 2508 FNL / 2137 FWL / TWSP: 24S / RANGE: 33E / SECTION: 1 / LAT: 32.2469597 / LONG: -103.5277029 (TVD: 0 feet, MD: 0 feet)
PPP: NESW / 2450 FSL / 1486 FWL / TWSP: 24S / RANGE: 33E / SECTION: 1 / LAT: 32.2461109 / LONG: -103.5298097 (TVD: 9820 feet, MD: 10181 feet)
PPP: NESW / 2640 FNL / 1488 FWL / TWSP: 24S / RANGE: 33E / SECTION: 12 / LAT: 32.2321185 / LONG: -103.5298019 (TVD: 9825 feet, MD: 15608 feet)
PPP: NENW / 0 FNL / 1492 FWL / TWSP: 24S / RANGE: 33E / SECTION: 12 / LAT: 32.2393765 / LONG: -103.5298059 (TVD: 9825 feet, MD: 12968 feet)
BHL: SESW / 25 FSL / 1486 FWL / TWSP: 24S / RANGE: 33E / SECTION: 12 / LAT: 32.2249138 / LONG: -103.5297976 (TVD: 9825 feet, MD: 18514 feet)

BLM Point of Contact

Name: TENILLE C MOLINA
Title: Land Law Examiner
Phone: (575) 234-2224
Email: TCMOLINA@BLM.GOV

CONFIDENTIAL

PECOS DISTRICT DRILLING CONDITIONS OF APPROVAL

OPERATOR'S NAME: Kaiser Francis
WELL NAME & NO.: Bell Lake Unit South 702H
LOCATION: 1-24S-33E-NMP
COUNTY: Lea County, New Mexico

Create COAs

<p style="text-align: center;">H₂S</p> <div style="border: 1px solid black; padding: 2px; text-align: center;">Not Reported</div>	<p style="text-align: center;">Cave / Karst</p> <div style="border: 1px solid black; padding: 2px; text-align: center;">Low</div>	<p style="text-align: center;">Waste Prevention Rule</p> <div style="border: 1px solid black; padding: 2px; text-align: center;">Waste Minimization Plan</div>
<p style="text-align: center;">Potash</p> <div style="border: 1px solid black; padding: 2px; text-align: center;">None</div>	<p style="text-align: center;">R-111-Q Design</p> <div style="border: 1px solid black; height: 20px; width: 100%;"></div>	
<p style="text-align: center;">Wellhead</p> <div style="border: 1px solid black; padding: 2px; text-align: center;">Multibowl</div> <p><input checked="" type="checkbox"/> Flex Hose</p> <p><input type="checkbox"/> Break Testing</p>	<p style="text-align: center;">Casing</p> <div style="border: 1px solid black; padding: 2px; text-align: center; margin-bottom: 5px;">3-String Well</div> <p> <input type="checkbox"/> Liner <input type="checkbox"/> Fluid Filled <input type="checkbox"/> Casing Clearance </p>	
	<p style="text-align: center;">Cementing</p> <p> <input type="checkbox"/> DV Tool <input type="checkbox"/> Bradenhead <input type="checkbox"/> Echometer </p> <p> <input type="checkbox"/> Offline Cement <input type="checkbox"/> Open Annulus <input type="checkbox"/> Pilot Hole </p>	
<p style="text-align: center;">Special Requirements</p> <p> <input type="checkbox"/> Capitan Reef <input type="checkbox"/> Water Disposal <input type="checkbox"/> COM <input checked="" type="checkbox"/> Unit </p>		

A. HYDROGEN SULFIDE

Hydrogen Sulfide (H₂S) monitors shall be installed prior to drilling out the surface shoe. If H₂S is detected in concentrations greater than 100 ppm, the Hydrogen Sulfide area shall meet 43 CFR 3176 requirements, which includes equipment and personnel/public protection items. If Hydrogen Sulfide is encountered, provide measured values and formations to the BLM.

B. CASING

1. The 13-3/8 inch surface casing shall be set at approximately **1900** feet (a minimum of **25 feet (Lea County)** into the Rustler Anhydrite, above the salt, and below usable fresh water) and cemented to the surface. **Express calculates to 15%. Additional cement maybe required.**
 - a. If cement does not circulate to the surface, the appropriate BLM office shall be notified and a temperature survey utilizing an electronic-type temperature survey with surface log readout will be used or a cement bond log shall be run to verify the top of the

- cement. Temperature survey will be run a minimum of six hours after pumping cement and ideally between 8-10 hours after completing the cement job.
- b. Wait on cement (WOC) time for a primary cement job will be a minimum of **8 hours** or **500 pounds compressive strength**, whichever is greater (including lead cement.)
 - c. Wait on cement (WOC) time for a remedial job will be a minimum of 4 hours after bringing cement to surface or 500 pounds compressive strength, whichever is greater.
 - d. If cement falls back, remedial cementing will be done prior to drilling out that string.
2. The minimum required fill of cement behind the **9-5/8** inch Intermediate casing is **cement to surface**. If cement does not circulate, see B.1.a, c-d above.
 3. The minimum required fill of cement behind the **5-1/2** inch production casing is at least **200 feet** into previous casing string. Operator shall provide method of verification. **Express calculates to 15%. Additional cement maybe required.**

C. PRESSURE CONTROL

1. Operator has proposed a multi-bowl wellhead assembly. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the surface casing shoe shall be **5000 (5M) psi**.
 - a. Wellhead shall be installed by manufacturer's representatives, submit documentation with subsequent sundry.
 - b. If the welding is performed by a third party, the manufacturer's representative shall monitor the temperature to verify that it does not exceed the maximum temperature of the seal.
 - c. Manufacturer representative shall install the test plug for the initial BOP test.
 - d. If the cement does not circulate and one-inch operations would have been possible with a standard wellhead, the well head shall be cut off, cementing operations performed and another wellhead installed.
 - e. Whenever any seal subject to test pressure is broken, all the tests in 43 CFR 3172 must be followed.
2. Variance approved to use flex line from BOP to choke manifold. Manufacturer's specification to be readily available. No external damage to flex line. Flex line to be installed as straight as possible (no hard bends).

D. SPECIAL REQUIREMENT(S)

Unit Wells:

The well sign for a unit well shall include the unit number in addition to the surface and bottom hole lease numbers. This also applies to participating area numbers. If a participating area has not been established, the operator can use the general unit designation but will replace the unit number with the participating area number when the sign is replaced.

Commercial Well Determination:

A commercial well determination shall be submitted after production has been established for at least six months. **(This is not necessary for secondary recovery unit wells)**

GENERAL REQUIREMENTS

The BLM is to be notified in advance for a representative to witness:

- a. Spudding well (minimum of 24 hours)
- b. Setting and/or Cementing of all casing strings (minimum of 4 hours)
- c. BOPE tests (minimum of 4 hours)

Contact Lea County Petroleum Engineering Inspection Staff:

Call the Hobbs Field Station, 414 West Taylor, Hobbs NM 88240, (575) 689-5981

1. Unless the production casing has been run and cemented or the well has been properly plugged, the drilling rig shall not be removed from over the hole without prior approval.
 - a. In the event the operator has proposed to drill multiple wells utilizing a skid/walking rig. Operator shall secure the wellbore on the current well, after installing and testing the wellhead, by installing a blind flange of like pressure rating to the wellhead and a pressure gauge that can be monitored while drilling is performed on the other well(s).
 - b. When the operator proposes to set surface casing with Spudder Rig
 - i. Notify the BLM when moving in and removing the Spudder Rig.
 - ii. Notify the BLM when moving in the 2nd Rig. Rig to be moved in within 90 days of notification that Spudder Rig has left the location.
 - iii. BOP/BOPE test to be conducted per **43 CFR 3172** as soon as 2nd Rig is rigged up on well.
2. Floor controls are required for 3M or Greater systems. These controls will be on the rig floor, unobstructed, readily accessible to the driller and will be operational at all times during drilling and/or completion activities. Rig floor is defined as the area immediately around the rotary table; the area immediately above the substructure on which the draw works are located, this does not include the dog house or stairway area.
3. For intervals in which cement to surface is required, cement to surface should be verified with a visual check and density or pH check to differentiate cement from spacer and drilling mud. The results should be documented in the driller's log and daily reports.

A. CASING

1. Changes to the approved APD casing program need prior approval if the items substituted are of lesser grade or different casing size or are Non-API. The Operator can exchange the components of the proposal with that of superior strength (i.e. changing from J-55 to N-80, or from 36# to 40#). Changes to the approved cement program need prior approval if the altered cement plan has less volume or strength or if the changes are substantial (i.e. Multistage tool, ECP, etc.). The initial wellhead installed on the well will remain on the well with spools used as needed.

2. Wait on cement (WOC) for Potash Areas: After cementing but before commencing any tests, the casing string shall stand cemented under pressure until both of the following conditions have been met: 1) cement reaches a minimum compressive strength of 500 psi for all cement blends of both lead and tail cement, 2) until cement has been in place at least 8 hours. WOC time will be recorded in the driller's log. The casing integrity test can be done (prior to the cement setting up) immediately after bumping the plug.
3. Wait on cement (WOC) for Water Basin: After cementing but before commencing any tests, the casing string shall stand cemented under pressure until both of the following conditions have been met: 1) cement reaches a minimum compressive strength of 500 psi at the shoe, 2) until cement has been in place at least 8 hours. WOC time will be recorded in the driller's log. See individual casing strings for details regarding lead cement slurry requirements. The casing integrity test can be done (prior to the cement setting up) immediately after bumping the plug.
4. Provide compressive strengths including hours to reach required 500 pounds compressive strength prior to cementing each casing string. Have well specific cement details onsite prior to pumping the cement for each casing string.
5. No pea gravel permitted for remedial or fall back remedial without prior authorization from the BLM engineer.
6. On that portion of any well approved for a 5M BOPE system or greater, a pressure integrity test of each casing shoe shall be performed. Formation at the shoe shall be tested to a minimum of the mud weight equivalent anticipated to control the formation pressure to the next casing depth or at total depth of the well. This test shall be performed before drilling more than 20 feet of new hole.
7. If hardband drill pipe is rotated inside casing, returns will be monitored for metal. If metal is found in samples, drill pipe will be pulled and rubber protectors which have a larger diameter than the tool joints of the drill pipe will be installed prior to continuing drilling operations.
8. Whenever a casing string is cemented in the R-111-Q potash area, the NMOCD requirements shall be followed.

B. PRESSURE CONTROL

1. All blowout preventer (BOP) and related equipment (BOPE) shall comply with well control requirements as described in **43 CFR 3172**.
2. If a variance is approved for a flexible hose to be installed from the BOP to the choke manifold, the following requirements apply: The flex line must meet the requirements of API 16C. Check condition of flexible line from BOP to choke manifold, replace if exterior is damaged or if line fails test. Line to be as straight as possible with no hard bends and is to be anchored according to Manufacturer's requirements. The flexible hose can be exchanged with a hose of equal size and equal or greater pressure rating. Anchor requirements, specification sheet and hydrostatic pressure test certification

- matching the hose in service, to be onsite for review. These documents shall be posted in the company man's trailer and on the rig floor.
3. 5M or higher system requires an HCR valve, remote kill line and annular to match. The remote kill line is to be installed prior to testing the system and tested to stack pressure.
 4. If the operator has proposed a multi-bowl wellhead assembly in the APD. The following requirements must be met:
 - i. Wellhead shall be installed by manufacturer's representatives, submit documentation with subsequent sundry.
 - ii. If the welding is performed by a third party, the manufacturer's representative shall monitor the temperature to verify that it does not exceed the maximum temperature of the seal.
 - iii. Manufacturer representative shall install the test plug for the initial BOP test.
 - iv. Whenever any seal subject to test pressure is broken, all the tests in 43 CFR 3172.6(b)(9) must be followed.
 - v. If the cement does not circulate and one inch operations would have been possible with a standard wellhead, the well head shall be cut off, cementing operations performed and another wellhead installed.
 5. The appropriate BLM office shall be notified a minimum of 4 hours in advance for a representative to witness the tests.
 - i. In a water basin, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. The casing cut-off and BOP installation can be initiated four hours after installing the slips, which will be approximately six hours after bumping the plug. For those casing strings not using slips, the minimum wait time before cut-off is eight hours after bumping the plug. BOP/BOPE testing can begin after cut-off or once cement reaches 500 psi compressive strength (including lead cement), whichever is greater. However, if the float does not hold, cut-off cannot be initiated until cement reaches 500 psi compressive strength (including lead when specified).
 - ii. In potash areas, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. For all casing strings, casing cut-off and BOP installation can be initiated at twelve hours after bumping the cement plug. The BOPE test can be initiated after bumping the cement plug with the casing valve open. (only applies to single stage cement jobs, prior to the cement setting up.)
 - iii. The tests shall be done by an independent service company utilizing a test plug not a cup or J-packer and can be initiated immediately with the casing valve open. The operator also has the option of utilizing an independent tester to test without a plug (i.e. against the casing) pursuant to **43 CFR 3172** with the

pressure not to exceed 70% of the burst rating for the casing. Any test against the casing must meet the WOC time for 8 hours or 500 pounds compressive strength, whichever is greater, prior to initiating the test (see casing segment as lead cement may be critical item).

- iv. The test shall be run on a 5000 psi chart for a 2-3M BOP/BOP, on a 10000 psi chart for a 5M BOP/BOPE and on a 15000 psi chart for a 10M BOP/BOPE. If a linear chart is used, it shall be a one hour chart. A circular chart shall have a maximum 2 hour clock. If a twelve hour or twenty-four hour chart is used, tester shall make a notation that it is run with a two hour clock.
- v. The results of the test shall be reported to the appropriate BLM office.
- vi. All tests are required to be recorded on a calibrated test chart. A copy of the BOP/BOPE test chart and a copy of independent service company test will be submitted to the appropriate BLM office.
- vii. The BOP/BOPE test shall include a low pressure test from 250 to 300 psi. The test will be held for a minimum of 10 minutes if test is done with a test plug and 30 minutes without a test plug. This test shall be performed prior to the test at full stack pressure.
- viii. BOP/BOPE must be tested by an independent service company within 500 feet of the top of the Wolfcamp formation if the time between the setting of the intermediate casing and reaching this depth exceeds 20 days. This test does not exclude the test prior to drilling out the casing shoe as per **43 CFR 3172**.

C. DRILLING MUD


Mud system monitoring equipment, with derrick floor indicators and visual and audio alarms, shall be operating before drilling into the Wolfcamp formation, and shall be used until production casing is run and cemented.

D. WASTE MATERIAL AND FLUIDS

All waste (i.e. drilling fluids, trash, salts, chemicals, sewage, gray water, etc.) created as a result of drilling operations and completion operations shall be safely contained and disposed of properly at a waste disposal facility. No waste material or fluid shall be disposed of on the well location or surrounding area. Porto-johns and trash containers will be on-location during fracturing operations or any other crew-intensive operations.

Approved by Zota Stevens on 10/6/2025
575-234-5998 / zstevens@blm.gov

C-102 Submit Electronically Via OCD Permitting	State of New Mexico Energy, Minerals & Natural Resources Department OIL CONSERVATION DIVISION	Revised July 9, 2024
		Submittal Type: <input checked="" type="checkbox"/> Initial Submittal <input type="checkbox"/> Amended Report <input type="checkbox"/> As Drilled
Property Name and Well Number BELL LAKE UNIT SOUTH #702H		



T-24-S, R-33-E
 SECTION 5
 LOT 1 - 39.94 ACRES
 LOT 2 - 39.83 ACRES
 LOT 3 - 39.71 ACRES
 LOT 4 - 39.60 ACRES


SURVEYORS CERTIFICATION
 I hereby certify that the well location shown on this plat was plotted from field notes of actual surveys made by me or under my supervision, and that the same is true and correct to the best of my belief.
 07/22/2025

Date of Survey
 Signature and Seal of Professional Surveyor:



C:\SURVEY\KANSAS_FRANCIS\BELL_LAKE_UNIT_SOUTH_PRODUCES\OIL_CONSERVATION\NATURAL_RESOURCE\NAD2011\2025_07_28_PM

LOCATION & ELEVATION VERIFICATION MAP



KAISER-FRANCIS OIL COMPANY

LEASE NAME & WELL NO.: BELL LAKE UNIT SOUTH #702H

SECTION 1 TWP 24-S RGE 33-E SURVEY N.M.P.M.
 COUNTY LEA STATE NM ELEVATION 3628'
 DESCRIPTION 2508' FNL & 2137' FWL

LATITUDE N 32.2469597 LONGITUDE W 103.5277029



SCALE: 1" = 2000'
 0' 1000' 2000'


THIS EASEMENT/SERVITUDE LOCATION SHOWN HEREON HAS BEEN SURVEYED ON THE GROUND UNDER MY SUPERVISION AND PREPARED ACCORDING TO THE EVIDENCE FOUND AT THE TIME OF SURVEY, AND DATA PROVIDED BY KAISER-FRANCIS OIL COMPANY. THIS CERTIFICATION IS MADE AND LIMITED TO THOSE PERSONS OR ENTITIES SHOWN ON THE FACE OF THIS PLAT AND IS NON-TRANSFERABLE. THIS SURVEY IS CERTIFIED FOR THIS TRANSACTION ONLY.

ALL BEARINGS, DISTANCES, AND COORDINATE VALUES CONTAINED HEREON ARE GRID BASED UPON THE NEW MEXICO COORDINATE SYSTEM OF 1983, EAST ZONE, U.S. SURVEY FEET.



481 WINSOTT ROAD, Ste. 200 • BENBROOK, TEXAS 76126
 TELEPHONE: (817) 744-7512 • FAX (817) 744-7554
 2903 NORTH BIG SPRING • MIDLAND, TEXAS 79705
 TELEPHONE: (432) 682-1653 OR (800) 767-1653 • FAX (432) 682-1743
 WWW.TOPOGRAPHIC.COM

EXHIBIT 2
VICINITY MAP



KAISER-FRANCIS OIL COMPANY

LEASE NAME & WELL NO.: BELL LAKE UNIT SOUTH #702H

SECTION 1 TWP 24-S RGE 33-E SURVEY N.M.P.M.

COUNTY LEA STATE NM

DESCRIPTION 2508' FNL & 2137' FWL

DISTANCE & DIRECTION

FROM INT. OF NM-128 & DELAWARE BASIN RD, GO NORTH ON
DELAWARE BASIN RD ±2.6 MILES. THENCE WEST (LEFT) ON BELL LAKE
RD ±1.0 MILES, THENCE SOUTH (LEFT) ON A LEASE ROAD ±410
FEET TO A POINT ±219 FEET NORTHEAST OF THE LOCATION.



SCALE: 1" = 10000'
0' 5000' 10000'



481 WINSOTT ROAD, Ste. 200 • BENBROOK, TEXAS 76126
TELEPHONE: (817) 744-7512 • FAX (817) 744-7554
2903 NORTH BIG SPRING • MIDLAND, TEXAS 79705
TELEPHONE: (432) 682-1653 OR (800) 767-1653 • FAX (432) 682-1743
WWW.TOPOGRAPHIC.COM


THIS EASEMENT/SERVITUDE LOCATION SHOWN HEREON HAS BEEN SURVEYED ON THE GROUND UNDER MY SUPERVISION AND PREPARED ACCORDING TO THE EVIDENCE FOUND AT THE TIME OF SURVEY, AND DATA PROVIDED BY KAISER-FRANCIS OIL COMPANY. THIS CERTIFICATION IS MADE AND LIMITED TO THOSE PERSONS OR ENTITIES SHOWN ON THE FACE OF THIS PLAT AND IS NON-TRANSFERABLE. THIS SURVEY IS CERTIFIED FOR THIS TRANSACTION ONLY.

ALL BEARINGS, DISTANCES, AND COORDINATE VALUES CONTAINED HEREON ARE GRID BASED UPON THE NEW MEXICO COORDINATE SYSTEM OF 1983, EAST ZONE, U.S. SURVEY FEET.

KAISER-FRANCIS OIL COMPANY

EXHIBIT 2A

SECTION 1, TOWNSHIP 24-S, RANGE 33-E, N.M.P.M.
LEA COUNTY, NEW MEXICO



SURFACE LOCATION (SHL)

NEW MEXICO EAST
NAD 1983
X=790405 Y=454512
LAT.: N 32.2469597
LONG.: W 103.5277029
2508' FNL 2137' FWL

KICK OFF POINT (KOP)

NEW MEXICO EAST
NAD 1983
X=789753 Y=454771
LAT.: N 32.2467859
LONG.: W 103.5298057
2245' FNL 1486' FWL

FIRST TAKE POINT (FTP)

NEW MEXICO EAST
NAD 1983
X=789756 Y=454198
LAT.: N 32.2461109
LONG.: W 103.5298097
2450' FSL 1486' FWL

BLM PERF. POINT (BPP1)

NEW MEXICO EAST
NAD 1983
X=789776 Y=451748
LAT.: N 32.2393765
LONG.: W 103.5298059
0' FSL 1492' FWL

BLM PERF. POINT (BPP2)


NEW MEXICO EAST
NAD 1983
X=789797 Y=449108
LAT.: N 32.2321185
LONG.: W 103.5298019
2640' FNL 1488' FWL

LAST TAKE POINT (LTP)

NEW MEXICO EAST
NAD 1983
X=789817 Y=446562
LAT.: N 32.2251199
LONG.: W 103.5297980
100' FSL 1486' FWL

BOTTOM HOLE LOCATION (BHL)

NEW MEXICO EAST
NAD 1983
X=789818 Y=446487
LAT.: N 32.2249138
LONG.: W 103.5297976
25' FSL 1486' FWL



DETAIL VIEW
SCALE: 1" = 400'

LEASE NAME & WELL NO.: BELL LAKE UNIT SOUTH #702H

SECTION 1 TWP 24-S RGE 33-E SURVEY N.M.P.M.
COUNTY LEA STATE NM
DESCRIPTION _____

DISTANCE & DIRECTION
FROM INT. OF NM-128 & DELAWARE BASIN RD. GO NORTH ON
DELAWARE BASIN RD ±2.6 MILES. THENCE WEST (LEFT) ON BELL LAKE
RD ±1.0 MILES, THENCE SOUTH (LEFT) ON A LEASE ROAD ±410 FEET
TO A POINT ±219 FEET NORTHEAST OF THE LOCATION.



Angel M. Baeza, P.S. No. 25116





481 WINSOTT ROAD, Ste. 200 • BENBROOK, TEXAS 76126
TELEPHONE: (817) 744-7512 • FAX (817) 744-7554
2903 NORTH BIG SPRING • MIDLAND, TEXAS 79705
TELEPHONE: (432) 682-1653 OR (800) 767-1653 • FAX (432) 682-1743
WWW.TOPOGRAPHIC.COM

KAISER-FRANCIS OIL COMPANY

SECTION 1, TOWNSHIP 24-S, RANGE 33-E, N.M.P.M.
LEA COUNTY, NEW MEXICO

LEGEND




Angel M. Baeza, P.S. No. 25116

LEASE NAME & WELL NO.: BELL LAKE UNIT SOUTH #702H
#702H LATITUDE N 32.2469597 #702H LONGITUDE W 103.5277029

CENTER OF PAD IS 2511' FNL & 2084' FWL

ALL BEARINGS, DISTANCES, AND COORDINATE VALUES CONTAINED HEREON ARE GRID BASED UPON THE NEW MEXICO COORDINATE SYSTEM OF 1983, EAST ZONE, U.S. SURVEY FEET. ELEVATIONS USED ARE NAVD88, OBTAINED THROUGH AN OPUS SOLUTION.

THIS EASEMENT/SERVITUDE LOCATION SHOWN HEREON HAS BEEN SURVEYED ON THE GROUND UNDER MY SUPERVISION AND PREPARED ACCORDING TO THE EVIDENCE FOUND AT THE TIME OF SURVEY, AND DATA PROVIDED BY KAISER-FRANCIS OIL COMPANY. THIS CERTIFICATION IS MADE AND LIMITED TO THOSE PERSONS OR ENTITIES SHOWN ON THE FACE OF THIS PLAT AND IS NON-TRANSFERABLE. THIS SURVEY IS CERTIFIED FOR THIS TRANSACTION ONLY.



481 WINSOTT ROAD, Ste. 200 • BENBROOK, TEXAS 76126
TELEPHONE: (817) 744-7512 • FAX (817) 744-7554
2903 NORTH BIG SPRING • MIDLAND, TEXAS 79705
TELEPHONE: (432) 682-1653 OR (800) 767-1653 • FAX (432) 682-1743
WWW.TOPOGRAPHIC.COM

ORIGINAL DOCUMENT SIZE: 8.5" X 11"

AERIAL PHOTO



KAISER-FRANCIS OIL COMPANY

LEASE NAME & WELL NO.: BELL LAKE UNIT SOUTH #702H

SECTION 1 TWP 24-S RGE 33-E SURVEY N.M.P.M.
 COUNTY LEA STATE NM ELEVATION 3628'
 DESCRIPTION 2508' FNL & 2137' FWL

LATITUDE N 32.2469597 LONGITUDE W 103.5277029



SCALE: 1" = 2000'
 0' 1000' 2000'

THIS EASEMENT/SERVITUDE LOCATION SHOWN HEREON HAS BEEN SURVEYED ON THE GROUND UNDER MY SUPERVISION AND PREPARED ACCORDING TO THE EVIDENCE FOUND AT THE TIME OF SURVEY, AND DATA PROVIDED BY KAISER-FRANCIS OIL COMPANY. THIS CERTIFICATION IS MADE AND LIMITED TO THOSE PERSONS OR ENTITIES SHOWN ON THE FACE OF THIS PLAT AND IS NON-TRANSFERABLE. THIS SURVEY IS CERTIFIED FOR THIS TRANSACTION ONLY.

ALL BEARINGS, DISTANCES, AND COORDINATE VALUES CONTAINED HEREON ARE GRID BASED UPON THE NEW MEXICO COORDINATE SYSTEM OF 1983, EAST ZONE, U.S. SURVEY FEET.




481 WINSOTT ROAD, Ste. 200 • BENBROOK, TEXAS 76126
 TELEPHONE: (817) 744-7512 • FAX (817) 744-7554
 2903 NORTH BIG SPRING • MIDLAND, TEXAS 79705
 TELEPHONE: (432) 682-1653 OR (800) 767-1653 • FAX (432) 682-1743
 WWW.TOPOGRAPHIC.COM

EXHIBIT 3

SECTION 1, TOWNSHIP 24-S, RANGE 33-E, N.M.P.M.
LEA COUNTY, NEW MEXICO

KAISER-FRANCIS OIL COMPANY



LEASE NAME & WELL NO.: BELL LAKE UNIT SOUTH #702H

SCALE: NTS

#702H LATITUDE N 32.2469597 #702H LONGITUDE W 103.5277029

ALL BEARINGS, DISTANCES, AND COORDINATE VALUES CONTAINED HEREON ARE GRID BASED UPON THE NEW MEXICO COORDINATE SYSTEM OF 1983, EAST ZONE, U.S. SURVEY FEET.

THIS EASEMENT/SERVITUDE LOCATION SHOWN HEREON HAS BEEN SURVEYED ON THE GROUND UNDER MY SUPERVISION AND PREPARED ACCORDING TO THE EVIDENCE FOUND AT THE TIME OF SURVEY, AND DATA PROVIDED BY KAISER-FRANCIS OIL COMPANY. THIS CERTIFICATION IS MADE AND LIMITED TO THOSE PERSONS OR ENTITIES SHOWN ON THE FACE OF THIS PLAT AND IS NON-TRANSFERABLE. THIS SURVEY IS CERTIFIED FOR THIS TRANSACTION ONLY.



481 WINSOTT ROAD, Ste. 200 • BENBROOK, TEXAS 76126
TELEPHONE: (817) 744-7512 • FAX (817) 744-7554
2903 NORTH BIG SPRING • MIDLAND, TEXAS 79705
TELEPHONE: (432) 682-1653 OR (800) 767-1653 • FAX (432) 682-1743
WWW.TOPOGRAPHIC.COM

State of New Mexico
 Energy, Minerals and Natural Resources Department

Submit Electronically
 Via E-permitting

Oil Conservation Division
 1220 South St. Francis Dr.
 Santa Fe, NM 87505

NATURAL GAS MANAGEMENT PLAN

This Natural Gas Management Plan must be submitted with each Application for Permit to Drill (APD) for a new or recompleted well.

Section 1 – Plan Description Effective May 25, 2021

I. Operator: Kaiser-Francis Oil Company OGRID: 12361 Date: 10/ 21 /2025

II. Type: Original Amendment due to 19.15.27.9.D(6)(a) NMAC 19.15.27.9.D(6)(b) NMAC Other.

If Other, please describe: _____

III. Well(s): Provide the following information for each new or recompleted well or set of wells proposed to be drilled or proposed to be recompleted from a single well pad or connected to a central delivery point.

Well Name	API	ULSTR	Footages	Anticipated Oil BBL/D	Anticipated Gas MCF/D	Anticipated Produced Water BBL/D
South Pad 1 wells listed on next page.						

IV. Central Delivery Point Name: BLSU CTB SW [See 19.15.27.9(D)(1) NMAC]

V. Anticipated Schedule: Provide the following information for each new or recompleted well or set of wells proposed to be drilled or proposed to be recompleted from a single well pad or connected to a central delivery point.

Well Name	API	Spud Date	TD Reached Date	Completion Commencement Date	Initial Flow Back Date	First Production Date
South Pad 1 anticipated schedule listed on next page.						

VI. Separation Equipment: Attach a complete description of how Operator will size separation equipment to optimize gas capture.

VII. Operational Practices: Attach a complete description of the actions Operator will take to comply with the requirements of Subsection A through F of 19.15.27.8 NMAC.

VIII. Best Management Practices: Attach a complete description of Operator’s best management practices to minimize venting during active and planned maintenance.

III. Wells

Well Name	Well Location (ULSTR)	Footages	Expected Oil BBLs/D	Expected Gas MCF/D	Expected Water BBLs/D	Flared or Vented
Bell Lake South Unit 702H	F-1-24S-33E	2508' FNL & 2137' FWL	800	1500	400	0
Bell Lake South Unit 603H	F-1-24S-33E	2467' FNL & 2169' FWL	800	1500	400	0
Bell Lake South Unit 604H	F-1-24S-33E	2495' FNL & 2180' FWL	800	1500	400	0
Bell Lake South Unit 102H	L-5-23S-34E	1770' FSL & 454' FWL	800	1500	400	0
Bell Lake South Unit 103H	L-5-23S-34E	1739' FSL & 454' FWL	800	1500	400	0
Bell Lake South Unit 104H	L-5-23S-34E	1830' FSL & 454' FWL	800	1500	400	0

V. Anticipated Schedule

Well Name	Spud	TD	Completion	Initial Flow Back	First Production
Bell Lake South Unit 102H	4/15/2026	4/29/2026	8/1/2026	9/1/2026	9/2/2026
Bell Lake South Unit 103H	4/30/2026	5/14/2026	8/1/2026	9/1/2026	9/2/2026
Bell Lake South Unit 104H	5/15/2026	5/29/2026	8/1/2026	9/1/2026	9/2/2026
Bell Lake South Unit 702H	5/30/2026	6/14/2026	8/1/2026	9/1/2026	9/2/2026
Bell Lake South Unit 603H	6/15/2026	6/29/2026	8/1/2026	9/1/2026	9/2/2026
Bell Lake South Unit 604H	6/30/2026	7/14/2026	8/1/2026	9/1/2026	9/2/2026

Kaiser Francis Oil Company Natural Gas Management Plan

VI. Separation Equipment:

The surface facility design includes the following process equipment: 3-phase separators (1 per well), a sales gas scrubber, one or two 3-phase heater treaters, multiple VRU compressors (sized for tank flash vapors and heater treater flash gas), multiple water and oil tanks, flare knockouts (HP & LP), and flares (HP &LP). All process vessels are sized to separate oil, water and gas based upon typical/historical predicted well performance. Each process vessels will be fitted with a Pressure Safety Valve (PSV) per ASME requirements to mitigate vessel rupture and loss of containment. The process vessels will be fitted with pressure transmitters that communicate to the facility control system. This will allow operators to monitor pressures. The control system will be configured to automatically shut in all wells at each well head via Emergency Shut Down (ESD) valve at programmed pressure levels to avoid over-pressure and potential vent of natural gas. Natural gas will be preferentially sold to pipeline and only during upset/emergency conditions will gas be directly automatically to the HP flare system until each well ESD valve closes. Flash gas from the tanks and heater treaters will be compressed via VRU compressors and will be preferentially sold to pipeline. Oil tanks and water tanks will be fitted with lockdown hatches and 32 oz PVRV's (Pressure/Vacuum Relief Vents) to protect the tanks from rupture/collapse. The tank header closed vent system will be sized to keep pressures below 20 oz to ensure the gas can get to the low-pressure (LP) flare even in the event the VRU's are not running. The tank header closed vent system will include a knockout vessel and LP flare. Only during upset/emergency conditions will tank flash vapors be direct to the LP flare system.

VII. Operational Practices:

During drilling operations- Gas meters will be installed at the shakers and Volume Totalizers will be installed on the pits. In the event that elevated gas levels, or a pit gain are observed, returns will be diverted to a gas buster. Gas coming off the gas buster will be combusted at the flare stack. A 10' or taller flare will be located at least 100' from the SHL.

During completions operations, including stimulation and frac plug drill out operations, hydrocarbon production to surface is minimized. When gas production does occur, gas will be combusted at a flare stack. A 10' or taller flare will be located at least 100' from the SHL.

During production operations, all process vessels (separators, heater treaters, and Tanks) will route gas outlets into the natural gas gathering pipeline. Gas will preferentially be routed to natural gas gathering pipeline and the flare system will be used only during emergency, or malfunction. Exceptions to this will include only those qualified emergencies as mentioned in the BLM Waste Prevention Rule. Operators will conduct weekly AVO inspections. These AVO inspection records will be stored for the required 5-year period and will be made available upon Division request.

VIII. Best Management Practices:

When performing routine or preventive maintenance on a vessel or tank, initially all inlet valves are closed, and the vessel or tank is allowed to depressurize to the flare. Once a vessel is depressurized to less than 1-2 psig, the remaining natural gas in the vessel is vented to atmosphere. Once a tank is depressurized to less than 1-2 oz, the remaining natural gas in the tank is vented to atmosphere. Once the vessel or tank is depressurized to atmospheric pressure, the vessel or tank can be safely opened, and maintenance performed.

Section 2 – Enhanced Plan

EFFECTIVE APRIL 1, 2022

Beginning April 1, 2022, an operator that is not in compliance with its statewide natural gas capture requirement for the applicable reporting area must complete this section.

Operator certifies that it is not required to complete this section because Operator is in compliance with its statewide natural gas capture requirement for the applicable reporting area.

IX. Anticipated Natural Gas Production:

Well	API	Anticipated Average Natural Gas Rate MCF/D	Anticipated Volume of Natural Gas for the First Year MCF

X. Natural Gas Gathering System (NGGS):

Operator	System	ULSTR of Tie-in	Anticipated Gathering Start Date	Available Maximum Daily Capacity of System Segment Tie-in

XI. Map. Attach an accurate and legible map depicting the location of the well(s), the anticipated pipeline route(s) connecting the production operations to the existing or planned interconnect of the natural gas gathering system(s), and the maximum daily capacity of the segment or portion of the natural gas gathering system(s) to which the well(s) will be connected.

XII. Line Capacity. The natural gas gathering system will will not have capacity to gather 100% of the anticipated natural gas production volume from the well prior to the date of first production.

XIII. Line Pressure. Operator does does not anticipate that its existing well(s) connected to the same segment, or portion, of the natural gas gathering system(s) described above will continue to meet anticipated increases in line pressure caused by the new well(s).

Attach Operator’s plan to manage production in response to the increased line pressure.

XIV. Confidentiality: Operator asserts confidentiality pursuant to Section 71-2-8 NMSA 1978 for the information provided in Section 2 as provided in Paragraph (2) of Subsection D of 19.15.27.9 NMAC, and attaches a full description of the specific information for which confidentiality is asserted and the basis for such assertion.

Section 3 - Certifications

Effective May 25, 2021

Operator certifies that, after reasonable inquiry and based on the available information at the time of submittal:

Operator will be able to connect the well(s) to a natural gas gathering system in the general area with sufficient capacity to transport one hundred percent of the anticipated volume of natural gas produced from the well(s) commencing on the date of first production, taking into account the current and anticipated volumes of produced natural gas from other wells connected to the pipeline gathering system; or

Operator will not be able to connect to a natural gas gathering system in the general area with sufficient capacity to transport one hundred percent of the anticipated volume of natural gas produced from the well(s) commencing on the date of first production, taking into account the current and anticipated volumes of produced natural gas from other wells connected to the pipeline gathering system.

If Operator checks this box, Operator will select one of the following:

Well Shut-In. Operator will shut-in and not produce the well until it submits the certification required by Paragraph (4) of Subsection D of 19.15.27.9 NMAC; or

Venting and Flaring Plan. Operator has attached a venting and flaring plan that evaluates and selects one or more of the potential alternative beneficial uses for the natural gas until a natural gas gathering system is available, including:

- (a) power generation on lease;
- (b) power generation for grid;
- (c) compression on lease;
- (d) liquids removal on lease;
- (e) reinjection for underground storage;
- (f) reinjection for temporary storage;
- (g) reinjection for enhanced oil recovery;
- (h) fuel cell production; and
- (i) other alternative beneficial uses approved by the division.

Section 4 - Notices

1. If, at any time after Operator submits this Natural Gas Management Plan and before the well is spud:

(a) Operator becomes aware that the natural gas gathering system it planned to connect the well(s) to has become unavailable or will not have capacity to transport one hundred percent of the production from the well(s), no later than 20 days after becoming aware of such information, Operator shall submit for OCD's approval a new or revised venting and flaring plan containing the information specified in Paragraph (5) of Subsection D of 19.15.27.9 NMAC; or

(b) Operator becomes aware that it has, cumulatively for the year, become out of compliance with its baseline natural gas capture rate or natural gas capture requirement, no later than 20 days after becoming aware of such information, Operator shall submit for OCD's approval a new or revised Natural Gas Management Plan for each well it plans to spud during the next 90 days containing the information specified in Paragraph (2) of Subsection D of 19.15.27.9 NMAC, and shall file an update for each Natural Gas Management Plan until Operator is back in compliance with its baseline natural gas capture rate or natural gas capture requirement.


2. OCD may deny or conditionally approve an APD if Operator does not make a certification, fails to submit an adequate venting and flaring plan which includes alternative beneficial uses for the anticipated volume of natural gas produced, or if OCD determines that Operator will not have adequate natural gas takeaway capacity at the time a well will be spud.


I certify that, after reasonable inquiry, the statements in and attached to this Natural Gas Management Plan are true and correct to the best of my knowledge and acknowledge that a false statement may be subject to civil and criminal penalties under the Oil and Gas Act.

Signature:	Christina Opfer
Printed Name:	Christina Opfer
Title:	Regulatory Manager
E-mail Address:	ChristinaO@kfoc.net
Date:	10/21/2025
Phone:	918-491-4468

OIL CONSERVATION DIVISION
(Only applicable when submitted as a standalone form)

Approved By:
Title:
Approval Date:
Conditions of Approval:







U.S. Department of the Interior
BUREAU OF LAND MANAGEMENT

Drilling Plan Data Report

10/13/2025

APD ID: 10400106497

Submission Date: 08/13/2025

Highlighted data reflects the most recent changes

Operator Name: KAISER FRANCIS OIL COMPANY

Well Name: BELL LAKE UNIT SOUTH

Well Number: 702H

Well Type: OIL WELL

Well Work Type: Drill

Show Final Text

Section 1 - Geologic Formations

Formation ID	Formation Name	Elevation	True Vertical	Measured Depth	Lithologies	Mineral Resources	Producing Formatio
16546638	---	3628	0	0	ALLUVIUM, SANDSTONE	NONE	N
16546639	RUSTLER ANHYDRITE	2313	1315	1315	ANHYDRITE	NONE	N
16546640	TOP OF SALT	2063	1565	1565	SALT	NONE	N
16546641	BASE OF SALT	-1337	4965	4965	SALT	NONE	N
16546642	LAMAR	-1607	5235	5235	LIMESTONE	NATURAL GAS, OIL	Y
16546643	BELL CANYON	-1652	5280	5280	LIMESTONE, SANDSTONE, SHALE	NATURAL GAS, OIL	Y
16546644	CHERRY CANYON	-2722	6350	6350	LIMESTONE, SANDSTONE, SHALE	NATURAL GAS, OIL	Y
16546645	BRUSHY CANYON	-3872	7500	7500	LIMESTONE, SANDSTONE, SHALE	NATURAL GAS, OIL	Y
16546646	BONE SPRING	-5342	8970	8970	LIMESTONE	NATURAL GAS, OIL	Y

Section 2 - Blowout Prevention

Pressure Rating (PSI): 5M

Rating Depth: 18000

Equipment: A 5M system will be installed according to 43 CFR 3172 consisting of an Annular Preventer, BOP with two rams, a blind ram and safety valves and appropriate handles located on the rig floor. BOP will be equipped with 2 side outlets(choke side shall be a minimum 3 line and kill side will be a minimum 2 line). Kill line will be installed with (2) valves and a check valve (2 min) of proper pressure rating for the system. A manual and hydraulic valve (2 min) will be installed on the choke line, 2 chokes will be used with one being remotely controlled. Fill up line will be installed above the uppermost preventer. Pressure gauge of proper pressure rating will be installed on choke manifold. Upper and lower kelly cocks will be utilized with handles readily available in plain sight. A float sub will be available at all times. All connections subject to well pressure will be flanged, welded, or clamped. BOP will be installed on top of a multi-bowl wellhead.

Requesting Variance? YES

Variance request: A variance to the required rigid steel line connecting the choke is requested. Certification is attached in the BOP attachments.

Testing Procedure: BOP/BOPE will be tested by an independent service company to 250 psi low and the high pressure indicated above per 43 CFR 3172 requirements. The System may be upgraded to a higher

Operator Name: KAISER FRANCIS OIL COMPANY

Well Name: BELL LAKE UNIT SOUTH

Well Number: 702H

pressure but still tested to the working pressure listed in the table above. If the system is upgraded all of the components installed will be functional and tested.

Choke Diagram Attachment:

- D2_Choke_Manifold_10k_20250731095341.pdf
- D2_Multibowl_Wellhead_Cactus_3_String_20250731095341.pdf
- D2_CHOKE_HOSE_M15181_20250731095341.pdf
- D2_Choke_Manifold_10k_20250828080428.pdf
- D2_Multibowl_Wellhead_Cactus_3_String_20250828080428.pdf
- D2_CHOKE_HOSE_M15181_20250828080429.pdf

BOP Diagram Attachment:

- D2_BOP_stack_5k_annular_20250731095347.pdf
- D2_BOP_stack_5k_annular_20250828080453.pdf

Section 3 - Casing

Casing ID	String Type	Hole Size	Csg Size	Condition	Standard	Tapered String	Top Set MD	Bottom Set MD	Top Set TVD	Bottom Set TVD	Top Set MSL	Bottom Set MSL	Calculated casing length MD	Grade	Weight	Joint Type	Collapse SF	Burst SF	Joint SF Type	Joint SF	Body SF Type	Body SF
1	SURFACE	17.5	13.375	NEW	API	N	0	1250	0	1250	3628	2378	1250	J-55	54.5	BUTT	1.9	4.6	DRY	13.3	DRY	12.5
2	INTERMEDIATE	12.25	9.625	NEW	API	N	0	5250	0	5250	3632	-1622	5250	P-110	40	BUTT	1.6	3.3	DRY	6.2	DRY	6.8
3	PRODUCTION	8.5	5.5	NEW	API	N	0	18154	0	9825	3628	-6197	18154	P-110	20	OTHER - GBCD	2.6	3	DRY	1.9	DRY	2

Casing Attachments

Operator Name: KAISER FRANCIS OIL COMPANY

Well Name: BELL LAKE UNIT SOUTH

Well Number: 702H

Casing Attachments

Casing ID: 1 **String** SURFACE

Inspection Document:

Spec Document:

Tapered String Spec:

Casing Design Assumptions and Worksheet(s):

D3_Casing_Assumptions_20250811131709.pdf

D3_Pipe_Body_and_API_Connections_Performance_Data_13.3750_54.5000_0.3800__J55_20250811131709.pdf

D3_Pipe_Body_and_API_Connections_Performance_Data_13.3750_54.5000_0.3800__J55_20250828080609.pdf

D3_Casing_Assumptions_20250828080609.pdf

Casing ID: 2 **String** INTERMEDIATE

Inspection Document:

Spec Document:

Tapered String Spec:

Casing Design Assumptions and Worksheet(s):

D3_API_BTC_9.625_0.395_P110_ICY_01242025_20250811131722.pdf

D3_Casing_Assumptions_20250811131722.pdf

D3_API_BTC_9.625_0.395_P110_ICY_01242025_20250828080630.pdf

D3_Casing_Assumptions_20250828080631.pdf

Operator Name: KAISER FRANCIS OIL COMPANY

Well Name: BELL LAKE UNIT SOUTH

Well Number: 702H

Casing Attachments

Casing ID: 3 **String** PRODUCTION

Inspection Document:

Spec Document:

Tapered String Spec:

Casing Design Assumptions and Worksheet(s):

D3_Casing_Assumptions_20250811131800.pdf

D3_5.5in_20ppf_P110_GBCD_Performance_Sheet_20250811131800.pdf

D3_5.5in_20ppf_P110_GBCD_Performance_Sheet_20250828080528.pdf

D3_Casing_Assumptions_20250828080528.pdf

Section 4 - Cement

String Type	Lead/Tail	Stage Tool Depth	Top MD	Bottom MD	Quantity(sx)	Yield	Density	Cu Ft	Excess%	Cement type	Additives
SURFACE	Lead		0	1030	717	1.75	13.5	1252	75	Class C	Poly-E-Flake-Calcium Chloride, 0.125 lbm/sk Poly-E-Flake
SURFACE	Tail		1030	1250	198	1.35	14.8	267.5	75	Class C	1% Calcium Chloride, 0.125 lbm/sk Poly-E-Flake
INTERMEDIATE	Lead		0	4750	1241	2.1	12	2604	75	Class C	5% Salt, 3 lbm/sk Kol-Seal, 0.13 lbm/sk Poly-E-Flake
INTERMEDIATE	Tail		4750	5250	205	1.34	14.8	274.1	75	Class C	0.4% Halad(R)-344, 0.125 lbm/sk Poly-E-Flake
PRODUCTION	Lead		5050	9352	322	3.52	10.5	1133	15	Class H	6 lbm/sk BRIDGEMAKER II LCM
PRODUCTION	Tail		9352	18154	1896	1.22	14.5	2319	15	Class H	none

Operator Name: KAISER FRANCIS OIL COMPANY

Well Name: BELL LAKE UNIT SOUTH

Well Number: 702H

Section 5 - Circulating Medium

Mud System Type: Closed

Will an air or gas system be Used? NO

Description of the equipment for the circulating system in accordance with 43 CFR 3172:

Diagram of the equipment for the circulating system in accordance with 43 CFR 3172:

Describe what will be on location to control well or mitigate other conditions: Sufficient mud materials to maintain mud properties and meet minimum lost circulation and weight increase requirements will be kept on location at all times.

Describe the mud monitoring system utilized: PVT/Totco/Visual Monitoring

Circulating Medium Table

Top Depth	Bottom Depth	Mud Type	Min Weight (lbs/gal)	Max Weight (lbs/gal)	Density (lbs/cu ft)	Gel Strength (lbs/100 sqft)	PH	Viscosity (CP)	Salinity (ppm)	Filtration (cc)	Additional Characteristics
0	1250	OTHER : Freshwater	8.4	8.9							
1250	5250	OTHER : Brine	9.8	10.2							
5250	1815 4	WATER-BASED MUD	8.7	9.3							

Section 6 - Test, Logging, Coring

List of production tests including testing procedures, equipment and safety measures:

top of cement on production casing will be determined by calculation or circulating cement to surface

List of open and cased hole logs run in the well:

MUD LOG/GEOLOGICAL LITHOLOGY LOG,GAMMA RAY LOG,DIRECTIONAL SURVEY,

Coring operation description for the well:

none planned

Operator Name: KAISER FRANCIS OIL COMPANY

Well Name: BELL LAKE UNIT SOUTH

Well Number: 702H

Section 7 - Pressure

Anticipated Bottom Hole Pressure: 4751

Anticipated Surface Pressure: 2589

Anticipated Bottom Hole Temperature(F): 173

Anticipated abnormal pressures, temperatures, or potential geologic hazards? NO

Describe:

Contingency Plans geohazards description:

Contingency Plans geohazards

Hydrogen Sulfide drilling operations plan required? YES

Hydrogen sulfide drilling operations

D7_H2S_Contingency_Plan_S_Pad_1_20250811122933.pdf

D7_H2S_Contingency_Plan_S_Pad_1_20250828080750.pdf

Section 8 - Other Information

Proposed horizontal/directional/multi-lateral plan submission:

BELL_LAKE_UNIT_SOUTH_702H_Plan_1_20250811132037.pdf

BELL_LAKE_UNIT_SOUTH_702H_Plan_1_20250828080802.pdf

Other proposed operations facets description:

Other proposed operations facets attachment:

D_Drilling_Plan_BLUS_702H_20250811132043.pdf

SBL_Pad_1R_NGMP_20250811122957.pdf

SBL_Pad_1R_NGMP_20250828080813.pdf

D_Drilling_Plan_BLUS_702H_20250828080813.pdf

Other Variance request(s)?: N

Other Variance attachment:



KAISER FRANCIS OIL CO.

**LEA COUNTY, N.M. BLUS
SEC 1-T24S-R33E
BELL LAKE UNIT SOUTH 702H**

Wellbore #1

Plan: Plan 1

Standard Planning Report

21 July, 2025

Kaiser-Francis Oil Company



Planning Report

Kaiser-Francis Oil Company

Database:	1 - EDM Production	Local Co-ordinate Reference:	Well BELL LAKE UNIT SOUTH 702H
Company:	KAISER FRANCIS OIL CO.	TVD Reference:	WELL @ 3627.80usft (Original Well Elev)
Project:	LEA COUNTY, N.M. BLUS	MD Reference:	WELL @ 3627.80usft (Original Well Elev)
Site:	SEC 1-T24S-R33E	North Reference:	Grid
Well:	BELL LAKE UNIT SOUTH 702H	Survey Calculation Method:	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	Plan 1		

Project	LEA COUNTY, N.M. BLUS		
Map System:	US State Plane 1983	System Datum:	Mean Sea Level
Geo Datum:	North American Datum 1983		
Map Zone:	New Mexico Eastern Zone		

Site	SEC 1-T24S-R33E				
Site Position:		Northing:	454,471.46 usft	Latitude:	32.24685137
From:	Map	Easting:	790,296.31 usft	Longitude:	-103.52805600
Position Uncertainty:	0.00 usft	Slot Radius:	13-3/16 "		

Well	BELL LAKE UNIT SOUTH 702H					
Well Position	+N/-S	0.00 usft	Northing:	454,511.46 usft	Latitude:	32.24695909
	+E/-W	0.00 usft	Easting:	790,404.31 usft	Longitude:	-103.52770572
Position Uncertainty		0.50 usft	Wellhead Elevation:	usft	Ground Level:	3,604.80 usft
Grid Convergence:		0.43 °				


Wellbore	Wellbore #1				
Magnetics	Model Name	Sample Date	Declination (°)	Dip Angle (°)	Field Strength (nT)
	BGGM CURRENT	7/1/2025	6.19	59.79	47,231.90000000

Design	Plan 1			
Audit Notes:				
Version:	Phase:	PLAN	Tie On Depth:	0.00
Vertical Section:	Depth From (TVD) (usft)	+N/-S (usft)	+E/-W (usft)	Direction (°)
	0.00	0.00	0.00	180.00

Plan Survey Tool Program	Date	7/21/2025		
Depth From (usft)	Depth To (usft)	Survey (Wellbore)	Tool Name	Remarks
1	0.00	18,154.46 Plan 1 (Wellbore #1)	MWD+HRGM	
			OWSG MWD + HRGM	



Planning Report



Database:	1 - EDM Production	Local Co-ordinate Reference:	Well BELL LAKE UNIT SOUTH 702H
Company:	KAISER FRANCIS OIL CO.	TVD Reference:	WELL @ 3627.80usft (Original Well Elev)
Project:	LEA COUNTY, N.M. BLUS	MD Reference:	WELL @ 3627.80usft (Original Well Elev)
Site:	SEC 1-T24S-R33E	North Reference:	Grid
Well:	BELL LAKE UNIT SOUTH 702H	Survey Calculation Method:	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	Plan 1		

Plan Sections										
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)	TFO (°)	Target
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
1,500.00	0.00	0.00	1,500.00	0.00	0.00	0.00	0.00	0.00	0.00	
1,650.00	3.00	308.00	1,649.93	2.42	-3.09	2.00	2.00	0.00	308.00	
2,350.00	3.00	308.00	2,348.97	24.97	-31.96	0.00	0.00	0.00	0.00	
2,500.00	0.00	0.00	2,498.90	27.39	-35.06	2.00	-2.00	34.67	180.00	
5,001.10	0.00	0.00	5,000.00	27.39	-35.06	0.00	0.00	0.00	0.00	
5,827.92	16.54	310.75	5,815.39	104.74	-124.82	2.00	2.00	-5.96	310.75	
7,673.47	16.54	310.75	7,584.61	447.65	-522.74	0.00	0.00	0.00	0.00	
8,500.29	0.00	0.00	8,400.00	525.00	-612.50	2.00	-2.00	0.00	180.00	
9,352.33	0.00	0.00	9,252.04	525.00	-612.50	0.00	0.00	0.00	0.00	
10,252.33	90.00	182.80	9,825.00	-47.27	-640.49	10.00	10.00	0.00	182.80	
10,412.92	90.00	179.59	9,825.00	-207.81	-643.84	2.00	0.00	-2.00	-90.00	
18,154.70	90.00	179.59	9,825.00	-7,949.38	-588.19	0.00	0.00	0.00	0.00	BLUS 702H LTP (100)



Planning Report

Kaiser-Francis Oil Company

Database:	1 - EDM Production	Local Co-ordinate Reference:	Well BELL LAKE UNIT SOUTH 702H
Company:	KAISER FRANCIS OIL CO.	TVD Reference:	WELL @ 3627.80usft (Original Well Elev)
Project:	LEA COUNTY, N.M. BLUS	MD Reference:	WELL @ 3627.80usft (Original Well Elev)
Site:	SEC 1-T24S-R33E	North Reference:	Grid
Well:	BELL LAKE UNIT SOUTH 702H	Survey Calculation Method:	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	Plan 1		

Planned Survey										
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)	
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
100.00	0.00	0.00	100.00	0.00	0.00	0.00	0.00	0.00	0.00	
200.00	0.00	0.00	200.00	0.00	0.00	0.00	0.00	0.00	0.00	
300.00	0.00	0.00	300.00	0.00	0.00	0.00	0.00	0.00	0.00	
400.00	0.00	0.00	400.00	0.00	0.00	0.00	0.00	0.00	0.00	
500.00	0.00	0.00	500.00	0.00	0.00	0.00	0.00	0.00	0.00	
600.00	0.00	0.00	600.00	0.00	0.00	0.00	0.00	0.00	0.00	
700.00	0.00	0.00	700.00	0.00	0.00	0.00	0.00	0.00	0.00	
800.00	0.00	0.00	800.00	0.00	0.00	0.00	0.00	0.00	0.00	
900.00	0.00	0.00	900.00	0.00	0.00	0.00	0.00	0.00	0.00	
1,000.00	0.00	0.00	1,000.00	0.00	0.00	0.00	0.00	0.00	0.00	
1,100.00	0.00	0.00	1,100.00	0.00	0.00	0.00	0.00	0.00	0.00	
1,200.00	0.00	0.00	1,200.00	0.00	0.00	0.00	0.00	0.00	0.00	
1,300.00	0.00	0.00	1,300.00	0.00	0.00	0.00	0.00	0.00	0.00	
1,400.00	0.00	0.00	1,400.00	0.00	0.00	0.00	0.00	0.00	0.00	
1,500.00	0.00	0.00	1,500.00	0.00	0.00	0.00	0.00	0.00	0.00	
1,600.00	2.00	308.00	1,599.98	1.07	-1.38	-1.07	2.00	2.00	0.00	
1,650.00	3.00	308.00	1,649.93	2.42	-3.09	-2.42	2.00	2.00	0.00	
1,700.00	3.00	308.00	1,699.86	4.03	-5.16	-4.03	0.00	0.00	0.00	
1,800.00	3.00	308.00	1,799.73	7.25	-9.28	-7.25	0.00	0.00	0.00	
1,900.00	3.00	308.00	1,899.59	10.47	-13.40	-10.47	0.00	0.00	0.00	
2,000.00	3.00	308.00	1,999.45	13.69	-17.53	-13.69	0.00	0.00	0.00	
2,100.00	3.00	308.00	2,099.31	16.92	-21.65	-16.92	0.00	0.00	0.00	
2,200.00	3.00	308.00	2,199.18	20.14	-25.78	-20.14	0.00	0.00	0.00	
2,300.00	3.00	308.00	2,299.04	23.36	-29.90	-23.36	0.00	0.00	0.00	
2,350.00	3.00	308.00	2,348.97	24.97	-31.96	-24.97	0.00	0.00	0.00	
2,400.00	2.00	308.00	2,398.92	26.31	-33.68	-26.31	2.00	-2.00	0.00	
2,500.00	0.00	0.00	2,498.90	27.39	-35.06	-27.39	2.00	-2.00	52.00	
2,600.00	0.00	0.00	2,598.90	27.39	-35.06	-27.39	0.00	0.00	0.00	
2,700.00	0.00	0.00	2,698.90	27.39	-35.06	-27.39	0.00	0.00	0.00	
2,800.00	0.00	0.00	2,798.90	27.39	-35.06	-27.39	0.00	0.00	0.00	
2,900.00	0.00	0.00	2,898.90	27.39	-35.06	-27.39	0.00	0.00	0.00	
3,000.00	0.00	0.00	2,998.90	27.39	-35.06	-27.39	0.00	0.00	0.00	
3,100.00	0.00	0.00	3,098.90	27.39	-35.06	-27.39	0.00	0.00	0.00	
3,200.00	0.00	0.00	3,198.90	27.39	-35.06	-27.39	0.00	0.00	0.00	
3,300.00	0.00	0.00	3,298.90	27.39	-35.06	-27.39	0.00	0.00	0.00	
3,400.00	0.00	0.00	3,398.90	27.39	-35.06	-27.39	0.00	0.00	0.00	
3,500.00	0.00	0.00	3,498.90	27.39	-35.06	-27.39	0.00	0.00	0.00	
3,600.00	0.00	0.00	3,598.90	27.39	-35.06	-27.39	0.00	0.00	0.00	
3,700.00	0.00	0.00	3,698.90	27.39	-35.06	-27.39	0.00	0.00	0.00	
3,800.00	0.00	0.00	3,798.90	27.39	-35.06	-27.39	0.00	0.00	0.00	
3,900.00	0.00	0.00	3,898.90	27.39	-35.06	-27.39	0.00	0.00	0.00	
4,000.00	0.00	0.00	3,998.90	27.39	-35.06	-27.39	0.00	0.00	0.00	
4,100.00	0.00	0.00	4,098.90	27.39	-35.06	-27.39	0.00	0.00	0.00	
4,200.00	0.00	0.00	4,198.90	27.39	-35.06	-27.39	0.00	0.00	0.00	
4,300.00	0.00	0.00	4,298.90	27.39	-35.06	-27.39	0.00	0.00	0.00	
4,400.00	0.00	0.00	4,398.90	27.39	-35.06	-27.39	0.00	0.00	0.00	
4,500.00	0.00	0.00	4,498.90	27.39	-35.06	-27.39	0.00	0.00	0.00	
4,600.00	0.00	0.00	4,598.90	27.39	-35.06	-27.39	0.00	0.00	0.00	
4,700.00	0.00	0.00	4,698.90	27.39	-35.06	-27.39	0.00	0.00	0.00	
4,800.00	0.00	0.00	4,798.90	27.39	-35.06	-27.39	0.00	0.00	0.00	
4,900.00	0.00	0.00	4,898.90	27.39	-35.06	-27.39	0.00	0.00	0.00	
5,001.10	0.00	0.00	5,000.00	27.39	-35.06	-27.39	0.00	0.00	0.00	
5,100.00	1.98	310.75	5,098.88	28.50	-36.35	-28.50	2.00	2.00	-49.79	



Planning Report

Kaiser-Francis Oil Company

Database:	1 - EDM Production	Local Co-ordinate Reference:	Well BELL LAKE UNIT SOUTH 702H
Company:	KAISER FRANCIS OIL CO.	TVD Reference:	WELL @ 3627.80usft (Original Well Elev)
Project:	LEA COUNTY, N.M. BLUS	MD Reference:	WELL @ 3627.80usft (Original Well Elev)
Site:	SEC 1-T24S-R33E	North Reference:	Grid
Well:	BELL LAKE UNIT SOUTH 702H	Survey Calculation Method:	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	Plan 1		

Planned Survey										
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)	
5,200.00	3.98	310.75	5,198.74	31.89	-40.29	-31.89	2.00	2.00	0.00	
5,300.00	5.98	310.75	5,298.36	37.56	-46.86	-37.56	2.00	2.00	0.00	
5,400.00	7.98	310.75	5,397.62	45.49	-56.06	-45.49	2.00	2.00	0.00	
5,500.00	9.98	310.75	5,496.39	55.68	-67.88	-55.68	2.00	2.00	0.00	
5,600.00	11.98	310.75	5,594.55	68.11	-82.31	-68.11	2.00	2.00	0.00	
5,700.00	13.98	310.75	5,691.99	82.77	-99.32	-82.77	2.00	2.00	0.00	
5,800.00	15.98	310.75	5,788.59	99.64	-118.90	-99.64	2.00	2.00	0.00	
5,827.92	16.54	310.75	5,815.39	104.74	-124.82	-104.74	2.00	2.00	0.00	
5,900.00	16.54	310.75	5,884.49	118.13	-140.36	-118.13	0.00	0.00	0.00	
6,000.00	16.54	310.75	5,980.36	136.71	-161.92	-136.71	0.00	0.00	0.00	
6,100.00	16.54	310.75	6,076.22	155.29	-183.48	-155.29	0.00	0.00	0.00	
6,200.00	16.54	310.75	6,172.08	173.87	-205.04	-173.87	0.00	0.00	0.00	
6,300.00	16.54	310.75	6,267.95	192.45	-226.60	-192.45	0.00	0.00	0.00	
6,400.00	16.54	310.75	6,363.81	211.03	-248.16	-211.03	0.00	0.00	0.00	
6,500.00	16.54	310.75	6,459.67	229.61	-269.73	-229.61	0.00	0.00	0.00	
6,600.00	16.54	310.75	6,555.54	248.20	-291.29	-248.20	0.00	0.00	0.00	
6,700.00	16.54	310.75	6,651.40	266.78	-312.85	-266.78	0.00	0.00	0.00	
6,800.00	16.54	310.75	6,747.27	285.36	-334.41	-285.36	0.00	0.00	0.00	
6,900.00	16.54	310.75	6,843.13	303.94	-355.97	-303.94	0.00	0.00	0.00	
7,000.00	16.54	310.75	6,938.99	322.52	-377.53	-322.52	0.00	0.00	0.00	
7,100.00	16.54	310.75	7,034.86	341.10	-399.09	-341.10	0.00	0.00	0.00	
7,200.00	16.54	310.75	7,130.72	359.68	-420.65	-359.68	0.00	0.00	0.00	
7,300.00	16.54	310.75	7,226.59	378.26	-442.22	-378.26	0.00	0.00	0.00	
7,400.00	16.54	310.75	7,322.45	396.84	-463.78	-396.84	0.00	0.00	0.00	
7,500.00	16.54	310.75	7,418.31	415.42	-485.34	-415.42	0.00	0.00	0.00	
7,600.00	16.54	310.75	7,514.18	434.00	-506.90	-434.00	0.00	0.00	0.00	
7,673.47	16.54	310.75	7,584.61	447.65	-522.74	-447.65	0.00	0.00	0.00	
7,700.00	16.01	310.75	7,610.08	452.50	-528.37	-452.50	2.00	-2.00	0.00	
7,800.00	14.01	310.75	7,706.66	469.40	-547.98	-469.40	2.00	-2.00	0.00	
7,900.00	12.01	310.75	7,804.09	484.09	-565.03	-484.09	2.00	-2.00	0.00	
8,000.00	10.01	310.75	7,902.25	496.56	-579.49	-496.56	2.00	-2.00	0.00	
8,100.00	8.01	310.75	8,001.01	506.77	-591.35	-506.77	2.00	-2.00	0.00	
8,200.00	6.01	310.75	8,100.26	514.74	-600.59	-514.74	2.00	-2.00	0.00	
8,300.00	4.01	310.75	8,199.87	520.43	-607.20	-520.43	2.00	-2.00	0.00	
8,400.00	2.01	310.75	8,299.73	523.85	-611.17	-523.85	2.00	-2.00	0.00	
8,500.29	0.00	0.00	8,400.00	525.00	-612.50	-525.00	2.00	-2.00	0.00	
8,600.00	0.00	0.00	8,499.71	525.00	-612.50	-525.00	0.00	0.00	0.00	
8,700.00	0.00	0.00	8,599.71	525.00	-612.50	-525.00	0.00	0.00	0.00	
8,800.00	0.00	0.00	8,699.71	525.00	-612.50	-525.00	0.00	0.00	0.00	
8,900.00	0.00	0.00	8,799.71	525.00	-612.50	-525.00	0.00	0.00	0.00	
9,000.00	0.00	0.00	8,899.71	525.00	-612.50	-525.00	0.00	0.00	0.00	
9,100.00	0.00	0.00	8,999.71	525.00	-612.50	-525.00	0.00	0.00	0.00	
9,200.00	0.00	0.00	9,099.71	525.00	-612.50	-525.00	0.00	0.00	0.00	
9,300.00	0.00	0.00	9,199.71	525.00	-612.50	-525.00	0.00	0.00	0.00	
9,352.33	0.00	0.00	9,252.04	525.00	-612.50	-525.00	0.00	0.00	0.00	
9,400.00	4.77	182.80	9,299.65	523.02	-612.60	-523.02	10.00	10.00	0.00	
9,450.00	9.77	182.80	9,349.24	516.71	-612.91	-516.71	10.00	10.00	0.00	
9,500.00	14.77	182.80	9,398.08	506.10	-613.42	-506.10	10.00	10.00	0.00	
9,550.00	19.77	182.80	9,445.81	491.28	-614.15	-491.28	10.00	10.00	0.00	
9,600.00	24.77	182.80	9,492.07	472.36	-615.07	-472.36	10.00	10.00	0.00	
9,650.00	29.77	182.80	9,536.50	449.49	-616.19	-449.49	10.00	10.00	0.00	
9,700.00	34.77	182.80	9,578.76	422.84	-617.50	-422.84	10.00	10.00	0.00	
9,750.00	39.77	182.80	9,618.54	392.61	-618.98	-392.61	10.00	10.00	0.00	
9,800.00	44.77	182.80	9,655.53	359.03	-620.62	-359.03	10.00	10.00	0.00	



Planning Report

Kaiser-Francis Oil Company

Database:	1 - EDM Production	Local Co-ordinate Reference:	Well BELL LAKE UNIT SOUTH 702H
Company:	KAISER FRANCIS OIL CO.	TVD Reference:	WELL @ 3627.80usft (Original Well Elev)
Project:	LEA COUNTY, N.M. BLUS	MD Reference:	WELL @ 3627.80usft (Original Well Elev)
Site:	SEC 1-T24S-R33E	North Reference:	Grid
Well:	BELL LAKE UNIT SOUTH 702H	Survey Calculation Method:	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	Plan 1		

Planned Survey									
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
9,850.00	49.77	182.80	9,689.45	322.36	-622.41	-322.36	10.00	10.00	0.00
9,900.00	54.77	182.80	9,720.04	282.87	-624.34	-282.87	10.00	10.00	0.00
9,950.00	59.77	182.80	9,747.07	240.88	-626.40	-240.88	10.00	10.00	0.00
10,000.00	64.77	182.80	9,770.33	196.69	-628.56	-196.69	10.00	10.00	0.00
10,050.00	69.77	182.80	9,789.64	150.64	-630.81	-150.64	10.00	10.00	0.00
10,100.00	74.77	182.80	9,804.87	103.09	-633.13	-103.09	10.00	10.00	0.00
10,150.00	79.77	182.80	9,815.88	54.39	-635.52	-54.39	10.00	10.00	0.00
10,200.00	84.77	182.80	9,822.61	4.92	-637.94	-4.92	10.00	10.00	0.00
10,252.33	90.00	182.80	9,825.00	-47.27	-640.49	47.27	10.00	10.00	0.00
10,300.00	90.00	181.85	9,825.00	-94.90	-642.42	94.90	2.00	0.00	-2.00
10,400.00	90.00	179.85	9,825.00	-194.89	-643.90	194.89	2.00	0.00	-2.00
10,412.92	90.00	179.59	9,825.00	-207.81	-643.84	207.81	2.00	0.00	-2.00
10,500.00	90.00	179.59	9,825.00	-294.88	-643.21	294.88	0.00	0.00	0.00
10,600.00	90.00	179.59	9,825.00	-394.88	-642.49	394.88	0.00	0.00	0.00
10,700.00	90.00	179.59	9,825.00	-494.88	-641.77	494.88	0.00	0.00	0.00
10,800.00	90.00	179.59	9,825.00	-594.88	-641.05	594.88	0.00	0.00	0.00
10,900.00	90.00	179.59	9,825.00	-694.87	-640.33	694.87	0.00	0.00	0.00
11,000.00	90.00	179.59	9,825.00	-794.87	-639.62	794.87	0.00	0.00	0.00
11,100.00	90.00	179.59	9,825.00	-894.87	-638.90	894.87	0.00	0.00	0.00
11,200.00	90.00	179.59	9,825.00	-994.86	-638.18	994.86	0.00	0.00	0.00
11,300.00	90.00	179.59	9,825.00	-1,094.86	-637.46	1,094.86	0.00	0.00	0.00
11,400.00	90.00	179.59	9,825.00	-1,194.86	-636.74	1,194.86	0.00	0.00	0.00
11,500.00	90.00	179.59	9,825.00	-1,294.86	-636.02	1,294.86	0.00	0.00	0.00
11,600.00	90.00	179.59	9,825.00	-1,394.85	-635.30	1,394.85	0.00	0.00	0.00
11,700.00	90.00	179.59	9,825.00	-1,494.85	-634.58	1,494.85	0.00	0.00	0.00
11,800.00	90.00	179.59	9,825.00	-1,594.85	-633.87	1,594.85	0.00	0.00	0.00
11,900.00	90.00	179.59	9,825.00	-1,694.85	-633.15	1,694.85	0.00	0.00	0.00
12,000.00	90.00	179.59	9,825.00	-1,794.84	-632.43	1,794.84	0.00	0.00	0.00
12,100.00	90.00	179.59	9,825.00	-1,894.84	-631.71	1,894.84	0.00	0.00	0.00
12,200.00	90.00	179.59	9,825.00	-1,994.84	-630.99	1,994.84	0.00	0.00	0.00
12,300.00	90.00	179.59	9,825.00	-2,094.84	-630.27	2,094.84	0.00	0.00	0.00
12,400.00	90.00	179.59	9,825.00	-2,194.83	-629.55	2,194.83	0.00	0.00	0.00
12,500.00	90.00	179.59	9,825.00	-2,294.83	-628.83	2,294.83	0.00	0.00	0.00
12,600.00	90.00	179.59	9,825.00	-2,394.83	-628.12	2,394.83	0.00	0.00	0.00
12,700.00	90.00	179.59	9,825.00	-2,494.83	-627.40	2,494.83	0.00	0.00	0.00
12,800.00	90.00	179.59	9,825.00	-2,594.82	-626.68	2,594.82	0.00	0.00	0.00
12,900.00	90.00	179.59	9,825.00	-2,694.82	-625.96	2,694.82	0.00	0.00	0.00
13,000.00	90.00	179.59	9,825.00	-2,794.82	-625.24	2,794.82	0.00	0.00	0.00
13,100.00	90.00	179.59	9,825.00	-2,894.82	-624.52	2,894.82	0.00	0.00	0.00
13,200.00	90.00	179.59	9,825.00	-2,994.81	-623.80	2,994.81	0.00	0.00	0.00
13,300.00	90.00	179.59	9,825.00	-3,094.81	-623.08	3,094.81	0.00	0.00	0.00
13,400.00	90.00	179.59	9,825.00	-3,194.81	-622.37	3,194.81	0.00	0.00	0.00
13,500.00	90.00	179.59	9,825.00	-3,294.81	-621.65	3,294.81	0.00	0.00	0.00
13,600.00	90.00	179.59	9,825.00	-3,394.80	-620.93	3,394.80	0.00	0.00	0.00
13,700.00	90.00	179.59	9,825.00	-3,494.80	-620.21	3,494.80	0.00	0.00	0.00
13,800.00	90.00	179.59	9,825.00	-3,594.80	-619.49	3,594.80	0.00	0.00	0.00
13,900.00	90.00	179.59	9,825.00	-3,694.80	-618.77	3,694.80	0.00	0.00	0.00
14,000.00	90.00	179.59	9,825.00	-3,794.79	-618.05	3,794.79	0.00	0.00	0.00
14,100.00	90.00	179.59	9,825.00	-3,894.79	-617.33	3,894.79	0.00	0.00	0.00
14,200.00	90.00	179.59	9,825.00	-3,994.79	-616.62	3,994.79	0.00	0.00	0.00
14,300.00	90.00	179.59	9,825.00	-4,094.78	-615.90	4,094.78	0.00	0.00	0.00
14,400.00	90.00	179.59	9,825.00	-4,194.78	-615.18	4,194.78	0.00	0.00	0.00
14,500.00	90.00	179.59	9,825.00	-4,294.78	-614.46	4,294.78	0.00	0.00	0.00
14,600.00	90.00	179.59	9,825.00	-4,394.78	-613.74	4,394.78	0.00	0.00	0.00



Planning Report

Kaiser-Francis Oil Company


Database:	1 - EDM Production	Local Co-ordinate Reference:	Well BELL LAKE UNIT SOUTH 702H
Company:	KAISER FRANCIS OIL CO.	TVD Reference:	WELL @ 3627.80usft (Original Well Elev)
Project:	LEA COUNTY, N.M. BLUS	MD Reference:	WELL @ 3627.80usft (Original Well Elev)
Site:	SEC 1-T24S-R33E	North Reference:	Grid
Well:	BELL LAKE UNIT SOUTH 702H	Survey Calculation Method:	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	Plan 1		

Planned Survey										
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)	
14,700.00	90.00	179.59	9,825.00	-4,494.77	-613.02	4,494.77	0.00	0.00	0.00	
14,800.00	90.00	179.59	9,825.00	-4,594.77	-612.30	4,594.77	0.00	0.00	0.00	
14,900.00	90.00	179.59	9,825.00	-4,694.77	-611.59	4,694.77	0.00	0.00	0.00	
15,000.00	90.00	179.59	9,825.00	-4,794.77	-610.87	4,794.77	0.00	0.00	0.00	
15,100.00	90.00	179.59	9,825.00	-4,894.76	-610.15	4,894.76	0.00	0.00	0.00	
15,200.00	90.00	179.59	9,825.00	-4,994.76	-609.43	4,994.76	0.00	0.00	0.00	
15,300.00	90.00	179.59	9,825.00	-5,094.76	-608.71	5,094.76	0.00	0.00	0.00	
15,400.00	90.00	179.59	9,825.00	-5,194.76	-607.99	5,194.76	0.00	0.00	0.00	
15,500.00	90.00	179.59	9,825.00	-5,294.75	-607.27	5,294.75	0.00	0.00	0.00	
15,600.00	90.00	179.59	9,825.00	-5,394.75	-606.55	5,394.75	0.00	0.00	0.00	
15,700.00	90.00	179.59	9,825.00	-5,494.75	-605.84	5,494.75	0.00	0.00	0.00	
15,800.00	90.00	179.59	9,825.00	-5,594.75	-605.12	5,594.75	0.00	0.00	0.00	
15,900.00	90.00	179.59	9,825.00	-5,694.74	-604.40	5,694.74	0.00	0.00	0.00	
16,000.00	90.00	179.59	9,825.00	-5,794.74	-603.68	5,794.74	0.00	0.00	0.00	
16,100.00	90.00	179.59	9,825.00	-5,894.74	-602.96	5,894.74	0.00	0.00	0.00	
16,200.00	90.00	179.59	9,825.00	-5,994.74	-602.24	5,994.74	0.00	0.00	0.00	
16,300.00	90.00	179.59	9,825.00	-6,094.73	-601.52	6,094.73	0.00	0.00	0.00	
16,400.00	90.00	179.59	9,825.00	-6,194.73	-600.80	6,194.73	0.00	0.00	0.00	
16,500.00	90.00	179.59	9,825.00	-6,294.73	-600.09	6,294.73	0.00	0.00	0.00	
16,600.00	90.00	179.59	9,825.00	-6,394.73	-599.37	6,394.73	0.00	0.00	0.00	
16,700.00	90.00	179.59	9,825.00	-6,494.72	-598.65	6,494.72	0.00	0.00	0.00	
16,800.00	90.00	179.59	9,825.00	-6,594.72	-597.93	6,594.72	0.00	0.00	0.00	
16,900.00	90.00	179.59	9,825.00	-6,694.72	-597.21	6,694.72	0.00	0.00	0.00	
17,000.00	90.00	179.59	9,825.00	-6,794.72	-596.49	6,794.72	0.00	0.00	0.00	
17,100.00	90.00	179.59	9,825.00	-6,894.71	-595.77	6,894.71	0.00	0.00	0.00	
17,200.00	90.00	179.59	9,825.00	-6,994.71	-595.05	6,994.71	0.00	0.00	0.00	
17,300.00	90.00	179.59	9,825.00	-7,094.71	-594.34	7,094.71	0.00	0.00	0.00	
17,400.00	90.00	179.59	9,825.00	-7,194.70	-593.62	7,194.70	0.00	0.00	0.00	
17,500.00	90.00	179.59	9,825.00	-7,294.70	-592.90	7,294.70	0.00	0.00	0.00	
17,600.00	90.00	179.59	9,825.00	-7,394.70	-592.18	7,394.70	0.00	0.00	0.00	
17,700.00	90.00	179.59	9,825.00	-7,494.70	-591.46	7,494.70	0.00	0.00	0.00	
17,800.00	90.00	179.59	9,825.00	-7,594.69	-590.74	7,594.69	0.00	0.00	0.00	
17,900.00	90.00	179.59	9,825.00	-7,694.69	-590.02	7,694.69	0.00	0.00	0.00	
18,000.00	90.00	179.59	9,825.00	-7,794.69	-589.30	7,794.69	0.00	0.00	0.00	
18,100.00	90.00	179.59	9,825.00	-7,894.69	-588.59	7,894.69	0.00	0.00	0.00	
18,154.70	90.00	179.59	9,825.00	-7,949.38	-588.19	7,949.38	0.00	0.00	0.00	

Design Targets										
Target Name	Dip Angle (°)	Dip Dir. (°)	TVD (usft)	+N/-S (usft)	+E/-W (usft)	Northing (usft)	Easting (usft)	Latitude	Longitude	
BLUS 702H FTP (2480' - hit/miss target - Shape - Point	0.00	0.00	9,825.00	24.40	-650.02	454,535.86	789,754.29	32.24703955	-103.52980749	
- plan misses target center by 13.74usft at 10181.62usft MD (9820.64 TVD, 23.17 N, -637.04 E)										
BLUS 702H LTP (100' F: - plan hits target center - Point	0.00	0.00	9,825.00	-7,949.38	-588.19	446,562.08	789,816.11	32.22512129	-103.52980047	



Planning Report



Database:	1 - EDM Production	Local Co-ordinate Reference:	Well BELL LAKE UNIT SOUTH 702H
Company:	KAISER FRANCIS OIL CO.	TVD Reference:	WELL @ 3627.80usft (Original Well Elev)
Project:	LEA COUNTY, N.M. BLUS	MD Reference:	WELL @ 3627.80usft (Original Well Elev)
Site:	SEC 1-T24S-R33E	North Reference:	Grid
Well:	BELL LAKE UNIT SOUTH 702H	Survey Calculation Method:	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	Plan 1		

Casing Points				
Measured Depth (usft)	Vertical Depth (usft)	Name	Casing Diameter (")	Hole Diameter (")
18,177.74		20" Casing	20	24

**KAISER-FRANCIS OIL COMPANY
HYDROGEN SULFIDE (H₂S) CONTINGENCY PLAN
FOR DRILLING/COMPLETION WORKOVER/FACILITY**

**BLUS 102H, 103H, 104H, 702H, 603H, 604H
SECTION 1 -T24S-R33E
LEA COUNTY, NM**

This well/facility is not expected to have H₂S, but due to the sensitive location, the following is submitted as requested.

TABLE OF CONTENTS

Emergency Response Activation and General Responsibilities	3
Individual Responsibilities During An H ₂ S Release	4
Procedure For Igniting An Uncontrollable Condition	5
Emergency Phone Numbers	6
Protection Of The General Public/Roe	7
Characteristics Of H ₂ S And SO ₂	8
Training	8
Public Relations	8
Maps	

EMERGENCY RESPONSE ACTIVATION AND GENERAL RESPONSIBILITIES

Activation of the Emergency Action Plan

In the event of any emergency situation, all personnel on location should first ensure that the following items are initiated. After that, they should refer to the appropriate Specific Emergency Guidance sections below for further responsibilities:

1. Notify the senior ranking contract representative on site.
2. Notify Kaiser-Francis representative in charge.
3. Notify civil authorities if the Kaiser-Francis Representative cannot be contacted and the situation dictates.
4. Perform rescue and first aid as required (without jeopardizing additional personnel).

General Responsibilities

In the event of an H₂S emergency, the following plan will be initiated.

- 1) All personnel will immediately evacuate to an up-wind and if possible up-hill "safe area".
- 2) If for any reason a person must enter the hazardous area, they must wear a SCBA (Self contained breathing apparatus).
- 3) Always use the "buddy system".
- 4) Isolate the well/problem if possible.
- 5) Account for all personnel
- 6) Display the proper colors, warning all unsuspecting personnel of the danger at hand
- 7) Contact the Company personnel as soon as possible if not at the location. (use the enclosed call list as instructed)

At this point the company representative will evaluate the situation and coordinate the necessary duties to bring the situation under control, and if necessary, the notification of emergency response agencies and residents.

INDIVIDUAL RESPONSIBILITIES DURING AN H₂S RELEASE

The following procedures and responsibilities will be implemented on activation of the H₂S siren and lights.

All Personnel:

1. On alarm, don escape unit (if available) and report to upwind briefing area.

Rig Manager/Tool Pusher:

1. Check that all personnel are accounted for and their condition.
2. Administer or arrange for first aid treatment, and/or call EMTs as needed.
3. Identify two people best suited to secure well and perform rescue, and instruct them to don SCBA.
4. Notify Contract management and Kaiser-Francis Representative.
5. Remain at the briefing area, assess and monitor personnel and overall situation for hazards or conditions that might warrant a change in the action plan.

Two People Responsible for Shut-in and Rescue:

1. Don SCBA and acquire tools to secure well and perform rescue, i.e., wrenches, retrieval ropes, etc.
2. Utilize the buddy system to secure well and perform rescue(s).
3. Return to the briefing area and stand by for further instructions.

All Other Personnel:

1. Isolate the area and prevent entry by other persons into the 100 ppm ROE. Additionally the first responder(s) must evacuate any public places encompassed by the 100 ppm ROE. First responder(s) must take care not to injure themselves during this operation. Company and/or local officials must be contacted to aid in this operation. Evacuation of the public should be beyond the 100 ppm ROE.

Kaiser-Francis Oil Company Representative:

1. Remain at the briefing area, assess and monitor personnel and overall situation for hazards or conditions that might warrant a change in the action plan.
2. Notify company management or Local Incident Commander, and Police, Fire Department, or other local emergency services as required.

PROCEDURE FOR IGNITING AN UNCONTROLLABLE CONDITION:

Should control of the well be considered lost and ignition considered, take care to protect against exposure to Sulfur Dioxide (SO₂). Intentional ignition must be coordinated with the NMOCD and local officials. Additionally the NM State Police shall be the Incident Command of any major release.

The decision to ignite a well should be a last resort and one if not both of the following pertain.

- 1) Human life and/or property are in danger.
- 2) There is no hope of bringing the situation under control with the prevailing conditions at the site.

INSTRUCTIONS FOR IGNITION:

- 1) Two people are required. They must be equipped with positive pressure; self contained breathing apparatus and a "D"-ring style, full body, OSHA approved safety harness. Non-flammable rope will be attached.
- 2) One of the people will be a qualified safety person who will test the atmosphere for H₂S, Oxygen, & LFL. The other person will be the company supervisor; he is responsible for igniting the well.
- 3) Ignite up-wind from a distance no closer than necessary. Make sure that where you ignite from has the maximum escape avenue available. A 25mm flare gun shall be used, with a +/-500' range to ignite the gas.
- 4) Prior to ignition, make a final check for combustible gases.
- 5) Following ignition, continue with the emergency actions & procedures as before.

CONTACTING AUTHORITIES

Kaiser-Francis personnel must liaison with local and state agencies to ensure a proper response to a major release. Additionally, the OCD must be notified of the release as soon as possible but no later than 4 hours. Agencies will ask for information such as type and volume of release, wind direction, location of release, etc. Be prepared with all information available. The following call list of essential and potential responders has been prepared for use during a release. This response plan must be in coordination with the State of New Mexico's 'Hazardous Materials Emergency Response Plan' (HMER).

EMERGENCY CALL LIST: (Start and continue until ONE of these people have been reached)

	<u>OFFICE</u>	<u>MOBILE</u>
Kaiser-Francis Oil Co.	918/494-0000	
Jeremy Parent	575-964-6256	580-504-2593
David Zerger	918/491-4350	918/557-6708
Aaron Daniels	918-491-4352	918-891-5199
Robert Sanford	918/491-4201	918/770-2682

EMERGENCY RESPONSE NUMBERS: Lea County, New Mexico

State Police – Artesia	575/748-9718
State Police – Hobbs	575/392-5580
State Police – Carlsbad	575/885-3138
Lea County Sheriff - Lovington	575/396-3611
Local Emergency Planning Center – Lea County	575/396-8607
Local Emergency Planning Center – Eddy County	575/885-3581
Fire Fighting, Rescue & Ambulance – Carlsbad	911 or 575/885-3125
Fire Fighting, Rescue & Ambulance – Hobbs	911 or 575/397-9308
Fire Fighting – Jal Volunteer Fire Department	911 or 505/395-2221
New Mexico Oil & Gas Commission – Artesia	575/748-1283
New Mexico Oil & Gas Commission – Hobbs	575/393-6161
Air Medical Transport Services – Hobbs	800/550-1025
Med Flight Air Ambulance – Albuquerque	505/842-4433
Angel MedFlight	844/553-9033
Cudd	800-990-2833
Wild Well Control	281-784-4700

PROTECTION OF THE GENERAL PUBLIC/ROE:

In the event of a release with a concentration greater than 100 ppm H₂S, the ROE (Radius of Exposure) calculations will be done to determine if the following conditions have been met:

- Does the 100 ppm ROE include any public area (any place not associated with this site)
- Does the 500 ppm ROE include any public road (any road which the general public may travel)
- Is the 100 ppm ROE equal to or greater than 3000 feet

If any one of these conditions have been met then the Contingency Plan will be implemented. The following shows how to calculate the radius of exposure and an example.

Calculation for the 100 ppm ROE:

$$X = [(1.589)(\text{concentration})(Q)]^{(0.6258)}$$

(H₂S concentrations in decimal form)

10,000 ppm +=1.+

1,000 ppm +=.1+

100 ppm +=.01+

10 ppm +=.001+

Calculation for the 500 ppm ROE:

$$X+[(0.4546)(\text{concentration})(Q)]^{(.06258)}$$

EXAMPLE: If a well/facility has been determined to have 150 ppm H₂S in the gas mixture and the well/facility is producing at a gas rate of 200 MCFPD then:

ROE for 100 PPM $X=[(1.589)(.0150)(200)]^{(0.6258)}$

$X=2.65'$

ROE for 500 PPM $X=[(.4546)(.0150)(200)]^{(0.6258)}$

$X=1.2'$

(These calculations will be forwarded to the appropriate District NMOCD office when applicable.)

PUBLIC EVACUATION PLAN:

(When the supervisor has determined that the General Public will be involved, the following plan will be implemented)

- 1) Notification of the emergency response agencies of the hazardous condition and Implement evacuation procedures.
- 2) A trained person in H₂S safety, shall monitor with detection equipment the H₂S Concentration, wind and area of exposure (ROE). This person will determine the outer perimeter of the hazardous area. The extent of the evacuation area will be determined from the data being collected. Monitoring shall continue until the situation has been resolved. **(All monitoring equipment will be UL approved, for use in class I groups A,B,C & D, Division I, hazardous locations. All monitors will have a minimum capability of measuring H₂S, oxygen, and flammable values.)**
- 3) Law enforcement shall be notified to set up necessary barriers and maintain such for the duration of the situation as well as aid in the evacuation procedure.
- 4) The company supervising personnel shall stay in communication with all agencies through out the duration of the situation and inform such agencies when the situation has been contained and the effected area(s) is safe to enter.

CHARACTERISTICS OF H₂S AND SO₂

Common Name	Chemical Formula	Specific Gravity	Threshold Limit	Hazardous Limit	Lethal Concentration
Hydrogen Sulfide	H ₂ S	1.189 Air = 1	10 ppm	100 ppm	600 ppm
Sulfur Dioxide	SO ₂	2.21 Air = 1	2 ppm	N/A	1000 ppm

TRAINING:

All responders must have training in the detection of H₂S measures for protection against the gas, equipment used for protection and emergency response. Weekly drills by all crews will be conducted and recorded in the IADC daily log. Additionally, responders must be equipped with H₂S monitors at all times.

PUBLIC RELATIONS

Kaiser-Francis recognizes that the news media have a legitimate interest in incidents at Kaiser-Francis facilities that could affect the public. It is to the company's benefit to cooperate with the news media when incidents occur because these media are our best liaison with the public.

Our objective is to see that all reports of any emergency are factual and represent the company's position fairly and accurately. Cooperation with news media representatives is the most reliable guarantee that this objective will be met.

All contract and Kaiser-Francis employees are instructed **NOT** to make any statement to the media concerning the emergency incident. If a media representative contacts any employee, they should refer them to the designated Emergency Command Center where they should contact the Incident Commander or his designated relief for any information concerning the incident.

Well Name: BELL LAKE UNIT SOUTH	Well Location: T24S / R33E / SEC 1 / SEW / 32.2469597 / -103.5277029	County or Parish/State: LEA / NM
Well Number: 702H	Type of Well: OIL WELL	Allottee or Tribe Name:
Lease Number: NMLC063993	Unit or CA Name: BELL LAKE-INT. BONE SPRING FMN	Unit or CA Number: NMNM68292H
US Well Number:	Operator: KAISER FRANCIS OIL COMPANY	

Notice of Intent

Sundry ID: 2884770

Type of Submission: Notice of Intent

Type of Action: APD Change

Date Sundry Submitted: 12/02/2025

Time Sundry Submitted: 09:03

Date proposed operation will begin: 12/02/2025

Procedure Description: Kaiser-Francis Oil Company requests to rename APD ID 10400106497 to adhere to NMOCD naming conventions. Current Well Name: Bell Lake Unit South 702H Requested Well Name: Bell Lake South Unit 702H

NOI Attachments

Procedure Description

NMOCD_C_102_Name_Change_Plat_BLSU_702H_20251202090324.pdf

Well Name: BELL LAKE UNIT SOUTH

Well Location: T24S / R33E / SEC 1 /
SENW / 32.2469597 / -103.5277029

County or Parish/State: LEA /
NM

Well Number: 702H

Type of Well: OIL WELL

Allottee or Tribe Name:

Lease Number: NMLC063993

Unit or CA Name: BELL LAKE-INT.
BONE SPRING FMN

Unit or CA Number:
NMNM68292H

US Well Number:

Operator: KAISER FRANCIS OIL
COMPANY

Operator

I certify that the foregoing is true and correct. Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction. Electronic submission of Sundry Notices through this system satisfies regulations requiring a

Operator Electronic Signature: CHRISTINA OPFER

Signed on: DEC 02, 2025 09:03 AM

Name: KAISER FRANCIS OIL COMPANY

Title: Regulatory Manager

Street Address: 6733 S YALE AVENUE

City: TULSA

State: OK

Phone: (918) 491-4468

Email address: CHRISTINAO@KFOC.NET

Field

Representative Name:

Street Address:

City:

State:

Zip:

Phone:

Email address:

BLM Point of Contact

BLM POC Name: TENILLE C MOLINA

BLM POC Title: Land Law Examiner

BLM POC Phone: 5752342224

BLM POC Email Address: TCMOLINA@BLM.GOV

Disposition: Approved

Disposition Date: 12/03/2025

Signature: For: Cody Layton Assistant Field Manager

Form 3160-5
(October 2024)

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB No. 1004-0220
Expires: October 31, 2027

SUNDRY NOTICES AND REPORTS ON WELLS
Do not use this form for proposals to drill or to re-enter an abandoned well. Use Form 3160-3 (APD) for such proposals.

5. Lease Serial No. **NMLC063993**

6. If Indian, Allottee or Tribe Name

SUBMIT IN TRIPLICATE - Other instructions on page 2

1. Type of Well
 Oil Well Gas Well Other

7. If Unit of CA/Agreement, Name and/or No.
BELL LAKE-INT. BONE SPRING FMN/NMNM68292H

8. Well Name and No.
BELL LAKE UNIT SOUTH/702H

2. Name of Operator **KAISER FRANCIS OIL COMPANY**

9. API Well No.

3a. Address **6733 S. Yale Ave., Tulsa, OK 74121**

3b. Phone No. (include area code)
(918) 491-0000

10. Field and Pool or Exploratory Area
BELL LAKE/BONE SPRING, SOUTH

4. Location of Well (Footage, Sec., T.,R.,M., or Survey Description)
SEC 1/T24S/R33E/NMP

11. Country or Parish, State
LEA/NM

12. CHECK THE APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input checked="" type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Hydraulic Fracturing	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input type="checkbox"/> Other
	<input checked="" type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandon	<input type="checkbox"/> Temporarily Abandon	
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	

13. Describe Proposed or Completed Operation: Clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recompleat horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be perfonned or provide the Bond No. on file with BLM/BIA. Required subsequent reports must be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompleat in a new interval, a Form 3160-4 must be filed once testing has been completed. Final Abandonment Notices must be filed only after all requirements, including reclamation, have been completed and the operator has detennined that the site is ready for final inspection.)

Kaiser-Francis Oil Company requests to rename APD ID 10400106497 to adhere to NMOCD naming conventions.

Current Well Name: Bell Lake Unit South 702H

Requested Well Name: Bell Lake South Unit 702H

14. I hereby certify that the foregoing is true and correct. Name (Printed/Typed)
CHRISTINA OPFER / Ph: (918) 491-4468

Title **Regulatory Manager**

Signature (Electronic Submission)

Date **12/02/2025**

THE SPACE FOR FEDERAL OR STATE OFFICE USE

Approved by
TENILLE C MOLINA / Ph: (575) 234-2224 / Approved

Title **Land Law Examiner**

Date **12/03/2025**

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Office **CARLSBAD**

Title 18 U.S.C Section 1001 and Title 43 U.S.C Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Instructions on page 2)

GENERAL INSTRUCTIONS

This form is designed for submitting proposals to perform certain well operations and reports of such operations when completed as indicated on Federal and Indian lands pursuant to applicable Federal law and regulations. Any necessary special instructions concerning the use of this form and the number of copies to be submitted, particularly with regard to local area or regional procedures and practices, are either shown below, will be issued by or may be obtained from the local Federal office.

SPECIFIC INSTRUCTIONS

Item 4 - Locations on Federal or Indian land should be described in accordance with Federal requirements. Consult the local Federal office for specific instructions.

Item 13: Proposals to abandon a well and subsequent reports of abandonment should include such special information as is required by the local Federal office. In addition, such proposals and reports should include reasons for the abandonment; data on any former or present productive zones or other zones with present significant fluid contents not sealed off by cement or otherwise; depths (top and bottom) and method of placement of cement plugs; mud or other material placed below, between and above plugs; amount, size, method of parting of any casing, liner or tubing pulled and the depth to the top of any tubing left in the hole; method of closing top of well and date well site conditioned for final inspection looking for approval of the abandonment. If the proposal will involve **hydraulic fracturing operations**, you must comply with 43 CFR 3162.3-3, including providing information about the protection of usable water. Operators should provide the best available information about all formations containing water and their depths. This information could include data and interpretation of resistivity logs run on nearby wells. Information may also be obtained from state or tribal regulatory agencies and from local BLM offices.

NOTICES

The privacy Act of 1974 and the regulation in 43 CFR 2.48(d) provide that you be furnished the following information in connection with information required by this application.

AUTHORITY: 30 U.S.C. 181 et seq., 351 et seq., 25 U.S.C. 396; 43 CFR 3160.

PRINCIPAL PURPOSE: The information is used to: (1) Evaluate, when appropriate, approve applications, and report completion of subsequent well operations, on a Federal or Indian lease; and (2) document for administrative use, information for the management, disposal and use of National Resource lands and resources, such as: (a) evaluating the equipment and procedures to be used during a proposed subsequent well operation and reviewing the completed well operations for compliance with the approved plan; (b) requesting and granting approval to perform those actions covered by 43 CFR 3162.3-2, 3162.3-3, and 3162.3-4; (c) reporting the beginning or resumption of production, as required by 43 CFR 3162.4-1(c) and (d) analyzing future applications to drill or modify operations in light of data obtained and methods used.

ROUTINE USES: Information from the record and/or the record will be transferred to appropriate Federal, State, local or foreign agencies, when relevant to civil, criminal or regulatory investigations or prosecutions in connection with congressional inquiries or to consumer reporting agencies to facilitate collection of debts owed the Government.

EFFECT OF NOT PROVIDING THE INFORMATION: Filing of this notice and report and disclosure of the information is mandatory for those subsequent well operations specified in 43 CFR 3162.3-2, 3162.3-3, 3162.3-4.

The Paperwork Reduction Act of 1995 requires us to inform you that:

The BLM collects this information to evaluate proposed and/or completed subsequent well operations on Federal or Indian oil and gas leases.

Response to this request is mandatory.

The BLM would like you to know that you do not have to respond to this or any other Federal agency-sponsored information collection unless it displays a currently valid OMB control number.

BURDEN HOURS STATEMENT: Public reporting burden for this form is estimated to average 8 hours per response, including the time for reviewing instructions, gathering and maintaining data, and completing and reviewing the form. Direct comments regarding the burden estimate or any other aspect of this form to U.S. Department of the Interior, Bureau of Land Management (1004-0137), Bureau Information Collection Clearance Officer (WO-630), 1849 C St., N.W., Mail Stop 401 LS, Washington, D.C. 20240


Additional Information

Location of Well

0. SHL: SENW / 2508 FNL / 2137 FWL / TWSP: 24S / RANGE: 33E / SECTION: 1 / LAT: 32.2469597 / LONG: -103.5277029 (TVD: 0 feet, MD: 0 feet)
PPP: NESW / 2450 FSL / 1486 FWL / TWSP: 24S / RANGE: 33E / SECTION: 1 / LAT: 32.2461109 / LONG: -103.5298097 (TVD: 9820 feet, MD: 10181 feet)
PPP: NESW / 2640 FNL / 1488 FWL / TWSP: 24S / RANGE: 33E / SECTION: 12 / LAT: 32.2321185 / LONG: -103.5298019 (TVD: 9825 feet, MD: 15608 feet)
PPP: NENW / 0 FNL / 1492 FWL / TWSP: 24S / RANGE: 33E / SECTION: 12 / LAT: 32.2393765 / LONG: -103.5298059 (TVD: 9825 feet, MD: 12968 feet)
BHL: SESW / 25 FSL / 1486 FWL / TWSP: 24S / RANGE: 33E / SECTION: 12 / LAT: 32.2249138 / LONG: -103.5297976 (TVD: 9825 feet, MD: 18514 feet)

CONFIDENTIAL

C-102 Submit Electronically Via OCD Permitting	State of New Mexico Energy, Minerals & Natural Resources Department OIL CONSERVATION DIVISION	Revised July 9, 2024
		Submittal Type: <input type="checkbox"/> Initial Submittal <input checked="" type="checkbox"/> Amended Report <input type="checkbox"/> As Drilled
Property Name and Well Number BELL LAKE SOUTH UNIT 702H		



T-24-S, R-33-E
 SECTION 5
 LOT 1 - 39.94 ACRES
 LOT 2 - 39.83 ACRES
 LOT 3 - 39.71 ACRES
 LOT 4 - 39.60 ACRES

SURVEYORS CERTIFICATION
 I hereby certify that the well location shown on this plat was plotted from field notes of actual surveys made by me or under my supervision, and that the same is true and correct to the best of my belief.
 07/22/2025

Date of Survey
 Signature and Seal of Professional Surveyor:



C:\SURVEY\KANSAS_FRANCIS\BELL_LAKE_SOUTH_UNIT_702H\PRODUCTION\BELL_LAKE_SOUTH_UNIT_702H\NATURAL_RESOURCE\MAP205_10228.PDF

Sante Fe Main Office
Phone: (505) 476-3441

General Information
Phone: (505) 629-6116

Online Phone Directory
<https://www.emnrd.nm.gov/ocd/contact-us>

State of New Mexico
Energy, Minerals and Natural Resources
Oil Conservation Division
1220 S. St Francis Dr.
Santa Fe, NM 87505

ACKNOWLEDGMENTS

Action 534531

ACKNOWLEDGMENTS

Operator: KAISER-FRANCIS OIL CO PO Box 21468 Tulsa, OK 741211468	OGRID: 12361
	Action Number: 534531
	Action Type: [C-101] BLM - Federal/Indian Land Lease (Form 3160-3)

ACKNOWLEDGMENTS

<input checked="" type="checkbox"/>	I hereby certify that no additives containing PFAS chemicals will be added to the completion or recompletion of this well.
-------------------------------------	--

Sante Fe Main Office
Phone: (505) 476-3441

General Information
Phone: (505) 629-6116

Online Phone Directory
<https://www.emnrd.nm.gov/oecd/contact-us>

**State of New Mexico
Energy, Minerals and Natural Resources
Oil Conservation Division
1220 S. St Francis Dr.
Santa Fe, NM 87505**

CONDITIONS

Action 534531

CONDITIONS

Operator: KAISER-FRANCIS OIL CO PO Box 21468 Tulsa, OK 741211468	OGRID: 12361
	Action Number: 534531
	Action Type: [C-101] BLM - Federal/Indian Land Lease (Form 3160-3)

CONDITIONS

Created By	Condition	Condition Date
christinaopf	Cement is required to circulate on both surface and intermediate1 strings of casing.	12/12/2025
jeffrey.harrison	If the method of isolation was not by circulation, a CBL must be performed; if strata isolation is not achieved, then remediation will be required before further operations.	3/4/2026
jeffrey.harrison	Cement must be in place for at least 8 hours and achieve a minimum compressive strength of 500 psi before performing further operations on the well.	3/4/2026
jeffrey.harrison	File As Drilled C-102 and a directional Survey with C-104 completion packet.	3/4/2026
jeffrey.harrison	Notify the OCD 24 hours prior to casing & cement.	3/4/2026
jeffrey.harrison	Once the well is spud, to prevent ground water contamination through whole or partial conduits from the surface, the operator shall drill without interruption through the fresh water zone or zones and shall immediately set in cement the water protection string.	3/4/2026
jeffrey.harrison	Oil base muds are not to be used until fresh water zones are cased and cemented providing isolation from the oil or diesel. This includes synthetic oils. Oil based mud, drilling fluids and solids must be contained in a steel closed loop system.	3/4/2026