

Irregular SECTION 7

TOWNSHIP 28N

RANGE 11W

5847 San Felipe Suite 3600
Houston, Texas 77057
Telephone: (713) 780-5000
Fax (713) 780-5273
Telex 9108813603

OIL CONSERVATION DIVISION
RECEIVED

'90 SEP 10 AM 9 43

August 22, 1990



State of New Mexico
Oil Conservation Division
P.O. Box 2088
Santa Fe, New Mexico 87504-2088

9/11/90

Copy sent to E. Busch

RE: Unorthodox Location, Administrative Approval Request
Gallegos Canyon Unit #516, ~~1814~~
NW 1/4 NW 1/4 Sec. 7 T28N R11W
San Juan County, New Mexico

Gentlemen:

BHP Petroleum respectfully requests that a non standard location be administratively approved to allow the GCU #516 well to be drilled 1745' FSL and 950' FWL to be completed in the Pictured Cliffs formation.

The non standard location is requested due to an irregular section. The proposed location can not be moved south to an orthodox location because of residential dwellings.

The subject location is immediately adjacent to the existing Amoco well location #138-E producing from the Dakota formation.

BHP Petroleum is the operator of all offsetting proration units.

Ernie Busch visited the subject location with J. C. Harris and myself on August 10, 1990 and concurred that the subject location was the most feasible.

For both economic and mechanical reasons BHP doesn't think that directionally drilling the proposed well to a standard location is feasible. Economically it is not feasible based on the extra expense of drilling a directional hole compared to the anticipated production. Our experience has shown that a rod pump will have to be installed to remove excess water from the well bore and a directionally drilled hole would greatly hinder or prohibit that.

Please do not hesitate to contact me if you have any questions.

Sincerely,

Chuck Williams *By [Signature]*

Chuck Williams
Field Services Administrator

Submit to Appropriate
District Office
State Lease - 6 copies
Fee Lease - 5 copies

State of New Mexico
Energy, Minerals and Natural Resources Department

Form C-101
Revised 1-1-89

OIL CONSERVATION DIVISION

P.O. Box 2088
Santa Fe, New Mexico 87504-2088

DISTRICT I
P.O. Box 1980, Hobbs, NM 88240

DISTRICT II
P.O. Drawer DD, Artesia, NM 88210

DISTRICT III
1000 Rio Brazos Rd., Aztec, NM 87410

API NO. (assigned by OCD on New Wells)

5. Indicate Type of Lease

STATE ☒ FEE ☐

6. State Oil & Gas Lease No.

B-10870-15

APPLICATION FOR PERMIT TO DRILL, DEEPEN, OR PLUG BACK

1a. Type of Work:

DRILL ☒ RE-ENTER ☐ DEEPEN ☐ PLUG BACK ☐

b. Type of Well:

OIL WELL ☐ GAS WELL ☒ OTHER ☐ SINGLE ZONE ☒ MULTIPLE ZONE ☐

7. Lease Name or Unit Agreement Name

Gallegos Canyon Unit

2. Name of Operator

BHP Petroleum (Americas) Inc.

8. Well No.

516

3. Address of Operator

5847 San Felipe Ste 3600 Houston TX 77057-3005

9. Pool name or Wildcat

W. Kutz Pictured Cliffs

4. Well Location

Unit Letter L : 1745 Feet From The South Line and 950' Feet From The West Line

Section 7 Township 28N Range 11N NMPM San Juan County

10. Proposed Depth
1511'

11. Formation
Pictured Cliffs

12. Rotary or C.T.
Rotary

13. Elevations (Show whether DF, RT, GR, etc.)

5426' GR

14. Kind & Status Plug. Bond

Blanket

15. Drilling Contractor

Unknown

16. Approx. Date Work will start

Fall 1990

17. PROPOSED CASING AND CEMENT PROGRAM *

SIZE OF HOLE	SIZE OF CASING	WEIGHT PER FOOT	SETTING DEPTH	SACKS OF CEMENT	EST. TOP
8 3/4"	7"	20#	± 130'	50 sx (57.5 cu.ft.)	Surface
6 1/4"	4 1/2"	10.5#	±1511'	191 sx (235 cu.ft.)	Surface

It is proposed to drill the subject well to 1511' with primary production anticipated in the Pictured Cliffs.

Estimated Formation Tops:

Ojo Alamo 196'
Kirtland 286'
Fruitland 1056'
Basal Fruitland Coal 1346'
Pictured Cliffs 1361'
T.D. 1511'

This is an unorthodox location due to irregular section. An unorthodox location request is being prepared for submission.

BOPE consist of 2000# Reagen Bladder type B.O.P., pipe rams & blind ram B.O.P.

IN ABOVE SPACE DESCRIBE PROPOSED PROGRAM: IF PROPOSAL IS TO DEEPEN OR PLUG BACK, GIVE DATA ON PRESENT PRODUCTIVE ZONE AND PROPOSED NEW PRODUCTIVE ZONE. GIVE BLOWOUT PREVENTER PROGRAM, IF ANY.

I hereby certify that the information above is true and complete to the best of my knowledge and belief.

SIGNATURE

Chuck Williams

TITLE

Field Services Administrator

DATE

7/26/90

TYPE OR PRINT NAME

(713) 780-5448

TELEPHONE NO.

(This space for State Use)

APPROVED BY

TITLE

DATE

CONDITIONS OF APPROVAL, IF ANY:

Submit to Appropriate
District Office
State Lease - 4 copies
Fee Lease - 3 copies

State of New Mexico
Energy, Minerals and Natural Resources Department

Form C-102
Revised 3-1-89

OIL CONSERVATION DIVISION

P.O. Box 2088

Santa Fe, New Mexico 87504-2088

DISTRICT I

P.O. Box 1980, Hobbs, NM 88240

DISTRICT II

P.O. Drawer DD, Artesia, NM 88210

DISTRICT III



1000 Rio Brazos Rd., Aztec, NM 87410

WELL LOCATION AND ACREAGE DEDICATION PLAT

All Distances must be from the outer boundaries of the section.

Operator BHP PETROLEUM (AMERICAS) INC.			Lease GALLEGOS CANYON UNIT		Well No. 516
Unit Letter L	Section 7	Township 28 N	Range 11 W	County San Juan	
Actual Footage Location of Well: 1745 feet from the South line and 950 feet from the West line					
Ground level Elev. 5426	Producing Formation Pictured Cliffs		Pool W. Kutz Pictured Cliffs	Dedicated Acreage: 132.99 Acres	

1. Outline the acreage dedicated to the subject well by colored pencil or hatchure marks on the plat below.
2. If more than one lease is dedicated to the well, outline each and identify the ownership thereof (both as to working interest and royalty).
3. If more than one lease of different ownership is dedicated to the well, have the interest of all owners been consolidated by communitization, unitization, force-pooling, etc.?
☐ Yes ☐ No If answer is "yes" type of consolidation _____
If answer is "no" list the owners and tract descriptions which have actually been consolidated. (Use reverse side of this form if necessary.)
No allowable will be assigned to the well until all interests have been consolidated (by communitization, unitization, forced-pooling, or otherwise) or until a non-standard unit, eliminating such interest, has been approved by the Division.



OPERATOR CERTIFICATION

I hereby certify that the information contained herein is true and complete to the best of my knowledge and belief.

Signature
Chuck Williams

Printed Name
Chuck Williams

Position
Field Services Administrator

Company
BHP Petroleum (Americas) Inc.

Date
7/26/90

SURVEYOR CERTIFICATION

I hereby certify that the well location shown on this plat was plotted from field notes of actual surveys made by me or under my supervision, and that the same is true and correct to the best of my knowledge and belief.

7-5-90

Date Surveyed
William E. Mahanke II

Signature & Seal of
Professional Surveyor

Certificate No.
#8466

BHP PETROLEUM (AMERICAS) INC.
GALLEGOS CANYON UNIT NO. 516
 1745' FSL & 950' FWL SECTION 7 T28N-R11W
 SAN JUAN COUNTY, NEW MEXICO
TEN POINT PROGRAM

1. **Surface Formation:** Nacimiento or valley fill

2 &

3. **Estimated Formation Tops:**

<u>Formation</u>	<u>Top</u>	<u>Expected Production</u>
Ojo Alamo	196	
Kirtland	286	
Fruitland	1056	
Basal Fruitland Coal	1346	Gas
Pictured Cliffs	1361	Gas
Total Depth	1511	

4. **Casing and Cementing Program:** A string of 7" 20# K-55 casing with ST&C couplings is to be set at $\pm 130'$ in an 8 $\frac{3}{4}"$ hole and cemented to the surface in a single stage with 50 sx Class 'H' cement (yield = $1.15 \text{ ft}^3/\text{sx}$) containing 3 % CaCl_2 and $\frac{1}{4}$ #/sx celloflake. Slurry volume assumes a 100 percent excess over calculated hole volume. Centralizers will be run on the bottom two joints as long as boulders are not encountered while drilling the surface hole. If boulders are encountered while drilling the surface hole, no centralizers will be run as it has been BHP P(A)'s experience centralizers have a tendency to knock off boulders and hang up the casing while running in the hole. Minimum clearance between collars and hole is 1.094". Prior to drilling out shoe, casing and BOPE will be tested to a minimum of 2000 psi. Safety factors utilized in the design of this casing string were: Burst = 1.1, Collapse = 1.125, and Tension = 1.8 or 100,000# overpull whichever was greater.

A production string of 4 $\frac{1}{2}"$ 10.5# K-55 casing with ST&C couplings will be run from the surface to total depth in a 6 $\frac{1}{4}"$ hole. This string will be cemented to the surface with a minimum of 141 sx of 50-50 pozmix containing 2 % gel, 0.5 % fluid loss additive and $\frac{1}{4}$ #/sx celloflake (yield = $1.26 \text{ ft}^3/\text{sx}$) followed by 50 sx of Class 'G' cement containing low fluid loss additives (yield = $1.15 \text{ ft}^3/\text{sx}$). Slurry volume assumes a 50 percent excess over calculated hole volume. Cement

volume is subject to change after review and recalculation of hole volume from the open hole calipers. Centralizers will be spaced such that a minimum of two are located above and two are located below the Basal Fruitland Coal; and, if any Ojo Alamo is present in the open hole section at the top of the hole, a minimum of one centralizer will be run just below the base and another into the base of Ojo Alamo. Minimum clearance between collars and hole is 1.25". Prior to perforating the casing for any attempted completion, the casing will be tested to a minimum of 2500 psi. Safety factors utilized in the design of this casing string were: Burst = 1.1, Collapse = 1.125, and Tension = 1.8 or 100,000# overpull whichever was greater.

A chronological log following the completion of the cementing operations detailing the pump rate, pump pressure, slurry density, and slurry volume for each job will be submitted in a Sundry Notice.

5. **Pressure Control Equipment:** (See attached schematic diagrams) A minimum of a 2M BOPE well control system will be utilized. BOP's and choke manifold will be installed and pressure tested before drilling out under surface casing and then will be checked daily as to mechanical operation condition. Ram type preventors will be tested to 70 percent of the internal yield pressure of the casing. The annular preventor will be tested to 50 percent of its working pressure.

A full opening internal blowout preventor or drill pipe safety valve will be on the drilling floor at all times and will be capable of fitting all connections.

6. **Mud Program:** A fresh water Low Solids, Non-Dispersed mud system will be used to drill this well. Sufficient materials will be on location at all times to maintain mud properties and to control any unforeseen lost circulation problems or abnormal pressures in the Farmington Sands of the Kirtland Formation. All drilling fluids will be contained in a steel pit. At the completion of drilling, the drilling fluid will be hauled off to be used for another well. The remaining accumulation of solids in the pit will be dumped into a small earthen pit beside the steel pit. As soon as this pit dries up, it will be covered up.

Mud program summary is as follows:

<u>Interval</u> <u>(feet)</u>	<u>Mud Weight</u> <u>(#/gal)</u>	<u>Viscosity</u> <u>(sec/qt)</u>
0 - 1000	8.4 or less	30 - 38
1000 - TD	9.3 or less	40 - 55

7. **Auxiliary Equipment:**

An upper Kelly Cock will be utilized. At a minimum, a flow sensor will be installed in the system and the mud volume constantly be visually monitored.

8. **Logging Program:** SP-DIL and GR-FDC-CNL logs will be run from TD to surface casing shoe.

Coring Program: No cores are planned.

Testing Program: No tests are planned.

Stimulation Program: Perf the Basal Fruitland Coal with 2 JSPF and frac with 50,000 gals of either a 70 quality nitrogen foam or a crosslinked-gelled water containing a minimum of 50,000 lbs of 20-40 mesh sand.


9. **Abnormal Pressure:** Although not expected, abnormal pressures are possible in the Farmington Sands of the Kirtland Formation.

Estimated Bottom Hole Pressure: 400 psi.

10. **Anticipated Starting Date:** As soon as all required approvals are received.


Duration of Operation: It is anticipated a total of 4 days will be required for drilling operations and 5 days for completion operations.

BHP PETROLEUM (AMERICAS) INC.
 GALLEGOS CANYON UNIT #516
 1745' FSL & 950' FWL
 Sec. 7, T28N, R11W
 San Juan Co., N.M.




SCALE: 1" = 30'


A-A' Vert.: 1" = 30' Horiz.: 1" = 50' C/L




B-B'




C-C'



A detailed topographic map of the Gallegos Canyon Unit #516. The map features contour lines indicating elevation, with labels such as 5350, 5400, 5430, 5470, 5500, 5600, and 5700. Several gas wells are marked with dots and labeled "Gas Well". A racetrack is shown in the upper right quadrant. A siphon is indicated near the bottom right. The map is divided into sections by a grid, with section numbers 26, 35, 36, 12, and 18 visible. A prominent road or boundary line runs horizontally across the upper portion of the map. The terrain is rugged, with deep canyons and steep slopes. A large, dark, irregularly shaped area is visible in the lower left, possibly representing a reservoir or a specific geological feature. The overall map is in black and white, with a high level of detail and contrast.

BHP PETROLEUM (AMERICAS) INC.
1745' FSL & 950' FWL
Sec. 7, T28N, R11W
San Juan Co., N.M.
GALLEGOS CANYON UNIT #516





STATE OF NEW MEXICO
ENERGY AND MINERALS DEPARTMENT
OIL CONSERVATION DIVISION
AZTEC DISTRICT OFFICE
RECEIVED

RREY CARRUTHERS
GOVERNOR

'90 OCT 5 AM 9 29

1000 PINTO HAZEL ROAD
AZTEC, NEW MEXICO 87410
(505) 334-0170

Date: 10-3-90

attn: M. S. Fagan

Oil Conservation Division
P.O. Box 2000
Santa Fe, NM 87504-2000

Re: Proposed HC _____
Proposed DHC _____
Proposed NSL X _____
Proposed SWD _____
Proposed WFX _____
Proposed PHX _____

Gentlemen:

I have examined the application dated 9-12-90

for the B.H.P. PETROAMERICAS) INC. G.C.U. # 516
Operator Lease & Well No.

L-7-28N-11W and my recommendations are as follows:
Unit, S-T-R

Approve

Yours truly,

Ernie Bush