



# NEW MEXICO ENERGY, MINERALS and NATURAL RESOURCES DEPARTMENT

**BILL RICHARDSON**  
Governor  
**Joanna Prukop**  
Cabinet Secretary

**Lori Wrotenbery**  
Director  
Oil Conservation Division

February 2, 2004

OXY USA WTP Limited Partnership  
P.O. Box 50520  
Midland, TX 79710-0250  
Attn: David Stewart or To Whom It May Concern

**RE: OXY Redemption #1, located 660' FSL & 660' FWL in Unit M of Section 15, Township 22 South-Range 27 East, Eddy County, New Mexico**

Dear Mr. Stewart,

Per your request on Friday, January 30th, 2004, I am returning the above application as denied for the above captioned application to drill (APD).

The New Mexico Oil Conservation Division (NMOCD) office in Artesia has determined that Tom Brown, Inc. has submitted an APD at the same location prior to your submittal on January 26, 2004.

Respectfully yours,

Bryan G. Arrant  
PES

A handwritten signature in black ink, appearing to read "Bryan G. Arrant".

BEFORE THE OIL CONSERVATION DIVISION  
Santa Fe, New Mexico  
Case No. 13226 Exhibit No. 16  
Submitted by:  
OXY USA WTP LTD. PARTNERSHIP  
Hearing Date: March 4, 2004

State of New Mexico  
Energy, Minerals & Natural Resources

Form C-10  
Revised March 17, 1994

District I  
1625 N. French Dr., Hobbs, NM 88240  
District II  
811 S. 1st Street, Artesia, NM 88210  
District III  
1000 Rio Brazos Rd., Aztec, NM 87410  
District IV  
2040 South Pacheco, Santa Fe, NM 87505

Oil Conservation Division  
2040 South Pacheco  
Santa Fe, NM 87505

RECEIVED  
JAN 9 6 2004  
OCD-ARTESIA  
Submit to appropriate District Office  
State Lease - 6 Copies  
Fee Lease - 5 Copies  
 AMENDED REPORT

**APPLICATION FOR PERMIT TO DRILL, RE-ENTER, DEEPEN, PLUGBACK, OR ADD A ZONE**

<sup>1</sup> Operator Name and Address OXY USA WTP Limited Partnership P.O. Box 50250 Midland, TX 79710-0250		<sup>2</sup> OGRID Number 192463	
<sup>4</sup> Property Code		<sup>3</sup> API Number 30- 015- [REDACTED]	
<sup>5</sup> Property Name OXY Redemption		Well No. 1	

<sup>7</sup> Surface Location

UL or lot no.	Section	Township	Range	Lot. Idn	Feet from the	North/South Line	Feet from the	East/West line	County
M	15	22S	27E		660	south	660	west	Eddy

<sup>8</sup> Proposed Bottom Hole Location If Different From Surface

UL or lot no.	Section	Township	Range	Lot. Idn	Feet from the	North/South Line	Feet from the	East/West line	County
<sup>9</sup> Proposed Pool 1 Undesignated Carlsbad Morrow, South					<sup>10</sup> Proposed Pool 2 73960				

<sup>11</sup> Work Type Code N	<sup>12</sup> Well Type Code G	<sup>13</sup> Cable/Rotary R	<sup>14</sup> Lease Type Code P	<sup>15</sup> Ground Level Elevation
<sup>16</sup> Multiple No	<sup>17</sup> Proposed Depth 12400'	<sup>18</sup> Formation Morrow	<sup>19</sup> Contractor N/A	<sup>20</sup> Spud Date 2/29/04

<sup>21</sup> Proposed Casing and Cement Program

Hole Size	Casing Size	Casing weight/foot	Setting Depth	Sacks of Cement	Estimated TOC
17-1/2"	13-3/8"	48#	625'	400sx	surface-circulate
12-1/4"	9-5/8"	36#	4500'	1200sx	surface-circulate
8-3/4"	5-1/2"	17#	12400'	1400sx	Est TOC-6000'

<sup>22</sup> Describe the proposed program. If this application is to DEEPEN or PLUG BACK, give the data on the present productive zone and proposed new productive zone. Describe the blowout prevention program, if any. Use additional sheets if necessary.

See Other Side

Operator to set surface casing Above Salado @ 400'

<sup>23</sup> I hereby certify that the information given above is true and complete to the best of my knowledge and belief.		OIL CONSERVATION DIVISION	
Signature: <i>David Stewart</i>		Approved by: [REDACTED]	
Printed name: David Stewart		Title:	
Title: Sr. Regulatory Analyst		Approval Date: [REDACTED] Expiration Date: [REDACTED]	
Date: 1/23/04	Phone: 432-685-5717	Conditions of Approval:	
		Attached <input type="checkbox"/> Denied	

**OXY Redemption #1**  
**660 FSL 660 FWL SWSW(M) SEC 15 T22S R27E Eddy County, NM**

**PROPOSED TD:** 12400' TVD

**BOP PROGRAM:** 0-625' None

625-4500' 13-3/8" 3M annular preventer, to be used as  
divertor only.

4500-12400' 11" 5M blind pipe rams with 5M annular  
preventer and rotating head below 8500'.

**CASING:** Surface: 13-3/8" OD 48# H40 ST&C new casing set at 0-625'  
17-1/2" hole

Intermediate: 9-5/8" OD 36# HCK55/K55 ST&C new casing at 0-4500'  
12-1/4" hole

Production: 5-1/2" OD 17# N80-HP110 LT&C new casing at 0-12400'  
8-3/4" hole N80-8800' HP110-3500'

**CEMENT:** Surface - Circulate cement with 200sx 35:65 POZ/C with 6% Bentonite  
+ 2% CaCl<sub>2</sub> + .25#/sx Cello-Seal followed by 200sx Cl C with 2% CaCl<sub>2</sub>.

Intermediate - Circulate cement with 1000sx 35:65 POZ/C with 6%  
Bentonite + 2% CaCl<sub>2</sub> + .25#/sx Cello-Seal followed by 200sx Cl C  
with 2% CaCl<sub>2</sub>.

Production - Cement with 1200sx 15:61:11 POZ/C/CSE with .5% FL-52  
+ .5% FL-25 + 8#/sx Gilsonite followed by 200sx Cl C with .7%  
FL-25. Estimated top of cement is 6000'.

Note: Cement volumes may need to be adjusted to hole caliper.

**MUD:** 0-625' Fresh water/native mud. Lime for pH control  
(9-10). Paper for seepage.  
Wt 8.7-9.2 ppg, Vis 32-34 sec

625-4500' Fresh/\*Brine water. Lime for pH control  
(10.0-10.5). Paper for seepage.  
Wt 8.3-9.0/10.0-10.1ppg, Vis 28-29 sec  
\*Fresh water will be used unless chlorides in  
the mud system increases to 20000PPM.

4500-8300' Fresh water. Lime for pH control(9-9.5).  
Paper for seepage.  
Wt 8.3-8.5 ppg, Vis 28-29 sec

8300-10000' Cut brine. Lime for pH control (10-10.5).  
Wt 9.6-10.0 ppg, Vis 28-29sec

10000-12300' Mud up with an Duo Vis/Flo Trol mud system.  
Wt 9.6-10.0ppg, Vis 32-36sec, WL<10cc

State of New Mexico

DISTRICT I  
P.O. Box 1980, Hobbs, NM 88241-1980

Energy, Minerals and Natural Resources Department

Form C-10  
Revised February 10, 199  
Submit to Appropriate District Office  
State Lease - 4 Copie  
Fee Lease - 3 Copie

DISTRICT II  
P.O. Drawer DD, Artesia, NM 88211-0719

OIL CONSERVATION DIVISION  
P.O. Box 2088

Santa Fe, New Mexico 87504-2088

DISTRICT III  
1000 Rio Brazos Rd., Aztec, NM 87410

DISTRICT IV  
P.O. BOX 2088, SANTA FE, N.M. 87504-2088

WELL LOCATION AND ACREAGE DEDICATION PLAT

AMENDED REPORT

API Number 30-015-		Pool Code 73960	Pool Name Undesignated Carlsbad Morrow, South
Property Code	Property Name OXY REDEMPTION		Well Number 1
OGRID No. 192463	Operator Name OXY U.S.A. W.T.P., LP		Elevation 3107'

Surface Location


UL or lot No.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County
M	15	22-S	27-E		660	SOUTH	660	WEST	EDDY

Bottom Hole Location If Different From Surface

UL or lot No.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County

Dedicated Acres 320	Joint or Infill N	Consolidation Code	Order No.
------------------------	----------------------	--------------------	-----------

NO ALLOWABLE WILL BE ASSIGNED TO THIS COMPLETION UNTIL ALL INTERESTS HAVE BEEN CONSOLIDATED OR A NON-STANDARD UNIT HAS BEEN APPROVED BY THE DIVISION



OPERATOR CERTIFICATION

I hereby certify the the information contained herein is true and complete to the best of my knowledge and belief.

*David Stewart*

Signature

David Stewart

Printed Name

Sr. Regulatory Analyst

Title

1/23/04

Date

SURVEYOR CERTIFICATION

I hereby certify that the well location shown on this plat was plotted from field notes of actual surveys made by me or under my supervision and that the same is true and correct to the best of my belief.

January 13, 2004

Date Surveyed AWB


Signature & Seal of Professional Surveyor

*Gary Eudson* 1/19/04  
04.11.0036

Certificate No. GARY EIDSON 12641

EXHIBIT A


ANNULAR PREVENTOR  
TO BE USED AS DIVERTOR ONLY



**BLOWOUT PREVENTOR SCHEMATIC**

**EXHIBIT A**

11" 5000# ram type preventers with one set blind rams and one set pipe rams and a 5000# annular type preventer. A choke manifold and 120 gallon accumulator with floor and remote operating stations and auxiliary power system.



**Hydrill GR  
Annular Preventer**

**Rams  
Shaffer Type "g"**

**To Choke Manifold**

**To Reserve Pit**


**4" Valve  
TYPE  
HCR  
VALVE**

**3" Choke (Manual)**

**Manifold Detail**


**Choke Manifold**

**SECTION 15, TOWNSHIP 22 SOUTH, RANGE 27 EAST, N.M.P.M.,**  
 EDDY COUNTY, NEW MEXICO.



**DIRECTIONS TO LOCATION:**

FROM THE INTERSECTION OF COUNTY ROAD #700 (CALVANI RD.) AND U.S. HWY 285. GO EAST ON CO. RD. #700 1.7 MILES TO RANCH ROAD. TURN LEFT AND GO 0.1 MILES NORTH TO THIS LOCATION.




**OXY U.S.A. W.T.P., LP**

THE OXY REDEMPTION #1 WELL LOCATED 660' FROM THE SOUTH LINE AND 660' FROM THE WEST LINE OF SECTION 15, TOWNSHIP 22 SOUTH, RANGE 27 EAST, N.M.P.M., EDDY COUNTY, NEW MEXICO.

Survey Date: 01/13/04	Sheet 1 of 1 Sheets
W.O. Number: 04.11.0036	DRAWN BY: A.W.B
Date: 01/14/04	DISK: CD#10
TOMBRO# 0036	Scale: 1"=100'

JOHN WEST SURVEYING COMPANY  
 412 N. DAL PASO - HOBBS, NEW MEXICO - 505-393-3117

# VICINITY MAP



SCALE: 1" = 2 MILES

SEC. 15 TWP. 22-S RGE. 27-E  
 SURVEY N.M.P.M.  
 COUNTY EDDY  
 DESCRIPTION 660' FSL & 660' FWL  
 ELEVATION 3107'  
 OPERATOR OXY U.S.A. W.T.P., LP  
 LEASE OXY REDEMPTION

JOHN WEST SURVEYING  
 HOBBS, NEW MEXICO  
 (505) 393-3117



**OXY USA WTP  
Limited Partnership  
PO Box 50250  
Midland, TX 79710**

**Hydrogen Sulfide (H<sub>2</sub>S)  
Contingency Plan**

**For**

**OXY Redemption No. 1  
660 ft FSL, 660 ft FWL  
Sec 15, T22S, R27E  
Eddy County, NM**

**And**

**McVay Drilling Co., Rig No. 8**

**TABLE OF CONTENTS**

<b><u>ITEM</u></b>	<b><u>PAGE</u></b>
PREFACE .....	3
LOCATION MAP.....	4
RIG SKETCH.....	5
EMERGENCY RESPONSE ACTIVATION AND GENERAL RESPONSIBILITIES	6
SPECIFIC EMERGENCY GUIDANCE	
- H2S Release .....	8
- Well Control.....	10
PUBLIC RELATIONS .....	13
PHONE CONTACTS – OP DOWNHOLE SERVICES GROUP .....	14
EMERGENCY PERSONELL NOTIFICATION NUMBERS.....	13
PHONE CONTACTS – OP PRODUCTION AND PLANT PERSONNEL .....	15
PHONE CONTACTS – OP HES PERSONNEL .....	16


## **PREFACE**

**An effective and viable Contingency Plan is intended to provide prior planning and guidance in responding to emergency incidents. The primary considerations in its development are protection of personnel, the public, company and public property, and the environment.**


**Although the plan addresses varied emergency situations which may occur, it recognizes that flexibility and the use of the organization's knowledge and experience is critical to safe resolution of emergency incidents. Response actions outlined in the plan provide a framework, which may be placed into operation without confusion. These actions should promote quick and decisive actions during the critical initial period and immediately following an emergency. As the response progresses, additional guidelines and procedures may need to be implemented as the situation dictates. In addition, all emergency incidents must be properly reported per the Oxy Incident Reporting and Notification Policy, state and federal requirements, etc.**

**This Contingency Plan is intended for use on Oxy Downhole Services Group projects and the operations within their area of responsibility, such as drilling, critical well work, etc.**


**Oxy Redemption. No. 1**  
**Y = 504595.5 N**  
**X = 546280.9 E**  
**Lat. 32° 23' 13.77" N**  
**Long. 104° 11' 00.25" W**



**North**



**From the intersection of County Road No. 700 (Calvani Rd.) and U.S. HWY 285 Go east on County Rd. 700 for 1.7 miles to ranch road. Turn left and go 0.1 miles north to this location**



**EMERGENCY RESPONSE ACTIVATION AND GENERAL RESPONSIBILITIES**

***Activation of the Emergency Action Plan***

- A. In the event of any emergency situation, all personnel on location should first ensure that the following items are initiated. After that, they should refer to the appropriate Specific Emergency Guidance sections on pages five (5) through nine (10) in this document for further responsibilities:
1. Notify the senior ranking contract representative on site.
  2. Notify Oxy representative in charge.
  3. Notify civil authorities if the Oxy Representative can not be contacted and the situation dictates.
  4. Perform rescue and first aid as required (without jeopardizing additional personnel).

### **General Responsibilities**

#### **Oxy Permian Personnel:**

- A. **Operations Specialist:** The Oxy Drilling/Critical Well Servicing Operations Specialist or contract personnel serving in that capacity will serve as Operations Chief Officer for all emergency incidents. The Operations Chief Officer is responsible for:
1. Notification to the Downhole Services Team Leader of the incident occurrence.
  2. Notification to the local RMT/PMT leader of the incident occurrence, and the need for the designated local RMT/PMT Incident Commander to act in that capacity for the response effort.
  3. Sole control of all tactical activities directed toward reducing the immediate hazard, establishing situational control and restoring the operations to a non-emergency state.
- B. **Local RMT/PMT Designated Incident Commander:** The Oxy local RMT/PMT Designated Incident Commander will serve as the overall Incident Commander for the drilling or critical well servicing emergency incident. The Incident Commander is responsible for:
1. Coordinating with the Downhole Services Team Leader for notification to the Oxy Crisis Management team of the incident occurrence.
  2. Establishing and managing the overall incident command structure and response from inception through restoration of normal activities in the area.
- C. **Downhole Services HES Tech:** The Downhole Services HES Tech (or his designate) is responsible for reporting to the incident as soon as reasonably possible, to provide support to the response effort as required by the Operations Chief Officer or the Incident Commander.

**Contract Drilling Personnel** will immediately report to their assigned stations and perform their duties as outlined in the appropriate Specific Emergency Guidance sections on pages five (5) through nine (9) in this document.

**Other Contractor Personnel** will report to the safe briefing area to assist Oxy personnel and civil authorities as requested when it is safe to do so and if they have been adequately trained in their assigned duties.

**Civil Authorities** (Law Enforcement, Fire, and EMS) will be responsible for:

1. Establishing membership in the Unified Incident Command.
2. As directed by the Incident Commander and the Unified Command, control site access, re-route traffic, and provide escort services for response personnel.
3. Perform all fire control activities in coordination with the Unified Command.
4. Initiate public evacuation plans as instructed by the Incident Commander.
5. Perform rescue or recovery activities with coordination from the Unified Command.
6. Provide medical assistance as dictated by the situation at hand.

**H2S RELEASE**

The following procedures and responsibilities will be implemented on activation of the H2S siren and lights.

**All Personnel:**

1. On alarm, don escape unit (if available) and report to upwind briefing area.

**Rig Manager/Tool Pusher:**

1. Check that all personnel are accounted for and their condition.
2. Administer or arrange for first aid treatment, and /or call EMTs as needed.
3. Identify two people best suited to secure well and perform rescue, and instruct them to don SCBA.
4. Notify Contractor management and Oxy Representative.
5. Remain at the briefing area, assess and monitor personnel and overall situation for hazards or conditions that might warrant a change in the action plan.

**Two People Responsible For Shut-in and Rescue:**

1. Don SCBA and acquire tools to secure well and perform rescue, i.e., wrenches, retrieval ropes, etc.
2. Utilize the buddy system to secure well and perform rescue(s).
3. Return to the briefing area and stand by for further instructions.

**All Other Personnel:**

1. Isolate the area and prevent entry by other persons into the 100 ppm ROE. Additionally the first responder(s) must evacuate any public places encompassed by the 100 ppm ROE. First responder(s) must take care not to injure themselves during this operation. Company and/or local officials must be contacted to aid in this operation. Evacuation of the public should be beyond the 100 ppm ROE.

**Oxy Representative:**

1. Remain at the briefing area, assess and monitor personnel and overall situation for hazards or conditions that might warrant a change in the action plan.
2. Notify Operation Specialists or Team Leader and RMT Leader or Local Incident Commander, and Police, Fire Department, or other local emergency services as required.

**Training**

All responders must have training in the detection of H<sub>2</sub>S measures for protection against the gas, equipment used for protection and emergency response. Weekly drills by all crews will be conducted and recorded in the IADC daily log. Additionally, responders must be equipped with H<sub>2</sub>S monitors at all times

**Ignition of Gas Source**

Should control of the well be considered lost and ignition considered, take care to protect against exposure to Sulfur Dioxide (SO<sub>2</sub>). Intentional ignition must be coordinated with the NMOCD and local officials. Additionally the NM State Police shall be the Incident Command of any major release.

#### Characteristics of H<sub>2</sub>S and SO<sub>2</sub>

Common Name	Chemical Formula	Specific Gravity	Threshold Limit	Hazardous Limit	Lethal Concentration
Hydrogen Sulfide	H <sub>2</sub> S	1.189 Air = 1	10 ppm	100 ppm	600 ppm
Sulfur Dioxide	SO <sub>2</sub>	2.21 Air = 1	2 ppm	N/A	1000 ppm

#### Contacting Authorities

Oxy Permian personnel must liaison with local and state agencies to ensure a proper response to a major release. Additionally, the OCD must be notified of the release as soon as possible but no later than 4 hours. Agencies will ask for information such type and volume of release, wind direction, location of release, etc. Be prepared with all information available. The following call list of essential and potential responders has been prepared for use during a release. This response plan must be in coordination with the State of New Mexico's 'Hazardous Materials Emergency Response Plan' (HMER).

## **WELL CONTROL**

The following procedures will be implemented when a loss of primary control is indicated. Indicators of loss of primary control are flow from the well, an increase in pit volume, or when the drilling fluid used to fill the hole on trips is less than the calculated pipe displacement volume. The emergency signal for well control procedures will be a single long blast of the rig air horn.

### **Kick While Drilling - Procedures And Responsibilities**

#### **Driller:**

1. Stop the rotary and hoist the kelly above the rotary table.
2. Stop the mud pump(s).
3. Check for flow.
4. If flowing, sound the alarm immediately.
5. Ensure that all crew members fill their responsibilities to secure the well.
6. Record drill pipe and casing shut-in pressures and pit volume increase and begin kill sheet.

#### **Derrickman:**

1. Go to BOP/choke manifold area.
2. Open choke line valve on BOP.
3. Signal to Floorman #1 that the choke line is open.
4. Close chokes after annular or pipe rams are closed.
5. Record shut-in casing pressure and pit volume increase.
6. Report readings and observations to Driller.
7. Verify actual mud weight in suction pit and report to Driller.
8. Be readily available as required for additional tasks.

#### **Floorman # 1:**

1. Go to accumulator control station and await signal from Derrickman.
2. Close annular preventer and HCR on signal (if available, if not then close pipe rams).
3. Record accumulator pressures and check for leaks in the BOP or accumulator system.
4. Report to Driller, and be readily available as required for additional tasks.

#### **Floorman # 2:**

1. Start water on motor exhausts.
2. Notify Contractor Tool Pusher or Rig Manager of well control situation.
3. Check location for ignition sources and extinguish or turn off, and stop any welding in progress.
4. Report to Driller, and be readily available as required for additional tasks.

**Floorman # 3:**

1. Stand-by with Driller, and be readily available as required for additional tasks.

**Tool Pusher/Rig Manager:**

1. Notify Oxy Representative and report to rig floor.
2. Review and verify all pertinent information.
3. Communicate information to Oxy Representative, and confer on an action plan.
4. Finalize well control worksheets, calculations and preparatory work for action plan.
5. Initiate and ensure the action plan is carried out.
6. Communicate any changes in well or site conditions, or any indications that the action plan needs to be revised to the Oxy representative.

**Oxy Representative:**

1. Notify Operation Specialists or Team Leader and RMT Leader or Local Incident Commander, and Police, Fire Department, or other local emergency services as required.

**Kick While Tripping - Procedures and Responsibilities**

**Driller:**

1. Sound the alarm immediately when pipe displacement volume is less than 75% of calculated.
2. Position the upper tool joint just above rotary table and set slips.
3. Check for flow.
4. Ensure that all crew members fill their responsibilities to secure the well.
5. Record drill pipe and casing shut-in pressures and pit volume increase, and begin kill sheets.

**Derrickman:** (same as while drilling)

**Floor Man # 1:**

1. Install full opening valve (with help from Floorman #2) in top drill string connection.
2. Tighten valve with make up tongs.
3. Go to accumulator control station and await signal from Derrickman.
4. Close annular preventer and HCR valve on signal (if available, if not then close pipe rams).
5. Record accumulator pressures and check for leaks in the BOP and accumulator system.
6. Report to Driller, and be readily available as required for additional tasks.

**Floor Man # 2:**

1. Assist installing full opening valve in drill string.
2. Position back-up tongs for valve make-up.
3. Start water on motor exhausts.
4. Notify Contractor Tool Pusher or Rig Manager of well control situation.
5. Check location for ignition sources and extinguish or turn off, and stop any welding in progress.
6. Report to Driller, and be readily available as required for additional tasks.

**Floorman # 3, Rig Manager/Tool Pusher, and Oxy Representative: (same as while drilling)**

## **PUBLIC RELATIONS**

Oxy recognizes that the news media have a legitimate interest in incidents at Oxy facilities that could affect the public. It is to the company's benefit to cooperate with the news media when incidents occur because these media are our best liaison with the public.

Our objective is to see that all reports of any emergency are factual and represent the company's position fairly and accurately. Cooperation with news media representatives is the most reliable guarantee that this objective will be met.

All contract and Oxy employees are instructed **NOT** to make any statement to the media concerning the emergency incident. If a media representative contacts any employee, they should refer them to the designated Emergency Command Center where they should contact the Incident Commander or his designated relief for any information concerning the incident.

**OXY PERMIAN DOWNHOLE SERVICES GROUP**

	<b>LOCATION</b>	<b>OFFICE</b>	<b>HOME</b>	<b>CELL</b>	<b>PAGER</b>
<b>Manager Operations Support</b>					
Hardesty, Steve	Midland	432-685-5880	432/694-6441	713-560-8095	
<b>Team Leader</b>					
Pennington, Randy	Midland	432-685-5684	432/689-7642	432-556-0207	713-312-8186
			Toledo Bend =	318-590-2349	
<b>Operations Specialists</b>					
Fleming, Joe	Midland	432-685-5858	432/699-0875	432-425-6075	432-498-3281
Ray, Fred	Midland	432-685-5683	432/362-2857	432-661-3893	432-499-3432
<b>HES Tech</b>					
Thompson, Don	Midland	432-685-5719	432/684-3900	432-556-1505	

**OXY Permian Production and Plant Personnel  
OXY Permian Crisis Team Hotline Notification (713) 935-7210**

PERSON	LOCATION	OFFICE	FAX	CELL	PAGER
<b>Asset Management-Operations Areas</b>					
OXY Permian General Manager: Tom Menges	Houston	(281) 552-1147	(281) 552-1484	(713) 560-8038	
South Permian Asset: Matt Hyde	Midland	(432) 685-5802	(432) 685-5930	(432) 556-5016	

<b>RMT/PMT Leaders: South Permian Asset</b>					
Frontier RMT: Tommy Johnson	Midland	(432) 685-5671	(432) 685-4054	(432) 238-9343	(432) 567-7038

PERSON	LOCATION	OFFICE	FAX	CELL	PAGER
<b>Production Coordinators: S. Permian Asset</b>					
New Mexico: John Erickson	Hobbs	(505) 393-2174	(505) 397-2671	(505) 390-6426	(505) 370-6836

**OXY Permian HES Personnel  
OXY Permian Crisis Team Hotline Notification (713) 935-7210**

PERSON	LOCATION	OFFICE	FAX	CELL	PAGER
<b>HES Coordinators &amp; Area of Responsibility</b>					
Frontier: Tom Scott	Midland	(432) 685-5677	(432) 685-5742	(432) 448-1121	(432) 498-1312
<b>HES Techs &amp; Area of Responsibility</b>					
Hobbs RMT: Steve Bishop	Hobbs	(505) 397-8251	(505) 397-8204	(505) 390-4784	(877) 339-1954-1118#
Frontier-New Mexico: Rick Kerby	Hobbs	(505) 393-2174	(505) 393-2671	(505) 390-8639	(505) 370-6527