

WELL NAME SHELL ISLETA #1
 TYPE WELL EXPLORATION WILDCAT
 FIELD/AREA ISLETA CENTRAL BLOCK (CACTUS)

APPROX. LOCATION (SUBJECT TO SURVEY) NW 1/4 Sec. 7 T7N R2E Valencia Co., New Mexico

EST. G. L. ELEVATION 5040 PROJECTED TD 16,300 OBJECTIVE Entrada Sandstone

CASING PROGRAM	LOGGING PROGRAMS	MAX DEV.	DEPTHS AND FORMATION TOPS	SPECIAL INSTRUCTIONS
13-3/8"	BHC FDC HDT DIL		400'	SAMPLES: Surface to 5,000' -- 30' 5,000' to TD - 10' CORES: 10 - 30' Conventional 200 - Sidewall shots DST'S: Tertiary - 2 Conventional Cretaceous - 5 Conventional Jurassic - 1 Conventional DEVIATION CONTROL Dogleg severity less than 1 1/2° per any 100' interval. Drop survey every 500' or on dull bits.
9-5/8"	BHC FDC HDT DIL		5000'	10 - 30' Conventional 200 - Sidewall shots DST'S: Tertiary - 2 Conventional Cretaceous - 5 Conventional Jurassic - 1 Conventional DEVIATION CONTROL Dogleg severity less than 1 1/2° per any 100' interval. Drop survey every 500' or on dull bits.
7" if Required	BHC FDC HDT DIL DIL/SP CNL/GR/CAL PML Seismic Reference Survey Two Man Logging Unit	Angle Buildup Less than 1° Per 1,000'	Menefee (K) 12,000' Dalton S.S. 13,540' Gallup S.S. 14,150' Greenhorn L.S. 14,950' Dakota S.S. 15,000' Morrison (Jr) 15,500' Todilto Anhy 16,000' Entrada S.S. 16,120' TD 16,300'	CEMENT 13-3/8": Cement to Surface 9-5/8": Cement to Surface WOC 18 hrs minimum on all jobs. MUD Surface to 400' - Spud Mud 400' to TD - Shell's "SK" and "SKE" polymer mud. See mud program for details.

GINATOR: L. A. Primm DATE 8/12/74

ENGINEERING APPROVAL:

ROLEUM: J. S. Miller

RATIONS: J. S. Miller

OPERATIONS APPROVAL:

[Signature]
 DIV. DRILLING SUPT.