

May 16, 1974

REPLY TO: 11
P. O. BOX 3000
CASPER, WYOMING 02601

NORTHERN DIVISION

Spill Prevention Control and Countermeasures Plan
-SPCC-

In accordance with U. S. Environmental Protection Agency Oil Pollution Prevention Regulation: CFR - Title 40, Part 112

Precautionary Measures:

- (1) Fuel Tanks:
 - (a) Skid Mounted
 - (b) Adequately braced and protected by skids
 - (c) Located so as to be protected from vehicular impact
 - (d) Adequate ditching provided so that fuel spillage from tank discharge valve is diverted into reserve pit for collection
 - (e) Regularly inspected for leaks
 - (f) Impact resistant
- (2) Fuel Lines
 - (a) Located in areas not traversed by vehicular traffic
 - (b) Where possible steel lines used instead of hose
 - (c) Inspected daily
 - (d) Ditched or diked to direct fuel line rupture to reserve pit
- (3) Absorptive materials on site (some or all present at all times)
 - (a) Montmorillonite clays
 - (b) Ground paper
 - (c) Sawdust
 - (d) Cellulose fibers (various types)
 - (e) Powdered barite
- (4) Ditching as shown on Diagram # 1
- (5) Reserve Pit (Retention Pond) provided on all locations
- (6) Manpower requirements
 - (a) Rig crew on site during drilling operations (5 men)

Edmund