Form 3160-3
(June 2015)

OCD – REC'D 6/22/2020

FORM APPROVED
OMB No. 1004-0137
Expires: January 31, 2018

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

APPLICATION FOR PERMIT TO DRILL OR REENTER

5. Lease Serial No.
NMNM015303

6. If Indian, Allotee or Tribe Name

1a. Type of work: ☑ DRILL ☐ REENTER

1b. Type of Well: ☑ Oil Well ☐ Gas Well ☐ Other

1c. Type of Completion: ☐ Hydraulic Fracturing ☐ Single Zone ☑ Multiple Zone

7. If Unit or CA Agreement, Name and No.

8. Lease Name and Well No.
CORRAL GORGE 12-13 FEDERAL COM
32H

2. Name of Operator
OXY USA INCORPORATED

9. API Well No.
3001547214

3a. Address
5 Greenway Plaza, Suite 110, Houston, TX 77046

3b. Phone No. *(include area code)*
(713) 366-5716

10. Field and Pool, or Exploratory
CORRAL DRAW BONE SPRING/RED TA

4. Location of Well *(Report location clearly and in accordance with any State requirements.*)*
At surface NWNW / 162 FNL / 285 FWL / LAT 32.151502 / LONG -103.945688
At proposed prod. zone SWSW / 20 FSL / 940 FWL / LAT 32.122813 / LONG -103.94352

11. Sec., T. R. M. or Blk. and Survey or Area
SEC 12/T25S/R29E/NMP

14. Distance in miles and direction from nearest town or post office*
8 miles

12. County or Parish
EDDY

13. State
NM

15. Distance from proposed* location to nearest property or lease line, ft. (Also to nearest drig. unit line, if any)
20 feet

16. No of acres in lease
1280

17. Spacing Unit dedicated to this well
640.0

18. Distance from proposed location* to nearest well, drilling, completed, applied for, on this lease, ft.
35 feet

19. Proposed Depth
10294 feet / 21207 feet

20. BLM/BIA Bond No. in file
FED: ESB000226

21. Elevations (Show whether DF, KDB, RT, GL, etc.)
3076 feet

22. Approximate date work will start*
10/19/2020

23. Estimated duration
20 days

24. Attachments

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No. 1, and the Hydraulic Fracturing rule per 43 CFR 3162.3-3 (as applicable)

1. Well plat certified by a registered surveyor.
2. A Drilling Plan.
3. A Surface Use Plan (if the location is on National Forest System Lands, the SUPO must be filed with the appropriate Forest Service Office).
4. Bond to cover the operations unless covered by an existing bond on file (see Item 20 above).
5. Operator certification.
6. Such other site specific information and/or plans as may be requested by the BLM.

25. Signature
(Electronic Submission)

Name *(Printed/Typed)*
JANA A / Ph: (713) 366-5716

Date
12/20/2019

Title
Regulatory Coordinator

Approved by *(Signature)*
(Electronic Submission)

Name *(Printed/Typed)*
Cody Layton / Ph: (575) 234-5959

Date
05/27/2020

Title
Assistant Field Manager Lands & Minerals

Office
Carlsbad Field Office

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.
Conditions of approval, if any, are attached.

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

APPROVED WITH CONDITIONS

(Continued on page 2)

*(Instructions on page 2)

Approval Date: 05/27/2020 Entered - KMS NMOCD

DISTRICT I
1625 N. FRENCH DR., HOBBS, NM 88240
Phone: (575) 393-6161 Fax: (575) 393-0720

DISTRICT II
811 S. FIRST ST., ARTESIA, NM 88210
Phone: (575) 748-1283 Fax: (575) 748-9720

DISTRICT III
1000 RIO BRAZOS RD., AZTEC, NM 87410
Phone: (505) 334-6178 Fax: (505) 334-6170

DISTRICT IV
1220 S. ST. FRANCIS DR., SANTA FE, NM 87505
Phone: (505) 476-3460 Fax: (505) 476-3462

State of New Mexico
Energy, Minerals & Natural Resources Department
OIL CONSERVATION DIVISION
1220 SOUTH ST. FRANCIS DR.
Santa Fe, New Mexico 87505

Form C-102
Revised August 1, 2011
Submit one copy to appropriate
District Office

☐ AMENDED REPORT

WELL LOCATION AND ACREAGE DEDICATION PLAT

API Number	Pool Code	Pool Name
30-015- 47214	98220	Purple Sage Wolfcamp

Property Code	Property Name	Well Number
328295	CORRAL GORGE 12_13 FEDERAL COM	32H

OGRID No.	Operator Name	Elevation
16696	OXY USA INC.	3075.8'

Surface Location

UL or lot No.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County
D	12	25-S	29-E		162	NORTH	285	WEST	EDDY

Bottom Hole Location If Different From Surface

UL or lot No.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County
M	13	25-S	29-E		20	SOUTH	940	WEST	EDDY

Dedicated Acres	Joint or Infill	Consolidation Code	Order No.
640	Y		

NO ALLOWABLE WILL BE ASSIGNED TO THIS COMPLETION UNTIL ALL INTERESTS HAVE BEEN CONSOLIDATED OR A NON-STANDARD UNIT HAS BEEN APPROVED BY THE DIVISION



KOP
50' FNL & 940' FWL
Y=419186.8 N
X=661959.5 E
LAT.=32.151823° N
LONG.=103.943573° W

FTP
100' FNL & 940' FWL
Y=419136.8 N
X=661959.7 E
LAT.=32.151685° N
LONG.=103.943573° W

POINT LEGEND	
1	Y=419226.6 N X=661019.2 E
2	Y=413910.8 N X=661057.8 E
3	Y=411258.7 N X=661065.8 E
4	Y=408605.1 N X=661074.2 E
5	Y=408628.9 N X=663731.3 E
6	Y=413944.9 N X=663703.8 E
7	Y=419255.4 N X=663676.6 E

* ALL COORDINATES ARE NAD 83 VALUES

PROPOSED BOTTOM HOLE LOCATION
Y=408633.5 N
X=662014.1 E
LAT.=32.122813° N
LONG.=103.943520° W

OPERATOR CERTIFICATION

I hereby certify that the information herein is true and complete to the best of my knowledge and belief, and that this organization either owns a working interest or unleased mineral interest in the land including the proposed bottom hole location or has a right to drill this well at this location pursuant to a contract with an owner of such mineral or working interest, or to a voluntary pooling agreement or a compulsory pooling order heretofore entered by the division.

Signature 12/12/19 Date

Jana Mendiola
Printed Name

janalyn_mendiola@oxy.com
E-mail Address

SURVEYOR CERTIFICATION

I hereby certify that the well location shown on this plat was plotted from field notes of actual surveys made by me or under my supervision, and that the same is true and correct to the best of my belief.

JULY 8, 2019
Date of Survey

Signature & Seal of Professional Surveyor

CHAD L. HARCROW
NEW MEXICO
17777
LICENSED PROFESSIONAL SURVEYOR

Chad Harcrow 08/22/19

Certificate No. CHAD HARCROW 17777

W.O. # 19-1242 DRAWN BY: AM

Operator Certification Data Report

06/22/2020

Operator Certification

I hereby certify that I, or someone under my direct supervision, have inspected the drill site and access route proposed herein; that I am familiar with the conditions which currently exist; that I have full knowledge of state and Federal laws applicable to this operation; that the statements made in this APD package are, to the best of my knowledge, true and correct; and that the work associated with the operations proposed herein will be performed in conformity with this APD package and the terms and conditions under which it is approved. I also certify that I, or the company I represent, am responsible for the operations conducted under this application. These statements are subject to the provisions of 18 U.S.C. 1001 for the filing of false statements.

NAME: Jana Lyn A. Mendiola **Signed on:** 12/19/2019

Title: Regulatory Coordinator

Street Address:

City: Midland **State:** TX **Zip:** 79710

Phone: (432)685-5936

Email address: Janalyn_mendiola@oxy.com

Field Representative

Representative Name: JIM WILSON

Street Address: 6001 DEAUVILLE BLVD

City: MIDLAND **State:** TX **Zip:** 79706

Phone: (575)631-2442

Email address: jim_wilson@oxy.com

APD ID: 10400052319 **Submission Date:** 12/20/2019

Operator Name: OXY USA INCORPORATED

Well Name: CORRAL GORGE 12-13 FEDERAL COM **Well Number:** 32H

Well Type: OIL WELL **Well Work Type:** Drill

Highlighted data reflects the most recent changes

Show Final Text

Section 1 - General

APD ID: 10400052319 **Tie to previous NOS?** N **Submission Date:** 12/20/2019

BLM Office: CARLSBAD **User:** Jana Lyn A. Mendiola **Title:** Regulatory Coordinator

Federal/Indian APD: FED **Is the first lease penetrated for production Federal or Indian?** FED

Lease number: NMNM015303 **Lease Acres:** 1280

Surface access agreement in place? **Allotted?** **Reservation:**

Agreement in place? NO **Federal or Indian agreement:**

Agreement number:

Agreement name:

Keep application confidential? N

Permitting Agent? NO **APD Operator:** OXY USA INCORPORATED

Operator letter of designation:

Operator Info

Operator Organization Name: OXY USA INCORPORATED

Operator Address: 5 Greenway Plaza, Suite 110 **Zip:** 77046

Operator PO Box:

Operator City: Houston **State:** TX

Operator Phone: (713)366-5716

Operator Internet Address:

Section 2 - Well Information

Well in Master Development Plan? NO **Master Development Plan name:**

Well in Master SUPO? NO **Master SUPO name:**

Well in Master Drilling Plan? NO **Master Drilling Plan name:**

Well Name: CORRAL GORGE 12-13 FEDERAL COM **Well Number:** 32H **Well API Number:**

Field/Pool or Exploratory? Field and Pool **Field Name:** CORRAL DRAW BONE SPRING **Pool Name:** RED TANK; BONE SPRING

Is the proposed well in an area containing other mineral resources? USEABLE WATER

Operator Name: OXY USA INCORPORATED

Well Name: CORRAL GORGE 12-13 FEDERAL COM **Well Number:** 32H

Is the proposed well in an area containing other mineral resources? USEABLE WATER

Is the proposed well in a Helium production area? N **Use Existing Well Pad?** N **New surface disturbance?**

Type of Well Pad: MULTIPLE WELL **Multiple Well Pad Name:** Corral Gorge 12-13 FEDERAL COM **Number:** 31H

Well Class: HORIZONTAL **Number of Legs:** 1

Well Work Type: Drill

Well Type: OIL WELL

Describe Well Type:

Well sub-Type: INFILL

Describe sub-type:

Distance to town: 8 Miles **Distance to nearest well:** 35 FT **Distance to lease line:** 20 FT

Reservoir well spacing assigned acres Measurement: 640 Acres

Well plat: CorralGorge12_13FdCom32H_SitePlan_20191212094301.pdf

CorralGorge12_13FdCom32H_C102_20191212095628.pdf

Well work start Date: 10/19/2020 **Duration:** 20 DAYS

Section 3 - Well Location Table

Survey Type: RECTANGULAR

Describe Survey Type:

Datum: NAD83 **Vertical Datum:** NAVD88

Survey number: **Reference Datum:** GROUND LEVEL

Wellbore	NS-Foot	NS Indicator	EW-Foot	EW Indicator	Twsp	Range	Section	Aliquot/Lot/Tract	Latitude	Longitude	County	State	Meridian	Lease Type	Lease Number	Elevation	MD	TVD	Will this well produce from this lease?
SHL Leg #1	162	FNL	285	FWL	25S	29E	12	Aliquot NWNW	32.151502	-103.945688	EDDY	NEW MEXICO	NEW MEXICO	S	STATE	3076	0	0	N
KOP Leg #1	50	FNL	940	FWL	25S	29E	12	Aliquot NWNW	32.151823	-103.943573	EDDY	NEW MEXICO	NEW MEXICO	S	STATE	-6745	9903	9821	N

Operator Name: OXY USA INCORPORATED

Well Name: CORRAL GORGE 12-13 FEDERAL COM **Well Number:** 32H

Wellbore	NS-Foot	NS Indicator	EW-Foot	EW Indicator	Twsp	Range	Section	Aliquot/Lot/Tract	Latitude	Longitude	County	State	Meridian	Lease Type	Lease Number	Elevation	MD	TVD	Will this well produce from this lease?
PPP Leg #1-1	100	FNL	940	FWL	25S	29E	12	Aliquot NWNW	32.151685	-103.943573	EDDY	NEW MEXICO	NEW MEXICO	S	STATE	-7218	10703	10294	Y
PPP Leg #1-2	5	FNL	929	FWL	25S	29E	12	Aliquot SWSW	32.137364	-103.943547	EDDY	NEW MEXICO	NEW MEXICO	F	NMNM 015303	-2042	5118	5118	Y
EXIT Leg #1	100	FSL	940	FWL	25S	29E	13	Aliquot SWSW	32.123032	-103.94352	EDDY	NEW MEXICO	NEW MEXICO	F	NMNM 015303	-18051	21127	21127	Y
BHL Leg #1	20	FSL	940	FWL	25S	29E	13	Aliquot SWSW	32.122813	-103.94352	EDDY	NEW MEXICO	NEW MEXICO	F	NMNM 015303	-7218	21207	10294	Y

OXY USA INC.

SITE PLAN
CEDCAN 1201
FAA PERMIT: NO



NO.	WELL	FOOTAGE	LAT.	LONG.	ELEV.	ID#
1	CORRAL GORGE 12_13 FED COM #31H	162' FNL & 250' FWL	32.151501° N	103.945801° W	3074.5'	IP-SMS-2302
2	CORRAL GORGE 12_13 FED COM #32H	162' FNL & 285' FWL	32.151502° N	103.945688° W	3075.8'	IP-SMS-2303
3	CORRAL GORGE 12_13 FED COM #311H	162' FNL & 320' FWL	32.151502° N	103.945575° W	3076.1'	IP-SMS-2300

NOTES:

1) LATS & LONGS SHOWN HEREON ARE MERCATOR GRID AND CONFORM TO THE NEW MEXICO COORDINATE SYSTEM "NEW MEXICO EAST ZONE" NORTH AMERICAN DATUM 1983.

2) DISTANCES ARE GRID VALUES.

3) ALL FEATURES ARE EXISTING UNLESS OTHERWISE NOTED

CERTIFICATION
I, CHAD HARCROW, A NEW MEXICO REGISTERED PROFESSIONAL SURVEYOR CERTIFY THAT I DIRECTED AND AM RESPONSIBLE FOR THIS SURVEY, THAT THIS SURVEY IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.

CHAD HARCROW NEW MEXICO 17777 LICENSED PROFESSIONAL SURVEYOR

Chad Harcrow 08/22/19
CHAD HARCROW N.M.P.S. NO. 17777 DATE

HARCROW SURVEYING, LLC
2316 W. MAIN ST, ARTESIA, N.M. 88210
PH: (575) 746-2158
c.harcrow@harcrowsurveying.com

200 0 200 400 Feet
Scale: 1"=200'

OXY USA INC.	
SURVEY DATE: JULY 8, 2019	SITE PLAN
DRAFTING DATE: AUGUST 19, 2019	PAGE: 1 OF 1
APPROVED BY: CH / DRAWN BY: WN	FILE: 19-1246

APD ID: 10400052319 **Submission Date:** 12/20/2019

Operator Name: OXY USA INCORPORATED

Well Name: CORRAL GORGE 12-13 FEDERAL COM **Well Number:** 32H

Well Type: OIL WELL **Well Work Type:** Drill

Highlighted data reflects the most recent changes

Show Final Text

Section 1 - Geologic Formations

Formation ID	Formation Name	Elevation	True Vertical Depth	Measured Depth	Lithologies	Mineral Resources	Producing Formation
607789	RUSTLER	3076	348	348	ANHYDRITE, DOLOMITE, SHALE	USEABLE WATER	N
607790	SALADO	2329	747	747	ANHYDRITE, DOLOMITE, HALITE, SHALE	OTHER : Salt	N
607791	CASTILE	1355	1721	1721	ANHYDRITE	OTHER : Salt	N
607792	LAMAR	-190	3266	3266	LIMESTONE, SANDSTONE, SILTSTONE	NATURAL GAS, OIL, OTHER : Brine	N
607793	BELL CANYON	-199	3275	3275	SANDSTONE, SILTSTONE	NATURAL GAS, OIL, OTHER : Brine	N
607794	CHERRY CANYON	-1093	4169	4173	SANDSTONE, SILTSTONE	NATURAL GAS, OIL, OTHER : Brine	N
607795	BRUSHY CANYON	-2458	5534	5558	LIMESTONE, SANDSTONE, SILTSTONE	NATURAL GAS, OIL, OTHER : Brine	N
607796	BONE SPRING	-3976	7052	7100	LIMESTONE, SANDSTONE, SILTSTONE	NATURAL GAS, OIL	Y
607797	BONE SPRING 1ST	-4899	7975	8037	LIMESTONE, SANDSTONE, SILTSTONE	NATURAL GAS, OIL	Y
607798	BONE SPRING 2ND	-5751	8827	8902	LIMESTONE, SANDSTONE, SILTSTONE	NATURAL GAS, OIL	Y
607801	BONE SPRING 3RD	-6854	9930	10018	LIMESTONE, SANDSTONE, SILTSTONE	NATURAL GAS, OIL	Y
607802	WOLFCAMP	-7168	10244	10465	SANDSTONE, SILTSTONE	NATURAL GAS, OIL	Y

Section 2 - Blowout Prevention

Pressure Rating (PSI): 5M **Rating Depth:** 10294

Equipment: 13-5/8" 5M/10M Annular, Blind Ram, Double Ram

Requesting Variance? YES

Variance request: OXY requests a variance for the use of a flexible choke line from the BOP to Choke Manifold.

Testing Procedure: OXY will utilize a 5M annular with a 10M BOPE stack. The BOP/BOPE will be tested by an independent service company to 250 psi low and the high pressure indicated above per Onshore Order 2 requirements. The System may be upgraded to a higher pressure but still tested to the working pressure listed in the table above. If the system is upgraded

all the components installed will be functional and tested. Pipe rams will be operationally checked each 24 hour period. Blind rams will be operationally checked on each trip out of the hole. These checks will be noted on the daily tour sheets. Other accessories to the BOP equipment will include a Kelly cock and floor safety valve (inside BOP) and choke lines and choke manifold. A multibowl or a unionized multibowl wellhead system will be employed. The wellhead and connection to the BOPE will meet all API 6A requirements. The BOP will be tested per Onshore Order #2 after installation on the surface casing which will cover testing requirements for a maximum of 30 days. If any seal subject to test pressure is broken the system must be tested. We will test the flange connection of the wellhead with a test port that is directly in the flange. We are proposing that we will run the wellhead through the rotary prior to cementing surface casing as discussed with the BLM on October 8, 2015. BOP Break Testing Request OXY requests permission to adjust the BOP break testing requirements as per the agreement reached in the OXY/BLM meeting on September 5, 2019. A separate sundry will be sent prior to spud that reflects the pad based break testing plan. BOP break test under the following conditions: 1. After a full BOP test is conducted 2. When skidding to drill an intermediate section where ICP is set into the third Bone Spring or shallower. 3. When skidding to drill a production section that does not penetrate into the third Bone Spring or deeper. If the kill line is broken prior to skid, two tests will be performed. 1. Wellhead flange, co-flex hose, kill line connections and upper pipe rams 2. Wellhead flange, HCR valve, check valve, upper pipe rams If the kill line is not broken prior to skid, only one test will be performed. 1. Wellhead flange, co-flex hose, check valve, upper pipe rams

Choke Diagram Attachment:

CorralGorge12_13FdCom32H_ChkManifold_20191212153210.pdf

BOP Diagram Attachment:

CorralGorge12_13FdCom32H_BOP_20191212153254.pdf

CorralGorge12_13FdCom32H_FlexHoseCert_20191212153553.pdf

Section 3 - Casing

Casing ID	String Type	Hole Size	Csg Size	Condition	Standard	Tapered String	Top Set MD	Bottom Set MD	Top Set TVD	Bottom Set TVD	Top Set MSL	Bottom Set MSL	Calculated casing length MD	Grade	Weight	Joint Type	Collapse SF	Burst SF	Joint SF Type	Joint SF	Body SF Type	Body SF
1	SURFACE	14.75	10.75	NEW	API	N	0	687	0	687	3076	2389	687	J-55	40.5	BUTT	1.125	1.2	BUOY	1.4	BUOY	1.4
2	INTERMEDIATE	9.875	7.625	NEW	API	N	0	9803	0	9719	3101	-6643	9803	HCL-80	26.4	BUTT	1.125	1.2	BUOY	1.4	BUOY	1.4
3	PRODUCTION	6.75	5.5	NEW	API	N	0	21207	0	10435	3101	-7359	21207	P-110	20	OTHER - DQX/SFWT ORQ/DQWT ORQ	1.125	1.2	BUOY	1.4	BUOY	1.4

Casing Attachments

Operator Name: OXY USA INCORPORATED

Well Name: CORRAL GORGE 12-13 FEDERAL COM **Well Number:** 32H

Casing Attachments

Casing ID: 1 **String Type:** SURFACE

Inspection Document:

Spec Document:

Tapered String Spec:

Casing Design Assumptions and Worksheet(s):

CorralGorge12_13FdCom32H_CsgCriteria_20191212153926.pdf

Casing ID: 2 **String Type:** INTERMEDIATE

Inspection Document:

Spec Document:

Tapered String Spec:

Casing Design Assumptions and Worksheet(s):

CorralGorge12_13FdCom32H_CsgCriteria_20191212154033.pdf

Casing ID: 3 **String Type:** PRODUCTION

Inspection Document:

Spec Document:

Tapered String Spec:

Casing Design Assumptions and Worksheet(s):

CorralGorge12_13FdCom32H_5.5_20_P110CY_TMKUPDQWTORQ_20191212154317.pdf

CorralGorge12_13FdCom32H_5.5_20_P110_DQX_20191212154330.pdf

CorralGorge12_13FdCom32H_5.5_20_P110HC_TMKUPSFTORQ_20191212154346.pdf

CorralGorge12_13FdCom32H_CsgCriteria_20191212154402.pdf

Operator Name: OXY USA INCORPORATED

Well Name: CORRAL GORGE 12-13 FEDERAL COM **Well Number:** 32H

Section 4 - Cement

String Type	Lead/Tail	Stage Tool Depth	Top MD	Bottom MD	Quantity(sx)	Yield	Density	Cu Ft	Excess%	Cement type	Additives
SURFACE	Lead		0	687	561	1.33	14.8	746	100	Cl C	Accelerator
INTERMEDIATE	Lead		0	5784	711	1.92	12.9	1365	10	Cl C	Accelerator
INTERMEDIATE	Tail		5784	9803	557	1.65	13.2	919	5	Cl H	Retarder, Dispersant, Salt
PRODUCTION	Lead		9303	21207	873	1.38	13.2	1205	20	Cl H	Retarder, Dispersant, Salt

Section 5 - Circulating Medium

Mud System Type: Closed

Will an air or gas system be Used? NO

Description of the equipment for the circulating system in accordance with Onshore Order #2:

Diagram of the equipment for the circulating system in accordance with Onshore Order #2:

Describe what will be on location to control well or mitigate other conditions: Sufficient mud materials to maintain mud properties and meet minimum lost circulation and weight increase requirements will be kept on location at all times. The following is a general list of products: Barite, Bentonite, Gypsum, Lime, Soda Ash, Caustic Soda, Nut Plug, Cedar Fiber, Cotton Seed Hulls, Drilling Paper, Salt Water Clay, CACL2.
Describe the mud monitoring system utilized: PVT/MD Totco/Visual Monitoring

Circulating Medium Table

Top Depth	Bottom Depth	Mud Type	Min Weight (lbs/gal)	Max Weight (lbs/gal)	Density (lbs/cu ft)	Gel Strength (lbs/100 sqft)	PH	Viscosity (CP)	Salinity (ppm)	Filtration (cc)	Additional Characteristics

Operator Name: OXY USA INCORPORATED

Well Name: CORRAL GORGE 12-13 FEDERAL COM **Well Number:** 32H

Top Depth	Bottom Depth	Mud Type	Min Weight (lbs/gal)	Max Weight (lbs/gal)	Density (lbs/cu ft)	Gel Strength (lbs/100 sqft)	PH	Viscosity (CP)	Salinity (ppm)	Filtration (cc)	Additional Characteristics
0	687	WATER-BASED MUD	8.6	8.8							
687	9803	OTHER : Saturated Brine Based Mud and/or Water Based and/or Oil Based Mud	8	10							
9803	21207	OTHER : Water Based and/or Oil Based Mud	9.5	12							

Section 6 - Test, Logging, Coring

List of production tests including testing procedures, equipment and safety measures:

GR from TD to surface (horizontal well - vertical portion of hole). Mud log from intermediate casing shoe to TD.

List of open and cased hole logs run in the well:

GAMMA RAY LOG,MUD LOG/GEOLOGICAL LITHOLOGY LOG,

Coring operation description for the well:

No coring is planned at this time.

Section 7 - Pressure

Anticipated Bottom Hole Pressure: 6424 **Anticipated Surface Pressure:** 1776

Anticipated Bottom Hole Temperature(F): 163

Anticipated abnormal pressures, temperatures, or potential geologic hazards? NO

Describe:

Contingency Plans geoharzards description:

Contingency Plans geohazards attachment:

Hydrogen Sulfide drilling operations plan required? YES

Hydrogen sulfide drilling operations plan:

CorralGorge12_13FdCom32H_H2S1_20191212162451.pdf

CorralGorge12_13FdCom32H_H2S2_20191212162504.pdf

CorralGorge12_13FdCom32H_H2S3ECL_20191212162517.pdf

Section 8 - Other Information

Proposed horizontal/directional/multi-lateral plan submission:

CorralGorge12_13FdCom32H_DirectPlot_20191212163127.pdf

CorralGorge12_13FdCom32H_DirectPlan_20191212163200.pdf

Other proposed operations facets description:

OXY requests the option to set casing shallower yet still below the salts if losses or hole conditions require this. Cement volumes may be adjusted if casing is set shallower and a DV tool may be run in case hole conditions merit pumping a second stage cement job to comply with permitted top of cement. If cement circulated to surface during first stage, we will drop a cancelation cone and not pump the second stage.

OXY requests the option to run production casing with DQX, SF TORQ, and/or DQW TORQ connections to accommodate hole conditions or drilling operations.

OXY requests to pump a two stage Intermediate casing cement job with the first stage being pumped conventionally with the calculated TOC @ the Brushy Canyon and the second stage performed as a bradenhead squeeze with planned cement from the top of the Brushy Canyon to Surface.

OXY requests a variance to cement the 7-5/8" intermediate casing string offline, see attached for additional information.

OXY requests permission to adjust the CBL requirement after bradenhead cement jobs, on 7-5/8 intermediate casings, as per the agreement reached in the OXY/BLM meeting on September 5, 2019.
Three string wells:
1. CBL will be required on one well per pad
2. If the pumped volume of cement is less than permitted in the APD, BLM will be notified and a CBL may be run
3. Echometer will be used after bradenhead cement job to determine TOC before pumping top-out cement

Annular Clearance Variance Request
As per the agreement reached in the OXY/BLM meeting on Feb 22, 2018, OXY requests permission to allow deviation from the 0.422 annular clearance requirement from Onshore Order #2 under the following conditions:
1. Annular clearance to meet or exceed 0.422 between intermediate casing ID and production casing coupling only on the first 500 overlap between both casings.
2. Annular clearance less than 0.422 is acceptable for the curve and lateral portions of the production open hole section.

Well will be drilled with a walking/skidding operation. Plan to drill the multiple well pad in batch by section: all surface sections, intermediate sections and production sections. The wellhead will be secured with a night cap whenever the rig is not over the well.

OXY requests the option to contract a Surface Rig to drill, set surface casing, and cement for this well. If the timing between rigs is such that OXY would not be able to preset surface, the Primary Rig will MIRU and drill the well in its entirety per the APD. See attached for additional spudder rig information.

Other proposed operations facets attachment:

CorralGorge12_13FdCom32H_DrillPlan_20191212163627.pdf

CorralGorge12_13FdCom32H_GasCapPlan_20191212163638.pdf

CorralGorge12_13FdCom32H_SpudRigData_20191212163651.pdf

Operator Name: OXY USA INCORPORATED

Well Name: CORRAL GORGE 12-13 FEDERAL COM **Well Number:** 32H

Other Variance attachment:

CorralGorge12_13FdCom32H_OfflineCmtgDetail_20191212163727.pdf

Permian Drilling
Hydrogen Sulfide Drilling Operations Plan
Corral Gorge 12-13 Federal Com 32H

Open drill site. No homes or buildings are near the proposed location.

1. Escape

   Personnel shall escape upwind of wellbore in the event of an emergency gas release. Escape can take place through the lease road on the Southeast side of the location. Personnel need to move to a safe distance and block the entrance to location. If the primary route is not an option due to the wind direction, then a secondary egress route should be taken.

▲ H2S Detectors. At least three detectors will be installed: bell nipple, rig floor and Shakers.

● Briefing Areas. At least two briefing areas will be placed, 90 deg off.

■ Wind direction indicators. Visible from rig floor and from the mud pits area.

A gas buster is connected to both the choke manifold and flowline outlets.



WIND: Prevailing winds are from the Southwest

Permian Drilling
Hydrogen Sulfide Drilling Operations Plan
New Mexico

Scope

This contingency plan establishes guidelines for the public, all company employees, and contract employees who's work activities may involve exposure to hydrogen sulfide (H2S) gas.
While drilling this well, it is possible to encounter H2S bearing formations. At all times, the first barrier to control H2S emissions will be the drilling fluid, which will have a density high enough to control influx.

Objective

1. Provide an immediate and predetermined response plan to any condition when H2S is detected. All H2S detections in excess of 10 parts per million (ppm) concentration are considered an Emergency.

2. Prevent any and all accidents, and prevent the uncontrolled release of hydrogen sulfide into the atmosphere.

3. Provide proper evacuation procedures to cope with emergencies.

4. Provide immediate and adequate medical attention should an injury occur.

Discussion

Implementation:	This plan with all details is to be fully implemented before drilling to commence.
Emergency response Procedure:	This section outlines the conditions and denotes steps to be taken in the event of an emergency.
Emergency equipment Procedure:	This section outlines the safety and emergency equipment that will be required for the drilling of this well.
Training provisions:	This section outlines the training provisions that must be adhered to prior to drilling.
Drilling emergency call lists:	Included are the telephone numbers of all persons to be contacted should an emergency exist.
Briefing:	This section deals with the briefing of all people involved in the drilling operation.
Public safety:	Public safety personnel will be made aware of any potential evacuation and any additional support needed.
Check lists:	Status check lists and procedural check lists have been included to insure adherence to the plan.
General information:	A general information section has been included to supply support information.

Hydrogen Sulfide Training

All personnel, whether regularly assigned, contracted, or employed on an unscheduled basis, will receive training from a qualified instructor in the following areas prior to commencing drilling operations on the well:

1. The hazards and characteristics of H2S.
2. Proper use and maintenance of personal protective equipment and life support systems.
3. H2S detection.
4. Proper use of H2S detectors, alarms, warning systems, briefing areas, evacuation procedures and prevailing winds.
5. Proper techniques for first aid and rescue procedures.
6. Physical effects of hydrogen sulfide on the human body.
7. Toxicity of hydrogen sulfide and sulfur dioxide.
8. Use of SCBA and supplied air equipment.
9. First aid and artificial respiration.
10. Emergency rescue.

In addition, supervisory personnel will be trained in the following areas:

1. The effects of H2S on metal components. If high tensile strength tubular is to be used, personnel will be trained in their special maintenance requirements.
2. Corrective action and shut-in procedures when drilling a well, blowout prevention and well control procedures.
3. The contents and requirements of the H2S Drilling Operations Plan.

H2S training refresher must have been taken within one year prior to drilling the well. Specifics on the well to be drilled will be discussed during the pre-spud meeting. H2S and well control (choke) drills will be performed while drilling the well, at least on a weekly basis. This plan shall be available in the well site. All personnel will be required to carry the documentation proving that the H2S training has been taken.

Service company and visiting personnel

A. Each service company that will be on this well will be notified if the zone contains H2S.

B. Each service company must provide for the training and equipment of their employees before they arrive at the well site.

C. Each service company will be expected to attend a well site briefing

Emergency Equipment Requirements

1. Well control equipment

The well shall have hydraulic BOP equipment for the anticipated pressures. Equipment is to be tested on installation and follow Oxy Well Control standard, as well as BLM Onshore Order #2.

Special control equipment:

A. Hydraulic BOP equipment with remote control on ground. Remotely operated choke.
B. Rotating head
C. Gas buster equipment shall be installed before drilling out of surface pipe.

2. Protective equipment for personnel

A. Four (4) 30-minute positive pressure air packs (2 at each briefing area) on location.

B. Adequate fire extinguishers shall be located at strategic locations.

C. Radio / cell telephone communication will be available at the rig.

- Rig floor and trailers.
- Vehicle.

3. Hydrogen sulfide sensors and alarms

A. H2S sensor with alarms will be located on the rig floor, at the bell nipple, and at the flow line. These monitors will be set to alarm at 10 ppm with strobe light, and audible alarm.
B. Hand operated detectors with tubes.
C. H2S monitor tester (to be provided by contract Safety Company.)
D. There shall be one combustible gas detector on location at all times.

4. Visual Warning Systems

A. One sign located at each location entrance with the following language:

Caution – potential poison gas
Hydrogen sulfide
No admittance without authorization

Wind sock – wind streamers:

A. One 36” (in length) wind sock located at protection center, at height visible from rig floor.
B. One 36” (in length) wind sock located at height visible from pit areas.

Condition flags

A. One each condition flag to be displayed to denote conditions.

green – normal conditions
yellow – potential danger
red – danger, H2S present

B. Condition flag shall be posted at each location sign entrance.

5. Mud Program

The mud program is designed to minimize the risk of having H2S and other formation fluids at surface. Proper mud weight and safe drilling practices will be applied. H2S scavengers will be used to minimize the hazards while drilling. Below is a summary of the drilling program.

Mud inspection devices:

Garrett gas train or hatch tester for inspection of sulfide concentration in mud system.

6. Metallurgy

A. Drill string, casing, tubing, wellhead, blowout preventers, drilling spools or adapters, kill lines, choke manifold, lines and valves shall be suitable for the H2S service.
B. All the elastomers, packing, seals and ring gaskets shall be suitable for H2S service.

7. Well Testing

No drill stem test will be performed on this well.

8. Evacuation plan

Evacuation routes should be established prior to well spud for each well and discussed with all rig personnel.

9. Designated area

A. Parking and visitor area: all vehicles are to be parked at a predetermined safe distance from the wellhead.
B. There will be a designated smoking area.
C. Two briefing areas on either side of the location at the maximum allowable distance from the well bore so they offset prevailing winds perpendicularly, or at a 45-degree angle if wind direction tends to shift in the area.

Emergency procedures

A. In the event of any evidence of H2S level above 10 ppm, take the following steps:

1. The Driller will pick up off bottom, shut down the pumps, slow down the pipe rotation.

2. Secure and don escape breathing equipment, report to the upwind designated safe briefing / muster area.

3. All personnel on location will be accounted for and emergency search should begin for any missing, the Buddy System will be implemented.

4. Order non-essential personnel to leave the well site, order all essential personnel out of the danger zone and upwind to the nearest designated safe briefing / muster area.

5. Entrance to the location will be secured to a higher level than our usual "Meet and Greet" requirement, and the proper condition flag will be displayed at the entrance to the location.

6. Take steps to determine if the H2S level can be corrected or suppressed and, if so, proceed as required.

B. If uncontrollable conditions occur:

1. Take steps to protect and/or remove any public in the down-wind area from the rig – partial evacuation and isolation. Notify necessary public safety personnel and appropriate regulatory entities (i.e. BLM) of the situation.

2. Remove all personnel to the nearest upwind designated safe briefing / muster area or off location.

3. Notify public safety personnel of safe briefing / muster area.

4. An assigned crew member will blockade the entrance to the location. No unauthorized personnel will be allowed entry to the location.

5. Proceed with best plan (at the time) to regain control of the well. Maintain tight security and safety procedures.

C. Responsibility:

1. Designated personnel.

a. Shall be responsible for the total implementation of this plan.
b. Shall be in complete command during any emergency.
c. Shall designate a back-up.

All personnel:	1.	On alarm, don escape unit and report to the nearest upwind designated safe briefing / muster area upw
	2.	Check status of personnel (buddy system).
	3.	Secure breathing equipment.
	4.	Await orders from supervisor.
Drill site manager:	1.	Don escape unit if necessary and report to nearest upwind designated safe briefing / muster area.
	2.	Coordinate preparations of individuals to return to point of release with tool pusher and driller (using the buddy system).
	3.	Determine H2S concentrations.
	4.	Assess situation and take control measures.
Tool pusher:	1.	Don escape unit Report to up nearest upwind designated safe briefing / muster area.
	2.	Coordinate preparation of individuals to return to point of release with tool pusher drill site manager (using the buddy system).
	3.	Determine H2S concentration.
	4.	Assess situation and take control measures.
Driller:	1.	Don escape unit, shut down pumps, continue

		rotating DP.
	2.	Check monitor for point of release.
	3.	Report to nearest upwind designated safe briefing / muster area.
	4.	Check status of personnel (in an attempt to rescue, use the buddy system).
	5.	Assigns least essential person to notify Drill Site Manager and tool pusher by quickest means in case of their absence.
	6.	Assumes the responsibilities of the Drill Site Manager and tool pusher until they arrive should they be absent.
Derrick man Floor man #1 Floor man #2	1.	Will remain in briefing / muster area until instructed by supervisor.
Mud engineer:	1.	Report to nearest upwind designated safe briefing / muster area.
	2.	When instructed, begin check of mud for ph and H2S level. (Garett gas train.)
Safety personnel:	1.	Mask up and check status of all personnel and secure operations as instructed by drill site manager.

Taking a kick

When taking a kick during an H2S emergency, all personnel will follow standard Well control procedures after reporting to briefing area and masking up.

Open-hole logging

All unnecessary personnel off floor. Drill Site Manager and safety personnel should monitor condition, advise status and determine need for use of air equipment.

Running casing or plugging

Following the same "tripping" procedure as above. Drill Site Manager and safety personnel should determine if all personnel have access to protective equipment.

Ignition procedures

The decision to ignite the well is the responsibility of the operator (Oxy Drilling Management). The decision should be made only as a last resort and in a situation where it is clear that:

1. Human life and property are endangered.
2. There is no hope controlling the blowout under the prevailing conditions at the well.

Instructions for igniting the well

1. Two people are required for the actual igniting operation. They must wear self-contained breathing units and have a safety rope attached. One man (tool pusher or safety engineer) will check the atmosphere for explosive gases with the gas monitor. The other man is responsible for igniting the well.
2. Primary method to ignite: 25 mm flare gun with range of approximately 500 feet.
3. Ignite upwind and do not approach any closer than is warranted.
4. Select the ignition site best for protection, and which offers an easy escape route.
5. Before firing, check for presence of combustible gas.
6. After lighting, continue emergency action and procedure as before.
7. All unassigned personnel will remain in briefing area until instructed by supervisor or directed by the Drill Site Manager.

Remember: After well is ignited, burning hydrogen sulfide will convert to sulfur dioxide, which is also highly toxic. **Do not assume the area is safe after the well is ignited.**

Status check list

Note: All items on this list must be completed before drilling to production casing point.

1. H2S sign at location entrance.
2. Two (2) wind socks located as required.
3. Four (4) 30-minute positive pressure air packs (2 at each Briefing area) on location for all rig personnel and mud loggers.
4. Air packs inspected and ready for use.
5. Cascade system and hose line hook-up as needed.
6. Cascade system for refilling air bottles as needed.
7. Condition flag on location and ready for use.
8. H2S detection system hooked up and tested.
9. H2S alarm system hooked up and tested.
10. Hand operated H2S detector with tubes on location.
11. 1 – 100' length of nylon rope on location.
12. All rig crew and supervisors trained as required.
13. All outside service contractors advised of potential H2S hazard on well.
14. No smoking sign posted and a designated smoking area identified.
15. Calibration of all H2S equipment shall be noted on the IADC report.

Checked by:_____ Date:_____

Procedural check list during H2S events

Perform each tour:

1. Check fire extinguishers to see that they have the proper charge.

2. Check breathing equipment to ensure that it in proper working order.

3. Make sure all the H2S detection system is operative.

Perform each week:

1. Check each piece of breathing equipment to make sure that demand or forced air regulator is working. This requires that the bottle be opened and the mask assembly be put on tight enough so that when you inhale, you receive air or feel air flow.

2. BOP skills (well control drills).

3. Check supply pressure on BOP accumulator stand by source.

4. Check breathing equipment mask assembly to see that straps are loosened and turned back, ready to put on.

5. Check pressure on breathing equipment air bottles to make sure they are charged to full volume. (Air quality checked for proper air grade "D" before bringing to location)

6. Confirm pressure on all supply air bottles.

7. Perform breathing equipment drills with on-site personnel.

8. Check the following supplies for availability.

    A. Emergency telephone list.
    B. Hand operated H2S detectors and tubes.

General evacuation plan

1. When the company approved supervisor (Drill Site Manager, consultant, rig pusher, or driller) determines the H2S gas cannot be limited to the well location and the public will be involved, he will activate the evacuation plan.

2. Drill Site Manager or designee will notify local government agency that a hazardous condition exists and evacuation needs to be implemented.

3. Company or contractor safety personnel that have been trained in the use of H2S detection equipment and self-contained breathing equipment will monitor H2S concentrations, wind directions, and area of exposure. They will delineate the outer perimeter of the hazardous gas area. Extension to the evacuation area will be determined from information gathered.

4. Law enforcement personnel (state police, police dept., fire dept., and sheriff's dept.) Will be called to aid in setting up and maintaining road blocks. Also, they will aid in evacuation of the public if necessary.

5. After the discharge of gas has been controlled, company safety personnel will determine when the area is safe for re-entry.

Important: Law enforcement personnel will not be asked to come into a contaminated area. Their assistance will be limited to uncontaminated areas. Constant radio contact will be maintained with them.

Emergency actions

Well blowout – if emergency

1. Evacuate all personnel to "Safe Briefing / Muster Areas" or off location if needed.

2. If sour gas – evacuate rig personnel.

3. If sour gas – evacuate public within 3000 ft radius of exposure.

4. Don SCBA and shut well in if possible using the buddy system.

5. Notify Drilling Superintendent and call 911 for emergency help (fire dept and ambulance) if needed.
6. Implement the Blowout Contingency Plan, and Drilling Emergency Action Plan.

6. Give first aid as needed.

Person down location/facility

1. If immediately possible, contact 911. Give location and wait for confirmation.

2. Don SCBA and perform rescue operation using buddy system.

Toxic effects of hydrogen sulfide

Hydrogen sulfide is extremely toxic. The acceptable ceiling concentration for eight-hour exposure is 10 ppm, which is .001% by volume. Hydrogen sulfide is heavier than air (specific gravity – 1.192) and colorless. It forms an explosive mixture with air between 4.3 and 46.0 percent by volume. Hydrogen sulfide is almost as toxic as hydrogen cyanide and is between five and six times more toxic than carbon monoxide. Toxicity data for hydrogen sulfide and various other gases are compared in table i. Physical effects at various hydrogen sulfide exposure levels are shown in table ii.

Table i
Toxicity of various gases

Common name	Chemical formula	Specific gravity (sc=1)	Threshold limit (1)	Hazardous limit (2)	Lethal concentration (3)
Hydrogen Cyanide	Hcn	0.94	10 ppm	150 ppm/hr	300 ppm
Hydrogen Sulfide	H2S	1.18	10 ppm	250 ppm/hr	600 ppm
Sulfur Dioxide	So2	2.21	5 ppm	-	1000 ppm
Chlorine	Cl2	2.45	1 ppm	4 ppm/hr	1000 ppm
Carbon Monoxide	Co	0.97	50 ppm	400 ppm/hr	1000 ppm
Carbon Dioxide	Co2	1.52	5000 ppm	5%	10%
Methane	Ch4	0.55	90,000 ppm	Combustible above 5% in air	

1) threshold limit – concentration at which it is believed that all workers may be repeatedly exposed day after day without adverse effects.

2) hazardous limit – concentration that will cause death with short-term exposure.

3) lethal concentration – concentration that will cause death with short-term exposure.

Toxic effects of hydrogen sulfide

Table ii
Physical effects of hydrogen sulfide

Percent (%)	Ppm	Concentration Grains 100 std. Ft3*	Physical effects
0.001	<10	00.65	Obvious and unpleasant odor.

0.002	10	01.30	Safe for 8 hours of exposure.
0.010	100	06.48	Kill smell in 3 – 15 minutes. May sting eyes and throat.
0.020	200	12.96	Kills smell shortly; stings eyes and throat.
0.050	500	32.96	Dizziness; breathing ceases in a few minutes; needs prompt artificial respiration.
0.070	700	45.36	Unconscious quickly; death will result if not rescued promptly.
0.100	1000	64.30	Unconscious at once; followed by death within minutes.

*at 15.00 psia and 60’f.

Use of self-contained breathing equipment (SCBA)

1. Written procedures shall be prepared covering safe use of SCBA's in dangerous atmosphere, which might be encountered in normal operations or in emergencies. Personnel shall be familiar with these procedures and the available SCBA.

2 SCBA's shall be inspected frequently at random to insure that they are properly used, cleaned, and maintained.

3. Anyone who may use the SCBA's shall be trained in how to insure proper face-piece to face seal. They shall wear SCBA's in normal air and then wear them in a test atmosphere. (note: such items as facial hair {beard or sideburns} and eyeglasses will not allow proper seal.) Anyone that may be reasonably expected to wear SCBA's should have these items removed before entering a toxic atmosphere. A special mask must be obtained for anyone who must wear eyeglasses or contact lenses.

4. Maintenance and care of SCBA's:

    a. A program for maintenance and care of SCBA's shall include the following:
        1. Inspection for defects, including leak checks.
        2. Cleaning and disinfecting.
        3. Repair.
        4. Storage.

    b. Inspection, self-contained breathing apparatus for emergency use shall be inspected monthly.
        1. Fully charged cylinders.
        2. Regulator and warning device operation.
        3. Condition of face piece and connections.
        4. Rubber parts shall be maintained to keep them pliable and prevent deterioration.

    c. Routinely used SCBA's shall be collected, cleaned and disinfected as frequently as necessary to insure proper protection is provided.

5. Persons assigned tasks that requires use of self-contained breathing equipment shall be certified physically fit (medically cleared) for breathing equipment usage at least annually.

6. SCBA's should be worn when:

    A. Any employee works near the top or on top of any tank unless test reveals less than 10 ppm of H2S.

B. When breaking out any line where H2S can reasonably be expected.

C. When sampling air in areas to determine if toxic concentrations of H2S exists.

D. When working in areas where over 10 ppm H2S has been detected.

E. At any time there is a doubt as to the H2S level in the area to be entered.

Rescue
First aid for H2S poisoning

Do not panic!

Remain calm – think!

1. Don SCBA breathing equipment.

2. Remove victim(s) utilizing buddy system to fresh air as quickly as possible. (go up-wind from source or at right angle to the wind. Not down wind.)

3. Briefly apply chest pressure – arm lift method of artificial respiration to clean the victim's lungs and to avoid inhaling any toxic gas directly from the victim's lungs.

4. Provide for prompt transportation to the hospital, and continue giving artificial respiration if needed.

5. Hospital(s) or medical facilities need to be informed, before-hand, of the possibility of H2S gas poisoning – no matter how remote the possibility is.

6. Notify emergency room personnel that the victim(s) has been exposed to H2S gas.

Besides basic first aid, everyone on location should have a good working knowledge of artificial respiration.

Revised CM 6/27/2012

OXY Permian Delaware NM Basin Drilling & Completions Incident Reporting

OXY Permian Crisis Team Hotline Notification

Person	Location	Office Phone	Cell/Mobile Phone
Drilling & Completions Department			
Drilling & Completions Manager: John Willis	Houston	(713) 366-5556	(713) 259-1417
Drilling Superintendent: Simon Benavides	Houston	(713) 215-7403	(832) 528-3547
Completions Superintendent: Chris Winter	Houston	(713) 366-5212	(806) 239-8774
Drilling Eng. Supervisor: Diego Tellez	Houston	(713) 350-4602	(713) 303-4932
Drilling Eng. Supervisor: Randy Neel	Houston	(713) 215-7987	(713) 517-5544
Completions Eng. Supervisor: Evan Hinkel	Houston	(713) 366-5436	(281) 236-6153
Drilling & Completions HES Lead. Ryan Green	Houston	713-336-5753	281-520-5216
Drilling & Completions HES Advisor:Kenny Williams	Carlsbad	(432) 686-1434	(337) 208-0911
Drilling & Completions HES Advisor:Kyle Holden	Carlsbad	(432) 686-1435	(661) 369-5328
Drilling & Completions HES Advisor Sr:Dave Schmidt	Carlsbad		(559) 310-8572
Drilling & Completions HES Advisor. :Seth Doyle	Carlsbad		(337) 499-0756
HES / Enviromental & Regulatory Department	Location	Office	Cell Phone
Jon Hamil-HES Manager	Houston	(713) 497-2494	(832) 537-9885
Mark Birk-HES Manager	Houston	(713) 350-4615	(949) 413-3127
Austin Tramell	Midland	(432) 699-4208	(575) 499-4919
Rico Munoz	Midland	(432) 699-8366	(432) 803-4116
Amber DuckWorth	Midland		(832) 966-1879
Kelley Montgomery- Regulatory Manager	Houston	(713) 366-5716	(832) 454-8137
Sandra Musallam -Regulatory Lead	Houston	+1 (713) 366-5106	+1 (713) 504-8577
Bishop, Steve-DOT Pipeline Coordinator	Midland	432-685-5614	
Wilson, Dusty-Safety Advisor	Midland	432-685-5771	(432) 254-2336
John W Dittrich Eniromental Advisor	Midland		(575) 390-2828
William (Jack) Calhoun-Environmental Lead	Houston	+713 (350) 4906	(281) 917-8571
Robert Barrow-Risk Engineer Manager	Houston	(713) 366-5611	(832) 867-5336
Sarah Holmes-HSE Cordinator	Midland	432-685-5758	
Administrative	Location	Office	
Sarah Holmes	Midland	432-685-5830	
Robertson, Debbie	Midland	432-685-5812	
Laci Hollaway	Midland	(432) 685-5716	(432) 631-6341
Administrative	Location	Office	
Rosalinda Escajeda	Midland	432-685-5831	

Person	Location	Office Phone	Cell/Mobile Phone
Moreno, Leslie (contract)	Hobbs	575-397-8247	
Sehon, Angela (contractor)	Levelland	806-894-8347	
Vasquez, Claudia (contractor)	North Cowden	432-385-3120	
XstremeMD	Location	Office	
Medical Case Management	Orla, TX	(337) 205-9314	
Axiom Medical Consulting	Location	Office	
Medical Case Management		(877) 502-9466	
Regulatory Agencies			
Bureau of Land Management	Carlsbad, NM	(505) 887-6544	
Bureau of Land Management	Hobbs, NM	(505) 393-3612	
Bureau of Land Management	Roswell, NM	(505) 393-3612	
Bureau of Land Management	Santa Fe, NM	(505) 988-6030	
DOT Juisdictional Pipelines-Incident Reporting New Mexico Public Regulaion Commission	Santa Fe, NM	(505) 827-3549 (505) 490-2375	
DOT Juisdictional Pipelines-Incident Reporting Texas Railroad Commission	Austin, TX	(512) 463-6788	
EPA Hot Line	Dallas, Texas	(214) 665-6444	
Federal OSHA, Area Office	Lubbock, Texas	(806) 472-7681	
National Response Center	Washington, D. C.	(800) 424-8802	
National Infrastructure Coordinator Center		(202) 282-9201	
New Mexico Air Quality Bureau	Santa Fe, NM	(505) 827-1494	
New Mexico Oil Conservation Division	Artesia, NM	(505) 748-1283	After Hours (505) 370-7545
New Mexico Oil Conservation Division	Hobbs, NM	(505) 393-6161	
New Mexico Oil Conservation Division	Santa Fe, NM	(505) 471-1068	
New Mexico OCD Environmental Bureau	Santa Fe, NM	(505) 476-3470	
New Mexico Environmental Department	Hobbs, NM	(505) 827-9329	
NM State Emergency Response Center	Santa Fe, NM	(505) 827-9222	
Railroad Commission of TX	District 1 San Antonio,	(210) 227-1313	
Railroad Commission of TX	District 7C San Angelo	(325) 657-7450	
Railroad Commission of TX	District 8, 8A Midland,	(432) 684-5581	
Texas Emergency Response Center	Austin, TX	(512) 463-7727	
TCEQ Air	Region 2 Lubbock, TX	(806) 796-3494	
TCEQ Water/Waste/Air	Region 3 Abilene, TX	(325) 698-9674	
TCEQ Water/Waste/Air	Region 7 Midland, TX	(432) 570-1359	
TCEQ Water/Waste/Air	Region 9 San Antonio,	(512) 734-7981	
TCEQ Water/Waste/Air	Region 8 San Angelo	(325) 655-9479	
Medical Facilities			
Abernathy Medical Clinic	Abernathy, TX	(806) 298-2524	
Alliance Hospital	Odessa, TX	(432) 550-1000	
Artesia General Hospital	Artesia, NM	(505) 748-3333	
Brownfield Regional Medical Center	Brownfield, TX	(806) 637-3551	

Person	Location	Office Phone	Cell/Mobile Phone
Cogdell Memorial Hospital	Snyder, TX	(325) 573-6374	
Covenant Hospital Levelland	Levelland, TX	(806) 894-4963	
Covenant Medical Center	Lubbock, TX	(806) 725-1011	
Covenant Medical Center Lakeside	Lubbock, TX	(806) 725-6000	
Covenant Family Health	Synder, TX	(325) 573-1300	
Crockett County Hospital	Ozona, TX	(325) 392-2671	
Guadalupe Medical Center	Carlsbad, NM	(505) 887-6633	
Lea Regional Hospital	Hobbs, NM	(505) 492-5000	
McCamey Hospital	McCamey, TX	(432) 652-8626	
Medical Arts Hospital	Lamesa, TX	(806) 872-2183	
Medical Center Hospital	Odessa, TX	(432) 640-4000	
Medi Center Hospital	San Angelo, TX	(325) 653-6741	
Memorial Hospital	Ft. Stockton	(432) 336-2241	
Memorial Hospital	Seminole, TX	(432) 758-5811	
Midland Memorial Hospital	Midland, TX	(432) 685-1111	
Nor-Lea General Hospital	Lovington, NM	(505) 396-6611	
Odessa Regional Hospital	Odessa, TX	(432) 334-8200	
Permian General Hospital	Andrews, TX	(432) 523-2200	
Reagan County Hospital	Big Lake, TX	(325) 884-2561	
Reeves County Hospital	Pecos, TX	(432) 447-3551	
Shannon Medical Center	San Angelo, TX	(325) 653-6741	
Union County General Hospital	Clayton, NM	(505) 374-2585	
University Medical Center	Lubbock, TX	(806) 725-8200	
Val Verde Regional Medical Center	Del Rio, TX	(830) 775-8566	
Ward Memorial Hospital	Monahans, TX	(432) 943-2511	
Yoakum County Hospital	Denver City, TX	(806) 592-5484	
Law Enforcement - Sheriff			
Andrews Cty Sheriff's Department	Andrews County(Andr	(432) 523-5545	
Crane Cty Sheriff's Department	Crane, County (Crane)	(432) 558-3571	
Crockett Cty Sheriff's Department	Crockett County (Ozor	(325) 392-2661	
Dawson Cty Sheriff's Department	Dawson County (Lame	(806) 872-7560	
Ector Cty Sheriff's Department	Ector County (Odessa)	(432) 335-3050	
Eddy Cty Sheriff's Department	Eddy County (Artesia)	(505) 746-2704	
Eddy Cty Sheriff's Department	Eddy County (Carlsbac	(505) 887-7551	
Gaines Cty Sheriff's Department	Gaines County (Semin	(432) 758-9871	
Hockley Cty Sheriff's Department	Hockley County(Level	(806) 894-3126	
Kent Cty (Jayton City Sheriff's Dept.)	Kent County(Jayton)	(806) 237-3801	
Lea Cty Sheriff's Department	Lea County (Eunice)	(505) 384-2020	
Lea Cty Sheriff's Department	Lea County (Hobbs)	(505) 393-2515	
Lea Cty Sheriff's Department	Lea County (Lovingtor	(505) 396-3611	
Lubbock Cty Sheriff's Department	Lubbock Cty (Abernat	(806) 296-2724	
Midland Cty Sheriff's Department	Midland County (Midl	(432) 688-1277	

Person	Location	Office Phone	Cell/Mobile Phone
Pecos Cty Sheriff's Department	Pecos County (Iraan)	(432) 639-2251	
Reeves Cty Sheriff's Department	Reeves County (Pecos)	(432) 445-4901	
Scurry Cty Sheriff's Department	Scurry County (Snyder	(325) 573-3551	
Terry Cty Sheriff's Department	Terry County (Brownfi	(806) 637-2212	
Union Cty Sheriff's Department	Union County (Clayton	(505) 374-2583	
Upton Cty Sheriff's Department	Upton County (Rankin	(432) 693-2422	
Ward Cty Sheriff's Department	Ward County (Monaha	(432) 943-3254	
Yoakum City Sheriff's Department	Yoakum Co. (Denever	(806) 456-2377	
Law Enforcement - Police			
Abernathy City Police	Abernathy, TX	(806) 298-2545	
Andrews City Police	Andrews, TX	(432) 523-5675	
Artesia City Police	Artesia, NM	(505) 746-2704	
Brownfield City Police	Brownfield, TX	(806) 637-2544	
Carlsbad City Police	Carlsbad, NM	(505) 885-2111	
Clayton City Police	Clayton, NM	(505) 374-2504	
Denver City Police	Denver City, TX	(806) 592-3516	
Eunice City Police	Eunice, NM	(505) 394-2112	
Hobbs City Police	Hobbs, NM	393-2677	
Jal City Police	Jal, NM	(505) 395-2501	
Jayton City Police	Jayton, TX	(806) 237-3801	
Lamesa City Police	Lamesa, TX	(806) 872-2121	
Levelland City Police	Levelland, TX	(806) 894-6164	
Lovington City Police	Lovington, NM	(505) 396-2811	
Midland City Police	Midland, TX	(432) 685-7113	
Monahans City Police	Monahans, TX	(432) 943-3254	
Odessa City Police	Odessa, TX	(432) 335-3378	
Seminole City Police	Seminole, TX	(432) 758-9871	
Snyder City Police	Snyder, TX	(325) 573-2611	
Sundown City Police	Sundown, TX	(806) 229-8241	
Law Enforcement - FBI			
FBI	Alburqueque, NM	(505) 224-2000	
FBI	Midland, TX	(432) 570-0255	
Law Enforcement - DPS			
NM State Police	Artesia, NM	(505) 746-2704	
NM State Police	Carlsbad, NM	(505) 885-3137	
NM State Police	Eunice, NM	(505) 392-5588	
NM State Police	Hobbs, NM	(505) 392-5588	
NM State Police	Clayton, NM	(505) 374-2473; 911	
TX Dept of Public Safety	Andrews, TX	(432) 524-1443	
TX Dept of Public Safety	Big Lake, TX	(325) 884-2301	

Person	Location	Office Phone	Cell/Mobile Phone
TX Dept of Public Safety	Brownfield, TX	(806) 637-2312	
TX Dept of Public Safety	Iraan, TX	(432) 639-3232	
TX Dept of Public Safety	Lamesa, TX	(806) 872-8675	
TX Dept of Public Safety	Levelland, TX	(806) 894-4385	
TX Dept of Public Safety	Lubbock, TX	(806) 747-4491	
TX Dept of Public Safety	Midland, TX	(432) 697-2211	
TX Dept of Public Safety	Monahans, TX	(432) 943-5857	
TX Dept of Public Safety	Odessa, TX	(432) 332-6100	
TX Dept of Public Safety	Ozona, TX	(325) 392-2621	
TX Dept of Public Safety	Pecos, TX	(432) 447-3533	
TX Dept of Public Safety	Seminole, TX	(432) 758-4041	
TX Dept of Public Safety	Snyder, TX	(325) 573-0113	
TX Dept of Public Safety	Terry County TX	(806) 637-8913	
TX Dept of Public Safety	Yoakum County TX	(806) 456-2377	
Firefighting & Rescue			
Abernathy	Abernathy, TX	(806) 298-2022	
Amistad/Rosebud	Amistad/Rosebud, NM	(505) 633-9113	
Andrews	Andrews, TX	523-3111	
Artesia	Artesia, NM	(505) 746-5051	
Big Lake	Big Lake, TX	(325) 884-3650	
Brownfield-Administrative & other calls	Brownfield, TX	(816) 637-4547	
Brownfield emergency only	Brownfield, TX	-911	
Carlsbad	Carlsbad, NM	(505) 885-3125	
Clayton	Clayton, NM	(505) 374-2435	
Cotton Center	Cotton Center, TX	(806) 879-2157	
Crane	Crane, TX	(432) 558-2361	
Del Rio	Del Rio, TX	(830) 774-8650	
Denver City	Denver City, TX	(806) 592-3516	
Eldorado	Eldorado, TX	(325) 853-2691	
Eunice	Eunice, NM	(505) 394-2111	
Garden City	Garden City, TX	(432) 354-2404	
Goldsmith	Goldsmith, TX	(432) 827-3445	
Hale Center	Hale Center, TX	(806) 839-2411	
Halfway	Halfway, TX		
Hobbs	Hobbs, NM	(505) 397-9308	
Jal	Jal, NM	(505) 395-2221	
Jayton	Jayton, TX	(806) 237-3801	
Kermit	Kermit, TX	(432) 586-3468	
Lamesa	Lamesa, TX	(806) 872-4352	
Levelland	Levelland, TX	(806) 894-3154	
Lovington	Lovington, NM	(505) 396-2359	
Maljamar	Maljamar, NM	(505) 676-4100	

Person	Location	Office Phone	Cell/Mobile Phone
McCamey	McCamey, TX	(432) 652-8232	
Midland	Midland, TX	(432) 685-7346	
Monahans	Monahans, TX	(432) 943-4343	
Nara Visa	Nara Visa, NM	(505) 461-3300	
Notrees	Notress, TX	(432) 827-3445	
Odessa	Odessa, TX	(432) 335-4659	
Ozona	Ozona, TX	(325) 392-2626	
Pecos	Pecos, TX	(432) 445-2421	
Petersburg	Petersburg, TX	(806) 667-3461	
Plains	Plains, TX	(806) 456-8067	
Plainview	Plainview, TX	(806) 296-1170	
Rankin	Rankin, TX	(432) 693-2252	
San Angelo	San Angelo, TX	(325) 657-4355	
Sanderson	Sanderson, TX	(432) 345-2525	
Seminole	Seminole, TX	758-9871	
Smyer	Smyer, TX	(806) 234-3861	
Snyder	Snyder, TX	(325) 573-6215	
Sundown	Sundown, TX	**911**	
Tucumcari	Tucumcari, NM	911	
West Odessa	Odessa, TX	(432) 381-3033	
Ambulance			
Abernathy Ambulance	Abernathy, TX	(806) 298-2241	
Amistad/Rosebud	Amistad/Rosebud, NM	(505) 633-9113	
Andrews Ambulance	Andrews, TX	(432) 523-5675	
Artesia Ambulance	Artesia, NM	(505) 746-2701	
Big Lake Ambulance	Big Lake, TX	(325) 884-2423	
Big Spring Ambulance	Big Spring, TX	(432) 264-2550	
Brownfield Ambulance	Brownfield, TX	(806) 637-2511	
Carlsbad Ambulance	Carlsbad, NM	(505) 885-2111; 911	
Clayton, NM	Clayton, NM	(505) 374-2501	
Denver City Ambulance	Denver City, TX	(806) 592-3516	
Eldorado Ambulance	Eldorado, TX	(325) 853-3456	
Eunice Ambulance	Eunice, NM	(505) 394-3258	
Goldsmith Ambulance	Goldsmith, TX	(432) 827-3445	
Hobbs, NM	Hobbs, NM	(505) 397-9308	
Jal, NM	Jal, NM	(505) 395-2501	
Jayton Ambulance	Jayton, TX	(806) 237-3801	
Lamesa Ambulance	Lamesa, TX	(806) 872-3464	
Levelland Ambulance	Levelland, TX	(806) 894-8855	
Lovington Ambulance	Lovington, NM	(505) 396-2811	
McCamey Hospital	McCamey, TX	(432) 652-8626	
Midland Ambulance	Midland, TX	(432) 685-7499	

Person	Location	Office Phone	Cell/Mobile Phone
Monahans Ambulance	Monahans, TX	3731	
Nara Visa, NM	Nara Visa, NM	(505) 461-3300	
Odessa Ambulance	Odessa, TX	(432) 335-3378	
Ozona Ambulance	Ozona, TX	(325) 392-2671	
Pecos Ambulance	Pecos, TX	(432) 445-4444	
Rankin Ambulance	Rankin, TX	(432) 693-2443	
San Angelo Ambulance	San Angelo, TX	(325) 657-4357	
Seminole Ambulance	Seminole, TX	758-9871	
Snyder Ambulance	Snyder, TX	(325) 573-1911	
Stanton Ambulance	Stanton, TX	(432) 756-2211	
Sundown Ambulance	Sundown, TX	**911**	
Tucumcari, NM	Tucumcari, NM	911	
Medical Air Ambulance Service			
AEROCARE - Methodist Hospital	Lubbock, TX	(800) 627-2376	
San Angelo Med-Vac Air Ambulance	San Angelo, TX	(800) 277-4354	
Southwest Air Ambulance Service	Stanford, TX	(800) 242-6199	
Southwest MediVac	Snyder, TX	(800) 242-6199	
Southwest MediVac	Hobbs, NM	(800) 242-6199	
Odessa Care Star	Odessa, TX	(888) 624-3571	
NWTH Medivac	Amarillo, TX	(800) 692-1331	

Project: PRD NM DIRECTIONAL PLANS (NAD 1983)
Site: Corral Gorge 12_13
Well: Corral Gorge 12_13 Fed Com 32H
Wellbore: Wellbore #1
Design: Permitting Plan

PROJECT DETAILS: NM DIRECTIONAL PLANS (NAD 1983)

Geodetic System: US State Plane 1983
Datum: North American Datum 1983
Ellipsoid: GRS 1980
Zone: New Mexico Eastern Zone

System Datum: Mean Sea Level

WELL DETAILS: Corral Gorge 12_13 Fed Com 32H

+N/-S	+E/-W	Northing	Easting	Latitude	Longitude
0.00	0.00	419067.56	661305.30	32° 9' 5.405317 N	103° 56' 44.477008 W

3075.80

SECTION DETAILS

MD	Inc	Azi	TVD	+N/-S	+E/-W	Dleg	TFace	VSect	Annotation
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
3625.00	0.00	0.00	3625.00	0.00	0.00	0.00	0.00	0.00	Build 2.00°/100'
4124.98	10.00	42.34	4122.44	32.17	29.31	2.00	42.34	-30.11	Hold 10.00° Tangent
8972.05	10.00	42.34	8895.89	654.33	596.13	0.00	0.00	-612.43	Turn 2.00°/100'
9902.99	10.00	179.70	9820.84	633.06	651.47	2.00	158.38	-587.46	KOP, Build 10.00°/100'
10702.99	90.00	179.70	10294.30	68.82	654.39	10.00	0.00	-24.31	Landing Point
21206.84	90.00	179.70	10294.30	-10434.90	708.77	0.00	0.00	10458.94	TD at 21206.84' MD



Azimuths to Grid North
True North: -0.21°
Magnetic North: 6.63°

Magnetic Field
Strength: 47835.0nT
Dip Angle: 59.82°
Date: 9/11/2019
Model: HDGM_FILE





OXY

PRD NM DIRECTIONAL PLANS (NAD 1983)
Corral Gorge 12_13
Corral Gorge 12_13 Fed Com 32H

Wellbore #1

Plan: Permitting Plan

Standard Planning Report

11 September, 2019

Database:	HOPSPP	**Local Co-ordinate Reference:**	Well Corral Gorge 12_13 Fed Com 32H
Company:	ENGINEERING DESIGNS	**TVD Reference:**	RKB=26.5' @ 3102.30ft
Project:	PRD NM DIRECTIONAL PLANS (NAD 1983)	**MD Reference:**	RKB=26.5' @ 3102.30ft
Site:	Corral Gorge 12_13	**North Reference:**	Grid
Well:	Corral Gorge 12_13 Fed Com 32H	**Survey Calculation Method:**	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	Permitting Plan		

Project PRD NM DIRECTIONAL PLANS (NAD 1983)

Map System:	US State Plane 1983	**System Datum:**	Mean Sea Level
Geo Datum:	North American Datum 1983		
Map Zone:	New Mexico Eastern Zone		Using geodetic scale factor

Site Corral Gorge 12_13

Site Position:		**Northing:**	418,266.21 usft	**Latitude:**	32° 8' 57.433960 N
From:	Map	**Easting:**	662,457.18 usft	**Longitude:**	103° 56' 31.111937 W
Position Uncertainty:	1.00 ft	**Slot Radius:**	13.200 in	**Grid Convergence:**	0.21 °

Well Corral Gorge 12_13 Fed Com 32H

Well Position	**+N/-S**	801.41 ft	**Northing:**	419,067.56 usft	**Latitude:**	32° 9' 5.405317 N
	+E/-W	-1,151.97 ft	**Easting:**	661,305.30 usft	**Longitude:**	103° 56' 44.477009 W
Position Uncertainty		2.00 ft	**Wellhead Elevation:**		**Ground Level:**	3,075.80 ft

Wellbore Wellbore #1

Magnetics	Model Name	Sample Date	Declination (°)	Dip Angle (°)	Field Strength (nT)
	HDGM_FILE	9/11/2019	6.83	59.82	47,835.00000000

Design Permitting Plan

Audit Notes:

Version:	**Phase:**	PROTOTYPE	**Tie On Depth:**	0.00

Vertical Section:	Depth From (TVD) (ft)	+N/-S (ft)	+E/-W (ft)	Direction (°)
	0.00	0.00	0.00	176.11

Plan Survey Tool Program **Date** 9/11/2019

	Depth From (ft)	Depth To (ft)	Survey (Wellbore)	Tool Name	Remarks
1	0.00	21,206.84	Permitting Plan (Wellbore #1)	B001Mb_MWD+HRGM	
				OWSG MWD + HRGM	

Plan Sections

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)	TFO (°)	Target
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
3,625.00	0.00	0.00	3,625.00	0.00	0.00	0.00	0.00	0.00	0.00	
4,124.98	10.00	42.34	4,122.44	32.17	29.31	2.00	2.00	0.00	42.34	
8,972.05	10.00	42.34	8,895.89	654.33	596.13	0.00	0.00	0.00	0.00	
9,902.99	10.00	179.70	9,820.84	633.06	651.47	2.00	0.00	14.76	158.38	
10,702.99	90.00	179.70	10,294.30	68.82	654.39	10.00	10.00	0.00	0.00	FTP (Corral Gorge
21,206.84	90.00	179.70	10,294.30	-10,434.90	708.77	0.00	0.00	0.00	0.00	PBHL (Corral Gorge

Database:	HOPSPP	**Local Co-ordinate Reference:**	Well Corral Gorge 12_13 Fed Com 32H
Company:	ENGINEERING DESIGNS	**TVD Reference:**	RKB=26.5' @ 3102.30ft
Project:	PRD NM DIRECTIONAL PLANS (NAD 1983)	**MD Reference:**	RKB=26.5' @ 3102.30ft
Site:	Corral Gorge 12_13	**North Reference:**	Grid
Well:	Corral Gorge 12_13 Fed Com 32H	**Survey Calculation Method:**	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	Permitting Plan		

Planned Survey

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
100.00	0.00	0.00	100.00	0.00	0.00	0.00	0.00	0.00	0.00
200.00	0.00	0.00	200.00	0.00	0.00	0.00	0.00	0.00	0.00
300.00	0.00	0.00	300.00	0.00	0.00	0.00	0.00	0.00	0.00
400.00	0.00	0.00	400.00	0.00	0.00	0.00	0.00	0.00	0.00
500.00	0.00	0.00	500.00	0.00	0.00	0.00	0.00	0.00	0.00
600.00	0.00	0.00	600.00	0.00	0.00	0.00	0.00	0.00	0.00
700.00	0.00	0.00	700.00	0.00	0.00	0.00	0.00	0.00	0.00
800.00	0.00	0.00	800.00	0.00	0.00	0.00	0.00	0.00	0.00
900.00	0.00	0.00	900.00	0.00	0.00	0.00	0.00	0.00	0.00
1,000.00	0.00	0.00	1,000.00	0.00	0.00	0.00	0.00	0.00	0.00
1,100.00	0.00	0.00	1,100.00	0.00	0.00	0.00	0.00	0.00	0.00
1,200.00	0.00	0.00	1,200.00	0.00	0.00	0.00	0.00	0.00	0.00
1,300.00	0.00	0.00	1,300.00	0.00	0.00	0.00	0.00	0.00	0.00
1,400.00	0.00	0.00	1,400.00	0.00	0.00	0.00	0.00	0.00	0.00
1,500.00	0.00	0.00	1,500.00	0.00	0.00	0.00	0.00	0.00	0.00
1,600.00	0.00	0.00	1,600.00	0.00	0.00	0.00	0.00	0.00	0.00
1,700.00	0.00	0.00	1,700.00	0.00	0.00	0.00	0.00	0.00	0.00
1,800.00	0.00	0.00	1,800.00	0.00	0.00	0.00	0.00	0.00	0.00
1,900.00	0.00	0.00	1,900.00	0.00	0.00	0.00	0.00	0.00	0.00
2,000.00	0.00	0.00	2,000.00	0.00	0.00	0.00	0.00	0.00	0.00
2,100.00	0.00	0.00	2,100.00	0.00	0.00	0.00	0.00	0.00	0.00
2,200.00	0.00	0.00	2,200.00	0.00	0.00	0.00	0.00	0.00	0.00
2,300.00	0.00	0.00	2,300.00	0.00	0.00	0.00	0.00	0.00	0.00
2,400.00	0.00	0.00	2,400.00	0.00	0.00	0.00	0.00	0.00	0.00
2,500.00	0.00	0.00	2,500.00	0.00	0.00	0.00	0.00	0.00	0.00
2,600.00	0.00	0.00	2,600.00	0.00	0.00	0.00	0.00	0.00	0.00
2,700.00	0.00	0.00	2,700.00	0.00	0.00	0.00	0.00	0.00	0.00
2,800.00	0.00	0.00	2,800.00	0.00	0.00	0.00	0.00	0.00	0.00
2,900.00	0.00	0.00	2,900.00	0.00	0.00	0.00	0.00	0.00	0.00
3,000.00	0.00	0.00	3,000.00	0.00	0.00	0.00	0.00	0.00	0.00
3,100.00	0.00	0.00	3,100.00	0.00	0.00	0.00	0.00	0.00	0.00
3,200.00	0.00	0.00	3,200.00	0.00	0.00	0.00	0.00	0.00	0.00
3,300.00	0.00	0.00	3,300.00	0.00	0.00	0.00	0.00	0.00	0.00
3,400.00	0.00	0.00	3,400.00	0.00	0.00	0.00	0.00	0.00	0.00
3,500.00	0.00	0.00	3,500.00	0.00	0.00	0.00	0.00	0.00	0.00
3,600.00	0.00	0.00	3,600.00	0.00	0.00	0.00	0.00	0.00	0.00
3,625.00	0.00	0.00	3,625.00	0.00	0.00	0.00	0.00	0.00	0.00
3,700.00	1.50	42.34	3,699.99	0.73	0.66	-0.68	2.00	2.00	0.00
3,800.00	3.50	42.34	3,799.89	3.95	3.60	-3.70	2.00	2.00	0.00
3,900.00	5.50	42.34	3,899.58	9.75	8.88	-9.13	2.00	2.00	0.00
4,000.00	7.50	42.34	3,998.93	18.12	16.51	-16.96	2.00	2.00	0.00
4,100.00	9.50	42.34	4,097.83	29.04	26.46	-27.18	2.00	2.00	0.00
4,124.98	10.00	42.34	4,122.44	32.17	29.31	-30.11	2.00	2.00	0.00
4,200.00	10.00	42.34	4,196.33	41.80	38.08	-39.12	0.00	0.00	0.00
4,300.00	10.00	42.34	4,294.81	54.64	49.78	-51.14	0.00	0.00	0.00
4,400.00	10.00	42.34	4,393.29	67.47	61.47	-63.15	0.00	0.00	0.00
4,500.00	10.00	42.34	4,491.77	80.31	73.16	-75.16	0.00	0.00	0.00
4,600.00	10.00	42.34	4,590.25	93.14	84.86	-87.18	0.00	0.00	0.00
4,700.00	10.00	42.34	4,688.73	105.98	96.55	-99.19	0.00	0.00	0.00
4,800.00	10.00	42.34	4,787.21	118.81	108.25	-111.21	0.00	0.00	0.00
4,900.00	10.00	42.34	4,885.69	131.65	119.94	-123.22	0.00	0.00	0.00
5,000.00	10.00	42.34	4,984.17	144.49	131.63	-135.23	0.00	0.00	0.00
5,100.00	10.00	42.34	5,082.65	157.32	143.33	-147.25	0.00	0.00	0.00

Database:	HOPSPP	**Local Co-ordinate Reference:**	Well Corral Gorge 12_13 Fed Com 32H
Company:	ENGINEERING DESIGNS	**TVD Reference:**	RKB=26.5' @ 3102.30ft
Project:	PRD NM DIRECTIONAL PLANS (NAD 1983)	**MD Reference:**	RKB=26.5' @ 3102.30ft
Site:	Corral Gorge 12_13	**North Reference:**	Grid
Well:	Corral Gorge 12_13 Fed Com 32H	**Survey Calculation Method:**	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	Permitting Plan		

Planned Survey

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
5,200.00	10.00	42.34	5,181.14	170.16	155.02	-159.26	0.00	0.00	0.00
5,300.00	10.00	42.34	5,279.62	182.99	166.72	-171.27	0.00	0.00	0.00
5,400.00	10.00	42.34	5,378.10	195.83	178.41	-183.29	0.00	0.00	0.00
5,500.00	10.00	42.34	5,476.58	208.66	190.10	-195.30	0.00	0.00	0.00
5,600.00	10.00	42.34	5,575.06	221.50	201.80	-207.32	0.00	0.00	0.00
5,700.00	10.00	42.34	5,673.54	234.34	213.49	-219.33	0.00	0.00	0.00
5,800.00	10.00	42.34	5,772.02	247.17	225.19	-231.34	0.00	0.00	0.00
5,900.00	10.00	42.34	5,870.50	260.01	236.88	-243.36	0.00	0.00	0.00
6,000.00	10.00	42.34	5,968.98	272.84	248.58	-255.37	0.00	0.00	0.00
6,100.00	10.00	42.34	6,067.46	285.68	260.27	-267.38	0.00	0.00	0.00
6,200.00	10.00	42.34	6,165.94	298.51	271.96	-279.40	0.00	0.00	0.00
6,300.00	10.00	42.34	6,264.43	311.35	283.66	-291.41	0.00	0.00	0.00
6,400.00	10.00	42.34	6,362.91	324.19	295.35	-303.43	0.00	0.00	0.00
6,500.00	10.00	42.34	6,461.39	337.02	307.05	-315.44	0.00	0.00	0.00
6,600.00	10.00	42.34	6,559.87	349.86	318.74	-327.45	0.00	0.00	0.00
6,700.00	10.00	42.34	6,658.35	362.69	330.43	-339.47	0.00	0.00	0.00
6,800.00	10.00	42.34	6,756.83	375.53	342.13	-351.48	0.00	0.00	0.00
6,900.00	10.00	42.34	6,855.31	388.36	353.82	-363.49	0.00	0.00	0.00
7,000.00	10.00	42.34	6,953.79	401.20	365.52	-375.51	0.00	0.00	0.00
7,100.00	10.00	42.34	7,052.27	414.04	377.21	-387.52	0.00	0.00	0.00
7,200.00	10.00	42.34	7,150.75	426.87	388.90	-399.54	0.00	0.00	0.00
7,300.00	10.00	42.34	7,249.23	439.71	400.60	-411.55	0.00	0.00	0.00
7,400.00	10.00	42.34	7,347.72	452.54	412.29	-423.56	0.00	0.00	0.00
7,500.00	10.00	42.34	7,446.20	465.38	423.99	-435.58	0.00	0.00	0.00
7,600.00	10.00	42.34	7,544.68	478.22	435.68	-447.59	0.00	0.00	0.00
7,700.00	10.00	42.34	7,643.16	491.05	447.37	-459.60	0.00	0.00	0.00
7,800.00	10.00	42.34	7,741.64	503.89	459.07	-471.62	0.00	0.00	0.00
7,900.00	10.00	42.34	7,840.12	516.72	470.76	-483.63	0.00	0.00	0.00
8,000.00	10.00	42.34	7,938.60	529.56	482.46	-495.65	0.00	0.00	0.00
8,100.00	10.00	42.34	8,037.08	542.39	494.15	-507.66	0.00	0.00	0.00
8,200.00	10.00	42.34	8,135.56	555.23	505.85	-519.67	0.00	0.00	0.00
8,300.00	10.00	42.34	8,234.04	568.07	517.54	-531.69	0.00	0.00	0.00
8,400.00	10.00	42.34	8,332.52	580.90	529.23	-543.70	0.00	0.00	0.00
8,500.00	10.00	42.34	8,431.01	593.74	540.93	-555.72	0.00	0.00	0.00
8,600.00	10.00	42.34	8,529.49	606.57	552.62	-567.73	0.00	0.00	0.00
8,700.00	10.00	42.34	8,627.97	619.41	564.32	-579.74	0.00	0.00	0.00
8,800.00	10.00	42.34	8,726.45	632.24	576.01	-591.76	0.00	0.00	0.00
8,900.00	10.00	42.34	8,824.93	645.08	587.70	-603.77	0.00	0.00	0.00
8,972.05	10.00	42.34	8,895.89	654.33	596.13	-612.43	0.00	0.00	0.00
9,000.00	9.48	43.59	8,923.43	657.79	599.35	-615.66	2.00	-1.85	4.47
9,100.00	7.68	49.41	9,022.31	668.10	610.10	-625.22	2.00	-1.80	5.82
9,200.00	6.00	58.61	9,121.60	675.17	619.64	-631.63	2.00	-1.68	9.20
9,300.00	4.58	74.11	9,221.18	678.99	627.94	-634.87	2.00	-1.42	15.51
9,400.00	3.74	99.45	9,320.92	679.55	635.00	-634.95	2.00	-0.84	25.34
9,500.00	3.87	129.85	9,420.71	676.85	640.82	-631.86	2.00	0.13	30.40
9,600.00	4.90	152.61	9,520.42	670.89	645.38	-625.61	2.00	1.02	22.76
9,700.00	6.40	166.18	9,619.94	661.68	648.67	-616.20	2.00	1.50	13.56
9,800.00	8.12	174.33	9,719.13	649.24	650.70	-603.65	2.00	1.72	8.15
9,900.00	9.94	179.58	9,817.89	633.58	651.47	-587.97	2.00	1.82	5.25
9,902.99	10.00	179.70	9,820.84	633.06	651.47	-587.46	2.00	1.86	4.27
10,000.00	19.70	179.70	9,914.49	608.23	651.60	-562.67	10.00	10.00	0.00
10,100.00	29.70	179.70	10,005.23	566.49	651.81	-521.02	10.00	10.00	0.00
10,200.00	39.70	179.70	10,087.34	509.64	652.11	-464.27	10.00	10.00	0.00
10,300.00	49.70	179.70	10,158.33	439.39	652.47	-394.16	10.00	10.00	0.00

Database:	HOPSPP	**Local Co-ordinate Reference:**	Well Corral Gorge 12_13 Fed Com 32H
Company:	ENGINEERING DESIGNS	**TVD Reference:**	RKB=26.5' @ 3102.30ft
Project:	PRD NM DIRECTIONAL PLANS (NAD 1983)	**MD Reference:**	RKB=26.5' @ 3102.30ft
Site:	Corral Gorge 12_13	**North Reference:**	Grid
Well:	Corral Gorge 12_13 Fed Com 32H	**Survey Calculation Method:**	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	Permitting Plan		

Planned Survey

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
10,400.00	59.70	179.70	10,216.04	357.88	652.89	-312.81	10.00	10.00	0.00
10,500.00	69.70	179.70	10,258.72	267.58	653.36	-222.69	10.00	10.00	0.00
10,600.00	79.70	179.70	10,285.07	171.25	653.86	-126.55	10.00	10.00	0.00
10,700.00	89.70	179.70	10,294.29	71.80	654.37	-27.29	10.00	10.00	0.00
10,702.99	90.00	179.70	10,294.30	68.82	654.39	-24.31	10.00	10.00	0.00
10,800.00	90.00	179.70	10,294.30	-28.19	654.89	72.51	0.00	0.00	0.00
10,900.00	90.00	179.70	10,294.30	-128.19	655.41	172.31	0.00	0.00	0.00
11,000.00	90.00	179.70	10,294.30	-228.19	655.93	272.12	0.00	0.00	0.00
11,100.00	90.00	179.70	10,294.30	-328.19	656.45	371.92	0.00	0.00	0.00
11,200.00	90.00	179.70	10,294.30	-428.19	656.96	471.73	0.00	0.00	0.00
11,300.00	90.00	179.70	10,294.30	-528.19	657.48	571.53	0.00	0.00	0.00
11,400.00	90.00	179.70	10,294.30	-628.19	658.00	671.33	0.00	0.00	0.00
11,500.00	90.00	179.70	10,294.30	-728.18	658.52	771.14	0.00	0.00	0.00
11,600.00	90.00	179.70	10,294.30	-828.18	659.03	870.94	0.00	0.00	0.00
11,700.00	90.00	179.70	10,294.30	-928.18	659.55	970.74	0.00	0.00	0.00
11,800.00	90.00	179.70	10,294.30	-1,028.18	660.07	1,070.55	0.00	0.00	0.00
11,900.00	90.00	179.70	10,294.30	-1,128.18	660.59	1,170.35	0.00	0.00	0.00
12,000.00	90.00	179.70	10,294.30	-1,228.18	661.11	1,270.16	0.00	0.00	0.00
12,100.00	90.00	179.70	10,294.30	-1,328.18	661.62	1,369.96	0.00	0.00	0.00
12,200.00	90.00	179.70	10,294.30	-1,428.18	662.14	1,469.76	0.00	0.00	0.00
12,300.00	90.00	179.70	10,294.30	-1,528.17	662.66	1,569.57	0.00	0.00	0.00
12,400.00	90.00	179.70	10,294.30	-1,628.17	663.18	1,669.37	0.00	0.00	0.00
12,500.00	90.00	179.70	10,294.30	-1,728.17	663.69	1,769.18	0.00	0.00	0.00
12,600.00	90.00	179.70	10,294.30	-1,828.17	664.21	1,868.98	0.00	0.00	0.00
12,700.00	90.00	179.70	10,294.30	-1,928.17	664.73	1,968.78	0.00	0.00	0.00
12,800.00	90.00	179.70	10,294.30	-2,028.17	665.25	2,068.59	0.00	0.00	0.00
12,900.00	90.00	179.70	10,294.30	-2,128.17	665.77	2,168.39	0.00	0.00	0.00
13,000.00	90.00	179.70	10,294.30	-2,228.16	666.28	2,268.19	0.00	0.00	0.00
13,100.00	90.00	179.70	10,294.30	-2,328.16	666.80	2,368.00	0.00	0.00	0.00
13,200.00	90.00	179.70	10,294.30	-2,428.16	667.32	2,467.80	0.00	0.00	0.00
13,300.00	90.00	179.70	10,294.30	-2,528.16	667.84	2,567.61	0.00	0.00	0.00
13,400.00	90.00	179.70	10,294.30	-2,628.16	668.35	2,667.41	0.00	0.00	0.00
13,500.00	90.00	179.70	10,294.30	-2,728.16	668.87	2,767.21	0.00	0.00	0.00
13,600.00	90.00	179.70	10,294.30	-2,828.16	669.39	2,867.02	0.00	0.00	0.00
13,700.00	90.00	179.70	10,294.30	-2,928.16	669.91	2,966.82	0.00	0.00	0.00
13,800.00	90.00	179.70	10,294.30	-3,028.15	670.42	3,066.63	0.00	0.00	0.00
13,900.00	90.00	179.70	10,294.30	-3,128.15	670.94	3,166.43	0.00	0.00	0.00
14,000.00	90.00	179.70	10,294.30	-3,228.15	671.46	3,266.23	0.00	0.00	0.00
14,100.00	90.00	179.70	10,294.30	-3,328.15	671.98	3,366.04	0.00	0.00	0.00
14,200.00	90.00	179.70	10,294.30	-3,428.15	672.50	3,465.84	0.00	0.00	0.00
14,300.00	90.00	179.70	10,294.30	-3,528.15	673.01	3,565.65	0.00	0.00	0.00
14,400.00	90.00	179.70	10,294.30	-3,628.15	673.53	3,665.45	0.00	0.00	0.00
14,500.00	90.00	179.70	10,294.30	-3,728.14	674.05	3,765.25	0.00	0.00	0.00
14,600.00	90.00	179.70	10,294.30	-3,828.14	674.57	3,865.06	0.00	0.00	0.00
14,700.00	90.00	179.70	10,294.30	-3,928.14	675.08	3,964.86	0.00	0.00	0.00
14,800.00	90.00	179.70	10,294.30	-4,028.14	675.60	4,064.66	0.00	0.00	0.00
14,900.00	90.00	179.70	10,294.30	-4,128.14	676.12	4,164.47	0.00	0.00	0.00
15,000.00	90.00	179.70	10,294.30	-4,228.14	676.64	4,264.27	0.00	0.00	0.00
15,100.00	90.00	179.70	10,294.30	-4,328.14	677.16	4,364.08	0.00	0.00	0.00
15,200.00	90.00	179.70	10,294.30	-4,428.14	677.67	4,463.88	0.00	0.00	0.00
15,300.00	90.00	179.70	10,294.30	-4,528.13	678.19	4,563.68	0.00	0.00	0.00
15,400.00	90.00	179.70	10,294.30	-4,628.13	678.71	4,663.49	0.00	0.00	0.00
15,500.00	90.00	179.70	10,294.30	-4,728.13	679.23	4,763.29	0.00	0.00	0.00
15,600.00	90.00	179.70	10,294.30	-4,828.13	679.74	4,863.10	0.00	0.00	0.00

Database:	HOPSPP	**Local Co-ordinate Reference:**	Well Corral Gorge 12_13 Fed Com 32H
Company:	ENGINEERING DESIGNS	**TVD Reference:**	RKB=26.5' @ 3102.30ft
Project:	PRD NM DIRECTIONAL PLANS (NAD 1983)	**MD Reference:**	RKB=26.5' @ 3102.30ft
Site:	Corral Gorge 12_13	**North Reference:**	Grid
Well:	Corral Gorge 12_13 Fed Com 32H	**Survey Calculation Method:**	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	Permitting Plan		

Planned Survey

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
15,700.00	90.00	179.70	10,294.30	-4,928.13	680.26	4,962.90	0.00	0.00	0.00
15,800.00	90.00	179.70	10,294.30	-5,028.13	680.78	5,062.70	0.00	0.00	0.00
15,900.00	90.00	179.70	10,294.30	-5,128.13	681.30	5,162.51	0.00	0.00	0.00
16,000.00	90.00	179.70	10,294.30	-5,228.12	681.82	5,262.31	0.00	0.00	0.00
16,100.00	90.00	179.70	10,294.30	-5,328.12	682.33	5,362.11	0.00	0.00	0.00
16,200.00	90.00	179.70	10,294.30	-5,428.12	682.85	5,461.92	0.00	0.00	0.00
16,300.00	90.00	179.70	10,294.30	-5,528.12	683.37	5,561.72	0.00	0.00	0.00
16,400.00	90.00	179.70	10,294.30	-5,628.12	683.89	5,661.53	0.00	0.00	0.00
16,500.00	90.00	179.70	10,294.30	-5,728.12	684.40	5,761.33	0.00	0.00	0.00
16,600.00	90.00	179.70	10,294.30	-5,828.12	684.92	5,861.13	0.00	0.00	0.00
16,700.00	90.00	179.70	10,294.30	-5,928.12	685.44	5,960.94	0.00	0.00	0.00
16,800.00	90.00	179.70	10,294.30	-6,028.11	685.96	6,060.74	0.00	0.00	0.00
16,900.00	90.00	179.70	10,294.30	-6,128.11	686.48	6,160.55	0.00	0.00	0.00
17,000.00	90.00	179.70	10,294.30	-6,228.11	686.99	6,260.35	0.00	0.00	0.00
17,100.00	90.00	179.70	10,294.30	-6,328.11	687.51	6,360.15	0.00	0.00	0.00
17,200.00	90.00	179.70	10,294.30	-6,428.11	688.03	6,459.96	0.00	0.00	0.00
17,300.00	90.00	179.70	10,294.30	-6,528.11	688.55	6,559.76	0.00	0.00	0.00
17,400.00	90.00	179.70	10,294.30	-6,628.11	689.06	6,659.56	0.00	0.00	0.00
17,500.00	90.00	179.70	10,294.30	-6,728.10	689.58	6,759.37	0.00	0.00	0.00
17,600.00	90.00	179.70	10,294.30	-6,828.10	690.10	6,859.17	0.00	0.00	0.00
17,700.00	90.00	179.70	10,294.30	-6,928.10	690.62	6,958.98	0.00	0.00	0.00
17,800.00	90.00	179.70	10,294.30	-7,028.10	691.14	7,058.78	0.00	0.00	0.00
17,900.00	90.00	179.70	10,294.30	-7,128.10	691.65	7,158.58	0.00	0.00	0.00
18,000.00	90.00	179.70	10,294.30	-7,228.10	692.17	7,258.39	0.00	0.00	0.00
18,100.00	90.00	179.70	10,294.30	-7,328.10	692.69	7,358.19	0.00	0.00	0.00
18,200.00	90.00	179.70	10,294.30	-7,428.10	693.21	7,458.00	0.00	0.00	0.00
18,300.00	90.00	179.70	10,294.30	-7,528.09	693.72	7,557.80	0.00	0.00	0.00
18,400.00	90.00	179.70	10,294.30	-7,628.09	694.24	7,657.60	0.00	0.00	0.00
18,500.00	90.00	179.70	10,294.30	-7,728.09	694.76	7,757.41	0.00	0.00	0.00
18,600.00	90.00	179.70	10,294.30	-7,828.09	695.28	7,857.21	0.00	0.00	0.00
18,700.00	90.00	179.70	10,294.30	-7,928.09	695.79	7,957.02	0.00	0.00	0.00
18,800.00	90.00	179.70	10,294.30	-8,028.09	696.31	8,056.82	0.00	0.00	0.00
18,900.00	90.00	179.70	10,294.30	-8,128.09	696.83	8,156.62	0.00	0.00	0.00
19,000.00	90.00	179.70	10,294.30	-8,228.08	697.35	8,256.43	0.00	0.00	0.00
19,100.00	90.00	179.70	10,294.30	-8,328.08	697.87	8,356.23	0.00	0.00	0.00
19,200.00	90.00	179.70	10,294.30	-8,428.08	698.38	8,456.03	0.00	0.00	0.00
19,300.00	90.00	179.70	10,294.30	-8,528.08	698.90	8,555.84	0.00	0.00	0.00
19,400.00	90.00	179.70	10,294.30	-8,628.08	699.42	8,655.64	0.00	0.00	0.00
19,500.00	90.00	179.70	10,294.30	-8,728.08	699.94	8,755.45	0.00	0.00	0.00
19,600.00	90.00	179.70	10,294.30	-8,828.08	700.45	8,855.25	0.00	0.00	0.00
19,700.00	90.00	179.70	10,294.30	-8,928.08	700.97	8,955.05	0.00	0.00	0.00
19,800.00	90.00	179.70	10,294.30	-9,028.07	701.49	9,054.86	0.00	0.00	0.00
19,900.00	90.00	179.70	10,294.30	-9,128.07	702.01	9,154.66	0.00	0.00	0.00
20,000.00	90.00	179.70	10,294.30	-9,228.07	702.53	9,254.47	0.00	0.00	0.00
20,100.00	90.00	179.70	10,294.30	-9,328.07	703.04	9,354.27	0.00	0.00	0.00
20,200.00	90.00	179.70	10,294.30	-9,428.07	703.56	9,454.07	0.00	0.00	0.00
20,300.00	90.00	179.70	10,294.30	-9,528.07	704.08	9,553.88	0.00	0.00	0.00
20,400.00	90.00	179.70	10,294.30	-9,628.07	704.60	9,653.68	0.00	0.00	0.00
20,500.00	90.00	179.70	10,294.30	-9,728.06	705.11	9,753.48	0.00	0.00	0.00
20,600.00	90.00	179.70	10,294.30	-9,828.06	705.63	9,853.29	0.00	0.00	0.00
20,700.00	90.00	179.70	10,294.30	-9,928.06	706.15	9,953.09	0.00	0.00	0.00
20,800.00	90.00	179.70	10,294.30	-10,028.06	706.67	10,052.90	0.00	0.00	0.00
20,900.00	90.00	179.70	10,294.30	-10,128.06	707.19	10,152.70	0.00	0.00	0.00
21,000.00	90.00	179.70	10,294.30	-10,228.06	707.70	10,252.50	0.00	0.00	0.00

Database:	HOPSPP	**Local Co-ordinate Reference:**	Well Corral Gorge 12_13 Fed Com 32H
Company:	ENGINEERING DESIGNS	**TVD Reference:**	RKB=26.5' @ 3102.30ft
Project:	PRD NM DIRECTIONAL PLANS (NAD 1983)	**MD Reference:**	RKB=26.5' @ 3102.30ft
Site:	Corral Gorge 12_13	**North Reference:**	Grid
Well:	Corral Gorge 12_13 Fed Com 32H	**Survey Calculation Method:**	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	Permitting Plan		

Planned Survey

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
21,100.00	90.00	179.70	10,294.30	-10,328.06	708.22	10,352.31	0.00	0.00	0.00
21,200.00	90.00	179.70	10,294.30	-10,428.06	708.74	10,452.11	0.00	0.00	0.00
21,206.84	90.00	179.70	10,294.30	-10,434.90	708.77	10,458.94	0.00	0.00	0.00

Design Targets

Target Name - hit/miss target - Shape	Dip Angle (°)	Dip Dir. (°)	TVD (ft)	+N/-S (ft)	+E/-W (ft)	Northing (usft)	Easting (usft)	Latitude	Longitude
PBHL (Corral Gorge - plan hits target center - Point	0.00	0.00	10,294.30	-10,434.90	708.77	408,633.46	662,014.02	32° 7' 22.124436 N	103° 56' 36.672268
FTP (Corral Gorge - plan hits target center - Point	0.00	0.00	10,294.30	68.82	654.39	419,136.37	661,959.64	32° 9' 6.062879 N	103° 56' 36.862665

Plan Annotations

Measured Depth (ft)	Vertical Depth (ft)	Local Coordinates +N/-S (ft)	Local Coordinates +E/-W (ft)	Comment
3,625.00	3,625.00	0.00	0.00	Build 2.00°/100'
4,124.98	4,122.44	32.17	29.31	Hold 10.00° Tangent
8,972.05	8,895.89	654.33	596.13	Turn 2.00°/100'
9,902.99	9,820.84	633.06	651.47	KOP, Build 10.00°/100'
10,702.99	10,294.30	68.82	654.39	Landing Point
21,206.84	10,294.30	-10,434.90	708.77	TD at 21206.84' MD

OXY USA Inc. - Corral Gorge 12-13 Federal Com 32H

1. Geologic Formations

TVD of target	10294'	Pilot Hole Depth	N/A
MD at TD:	21207'	Deepest Expected fresh water:	348'

Delaware Basin

Formation	TVD - RKB	Expected Fluids
Rustler	348	
Salado	747	Salt
Castile	1,721	Salt
Lamar/Delaware	3,266	Oil/Gas/Brine
Bell Canyon	3,275	Oil/Gas/Brine
Cherry Canyon	4,169	Oil/Gas/Brine
Brushy Canyon	5,534	Losses
Bone Spring	7,052	Oil/Gas
1st Bone Spring	7,975	Oil/Gas
2nd Bone Spring	8,827	Oil/Gas
3rd Bone Spring	9,930	Oil/Gas
Wolfcamp	**10,244**	**Oil/Gas**

*H2S, water flows, loss of circulation, abnormal pressures, etc.

2. Casing Program

Hole Size (in)	Casing Interval		Csg. Size (in)	Weight (lbs)	Grade	Conn.	SF Collapse	SF Burst	Buoyant Body SF Tension	Buoyant Joint SF Tension
	From (ft)	To (ft)								
14.75	0	687	10.75	40.5	J-55	BTC	1.125	1.2	1.4	1.4
9.875	0	9803	7.625	26.4	L-80 HC	BTC	1.125	1.2	1.4	1.4
6.75	0	21207	5.5	20	P-110	DQX	1.125	1.2	1.4	1.4
							SF Values will meet or Exceed			

All casing strings will be tested in accordance with Onshore Oil and Gas Order #2 III.B.1.h

*Oxy requests the option to set casing shallower yet still below the salts if losses or hole conditions require this. Cement volumes may be adjusted if casing is set shallower and a DV tool may be run in case hole conditions merit pumping a second stage cement job to comply with permitted top of cement. If cement circulated to surface during first stage, we will drop a cancelation cone and not pump the second stage.

*Oxy requests the option to run production casing with DQX, SF TORQ, and/or DQW TORQ connections to accommodate hole conditions or drilling operations.

OXY USA Inc. - Corral Gorge 12-13 Federal Com 32H

Annular Clearance Variance Request

As per the agreement reached in the Oxy/BLM face-to-face meeting on Feb 22, 2018, Oxy requests permission to allow deviation from the 0.422" annular clearance requirement from Onshore Order #2 under the following conditions:

1. Annular clearance to meet or exceed 0.422" between intermediate casing ID and production casing coupling only on the first 500' overlap between both casings.
2. Annular clearance less than 0.422" is acceptable for the curve and lateral portions of the production open hole section.

	Y or N
Is casing new? If used, attach certification as required in Onshore Order #1	Y
Does casing meet API specifications? If no, attach casing specification sheet.	Y
Is premium or uncommon casing planned? If yes attach casing specification sheet.	Y
Does the above casing design meet or exceed BLM's minimum standards? If not provide justification (loading assumptions, casing design criteria).	Y
Will the intermediate pipe be kept at a minimum 1/3 fluid filled to avoid approaching the collapse pressure rating of the casing?	Y
Is well located within Capitan Reef?	N
If yes, does production casing cement tie back a minimum of 50' above the Reef?	
Is well within the designated 4 string boundary.	
Is well located in SOPA but not in R-111-P?	N
If yes, are the first 2 strings cemented to surface and 3rd string cement tied back 500' into previous casing?	
Is well located in R-111-P and SOPA?	N
If yes, are the first three strings cemented to surface?	
Is 2nd string set 100' to 600' below the base of salt?	
Is well located in high Cave/Karst?	N
If yes, are there two strings cemented to surface?	
(For 2 string wells) If yes, is there a contingency casing if lost circulation occurs?	
Is well located in critical Cave/Karst?	N
If yes, are there three strings cemented to surface?	

3. Cementing Program

Casing String	# Sks	Wt. (lb/gal)	Yld (ft3/sack)	H20 (gal/sk)	500# Comp. Strength (hours)	Slurry Description
Surface (Lead)	N/A	N/A	N/A	N/A	N/A	N/A
Surface (Tail)	561	14.8	1.33	6.365	5:26	Class C Cement, Accelerator
Intermediate 1st Stage (Lead)	N/A	N/A	N/A	N/A	N/A	N/A
Intermediate 1st Stage (Tail)	557	13.2	1.65	8.640	11:54	Class H Cement, Retarder, Dispersant, Salt
Intermediate 2nd Stage (Tail Slurry) to be pumped as Bradenhead Squeeze from surface, down the Intermediate annulus						
Intermediate 2nd Stage (Lead)	N/A	N/A	N/A	N/A	N/A	N/A
Intermediate 2nd Stage (Tail)	711	12.9	1.92	10.41	23:10	Class C Cement, Accelerator
Production (Lead)	N/A	N/A	N/A	N/A	N/A	N/A
Production (Tail)	873	13.2	1.38	6.686	3:39	Class H Cement, Retarder, Dispersant, Salt

Casing String	Top (ft)	Bottom (ft)	% Excess
Surface (Lead)	N/A	N/A	N/A
Surface (Tail)	0	687	100%
Intermediate 1st Stage (Lead)	N/A	N/A	N/A
Intermediate 1st Stage (Tail)	5784	9803	5%
Intermediate 2nd Stage (Lead)	N/A	N/A	N/A
Intermediate 2nd Stage (Tail)	0	5784	10%
Production (Lead)	N/A	N/A	N/A
Production (Tail)	9303	21207	20%

Oxy requests a variance to cement the 9.625" and/or 7.625" intermediate casing strings offline, see attached for additional information.

Bradenhead CBL - OXY requests permission to adjust the CBL requirement after bradenhead cement jobs, on 7-5/8" intermediate casings, as per the agreement reached in the OXY/BLM meeting on September 5, 2019.

Three string wells:

- CBL will be required on one well per pad
- If the pumped volume of cement is less than permitted in the APD, BLM will be notified and a CBL may be run
- Echometer will be used after bradenhead cement job to determine TOC before pumping top-out cement

4. Pressure Control Equipment

BOP installed and tested before drilling which hole?	Size?	Min. Required WP	Type	✓	Tested to:
9.875" Hole	13-5/8"	3M	Annular	✓	70% of working pressure
		3M	Blind Ram	✓	250 psi / 3000 psi
			Pipe Ram		
			Double Ram	✓	
			Other*		
6.75" Hole	13-5/8"	5M	Annular	✓	70% of working pressure
		5M	Blind Ram	✓	250 psi / 5000 psi
			Pipe Ram		
			Double Ram	✓	
			Other*		

*Specify if additional ram is utilized.

Oxy will utilize a 5M annular with a 10M BOPE stack. The BOP/BOPE will be tested by an independent service company to 250 psi low and the high pressure indicated above per Onshore Order 2 requirements. The System may be upgraded to a higher pressure but still tested to the working pressure listed in the table above. If the system is upgraded all the components installed will be functional and tested.

Pipe rams will be operationally checked each 24 hour period. Blind rams will be operationally checked on each trip out of the hole. These checks will be noted on the daily tour sheets. Other accessories to the BOP equipment will include a Kelly cock and floor safety valve (inside BOP) and choke lines and choke manifold. See attached schematics.

	Formation integrity test will be performed per Onshore Order #2. On Exploratory wells or on that portion of any well approved for a 5M BOPE system or greater, a pressure integrity test of each casing shoe shall be performed. Will be tested in accordance with Onshore Oil and Gas Order #2 III.B.1.i.
	A variance is requested for the use of a flexible choke line from the BOP to Choke Manifold. See attached for specs and hydrostatic test chart.
Y	Are anchors required by manufacturer?
	A multibowl or a unionized multibowl wellhead system will be employed. The wellhead and connection to the BOPE will meet all API 6A requirements. The BOP will be tested per Onshore Order #2 after installation on the surface casing which will cover testing requirements for a maximum of 30 days. If any seal subject to test pressure is broken the system must be tested. We will test the flange connection of the wellhead with a test port that is directly in the flange. We are proposing that we will run the wellhead through the rotary prior to cementing surface casing as discussed with the BLM on October 8, 2015. See attached schematics.

BOP Break Testing Request

OXY requests permission to adjust the BOP break testing requirements as per the agreement reached in the OXY/BLM meeting on September 5, 2019. A separate sundry will be sent prior to spud that reflects the pad based break testing plan.

BOP break test under the following conditions:

1. After a full BOP test is conducted
2. When skidding to drill an intermediate section where ICP is set into the third Bone Spring or shallower.
3. When skidding to drill a production section that does not penetrate into the third Bone Spring or deeper.

If the kill line is broken prior to skid, two tests will be performed.

1. Wellhead flange, co-flex hose, kill line connections and upper pipe rams
2. Wellhead flange, HCR valve, check valve, upper pipe rams

If the kill line is not broken prior to skid, only one test will be performed.

1. Wellhead flange, co-flex hose, check valve, upper pipe rams

5. Mud Program

Depth		Type	Weight (ppg)	Viscosity	Water Loss
From (ft)	To (ft)				
0	687	Water-Based Mud	8.6-8.8	40-60	N/C
687	9803	Saturated Brine-Based or Oil-Based Mud	8.0-10.0	35-45	N/C
9803	21207	Water-Based or Oil-Based Mud	9.5-12.0	38-50	N/C

Sufficient mud materials to maintain mud properties and meet minimum lost circulation and weight increase requirements will be kept on location at all times. The following is a general list of products: Barite, Bentonite, Gypsum, Lime, Soda Ash, Caustic Soda, Nut Plug, Cedar Fiber, Cotton Seed Hulls, Drilling Paper, Salt Water Clay, CACL2. Oxy will use a closed mud system.

What will be used to monitor the loss or gain of fluid?	PVT/MD Totco/Visual Monitoring

6. Logging and Testing Procedures

Logging, Coring and Testing.	
Yes	Will run GR from TD to surface (horizontal well – vertical portion of hole). Stated logs run will be in the Completion Report and submitted to the BLM.
No	Logs are planned based on well control or offset log information.
No	Drill stem test? If yes, explain
No	Coring? If yes, explain

Additional logs planned		Interval
No	Resistivity	
No	Density	
No	CBL	
Yes	Mud log	ICP - TD
No	PEX	

7. Drilling Conditions

Condition	Specify what type and where?
BH Pressure at deepest TVD	6424 psi
Abnormal Temperature	No
BH Temperature at deepest TVD	163°F

Pump high viscosity sweeps as needed for hole cleaning. The mud system will be monitored visually/manually as well as with an electronic PVT. The necessary mud products for additional weight and fluid loss control will be on location at all times. Appropriately weighted mud will be used to isolate potential gas, oil, and water zones until such time as casing can be cemented into place for zonal isolation.

Hydrogen Sulfide (H2S) monitors will be installed prior to drilling out the surface shoe. If H2S is detected in concentrations greater than 100 ppm, the operator will comply with the provisions of Onshore Oil and Gas Order #6. If Hydrogen Sulfide is encountered, measured values and formations will be provided to the BLM.	
N	H2S is present
Y	H2S Plan attached

8. Other facets of operation

	Yes/No
Will the well be drilled with a walking/skidding operation? If yes, describe. • We plan to drill the three well pad in batch by section: all surface sections, intermediate sections and production sections. The wellhead will be secured with a night cap whenever the rig is not over the well.	Yes
Will more than one drilling rig be used for drilling operations? If yes, describe. • Oxy requests the option to contract a Surface Rig to drill, set surface casing, and cement for this well. If the timing between rigs is such that Oxy would not be able to preset surface, the Primary Rig will MIRU and drill the well in its entirety per the APD. Please see the attached document for information on the spudder rig.	Yes

Total estimated cuttings volume: 1513.5 bbls**.**

9. Company Personnel

Name	Title	Office Phone	Mobile Phone
Garrett Granier	Drilling Engineer	713-513-6633	832-265-0581
William Turner	Drilling Engineer Supervisor	713-350-4951	661-817-4586
Simon Benavides	Drilling Superintendent	713-522-8652	281-684-6897
Diego Tellez	Drilling Manager	713-350-4602	713-303-4932

District I
1625 N. French Dr., Hobbs, NM 88240
District II
811 S. First St., Artesia, NM 88210
District III
1000 Rio Brazos Road, Aztec, NM 87410
District IV
1220 S. St. Francis Dr., Santa Fe, NM 87505

State of New Mexico
Energy, Minerals and Natural Resources Department

Oil Conservation Division
1220 South St. Francis Dr.
Santa Fe, NM 87505

Submit Original
to Appropriate
District Office

GAS CAPTURE PLAN

Date: 12/3/2019

☒ Original
☐ Amended - Reason for Amendment:

Operator & OGRID No.: OXY USA INC. - 16696

This Gas Capture Plan outlines actions to be taken by the Operator to reduce well/production facility flaring/venting for new completion (new drill, recomplete to new zone, re-frac) activity.

Note: Form C-129 must be submitted and approved prior to exceeding 60 days allowed by Rule (Subsection A of 19.15.18.12 NMAC).

Well(s)/Production Facility – Name of facility

The well(s) that will be located at the production facility are shown in the table below.

Well Name	API	Well Location (ULSTR)	Footages	Expected Peak MCF/D	Flared or Vented	Comments
Corral Gorge 12-13 Fd Com 1H	Pending	D-12-25S-29E	795 N 1430 W	3900	-	
Corral Gorge 12-13 Fd Com 2H	Pending	D-12-25S-29E	795 N 1495 W	3900	-	
Corral Gorge 12-13 Fd Com 3H	Pending	C-12-25S-29E	540 N 2262 W	3900	-	
Corral Gorge 12-13 Fd Com 4H	Pending	C-12-25S-29E	540 N 2297 W	3900	-	
Corral Gorge 12-13 Fd Com 5H	Pending	A-12-25S-29E	740 N 1170 E	3900	-	
Corral Gorge 12-13 Fd Com 6H	Pending	A-12-25S-29E	740 N 1100 E	3900	-	
Corral Gorge 12-13 Fd Com 11H	Pending	C-12-25S-29E	795 N 1460 W	3700	-	
Corral Gorge 12-13 Fd Com 12H	Pending	C-12-25S-29E	795 N 1530 W	3700	-	
Corral Gorge 12-13 Fd Com13H	Pending	A-12-25S-29E	740 N 1200 E	3700	-	
Corral Gorge 12-13 Fd Com 14H	Pending	A-12-25S-29E	740 N 1135 E	3700	-	
Corral Gorge 12-13 Fd Com 21H	Pending	C-12-25S-29E	975 N 1430 W	3600	-	
Corral Gorge 12-13 Fd Com 22H	Pending	C-12-25S-29E	975 N 1465W	3600	-	
Corral Gorge 12-13 Fd Com 23H	Pending	C-12-25S-29E	975 N 1500 W	3600	-	
Corral Gorge 12-13 Fd Com 24H	Pending	A-12-25S-29E	920 N 1200 E	3600	-	
Corral Gorge 12-13 Fd Com 25H	Pending	A-12-25S-29E	920 N 1165 E	3600	-	
Corral Gorge 12-13 Fd Com 26H	Pending	A-12-25S-29E	920 N 1130 E	3600	-	
Corral Gorge 12-13 Fd Com 311H	Pending	D-12-25S-29E	162 N 320 W	4300	-	
Corral Gorge 12-13 Fd Com 312H	Pending	A-12-25S-29E	360 N 260 E	4300	-	
Corral Gorge 12-13 Fd Com 31H	Pending	D-12-25S-29E	162 N 250 W	4400	-	
Corral Gorge 12-13 Fd Com 32H	Pending	D-12-25S-29E	162 N 285 W	4400	-	
Corral Gorge 12-13 Fd Com 33H	Pending	N-1-25S-29E	230 S 2605 W	4400	-	
Corral Gorge 12-13 Fd Com 34H	Pending	N-1-25S-29E	230 S 2635 W	4400	-	
Corral Gorge 12-13 Fd Com 35H	Pending	O-1-25S-29E	230 S 2645 E	4400	-	
Corral Gorge 12-13 Fd Com 36H	Pending	O-1-25S-29E	230 S 2610 E	4400	-	
Corral Gorge 12-13 Fd Com 37H	Pending	A-12-25S-29E	360 N 225 E	4400	-	
Corral Gorge 12-13 Fd Com 38H	Pending	A-12-25S-29E	360 N 190 E	4400	-	

Well Name	API	Well Location (ULSTR)	Footages	Expected Peak MCF/D	Flared or Vented	Comments
Corral Gorge 12-13 Fd Com 41H	Pending	M-1-25S-29E	235 S 1270 W	6600	-	
Corral Gorge 12-13 Fd Com 42H	Pending	N-1-25S-29E	235 S 1335 W	6600	-	
Corral Gorge 12-13 Fd Com 43H	Pending	P-1-25S-29E	260 S 970 E	6600	-	
Corral Gorge 12-13 Fd Com 44H	Pending	P-1-25S-29E	260 S 905 E	6600	-	
Corral Gorge 12-13 Fd Com 51H	Pending	M-1-25S-29E	235 S 1300 W	7100	-	
Corral Gorge 12-13 Fd Com 52H	Pending	N-1-25S-29E	235 S 1370 W	7100	-	
Corral Gorge 12-13 Fd Com 53H	Pending	P-1-25S-29E	260 S 940 E	7100	-	
Corral Gorge 12-13 Fd Com 54H	Pending	P-1-25S-29E	260 S 870 E	7100	-	
Corral Gorge 12-13 Fd Com 71H	Pending	C-12-25S-29E	540 N 1987 W	1200	-	
Corral Gorge 12-13 Fd Com 72H	Pending	C-12-25S-29E	540 N 2022 W	1200	-	
Corral Gorge 12-13 Fd Com 73H	Pending	A-12-25S-29E	360 N 535 E	1200	-	
Corral Gorge 12-13 Fd Com 74H	Pending	A-12-25S-29E	360 N 500 E	1200	-	

Gathering System and Pipeline Notification

Well(s) will be connected to a production facility after flowback operations are complete, where a gas transporter system is in place. The gas produced from the production facility is sent to ETC Texas Pipeline, LTD ("ETC") and Enterprise Field Services, LLC ("Enterprise") via the Oxy gas network. This network is connected to Enterprise and ETC high pressure gathering systems located in Eddy County, New Mexico. Produced gas is compressed by OXY USA INC. ("OXY") to the appropriate pressures for each gathering system. OXY provides (periodically) to ETC and Enterprise a drilling, completion and estimated first production date for wells that are scheduled to be drilled in the foreseeable future. In addition, OXY has periodic conference calls with these Midstream companies to discuss changes to drilling and completion schedules. Gas from these wells will be processed at the following plants:

Orla Plant Processing Plant located in Sec. 35, Block 57, T2, T&P RR CO, Reeves, County, Texas.

OXY USA WTP LP Processing Plant located in Sec. 23, Twn. 21S, Rng. 23E, Eddy County, New Mexico.

The actual flow of the gas will be based on compression operating parameters and gathering system pressures.

Flowback Strategy

After the fracture treatment/completion operations, well(s) will be produced to temporary production tanks and gas will be flared or vented. During flowback, the fluids and sand content will be monitored. When the produced fluids contain minimal sand, the wells will be turned to production facilities. Gas sales should start as soon as the wells start flowing through the production facilities, unless there are operational issues on Enterprise and/or ETC systems at that time. Based on current information, it is OXY's belief the system can take this gas upon completion of the well(s).

Safety requirements during cleanout operations from the use of underbalanced air cleanout systems may necessitate that sand and non-pipeline quality gas be vented and/or flared rather than sold on a temporary basis.

Alternatives to Reduce Flaring

Below are alternatives considered from a conceptual standpoint to reduce the amount of gas flared.

- Power Generation – On lease
  - Only a portion of gas is consumed operating generators, remainder of gas would be flared
- Compressed Natural Gas – On lease
  - Gas flared would be minimal, but might be uneconomical to operate when gas volume declines
- NGL Removal – On lease
  - Plants are expensive, residue gas is still flared, and uneconomical to operate when gas volume declines

OXY USA Inc.
APD Attachment
Offline Cementing

OXY respectfully requests a variance to cement the 9-5/8" and/or 7-5/8" intermediate casing strings offline.

The summarized operational sequence will be as follows:

1. Run casing as per normal operations. While running casing, conduct negative pressure test and confirm integrity of the float equipment (float collar and shoe).
2. Land casing.
3. Fill pipe with kill weight fluid, and confirm well is static.
    a. If well is not static notify BLM and kill well.
    b. Once well is static notify BLM with intent to proceed with nipple down and offline cementing.
4. Set and pressure test annular packoff.
5. After confirmation of both annular barriers and internal barriers, nipple down BOP and install cap flange. If any barrier fails to test, the BOP stack will not be nippled down until after the cement job is completed.
6. Skid rig to next well on pad.
7. Confirm well is static before removing cap flange.
8. If well is not static notify BLM and kill well prior to cementing or nippling up for further remediation.
9. Install offline cement tool.
10. Rig up cement equipment.
    a. Notify BLM prior to cement job.
11. Perform cement job.
12. Confirm well is static and floats are holding after cement job.
13. Remove cement equipment, offline cement tools and install night cap with pressure gauge for monitoring.



VDOR - EAST

REVISION BLOCK						ENGINEERING RECORD		FLEX 3 RIG DIAGRAM
NO.	DATE	DESCRIPTION	BY	CHK	APP	BY	DATE	Corral Gorge 12-13 Fed Com # 31H, 32H, 311H EDDY COUNTY, NEW MEXICO

OXY USA INC.

SITE PLAN
CEDCAN 1201
FAA PERMIT: NO



NO.	WELL	FOOTAGE	LAT.	LONG.	ELEV.	ID#
1	CORRAL GORGE 12_13 FED COM #31H	162' FNL & 250' FWL	32.151501° N	103.945801° W	3074.5'	IP-SMS-2302
2	CORRAL GORGE 12_13 FED COM #32H	162' FNL & 285' FWL	32.151502° N	103.945688° W	3075.8'	IP-SMS-2303
3	CORRAL GORGE 12_13 FED COM #311H	162' FNL & 320' FWL	32.151502° N	103.945575° W	3076.1'	IP-SMS-2300

NOTES:

1) LATS & LONGS SHOWN HEREON ARE MERCATOR GRID AND CONFORM TO THE NEW MEXICO COORDINATE SYSTEM "NEW MEXICO EAST ZONE" NORTH AMERICAN DATUM 1983.

2) DISTANCES ARE GRID VALUES.

3) ALL FEATURES ARE EXISTING UNLESS OTHERWISE NOTED

CERTIFICATION
I, CHAD HARCROW, A NEW MEXICO REGISTERED PROFESSIONAL SURVEYOR CERTIFY THAT I DIRECTED AND AM RESPONSIBLE FOR THIS SURVEY, THAT THIS SURVEY IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.

CHAD HARCROW NEW MEXICO 17777 LICENSED PROFESSIONAL SURVEYOR

Chad Harcrow
CHAD HARCROW N.M.P.S. NO. 17777

08/22/19
DATE

HARCROW SURVEYING, LLC
2316 W. MAIN ST, ARTESIA, N.M. 88210
PH: (575) 746-2158
c.harcrow@harcrowsurveying.com

200 0 200 400 Feet

Scale: 1"=200'

OXY USA INC.	
SURVEY DATE: JULY 8, 2019	SITE PLAN
DRAFTING DATE: AUGUST 19, 2019	PAGE: 1 OF 1
APPROVED BY: CH / DRAWN BY: WN	FILE: 19-1246

Oxy Single Centrifuge Closed Loop System – New Mexico Flex III

May 28, 2013



Oxy



Oxy Single Centrifuge Closed Loop System – New Mexico Flex III

May 28, 2013