

Submit 1 Copy To Appropriate District
Office
District I
1625 N French Dr, Hobbs, NM 88240
District II
1301 W Grand Ave, Artesia, NM 88210
District III
1000 Rio Brazos Rd, Aztec, NM 87410
District IV
1220 S St Francis Dr, Santa Fe, NM
87505

State of New Mexico
Energy, Minerals and Natural Resources

Form C-103
October 13, 2009

OIL CONSERVATION DIVISION
1220 South St. Francis Dr.
Santa Fe, NM 87505

WELL API NO. 30-015-25060 ✓
5. Indicate Type of Lease STATE <input type="checkbox"/> FEE <input checked="" type="checkbox"/>
6. State Oil & Gas Lease No.
7. Lease Name or Unit Agreement Name Scripps ✓
8. Well Number 5 ✓
9. OGRID Number 025575 ✓
10. Pool name or Wildcat Atoka Glorieta Yeso

SUNDRY NOTICES AND REPORTS ON WELLS (DO NOT USE THIS FORM FOR PROPOSALS TO DRILL OR TO DEEPEN OR PLUG BACK TO A DIFFERENT RESERVOIR USE "APPLICATION FOR PERMIT" (FORM C-101) FOR SUCH PROPOSALS)	
1. Type of Well: Oil Well <input checked="" type="checkbox"/> Gas Well <input type="checkbox"/> Other <input type="checkbox"/>	
2. Name of Operator Yates Petroleum Corporation ✓	
3. Address of Operator 105 South Fourth Street, Artesia, NM 88210	
4. Well Location Unit Letter <u>L</u> : <u>2260</u> feet from the <u>South</u> line and <u>330</u> feet from the <u>West</u> line Section <u>25</u> Township <u>18S</u> Range <u>26E</u> NMPM <u>Eddy</u> County <u>✓</u>	
11. Elevation (Show whether DR, RKB, RT, GR, etc.) 3283' GR	

12. Check Appropriate Box to Indicate Nature of Notice, Report or Other Data

NOTICE OF INTENTION TO:
PERFORM REMEDIAL WORK ☐ PLUG AND ABANDON ☒
TEMPORARILY ABANDON ☐ CHANGE PLANS ☐
PULL OR ALTER CASING ☐ MULTIPLE COMPL ☐
DOWNHOLE COMMINGLE ☐

SUBSEQUENT REPORT OF:
REMEDIAL WORK ☐ ALTERING CASING ☐
COMMENCE DRILLING OPNS ☐ P AND A ☐
CASING/CEMENT JOB ☐

OTHER: ☐

OTHER:

**Notify OCD 24 hrs. prior
to any work done.**

13. Describe proposed or completed operations. (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work). SEE RULE 19.15.7:14 NMAC. For Multiple Completions: Attach wellbore diagram of proposed completion or recompletion.


Yates Petroleum Corporation plans to plug and abandon this well as follows:

1. NU BOP. RU all safety equipment as needed. No casing recovery will be attempted as production casing is cemented to surface. POOH with tubing and production equipment if any exist.
2. Set a CIBP at 2823' and cap it with 25 sx Class "C" cement.
3. Spot a 240' (25 sx) Class "C" cement plug from 735'-975'. This will leave a plug across surface casing shoe. WOC and tag, reset if necessary.
4. Set a 240' (25 sx) Class "C" cement plug from 240' up to surface. WOC and tag, reset if necessary.
5. Remove all surface equipment and weld dry hole marker and clean location as per regulations

NOTE Yates Petroleum Corporation will use steel pits and no earth pits

**SEE ATTACHED
CONDITIONS OF
APPROVAL**

Rig Release Date.



I hereby certify that the information above is true and complete to the best of my knowledge and belief.

SIGNATURE Tina Huerta TITLE Regulatory Compliance Supervisor DATE October 6, 2011

Type or print name Tina Huerta E-mail address: tinah@yatespetroleum.com PHONE: 575-748-4168

For State Use Only

APPROVED BY [Signature] TITLE Approval Granted providing work is complete by 1/18/2012 DATE 10/18/2011

Conditions of Approval (if any):

WELL NAME: Scripps #5 FIELD: _____

LOCATION: 2,260' FSL & 330' FWL of Section 25-18S-26E Eddy Co., NM

GL: 3,283' ZERO: _____ KB: _____

SPUD DATE: 11/9/84 COMPLETION DATE: 1/1/85

COMMENTS: API No.: 30-015-25060

CASING PROGRAM

8-5/8" 2.4#	925'
5-1/2" 15.5#	3,750'

12-1/4" Hole

7-7/8" Hole

Before

8-5/8" @ 925' w/500 sx (Circ)

TOPS

SA 1,155'
Glorieta 2,826'

Yeso Perfs: 2,873-3,549'

5-1/2" @ 3,750' w/725 sx
(Circ)

PBTD: 3,699'
TD: 3,750'

Not to Scale
9/9/10
DC/Hill

WELL NAME: Scripps #5 FIELD: _____

LOCATION: 2,260' FSL & 330' FWL of Section 25-18S-26E Eddy Co., NM


GL: 3,283' ZERO: _____ KB: _____

SPUD DATE: 11/9/84 COMPLETION DATE: 1/1/85

COMMENTS: API No.: 30-015-25060

CASING PROGRAM

8-5/8" 2.4#	925'
5-1/2" 15.5#	3,750'



After

TOPS

SA 1,155'
Glorieta 2,826'

Not to Scale
9/9/10
DC/Hill

NEW MEXICO OIL CONSERVATION DIVISION
DISTRICT 2 OFFICE
811 S. FIRST STREET
ARTESIA, NM 88210
(575)748-1283

CONDITIONS OF APPROVAL FOR PLUGGING & ABANDONMENT

Operator: Yates Petroleum Corp.
Well Name & Number: Scripps #5
API #: 30-015-25060

1. Produced water **will not** be used during any part of the plugging & abandonment operation.
2. Notify NMOCD Dist. 2 office at least 24 hrs before beginning work.
3. Closed Loop System is to be used for entire plugging operation. Upon completion, contents of steel pit are to be hauled to a permitted disposal location.
4. Trucking companies being used to haul oilfield waste fluids to a disposal – commercial or private – shall have an approved NMOCD C-133 permit. A copy of this permit shall be available in each truck used to haul waste products. It is the responsibility of the operator, as well as the contractor, to verify that this permit is in place prior to performing work. Drivers shall produce a copy upon request of NMOCD Field Inspectors.
5. A subsequent C-103 will serve as notification that the well bore has been plugged **ONLY**. A C-103 FINAL shall be filed before any bonding can be released on the well. Upon receipt of the Final, an inspection will be performed to verify that the location has been satisfactorily cleaned to NMOCD standards.
6. If work has not begun within 90 days of the approval of this procedure, an extension request must be filed, stating reason that well has not been plugged.
7. Every attempt must be made to clean the well bore out to below the perfs, before any plugs can be set, by whatever means possible.

8. Cement Retainers may not be used.

9. Squeeze pressures not to exceed 500 psi., unless approval is given by NMOCD Plugging Supervisor.

10. Plugs may be combined after consulting with NMOCD P & A Supervisor.

11. Minimum WOC time for tag plugs will be 4 hrs.

DG

Date: 10/18/2011