8. Cement Retainers may not be used.

- 9. Squeeze pressures not to exceed 500 psi., unless approval is given by NMOCD Plugging Supervisor.
- 10. Plugs may be combined after consulting with NMOCD P & A Supervisor.
- 11. Minimum WOC time for tag plugs will be 4 hrs.

DC

Date: 1/30/2012