

District I
1625 N French Dr., Hobbs, NM 88240
District II
1301 W Grand Ave., Artesia, NM 88210
District III
1000 Rio Brazos Rd., Aztec, NM 87410
District IV
1220 S St Francis Dr., Santa Fe, NM 87505

OIL CONSERVATION DIVISION
1220 South St. Francis Dr.
Santa Fe, NM 87505

WELL API NO. 30-015-38467 ✓
5. Indicate Type of Lease STATE <input checked="" type="checkbox"/> / FEE <input type="checkbox"/>
6. State Oil & Gas Lease No.
7. Lease Name or Unit Agreement Name N B TWEEN STATE ✓
8. Well Number 022 ✓
9. OGRID Number 873 ✓
10. Pool name or Wildcat ARTESIA;GLORIETA-YESO (O) 96830

SUNDRY NOTICES AND REPORTS ON WELLS
(DO NOT USE THIS FORM FOR PROPOSALS TO DRILL OR TO DEEPEN OR REFRAC TO A DIFFERENT RESERVOIR USE "APPLICATION FOR PERMIT" (FORM C-100) FOR SUCH PROPOSALS.)


1. Type of Well: ☒ Well ☐ Gas Well ☐ Other

2. Name of Operator
APACHE CORPORATION ✓

3. Address of Operator
303 VETERANS AIRPARK LANE, STE 3000; MIDLAND, TX 79705

4. Well Location
Unit Letter K : 2310 feet from the SOUTH line and 1650 feet from the WEST line
Section 25 Township 17S Range 28E NMPM County EDDY

11. Elevation (Show whether DR, RKB, RT, GR, etc.)
3670' GR



12. Check Appropriate Box to Indicate Nature of Notice, Report or Other Data

NOTICE OF INTENTION TO:		SUBSEQUENT REPORT OF:	
PERFORM REMEDIAL WORK <input type="checkbox"/>	PLUG AND ABANDON <input type="checkbox"/>	REMEDIAL WORK <input type="checkbox"/>	ALTERING CASING <input type="checkbox"/>
TEMPORARILY ABANDON <input type="checkbox"/>	CHANGE PLANS <input type="checkbox"/>	COMMENCE DRILLING OPNS. <input type="checkbox"/>	P AND A <input type="checkbox"/>
PULL OR ALTER CASING <input type="checkbox"/>	MULTIPLE COMPL <input type="checkbox"/>	CASING/CEMENT JOB <input type="checkbox"/>	
DOWNHOLE COMMINGLE <input type="checkbox"/>			
OTHER: <input type="checkbox"/>		OTHER: COMPLETION - PAGE ONE OF TWO <input checked="" type="checkbox"/>	

13. Describe proposed or completed operations. (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work). SEE RULE 1103. For Multiple Completions: Attach wellbore diagram of proposed completion or recompletion.

06-21-2011: RIH W/GR/CCL/CBL; RIH W/3 1/8" SLICK GUN & PERF LOWER @ BLINEBRY & TUBB ZONES @ 5142, 5148, 5168, 5173, 5185, 5191, 5203, 5208, 5264, 5270, 5500, 5558' (2 JSPF) (12' NET - 24 HOLES).
06-22-2011: ACIDIZE LOWER BLINEBRY & TUBB W/2000 GALS 15% HCL NEFE ACID. PREP TO FRAC AT A LATER DATE.
07-17-2011: START 1ST STAGE LOWER BLINEBRY & TUBB FRAC. PUMP 19975 GALS 20# PAD. PUMP 151483 GALS 20# W/ 136918 LBS 16/30 WHTSD; 30.4 K 16/30 SIBERPROP; 4943 GAL 20# LINEAR GEL FLUSH. RIH W/ 3 1/8" GUNS & PERF MIDDLE & UPPER BLINEBRY @ 4820', 4839', 4847', 4854', 4878', 4944', 4960', 4968', 5009'. W/ 2 JSPF, 18 HOLES. ACIDIZE W/ 2016 GALS 15% HCL. START 2ND STAGE MIDDLE & UPPER BLINEBRY FRAC. PUMP 17,761 GALS 20# PAD. PUMP 127775 GALS 20# W/ 88400 LBS 16/30 WHT, 28800# SIBERPROP; 4032 GAL 20# LINEAR GEL FLUSH. RIH W/ CBP & SET @ 4400'. RIH W/ 3 1/8" GUNS&PERFUPPERPADDOCK@3806', 3809', 3836', 3841', 3850', 3860', 3866', 3870', 3883', 3891', 3901', 3918', 3921', 3931', 3939', 3967', 3984', 3993', 4003', 4011', 4016', 4031', 4036', 4049', 4062', 4084', 4167', 4173', 4182', 4186', 4196', 4295', 4320'. W/ 1 JSPF, 33 HOLES. ACIDIZE W/ 2500 GALS 15% HCL. START 3RD STAGE UPPER PADDOCK FRAC. PUMP 20,000 GALS 20# PAD. PUMP 139831 GALS 20# W/165300 LBS 16/30 WHT, 3630 GAL 10# LINEAR GEL FLUSH; 35.9K# SIBERPROP. SEE PAGE TWO

Spud Date:

06/01/2011

Rig Release Date:

06/11/2011

I hereby certify that the information above is true and complete to the best of my knowledge and belief.

SIGNATURE

Beverly Hatfield

TITLE SR. STAFF ENGR TECH

DATE 07/17/2011

Type or print name BEV HATFIELD

E-mail address: beverly.hatfield@apachecorp.com

PHONE: 432-818-1906

For State Use Only

APPROVED BY:

T.C. Shepard

TITLE

Geologist

DATE

NOV 01 2011

Conditions of Approval (if any):

dm

District I
1625 N French Dr., Hobbs, NM 88240
District II
1301 W Grand Ave., Artesia, NM 88210
District III
1000 Rio Brazos Rd., Aztec, NM 87410
District IV
1220 S St Francis Dr., Santa Fe, NM 87505

OIL CONSERVATION DIVISION
1220 South St. Francis Dr.
Santa Fe, NM 87505

WELL API NO. 30-015-38467
5. Indicate Type of Lease STATE <input checked="" type="checkbox"/> FEE <input type="checkbox"/>
6. State Oil & Gas Lease No.
7. Lease Name or Unit Agreement Name N B TWEEN STATE
8. Well Number 022
9. OGRID Number 873
10. Pool name or Wildcat ARTESIA;GLORIETA-YESO (O) 96830
11. Elevation (Show whether DR, RKB, RT, GR, etc.) 3670' GR

SUNDRY NOTICES AND REPORTS ON WELLS
(DO NOT USE THIS FORM FOR PROPOSALS TO DRILL OR TO DEEPEN OR PLUG BACK TO A DIFFERENT RESERVOIR USE "APPLICATION FOR PERMIT" (FORM C-101) FOR SUCH PROPOSALS)

1. Type of Well: ☒ Well ☐ Gas Well ☐ Other

2. Name of Operator
APACHE CORPORATION

3. Address of Operator
303 VETERANS AIRPARK LANE, STE 3000; MIDLAND, TX 79705


4. Well Location
Unit Letter K : 2310 feet from the SOUTH line and 1650 feet from the WEST line
Section 25 Township 17S Range 28E NMPM County EDDY

12. Check Appropriate Box to Indicate Nature of Notice, Report or Other Data

<p>NOTICE OF INTENTION TO:</p> <p>PERFORM REMEDIAL WORK <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/></p> <p>TEMPORARILY ABANDON <input type="checkbox"/> CHANGE PLANS <input type="checkbox"/></p> <p>PULL OR ALTER CASING <input type="checkbox"/> MULTIPLE COMPL <input type="checkbox"/></p> <p>DOWNHOLE COMMINGLE <input type="checkbox"/></p> <p>OTHER: <input type="checkbox"/></p>	<p>SUBSEQUENT REPORT OF:</p> <p>REMEDIAL WORK <input type="checkbox"/> ALTERING CASING <input type="checkbox"/></p> <p>COMMENCE DRILLING OPNS. <input type="checkbox"/> P AND A <input type="checkbox"/></p> <p>CASING/CEMENT JOB <input type="checkbox"/></p> <p>OTHER: COMPLETION - PAGE TWO OF TWO <input checked="" type="checkbox"/></p>
--	--

13. Describe proposed or completed operations. (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work). SEE RULE 1103. For Multiple Completions: Attach wellbore diagram of proposed completion or recompletion.

7-26-11 RIH W/2 7/8" PURGE VALVE, 2 JTS 2 7/8" J-55 TBG, 2 7/8" CAVINS DESANDER, 2 7/8" X 4' TBG SUB, 2 7/8" SN, 2 7/8" TK-99 BLAST JOINT, 56 JTS 2 7/8" J-55 TBG, 5 1/2" X 2 7/8" TAC, & 119 JTS 2 7/8" J-55 TBG. ETD @ 5614' RKB. SN @ 5526.58' RKB. TAC SET @ 3738.97' RKB.
8-02-11 HOOK UP ELECTRIC, BUILD WELLHEAD, LAY FLOWLINE, INSTALL VFD, CONNECT KILL SWITCHES.
INSTALL POC. ENERGIZE MOTOR. TURN PRODUCTION TO BATTERY.



Spud Date: 06/01/2011

Rig Release Date: 06/11/2011

I hereby certify that the information above is true and complete to the best of my knowledge and belief.

SIGNATURE Beverly Hatfield TITLE SR. STAFF ENGR TECH DATE 09/07/2011

Type or print name BEV HATFIELD E-mail address: beverly.hatfield@apachecorp.com PHONE: 432-818-1906

For State Use Only

APPROVED BY: J. C. Shepard TITLE Geologist DATE NOV 01 2011

Conditions of Approval (if any):