DISTRICT J
1625 N. French Dr., Hobbs, NM 88240
Phone: (573) 393-6161 Fax: (575) 393-0720
DISTRICT J
811 S. First St., Artesia, NM 88210
Phone: (575) 748-1283 Fax: (575) 748-9720
DISTRICT JII
1000 Rio Brazos Road, Aztec, NM 87410
Phone: (505) 334-6176 Fax: (505) 334-6170
DISTRICT JV
DISTRICT JV
1220 S. St. Francis Dr., Santa Fe, NM 87505
Phone: (505) 476-3460 Fax: (505) 476-3462

API Number

State of New Mexico Energy, Minerals & Natural Resources Department OIL CONSERVATION DIVISION 1220 South St. Francis Dr. Santa Fe, New Mexico 87505

Form C-102 Revised August 1, 2011 Submit one copy to appropriate District Office

□AMENDED REPORT

Pool Name

WELL LOCATION AND ACREAGE DEDICATION PLAT

50 R	> ユ				KOO 22 ST				14	
OGRIDA	No./_	Operator Name OXY U.S.A. INC.							Elevation	
1009	10_								3562	
		1 4	T - 6	1	Surface Locat		,	T017 - 17	<i>C</i>	
UL or lot No.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County	
D	22	17-S	28-E		1175	NORTH	212	.WEST	EDDY	
		· · · · · · · · · · · · · · · · · · ·	·			erent From Surface	**			
UL or lot No.	Section	Township	Range	Lot ldm	Feet from the	North/South line	Feet from the	East/West line	County	
Dedicated Acres	Joint or	Infill C	onsolidation Co	ode Ord	ler No.					
NO ALLOWABLE W	ILL BE ASSIGN	VED TO THIS CO	OMPLETION UN	ITIL ALL INTE	RESTS HAVE BEEN (CONSOLIDATED OR A	NON-STANDARD UNIT	HAS BEEN APPROVE	ED BY THE DIVISIO	
212		and the second s	GEODETIC CC NAD 2: SURFACE Y=6634 X=5498 LAT.=32.8 LONG.=104,	7 NME LOCATION 40.5 N 175.9 E			I hereby certificate to that this organized with this organized hereby certificate to the complete to the thing this to of such mine pooling agree heretofore enterested and correct to the complete to the co	EYOR CERTIFI ify that the well location: rom field notes of actual my supervision, and that the best of my belief. AUGUST 27, 2 vey Seal of Professional	crein is true and e and belief, and orking interest or including the a right to drill this tract with an owner or to a voluntary cooling order CATION Shown on this plat surveys made by the same is true 2012 Surveyor: 21/29/2012 Eidson 12641 J. Eidson 3239	

APD DATA - DRILLING PLAN -

OPERATOR NAME / NUMBER: OXY USA WTP LP

LEASE NAME / NUMBER: Roo 22 State #14

STATE: NM

COUNTY: Eddy

SURFACE LOCATION: 1175' FNL & 212' FWL, Sec 22, T 17S, R 28E

C-102 PLAT APPROX GR ELEV: 3562'

EST KB ELEV: 3576' (14' KB)

1. GEOLOGIC NAME OF SURFACE FORMATION

a. Permian

2. ESTIMATED TOPS OF GEOLOGICAL MARKERS & DEPTHS OF ANTICIPATED FRESH WATER, OIL OR GAS

Formation	TV Depth Top	Expected Fluids
Rustler	100	Fresh Water
Top of Salt	310	-
Base of Salt	390	-
Yates	410	-
Seven Rivers	604	-
Queen	1170	-
Grayburg	1640	Oil
San Andres	1749	Oil/Water
Glorietta	3350	Oil
Paddock	3440	Oil
Blinebry	3900	Oil
Tubb - Base of Yeso	4820	Oil
TD	5100	TD

A. Fresh Water formation is outcropping and will be covered with the 16" conductor pipe, which will be set at 120' prior to spud.

GREATEST PROJECTED TD 5100' MD / 5100' TVD

OBJECTIVE: Yeso

3. CASING PROGRAM

Surface Casing: 8.625" casing set at ± 400 ' MD/ 400' TVD in a 11" hole filled with 8.4 ppg mud

Interval	Length	Wt	Gr	Condition	Cplg	Coll Rating (psi)	Burst Rating (psi)	Jt Str (M-lbs)	ID (in)	Drift (in)	SF Coll	SF Burst	SF Ten
0'- 400'	400'	24	J-55	New	ST&C	1370	2950	244	8.097	7.972	10.17	1.72	29.16

Production Casing: 5.5" casing set at ± 5100'MD / 5100'TVD in a 7.875" hole filled 9.6 ppg mud

										PFO			
						Coll	Burst						
			İ	Condition		Rating	Rating	Jt Str	ID	Drift	SF	SF	SF
Interval	Length	Wt_	Gr	<u> </u>	Cplg	(psi)	(psi)	(M-lbs)	(in)	(in)	Coll	Burst	Ten
0'- 5100'	5100'	17	L-80	New	LT&C	6290	7740	338	4.892	4.767	2.47	3.80	4.57

Collapse and burst loads calculated using Stress Check with actual anticipated loads.

4. CEMENT PROGRAM:

Surface Interval

Interval	Amount sx	Ft of Fill	Туре	Gal/Sk	PPG	Ft ³ /sk	24 Hr Comp
Surface (TOC:	: 0' - 400')	-					
Lead: 0' - 400' (165% Excess)	210	400'	Premium Plus Cement: 1 % Calcium Chloride - Flake	6.36	14.8	1.34	1608 psi

Production Interval

Interval	Amount sx	Ft of Fill	Туре	Gal/Sk	PPG	Ft ³ /sk	24 Hr Comp
Production (To	OC: 0' - 5100')					
Lead: 0' - 3000' (100 % Excess)	550	3000'	Halliburton Light Premium Plus: 5% Salt, 3 lbm/sk Kol-Seal, 0.125 lb/sx Poly-E-Flake, 0.35% HR-800	9.69	12.9	1.87	660 psi
Tail: 3000' – 5100' (100 % Excess)	470	2100'	Premium Plus Cement: 0.5% Halad ®-344, 0.2% WellLife 734, 5 lbm/sk Microbond, 0.3% Econolite, 0.3% CFR-3	7.72	14.2	1.55	1914 psi

Description of Cement Additives: Cal-Seal 60 (Accelerator), Poly-E-Flake (Lost Circulation Additive), Kol-Seal (Lost Circulation Additive), Calcium Chloride – Flake (Accelerator), HR-800 (Retarder), Halad ®-344 (Low Fluid Loss Control), WellLife 734 (Cement Enhancer), Microbond (Expander), Econolite (Ligh Weight Additive), CFR-3 (Dispersant)

If a caliper log is run, cement volumes will be adjusted to caliper volume + 35% excess for the production hole.

5. PRESSURE CONTROL EQUIPMENT

Surface: 0 - 400' None.

Production: 0 - 5100' the minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required to drill below the surface casing shoe shall be 3000 (3M) psi. Operator will be using an 11" 3M two ram stack with 3M annular preventer, & 3M Choke Manifold.

- **a.** The 11" 3000 psi blowout prevention equipment will be installed and operational after setting the 8 5/8" surface casing and the 8 5/8" SOW x 11" 3K conventional wellhead; the rotating head body will be installed but the rubber will be installed when it becomes operationally necessary.
- **b.** The BOP and ancillary BOPE will be tested by a third party upon installation to the 8 5/8" 24# J-55 surface casing. All equipment will be tested to 250/3000 psi for 10 minutes and charted, except the annular, which will be tested to 70% of working pressure. This is to be in compliance with the Onshore Order # 2 which states the BOPE shall be tested to 70% of the yield of the casing when the BOP and casing are not isolated.
- c. The pipe rams will be functionally tested during each 24 hour period; the blind rams will be functionally tested on each trip out of the hole. These functional tests will be documented on the Daily Driller's Log. Other accessory equipment (BOPE) will include a safety valve and subs as needed to fit all drill strings, and a 2" kill line and 3" choke line having a 3000 psi WP rating. Oxy requests that the system be tested at 3,000 psi.

d. Oxy requests a variance if Savanna 415 is used to drill this well to use a co-flex line between the BOP and choke manifold. See attached schematic.

Manufacturer: <u>Hebei Ouya Ltd.</u> Serial Number: 1642343-04

Length: 39" Size: 3" Ends: flanges

WP rating: 3000 psi Anchors required by manufacturer: No

e. See attached BOP & Choke manifold diagrams.

6. MUD PROGRAM:

Depth	Mud Wt ppg	Vis Sec	Fluid Loss	Type System
0 – 400'	8.4 - 8.8	27 – 38	NC	Fresh Water / Spud Mud
400' – TD	9.6 – 10	28 – 40	10 - 20	Brine Water / Salt Gel

Remarks: Pump high viscosity sweeps as needed for hole cleaning. The mud system will be monitored visually/manually as well as with an electronic PVT. The necessary mud products for additional weight and fluid loss control will be on location at all times.

A. Appropriately weighted mud will be used to isolate potential gas, oil, and water zones until such time as casing can be cemented into place for zonal isolation.

7. AUXILIARY WELL CONTROL AND MONITORING EQUIPMENT

- **a.** A Kelly cock will be in the drill string at all times.
- **b.** A full opening drill pipe stabbing valve having the appropriate connections will be on the rig floor unobstructed and readily accessible at all times.
- c. Hydrogen Sulfide detection equipment will be in operation after drilling out the surface casing shoe until the production casing is cemented. Breathing equipment will be on location upon drilling the surface casing shoe until total depth is reached. If Hydrogen Sulfide is encountered, measured amounts and formations will be reported to the BLM

8. LOGGING / CORING AND TESTING PROGRAM:

A. Mud Logger: Log from 2000' to TD.

B. DST's: None.

C. Open Hole Logs as follows: Triple combo from 400' to TD.

9. POTENTIAL HAZARDS:

- A. H2S detection equipment will be in operation after drilling out the surface casing shoe until the production casing has been cemented. Breathing equipment will be on location from drilling out the surface shoe until production casing is cemented. If H2S is encountered the operator will comply with Onshore Order #6.
- B. The bottomhole pressure is anticipated to be **2545** psi.
- C. No abnormal temperatures or pressures are anticipated. The highest anticipated pressure gradient is 0.50 psi/ft. All personnel will be familiar with all aspects of safe operation of equipment being used to drill this well. Adequate flare lines will be installed off the mud/gas separator where gas may be flared safely.

10. ANTICIPATED STARTING DATE AND DURATION OF OPERATIONS

Road and location construction will begin after the BLM has approved the APD. Anticipated spud date will be as soon as possible after BLM approval and as soon as a rig will be available. Move in operations and drilling is expected to take 15 days. If production casing is run, then an additional 30 days will be needed to complete the well and construct surface facilities and/or lay flow lines in order to place well on production.

11. COMPANY PERSONNEL:

Name	Title	Office Phone
Anthony Tschacher	Drilling Engineer	713-985-6949
Sebastian Millan	Drilling Engineer Supervisor	713-350-4950
Roger Allen	Drilling Superintendent	713- 215-7617
Douglas Chester	Drilling Manager	713-366-5194